

Project Manual

Apiculture Facility Bid Set



Raleigh, NC

SCO ID No. 22-24494-01A

Code: 42124

Item: 315

NCSU Project No.: 202220007



think | design biloba Architecture, PLLC

PROJECT MANUAL
APICULTURE FACILITY
BID SET
NC STATE UNIVERSITY
RALEIGH, NC
SCO ID NO. 22-24494-01A

BILOBA ARCHITECTURE, PLLC
8801 JM KEYNES DRIVE, SUITE 365
CHARLOTTE, NC 28262


PROJECT 132
JANUARY 10, 2025

DOCUMENT 000107 - SEALS PAGE

1.1 DESIGN PROFESSIONALS OF RECORD

A. Architect:

1. Ian Patrick.
2. 12802.
3. Responsible for Divisions 00-12 Sections except where indicated as prepared by other design professionals of record and NCSU authored sections.



01.10.2025

B. Civil Engineer:

1. Roy Lorenzen.
2. 15834
3. Responsible for Section 01 5639 and Division 31-33 Sections.



C. Structural Engineer:

1. Thomas McLane.
2. 046260.
3. Responsible for Sections 03 1000, 03 2000, 03 3000, 05 1200, 05 2100, 05 3100, and 05 4400.



01/10/2025

D. Plumbing and HVAC Engineer:

1. Sean Rask
2. 046583.
3. Responsible for Division 21-23 Sections.



1/10/2025

E. Electrical Engineer:

1. Kyle Pittman
2. 049995.
3. Responsible for Division 26 Sections and 28 4621.11.



01/10/2025

END OF DOCUMENT 000107

NOTICE TO BIDDERS

Sealed proposals will be received by North Carolina State University in Raleigh, NC, in the Large Conference Room 35, Administrative Services III Building, 2701 Sullivan Drive. Raleigh, NC 27607 up to 2:00 pm February 19, 2025 and immediately thereafter publicly opened and read for the furnishing of labor, material and equipment entering into the construction of

Apiculture Facility

New steel framed building, sitework, and other items as indicated in the Contract Documents .

Bids will be received for Contract type – single prime. All proposals shall be lump sum.

Pre-Bid Meeting

An open, non-mandatory pre-bid meeting will be held for all interested bidders at 3:00 pm January 28, 2025 in the Large Conference Room 35, Administrative Services III Building, 2701 Sullivan Drive. Raleigh, NC 27607. The meeting will address project specific questions, issues, bidding procedures and bid forms.

The meeting is also to identify preferred brand alternates and their performance standards that the owner will consider for approval on this project.

In accordance with General Statute GS 133-3, Specifications may list one or more preferred brands as an alternate to the base bid in limited circumstances. Specifications containing a preferred brand alternate under this section must identify the performance standards that support the preference. Performance standards for the preference must be approved in advance by the owner in an open meeting. Any alternate approved by the owner shall be approved only where (i) the preferred alternate will provide cost savings, maintain or improve the functioning of any process or system affected by the preferred item or items, or both, and (ii) a justification identifying these criteria is made available in writing to the public.

In accordance with GS133-3 and SCO procedures the following preferred brand items are being considered as Alternates by the owner for this project:

- A. Door Hardware
- B. Controller
- C. Controls

Justification of any approvals will be made available to the public in writing no later than seven (7) days prior to bid date.

Complete plans, specifications and contract documents will be open for inspection in the offices of Biloba Architecture and NC State University Facilities Management and in the plan rooms of the Associated General Contractors, Carolinas Branch, Raleigh in the local North Carolina offices of McGraw-Hill Dodge Corporation, and in the Eastern Regional Office of Reed Construction Data in Norcross, GA and in Minority Plan Rooms in

Hispanic Contractors Association of the Carolinas (HCAC) in Winston-Salem, Charlotte and Raleigh Areas – 877-227-1680

or may be obtained by those qualified as prime bidders, upon deposit of two-hundred fifty dollars (\$250.00) in cash or certified check. The full plan deposit will be returned to those bidders provided all documents are returned in good, usable condition within ten (10) days after

the bid date. An electronic, PDF version of the Bid Documents is available free of charge from Biloba Architecture, PLLC upon request.

NOTE: The bidder shall include with the bid proposal the form *Identification of Minority Business Participation* identifying the minority business participation it will use on the project and shall include either *Affidavit A* or *Affidavit B* as applicable. Forms and instructions are included within the Proposal Form in the bid documents. Failure to complete these forms is grounds for rejection of the bid. (GS143-128.2c Effective 1/1/2002.)

All contractors are hereby notified that they must have proper license as required under the state laws governing their respective trades.

General contractors are notified that Chapter 87, Article 1, General Statutes of North Carolina, will be observed in receiving and awarding general contracts. General contractors submitting bids on this project must have license classification for Building.

NOTE--SINGLE PRIME CONTRACTS: Under GS 87-1, a contractor that superintends or manages construction of any building, highway, public utility, grading, structure or improvement shall be deemed a "general contractor" and shall be so licensed. Therefore a single prime project that involves other trades will require the single prime contractor to hold a proper General Contractors license. **EXCEPT:** On public buildings being bid single prime, where the total value of the general construction does not exceed 25% of the total construction value, contractors under GS87- Arts 2 and 4 (Plumbing, Mechanical & Electrical) may bid and contract directly with the Owner as the SINGLE PRIME CONTRACTOR and may subcontract to other properly licensed trades. GS87-1.1- Rules .0210

Each proposal shall be accompanied by a cash deposit or a certified check drawn on some bank or trust company, insured by the Federal Deposit Insurance Corporation, of an amount equal to not less than five percent (5%) of the proposal, or in lieu thereof a bidder may offer a bid bond of five percent (5%) of the bid executed by a surety company licensed under the laws of North Carolina to execute the contract in accordance with the bid bond. Said deposit shall be retained by the owner as liquidated damages in event of failure of the successful bidder to execute the contract within ten days after the award or to give satisfactory surety as required by law.

A performance bond and a payment bond will be required for one hundred percent (100%) of the contract price.

Payment will be made based on ninety-five percent (95%) of monthly estimates and final payment made upon completion and acceptance of work.

No bid may be withdrawn after the scheduled closing time for the receipt of bids for a period of 30 days.

The owner reserves the right to reject any or all bids and to waive informalities.

Designer:
Biloba Architecture, PLLC

Owner:
NC State University

8801 JM Keynes Drive; Suite 365
Charlotte, NC 28262

2601 Wolf Village Way; Ste 300
Raleigh, NC 27695

704-248-2922

919.515.2991

TABLE OF CONTENTS

TITLE PAGE
SEALS PAGE
NOTICE TO BIDDERS
TABLE OF CONTENTS
INSTRUCTIONS TO BIDDERS AND GENERAL CONDITIONS OF THE CONTRACT
SUPPLEMENTARY GENERAL CONDITIONS
MBE GUIDELINES
GEOTECHNICAL REPORT
SEPTIC DRAIN FIELD SOILS REPORT
EROSION AND SEDIMENTATION CONTROL PLAN
STORMWATER IMPACT ANALYSIS
ASBESTOS ABATEMENT SPECIFICATIONS

DIVISION 01 - GENERAL REQUIREMENTS

NCSU Design and Construction Guidelines
NCSU Temporary Facilities
NCSU Contractor Safety
NCSU Reuse, Recycling, and Waste
011000 - SUMMARY
012100 - ALLOWANCES
012200 - UNIT PRICES
012300 - ALTERNATES
012500 - SUBSTITUTION PROCEDURES
012600 - CONTRACT MODIFICATION PROCEDURES
012900 - PAYMENT PROCEDURES
013100 - PROJECT MANAGEMENT AND COORDINATION
013200 - CONSTRUCTION PROGRESS DOCUMENTATION
013300 - SUBMITTAL PROCEDURES
014000 - QUALITY REQUIREMENTS
014200 - REFERENCES
014339 - MOCKUPS
015000 - TEMPORARY FACILITIES AND CONTROLS
015639 - TEMPORARY TREE AND PLANT PROTECTION
016000 - PRODUCT REQUIREMENTS
017300 - EXECUTION
017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
017700 - CLOSEOUT PROCEDURES
017823 - OPERATION AND MAINTENANCE DATA
017839 - PROJECT RECORD DOCUMENTS
017900 - DEMONSTRATION AND TRAINING

DIVISION 03 - CONCRETE

03 1000 - CONCRETE FORMING AND ACCESSORIES
03 2000 - CONCRETE REINFORCING
03 3000 - CAST-IN-PLACE CONCRETE
03 3543 - POLISHED CONCRETE FINISHING

DIVISION 05 - METALS

05 1200 - STRUCTURAL STEEL FRAMING

05 1200 – STEEL JOIST FRAMING
05 3100 – STEEL DECKING
05 4000 - COLD-FORMED METAL FRAMING
05 4400 - COLD-FORMED METAL TRUSSES
055000 - METAL FABRICATIONS

DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES

06 1600 – SHEATHING
06 2013 – EXTERIOR FINISH CARPENTRY
06 4116 – PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS
064216.10 - MDF WOOD PANELING
064216.11 - PAPER COMPOSITE PANELING
066400 - PLASTIC PANELING

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 2100 – THERMAL INSULATION
07 2726 – FLUID-APPLIED MEMBRANE AIR BARRIERS
07 4113.16 – STANDING-SEAM METAL ROOF PANELS
07 4213.13 – FORMED METAL WALL PANELS
07 4293 – SOFFIT PANELS
07 6200 – SHEET METAL FLASHING AND TRIM
07 9200 - JOINT SEALANTS
07 9219 – ACOUSTICAL JOINT SEALANTS

DIVISION 08 - OPENINGS

08 1113 - HOLLOW METAL DOORS AND FRAMES
08 1416 – FLUSH WOOD DOORS
083113 - ACCESS DOORS AND FRAMES
08 3323 – OVERHEAD COILING DOORS
08 3513.13 – MULTIPANEL FOLDING ALUMINUM-FRAMED GLASS DOORS
083800 - TRAFFIC DOORS
08 4113 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
08 7100 - DOOR HARDWARE
08 8000 – GLAZING
089119 - FIXED LOUVERS

DIVISION 09 - FINISHES

09 2216 - NON-STRUCTURAL METAL FRAMING
092400 - CEMENT PLASTERING
09 2900 - GYPSUM BOARD
09 3013 - CERAMIC TILING
09 5113 - ACOUSTICAL PANEL CEILINGS
095480 - SUSPENDED PLASTIC PANEL CEILINGS
09 6513 - RESILIENT BASE AND ACCESSORIES
096516 - RESILIENT SHEET FLOORING
097200 - WALL COVERINGS
098436 - SOUND-ABSORBING CEILING UNITS
09 9113 - EXTERIOR PAINTING
09 9123 - INTERIOR PAINTING

099611 - HIGH-PERFORMANCE COATINGS

DIVISION 10 - SPECIALTIES

101100 - VISUAL DISPLAY UNITS
101423 - PANEL SIGNAGE
10 2113.19 – PLASTIC TOILET COMPARTMENTS
10 2800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

DIVISION 11 – EQUIPMENT

114000 - FOODSERVICE EQUIPMENT
114001 - INSECT REARING ROOMS

DIVISION 12 – FURNISHINGS

12 3553.13 – METAL LABORATORY CASEWORK
123661.19 - QUARTZ AGGLOMERATE COUNTERTOPS

DIVISION 22 – PLUMBING

22 0513 COMMON MOTOR REQUIREMENTS FOR PLUMBING EQUIPMENT
22 0517 SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING
22 0518 ESCUTCHEONS FOR PLUMBING PIPING
22 0519 METERS AND GAGES FOR PLUMBING PIPING
22 0523.12 BALL VALVES FOR PLUMBING PIPING
22 0523.14 CHECK VALVES FOR PLUMBING PIPING
22 0523.15 GATE VALVES FOR PLUMBING PIPING
22 0529 HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT
22 0548.13 VIBRATION CONTROLS FOR PLUMBING PIPING AND EQUIPMENT
22 0553 IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT
22 0719 PLUMBING PIPING INSULATION
22 1116 DOMESTIC WATER PIPING
22 1119 DOMESTIC WATER PIPING SPECIALTIES
22 1123.21 INLINE, DOMESTIC WATER PUMPS
22 1316 SANITARY WASTE AND VENT PIPING
22 1319 SANITARY WASTE PIPING SPECIALTIES
22 1319.13 SANITARY DRAINS
221353 FACILITY SEPTIC TANKS
22 3300 ELECTRIC, DOMESTIC WATER HEATERS
22 4213.13 COMMERCIAL WATER CLOSETS
22 4213.16 COMMERCIAL URINALS
22 4216.13 COMMERCIAL LAVATORIES
22 4216.16 COMMERCIAL SINKS
22 4716 PRESSURE WATER COOLERS

DIVISION 23 – HVAC

23 0513	COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT
23 0517	SLEEVES AND SLEEVE SEALS FOR HVAC PIPING
23 0518	ESCUTCHEONS FOR HVAC PIPING
23 0529	HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
23 0548.13	VIBRATION CONTROLS FOR HVAC
23 0553	IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
23 0593	TESTING, ADJUSTING, AND BALANCING FOR HVAC
23 0713	DUCT INSULATION
23 0923	DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC
23 2113	HYDRONIC PIPING
23 3113	METAL DUCTS
23 3300	AIR DUCT ACCESSORIES
23 3346	FLEXIBLE DUCTS
23 3416	CENTRIFUGAL HVAC FANS
23 3600	AIR TERMINAL UNITS
23 3713.13	AIR DIFFUSERS
23 3713.23	REGISTERS AND GRILLES
23 7416.11	PACKAGED, SMALL CAPACITY, ROOFTOP AIR-CONDITIONING UNITS

DIVISION 26 – ELECTRICAL

26 0519	LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES
26 0526	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
26 0529	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
26 0533	RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS
26 0543	UNDERGROUND DUCTS AND RACEWAYS FOR ELECTRICAL SYSTEMS
26 0548.16	SEISMIC CONTROLS FOR ELECTRICAL SYSTEMS
26 0553	IDENTIFICATION FOR ELECTRICAL SYSTEMS
26 0573	COORDINATION STUDIES
26 0923	LIGHTING CONTROL DEVICES
26 2416	PANELBOARDS
26 2726	WIRING DEVICES
26 2813	FUSES
26 2816	ENCLOSED SWITCHES AND CIRCUIT BREAKERS
26 2923	VARIABLE FREQUENCY MOTOR CONTROLLERS
26 3214	DIESEL-ENGINE-DRIVEN GENERATOR
26 3600	TRANSFER SWITCHES
26 3610	GENERATOR DOCKING STATION

- 26 4313 SURGE PROTECTION FOR LOW-VOLTAGE ELECTRICAL POWER CIRCUITS
- 26 5119 LED INTERIOR LIGHTING
- 26 5213 EMERGENCY AND EXIT LIGHTING

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

- 28 4621.11 ADDRESSABLE FIRE-ALARM SYSTEM

DIVISION 31 - EARTHWORK

- 31 1000 – SITE CLEARING
- 312040 - EROSION & SEDIMENT CONTROL

DIVISION 32 – EXTERIOR IMPROVEMENTS

- 321220 - AGGREGATES
- 32 1313 – CONCRETE PAVING
- 32 1373 – CONCRETE PAVING JOINT SEALANTS
- 32 1713– PARKING BUMPERS
- 32 1723– PAVEMENT MARKINGS
- 32 1726– TACTILE WARNING SURFACING
- 32 3300– SITE FURNISHINGS
- 329100 - PLANTING SOIL
- 32 9115– SOIL PREPARATION
- 32 9200 – TURF AND GRASSES
- 32 9300 – PLANTS

DIVISION 33 – UTILITIES

- 331200 - WATER UTILITY DISTRIBUTION EQUIPMENT
- 333000 - SANITARY SEWERAGE UTILITIES
- 334100 - STORM UTILITY DRAINAGE PIPING

APPENDIX

- FORM OF PROPOSAL
- MBE AFFIDAVITS
- FORM OF BID BOND
- FORM OF CONSTRUCTION CONTRACT
- FORM OF PERFORMANCE BOND
- FORM OF PAYMENT BOND
- SHEET FOR ATTACHING POWER OF ATTORNEY
- SHEET FOR ATTACHING INSURANCE CERTIFICATES
- APPROVAL OF THE ATTORNEY GENERAL
- OFFICE OF STATE BUDGET AND MANAGEMENT

END TABLE OF CONTENTS

**INSTRUCTIONS TO BIDDERS
AND
GENERAL CONDITIONS OF THE CONTRACT**

STANDARD FORM FOR CONSTRUCTION PROJECTS

**STATE CONSTRUCTION OFFICE
NORTH CAROLINA
DEPARTMENT OF ADMINISTRATION**

Form OC-15

This document is intended for use on State capital construction projects and shall not be used on any project that is not reviewed and approved by the State Construction Office. Extensive modification to the General Conditions by means of “Supplementary General Conditions” is strongly discouraged. State agencies and institutions may include special requirements in “Division 1 – General Requirements” of the specifications, where they do not conflict with the General Conditions.

**Twenty Fourth Edition January 2013
Revision 1 - May 2024: Article 23.b**

INSTRUCTIONS TO BIDDERS

For a proposal to be considered it must be in accordance with the following instructions:

1. PROPOSALS

Proposals must be made in strict accordance with the Form of Proposal provided therefor, and all blank spaces for bids, alternates, and unit prices applicable to bidder's work shall be properly filled in. When requested alternates are not bid, the proposer shall so indicate by the words "No Bid". Any blanks shall also be interpreted as "No Bid". The bidder agrees that bid on Form of Proposal detached from specifications will be considered and will have the same force and effect as if attached thereto. Photocopied or faxed proposals will not be considered. Numbers shall be stated both in writing and in figures for the base bids and alternates. If figures and writing differ, the written number will supersede the figures.

Any modifications to the Form of Proposal (including alternates and/or unit prices) will disqualify the bid and may cause the bid to be rejected.

The bidder shall fill in the Form of Proposal as follows:

- a. If the documents are executed by a sole owner, that fact shall be evidenced by the word "Owner" appearing after the name of the person executing them.
- b. If the documents are executed by a partnership, that fact shall be evidenced by the word "Co-Partner" appearing after the name of the partner executing them.
- c. If the documents are executed on the part of a corporation, they shall be executed by either the president or the vice president and attested by the secretary or assistant secretary in either case, and the title of the office of such persons shall appear after their signatures. The seal of the corporation shall be impressed on each signature page of the documents.
- d. If the proposal is made by a joint venture, it shall be executed by each member of the joint venture in the above form for sole owner, partnership or corporation, whichever form is applicable.
- e. All signatures shall be properly witnessed.
- f. If the contractor's license of a bidder is held by a person other than an owner, partner or officer of a firm, then the licensee shall also sign and be a party to the proposal. The title "Licensee" shall appear under his/her signature.

Proposals should be addressed as indicated in the Advertisement for Bids and be delivered, enclosed in an opaque sealed envelope, marked "Proposal" and bearing the title of the work, name of the bidder, and the contractor's license number of the bidder. Bidders should clearly mark on the outside of the bid envelope which contract(s) they are bidding.

Bidder shall identify on the bid, the minority businesses that will be utilized on the project with corresponding total dollar value of the bid and affidavit listing good faith efforts or an affidavit indicating work under contract will be self-performed, as required by G.S. 143-128.2(c) and G.S. 143-128.2(f). Failure to comply with these requirements is grounds for rejection of the bid.

For projects bid in the single-prime alternative, the names and license numbers of major subcontractors shall be listed on the proposal form.

It shall be the specific responsibility of the bidder to deliver his bid to the proper official at the selected place and prior to the announced time for the opening of bids. Later delivery of a bid for any reason, including delivery by any delivery service, shall disqualify the bid.

Unit prices quoted in the proposal shall include overhead and profit and shall be the full compensation for the contractor's cost involved in the work. See General Conditions, Article 19c-1.

2. EXAMINATION OF CONDITIONS

It is understood and mutually agreed that by submitting a bid the bidder acknowledges that he has carefully examined all documents pertaining to the work, the location, accessibility and general character of the site of the work and all existing buildings and structures within and adjacent to the site, and has satisfied himself as to the nature of the work, the condition of existing buildings and structures, the conformation of the ground, the character, quality and quantity of the material to be encountered, the character of the equipment, machinery, plant and any other facilities needed preliminary to and during prosecution of the work, the general and local conditions, the construction hazards, and all other matters, including, but not limited to, the labor situation which can in any way affect the work under the contract, and including all safety measures required by the Occupational Safety and Health Act of 1970 and all rules and regulations issued pursuant thereto. It is further mutually agreed that by submitting a proposal the bidder acknowledges that he has satisfied himself as to the feasibility and meaning of the plans, drawings, specifications and other contract documents for the construction of the work and that he accepts all the terms, conditions and stipulations contained therein; and that he is prepared to work in cooperation with other contractors performing work on the site.

Reference is made to contract documents for the identification of those surveys and investigation reports of subsurface or latent physical conditions at the site or otherwise affecting performance of the work which have been relied upon by the designer in preparing the documents. The owner will make copies of all such surveys and reports available to the bidder upon request.

Each bidder may, at his own expense, make such additional surveys and investigations as he may deem necessary to determine his bid price for the performance of the work. Any on-site investigation shall be done at the convenience of the owner. Any reasonable request for access to the site will be honored by the owner.

3. BULLETINS AND ADDENDA

Any addenda to specifications issued during the time of bidding are to be considered covered in the proposal and in closing a contract they will become a part thereof. It shall be the bidder's responsibility to ascertain prior to bid time the addenda issued and to see that his bid includes any changes thereby required.

Should the bidder find discrepancies in, or omission from, the drawings or documents or should he be in doubt as to their meaning, he shall at once notify the designer who will send written instructions in the form of addenda to all bidders. Notification should be no later than seven (7) days prior to the date set for receipt of bids. Neither the owner nor the designer will be responsible for any oral instructions.

All addenda should be acknowledged by the bidder(s) on the Form of Proposal. However, even if not acknowledged, by submitting a bid, the bidder has certified that he has reviewed all issued addenda and has included all costs associated within his bid.

4. BID SECURITY

Each proposal shall be accompanied by a cash deposit or a certified check drawn on some bank or trust company insured by the Federal Deposit Insurance Corporation, or a bid bond in an amount equal to not less than five percent (5%) of the proposal, said deposit to be retained by the owner as liquidated damages in event of failure of the successful bidder to execute the contract within ten (10) days after the award or to give satisfactory surety as required by law (G.S. 143-129).

Bid bond shall be conditioned that the surety will, upon demand, forthwith make payment to the obligee upon said bond if the bidder fails to execute the contract. The owner may retain bid securities of any bidder(s) who may have a reasonable chance of award of contract for the full duration of time stated in the Notice to Bidders. Other bid securities may be released sooner, at the discretion of the owner. All bid securities (cash or certified checks) shall be returned to the bidders promptly after award of contracts, and no later than seven (7) days after expiration of the holding period stated in the Notice to Bidders. Standard Form of Bid Bond is included in these specifications and shall be used.

5. RECEIPT OF BIDS

Bids shall be received in strict accordance with requirements of the General Statutes of North Carolina. Bid security shall be required as prescribed by statute. Prior to the closing of the bid, the bidder will be permitted to change or withdraw his bid. Guidelines for opening of public construction bids are available from the State Construction Office.

6. OPENING OF BIDS

Upon opening, all bids shall be read aloud. Once bidding is closed, there shall not be any withdrawal of bids by any bidder and no bids may be returned by the designer to any bidder. After the opening of bids, no bid may be withdrawn, except under the provisions of General Statute 143-129.1, for a period of thirty days unless otherwise specified. Should the successful bidder default and fail to execute a contract, the contract may be awarded to the next lowest and responsible bidder. The owner reserves the unqualified right to reject any and all bids. Reasons for rejection may include, but shall not be limited to, the following:

- a. If the Form of Proposal furnished to the bidder is not used or is altered.
- b. If the bidder fails to insert a price for all bid items, alternate and unit prices requested.
- c. If the bidder adds any provisions reserving the right to accept or reject any award.
- d. If there are unauthorized additions or conditional bids, or irregularities of any kind which tend to make the proposal incomplete, indefinite or ambiguous as to its meaning.
- e. If the bidder fails to complete the proposal form where information is requested so the bid may be properly evaluated by the owner.
- f. If the unit prices contained in the bid schedule are unacceptable to the owner and the State Construction Office.
- g. If the bidder fails to comply with other instructions stated herein.

7. BID EVALUATION

The award of the contract will be made to the lowest responsible bidder as soon as practical. The owner may award on the basis of the base bid and any alternates the owner chooses.

Before awarding a contract, the owner may require the apparent low bidder to qualify himself to be a responsible bidder by furnishing any or all of the following data:

- a. The latest financial statement showing assets and liabilities of the company or other information satisfactory to the owner.
- b. A listing of completed projects of similar size.
- c. Permanent name and address of place of business.
- d. The number of regular employees of the organization and length of time the organization has been in business under present name.
- e. The name and home office address of the surety proposed and the name and address of the responsible local claim agent.
- f. The names of members of the firms who hold appropriate trade licenses, together with license numbers.
- g. If prequalified, contractor info will be reviewed and evaluated comparatively to submitted prequalification package.

Failure or refusal to furnish any of the above information, if requested, shall constitute a basis for disqualification of any bidder.

In determining the lowest responsible, responsive bidder, the owner shall take into consideration the bidder's compliance with the requirements of G.S. 143-128.2(c), the past performance of the bidder on construction contracts for the State with particular concern given to completion times, quality of work, cooperation with other contractors, and cooperation with the designer and owner. Failure of the low bidder to furnish affidavit and/or documentation as required by G.S. 143-128.2(c) shall constitute a basis for disqualification of the bid.

Should the owner adjudge that the apparent low bidder is not the lowest responsible, responsive bidder by virtue of the above information, said apparent low bidder will be so notified and his bid security shall be returned to him.

8. PERFORMANCE BOND

The successful bidder, upon award of contract, shall furnish a performance bond in an amount equal to 100 percent of the contract price. See Article 35, General Conditions.

9. PAYMENT BOND

The successful bidder, upon award of contract, shall furnish a payment bond in an amount equal to 100 percent of the contract price. See Article 35, General Conditions.

10. PAYMENTS

Payments to the successful bidders (contractors) will be made on the basis of monthly estimates. See Article 31, General Conditions.

11. PRE-BID CONFERENCE

Prior to the date set for receiving bids, the Designer may arrange and conduct a Pre-Bid Conference for all prospective bidders. The purpose of this conference is to review project requirements and to respond to questions from prospective bidders and their subcontractors or material suppliers related to the intent of bid documents. Attendance by prospective bidders shall be as required by the "Notice to Bidders".

12. SUBSTITUTIONS

In accordance with the provisions of G.S. 133-3, material, product, or equipment substitutions proposed by the bidders to those specified herein can only be considered during the bidding phase until ten (10) days prior to the receipt of bids when submitted to the Designer with sufficient data to confirm material, product, or equipment equality. Proposed substitutions submitted after this time will be considered only as potential change order.

Submittals for proposed substitutions shall include the following information:

- a. Name, address, and telephone number of manufacturer and supplier as appropriate.
- b. Trade name, model or catalog designation.
- c. Product data including performance and test data, reference standards, and technical descriptions of material, product, or equipment. Include color samples and samples of available finishes as appropriate.
- d. Detailed comparison with specified products including performance capabilities, warranties, and test results.
- e. Other pertinent data including data requested by the Designer to confirm product equality.

If a proposed material, product, or equipment substitution is deemed equal by the Designer to those specified, all bidders of record will be notified by Addendum.

GENERAL CONDITIONS OF THE CONTRACT

The use or reproduction of this document or any part thereof is authorized for and limited to use on projects of the State of North Carolina, and is distributed by, through and at the discretion of the State Construction Office, Raleigh, North Carolina, for that distinct and sole purpose.

TABLE OF CONTENTS

ARTICLE	TITLE	PAGE
1	Definitions.....	9
2	Intent and Execution of Documents	11
3	Clarifications and Detail Drawings	12
4	Copies of Drawings and Specifications.....	12
5	Shop Drawings, Submittals, Samples, Data	13
6	Working Drawings and Specifications at the Job Site	13
7	Ownership of Drawings and Specifications	14
8	Materials, Equipment, Employees	14
9	Royalties, Licenses and Patent	15
10	Permits, Inspections, Fees, Regulations	15
11	Protection of Work, Property and the Public	16
12	Sedimentation Pollution Control Act of 1973	17
13	Inspection of the Work.....	17
14	Construction Supervision and Schedule	18
15	Separate Contracts and Contractor Relationships.....	22
16	Subcontracts and Subcontractors	23
17	Contractor and Subcontractor Relationships.....	23
18	Designer's Status	24
19	Changes in the Work	25
20	Claims for Extra Cost	27
21	Minor Changes in the Work	29
22	Uncorrected Faulty Work.....	29
23	Time of Completion, Delays, Extension of Time	29
24	Partial Utilization: Beneficial Occupancy	30
25	Final Inspection, Acceptance, and Project Closeout	31
26	Correction of Work Before Final Payment	31
27	Correction of Work After Final Payment	32
28	Owner's Right to Do Work	32
29	Annulment of Contract.....	32
30	Contractor's Right to Stop Work or Terminate the Contract	33
31	Requests for Payments	33
32	Certificates of Payment and Final Payment.....	34
33	Payments Withheld.....	36
34	Minimum Insurance Requirements.....	36
35	Performance Bond and Payment Bond.....	37
36	Contractor's Affidavit.....	38
37	Assignments	38
38	Use of Premises.....	38
39	Cutting, Patching and Digging.....	38
40	Utilities, Structures, Signs	38
41	Cleaning Up.....	40
42	Guarantee	41

43 Codes and Standards41
44 Indemnification.....41
45 Taxes41
46 Equal Opportunity Clause.....42
47 Employment of the Handicapped42
48 Asbestos-Containing Materials (ACM)43
49 Minority Business Participation.....43
50 Contractor Evaluation43
51 Gifts43
52 Auditing Access to Persons and Records.....44
53 North Carolina False Claims Act44
54 Termination for Convenience45

ARTICLE 1 - DEFINITIONS

- a. The **contract documents** consist of the Notice to Bidders; Instructions to Bidders; General Conditions of the Contract; special conditions if applicable; Supplementary General Conditions; the drawing and specifications, including all bulletins, addenda or other modifications of the drawings and specifications incorporated into the documents prior to their execution; the proposal; the contract; the performance bond; the payment bond; insurance certificates; the approval of the attorney general; and the certificate of the Office of State Budget and Management. All of these items together form the contract.
- b. The **owner** is the State of North Carolina through the agency named in the contract.
- c. The **designer(s)** are those referred to within this contract, or their authorized representatives. The Designer(s), as referred to herein, shall mean architect and/or engineer. They will be referred to hereinafter as if each were of the singular number, masculine gender.
- d. The **contractor**, as referred to hereinafter, shall be deemed to be either of the several contracting parties called the "Party of the First Part" in either of the several contracts in connection with the total project. Where, in special instances hereinafter, a particular contractor is intended, an adjective precedes the word "contractor," as "general," "heating," etc. For the purposes of a single prime contract, the term Contractor shall be deemed to be the single contracting entity identified as the "Party of the First Part" in the single Construction Contract. Any references or adjectives that name or infer multiple prime contractors shall be interpreted to mean the single prime Contractor.
- e. A **subcontractor**, as the term is used herein, shall be understood to be one who has entered into a direct contract with a contractor, and includes one who furnishes materials worked to a special design in accordance with plans and specifications covered by the contract, but does not include one who only sells or furnishes materials not requiring work so described or detailed.
- f. **Written notice** shall be defined as notice in writing delivered in person to the contractor, or to a partner of the firm in the case of a partnership, or to a member of the contracting organization, or to an officer of the organization in the case of a corporation, or sent to the last known business address of the contracting organization by registered mail.
- g. **Work**, as used herein as a noun, is intended to include materials, labor, and workmanship of the appropriate contractor.
- h. The **project** is the total construction work to be performed under the contract documents by the several contractors.
- i. **Project Expediter**, as used herein, is an entity stated in the contract documents, designated to effectively facilitate scheduling and coordination of work activities. See Article 14(f) for responsibilities of a Project Expediter. **For the purposes of a single prime contract, the single prime contractor shall be designated as the Project Expediter.**
- j. **Change order**, as used herein, shall mean a written order to the contractor subsequent to the signing of the contract authorizing a change in the contract. The change order shall be signed by the contractor, designer and the owner, and approved by the State Construction Office, in that order (Article 19).

- k. **Field Order**, as used herein, shall mean a written approval for the contractor to proceed with the work requested by owner prior to issuance of a formal Change Order. The field order shall be signed by the contractor, designer, owner, and State Construction Office.
- l. **Time of completion**, as stated in the contract documents, is to be interpreted as consecutive calendar days measured from the date established in the written Notice to Proceed, or such other date as may be established herein (Article 23).
- m. **Liquidated damages**, as stated in the contract documents [, is an amount reasonably estimated in advance to cover the consequential damages associated with the Owner's economic loss in not being able to use the Project for its intended purposes at the end of the contract's completion date as amended by change order, if any, by reason of failure of the contractor(s) to complete the work within the time specified. Liquidated damages does not include the Owner's extended contract administration costs (including but not limited to additional fees for architectural and engineering services, testing services, inspection services, commissioning services, etc.), such other damages directly resulting from delays caused solely by the contractor, or consequential damages that the Owner identified in the bid documents that may be impacted by any delay caused solely by the Contractor (e.g., if a multi-phased project-subsequent phases, delays in start other projects that are dependent on the completion of this Project, extension of leases and/or maintenance agreements for other facilities).
- n. **Surety**, as used herein, shall mean the bonding company or corporate body which is bound with and for the contractor, and which engages to be responsible for the contractor and his acceptable performance of the work.
- o. **Routine written communications between the Designer and the Contractor** are any communication other than a "request for information" provided in letter, memo, or transmittal format, sent by mail, courier, electronic mail, or facsimile. Such communications can not be identified as "request for information".
- p. **Clarification or Request for information (RFI)** is a request from the Contractor seeking an interpretation or clarification by the Designer relative to the contract documents. The RFI, which shall be labeled (RFI), shall clearly and concisely set forth the issue or item requiring clarification or interpretation and why the response is needed. The RFI must set forth the Contractor's interpretation or understanding of the contract documents requirements in question, along with reasons for such an understanding.
- q. **Approval** means written or imprinted acknowledgement that materials, equipment or methods of construction are acceptable for use in the work.
- r. **Inspection** shall mean examination or observation of work completed or in progress to determine its compliance with contract documents.
- s. **"Equal to" or "approved equal"** shall mean materials, products, equipment, assemblies, or installation methods considered equal by the bidder in all characteristics (physical, functional, and aesthetic) to those specified in the contract documents. Acceptance of equal is subject to approval of Designer and owner.
- t. **"Substitution" or "substitute"** shall mean materials, products, equipment, assemblies, or installation methods deviating in at least one characteristic (physical, functional, or aesthetic) from those specified, but which in the opinion of the bidder would improve competition and/or enhance the finished installation. Acceptance of substitution is subject to the approval of the Designer and owner.

- u. **Provide** shall mean furnish and install complete in place, new, clean, operational, and ready for use.
- v. **Indicated and shown** shall mean provide as detailed, or called for, and reasonably implied in the contract documents.
- w. **Special inspector** is one who inspects materials, installation, fabrication, erection or placement of components and connections requiring special expertise to ensure compliance with the approved construction documents and referenced standards.
- x. **Commissioning** is a quality assurance process that verifies and documents that building components and systems operate in accordance to the owner's project requirements and the project design documents.
- y. **Designer Final Inspection** is the inspection performed by the design team to determine the completeness of the project in accordance with approved plans and specifications. This inspection occurs prior to SCO final inspection.
- z. **SCO Final Inspection** is the inspection performed by the State Construction Office to determine the completeness of the project in accordance with NC Building Codes and approved plans and specifications.
- aa. **Beneficial Occupancy** is requested by the owner and is occupancy or partial occupancy of the building after all life safety items have been completed as determined by the State Construction Office. Life safety items include but not limited to fire alarm, sprinkler, egress and exit lighting, fire rated walls, egress paths and security.
- bb. Final Acceptance is the date in which the State Construction Office accepts the construction as totally complete. This includes the SCO Final Inspection and certification by the designer that all punch lists are completed.

ARTICLE 2 - INTENT AND EXECUTION OF DOCUMENTS

- a. The drawings and specifications are complementary, one to the other, and that which is shown on the drawings or called for in the specifications shall be as binding as if it were both called for and shown. The intent of the drawings and specifications is to establish the scope of all labor, materials, transportation, equipment, and any and all other things necessary to provide a bid for a complete job. In case of discrepancy or disagreement in the contract documents, the order of precedence shall be: Form of Contract, specifications, large-scale detail drawings, small-scale drawings.
- b. The wording of the specifications shall be interpreted in accordance with common usage of the language except that words having a commonly used technical or trade meaning shall be so interpreted in preference to other meanings.
- c. The contractor shall execute each copy of the proposal, contract, performance bond and payment bond as follows:
 - 1. If the documents are executed by a sole owner, that fact shall be evidenced by the word "Owner" appearing after the name of the person executing them.
 - 2. If the documents are executed by a partnership, that fact shall be evidenced by the word "Co-Partner" appearing after the name of the partner executing them.

3. If the documents are executed on the part of a corporation, they shall be executed by either the president or the vice president and attested by the secretary or assistant secretary in either case, and the title of the office of such persons shall appear after their signatures. The seal of the corporation shall be impressed on each signature page of the documents.
4. If the documents are made by a joint venture, they shall be executed by each member of the joint venture in the above form for sole owner, partnership or corporation, whichever form is applicable to each particular member.
5. All signatures shall be properly witnessed.
6. If the contractor's license is held by a person other than an owner, partner or officer of a firm, then the licensee shall also sign and be a party to the contract. The title "Licensee" shall appear under his/her signature.
7. The bonds shall be executed by an attorney-in-fact. There shall be attached to each copy of the bond a certified copy of power of attorney properly executed and dated.
8. Each copy of the bonds shall be countersigned by an authorized individual agent of the bonding company licensed to do business in North Carolina. The title "Licensed Resident Agent" shall appear after the signature.
9. The seal of the bonding company shall be impressed on each signature page of the bonds.
10. The contractor's signature on the performance bond and the payment bond shall correspond with that on the contract. The date of performance and payment bond shall not be prior to the date of the contract.

ARTICLE 3 - CLARIFICATIONS AND DETAIL DRAWINGS

- a. In such cases where the nature of the work requires clarification by the designer, such clarification shall be furnished by the designer with reasonable promptness by means of written instructions or detail drawings, or both. Clarifications and drawings shall be consistent with the intent of contract documents, and shall become a part thereof.
- b. The contractor(s) and the designer shall prepare, if deemed necessary, a schedule fixing dates upon which foreseeable clarifications will be required. The schedule will be subject to addition or change in accordance with progress of the work. The designer shall furnish drawings or clarifications in accordance with that schedule. The contractor shall not proceed with the work without such detail drawings and/or written clarifications.

ARTICLE 4 - COPIES OF DRAWINGS AND SPECIFICATIONS

The designer or Owner shall furnish free of charge to the contractors electronic copies of plans and specifications. If requested by the contractor, paper copies of plans and specifications shall be furnished free of charge as follows:

- a. General contractor - Up to twelve (12) sets of general contractor drawings and specifications, up to six (6) sets of which shall include drawings and specifications of all other contracts, plus a clean set of black line prints on white paper of all appropriate drawings, upon which the contractor shall clearly and legibly record all work-in-place that is at variance with the contract documents.

- b. Each other contractor - Up to six (6) sets of the appropriate drawings and specifications, up to three (3) sets of which shall include drawings and specifications of all other contracts, plus a clean set of black line prints on white paper of all appropriate drawings, upon which the contractor shall clearly and legibly record all work-in-place that is at variance with the contract documents.
- c. Additional sets shall be furnished at cost, including mailing, to the contractor upon request by the contractor. This cost shall be stated in the bidding documents.
- d. For the purposes of a single-prime contract, the contractor shall receive up to 30 sets of drawings and specifications, plus a clean set of black line prints on white paper of all appropriate drawings, upon which the contractor shall clearly and legibly record all work-in-place that is at variance with the contract documents.

ARTICLE 5 - SHOP DRAWINGS, SUBMITTALS, SAMPLES, DATA

- a. Within 15 consecutive calendar days after the notice to proceed, each prime contractor shall submit a schedule for submission of all shop drawings, product data, samples, and similar submittals through the Project Expediter to the Designer. This schedule shall indicate the items, relevant specification sections, other related submittal, data, and the date when these items will be furnished to the designer.
- b. The Contractor(s) shall review, approve and submit to the Designer all Shop Drawings, Coordination Drawings, Product Data, Samples, Color Charts, and similar submittal data required or reasonably implied by the Contract Documents. Required Submittals shall bear the Contractor's stamp of approval, any exceptions to the Contract Documents shall be noted on the submittals, and copies of all submittals shall be of sufficient quantity for the Designer to retain up to three (3) copies of each submittal for his own use plus additional copies as may be required by the Contractor. Submittals shall be presented to the Designer in accordance with the schedule submitted in paragraph (a). so as to cause no delay in the activities of the Owner or of separate Contractors.
- c. The Designer shall review required submittals promptly, noting desired corrections if any, and retaining three (3) copies (1 for the Designer, 1 for the owner and 1 for SCO) for his use. The remaining copies of each submittal shall be returned to the Contractor not later than twenty (20) days from the date of receipt by the Designer, for the Contractor's use or for corrections and resubmittal as noted by the Designer. When resubmittals are required, the submittal procedure shall be the same as for the original submittals.
- d. Approval of shop drawings/submittals by the Designer shall not be construed as relieving the Contractor from responsibility for compliance with the design or terms of the contract documents nor from responsibility of errors of any sort in the shop drawings, unless such lack of compliance or errors first have been called in writing to the attention of the Designer by the Contractor.

ARTICLE 6 - WORKING DRAWINGS AND SPECIFICATIONS AT THE JOB SITE

- a. The contractor shall maintain, in readable condition at his job office, one complete set of working drawings and specifications for his work including all shop drawings. Such drawings and specifications shall be available for use by the designer, his authorized representative, owner or State Construction Office.

- b. The contractor shall maintain at the job office, a day-to-day record of work-in-place that is at variance with the contract documents. Such variations shall be fully noted on project drawings by the contractor and submitted to the designer upon project completion and no later than 30 days after final acceptance of the project.
- c. The contractor shall maintain at the job office a record of all required tests that have been performed, clearly indicating the scope of work inspected and the date of approval or rejection.

ARTICLE 7 - OWNERSHIP OF DRAWINGS AND SPECIFICATIONS

All drawings and specifications are instruments of service and remain the property of the owner. The use of these instruments on work other than this contract without permission of the owner is prohibited. All copies of drawings and specifications other than contract copies shall be returned to the owner upon request after completion of the work.

ARTICLE 8 - MATERIALS, EQUIPMENT, EMPLOYEES

- a. The contractor shall, unless otherwise specified, supply and pay for all labor, transportation, materials, tools, apparatus, lights, power, heat, sanitary facilities, water, scaffolding and incidentals necessary for the completion of his work, and shall install, maintain and remove all equipment of the construction, other utensils or things, and be responsible for the safe, proper and lawful construction, maintenance and use of same, and shall construct in the best and most workmanlike manner, a complete job and everything incidental thereto, as shown on the plans, stated in the specifications, or reasonably implied therefrom, all in accordance with the contract documents.
- b. All materials shall be new and of quality specified, except where reclaimed material is authorized herein and approved for use. Workmanship shall at all times be of a grade accepted as the best practice of the particular trade involved, and as stipulated in written standards of recognized organizations or institutes of the respective trades except as exceeded or qualified by the specifications.
- c. Upon notice, the contractor shall furnish evidence as to quality of materials.
- d. Products are generally specified by ASTM or other reference standard and/or by manufacturer's name and model number or trade name. When specified only by reference standard, the Contractor may select any product meeting this standard, by any manufacturer. When several products or manufacturers are specified as being equally acceptable, the Contractor has the option of using any product and manufacturer combination listed. However, the contractor shall be aware that the cited examples are used only to denote the quality standard of product desired and that they do not restrict bidders to a specific brand, make, manufacturer or specific name; that they are used only to set forth and convey to bidders the general style, type, character and quality of product desired; and that equivalent products will be acceptable. Request for substitution of materials, items, or equipment shall be submitted to the designer for approval or disapproval; such approval or disapproval shall be made by the designer prior to the opening of bids. Alternate materials may be requested after the award if it can clearly be demonstrated that it is an added benefit to the owner and the designer and owner approves.
- e. The designer is the judge of equality for proposed substitution of products, materials or equipment.

- g. If at any time during the construction and completion of the work covered by these contract documents, the language, conduct, or attire of any workman of the various crafts be adjudged a nuisance to the owner or designer, or if any workman be considered detrimental to the work, the contractor shall order such parties removed immediately from grounds.

ARTICLE 9 - ROYALTIES, LICENSES AND PATENTS

It is the intention of the contract documents that the work covered herein will not constitute in any way infringement of any patent whatsoever unless the fact of such patent is clearly evidenced herein. The contractor shall protect and save harmless the owner against suit on account of alleged or actual infringement. The contractor shall pay all royalties and/or license fees required on account of patented articles or processes, whether the patent rights are evidenced hereinafter.

ARTICLE 10 - PERMITS, INSPECTIONS, FEES, REGULATIONS

- a. The contractor shall give all notices and comply with all laws, ordinances, codes, rules and regulations bearing on the conduct of the work under this contract. If the contractor observes that the drawings and specifications are at variance therewith, he shall promptly notify the designer in writing. See Instructions to Bidders, Paragraph 3, Bulletins and Addenda. Any necessary changes required after contract award shall be made by change order in accordance with Article 19. If the contractor performs any work knowing it to be contrary to such laws, ordinances, codes, rules and regulations, and without such notice to the designer, he shall bear all cost arising therefrom. Additional requirements implemented after bidding will be subject to equitable negotiations.
- b. All work under this contract shall conform to the North Carolina State Building Code and other State, local and national codes as are applicable. The cost of all required inspections and permits shall be the responsibility of the contractor and included within the bid proposal. All water taps, meter barrels, vaults and impact fees shall be paid by the contractor unless otherwise noted.
- d. Projects constructed by the State of North Carolina or by any agency or institution of the State are not subject to inspection by any county or municipal authorities and are not subject to county or municipal building codes. The contractor shall, however, cooperate with the county or municipal authorities by obtaining building permits. Permits shall be obtained at no cost.
- e. Projects involving local funding (community colleges) are subject also to county and municipal building codes and inspection by local authorities. The contractor shall pay the cost of these permits and inspections.

ARTICLE 11 - PROTECTION OF WORK, PROPERTY AND THE PUBLIC

- a. The contractors shall be jointly responsible for the entire site and the building or construction of the same and provide all the necessary protections, as required by the owner or designer, and by laws or ordinances governing such conditions. They shall be responsible for any damage to the owner's property, or of that of others on the job, by them, their personnel, or their subcontractors, and shall make good such damages. They shall be responsible for and pay for any damages caused to the owner. All contractors shall have access to the project at all times.
- b. The contractor shall provide cover and protect all portions of the structure when the work is not in progress, provide and set all temporary roofs, covers for doorways, sash and windows, and all other materials necessary to protect all the work on the building, whether set by him, or any of the subcontractors. Any work damaged through the lack of proper protection or from any other cause, shall be repaired or replaced without extra cost to the owner.
- c. No fires of any kind will be allowed inside or around the operations during the course of construction without special permission from the designer and owner.
- d. The contractor shall protect all trees and shrubs designated to remain in the vicinity of the operations by building substantial boxes around same. He shall barricade all walks, roads, etc., as directed by the designer to keep the public away from the construction. All trenches, excavations or other hazards in the vicinity of the work shall be well barricaded and properly lighted at night.
- e. The contractor shall provide all necessary safety measures for the protection of all persons on the job, including the requirements of the A.G.C. *Accident Prevention Manual in Construction*, as amended, and shall fully comply with all state laws or regulations and North Carolina State Building Code requirements to prevent accident or injury to persons on or about the location of the work. He shall clearly mark or post signs warning of hazards existing, and shall barricade excavations, elevator shafts, stairwells and similar hazards. He shall protect against damage or injury resulting from falling materials and he shall maintain all protective devices and signs throughout the progress of the work.
- f. The contractor shall adhere to the rules, regulations and interpretations of the North Carolina Department of Labor relating to Occupational Safety and Health Standards for the Construction Industry (Title 29, Code of Federal Regulations, Part 1926, published in Volume 39, Number 122, Part II, June 24, 1974, *Federal Register*), and revisions thereto as adopted by General Statutes of North Carolina 95-126 through 155.
- g. The contractor shall designate a responsible person of his organization as safety officer/inspector to inspect the project site for unsafe health and safety hazards, to report these hazards to the contractor for correction, and whose duties also include accident prevention on the project, and to provide other safety and health measures on the project site as required by the terms and conditions of the contract. The name of the safety inspector shall be made known to the designer and owner at the time of the preconstruction conference and in all cases prior to any work starting on the project.
- h. In the event of emergency affecting the safety of life, the protection of work, or the safety of adjoining properties, the contractor is hereby authorized to act at his own discretion, without further authorization from anyone, to prevent such threatened injury or damage.

Any compensation claimed by the contractor on account of such action shall be determined as provided for under Article 19(b).

- i. Any and all costs associated with correcting damage caused to adjacent properties of the construction site or staging area shall be borne by the contractor. These costs shall include but not be limited to flooding, mud, sand, stone, debris, and discharging of waste products.

ARTICLE 12 - SEDIMENTATION POLLUTION CONTROL ACT OF 1973

- a. Any land-disturbing activity performed by the contractor(s) in connection with the project shall comply with all erosion control measures set forth in the contract documents and any additional measures which may be required in order to ensure that the project is in full compliance with the Sedimentation Pollution Control Act of 1973, as implemented by Title 15, North Carolina Administrative Code, Chapter 4, Sedimentation Control, Subchapters 4A, 4B and 4C, as amended (15 N.C.A.C. 4A, 4B and 4C).
- b. Upon receipt of notice that a land-disturbing activity is in violation of said act, the contractor(s) shall be responsible for ensuring that all steps or actions necessary to bring the project in compliance with said act are promptly taken.
- c. The contractor(s) shall be responsible for defending any legal actions instituted pursuant to N.C.G.S. 113A-64 against any party or persons described in this article.
- d. To the fullest extent permitted by law, the contractor(s) shall indemnify and hold harmless the owner, the designer and the agents, consultants and employees of the owner and designer, from and against all claims, damages, civil penalties, losses and expenses, including, but not limited to, attorneys' fees, arising out of or resulting from the performance of work or failure of performance of work, provided that any such claim, damage, civil penalty, loss or expense is attributable to a violation of the Sedimentation Pollution Control Act. Such obligation shall not be construed to negate, abridge or otherwise reduced any other right or obligation of indemnity which would otherwise exist as to any party or persons described in this article.

ARTICLE 13 - INSPECTION OF THE WORK

- a. It is a condition of this contract that the work shall be subject to inspection during normal working hours and during any time work is in preparation and progress by the designer, designated official representatives of the owner, State Construction Office and those persons required by state law to test special work for official approval. The contractor shall therefore provide safe access to the work at all times for such inspections.
- b. All instructions to the contractor will be made only by or through the designer or his designated project representative. Observations made by official representatives of the owner shall be conveyed to the designer for review and coordination prior to issuance to the contractor.
- c. All work shall be inspected by designer, special inspector and/or State Construction Office prior to being covered by the contractor. Contractor shall give a minimum two weeks notice unless otherwise agreed to by all parties. If inspection fails, after the first reinspection all costs associated with additional reinspections shall be borne by the contractor.

- d. Where special inspection or testing is required by virtue of any state laws, instructions of the designer, specifications or codes, the contractor shall give adequate notice to the designer of the time set for such inspection or test, if the inspection or test will be conducted by a party other than the designer. Such special tests or inspections will be made in the presence of the designer, or his authorized representative, and it shall be the contractor's responsibility to serve ample notice of such tests.
- e. All laboratory tests shall be paid by the owner unless provided otherwise in the contract documents except the general contractor shall pay for laboratory tests to establish design mix for concrete, and for additional tests to prove compliance with contract documents where materials have tested deficient except when the testing laboratory did not follow the appropriate ASTM testing procedures.
- f. Should any work be covered up or concealed prior to inspection and approval by the designer, special inspector, and/or State Construction Office such work shall be uncovered or exposed for inspection, if so requested by the designer in writing. Inspection of the work will be made upon notice from the contractor. All cost involved in uncovering, repairing, replacing, recovering and restoring to design condition, the work that has been covered or concealed will be paid by the contractor involved.

ARTICLE 14 - CONSTRUCTION SUPERVISION AND SCHEDULE

- a. Throughout the progress of the work, each contractor shall keep at the job site, a competent superintendent and supervisory staff satisfactory to the designer and the owner. The superintendent and supervisory staff shall not be changed without the consent of the designer and owner unless said superintendent ceases to be employed by the contractor or ceases to be competent as determined by the contractor, designer or owner. The superintendent and other staff designated by the contractor in writing shall have authority to act on behalf of the contractor, and instructions, directions or notices given to him shall be as binding as if given to the contractor. However, directions, instructions, and notices shall be confirmed in writing.
- b. The contractor shall examine and study the drawings and specifications and fully understand the project design, and shall provide constant and efficient supervision to the work. Should he discover any discrepancies of any sort in the drawings or specifications, he shall report them to the designer without delay. He will not be held responsible for discrepancies in the drawings and/or specifications, but shall be held responsible to report them should they become known to him.
- c. All contractors shall be required to cooperate and consult with each other during the construction of this project. Prior to installation of work, all contractors shall jointly prepare coordination drawings, showing locations of various ductworks, piping, motors, pumps, and other mechanical or electrical equipment, in relation to the structure, walls and ceilings. These drawings shall be submitted to the designer through the Project Expediter for information only. Each contractor shall lay out and execute his work to cause the least delay to other contractors. Each contractor shall be financially responsible for any damage to other contractor's work and for undue delay caused to other contractors on the project.
- d. The contractor is required to attend job site progress conferences as called by the designer. The contractor shall be represented at these job progress conferences by both home office and project personnel. These representatives shall have authority to act on behalf of the contractor. These meetings shall be open to subcontractors, material

suppliers and any others who can contribute toward maintaining required job progress. It shall be the principal purpose of these meetings, or conferences, to effect coordination, cooperation and assistance in every practical way toward the end of maintaining progress of the project on schedule and to complete the project within the specified contract time. Each contractor shall be prepared to assess progress of the work as required in his particular contract and to recommend remedial measures for correction of progress as may be appropriate. The designer or his authorized representative shall be the coordinator of the conferences and shall preside as chairman. The contractor shall turn over a copy of his daily reports to the Designer and Owner at the job site progress conference. Owner will determine daily report format.

- e The contractor(s) shall, employ an engineer or a land surveyor licensed in the State of North Carolina to lay out the work and to establish a bench mark in a location where same will not be disturbed and where direct instruments sights may be taken.
- f. The designer shall designate a Project Expediter on projects involving two or more prime contracts. The Project Expediter shall be designated in the Supplementary General Conditions. The Project Expediter shall have at a minimum the following responsibilities.
 - 1. Prepare the project construction schedule and shall allow all prime contractors (multi-prime contract) and subcontractors (single-prime contract) performing general, plumbing, HVAC, and electrical work equal input into the preparation of the initial construction schedule.
 - 2. Maintain a project progress schedule for all contractors.
 - 3. Give adequate notice to all contractors to ensure efficient continuity of all phases of the work.
 - 4. Notify the designer of any changes in the project schedule.
 - 5. Recommend to the owner whether payment to a contractor shall be approved.
- g. It shall be the responsibility of the Project Expediter to cooperate with and obtain from several prime contractors and subcontractors on the job, their respective work activities and integrate these activities into a project construction schedule in form of a detailed bar chart or Critical Path Method (CPM), schedule. Each prime contractor shall provide work activities within fourteen (14) days of request by the Project Expediter. A “work activity”, for scheduling purposes, shall be any component or contractual requirement of the project requiring at least one (1) day, but not more than fourteen (14) days, to complete or fulfill. The project construction schedule shall graphically show all salient features of the work required to construct the project from start to finish and within the allotted time established in the contract. The time (in days) between the contractor’s early completion and contractual completion dates is part of the project total float time; and shall be used as such, unless amended by a change order. On a multi-prime project, each prime contractor shall review the proposed construction schedule and approve same in writing. The Project Expediter shall submit the proposed construction schedule to the designer for comments. The complete Project construction schedule shall be of the type set forth in the Supplementary General Condition or subparagraph (1) or (2) below, as appropriate:

1. For a project with total contracts of \$500,000 or less, a bar chart schedule will satisfy the above requirement. The schedule shall indicate the estimated starting and completion dates for each major element of the work.
2. For a project with total contracts over \$500,000, a Critical Path Method (CPM) schedule shall be utilized to control the planning and scheduling of the Work. The CPM schedule shall be the responsibility of the Project Expediter and shall be paid for by the Project Expediter.

Bar Chart Schedule: Where a bar chart schedule is required, it shall be time-scaled in weekly increments, shall indicate the estimated starting and completion dates for each major element of the work by trade and by area, level, or zone, and shall schedule dates for all salient features, including but not limited to the placing of orders for materials, submission of shop drawings and other Submittals for approval, approval of shop drawings by designers, the manufacture and delivery of material, the testing and the installation of materials, supplies and equipment, and all Work activities to be performed by the Contractor. The Contractor shall allow sufficient time in his schedule for all commissioning, required inspections and completion of final punchlist(s). Each Work activity will be assigned a time estimate by the Contractor. One day shall be the smallest time unit used.

CPM Schedule: Where a CPM schedule is required, it shall be in time-scaled precedence format using the Project Expediter's logic and time estimates. The CPM schedule shall be drawn or plotted with activities grouped or zoned by Work area or subcontract as opposed to a random (or scattered) format. The CPM schedule shall be time-scaled on a weekly basis and shall be drawn or plotted at a level of detail and logic which will schedule all salient features of the work to be performed by the Contractor. The Contractor shall allow sufficient time in his schedule for all commissioning, required inspections and completion of final punchlist(s).. Each Work activity will be assigned a time estimate by the Contractor. One day shall be the smallest time unit used.

The CPM schedule will identify and describe each activity, state the duration of each activity, the calendar dates for the early and late start and the early and late finish of each activity, and clearly highlight all activities on the critical path. "Total float" and "free float" shall be indicated for all activities. Float time shall not be considered for the exclusive use or benefit of either the Owner or the Contractor, but must be allocated in the best interest of completing the Work within the Contract time. Extensions to the Contract time, when granted by Change Order, will be granted only when equitable time adjustment exceeds the Total Float in the activity or path of activities affected by the change. On contracts with a price over \$2,500,000, the CPM schedule shall also show what part of the Contract Price is attributable to each activity on the schedule, the sum of which for all activities shall equal the total Contract Price.

Early Completion of Project: The Contractor may attempt to complete the project prior to the Contract Completion Date. However, such planned early completion shall be for the Contractor's convenience only and shall not create any additional rights of the Contractor or obligations of the Owner under this Contract, nor shall it change the Time

for Completion or the Contract Completion Date. The Contractor shall not be required to pay liquidated damages to the Owner because of its failure to complete by its planned earlier date. Likewise, the Owner shall not pay the Contractor any additional compensation for early completion nor will the Owner owe the Contractor any compensation should the Owner, its officers, employees, or agents cause the Contractor not to complete earlier than the date required by the Contract Documents.

- h. The proposed project construction schedule shall be presented to the designer no later than fifteen (15) days after written notice to proceed. No application for payment will be processed until this schedule is accepted by the designer and owner.
- i. The approved project construction schedule shall be distributed to all contractors and displayed at the job site by the Project Expediter.
- j. The several contractors shall be responsible for their work activities and shall notify the Project Expediter of any necessary changes or adjustments to their work. The Project Expediter shall maintain the project construction schedule, making biweekly adjustments, updates, corrections, etc., that are necessary to finish the project within the Contract time, keeping all contractors and the designer fully informed. Copy of a bar chart schedule annotated to show the current progress shall be submitted by the Contractor(s) to the designer, along with monthly request for payment. For project requiring CPM schedule, the Contractor shall submit a biweekly report of the status of all activities. The bar chart schedule or status report shall show the actual Work completed to date in comparison with the original Work scheduled for all activities. If any activities of the work of several contractors are behind schedule, the contractor must indicate in writing, what measures will be taken to bring each such activity back on schedule and to ensure that the Contract Completion Date is not exceeded. A plan of action and recovery schedule shall be developed and submitted to the designer by the Project Expediter, when (1) the contractor's report indicates delays, that are in the opinion of the designer or the owner, of sufficient magnitude that the contractor's ability to complete the work by the scheduled completion is brought into question; (2) the updated construction schedule is thirty (30) days behind the planned or baseline schedule and no legitimate time extensions, as determined by the Designer, are in process; and (3) the contractor desires to make changes in the logic (sequencing of work) or the planned duration of future activities of the CPM schedule which, in the opinion of the designer or the owner, are of a major nature. The plan of action, when required shall be submitted to the Owner for review within two (2) business days of the Contractor receiving the Owner's written demand. The recovery schedule, when required, shall be submitted to the Owner within five (5) calendar days of the Contractor's receiving the Owner's written demand. Failure to provide an updated construction schedule or a recovery schedule may be grounds for rejection of payment applications or withholding of funds as set forth in Article 33.
- k. The Project Expediter shall notify each contractor of such events or time frames that are critical to the progress of the job. Such notice shall be timely and reasonable. Should the progress be delayed due to the work of any of the several contractors, it shall be the duty of the Project Expediter to immediately notify the contractor(s) responsible for such delay, the designer, the State Construction Office and other prime contractors. The designer shall determine the contractor(s) who caused the delays and notify the bonding company of the responsible contractor(s) of the delays; and shall make a recommendation to the owner regarding further action.
- l. Designation as Project Expediter entails an additional project control responsibility and does not alter in any way the responsibility of the contractor so designated, nor the

responsibility of the other contractors involved in the project. The project expeditor's Superintendent(s) shall be in attendance at the Project site at all times when work is in progress unless conditions are beyond the control of the Contractor or until termination of the Contract in accordance with the Contract Documents. It is understood that such Superintendent shall be acceptable to the Owner and Designer and shall be the one who will be continued in that capacity for the duration of the project unless he ceases to be on the Contractor's payroll or the Owner otherwise agrees. The Superintendent shall not be employed on any other project for or by the Contractor or by any other entity during the course of the Work. If the Superintendent is employed by the Contractor on another project without the Owner's approval, then the Owner may deduct from the Contractor's monthly general condition costs and amount representing the Superintendent's cost and shall deduct that amount for each month thereafter until the Contractor has the Superintendent back on the Owner's Project full-time.

ARTICLE 15 - SEPARATE CONTRACTS AND CONTRACTOR RELATIONSHIPS

- a. Effective from January 1, 2002, Chapter 143, Article 8, was amended, to allow public contracts to be delivered by the following delivery methods: single-prime, dual (single-prime and separate-prime), construction manager at risk, and alternative contracting method as approved by the State Building Commission. The owner reserves the right to prepare separate specifications, receive separate bids, and award separate contracts for such other major items of work as may be in the best interest of the State. For the purposes of a single prime contract, refer to Article 1 – Definitions.
- b. All contractors shall cooperate with each other in the execution of their work, and shall plan their work in such manner as to avoid conflicting schedules or delay of the work. See Article 14, Construction Supervision.
- c. If any part of contractor's work depends upon the work of another contractor, defects which may affect that work shall be reported to the designer in order that prompt inspection may be made and the defects corrected. Commencement of work by a contractor where such condition exists will constitute acceptance of the other contractor's work as being satisfactory in all respects to receive the work commenced, except as to defects which may later develop. The designer shall be the judge as to the quality of work and shall settle all disputes on the matter between contractors.
- d. Any mechanical or electrical work such as sleeves, inserts, chases, openings, penetrations, etc., which is located in the work of the general contractor shall be built in by the general contractor. The respective mechanical and electrical contractors shall set all sleeves, inserts and other devices that are to be incorporated into the structure in cooperation and under the supervision of the general contractor. The responsibility for the exact location of such items shall be that of the mechanical and/or electrical contractor.
- e. The designer and the owner shall have access to the work whenever it is in preparation and progress and during normal working hours. The contractor shall provide facilities for such access so the designer may perform his functions under the contract documents.
- f. Should a contractor cause damage to the work or property of another contractor, he shall be directly responsible, and upon notice, shall promptly settle the claim or otherwise resolve the dispute.

ARTICLE 16 - SUBCONTRACTS AND SUBCONTRACTORS

- a. Within thirty (30) days after award of the contract, the contractor shall submit to the designer, owner and to the State Construction Office a list giving the names and addresses of subcontractors and equipment and material suppliers he proposes to use, together with the scope of their respective parts of the work. Should any subcontractor be disapproved by the designer or owner, the designer or owner shall submit his reasons for disapproval in writing to the State Construction Office for its consideration with a copy to the contractor. If the State Construction Office concurs with the designer's or owner's recommendation, the contractor shall submit a substitute for approval. The designer and owner shall act promptly in the approval of subcontractors, and when approval of the list is given, no changes of subcontractors will be permitted except for cause or reason considered justifiable by the designer or owner.
- b. The designer will furnish to any subcontractor, upon request, evidence regarding amounts of money paid to the contractor on account of the subcontractor's work.
- c. The contractor is and remains fully responsible for his own acts or omissions as well as those of any subcontractor or of any employee of either. The contractor agrees that no contractual relationship exists between the subcontractor and the owner in regard to the contract, and that the subcontractor acts on this work as an agent or employee of the contractor.
- d. The owner reserves the right to limit the amount of portions of work to be subcontracted as hereinafter specified.

ARTICLE 17 - CONTRACTOR AND SUBCONTRACTOR RELATIONSHIPS

The contractor agrees that the terms of these contract documents shall apply equally to each subcontractor as to the contractor, and the contractor agrees to take such action as may be necessary to bind each subcontractor to these terms. The contractor further agrees to conform to the Code of Ethical Conduct as adopted by the Associated General Contractors of America, Inc., with respect to contractor-subcontractor relationships, and that payments to subcontractors shall be made in accordance with the provisions of G.S. 143-134.1 titled Interest on final payments due to prime contractors: payments to subcontractors.

- a. On all public construction contracts which are let by a board or governing body of the state government or any political subdivision thereof, except contracts let by the Department of Transportation pursuant to G.S. 136-28.1, the balance due prime contractors shall be paid in full within 45 days after respective prime contracts of the project have been accepted by the owner, certified by the architect, engineer or designer to be completed in accordance with terms of the plans and specifications, or occupied by the owner and used for the purpose for which the project was constructed, whichever occurs first. Provided, however, that whenever the architect or consulting engineer in charge of the project determines that delay in completion of the project in accordance with terms of the plans and specifications is the fault of the contractor, the project may be occupied and used for the purposes for which it was constructed without payment of any interest on amounts withheld past the 45 day limit. No payment shall be delayed because of the failure of another prime contractor on such project to complete his contract. Should final payment to any prime contractor beyond the date such contracts have been certified to be completed by the designer or architect, accepted by the owner, or occupied by the owner and used for the purposes for which the project was constructed, be delayed by more than 45 days, said prime contractor shall be paid interest, beginning on the 46th day, at the rate of one percent (1%) per month or fraction thereof unless a lower rate is

agreed upon on such unpaid balance as may be due. In addition to the above final payment provisions, periodic payments due a prime contractor during construction shall be paid in accordance with the payment provisions of the contract documents or said prime contractor shall be paid interest on any such unpaid amount at the rate stipulated above for delayed final payments. Such interest shall begin on the date the payment is due and continue until the date on which payment is made. Such due date may be established by the terms of the contract. Funds for payment of such interest on state-owned projects shall be obtained from the current budget of the owning department, institution or agency. Where a conditional acceptance of a contract exists, and where the owner is retaining a reasonable sum pending correction of such conditions, interest on such reasonable sum shall not apply.

- b. Within seven days of receipt by the prime contractor of each periodic or final payment, the prime contractor shall pay the subcontractor based on work completed or service provided under the subcontract. Should any periodic or final payment to the subcontractor be delayed by more than seven days after receipt of periodic or final payment by the prime contractor, the prime contractor shall pay the subcontractor interest, beginning on the eighth day, at the rate of one percent (1%) per month or fraction thereof on such unpaid balance as may be due.
- c. The percentage of retainage on payments made by the prime contractor to the subcontractor shall not exceed the percentage of retainage on payments made by the owner to the prime contractor. Any percentage of retainage on payments made by the prime contractor to the subcontractor that exceeds the percentage of retainage on payments made by the owner to the prime contractor shall be subject to interest to be paid by the prime contractor to the subcontractor at the rate of one percent (1%) per month or fraction thereof.
- d. Nothing in this section shall prevent the prime contractor at the time of application and certification to the owner from withholding application and certification to the owner for payment to the subcontractor for unsatisfactory job progress; defective construction not remedied; disputed work; third-party claims filed or reasonable evidence that claim will be filed; failure of subcontractor to make timely payments for labor, equipment and materials; damage to prime contractor or another subcontractor; reasonable evidence that subcontract cannot be completed for the unpaid balance of the subcontract sum; or a reasonable amount for retainage not to exceed the initial percentage retained by owner.

ARTICLE 18 - DESIGNER'S STATUS

- a. The designer shall provide general administration of the performance of construction contracts, including liaison and necessary inspection of the work to ensure compliance with plans and specifications. He is the agent of the owner only for the purpose of constructing this work and to the extent stipulated in the contract documents. He has authority to direct work to be performed, to stop work, to order work removed, or to order corrections of faulty work, where any such action by the designer may be necessary to assure successful completion of the work.
- b. The designer is the impartial interpreter of the contract documents, and, as such, he shall exercise his powers under the contract to enforce faithful performance by both the owner and the contractor, taking sides with neither.
- c. Should the designer cease to be employed on the work for any reason whatsoever, then the owner shall employ a competent replacement who shall assume the status of the former designer.

- d. The designer and his consultants will make inspections of the project. He will inspect the progress, the quality and the quantity of the work.
- e. The designer and the owner shall have access to the work whenever it is in preparation and progress during normal working hours. The contractor shall provide facilities for such access so the designer and owner may perform their functions under the contract documents.
- f. Based on the designer's inspections and evaluations of the project, the designer shall issue interpretations, directives and decisions as may be necessary to administer the project. His decisions relating to artistic effect and technical matters shall be final, provided such decisions are within the limitations of the contract.

ARTICLE 19 - CHANGES IN THE WORK

- a. The owner may have changes made in the work covered by the contract. These changes will not invalidate and will not relieve or release the contractor from any guarantee given by him pertinent to the contract provisions. These changes will not affect the validity of the guarantee bond and will not relieve the surety or sureties of said bond. All extra work shall be executed under conditions of the original contract.
- b. Except in an emergency endangering life or property, no change shall be made by the contractor except upon receipt of approved change order or written field order from the designer, countersigned by the owner and the state construction office authorizing such change. No claim for adjustments of the contract price shall be valid unless this procedure is followed.

A field order, transmitted by fax, electronically, or hand delivered, may be used where the change involved impacts the critical path of the work. A formal change order shall be issued as expeditiously as possible.

In the event of emergency endangering life or property, the contractor may be directed to proceed on a time and material basis whereupon the contractor shall proceed and keep accurately on such form as specified by the designer or owner, a correct account of costs together with all proper invoices, payrolls and supporting data. Upon completion of the work the change order will be prepared as outlined under either Method "c(1)" or Method "c(2)" or both.

- c. In determining the values of changes, either additive or deductive, contractors are restricted to the use of the following methods:
 - 1. Where the extra work involved is covered by unit prices quoted in the proposal, or subsequently agreed to by the Contractor, Designer, Owner and State Construction Office the value of the change shall be computed by application of unit prices based on quantities, estimated or actual as agreed of the items involved, except in such cases where a quantity exceeds the estimated quantity allowance in the contract by one hundred percent (100%) or more. In such cases, either party may elect to proceed under subparagraph c2 herein. If neither party elects to proceed under c2, then unit prices shall apply.
 - 2. The contracting parties shall negotiate and agree upon the equitable value of the change prior to issuance of the change order, and the change order shall stipulate the corresponding lump sum adjustment to the contract price.

- d. Under Paragraph "b" and Methods "c(2)" above, the allowances for overhead and profit combined shall be as follows: all contractors (the single contracting entity (prime), his subcontractors(1st tier subs), or their sub-subcontractors (2nd tier subs, 3rd tier subs, etc)) shall be allowed a maximum of 10% on work they each self-perform; the prime contractor shall be allowed a maximum of 5% on contracted work of his 1st tier sub; 1st tier, 2nd tier, 3rd tier, etc contractors shall be allowed a maximum of 2.5% on the contracted work of their subs. ; Under Method "c(1)", no additional allowances shall be made for overhead and profit. In the case of deductible change orders, under Method "c(2)" and Paragraph (b) above, the contractor shall include no less than five percent (5%) profit, but no allowances for overhead.
- e. The term "net cost" as used herein shall mean the difference between all proper cost additions and deductions. The "cost" as used herein shall be limited to the following:
1. The actual costs of materials and supplies incorporated or consumed as part of the work;
 2. The actual costs of labor expended on the project site; labor expended in coordination, change order negotiation, record document maintenance, shop drawing revision or other tasks necessary to the administration of the project are considered overhead whether they take place in an office or on the project site.
 3. The actual costs of labor burden, limited to the costs of social security (FICA) and Medicare/Medicaid taxes; unemployment insurance costs; health/dental/vision insurance premiums; paid employee leave for holidays, vacation, sick leave, and/or petty leave, not to exceed a total of 30 days per year; retirement contributions; worker's compensation insurance premiums; and the costs of general liability insurance when premiums are computed based on payroll amounts; the total of which shall not exceed thirty percent (30%) of the actual costs of labor;
 4. The actual costs of rental for tools, excluding hand tools; equipment; machinery; and temporary facilities required for the work;
 5. The actual costs of premiums for bonds, insurance, permit fees, and sales or use taxes related to the work.

Overtime and extra pay for holidays and weekends may be a cost item only to the extent approved by the owner.

- f. Should concealed conditions be encountered in the performance of the work below grade, or should concealed or unknown conditions in an existing structure be at variance with the conditions indicated by the contract documents, the contract sum and time for completion may be equitably adjusted by change order upon claim by either party made within thirty (30) days after the condition has been identified. The cost of such change shall be arrived at by one of the foregoing methods. All change orders shall be supported by a unit cost breakdown showing method of arriving at net cost as defined above.
- g. In all change orders, the procedure will be for the designer to request proposals for the change order work in writing. The contractor will provide such proposal and supporting data in suitable format. The designer shall verify correctness. Delay in the processing of the change order due to lack of proper submittal by the contractor of all required supporting data shall not constitute grounds for a time extension or basis of a claim. Within fourteen (14) days after receipt of the contractor's accepted proposal including all supporting documentation required by the designer, the designer shall prepare the change order and forward to the contractor for his signature or otherwise respond, in writing, to

the contractor's proposal. Within seven (7) days after receipt of the change order executed by the contractor, the designer shall, certify the change order by his signature, and forward the change order and all supporting data to the owner for the owner's signature. The owner shall execute the change order and forward to the State Construction Office for final approval, within seven (7) days of receipt. The State Construction Office shall act on the change order within seven (7) days. In case of emergency or extenuating circumstances, approval of changes may be obtained verbally by telephone or field orders approved by all parties, then shall be substantiated in writing as outlined under normal procedure.

- h. At the time of signing a change order, the contractor shall be required to certify as follows:

"I certify that my bonding company will be notified forthwith that my contract has been changed by the amount of this change order, and that a copy of the approved change order will be mailed upon receipt by me to my surety."

- i. A change order, when issued, shall be full compensation, or credit, for the work included, omitted or substituted. It shall show on its face the adjustment in time for completion of the project as a result of the change in the work.
- j. If, during the progress of the work, the owner requests a change order and the contractor's terms are unacceptable, the owner, with the approval of the State Construction Office, may require the contractor to perform such work on a time and material basis whereupon the contractor shall proceed and keep accurately on such form as specified by the Designer or owner, a correct account of cost together with all proper invoices, payrolls and supporting data. Upon completion of the work a change order will be prepared with allowances for overhead and profit per paragraph d. above and "net cost" and "cost" per paragraph e. above. Without prejudice, nothing in this paragraph shall preclude the owner from performing or to have performed that portion of the work requested in the change order.

ARTICLE 20 - CLAIMS FOR EXTRA COST

- a. Should the contractor consider that as a result of instructions given by the designer, he is entitled to extra cost above that stated in the contract, he shall give written notice thereof to the designer within seven (7) days without delay. The written notice shall clearly state that a claim for extra cost is being made and shall provide a detailed justification for the extra cost. The contractor shall not proceed with the work affected until further advised, except in emergency involving the safety of life or property, which condition is covered in Article 19(b) and Article 11(h). No claims for extra compensation shall be considered unless the claim is so made. The designer shall render a written decision within seven (7) days of receipt of claim.
- b. The contractor shall not act on instructions received by him from persons other than the designer, and any claims for extra compensation or extension of time on account of such instruction will not be honored. The designer shall not be responsible for misunderstandings claimed by the contractor of verbal instructions which have not been confirmed in writing, and in no case shall instructions be interpreted as permitting a departure from the contract documents unless such instruction is confirmed in writing and supported by a properly authorized change order.
- c. Should a claim for extra compensation that complies with the requirements of (a) above by the contractor and is denied by the designer or owner, and cannot be resolved by a

representative of the State Construction Office, the contractor may request a mediation in connection with GS 143-128(f1) in the dispute resolution rules adopted by the State Building Commission (1 N.C.A.C. 30H .0101 through .1001). If the contractor is unable to resolve its claim as a result of mediation, the contractor may pursue the claim in accordance with the provisions of G.S. 143-135.3, or G.S. 143-135.6 where Community Colleges are the owner, and the following:

1. A contractor who has not completed a contract with a board for construction or repair work and who has not received the amount he claims is due under the contract may submit a verified written claim to the director of the State Construction Office of the Department of Administration for the amount the contractor claims is due. The director may deny, allow or compromise the claim, in whole or in part. A claim under this subsection is not a contested case under Chapter 150B of the General Statutes.
2. (a) A contractor who has completed a contract with a board for construction or repair work and who has not received the amount he claims is due under the contract may submit a verified written claim to the director of the State Construction Office of the Department of Administration for the amount the contractor claims is due. The claim shall be submitted within sixty (60) days after the contractor receives a final statement of the board's disposition of his claim and shall state the factual basis for the claim.
 - (b) The director shall investigate a submitted claim within ninety (90) days of receiving the claim, or within any longer time period upon which the director and the contractor agree. The contractor may appear before the director, either in person or through counsel, to present facts and arguments in support of his claim. The director may allow, deny or compromise the claim, in whole or in part. The director shall give the contractor a written statement of the director's decision on the contractor's claim.
 - (c) A contractor who is dissatisfied with the director's decision on a claim submitted under this subsection may commence a contested case on the claim under Chapter 150B of the General Statutes. The contested case shall be commenced within sixty (60) days of receiving the director's written statement of the decision.
 - (d) As to any portion of a claim that is denied by the director, the contractor may, in lieu of the procedures set forth in the preceding subsection of this section, within six (6) months of receipt of the director's final decision, institute a civil action for the sum he claims to be entitled to under the contract by filing a verified complaint and the issuance of a summons in the Superior Court of Wake County or in the superior court of any county where the work under the contract was performed. The procedure shall be the same as in all civil actions except that all issues shall be tried by the judge, without a jury.

ARTICLE 21 - MINOR CHANGES IN THE WORK

The designer will have the authority to order minor changes in the work not involving an adjustment in the contract sum or time for completion, and not inconsistent with the intent of the contract documents. Such changes shall be effected by written order, copied to the State Construction Office, and shall be binding on the owner and the contractor.

ARTICLE 22 - UNCORRECTED FAULTY WORK

Should the correction of faulty or damaged work be considered inadvisable or inexpedient by the owner and the designer, the owner shall be reimbursed by the contractor. A change order will be issued to reflect a reduction in the contract sum.

ARTICLE 23 - TIME OF COMPLETION, DELAYS, EXTENSION OF TIME

- a. The time of completion is stated in the Supplementary General Conditions and in the Form of Construction Contract. The Project Expediter, upon notice of award of contract, shall prepare a construction schedule to complete the project within the time of completion as required by Article 14.
- b. The contractors shall commence work to be performed under this agreement on a date to be specified in a written Notice to Proceed from the designer and shall fully complete all work hereunder within the time of completion stated. Time is of the essence and the contractor acknowledges the Owner will likely suffer financial damage for failure to complete the work within the time of completion. For each day in excess of the above number of days, the contractor(s) shall pay the owner the sum stated as liquidated damages reasonably estimated in advance to cover the losses to be incurred by the owner by reason of failure of said contractor(s) to complete the work within the time specified, such time being in the essence of this contract and a material consideration thereof. Should the work be delayed by both the owner and contractor, liquidated damages shall be apportioned to reflect the delays of each party. In the case of concurrent delays, contractor caused delays shall be accounted for before owner and designer caused delays.
- c. In the event of multiple prime contractors, the designer shall be the judge as to the division of responsibility between the contractor(s), based on the construction schedule, weekly reports and job records, and shall apportion the amount of liquidated damages to be paid by each of them, according to delay caused by any or all of them.
- d. If the contractor is delayed at any time in the progress of his work solely by any act or negligence of the owner, the designer, or by any employee of either; by any separate contractor employed by the owner; by changes ordered in the work; by labor disputes at the project site; by abnormal weather conditions not reasonably anticipated for the locality where the work is performed; by unavoidable casualties; by any causes beyond the contractor's control; or by any other causes which the designer and owner determine may justify the delay, then the contract time may be extended by change order only for the time which the designer and owner may determine is reasonable.

Time extensions will not be granted for rain, wind, snow or other natural phenomena of normal intensity for the locality where work is performed. For purpose of determining extent of delay attributable to unusual weather phenomena, a determination shall be made by comparing the weather for the contract period involved with the average of the preceding five (5) year climatic range during the same time interval based on the National Oceanic and Atmospheric Administration National Weather Service statistics for the locality where work is performed and on daily weather logs kept on the job site by the contractor reflecting the effect of the weather on progress of the work and initialed by the designer's representative. No weather delays shall be considered after the building is dried in unless work claimed to be delayed is on the critical path of the baseline schedule or approved updated schedule. Time extensions for weather delays, acts of God, labor disputes, fire, delays in transportation, unavoidable casualties or other delays which are beyond the control of the Owner do not entitle the Contractor to compensable damages for delays. Any contractor claim for compensable damages for delays is limited to delays caused solely by the owner or its agents. Contractor caused delays shall be accounted for before owner or designer caused delays in the case of concurrent delays.

- e. Request for extension of time shall be made in writing to the designer, copies to the owner and SCO, within twenty (20) days following cause of delay. In case of continuing cause for delay, the Contractor shall notify the Designer to the designer, copies to the owner and SCO, of the delay within 20 days of the beginning of the delay and only one claim is necessary.
- f. The contractor shall notify his surety in writing of extension of time granted.
- g. No claim for time extension shall be allowed on account of failure of the designer to furnish drawings or instructions until twenty (20) days after demand for such drawings and/or instructions. See Article 5c. Demand must be in written form clearly stating the potential for delay unless the drawings or instructions are provided. Any delay granted will begin after the twenty (20) day demand period is concluded.

ARTICLE 24 - PARTIAL UTILIZATION/BENEFICIAL OCCUPANCY

- a. The owner may desire to occupy or utilize all or a portion of the project prior to the completion of the project.
- b. Should the owner request a utilization of a building or portion thereof, the designer shall perform a designer final inspection of area after being notified by the contractor that the area is ready for such. After the contractor has completed designer final inspection punch list and the designer has verified, then the designer shall schedule a beneficial occupancy inspection at a time and date acceptable to the owner, contractor(s) and State Construction Office. If beneficial occupancy is granted by the State Construction Office, in such areas the following will be established:
 - 1. The beginning of guarantees and warranties period for the equipment necessary to support. in the area.
 - 2. The owner assumes all responsibilities for utility costs for entire building.
 - 2. Contractor will obtain consent of surety.
 - 3. Contractor will obtain endorsement from insurance company permitting beneficial occupancy.
- c. The owner shall have the right to exclude the contractor from any part of the project which the designer has so certified to be substantially complete, but the owner will allow the contractor reasonable access to complete or correct work to bring it into compliance with the contract.
- d. Occupancy by the owner under this article will in no way relieve the contractor from his contractual requirement to complete the project within the specified time. The contractor will not be relieved of liquidated damages because of beneficial occupancy. The designer may prorate liquidated damages based on the percentage of project occupied.

ARTICLE 25 - FINAL INSPECTION, ACCEPTANCE, AND PROJECT CLOSEOUT

- a. Upon notification from the contractor(s) that the project is complete and ready for inspection, the designer shall make a Designer final inspection to verify that the project is complete and ready for SCO final inspection. Prior to SCO final inspection, the contractor(s) shall complete all items requiring corrective measures noted at the Designer

final inspection. The designer shall schedule a SCO final inspection at a time and date acceptable to the owner, contractor(s) and State Construction Office.

- b. At the SCO final inspection, the designer and his consultants shall, if job conditions warrant, record a list of items that are found to be incomplete or not in accordance with the contract documents. At the conclusion of the SCO final inspection, the designer and State Construction Office representative shall make one of the following determinations:
 - 1. That the project is completed and accepted.
 - 2. That the project will be accepted subject to the correction of the list of discrepancies (punch list). All punch list items must be completed within thirty (30) days of SCO final inspection or the owner may invoke Article 28, Owner's Right to Do Work.
 - 4. That the project is not complete and another date for a SCO final inspection will be established.
- c. Within fourteen (14) days of final acceptance per Paragraph b1 or within fourteen (14) days after completion of punch list per Paragraph b2 above, the designer shall certify the work and issue applicable certificate(s) of compliance.
- d. Any discrepancies listed or discovered after the date of SCO final inspection and acceptance under Paragraphs b1 or b2 above shall be handled in accordance with Article 42, Guarantee.
- f. The final acceptance date will establish the following:
 - 1. The beginning of guarantees and warranties period.
 - 2. The date on which the contractor's insurance coverage for public liability, property damage and builder's risk may be terminated.
 - 3. That no liquidated damages (if applicable) shall be assessed after this date.
 - 4. The termination date of utility cost to the contractor.
- g. **Prior to issuance of final acceptance date, the contractor shall have his authorized representatives visit the project and give full instructions to the designated personnel regarding operating, maintenance, care, and adjustment of all equipment and special construction elements. In addition, the contractor shall provide to the owner a complete instructional video (media format acceptable to the owner) on the operation, maintenance, care and adjustment of all equipment and special construction elements.**

ARTICLE 26 - CORRECTION OF WORK BEFORE FINAL PAYMENT

- a. Any work, materials, fabricated items or other parts of the work which have been condemned or declared not in accordance with the contract by the designer shall be promptly removed from the work site by the contractor, and shall be immediately replaced by new work in accordance with the contract at no additional cost to the owner. Work or property of other contractors or the owner, damaged or destroyed by virtue of such faulty work, shall be made good at the expense of the contractor whose work is faulty.

- b. Correction of condemned work described above shall commence within twenty-four (24) hours after receipt of notice from the designer, and shall make satisfactory progress, as determined by the designer, until completed.
- c. Should the contractor fail to proceed with the required corrections, then the owner may complete the work in accordance with the provisions of Article 28.

ARTICLE 27 - CORRECTION OF WORK AFTER FINAL PAYMENT

See Article 35, Performance Bond and Payment Bond, and Article 42, Guarantee. Neither the final certificate, final payment, occupancy of the premises by the owner, nor any provision of the contract, nor any other act or instrument of the owner, nor the designer, shall relieve the contractor from responsibility for negligence, or faulty material or workmanship, or failure to comply with the drawings and specifications. Contractor shall correct or make good any defects due thereto and repair any damage resulting there from, which may appear during the guarantee period following final acceptance of the work except as stated otherwise under Article 42, Guarantee. The owner will report any defects as they may appear to the contractor and establish a time limit for completion of corrections by the contractor. The owner will be the judge as to the responsibility for correction of defects.

ARTICLE 28 - OWNER'S RIGHT TO DO WORK

If, during the progress of the work or during the period of guarantee, the contractor fails to prosecute the work properly or to perform any provision of the contract, the owner, after seven (7) days' written notice sent by certified mail, return receipt requested, to the contractor from the designer, may perform or have performed that portion of the work. The cost of the work may be deducted from any amounts due or to become due to the contractor, such action and cost of same having been first approved by the designer. Should the cost of such action of the owner exceed the amount due or to become due the contractor, then the contractor or his surety, or both, shall be liable for and shall pay to the owner the amount of said excess.

ARTICLE 29 - ANNULMENT OF CONTRACT

If the contractor fails to begin the work under the contract within the time specified, or the progress of the work is not maintained on schedule, or the work is not completed within the time above specified, or fails to perform the work with sufficient workmen and equipment or with sufficient materials to ensure the prompt completion of said work, or shall perform the work unsuitably or shall discontinue the prosecution of the work, or if the contractor shall become insolvent or be declared bankrupt or commit any act of bankruptcy or insolvency, or allow any final judgment to stand against him unsatisfied for a period of forty-eight (48) hours, or shall make an assignment for the benefit of creditors, or for any other cause whatsoever shall not carry on the work in an acceptable manner, the owner may give notice in writing, sent by certified mail, return receipt requested, to the contractor and his surety of such delay, neglect or default, specifying the same, and if the contractor within a period of seven (7) days after such notice shall not proceed in accordance therewith, then the owner shall, declare this contract in default, and, thereupon, the surety shall promptly take over the work and complete the performance of this contract in the manner and within the time frame specified. In the event the surety shall fail to take over the work to be done under this contract within seven (7) days after being so notified and notify the owner in writing, sent by certified mail, return receipt requested, that he is taking the same over and stating that he will diligently pursue and complete the same, the owner shall have full power and authority, without violating the contract, to take the prosecution of the work out of the hands of said contractor, to appropriate or use any or all contract materials and equipment on the grounds as may be suitable and acceptable and may enter into an agreement, either by public letting or negotiation, for the completion of said contract according to the terms and provisions thereof

or use such other methods as in his opinion shall be required for the completion of said contract in an acceptable manner. All costs and charges incurred by the owner, together with the costs of completing the work under contract, shall be deducted from any monies due or which may become due said contractor and surety. In case the expense so incurred by the owner shall be less than the sum which would have been payable under the contract, if it had been completed by said contractor, then the said contractor and surety shall be entitled to receive the difference, but in case such expense shall exceed the sum which would have been payable under the contract, then the contractor and the surety shall be liable and shall pay to the owner the amount of said excess.

ARTICLE 30 - CONTRACTOR'S RIGHT TO STOP WORK OR TERMINATE THE CONTRACT

- a. Should the work be stopped by order of a court having jurisdiction, or by order of any other public authority for a period of three months, due to cause beyond the fault or control of the contractor, or if the owner should fail or refuse to make payment on account of a certificate issued by the designer within forty-five (45) days after receipt of same, then the contractor, after fifteen (15) days' written notice sent by certified mail, return receipt requested, to the owner and the designer, may suspend operations on the work or terminate the contract.
- b. The owner shall be liable to the contractor for the cost of all materials delivered and work performed on this contract plus 10 percent overhead and profit and shall make such payment. The designer shall be the judge as to the correctness of such payment.

ARTICLE 31 - REQUEST FOR PAYMENT

- a. Not later than the fifth day of the month, the contractor shall submit to the designer a request for payment for work done during the previous month. The request shall be in the form agreed upon between the contractor and the designer, but shall show substantially the value of work done and materials delivered to the site during the period since the last payment, and shall sum up the financial status of the contract with the following information:
 1. Total of contract including change orders.
 2. Value of work completed to date.
 3. Less five percent (5%) retainage, provided however, that after fifty percent (50%) of the contractor's work has been satisfactorily completed on schedule, with approval of the owner and the State Construction Office and written consent of the surety, further requirements for retainage will be waived only so long as work continues to be completed satisfactorily and on schedule.
 4. Less previous payments.
 5. Current amount due.
- b. The contractor, upon request of the designer, shall substantiate the request with invoices of vouchers or payrolls or other evidence.
- c. Prior to submitting the first request, the contractor shall prepare for the designer a schedule showing a breakdown of the contract price into values of the various parts of the work, so arranged as to facilitate payments to subcontractors in accordance with Article 17, Contractor and Subcontractor Relationships. The contractor(s) shall list the

value of each subcontractor and supplier, identifying each minority business subcontractor and supplier as listed in Affidavit C, if applicable.

- d. When payment is made on account of stored materials and equipment, such materials must be stored on the owner's property, and the requests for payments shall be accompanied by invoices or bills of sale or other evidence to establish the owner's title to such materials and equipment. Such payments will be made only for materials that have been customized or fabricated specifically for this project. Raw materials or commodity products including but not limited to piping, conduit, CMU, metal studs and gypsum board may not be submitted. Responsibility for such stored materials and equipment shall remain with the contractor regardless of ownership title. Such stored materials and equipment shall not be removed from the owner's property. Should the space for storage on-site be limited, the contractor, at his option, shall be permitted to store such materials and/or equipment in a suitable space off-site. Should the contractor desire to include any such materials or equipment in his application for payment, they must be stored in the name of the owner in an independent, licensed, bonded warehouse approved by the designer, owner and the State Construction Office and located as close to the site as possible. The warehouse selected must be approved by the contractor's bonding and insurance companies; the material to be paid for shall be assigned to the owner and shall be inspected by the designer. Upon approval by the designer, owner and SCO of the storage facilities and materials and equipment, payment therefore will be certified. Responsibility for such stored materials and equipment shall remain with the contractor. Such stored materials and equipment shall not be moved except for transportation to the project site. Under certain conditions, the designer may approve storage of materials at the point of manufacture, which conditions shall be approved by the designer, the owner and the State Construction Office prior to approval for the storage and shall include an agreement by the storing party which unconditionally gives the State absolute right to possession of the materials at anytime. Bond, security and insurance protection shall continue to be the responsibility of the contractor(s).
- e. In the event of beneficial occupancy, retainage of funds due the contractor(s) may be reduced with the approval of the State Construction Office to an equitable amount to cover the list of items to be completed or corrected. Retainage may not be reduced to less than two and one-half (2 1/2) times the estimated value of the work to be completed or corrected. Reduction of retainage must be with the consent and approval of the contractor's bonding company.

ARTICLE 32 - CERTIFICATES OF PAYMENT AND FINAL PAYMENT

- a. Within five (5) days from receipt of request for payment from the contractor, the designer shall issue and forward to the owner a certificate for payment. This certificate shall indicate the amount requested or as approved by the designer. If the certificate is not approved by the designer, he shall state in writing to the contractor and the owner his reasons for withholding payment.
- b. No certificate issued or payment made shall constitute an acceptance of the work or any part thereof. The making and acceptance of final payment shall constitute a waiver of all claims by the owner except:
 - 1. Claims arising from unsettled liens or claims against the contractor.
 - 2. Faulty work or materials appearing after final payment.
 - 3. Failure of the contractor to perform the work in accordance with drawings and specifications, such failure appearing after payment.

4. As conditioned in the performance bond and payment bond.
- c. The making and acceptance of final payment shall constitute a waiver of all claims by the contractor except those claims previously made and remaining unsettled (Article 20(c)).
- d. Prior to submitting request for final payment to the designer for approval, the contractor shall fully comply with all requirements specified in the “ project closeout” section of the specifications. These requirements include but not limited to the following:
 1. Submittal of Product and Operating Manuals, Warranties and Bonds, Guarantees, Maintenance Agreements, As-Built Drawings, Certificates of Inspection or Approval from agencies having jurisdiction. (The designer must approve the Manuals prior to delivery to the owner).
 2. Transfer of Required attic stock material and all keys in an organized manner.
 3. Record of Owner’s training.
 4. Resolution of any final inspection discrepancies.
 5. Granting access to Contractor’s records, if Owner’s internal auditors have made a request for such access pursuant to Article 52.
- e. The contractor shall forward to the designer, the final application for payment along with the following documents:
 1. List of minority business subcontractors and material suppliers showing breakdown of contract amounts and total actual payments to subs and material suppliers.
 2. Affidavit of Release of Liens.
 3. Affidavit of contractors of payment to material suppliers and subcontractors. (See Article 36).
 4. Consent of Surety to Final Payment.
 5. Certificates of state agencies required by state law.
- f. The designer will not authorize final payment until the work under contract has been certified by designer, certificates of compliance issued, and the contractor has complied with the closeout requirements. The designer shall forward the contractor’s final application for payment to the owner along with respective certificate(s) of compliance required by law.

ARTICLE 33 - PAYMENTS WITHHELD

- a. The designer with the approval of the State Construction Office may withhold payment for the following reasons:
 1. Faulty work not corrected.

2. The unpaid balance on the contract is insufficient to complete the work in the judgment of the designer.
 3. To provide for sufficient contract balance to cover liquidated damages that will be assessed.
- b. The secretary of the Department of Administration may authorize the withholding of payment for the following reasons:
 1. Claims filed against the contractor or evidence that a claim will be filed.
 2. Evidence that subcontractors have not been paid.
 - c. The Owner may withhold all or a portion of Contractor's general conditions costs set forth in the approved schedule of values, if Contractor has failed to comply with: (1) a request to access its records by Owner's internal auditors pursuant to Article 52; (2) a request for a plan of action and/or recovery schedule under Article 14.j or provide The Owner; (3) a request to provide an electronic copies of Contractor's baseline schedule, updates with all logic used to create the schedules in the original format of the scheduling software; and (4) Contractor's failure to have its Superintendent on the Project full-time; (
 - d. When grounds for withholding payments have been removed, payment will be released. Delay of payment due the contractor without cause will make owner liable for payment of interest to the contractor in accordance with G.S. 143-134.1. As provided in G.S.143-134.1(e) the owner shall not be liable for interest on payments withheld by the owner for unsatisfactory job progress, defective construction not remedied, disputed work, or third-party claims filed against the owner or reasonable evidence that a third-party claim will be filed.

ARTICLE 34 - MINIMUM INSURANCE REQUIREMENTS

The work under this contract shall not commence until the contractor has obtained all required insurance and verifying certificates of insurance have been approved in writing by the owner. These certificates shall document that coverages afforded under the policies will not be cancelled, reduced in amount or coverages eliminated until at least thirty (30) days after mailing written notice, by certified mail, return receipt requested, to the insured and the owner of such alteration or cancellation. If endorsements are needed to comply with the notification or other requirements of this article copies of the endorsements shall be submitted with the certificates.

a. Worker's Compensation and Employer's Liability

The contractor shall provide and maintain, until final acceptance, workmen's compensation insurance, as required by law, as well as employer's liability coverage with minimum limits of \$100,000.

b. Public Liability and Property Damage

The contractor shall provide and maintain, until final acceptance, comprehensive general liability insurance, including coverage for premises operations, independent contractors, completed operations, products and contractual exposures, as shall protect such contractors from claims arising out of any bodily injury, including accidental death, as well as from claims for property damages which may arise from operations under this contract, whether such operations be by the contractor or by any subcontractor, or by

anyone directly or indirectly employed by either of them and the minimum limits of such insurance shall be as follows:

Bodily Injury: \$500,000 per occurrence
Property Damage: \$100,000 per occurrence / \$300,000 aggregate

In lieu of limits listed above, a \$500,000 combined single limit shall satisfy both conditions.

Such coverage for completed operations must be maintained for at least two (2) years following final acceptance of the work performed under the contract.

c. Property Insurance (Builder's Risk/Installation Floater)

The contractor shall purchase and maintain property insurance until final acceptance, upon the entire work at the site to the full insurable value thereof. This insurance shall include the interests of the owner, the contractor, the subcontractors and sub-subcontractors in the work and shall insure against the perils of fire, wind, rain, flood, extended coverage, and vandalism and malicious mischief. If the owner is damaged by failure of the contractor to purchase or maintain such insurance, then the contractor shall bear all reasonable costs properly attributable thereto; the contractor shall effect and maintain similar property insurance on portions of the work stored off the site when request for payment per articles so includes such portions.

d. Deductible

Any deductible, if applicable to loss covered by insurance provided, is to be borne by the contractor.

e. Other Insurance

The contractor shall obtain such additional insurance as may be required by the owner or by the General Statutes of North Carolina including motor vehicle insurance, in amounts not less than the statutory limits.

f. Proof of Carriage

The contractor shall furnish the owner with satisfactory proof of carriage of the insurance required before written approval is granted by the owner.

ARTICLE 35 - PERFORMANCE BOND AND PAYMENT BOND

- a. Each contractor shall furnish a performance bond and payment bond executed by a surety company authorized to do business in North Carolina. The bonds shall be in the full contract amount. Bonds shall be executed in the form bound with these specifications.
- b. All bonds shall be countersigned by an authorized agent of the bonding company who is licensed to do business in North Carolina.

ARTICLE 36 - CONTRACTOR'S AFFIDAVIT

The final payment of retained amount due the contractor on account of the contract shall not become due until the contractor has furnished to the owner through the designer an affidavit signed, sworn and notarized to the effect that all payments for materials, services or subcontracted work in connection with his contract have been satisfied, and that no claims or

liens exist against the contractor in connection with this contract. In the event that the contractor cannot obtain similar affidavits from subcontractors to protect the contractor and the owner from possible liens or claims against the subcontractor, the contractor shall state in his affidavit that no claims or liens exist against any subcontractor to the best of his (the contractor's) knowledge, and if any appear afterward, the contractor shall save the owner harmless.

ARTICLE 37 - ASSIGNMENTS

The contractor shall not assign any portion of this contract nor subcontract in its entirety. Except as may be required under terms of the performance bond or payment bond, no funds or sums of money due or become due the contractor under the contract may be assigned.

ARTICLE 38 - USE OF PREMISES

- a. The contractor(s) shall confine his apparatus, the storage of materials and the operations of his workmen to limits indicated by law, ordinances, permits or directions of the designer and owner and shall not exceed those established limits in his operations.
- b. The contractor(s) shall not load or permit any part of the structure to be loaded with a weight that will endanger its safety.
- c. The contractor(s) shall enforce the designer's and owner's instructions regarding signs, advertisements, fires and smoking.
- d. No firearms, any type of alcoholic beverages, or drugs (other than those prescribed by a physician) will be permitted at the job site.

ARTICLE 39 - CUTTING, PATCHING AND DIGGING

- a. The contractor shall do all cutting, fitting or patching of his work that may be required to make its several parts come together properly and fit it to receive or be received by work of other contractors shown upon or reasonably implied by the drawings and specifications for the completed structure, as the designer may direct.
- b. Any cost brought about by defective or ill-timed work shall be borne by the party responsible therefor.
- c. No contractor shall endanger any work of another contractor by cutting, digging or other means. No contractor shall cut or alter the work of any other contractor without the consent of the designer and the affected contractor(s).

ARTICLE 40 - UTILITIES, STRUCTURES, SIGNS

- a. The contractor shall provide necessary and adequate facilities for water, electricity, gas, oil, sewer and other utility services which maybe necessary and required for completion of the project including all utilities required for testing, cleaning, balancing, and sterilization of designated plumbing, mechanical and electrical systems. Any permanent meters installed shall be listed in the contractor's name until work has a final acceptance. The contractor will be solely responsible for all utility costs prior to final acceptance. Contractor shall contact all affected utility companies prior to bid to determine their requirements to provide temporary and permanent service and include all costs associated with providing those services in their bid. Coordination of the work of the utility companies during construction is the sole responsibility of the contractor.

- b. Meters shall be relisted in the owner's name on the day following final acceptance of the Project Expediter's work, and the owner shall pay for services used after that date.
- c. The owner shall be reimbursed for all metered utility charges after the meter is relisted in the owner's name and prior to completion and acceptance of the work of **all** contractors. Reimbursement shall be made by the contractor whose work has not been completed and accepted. If the work of two or more contractors has not been completed and accepted, reimbursement to the owner shall be paid by the contractors involved on the basis of assessments by the designer.
- d. Prior to the operation of permanent systems, the Project Expediter will provide temporary power, lighting, water, and heat to maintain space temperature above freezing, as required for construction operations.
- e. All contractors shall have the permanent building systems in sufficient readiness for furnishing temporary climatic control at the time a building is enclosed and secured. The HVAC systems shall maintain climatic control throughout the enclosed portion of the building sufficient to allow completion of the interior finishes of the building. A building shall be considered enclosed and secured when windows, doorways (exterior, mechanical, and electrical equipment rooms), and hardware are installed; and other openings have protection which will provide reasonable climatic control. The appropriate time to start the mechanical systems and climatic condition shall be jointly determined by the contractor(s), the designer and owner. Use of the equipment in this manner shall be subject to the approval of the Designer and owner and shall in no way affect the warranty requirements of the contractor(s).
- f. The electrical contractor shall have the building's permanent power wiring distribution system in sufficient readiness to provide power as required by the HVAC contractor for temporary climatic control.
- g. The electrical contractor shall have the building's permanent lighting system ready at the time the general contractor begins interior painting and shall provide adequate lighting in those areas where interior painting and finishing is being performed.
- h. Each prime contractor shall be responsible for his permanently fixed service facilities and systems in use during progress of the work. The following procedures shall be strictly adhered to:
 - 1. Prior to final acceptance of work by the State Construction Office, each contractor shall remove and replace any parts of the permanent building systems damaged through use during construction.
 - 2. Temporary filters as recommended by the equipment manufacturer in order to keep the equipment and ductwork clean and free of dust and debris shall be installed in each of the heating and air conditioning units and at each return grille during construction. New filters shall be installed in each unit prior to the owner's acceptance of the work.
 - 3. Extra effort shall be maintained to keep the building and the site adjacent to the building clean and under no circumstances shall air systems be operated if finishing and site work operations are creating dust in excess of what would be considered normal if the building were occupied.
 - 4. It shall be understood that any warranty on equipment presented to the owner shall extend from the day of final acceptance by the owner. The cost of warranting the

equipment during operation in the finishing stages of construction shall be borne by the contractor whose system is utilized.

5. The electrical contractor shall have all lamps in proper working condition at the time of final project acceptance.
 - i. The Project Expediter shall provide, if required and where directed, a shed for toilet facilities and shall furnish and install in this shed all water closets required for a complete and adequate sanitary arrangement. These facilities will be available to other contractors on the job and shall be kept in a neat and sanitary condition at all times. Chemical toilets are acceptable.
 - j. The Project Expediter shall, if required by the Supplementary General Conditions and where directed, erect a temporary field office, complete with lights, telephone, heat and air conditioning. A portion of this office shall be partitioned off, of sufficient size, for the use of a resident inspector, should the designer so direct.
 - k. On multi-story construction projects, the Project Expediter shall provide temporary elevators, lifts, or other special equipment for the general use of all contractors. The cost for such elevators, lifts or other special equipment and the operation thereof shall be included in the Project Expediter's bid.
 - l. The Project Expediter will erect one sign on the project if required. The sign shall be of sound construction, and shall be neatly lettered with black letters on white background. The sign shall bear the name of the project, and the names of prime contractors on the project, and the name of the designer and consultants. Directional signs may be erected on the owner's property subject to approval of the owner with respect to size, style and location of such directional signs. Such signs may bear the name of the contractor and a directional symbol. No other signs will be permitted except by permission of the owner.

ARTICLE 41 - CLEANING UP

- a. The contractors shall keep the building and surrounding area reasonably free from rubbish at all times, and shall remove debris from the site on a timely basis or when directed to do so by the designer or Project Expediter. The Project Expediter shall provide an on site refuse container(s) for the use of all contractors. Each contractor shall remove their rubbish and debris from the building on a daily basis. The Project Expediter shall broom clean the building as required to minimize dust and dirt accumulation.
- b. The Project Expediter shall provide and maintain suitable all-weather access to the building.
- c. Before final inspection and acceptance of the building, each contractor shall clean his portion of the work, including glass, hardware, fixtures, masonry, tile and marble (using no acid), clean and wax all floors as specified, and completely prepare the building for use by the owner, with no cleaning required by the owner.

ARTICLE 42 - GUARANTEE

- a. The contractor shall unconditionally guarantee materials and workmanship against patent defects arising from faulty materials, faulty workmanship or negligence for a period of twelve (12) months following the date of final acceptance of the work or beneficial occupancy and shall replace such defective materials or workmanship without cost to the owner.

- b. Where items of equipment or material carry a manufacturer's warranty for any period in excess of twelve (12) months, then the manufacturer's warranty shall apply for that particular piece of equipment or material. The contractor shall replace such defective equipment or materials, without cost to the owner, within the manufacturer's warranty period.
- c. Additionally, the owner may bring an action for latent defects caused by the negligence of the contractor which is hidden or not readily apparent to the owner at the time of beneficial occupancy or final acceptance, whichever occurred first, in accordance with applicable law.
- d. Guarantees for roof, equipment, materials, and supplies shall be stipulated in the specifications sections governing such roof, equipment, materials, or supplies.

ARTICLE 43 - CODES AND STANDARDS

Wherever reference is given to codes, standard specifications or other data published by regulating agencies including, but not limited to, national electrical codes, North Carolina state building codes, federal specifications, ASTM specifications, various institute specifications, etc., it shall be understood that such reference is to the latest edition including addenda published prior to the date of the contract documents.

ARTICLE 44 - INDEMNIFICATION

To the fullest extent permitted by law, the contractor shall indemnify and hold harmless the owner, the designer and the agents, consultants and employees of the owner and designer, from and against all claims, damages, losses and expenses, including, but not limited to, attorneys' fees, arising out of or resulting from the performance or failure of performance of the work, provided that any such claim, damage, loss or expense (1) is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the work itself) including the loss of use resulting there from, and (2) is caused in whole or in part by any negligent act or omission of the contractor, the contractor's subcontractor, or the agents of either the contractor or the contractor's subcontractor. Such obligation shall not be construed to negate, abridge or otherwise reduce any other right or obligation of indemnity which would otherwise exist as to any party or person described in this article.

ARTICLE 45 - TAXES

- a. Federal excise taxes do not apply to materials entering into state work (Internal Revenue Code, Section 3442(3)).
- b. Federal transportation taxes do not apply to materials entering into state work (Internal Revenue Code, Section 3475(b) as amended).
- c. North Carolina sales tax and use tax, as required by law, do apply to materials entering into state work and such costs shall be included in the bid proposal and contract sum.
- d. Local option sales and use taxes, as required by law, do apply to materials entering into state work as applicable and such costs shall be included in the bid proposal and contract sum.
- e. **Accounting Procedures for Refund of County Sales & Use Tax**

Amount of county sales and use tax paid per contractor's statements:

Contractors performing contracts for state agencies shall give the state agency for whose project the property was purchased a signed statement containing the information listed in G.S. 105-164.14(e).

The Department of Revenue has agreed that in lieu of obtaining copies of sales receipts from contractors, an agency may obtain a certified statement as of April 1, 1991 from the contractor setting forth the date, the type of property and the cost of the property purchased from each vendor, the county in which the vendor made the sale and the amount of local sales and use taxes paid thereon. If the property was purchased out-of-state, the county in which the property was delivered should be listed. The contractor should also be notified that the certified statement may be subject to audit.

In the event the contractors make several purchases from the same vendor, such certified statement must indicate the invoice numbers, the inclusive dates of the invoices, the total amount of the invoices, the counties, and the county sales and use taxes paid thereon.

Name of taxing county: The position of a sale is the retailer's place of business located within a taxing county where the vendor becomes contractually obligated to make the sale. Therefore, it is important that the county tax be reported for the county of sale rather than the county of use.

When property is purchased from out-of-state vendors and the county tax is charged, the county should be identified where delivery is made when reporting the county tax.

Such statement must also include the cost of any tangible personal property withdrawn from the contractor's warehouse stock and the amount of county sales or use tax paid thereon by the contractor.

Similar certified statements by his subcontractors must be obtained by the general contractor and furnished to the claimant.

Contractors are not to include any tax paid on supplies, tools and equipment which they use to perform their contracts and should include only those building materials, supplies, fixtures and equipment which actually become a part of or annexed to the building or structure.

ARTICLE 46 - EQUAL OPPORTUNITY CLAUSE

The non-discrimination clause contained in Section 202 (Federal) Executive Order 11246, as amended by Executive Order 11375, relative to equal employment opportunity for all persons without regard to race, color, religion, sex or national origin, and the implementing rules and regulations prescribed by the secretary of Labor, are incorporated herein.

ARTICLE 47 - EMPLOYMENT OF INDIVIDUALS WITH DISABILITIES

The contractor(s) agree not to discriminate against any employee or applicant for employment because of physical or mental disabilities in regard to any position for which the employee or applicant is qualified. The contractor agrees to take affirmative action to employ, advance in employment and otherwise treat qualified individuals with such disabilities without discrimination based upon their physical or mental disability in all employment practices.

ARTICLE 48 - ASBESTOS-CONTAINING MATERIALS (ACM)

The State of North Carolina has attempted to address all asbestos-containing materials that are to be disturbed in the project. However, there may be other asbestos-containing materials in the work areas that are not to be disturbed and do not create an exposure hazard.

Contractors are reminded of the requirements of instructions under Instructions to Bidders and General Conditions of the Contract, titled Examination of Conditions. Statute 130A, Article 19, amended August 3, 1989, established the Asbestos Hazard Management Program that controls asbestos abatement in North Carolina. The latest edition of *Guideline Criteria for Asbestos Abatement* from the State Construction Office is to be incorporated in all asbestos abatement projects for the Capital Improvement Program.

ARTICLE 49 - MINORITY BUSINESS PARTICIPATION

GS 143-128.2 establishes a ten percent (10%) goal for participation by minority businesses in total value of work for each State building project. The document, *Guidelines for Recruitment and Selection of Minority Businesses for Participation in State Construction Contracts* including Affidavits and Appendix E are hereby incorporated into and made a part of this contract.

ARTICLE 50 – CONTRACTOR EVALUATION

The contractor's overall work performance on the project shall be fairly evaluated in accordance with the State Building Commission policy and procedures, for determining qualifications to bid on future State capital improvement projects. In addition to final evaluation, interim evaluation may be prepared during the progress of project. The document, *Contractor Evaluation Procedures*, is hereby incorporated and made a part of this contract. The owner may request the contractor's comments to evaluate the designer.

ARTICLE 51 – GIFTS

Pursuant to N.C. Gen. Stat. § 133-32, it is unlawful for any vendor or contractor (i.e. architect, bidder, contractor, construction manager, design professional, engineer, subcontractor, supplier, vendor, etc.), to make gifts or to give favors to any State employee. This prohibition covers those vendors and contractors who: (1) have a contract with a governmental agency; or (2) have performed under such a contract within the past year; or (3) anticipate bidding on such a contract in the future. For additional information regarding the specific requirements and exemptions, vendors and contractors are encouraged to review G.S. Sec. 133-32.

During the construction of the Project, the Contractor is prohibited from making gifts to any of the Owner's employees, Owner's project representatives (architect, engineers, construction manager and their employees), employees of the State Construction Office and/or any other State employee that may have any involvement, influence, responsibilities, oversight, management and/or duties that pertain to and/or relate to the contract administration, financial administration and/or disposition of claims arising from and/or relating to the Contract and/or Project.

ARTICLE 52 – AUDITING-ACCESS TO PERSONS AND RECORDS

In accordance with N.C. General Statute 147-64.7, the State Auditor shall have access to Contractor's officers, employees, agents and/or other persons in control of and/or responsible for the Contractor's records that relate to this Contracts for purposes of conducting audits under the referenced statute. The Owner's internal auditors shall also have the right to access and copy the Contractor's records relating to the Contract and Project during the term of the Contract and within two years following the completion of the Project/close-out of the Contract to verify accounts, accuracy, information, calculations and/or data affecting and/or

relating to Contractor's requests for payment, requests for change orders, change orders, claims for extra work, requests for time extensions and related claims for delay/extended general conditions costs, claims for lost productivity, claims for loss efficiency, claims for idle equipment or labor, claims for price/cost escalation, pass-through claims of subcontractors and/or suppliers, and/or any other type of claim for payment or damages from Owner and/or its project representatives.

ARTICLE 53 – NORTH CAROLINA FALSE CLAIMS ACT

The North Carolina False Claims Act ("NCFCA"), N.C. Gen. Stat. § 1-605 through 1-618, applies to this Contract. The Contractor should familiarize itself with the entire NCFCA and should seek the assistance of an attorney if it has any questions regarding the NCFCA and its applicability to any requests, demands and/or claims for payment its submits to the State through the contracting state agency, institution, university or community college.

The purpose of the NCFCA "is to deter persons from knowingly causing or assisting in causing the State to pay claims that are false or fraudulent and to provide remedies in the form of treble damages and civil penalties when money is obtained from the State by reason of a false or fraudulent claim." (Section 1-605(b).) A contractor's liability under the NCFCA may arise from, but is not limited to: requests for payment, invoices, billing, claims for extra work, requests for change orders, requests for time extensions, claims for delay damages/extended general conditions costs, claims for lost productivity, claims for loss efficiency, claims for idle equipment or labor, claims for price/cost escalation, pass-through claims of subcontractors and/or suppliers, documentation used to support any of the foregoing requests or claims, and/or any other request for payment from the State through the contracting state agency, institution, university or community college. The parts of the NCFCA that are most likely to be enforced with respect to this type of contract are as follows:

- A "claim" is "[a]ny request or demand, whether under a contract or otherwise, for money or property and whether or not the State has title to the money or property that (i) is presented to an officer, employee, or agent of the State or (ii) is made to a contractor ... if the money or property is to be spent or used on the State's behalf or to advance a State program or interest and if the State government: (a) provides or has provided any portion of the money or property that is requested or demanded; or (b) will reimburse such contractor ... for any portion of the money or property which is requested or demanded." (Section 1-606(2).)
- "Knowing" and "knowingly." – Whenever a person, with respect to information, does any of the following: (a) Has actual knowledge of the information; (b) Acts in deliberate ignorance of the truth or falsity of the information; and/or (c) Acts in reckless disregard of the truth or falsity of the information. (Section 1-606(4).) Proof of specific intent to defraud is not required. (Section 1-606(4).)
- "Material" means having a natural tendency to influence, or be capable of influencing, the payment or receipt of money or property. (Section 1-606(4).)
- Liability. – "Any person who commits any of the following acts shall be liable to the State for three times the amount of damages that the State sustains because of the act of that person[:] ... (1) Knowingly presents or causes to be presented a false or fraudulent claim for payment or approval. (2) Knowingly makes, uses, or causes to be made or used, a false record or statement material to a false or fraudulent claim. (3) Conspires to commit a violation of subdivision (1), (2) ..." (Section 1-607(a)(1), (2).)

- The NCFCA shall be interpreted and construed so as to be consistent with the federal False Claims Act, 31 U.S.C. § 3729, et seq., and any subsequent amendments to that act. (Section 1-616(c).)

Finally, the contracting state agency, institution, university or community college may refer any suspected violation of the NCFCA by the Contractor to the Attorney General's Office for investigation. Under Section 1-608(a), the Attorney General is responsible for investigating any violation of NCFCA, and may bring a civil action against the Contractor under the NCFCA. The Attorney General's investigation and any civil action relating thereto are independent and not subject to any dispute resolution provision set forth in this Contract. (See Section 1-608(a).)

ARTICLE 54 – TERMINATION FOR CONVENIENCE

Owner may at any time and for any reason terminate Contractor's services and work at Owner's convenience. Upon receipt of such notice, Contractor shall, unless the notice directs otherwise, immediately discontinue the work and placing of orders for materials, facilities and supplies in connection with the performance of this Agreement.

Upon such termination, Contractor shall be entitled to payment only as follows: (1) the actual cost of the work completed in conformity with this Agreement; plus, (2) such other costs actually incurred by Contractor as are permitted by the prime contract and approved by Owner; (3) plus ten percent (10%) of the cost of the work referred to in subparagraph (1) above for overhead and profit. There shall be deducted from such sums as provided in this subparagraph the amount of any payments made to Contractor prior to the date of the termination of this Agreement. Contractor shall not be entitled to any claim or claim of lien against Owner for any additional compensation or damages in the event of such termination and payment.

**SUPPLEMENTARY GENERAL CONDITIONS
(SGC's) OF THE CONTRACT**

**STANDARD FORM FOR CONSTRUCTION
CONTRACTS**

**NORTH CAROLINA STATE
UNIVERSITY**

NC State University Design and Construction Guidelines

Supplementary General Conditions

SUPPLEMENTARY GENERAL CONDITIONS (SGC's) OF THE CONTRACT

The use or reproduction of this document or any part thereof is authorized for and limited to use on projects of North Carolina State University, and is distributed by, through and at the discretion of the University for that distinct and sole purpose. This document supplements but does not alter in any way the requirements of the General Conditions of the Contract.

TABLE OF CONTENTS

1.0	SGC Article 1 – Definitions.....	3
2.0	SGC Article 14 – Construction Supervision and Schedule	3-4
3.0	SGC Article 23 - Time Of Completion, Delays, Extension of Time	4
4.0	SGC Article 40 – Utilities, Structures, Signs	5

1.0 SGC Article 1 – Definitions

- A. As defined in Article 1 of the General Conditions, the Supplementary General Conditions are considered part of the contract documents.
- B. The Owner is the State of North Carolina through North Carolina State University.
- C. Provide shall mean purchase, deliver, and install, new, clean, and completely operational, fully tested and ready for use.

2.0 SGC Article 14 – Construction Supervision and Schedule

- A. The contractor(s) shall employ an engineer or a land surveyor licensed in the State of North Carolina to lay out the work and to establish a benchmark nearby in a location where same will not be disturbed and where direct instruments sights may be taken.
- B. The designer shall designate a Project Expediter on projects involving two or more prime contracts. The Project Expediter shall be the General Contractor unless determined otherwise by the designer. The Project Expediter shall have the responsibilities described in Article 14.f. of the General Conditions.
- C. Project Construction Schedule. North Carolina State University requires a CPM schedule for all projects, regardless of size and/or dollar amount. Bar Chart schedules may be allowed on a case-by-case basis. All CPM schedules shall meet the requirements of the General Conditions as well as the following:
 - 1. The CPM Baseline Schedule or Updated Schedule shall consist of the computer files on electronic media necessary to recreate the schedule. Files shall consist of four discrete items:
 - a) The Activity description including the original and remaining durations, and percent complete. Show other computed information such as early and late computed start and finish times and various types of floats.
 - b) The logical predecessor and successor relationships that connect the various activities together to form a CPM network. All activities shall be linked with no

NC State University Design and Construction Guidelines

Supplementary General Conditions

constraints placed on any activity unless critical milestone dates are dictated in the contract.

- c) Constraints listing if any must exist.
 - d) All hidden codes or constraints assigned to activities by the Scheduler, which help define the intended workflow or project organization.
2. Each schedule submittal shall include a cover letter, a narrative, a hard copy of the schedule and the schedule files on electronic media. The schedule update narrative should state what activity changes happened on the project, including missing data, upcoming changes, documented delays, potential delays and other facts.
 3. Contractors and subcontractors shall include a minimum of five (5) full days in their base bid for their project superintendent and project manager to attend a preliminary scheduling meeting with the project expediter. Each contractor shall attend additional scheduling meetings as required until an acceptable construction schedule conforming to the contract time is completed and approved via signing of the printed schedule by the single or each prime contractor (project manager and superintendent). Copies of the signed schedule shall be given to the Designer, Owner and each signatory; the original shall be displayed at the jobsite. The submitted schedule shall show the contract project completion date.
 4. The schedule shall be updated monthly or at the Designer and/or Owner's request. The project expediter shall make all updates, adjustments, corrections, etc., with input provided from the other prime or subcontractors. It will be the responsibility of each prime and/or subcontractor to either agree or disagree with the updated schedule via signing and dating the schedule submitted by the project expediter or providing a written summary of schedule exceptions and/or inaccuracies.
 5. Project expediter is required to provide an updated construction schedule with each monthly payment application. It will be the responsibility of each prime and/or subcontractor to either agree or disagree with the updated schedule via signing and dating the schedule submitted by the project expediter or providing a written summary of schedule exceptions and/or inaccuracies. Payment requests received without one or the other of the above will be considered incomplete and will be returned as being incomplete. The only contractor required to submit a copy of the updated progress schedule with his monthly payment application is the project expediter.
 6. A completion or finish schedule is required at 80% project completion, illustrating tasks remaining to complete the project. The designer and Owner are required to approve finish schedule.
 7. Project expediter shall include all relevant testing and inspections on the CPM schedule, including but not limited to: telecom/data wiring tests and as-built drawings, fire alarm system testing, fire suppression system testing, piping pressure testing, all applicable NFPA, DOI, DOL tests and commissioning activities.
 8. The Contractor will schedule as Milestones in the CPM schedule and ensure they are met the following activities: MEPFP Coordination drawings, Casework and Fume Hood Submittals and shop drawings shall be submitted to the design team for review NO LATER than 30 days after the Notice To Proceed.

NC State University Design and Construction Guidelines

Supplementary General Conditions

3.0 SGC Article 23 - Time Of Completion, Delays, Extension of Time

A. For each day in excess of the number of days shown below, the contractor(s) shall pay the owner liquidated damages in the amount of \$_____ per consecutive calendar day. [Designer and Owner to jointly determine amount of LD's based on specific project requirements.]

This project does not include Commissioning

B. The time of completion for this project is _____ consecutive calendar days and begins on the date stated in the Designer's Notice to Proceed letter issued to the contractor.

This project includes Commissioning

B. The time of completion to SUBSTANTIAL COMPLETION for this project is _____ consecutive calendar days and begins on the date stated in the Designer's Notice to Proceed letter issued to the contractor. SUBSTANTIAL COMPLETION for this project is defined as the General Contractor and its subcontractors having completed the following:

1. GC's Pre-Final Punch List
2. Testing Adjusting and Balancing (TAB) is complete per the project specifications.
3. Pre-Functional Testing shall be complete and the completed report shall be issued to the design team prior to SUBSTANTIAL COMPLETION.

For a period not to exceed _____ weeks following immediately after SUBSTANTIAL COMPLETION, the Owner's agents will perform Enhanced Start UP of MEP systems and punch list generation and back punch activities. The contractor will be responsible for assisting in all testing and punch activities including the completion of all adjusting, balancing, repairing, correcting, replacing and completing unacceptable or otherwise incomplete work identified by the design team.

NC State University Design and Construction Guidelines

Supplementary General Conditions

4.0 SGC Article 40 – Utilities, Structures, Signs

- A. UTILITIES FOR NEW BUILDINGS - The Project Expediter will make arrangements with the appropriate utility service providers to provide temporary utilities to the site. The Project Expediter shall bear the costs of providing all temporary utilities to the site and all charges for temporary utilities during the project duration.
- B. UTILITIES FOR EXISTING BUILDINGS – The Project Expediter will make arrangements with either the appropriate utility service providers or with NCSU (if the existing building is already metered) to provide temporary utilities to the site. The University will bear the cost of all temporary utilities except the use of supplemental generators for power. The contractor may use what is available on site without affecting the ongoing operations of the Owner in any way, but may not request additional services that are not already present. Anything additional required by the contractor will be procured and paid for by the contractor

Electricity: \$ _____/KWH (kilo-watt hour)

Water: \$ _____/CCS (hundred cubic feet)

Steam: \$ _____/thousand pounds

Natural gas: \$ _____/deca-therm

GUIDELINES FOR RECRUITMENT AND SELECTION OF MINORITY BUSINESSES FOR PARTICIPATION IN STATE CONSTRUCTION CONTRACTS

In accordance with G.S. 143-128.2 (effective January 1, 2002) these guidelines establish goals for minority participation in single-prime bidding, separate-prime bidding, construction manager at risk, and alternative contracting methods, on State construction projects in the amount of \$300,000 or more. The legislation provides that the State shall have a verifiable ten percent (10%) goal for participation by minority businesses in the total value of work for each project for which a contract or contracts are awarded. These requirements are published to accomplish that end.

SECTION A: INTENT

It is the intent of these guidelines that the State of North Carolina, as awarding authority for construction projects, and the contractors and subcontractors performing the construction contracts awarded shall cooperate and in good faith do all things legal, proper and reasonable to achieve the statutory goal of ten percent (10%) for participation by minority businesses in each construction project as mandated by GS 143-128.2. Nothing in these guidelines shall be construed to require contractors or awarding authorities to award contracts or subcontracts to or to make purchases of materials or equipment from minority-business contractors or minority-business subcontractors who do not submit the lowest responsible, responsive bid or bids.

SECTION B: DEFINITIONS

1. Minority - a person who is a citizen or lawful permanent resident of the United States and who is:
 - a. Black, that is, a person having origins in any of the black racial groups in Africa;
 - b. Hispanic, that is, a person of Spanish or Portuguese culture with origins in Mexico, South or Central America, or the Caribbean Islands, regardless of race;
 - c. Asian American, that is, a person having origins in any of the original peoples of the Far East, Southeast Asia and Asia, the Indian subcontinent, the Pacific Islands;
 - d. American Indian, that is, a person having origins in any of the original peoples of North America; or
 - e. Female
2. Minority Business - means a business:
 - a. In which at least fifty-one percent (51%) is owned by one or more minority persons, or in the case of a corporation, in which at least fifty-one percent (51%) of the stock is owned by one or more minority persons or socially and economically disadvantaged individuals; and
 - b. Of which the management and daily business operations are controlled by one or more of the minority persons or socially and economically disadvantaged individuals who own it.
3. Socially and economically disadvantaged individual - means the same as defined in 15 U.S.C. 637. "Socially disadvantaged individuals are those who have been subjected to racial or ethnic prejudice or cultural bias because of their identity as a member of a group without regard to their individual qualities". "Economically disadvantaged individuals are those socially disadvantaged individuals whose ability to compete in the free enterprise system has been impaired due to diminished capital and credit opportunities as compared to others in the same business area who are not socially disadvantaged".
4. Public Entity - means State and all public subdivisions and local governmental units.
5. Owner - The State of North Carolina, through the Agency/Institution named in the contract.
6. Designer – Any person, firm, partnership, or corporation, which has contracted with the State of North Carolina to perform architectural or engineering, work.
7. Bidder - Any person, firm, partnership, corporation, association, or joint venture seeking to be awarded a public contract or subcontract.

8. Contract - A mutually binding legal relationship or any modification thereof obligating the seller to furnish equipment, materials or services, including construction, and obligating the buyer to pay for them.
9. Contractor - Any person, firm, partnership, corporation, association, or joint venture which has contracted with the State of North Carolina to perform construction work or repair.
10. Subcontractor - A firm under contract with the prime contractor or construction manager at risk for supplying materials or labor and materials and/or installation. The subcontractor may or may not provide materials in his subcontract.

SECTION C: RESPONSIBILITIES

1. Office for Historically Underutilized Businesses, Department of Administration (hereinafter referred to as HUB Office).

The HUB Office has established a program, which allows interested persons or businesses qualifying as a minority business under G.S. 143-128.2, to obtain certification in the State of North Carolina procurement system. The information provided by the minority businesses will be used by the HUB Office to:

- a. Identify those areas of work for which there are minority businesses, as requested.
- b. Make available to interested parties a list of prospective minority business contractors and subcontractors.
- c. Assist in the determination of technical assistance needed by minority business contractors.

In addition to being responsible for the certification/verification of minority businesses that want to participate in the State construction program, the HUB Office will:

- (1) Maintain a current list of minority businesses. The list shall include the areas of work in which each minority business is interested.
- (2) Inform minority businesses on how to identify and obtain contracting and subcontracting opportunities through the State Construction Office and other public entities.
- (3) Inform minority businesses of the contracting and subcontracting process for public construction building projects.
- (4) Work with the North Carolina trade and professional organizations to improve the ability of minority businesses to compete in the State construction projects.
- (5) The HUB Office also oversees the minority business program by:
 - a. Monitoring compliance with the program requirements.
 - b. Assisting in the implementation of training and technical assistance programs.
 - c. Identifying and implementing outreach efforts to increase the utilization of minority businesses.
 - d. Reporting the results of minority business utilization to the Secretary of the Department of Administration, the Governor, and the General Assembly.

2. State Construction Office

The State Construction Office will be responsible for the following:

- a. Furnish to the HUB Office a minimum of twenty-one days prior to the bid opening the following:
 - (1) Project description and location;
 - (2) Locations where bidding documents may be reviewed;
 - (3) Name of a representative of the owner who can be contacted during the advertising period to advise who the prospective bidders are;
 - (4) Date, time and location of the bid opening.
 - (5) Date, time and location of prebid conference, if scheduled.
- b. Attending scheduled prebid conference, if necessary, to clarify requirements of the general statutes regarding minority-business participation, including the bidders' responsibilities.

- c. Reviewing the apparent low bidders' statutory compliance with the requirements listed in the proposal, that must be complied with, if the bid is to be considered as responsive, prior to award of contracts. The State reserves the right to reject any or all bids and to waive informalities.
- d. Reviewing of minority business requirements at Preconstruction conference.
- e. Monitoring of contractors' compliance with minority business requirements in the contract documents during construction.
- f. Provide statistical data and required reports to the HUB Office.
- g. Resolve any protest and disputes arising after implementation of the plan, in conjunction with the HUB Office.

3. Owner

Before awarding a contract, owner shall do the following:

- a. Develop and implement a minority business participation outreach plan to identify minority businesses that can perform public building projects and to implement outreach efforts to encourage minority business participation in these projects to include education, recruitment, and interaction between minority businesses and non-minority businesses.
- b. Attend the scheduled prebid conference.
- c. At least 10 days prior to the scheduled day of bid opening, notify minority businesses that have requested notices from the public entity for public construction or repair work and minority businesses that otherwise indicated to the Office for Historically Underutilized Businesses an interest in the type of work being bid or the potential contracting opportunities listed in the proposal. The notification shall include the following:
 - 1. A description of the work for which the bid is being solicited.
 - 2. The date, time, and location where bids are to be submitted.
 - 3. The name of the individual within the owner's organization who will be available to answer questions about the project.
 - 4. Where bid documents may be reviewed.
 - 5. Any special requirements that may exist.
- d. Utilize other media, as appropriate, likely to inform potential minority businesses of the bid being sought.
- e. Maintain documentation of any contacts, correspondence, or conversation with minority business firms made in an attempt to meet the goals.
- f. Review, jointly with the designer, all requirements of G.S. 143-128.2(c) and G.S. 143-128.2(f) – (i.e. bidders' proposals for identification of the minority businesses that will be utilized with corresponding total dollar value of the bid and affidavit listing good faith efforts, or affidavit of self-performance of work, if the contractor will perform work under contract by its own workforce) - prior to recommendation of award to the State Construction Office.
- g. Evaluate documentation to determine good faith effort has been achieved for minority business utilization prior to recommendation of award to State Construction Office.
- h. Review prime contractors' pay applications for compliance with minority business utilization commitments prior to payment.
- i. Make documentation showing evidence of implementation of Owner's responsibilities available for review by State Construction Office and HUB Office, upon request

4. Designer

Under the single-prime bidding, separate prime bidding, construction manager at risk, or alternative contracting method, the designer will:

- a. Attend the scheduled prebid conference to explain minority business requirements to the prospective bidders.
- b. Assist the owner to identify and notify prospective minority business prime and subcontractors of potential contracting opportunities.
- c. Maintain documentation of any contacts, correspondence, or conversation with minority business firms made in an attempt to meet the goals.
- d. Review jointly with the owner, all requirements of G.S. 143-128.2(c) and G.S.143-128.2(f) – (i.e. bidders' proposals for identification of the minority businesses that will be utilized with

corresponding total dollar value of the bid and affidavit listing Good Faith Efforts, or affidavit of self-performance of work, if the contractor will perform work under contract by its own workforce) - prior to recommendation of award.

- e. During construction phase of the project, review “MBE Documentation for Contract Payment” – (Appendix E) for compliance with minority business utilization commitments. Submit Appendix E form with monthly pay applications to the owner and forward copies to the State Construction Office.
- f. Make documentation showing evidence of implementation of Designer’s responsibilities available for review by State Construction Office and HUB Office, upon request.

5. Prime Contractor(s), CM at Risk, and Its First-Tier Subcontractors

Under the single-prime bidding, the separate-prime bidding, construction manager at risk and alternative contracting methods, contractor(s) will:

- a. Attend the scheduled prebid conference.
- b. Identify or determine those work areas of a subcontract where minority businesses may have an interest in performing subcontract work.
- c. At least ten (10) days prior to the scheduled day of bid opening, notify minority businesses of potential subcontracting opportunities listed in the proposal. The notification will include the following:
 - (1) A description of the work for which the subbid is being solicited.
 - (2) The date, time and location where subbids are to be submitted.
 - (3) The name of the individual within the company who will be available to answer questions about the project.
 - (4) Where bid documents may be reviewed.
 - (5) Any special requirements that may exist, such as insurance, licenses, bonds and financial arrangements.

If there are more than three (3) minority businesses in the general locality of the project who offer similar contracting or subcontracting services in the specific trade, the contractor(s) shall notify three (3), but may contact more, if the contractor(s) so desires.

- d. During the bidding process, comply with the contractor(s) requirements listed in the proposal for minority participation.
- e. Identify on the bid, the minority businesses that will be utilized on the project with corresponding total dollar value of the bid and affidavit listing good faith efforts as required by G.S. 143-128.2(c) and G.S. 143-128.2(f).
- f. Make documentation showing evidence of implementation of PM, CM-at-Risk and First-Tier Subcontractor responsibilities available for review by State Construction Office and HUB Office, upon request.
- g. Upon being named the apparent low bidder, the Bidder shall provide one of the following: (1) an affidavit (Affidavit C) that includes a description of the portion of work to be executed by minority businesses, expressed as a percentage of the total contract price, which is equal to or more than the applicable goal; (2) if the percentage is not equal to the applicable goal, then documentation of all good faith efforts taken to meet the goal. Failure to comply with these requirements is grounds for rejection of the bid and award to the next lowest responsible and responsive bidder.
- h. The contractor(s) shall identify the name(s) of minority business subcontractor(s) and corresponding dollar amount of work on the schedule of values. The schedule of values shall be provided as required in Article 31 of the General Conditions of the Contract to facilitate payments to the subcontractors.
- i. The contractor(s) shall submit with each monthly pay request(s) and final payment(s), “MBE Documentation for Contract Payment” – (Appendix E), for designer’s review.
- j. During the construction of a project, at any time, if it becomes necessary to replace a minority business subcontractor, immediately advise the owner, State Construction Office, and the Director of the HUB Office in writing, of the circumstances involved. The prime contractor shall make a good faith effort to replace a minority business subcontractor with another minority business subcontractor.

- k. If during the construction of a project additional subcontracting opportunities become available, make a good faith effort to solicit subbids from minority businesses.
- l. It is the intent of these requirements apply to all contractors performing as prime contractor and first tier subcontractor under construction manager at risk on state projects.

6. Minority Business Responsibilities

While minority businesses are not required to become certified in order to participate in the State construction projects, it is recommended that they become certified and should take advantage of the appropriate technical assistance that is made available. In addition, minority businesses who are contacted by owners or bidders must respond promptly whether or not they wish to submit a bid.

SECTION 4: DISPUTE PROCEDURES

It is the policy of this state that disputes that involves a person's rights, duties or privileges, should be settled through informal procedures. To that end, minority business disputes arising under these guidelines should be resolved as governed under G.S. 143-128(g).

SECTION 5: These guidelines shall apply upon promulgation on state construction projects. Copies of these guidelines may be obtained from the Department of Administration, State Construction Office, (physical address) 301 North Wilmington Street, Suite 450, NC Education Building, Raleigh, North Carolina, 27601-2827, (mail address) 1307 Mail Service Center, Raleigh, North Carolina, 27699-1307, phone (919) 807-4100, Website: www.nc-sco.com

SECTION 6: In addition to these guidelines, there will be issued with each construction bid package provisions for contractual compliance providing minority business participation in the state construction program.

MINORITY BUSINESS CONTRACT PROVISIONS (CONSTRUCTION)

APPLICATION:

The **Guidelines for Recruitment and Selection of Minority Businesses for Participation in State Construction Contracts** are hereby made a part of these contract documents. These guidelines shall apply to all contractors regardless of ownership. Copies of these guidelines may be obtained from the Department of Administration, State Construction Office, (physical address) 301 North Wilmington Street, Suite 450, NC Education Building, Raleigh, North Carolina, 27601-2827, (mail address) 1307 Mail Service Center, Raleigh, North Carolina, 27699-1307, phone (919) 807-4100, Website: <http://www.nc-sco.com>

MINORITY BUSINESS SUBCONTRACT GOALS:

The goals for participation by minority firms as subcontractors on this project have been set at 10%.

The bidder must identify on its bid, the minority businesses that will be utilized on the project with corresponding total dollar value of the bid and affidavit (Affidavit A) listing good faith efforts **or** affidavit (Affidavit B) of self-performance of work, if the bidder will perform work under contract by its own workforce, as required by G.S. 143-128.2(c) and G.S. 143-128.2(f).

The lowest responsible, responsive bidder must provide Affidavit C, that includes a description of the portion of work to be executed by minority businesses, expressed as a percentage of the total contract price, which is equal to or more than the applicable goal.

OR

Provide Affidavit D, that includes a description of the portion of work to be executed by minority businesses, expressed as a percentage of the total contract price, **with documentation of Good Faith Effort, if the percentage is not equal to the applicable goal.**

OR

Provide Affidavit B, which includes sufficient information for the State to determine that the bidder does not customarily subcontract work on this type project.

The above information must be provided as required. Failure to submit these documents is grounds for rejection of the bid.

MINIMUM COMPLIANCE REQUIREMENTS:

All written statements, affidavits or intentions made by the Bidder shall become a part of the agreement between the Contractor and the State for performance of this contract. Failure to comply with any of these statements, affidavits or intentions, or with the minority business Guidelines shall constitute a breach of the contract. A finding by the State that any information submitted either prior to award of the contract or during the performance of the contract is inaccurate, false or incomplete, shall also constitute a breach of the contract. Any such breach may result in termination of the contract in accordance with the termination provisions contained in the contract. It shall be solely at the option of the State whether to terminate the contract for breach.

In determining whether a contractor has made Good Faith Efforts, the State will evaluate all efforts made by the Contractor and will determine compliance in regard to quantity, intensity, and results of these efforts. Good Faith Efforts include:

- (1) Contacting minority businesses that reasonably could have been expected to submit a quote and that were known to the contractor or available on State or local government maintained lists at least 10 days before the bid or proposal date and notifying them of the nature and scope of the work to be performed.
- (2) Making the construction plans, specifications and requirements available for review by prospective minority businesses, or providing these documents to them at least 10 days before the bid or proposals are due.
- (3) Breaking down or combining elements of work into economically feasible units to facilitate minority participation.
- (4) Working with minority trade, community, or contractor organizations identified by the Office for Historically Underutilized Businesses and included in the bid documents that provide assistance in recruitment of minority businesses.
- (5) Attending any prebid meetings scheduled by the public owner.
- (6) Providing assistance in getting required bonding or insurance or providing alternatives to bonding or insurance for subcontractors.
- (7) Negotiating in good faith with interested minority businesses and not rejecting them as unqualified without sound reasons based on their capabilities. Any rejection of a minority business based on lack of qualification should have the reasons documented in writing.
- (8) Providing assistance to an otherwise qualified minority business in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letters of credit, including waiving credit that is ordinarily required. Assisting minority businesses in obtaining the same unit pricing with the bidder's suppliers in order to help minority businesses in establishing credit.
- (9) Negotiating joint venture and partnership arrangements with minority businesses in order to increase opportunities for minority business participation on a public construction or repair project when possible.
- (10) Providing quick pay agreements and policies to enable minority contractors and suppliers to meet cash-flow demands.

APPENDIX E

MBE DOCUMENTATION FOR CONTRACT PAYMENTS

Prime Contractor/Architect: _____

Address & Phone: _____

Project Name: _____

Pay Application #: _____ Period: _____

The following is a list of payments made to Minority Business Enterprises on this project for the above-mentioned period.

MBE FIRM NAME	* INDICATE TYPE OF MBE	AMOUNT PAID THIS MONTH	TOTAL PAYMENTS TO DATE	TOTAL AMOUNT COMMITTED

*Minority categories: Black, African American (B), Hispanic (H), Asian American (A), American Indian (I), Female (F), Social and Economically Disadvantage (D)

Date: _____ Approved/Certified By: _____

Name

Title

Signature

SUBMIT WITH EACH PAY REQUEST & FINAL PAYMENT



REPORT OF GEOTECHNICAL ENGINEERING EVALUATION

PROPOSED APICULTURE FACILITY RALEIGH, NC

NORTH CAROLINA STATE UNIVERSITY

PROJECT NO.: 6468-23-0125
DATE: MARCH 04, 2024

WSP USA ENVIRONMENT & INFRASTRUCTURE INC.
4021 STIRRUP CREEK DRIVE, SUITE 100
DURHAM, NORTH CAROLINA 27703
NORTH CAROLINA ENGINEERING FIRM LICENSE NO. F-1253

WSP.COM



March 04, 2024

Ms. Melissa Diamond
Formal Design Project Manager
Design & Construction
Facilities Division
North Carolina State University
Raleigh, 27606
mrdiamond@ncsu.edu
919-513-0373

Subject: Report of Geotechnical Engineering Evaluation
Proposed Apiculture Facility
North Carolina State University
4329 Inwood Road
Raleigh, North Carolina
WSP Project No. 6468-23-0125

Dear Ms. Diamond,

WSP USA Environment & Infrastructure Inc. (WSP) is pleased to provide this Report of Geotechnical Engineering Evaluation for the proposed Apiculture Facility to be located at 4329 Inwood Road in Raleigh, North Carolina. Our services were provided in accordance with our Proposal No. PROP23CARO-242 dated October 6, 2023, and authorized by you.

The purpose of our evaluation was to assess the subsurface conditions encountered at the site in order to provide geotechnical engineering recommendations for the design and construction of the project. This report presents the results of our evaluation, site preparation guidelines, and geotechnical design recommendations and parameters for the planned development.

Thank you for the opportunity to provide our professional geotechnical services for this project. We would be pleased to discuss our recommendations with you and welcome the opportunity to continue to provide geotechnical consulting and construction materials testing services as this project progresses.

Sincerely,
WSP USA Environment & Infrastructure Inc.

F.A. KAYSER

Mohammad Kayser, Ph.D. P.E.
Senior Engineer
Registered, North Carolina 046209



Bon Lien, Ph.D., P.E.
Principal Engineer, Geotechnical
Registered, North Carolina 030132



TABLE OF CONTENTS

1	PROJECT AND SITE INFORMATION.....	1
1.1	INTRODUCTION	1
1.2	SITE DESCRIPTION AND PROPOSED CONSTRUCTION	1
2	FIELD EVALUATION	2
2.1	GENERAL.....	2
2.2	DRILLING METHODS	2
2.3	SOIL BORING LOGS	2
3	AREA GEOLOGY AND SUBSURFACE CONDITIONS	3
3.1	GEOLOGIC SETTING	3
3.2	GENERALIZED SUBSURFACE STRATIGRAPHY	3
3.2.1	TOPSOIL.....	3
3.2.2	RESIDUAL SOILS/ PARTIALLY WEATHERED ROCK (PWR)	4
3.2.3	DEPTH-TO-WATER.....	4
3.3	SEPTIC DRAIN FIELD PRELIMINARY SOILS INVESTIGATION.....	4
3.4	SEISMIC SITE CLASS	5
4	GEOTECHNICAL RECOMMENDATIONS	6
4.1	EARTHWORK.....	6
4.1.1	SITE PREPARATION	6
4.1.2	EXCAVATION.....	7
4.1.3	STRUCTURAL FILL MATERIALS AND RE-USE OF EXCAVATED MATERIALS.....	7
4.1.4	FILL PLACEMENT AND COMPACTION.....	7
4.1.5	SITE DRAINAGE.....	8
4.2	BUILDING FOUNDATIONS	8
4.3	GRADE SLABS.....	9



5 LIMITATIONS 10

ATTACHMENTS

APPENDICES

APPENDIX A: FIGURES

APPENDIX B: SOIL BORING LOGS

1 PROJECT AND SITE INFORMATION

1.1 INTRODUCTION

In accordance with our Proposal No. PROP23CARO-242 dated October 6, 2023, and authorized by North Carolina State University, we have performed a geotechnical evaluation for the proposed Apiculture Facility located at 4329 Inwood Road in Raleigh, North Carolina.

The purpose of our evaluation was to assess the subsurface conditions encountered at the site and provide geotechnical engineering recommendations for the design and construction of the project. This report presents the results of our evaluation, site preparation guidelines, and geotechnical design parameters and recommendations for the proposed development.

1.2 SITE DESCRIPTION AND PROPOSED CONSTRUCTION

Based on information provided to us, we understand that an apiculture facility has been proposed to be constructed at 4329 Inwood Road in Raleigh, North Carolina (see Figure 1 in Appendix A). It is our understanding only western portion of the about 15.7-acre site will be used for the proposed development. Based on our recent site visits, the proposed development area is currently an open area with some vegetations along the property boundary.

Based on the information provided to us, the new facility will be a one-story, 25-foot tall, steel structure with roof deck. There will not be any elevated slabs. Finished Floor Elevation of the building is proposed to be at 352.5 feet. Up to about 1 foot of cut and 2 feet of fill will be required to establish site grades for the proposed construction.

The building will have a footprint of about 4,900 square feet, with typical column spacing of 20 to 25 feet. The maximum column load and wall load are anticipated to be 60 kips and 1 kip/ft, respectively. A 1,500 square feet septic drain field is proposed at the southeast side of the site. A sanitary sewer line will connect the apiculture building to the septic drain field. Access driveway and several parking stalls near the proposed facility are also proposed.

2 FIELD EVALUATION

2.1 GENERAL

On February 2 and 5, 2024, WSP conducted a subsurface exploration at the project site to evaluate the existing subsurface conditions and to collect soil samples for classification. Our evaluation consisted of drilling and sampling six exploratory soil test borings (B-1 through B-6) in general accordance with ASTM D1586 using a track mounted drill rig with standard auger drilling equipment. Borings were drilled to termination depths of between approximately 20 and 42 feet below the existing ground surface. For the septic drain field, the design team requested to perform two borings to confirm the soils and suitability of a drain field location. Also, suitability of the soil in the area of potential septic drain field was requested to be evaluated.

Prior to drilling, the boring locations were staked using a handheld GPS device and N.C. One-Call was contacted to mark public utilities. Boring locations on Figure 1 should be considered approximate. The ground surface elevations shown on the attached soil test boring records were estimated based on the provided grading and Storm Drainage Plan (sheet C5.00), therefore, should be considered approximate.

2.2 DRILLING METHODS

Soil test borings were drilled by mechanically twisting hollow-stem augers into the soil. Soil sampling and Standard Penetration Testing (SPT) were performed in general accordance with ASTM D1586 using an automatic hammer system. At assigned intervals, soil samples were obtained with a standard 1.4-inch I.D., 2-inch O.D. split-spoon sampler. The sampler was first seated 6 inches to penetrate any loose cuttings, and then driven an additional 12 inches with blows from a 140-pound hammer falling 30 inches. The number of hammer blows required to drive the sampler the final 12 inches was recorded and is designated as the SPT "N-Value" or "standard penetration resistance". The N-Value, when properly evaluated, is an index to soil shear strength and foundation support capability.

Portions of split spoon samples were sealed in containers and returned to our laboratory where they were visually classified by a geotechnical engineer. Selected samples were assigned for subsequent index laboratory testing. The depth to water was measured in the boreholes at the time of drilling and prior to backfilling. The boreholes were then backfilled with soil cuttings.

2.3 SOIL BORING LOGS

The attached Soil Boring Logs represent our interpretation of the field drilling logs based on engineering examination of the field samples. Therefore, these boring logs contain both factual and interpretive information. Lines delineating subsurface strata on the boring logs are intended to group soils having similar engineering properties and characteristics. They should be considered approximate as the actual transition between soil types (strata) may be gradual. A Key to the Soil Symbols and Descriptions used on the boring logs is also included.

3 AREA GEOLOGY AND SUBSURFACE CONDITIONS

3.1 GEOLOGIC SETTING

The project site is located in the Piedmont Physiographic Province of North Carolina. The Piedmont Province region generally consists of hills and ridges that are intertwined with an established system of draws and streams. According to our review of the 1985 Geologic Map of North Carolina, published by the Department of Natural Resources and Community Development, the site is geologically located within the Raleigh belt with bedrock materials consisting of felsic mica gneiss. These materials were deposited during the Cambrian to Late Proterozoic Period. The bedrock materials have weathered in place to form the residual soils which are typically found near the ground surface of the site.

The virgin soils encountered in this area are the residual product of in-place weathering of rock, which was similar to the rock presently underlying the site. In areas not altered by erosion or disturbed by the activities of development, the typical residual soil profile consists of clayey soils near the surface, where soil weathering is more advanced, underlain by sandy silts and silty sands. The less weathered soils exhibit relict features of the parent rock, including foliation patterns and joints.

The boundary between soil and rock is not sharply defined. This transitional zone, termed "partially weathered rock" (PWR), is normally found overlying the parent bedrock. PWR is defined, for engineering purposes, as residual material with standard penetration resistance values in excess of 100 blows per foot. Fractures, joints, and the presence of less resistant rock types facilitate weathering. Consequently, the profile of the PWR and hard rock is quite irregular and erratic, even over short horizontal distances. Also, it is not unusual to find lenses and boulders of hard rock and zones of PWR within the soil mantle, well above the general bedrock level.

3.2 GENERALIZED SUBSURFACE STRATIGRAPHY

General subsurface conditions observed during our geotechnical evaluation are described in this section. For more detailed soil descriptions and stratifications at a particular boring location, the respective "Soil Boring Log", attached to this report should be reviewed. In addition, a generalized subsurface profile is included as Figure 2, attached to this report.

3.2.1 TOPSOIL

Approximately four inches of topsoil was noted at the surface of the borings. Topsoil is typically a dark-colored soil material containing roots, fibrous matter, and/or other organic components, and is generally unsuitable for engineering purposes. It should be noted that WSP has not performed any laboratory testing to determine the organic content or other horticultural properties of the observed surficial materials. Furthermore, the transition from topsoil to underlying material may be gradual, and therefore, the observation and measurement of these

thicknesses is somewhat subjective. Actual topsoil depths should be expected to vary across the project site and will generally increase as the amount of vegetation present over the site increases.

3.2.2 RESIDUAL SOILS/ PARTIALLY WEATHERED ROCK (PWR)

Residual soils were encountered at the borings below the surficial topsoil and extended to termination depths of the borings. When sampled, the residual soils generally consisted of soft to stiff highly plastic elastic silt (MH) and sandy clay (CH), low plasticity silt (ML) and sandy clay (CL), and very loose to medium dense silty sand (SM) and clayey sand (SC). Highly plastic soils (CH and MH) were encountered in the borings in the upper about 3 to 6 feet of the soil profile. SPT N-values for the sampled residuum generally ranged from 2 to 21 blows per feet (bpf). Near surface soft soils were encountered in boring B-1 from the ground surface to depth of about 3 feet. Soft or very loose soils were encountered deeper in the soil profile in borings B-2, B-4 and B-5 to depths ranging from about 8 to 27 feet, 8 to 17 feet and 12 to 17 feet, respectively.

PWR was encountered in boring B-2 at a depth of about 39.5 feet. Materials causing auger refusal was encountered in boring B-2 at a depth of about 42 feet.

3.2.3 DEPTH-TO-WATER

The boreholes were sounded for the presence and depth of groundwater at the time of boring and prior to backfilling the boreholes. Groundwater was encountered during drilling in borings B-2 and B-3 at depths of approximately 20 and 18 feet below the existing ground surface, respectively. After a stabilization period of approximately 24 hours, groundwater was encountered at these two borings at depths of about 18 and 17 feet, respectively. Groundwater was not encountered at the remaining borings.

The groundwater level at the project site is anticipated to fluctuate seasonally depending on the amount of rainfall, prevailing weather conditions, subsurface drainage characteristics, and the influence of nearby construction. Groundwater elevations will vary seasonally, with higher levels typically occurring during late winter and early spring or with the water levels of surrounding creeks. Additionally, the construction process itself can alter groundwater elevations.

Borehole cave in depths measured and shown on the boring logs in which groundwater was not encountered during our field exploration can sometimes be indicative of perched groundwater being present near these depths causing the boreholes to collapse at or near these depths.

3.3 SEPTIC DRAIN FIELD PRELIMINARY SOILS EXPLORATION

On February 6, 2024, Jan Gay a licensed soil scientist with WSP conducted a preliminary soils exploration within the project site. It is our understanding that an area suitable for an initial system and repair area be able to accommodate a daily design flow of 500 gallons per day is being sought for this site. Soil characteristics were evaluated using hand auger borings at the two provided Boring locations SS B-1 and SS B-2, within approximately 100 feet by 40 feet depicted area.

The area was evaluated for five criteria to determine suitability to support an on-site wastewater disposal system:

- Topography and landscape position
- Soil characteristics
- Soil wetness
- Soil depth, and
- Restrictive horizons

The landscape in the evaluated area consists of a relatively consistent linear side slope (5%) located within a maintained yard. Soils within the proposed initial system and repair area consist of clay loam material. Evidence of soil wetness was noted in the evaluated soil columns. At SS B-1 and a point approximately 40 feet Northwest of SS B-1, evidence of soil wetness was noted between 17 and 25 inches below the soil surface. At SS B-2 and a point approximately 40 feet Northeast of SS B-2, evidence of soil wetness was noted between 25 and 26 inches below ground surface.

Evidence of restrictive horizons was noted near the depths of soil wetness. The soils appear to be slightly expansive at the explored depth range of 17 to 26 inches below the ground surface. A long-term acceptance rate (LTAR) of 0.35 gallons/day/ft² (gpd) is likely appropriate for this area. Soil depth and available area are limiting factors for this site. With an available depth of 17 inches below ground surface, an at-grade sub-surface drip system may be appropriate for this site.

The available space set aside for the initial system and repair is approximately 4,000 square feet. This area may be enough to accommodate the subsurface drip system for initial system and repair area but is not large enough to accommodate any type of conventional subsurface disposal system.

As a courtesy, an additional boring was evaluated further up the slope, near boring B-5. Topography in this area was consistent (less than 5% grade changes). Soil encountered at this boring location was clay loam in texture. No evidence of soil wetness or restrictive horizons were noted within the depth of exploration 48 inches below the existing ground surface. An LTAR of 0.4 gpd is likely appropriate for this area.

The findings denoted represent the field conditions observed during the field review. Any disturbance in or near these areas subsequent to our review period may render these findings null and void.

3.4 SEISMIC SITE CLASS

The site seismic class was calculated based on correlation of the weighted average SPT N-value and soil shear wave velocity for the top 100 feet below the proposed lowest building finished floor elevation in accordance with the 2018 North Carolina Building Code. Based on the subsurface conditions encountered by our soil test borings and our understanding of the proposed construction, a Seismic Site Class D is determined based on the N-value methodology.

4 GEOTECHNICAL RECOMMENDATIONS

The following sections present our geotechnical recommendations, which are developed based on our understanding of the proposed construction, the observed subsurface conditions, and our experience. If the proposed construction is changed from that discussed herein or subsurface conditions other than those shown on the boring logs are observed at the time of construction, WSP should be retained to conduct a review of the new information and to evaluate the need for additional recommendations.

4.1 EARTHWORK

The following sections present our earthwork recommendations for this project. In general, local construction standards and specifications should be applied, unless otherwise noted.

4.1.1 SITE PREPARATION

Prior to placing any fill, pavement, or flatwork, the following guidelines should be followed:

- Existing vegetation should be stripped and removed from the site. Stripping and clearing should extend 10 feet beyond the planned construction limits.
- Obstructions that extend below finish grade, if any, should be removed and the resulting holes filled with structural fill that is placed and compacted as recommended in this report.
- Root balls from tree removal operations should be removed and the resulting voids be filled with compacted structural fill.
- After stripping, clearing, grubbing, and root raking is performed, the exposed subgrade should be visually observed and evaluated by proof-rolling prior to receiving fill or construction.
- Proof-rolling should be accomplished with a pneumatic-tired roller, a loaded dump truck, or similar equipment weighing approximately 20 tons. A geotechnical engineer or his/her representative should observe the proof-rolling operations and make recommendations should unstable or unsuitable conditions be encountered. Should proof-rolling operations indicate rutting, excessive pumping, yielding (with depressions greater than approximately $\frac{1}{2}$ " ; referring to ACI 302.1R-15, 6.1.1), the unstable subgrade should be repaired.
- Proof-rolling should be performed after a suitable period of dry weather to avoid degrading an otherwise acceptable subgrade. The proofroller should make at least four passes over each location, with the last two passes perpendicular to the first two. The exposed subgrade should be dry to avoid deterioration of the subgrade due to proof rolling operations.

- Highly plastic soils (CH and MH) were encountered in the borings performed at this site to depths ranging from about 3 to 6 feet. These soils are prone to shrink/swell and therefore can potentially create cracking or distress to the foundation or pavement due to excessive wetting or drying of the soils. The on-site excavated, highly plastic soils should not be used as structural fill at the project site.
- Near surface soft soils were encountered in one boring in the upper about 3 feet of the soil profile. These soils could be encountered at the other unexplored areas of the site. If these soils are encountered at foundation bearing grades or pavement subgrade during proof-rolling, they may need to be undercut and replaced with compacted structural fill approved by the project geotechnical engineer or his representative.

4.1.2 EXCAVATION

Based on the results of our soil test borings and anticipated excavation depths for construction of the building foundation and utilities, excavation could possibly be performed by using conventional excavating techniques. We anticipate that the residual soils can be excavated using pans, scrapers, backhoes or front-end loaders.

4.1.3 STRUCTURAL FILL MATERIALS AND RE-USE OF EXCAVATED MATERIALS

Unless otherwise recommended, compacted structural fill should have less than five percent organic content by weight and have a maximum particle size of three inches, and consist of materials classified as either SC, SM, SP, SW, GC, GM, GP, or GW per ASTM D2487, or on-site excavated soils classified as ML or CL with a plasticity index (PI) no greater than 25. Off-site borrow soils, if needed, should be classified as SC, SM, SP, SW, ML, GC, GM, GP, or GW in accordance with ASTM D2487. Soils classified as silty/lean clays (CL) with a PI-value greater than 25, elastic silts (MH), clays of high plasticity (CH), organic silts (OL), organic clays (OH), or highly organic clays/peat (PT) should not be used as backfill behind retaining walls.

Note that the on-site excavated ML or CL soils could be difficult to compact if they are too wet or too dry. As a result, the ability to use such soils will depend on their moisture contents and the prevailing weather conditions. Soils that are too wet to properly compact could be dried by aeration or mixed with an additive such as cement or lime to stabilize the soil and facilitate compaction.

4.1.4 FILL PLACEMENT AND COMPACTION

Before filling operations begin, representative samples of each proposed fill material should be collected and tested to determine the compaction and classification characteristics (i.e., moisture-density relationships). Structural fill soils should be placed in thin (not greater than 8 inches), loose lifts and compacted to 95 percent or better of the soil's Standard Proctor maximum dry density (ASTM D698) at near optimum moisture content ($\pm 3\%$). The upper 18 inches of structural fill within the parking and drive areas should be compacted to a minimum of 98 percent of the soil's Standard Proctor maximum dry density (ASTM D698) at near optimum moisture content.

Based on the soil samples obtained during our field exploration, some adjustment of the moisture content (such as wetting, drying) may be required during the filling operation to

obtain the required degree of compaction. The adjustment of the moisture content is highly dependent on weather conditions and site drainage conditions. Therefore, the grading contractor should be prepared to both dry and wet the fill materials to obtain the specified compaction during grading.

Once compaction begins, density tests should be performed by an experienced engineering technician working under the direct supervision of the Geotechnical Engineer-of-Record to measure the degree of compaction being obtained. We recommend performing one in-place density test per 2,500 square feet for each fill lift with a minimum of two tests per lift in small areas to confirm that the contractor's means and methods are suitable for achieving the specified compaction.

4.1.5 SITE DRAINAGE

Adequate drainage should be provided to reduce seasonal variations in the moisture content of foundation soils. Pavement, sidewalks, and finished grades within 5 feet of the planned structure should be sloped away, at a slope of 2 percent or more, from the structure to reduce the potential for water ponding near foundation elements. The long-term performance of the foundation system depends, in part, on maintaining positive surface drainage throughout the life of the structure.

4.2 BUILDING FOUNDATIONS

In general, shallow foundations such as spread, strip, or combination footings may be used to support the planned building. Following approval of foundation bearing surfaces by the engineering technician, as discussed below, spread foundations bearing on residual soil as encountered during our subsurface exploration, or newly placed and compacted structural fill may be designed with a net allowable maximum bearing pressure of 2,000 psf.

This recommended allowable bearing pressure is based on correlations between the standard penetration test resistances and soil shear strengths. A coefficient of 0.35 should be used for evaluating ultimate frictional resistance to sliding at the foundation-soil contact.

For the maximum design column load of 60 kips, a total foundation settlement of approximately 1 inch or less was estimated. Once a final foundation plan with structural loads is completed, WSP should be provided an opportunity to review the plan to confirm estimated settlements are still 1 inch or less, particularly if the maximum structural loads are greater than the maximum column load of 60 kips and maximum wall load of 1 kips per linear feet.

Widths for individual column and continuous wall (strip) footings should be 36 and 18 inches, or more, respectively, to provide a margin of safety against local or punching-type shear failures of the foundation soils. Exterior and interior footings should bear at least 18 inches below final exterior grade and 12 inches below finished floor elevation, respectively, to provide frost protection and protective embedment.

It should be noted that exposure to the environment during the construction may weaken the soils at the footing bearing level if the foundation excavations remain open for long periods of time. Therefore, we recommend that the footings be constructed, and the excavation be extended to final grade as soon as possible to mitigate the potential damage to the bearing soils. The foundation bearing grades should be level or suitably benched and be free of loose soil, ponded water and debris. Foundation concrete should not be placed on soils that have

been disturbed by seepage. If the bearing soils are softened by surface water intrusion or exposure, the softened soils must be removed immediately prior to placement of concrete. If the excavation must remain open overnight or if rainfall becomes imminent while the bearing soils are exposed, we recommend that a 2 to 4-inch thick "mud-mat" of "lean" (2,000 psi compressive strength) concrete be placed on the bearing soils before the placement of reinforcing steel.

An engineering technician working under the supervision of the geotechnical engineer should observe the foundation excavations immediately prior to concrete placement and document that the residual soil foundation bearing conditions are suitable. The engineering technician should perform hand-auger borings with dynamic cone penetrometer (DCP) testing within the excavated foundation bearing grade area. Significant differences between the actual bearing conditions and those indicated by this exploration should be brought to the attention of the owner's representative along with appropriate recommendations for correction of the observed differences (such as, but not limited to, excavation and replacement of unsuitable bearing material, lowering the foundation bearing elevation, or increasing the foundation bearing area).

4.3 GRADE SLABS

Grade slabs may be soil supported in accordance with the recommendations in this report. The grade slab should be jointed around columns and along footing-supported walls so that the slab and foundations can settle differentially without damage. Joints containing dowels or keys may be used in the slab to permit movement between parts of the slab without cracking or sharp vertical displacements. We recommend a vapor barrier be placed below the grade slab to reduce the potential for soil moisture transmission through the slab, along with 4 to 6 inches of well-compacted crusher run gravel placed on the prepared subgrade. A subgrade modulus value k , of 125 pci (pounds per cubic inch), may be used for design of grade slabs placed on successfully proofrolled fill or in-situ residual soil. This recommended subgrade modulus is for a 12-inch by 12-inch test plate and should be reduced for design of a full-size slab. If needed, WSP can provide recommendations for the appropriate subgrade modulus value to be used for design.

5 LIMITATIONS

The recommendations provided are based in part on project information provided to us, and they only apply to the specific project and site discussed in this report. If the project information referenced in this report contains incorrect information or if additional information is available, you should convey the correct or additional information to us and retain us to review our recommendations. We can then modify our recommendations as necessary.

Regardless of the thoroughness of a geotechnical exploration, there is always a possibility that conditions between borings will be different from those at specific boring locations, and that conditions will not be as anticipated by the designers or contractors. In addition, the construction process may itself alter soil conditions. Therefore, experienced geotechnical personnel should observe and document the construction procedures used and the conditions encountered. Unanticipated conditions and inadequate procedures should be reported to the design team along with timely recommendations to solve the problems created. We are available to assist the design and construction team in providing this service based upon our familiarity with the project, the subsurface conditions, and the intent of the recommendations.

WSP prepared this report solely for the use of the intended recipient, North Carolina State University, in accordance with our Proposal dated October 6, 2023. The intended recipient is solely responsible for the disclosure of any information contained in this report. The content and opinions contained in the present report are based on the observations and/or information available to WSP at the time of preparation. If a third party makes use of, relies on, or makes decisions in accordance with this report, said third party is solely responsible for such use, reliance, or decisions. WSP does not accept responsibility for damages, if any, suffered by any third party as a result of decisions made or actions taken by said third party based on this report. This limitations statement is considered an integral part of this report.

APPENDIX

A FIGURES





Legend

- Boring Location
- Parcel Boundary



0 25 50 Feet



© OpenStreetMap (and) contributors, CC-BY-SA



WSP USA Environment & Infrastructure Inc.
4021 Stirrup Creek Drive
Durham, NC 27703

Note: This map is for reference only.

TITLE:
BORING LOCATION PLAN
Proposed Apiculture Facility
4327 Inwood Road
Raleigh, North Carolina 27603


PREPARED BY:
G. HUTCHINS 2/29/2024

CHECKED BY:
M. KAYSER 2/29/2024

PROJECT NUMBER:
6268-23-0125

REFERENCE:
biloba Architecture, PLLC Sheet C3.01
dated 10/12/2023

Figure No.
1



THE SOIL PROFILE SHOWN IS BASED ON INTERPOLATION OF CONDITIONS AT WIDELY SPACED BORINGS OR SOUNDINGS AND REASONABLE ENGINEERING JUDGMENT AND IS NOT WARRANTED.

SEE KEY SHEET IN APPENDIX FOR KEY TO SYMBOLS AND DESCRIPTIONS

B-1 BORING NO.
26.0
BORING ELEVATION

GROUND WATER
24 HOUR READING
TIME OF BORING

BORING DEPTH

15 SPLIT SPOON SAMPLE
SPT "N" Value

ROCK CORE SAMPLE

UNDISTURBED SAMPLE

SUBSURFACE PROFILE

FIGURE NO. 2

PROJECT: NCSU Apiculture Facility

PROJECT NO.: 6468-23-0125

APPENDIX

B

SOIL BORING LOGS

MAJOR DIVISIONS			GROUP SYMBOLS	TYPICAL NAMES	Undisturbed Sample	Auger Cuttings	
COARSE GRAINED SOILS (More than 50% of material is LARGER than No. 200 sieve size)	GRAVELS (More than 50% of coarse fraction is LARGER than the No. 4 sieve size)	CLEAN GRAVELS (Little or no fines)	 GW	Well graded gravels, gravel - sand mixtures, little or no fines.	 Split Spoon Sample	 Bulk Sample	
		GRAVELS WITH FINES (Appreciable amount of fines)	 GP	Poorly graded gravels or gravel - sand mixtures, little or no fines.	 Rock Core	 Crandall Sampler	
		SANDS (More than 50% of coarse fraction is SMALLER than the No. 4 Sieve Size)	CLEAN SANDS (Little or no fines)	 GM	Silty gravels, gravel - sand - silt mixtures.	 Dilatometer	 Pressure Meter
			SW	Well graded sands, well graded sands with gravel.	 Packer	 No Recovery	
	FINE GRAINED SOILS (More than 50% of material is SMALLER than No. 200 sieve size)	SANDS WITH FINES (Appreciable amount of fines)	 SP	Poorly graded sands, poorly graded sands with gravel.	 Water Table at time of drilling	 Water Table after 24 hours	
			 SM	Silty sands.	 Caved Depth	Monitoring Well Explanation  Cement  Bentonite  Sand Filter  Screen	
			 SC	Clayey sands.			
		SILTS AND CLAYS (Liquid limit LESS than 50)	SILTS AND CLAYS (Liquid limit GREATER than 50)	 ML	Inorganic silts, sandy or clayey silts with low plasticity.	Correlation of Penetration Resistance with Relative Density and Consistency	
				 CL	Inorganic clays of low plasticity.		
				 OL	Organic silts and organic silty clays of low plasticity.		
SILTS AND CLAYS (Liquid limit GREATER than 50)	 MH		Inorganic silts, elastic silts.	NON-COHESIVE			
	 CH		Inorganic clays of high plasticity, fat clays	No. of Blows	Relative Density	COHESIVE	
CORED ROCK	SILTS AND CLAYS (Liquid limit GREATER than 50)	 OH	Organic clays of high plasticity, organic silts.	0 - 4	Very Loose	No. of Blows	Consistency
		 RK	Rock	5 - 10	Loose	0 - 1	Very Soft
				11 - 30	Medium Dense	5 - 8	Firm
				31 - 50	Dense	9 - 15	Stiff
				Over 50	Very Dense	16 - 30	Very Stiff
						Over 30	Hard

BOUNDARY CLASSIFICATIONS: Soils possessing characteristics of two groups are designated by combinations of group symbols.

SILT OR CLAY	SAND			GRAVEL		Cobbles	Boulders
	Fine	Medium	Coarse	Fine	Coarse		

No.200 No.40 No.10 No.4 3/4" 3" 12"


U.S. STANDARD SIEVE SIZE

Reference: "Classification of Soils for Engineering Purposes" (Unified Soil Classification System) ASTM D 2487, and/or "Description and Identification of Soils" (Visual-Manual Procedure), ASTM D 2488.



KEY TO SYMBOLS AND DESCRIPTIONS

WSP USA Environment & Infrastructure Inc.




SOIL LOG NCSU APICULTURE FACILITY, GPI 2/26/24

DRILLER: David Hall
 EQUIPMENT: Geoprobe 7822
 METHOD: 3.25" HSA
 HOLE DIA.:
 REMARKS:
 PREPARED BY: MNQ
 CHECKED BY: TPQ

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

SOIL TEST BORING RECORD	
PROJECT: NCSU Apiculture Facility	BORING NO.: B-1
LATITUDE: 723,337.6690	
LONGITUDE: 1,443,575.8340	
DRILLED: February 5, 2024	
PROJ. NO.: 6468-23-0125	PAGE 1 OF 1

wsp




SOIL LOG NCSU APICULTURE FACILITY.GPI 2/26/24

DRILLER: David Hall
 EQUIPMENT: Geoprobe 7822
 METHOD: 3.25" HSA
 HOLE DIA.:
 REMARKS:
 PREPARED BY: MNQ
 CHECKED BY: TPQ

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

SOIL TEST BORING RECORD	
PROJECT: NCSU Apiculture Facility	BORING NO.: B-2
LATITUDE: 723,286.4100	
LONGITUDE: 1,443,666.2420	
DRILLED: February 2, 2024	
PROJ. NO.: 6468-23-0125	PAGE 1 OF 2




DRILLER: David Hall
 EQUIPMENT: Geoprobe 7822
 METHOD: 3.25" HSA
 HOLE DIA.:
 REMARKS:
 PREPARED BY: MNQ
 CHECKED BY: TPQ

SOIL TEST BORING RECORD	
PROJECT: NCSU Apiculture Facility	BORING NO.: B-2
LATITUDE: 723,286.4100	
LONGITUDE: 1,443,666.2420	
DRILLED: February 2, 2024	
PROJ. NO.: 6468-23-0125	PAGE 2 OF 2

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.






SOIL LOG NCSU APICULTURE FACILITY, GPI 2/26/24

DRILLER: David Hall
EQUIPMENT: Geoprobe 7822
METHOD: 3.25" HSA
HOLE DIA.:
REMARKS:

PREPARED BY: MNQ
CHECKED BY: TPQ

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

SOIL TEST BORING RECORD	
PROJECT: NCSU Apiculture Facility	BORING NO.: B-3
LATITUDE: 723,257.5090	
LONGITUDE: 1,443,643.6690	
DRILLED: February 2, 2024	
PROJ. NO.: 6468-23-0125	PAGE 1 OF 1




SOIL LOG NCSU APICULTURE FACILITY, GPI 2/26/24

DRILLER: David Hall
EQUIPMENT: Geoprobe 7822
METHOD: 3.25" HSA
HOLE DIA.:
REMARKS:

PREPARED BY: MNQ
CHECKED BY: TPQ

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

SOIL TEST BORING RECORD	
PROJECT: NCSU Apiculture Facility	BORING NO.: B-4
LATITUDE: 723,317.7060	
LONGITUDE: 1,443,615.4750	
DRILLED: February 5, 2024	
PROJ. NO.: 6468-23-0125	PAGE 1 OF 1




SOIL LOG NCSU APICULTURE FACILITY, GPI 2/26/24

DRILLER: David Hall
 EQUIPMENT: Geoprobe 7822
 METHOD: 3.25" HSA
 HOLE DIA.:
 REMARKS:
 PREPARED BY: MNQ
 CHECKED BY: TPQ

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

SOIL TEST BORING RECORD	
PROJECT: NCSU Apiculture Facility	BORING NO.: B-5
LATITUDE: 723,268.7650	
LONGITUDE: 1,443,690.3410	
DRILLED: February 5, 2024	
PROJ. NO.: 6468-23-0125	PAGE 1 OF 1





SOIL LOG NCSU APICULTURE FACILITY, GPI 2/26/24

DRILLER: David Hall
 EQUIPMENT: Geoprobe 7822
 METHOD: 3.25" HSA
 HOLE DIA.:
 REMARKS:
 PREPARED BY: MNQ
 CHECKED BY: TPQ

THIS RECORD IS A REASONABLE INTERPRETATION OF SUBSURFACE CONDITIONS AT THE EXPLORATION LOCATION. SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND AT OTHER TIMES MAY DIFFER. INTERFACES BETWEEN STRATA ARE APPROXIMATE. TRANSITIONS BETWEEN STRATA MAY BE GRADUAL.

SOIL TEST BORING RECORD	
PROJECT: NCSU Apiculture Facility	BORING NO.: B-6
LATITUDE: 723,243.3560	
LONGITUDE: 1,443,268.7530	
DRILLED: February 2, 2024	
PROJ. NO.: 6468-23-0125	PAGE 1 OF 1



Ms. Melissa Diamond
Formal Design Project Manager
Design & Construction
Facilities Division
North Carolina State University
Raleigh, 27606
mrdiamond@ncsu.edu
919-513-0373

Re: Septic Drain Field Preliminary Soils Exploration
4329 Inwood Road, Raleigh
Wake County, North Carolina
PIN 0791780255

To evaluate suitability of soil for septic drain field, WSP conducted a preliminary soils exploration, on February 6, 2024, within an area proposed by the design team at the Proposed Apiculture Facility site. It is our understanding that an area suitable for an initial system and repair area be able to accommodate a daily design flow of 500 gallons per day is being sought for this site. Based on results of an initial review, as presented in Section 3.3 of the *Report of Geotechnical Engineering Evaluation* prepared by WSP dated March 4, 2024, it was determined that the initial area evaluated would not accommodate the proposed disposal system. Subsequently, upon a request from the project design team, additional soil exploration was conducted by WSP on April 30, 2024.

Locations of the additional areas tested in April are shown in attached Figure No. 1 site test plan. The results were evaluated based on the following criteria to determine suitability to support an on-site wastewater disposal system:

- Topography and landscape position
- Soil characteristics
- Soil wetness
- Soil depth, and
- Restrictive horizons

The landscape in the evaluated areas consisted of a relatively consistent linear side slope (5%) located within a maintained yard. Soils encountered within the recently explored areas consisted of clay loam material. Evidence of soil wetness was not noted in any of the evaluated soil columns.

No evidence of restrictive horizons was noted within the evaluated soil columns. A long-term acceptance rate (LTAR) of 0.4 gallons/day/ft² (gpd per square feet) is likely appropriate for these areas. The soils encountered and evaluated at the additional investigated locations are likely suitable for the proposed disposal system. However, available space may be a limiting factor for this site.



The available space set aside for the initial system as a conventional system is very limited. The use of a 50% reduction system would require approximately 210 feet of trench to accommodate the proposed 500 gpd system. The available space will determine on the exact placement of the buildings and other construction. The initial area reviewed may be large enough to accommodate the repair system.

The findings denoted represent the field conditions observed during the field review. Any disturbance in or near these areas subsequent to the review period may render these findings null and void.

The field test results are not intended to be design rates. Instead, they represent the result of our tests, at the depths and locations indicated. Accordingly, the designer should determine the design rate by applying an appropriate factor of safety, considering that, with time, the bottoms of infiltration systems tend to plug with organics, sediments, and other debris. Long term maintenance will likely be required to remove these deleterious materials to help reduce decreases in actual percolation rates and maintain serviceability of the drain field.

WSP prepared this letter report solely for the use of the intended recipient, North Carolina State University, in accordance with our Proposal dated April 18, 2024. The intended recipient is solely responsible for the disclosure of any information contained in this report. The contents and opinions presented in this report are based on the observations and/or information available to WSP at the time of preparing this report.

Sincerely,

For Jan Gay
NC Licensed Soil Scientist # 1158



8801 JM Keynes Drive
Suite 365
Charlotte, NC 28262
704.248.2922
www.biloba.co

Civil, Landscape Architecture and Structural Engineer

Stewart Inc.
Raleigh 223 S. West Street, Suite 1100
Raleigh, NC 27603
NC Certificate of Licensure: C-1051

Plumbing, Mechanical, and Electrical Engineer:
RMF Engineering
8081 Arco Corporate Dr Suite 300
Raleigh, NC 27617
NC Certificate of Licensure: C-1125



Drawn CO
Checked BAH
Date FEBRUARY 14, 2024
Revisions


LINETYPE LEGEND:	
SYMBOL	DESCRIPTION
	LIMITS OF DISTURBANCE
	PROPERTY LINE
	EASEMENT
	SETBACK
	RIPARIAN BUFFER (50')
	TREE PROTECTION FENCE
	ACCESSIBLE ROUTE

SITE LEGEND:	
SYMBOL	DESCRIPTION
	PROPOSED BUILDING
	PROPOSED CONCRETE SIDEWALK
	PROPOSED BRICK SIDEWALK
	PROPOSED HEAVY DUTY PAVEMENT
	PROPOSED CONCRETE PAVERS
	PROPOSED GRAVEL
	PROPOSED CURB & GUTTER
	PROPOSED STOP BAR
	PROPOSED CROSSWALK
	PROPOSED 6' WIDE STANDARD CROSSWALK
	PROPOSED 10' WIDE HIGH VISIBILITY CROSSWALK
	PROPOSED SIGN
	PROPOSED ADA PARKING SPACE
	PROPOSED KEYSTONE WALL
	PROPOSED CIP WALL
	PROPOSED WHEEL STOP
	PROPOSED GRAVEL TRAIL
	PROPOSED ASPHALT TRAIL
	PROPOSED TREELINE
	PROPOSED FENCE
	PROPOSED VEHICLE GATE (X' WIDE)
	PROPOSED LIGHT
	PROPOSED BIKE RACK
	PROPOSED BENCH
	PROPOSED BOLLARD
	LIMITS OF PEDESTRIAN STEEL PLATE
	LIMITS OF DISTURBANCE

NOTES:

- SEE SHEET C0.10 FOR GENERAL AND SITE NOTES
- ALL GRADING, LANDSCAPING, MULCH PATHS, AND SEATING IS BY NCSU.

SITE DATA	
PROJECT NAME:	NCSU APICULTURE FACILITY
COUNTY:	WAKE
PARCEL PIN #:	0791790255
PARCEL OWNER:	STATE OF NORTH CAROLINA
PARCEL AREA:	15.70 AC
CURRENT ZONING:	R-1
FLOOD PLAIN DATA:	ZONE X
RIVER BASIN:	SWIFT CREEK TRIBUTARY
PLANNING JURISDICTION:	CITY OF RALEIGH
PROPOSED BUILDING:	1 STORY FRAME HOUSE WITH 1 CAR



Copyright 2023. All rights reserved. Printed or electronic drawings and documentation may not be reproduced in any form without written permission from Biloba Architecture, PLLC.

NCSU Apiculture Facility
Raleigh, NC
SCO ID No: 22-24494
Code: 42124 Item: 315
NCSU: 202220007

Project Number 132
Title **SITE PLAN**

Sheet
C3.00

Plate

ADDITIONAL AREAS EVALUATED

N/F
STATE OF NORTH CAROLINA
DB 8489 PG 2026
PIN: 0791790073
47.77 AC




Figure No. 1: Site Test Plan

L:\Projects\2023\20230202 - NCSU Apiculture Facility\DWGS\2-PERMITTING\3-Sheets\C22062-C3.00 Site Plan.dwg Feb 21, 2024 - 12:52pm

EC Narrative

For the proposed

NCSU APICULTURE FACILITY

Raleigh, North Carolina

Prepared for

NC STATE UNIVERSITY

Prepared By

Stewart



STEWART

Submitted on July 01, 2024

Erosion and Sedimentation Control Plan

For

**NCSU APICULTURE FACILITY
4325 Inwood Road
Raleigh, North Carolina**

Prepared for:

NC State University

Prepared by:

**Stewart
C-1051
223 S. West St., Ste 1100
Raleigh, NC 27601
919.380.8750**



FOR REVIEW ONLY

Stewart Project No. C22062

July 01, 2024

Table of Contents

- 1. Table of Contents & Narrative**
 - A. Checklist**
 - B. Financial Responsibility Form**
 - C. Vicinity Map**
 - D. QUAD Map**
 - E. FEMA Map**
 - F. Web Soil Report**
 - G. Wake County Soil Survey Map**
 - H. Storm Drainage & Erosion Control Calculations (Rainfall Data, Drainage Area Maps, Impervious Area Maps, Peak Flow Analysis Calculations, HGLs, Diversion Ditch Drainage area exhibit, Erosion Control Calculations, Time of Concentration Calculations)**
 - I. Deed, Plat and Lease Agreement**

Erosion Control Narrative
NCSU APICULTURE FACILITY
4325 INWOOD ROAD
RALEIGH, NORTH CAROLINA

SUMMARY

Site Information

The proposed NC Apiculture Facility is located at 4325 Inwood Road in Raleigh (PIN 0791780255). The total area of the parcel is 15.70 acres. There are currently 3 existing structures on the property.

The site is within the Swift Creek Watershed (part of the Neuse River Basin) but is not within any water supply watershed or FEMA Floodplain. The Web Soil Survey Map indicates the soils on site consist of Cecil sandy loam, 2 to 6 percent slopes (CeB) which is classified as Hydrologic Soil Group A.

No right of way improvement impervious areas is being included in this project. Two treatment swales will be used for nutrient removal on site. Per Raleigh iMAPS, there are no flood prone soils or floodplains on site.

As seen in the NCSU Apiculture Facility Stormwater Analysis figures, stormwater runoff from the site is currently directed to two points that flow south to Swift Creek

Proposed Improvements

Proposed development on the site will include Proposed development of the site will include one building with 7 parking spaces, gravel driveways, sidewalks, a well, and mulch pathways. Stormwater structures, sanitary sewer and waterlines will be included in the updated site. The proposed impervious cover is 0.415 ac / 18,085 sf.

The total disturbed area is 2.08 acres. The existing impervious surface for the parcel is 0.578 ac / 25,158 sf (3.68% of the 15.70 ac). The total impervious (existing and proposed) surface for the parcel is 0.993 ac (6.32% of the 15.70 ac). The drainage patterns will remain the same.

Stormwater runoff will continue to be directed to the same two analysis points that discharge into Swift Creek. The proposed drainage areas follow the same drainage patterns as the existing drainage areas. The increase in impervious cover will be mitigated with vegetated swales.

Erosion Control Devices

The following erosion control devices will be used throughout the project:

- 1- Temporary Construction Entrance/Exit
- 2- Tree Preservation and Protection
- 3- Temporary Seeding
- 4- Permanent Seeding
- 5- Mulching
- 6- Rolled Erosion Controlled Products
- 7- Inlet Protection
- 8- Wattles/Silt sock
- 9- Silt Fence
- 10-Silt Fence Outlets
- 11-Concrete Washout
- 12-Diversion Ditches

The project has been set up with two (2) erosion control phases. The first phase (I) will be

the installation of the perimeter devices, construction entrance/exit, tree protection and inlet protection on existing stormwater inlets. Once the erosion control installation is approved, demolition of miscellaneous site items will take place.

Utility, storm drainage grading, and site construction shall take place during phase (II) two. Inlet protection and stabilization shall be installed in conjunction with the storm drainage features. All E&SC measures must be maintained until all areas have been stabilized with the establishment of permanent vegetation. All erosion control devices shall be adjusted and reinstalled as the site is constructed. Any dewatering on the project is to be done through the diversion ditches.

All erosion control measures shall be inspected and maintained, if needed at least once per week and after every rainfall event. All erosion control devices shall be maintained as specified by the contract documents. A rain gauge shall be installed at the project site to facilitate rainfall monitoring. Contractor shall maintain these records on-site for audit. Inspections are required until project stabilization is evident by 90% vegetative growth for areas provided seeding.

Contractor shall be responsible for conducting "SELF-INSPECTIONS" indicating date devices are installed and stabilization measures initiated. The "SELF-INSPECTION" reports shall be maintained and submitted once stabilization of project has been accomplished and temporary measures have been removed. Pursuant to the NC General Statute 113A-54.1 (E), the contractor shall conduct "SELF-INSPECTIONS" of erosion control devices at completion of each construction phase and document such inspections as outlines in 5A NCAC 04B.0131. For "INSPECTION AND MONITORING RECORDS FOR ACTIVITIES UNDER STORMWATER GENERAL PERMIT NCG010000 AND SELF INSPECTION RECORDS FOR LAND DISTURBING ACTIVITIES PER G.S.113A-54.1 FORM" See: <https://deq.nc.gov/about/divisions/energy-mineral-land-resources/erosion-sediment-control/forms>. Self-inspection for erosion and sedimentation control measures are to be performed at least once every 7 calendar days and within 24 hours of every rain event greater than 1 inch. Any needed repairs shall be made immediately to maintain measures as designed. All ESC measures shall be maintained as specified on the construction drawings.

Site stabilization is required prior final approval of the erosion control permit and city grading permit and issuance of Certificate of occupancy. When the project is complete, the permittee shall contact DEMLR to close out the E & SC plan. After DEMLR informs the permittee of the project closeout, via inspection report and letter, the permittee shall visit the website at deq.nc.gov/NCG01 to submit an electronic notice of termination (e-NOT A \$100 annual general permit fee will be charged until the e-NOT has been filled out.

Storm Drainage

Peak Flow

The tables below show the pre- and post-development peak flows for the required 2 and 10-year storms during the 24-hour storm event for the parcel.

Peak Flow Analysis								
	Drainage Area (ac)	Composite Curve Number	2-yr Peak Flow		Percent Increase	10-yr Peak Flow		Percent Increase
			Pre (cfs)	Post (cfs)		Pre (cfs)	Post (cfs)	
Analysis Point 1	3.65	51	0.13	0.031	-76%	2.43	2.107	-13%
Analysis Point 2	0.43	55	0.036	0.016	-56%	0.277	0.23	-17%

As is shown, the peak flow for the post developed condition has been mitigated with on-site detention to control the peak flows for the 2-yr and 10-yr 24-hour storm events.

CHECKLIST


FRO



Produced by the United States Geological Survey
North American Datum of 1983 (NAD83)
World Geodetic System of 1984 (WGS84). Projection and
1 000-meter grid/Universal Transverse Mercator, Zone 17S
Data is provided by The National Map (TNM), is the best available at the time of map
generation, and includes data content from supporting themes of Elevation,
Hydrography, Geographic Names, Boundaries, Transportation, Structures, Land Cover,
and Orthimagery. Refer to associated Federal Geographic Data Committee (FGDC)
Metadata for additional source data information.

This map is not a legal document. Boundaries may be generalized for this map scale.
Private lands within government reservations may not be shown. Obtain permission
before entering private lands. Temporal changes may have occurred since these data
were collected and some data may no longer represent actual surface conditions.

Learn About The National Map: <https://nationalmap.gov>



CONTOUR INTERVAL 10 FEET
NORTH AMERICAN VERTICAL DATUM OF 1988
CONTOUR SMOOTHNESS - Medium



QUADRANGLE LOCATION

Cary	Raleigh West	Raleigh East
Apex	Lake Wheeler	Garner
Fuquay-Varina	Angier	Edmondson




LAKE WHEELER, NC
2024

ADJOINING QUADRANGLES

National Flood Hazard Layer FIRMMette



78°40'49"W 35°43'38"N



1:6,000

78°40'11"W 35°43'9"N

Basemap Imagery Source: USGS National Map 2023

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone D
GENERAL STRUCTURES		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		20.2 Cross Sections with 1% Annual Chance Water Surface Elevation 17.5
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
		Coastal Transect Baseline
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped

The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **2/19/2024 at 1:32 PM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

Custom Soil Resource Report Soil Map



Soil Map may not be valid at this scale.

Map Scale: 1:1,610 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 17N WGS84



MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features

-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Wake County, North Carolina
 Survey Area Data: Version 25, Oct 2, 2023

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 24, 2022—May 9, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
CeB	Cecil sandy loam, 2 to 6 percent slopes	8.4	78.3%
CeC	Cecil sandy loam, 6 to 10 percent slopes	0.0	0.0%
PaC	Pacolet sandy loam, 6 to 10 percent slopes	2.3	21.7%
Totals for Area of Interest		10.7	100.0%



NOAA Atlas 14, Volume 2, Version 3
Location name: Raleigh, North Carolina, USA*
Latitude: 35.7286°, Longitude: -78.6836°
Elevation: 397 ft**



* source: ESRI Maps
 ** source: USGS

POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

PF tabular





PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.408 (0.374-0.446)	0.477 (0.437-0.521)	0.549 (0.503-0.599)	0.610 (0.558-0.665)	0.674 (0.614-0.734)	0.721 (0.654-0.786)	0.764 (0.689-0.832)	0.800 (0.718-0.873)	0.842 (0.749-0.918)	0.875 (0.772-0.957)
10-min	0.652 (0.598-0.712)	0.763 (0.700-0.834)	0.878 (0.806-0.959)	0.975 (0.893-1.06)	1.07 (0.978-1.17)	1.15 (1.04-1.25)	1.21 (1.09-1.32)	1.27 (1.14-1.38)	1.33 (1.18-1.45)	1.38 (1.22-1.51)
15-min	0.815 (0.747-0.890)	0.959 (0.879-1.05)	1.11 (1.02-1.21)	1.23 (1.13-1.35)	1.36 (1.24-1.48)	1.45 (1.32-1.58)	1.53 (1.38-1.67)	1.60 (1.44-1.75)	1.68 (1.49-1.83)	1.73 (1.53-1.89)
30-min	1.12 (1.02-1.22)	1.32 (1.22-1.45)	1.58 (1.45-1.72)	1.79 (1.64-1.95)	2.02 (1.84-2.20)	2.19 (1.99-2.39)	2.35 (2.12-2.56)	2.49 (2.24-2.72)	2.67 (2.37-2.91)	2.80 (2.47-3.06)
60-min	1.39 (1.28-1.52)	1.66 (1.52-1.82)	2.02 (1.86-2.21)	2.33 (2.13-2.54)	2.68 (2.45-2.93)	2.97 (2.69-3.23)	3.24 (2.92-3.52)	3.50 (3.14-3.81)	3.82 (3.40-4.17)	4.09 (3.61-4.47)
2-hr	1.63 (1.49-1.80)	1.95 (1.78-2.14)	2.40 (2.19-2.64)	2.79 (2.53-3.06)	3.26 (2.94-3.58)	3.65 (3.28-4.00)	4.03 (3.59-4.41)	4.41 (3.90-4.82)	4.90 (4.30-5.36)	5.31 (4.62-5.82)
3-hr	1.73 (1.58-1.90)	2.07 (1.89-2.28)	2.56 (2.33-2.82)	2.99 (2.72-3.29)	3.54 (3.19-3.88)	4.00 (3.59-4.38)	4.46 (3.96-4.88)	4.93 (4.35-5.39)	5.57 (4.86-6.09)	6.12 (5.28-6.70)
6-hr	2.07 (1.90-2.28)	2.49 (2.28-2.73)	3.08 (2.81-3.37)	3.60 (3.28-3.94)	4.27 (3.86-4.66)	4.84 (4.36-5.28)	5.42 (4.83-5.90)	6.02 (5.31-6.55)	6.84 (5.96-7.44)	7.54 (6.50-8.22)
12-hr	2.44 (2.24-2.68)	2.93 (2.68-3.21)	3.64 (3.32-3.98)	4.28 (3.89-4.68)	5.12 (4.62-5.58)	5.84 (5.23-6.35)	6.58 (5.84-7.15)	7.36 (6.46-7.99)	8.44 (7.29-9.16)	9.39 (7.98-10.2)
24-hr	2.90 (2.69-3.12)	3.49 (3.25-3.77)	4.39 (4.08-4.74)	5.10 (4.72-5.50)	6.07 (5.60-6.54)	6.84 (6.30-7.36)	7.62 (7.00-8.21)	8.43 (7.73-9.09)	9.55 (8.71-10.3)	10.4 (9.48-11.3)
2-day	3.35 (3.12-3.60)	4.04 (3.76-4.34)	5.04 (4.68-5.42)	5.83 (5.40-6.26)	6.90 (6.38-7.41)	7.74 (7.14-8.33)	8.61 (7.92-9.26)	9.51 (8.72-10.2)	10.7 (9.80-11.6)	11.7 (10.6-12.6)
3-day	3.55 (3.31-3.81)	4.27 (3.98-4.58)	5.30 (4.93-5.69)	6.11 (5.68-6.55)	7.22 (6.69-7.74)	8.10 (7.48-8.69)	9.00 (8.29-9.66)	9.93 (9.12-10.7)	11.2 (10.2-12.0)	12.2 (11.1-13.1)
4-day	3.75 (3.50-4.02)	4.50 (4.20-4.82)	5.56 (5.19-5.95)	6.40 (5.95-6.84)	7.55 (7.00-8.07)	8.46 (7.83-9.05)	9.40 (8.66-10.1)	10.4 (9.52-11.1)	11.7 (10.7-12.5)	12.7 (11.6-13.6)
7-day	4.35 (4.07-4.64)	5.19 (4.86-5.54)	6.33 (5.92-6.76)	7.24 (6.76-7.72)	8.48 (7.90-9.04)	9.47 (8.79-10.1)	10.5 (9.70-11.2)	11.5 (10.6-12.3)	12.9 (11.9-13.9)	14.1 (12.9-15.1)
10-day	4.96 (4.65-5.29)	5.90 (5.53-6.29)	7.10 (6.65-7.57)	8.05 (7.52-8.56)	9.32 (8.69-9.92)	10.3 (9.60-11.0)	11.3 (10.5-12.1)	12.4 (11.4-13.2)	13.7 (12.7-14.7)	14.8 (13.6-15.8)
20-day	6.65 (6.24-7.09)	7.86 (7.37-8.37)	9.29 (8.71-9.90)	10.4 (9.76-11.1)	12.0 (11.2-12.7)	13.2 (12.3-14.0)	14.4 (13.3-15.3)	15.6 (14.4-16.6)	17.2 (15.9-18.4)	18.5 (17.1-19.8)
30-day	8.26 (7.78-8.77)	9.72 (9.14-10.3)	11.3 (10.6-12.0)	12.6 (11.8-13.3)	14.2 (13.3-15.1)	15.4 (14.4-16.4)	16.7 (15.6-17.7)	17.9 (16.7-19.1)	19.6 (18.2-20.9)	20.8 (19.3-22.3)
45-day	10.5 (10.0-11.1)	12.4 (11.7-13.0)	14.1 (13.4-14.9)	15.5 (14.7-16.4)	17.3 (16.4-18.2)	18.7 (17.6-19.7)	20.0 (18.8-21.1)	21.3 (20.0-22.5)	23.0 (21.5-24.3)	24.3 (22.7-25.7)
60-day	12.6 (12.0-13.3)	14.7 (14.0-15.5)	16.7 (15.8-17.6)	18.2 (17.2-19.2)	20.1 (19.0-21.2)	21.6 (20.4-22.8)	23.0 (21.7-24.3)	24.3 (22.9-25.7)	26.1 (24.5-27.6)	27.4 (25.7-29.1)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical


PDS-based depth-duration-frequency (DDF) curves
Latitude: 35.7286°, Longitude: -78.6836°




[Back to Top](#)

Maps & aerials

Small scale terrain




Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)



NOAA Atlas 14, Volume 2, Version 3
Location name: Raleigh, North Carolina, USA*
Latitude: 35.7286°, Longitude: -78.6836°
Elevation: 397 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	4.90 (4.49-5.35)	5.72 (5.24-6.25)	6.59 (6.04-7.19)	7.32 (6.70-7.98)	8.09 (7.37-8.81)	8.65 (7.85-9.43)	9.17 (8.27-9.98)	9.60 (8.62-10.5)	10.1 (8.99-11.0)	10.5 (9.26-11.5)
10-min	3.91 (3.59-4.27)	4.58 (4.20-5.00)	5.27 (4.84-5.75)	5.85 (5.36-6.38)	6.44 (5.87-7.02)	6.89 (6.25-7.51)	7.28 (6.56-7.93)	7.61 (6.83-8.30)	7.99 (7.10-8.71)	8.27 (7.30-9.04)
15-min	3.26 (2.99-3.56)	3.84 (3.52-4.19)	4.44 (4.08-4.85)	4.94 (4.52-5.38)	5.44 (4.96-5.93)	5.82 (5.28-6.34)	6.14 (5.53-6.68)	6.40 (5.74-6.98)	6.70 (5.96-7.31)	6.92 (6.10-7.56)
30-min	2.23 (2.05-2.44)	2.65 (2.43-2.90)	3.16 (2.90-3.45)	3.58 (3.27-3.90)	4.03 (3.67-4.39)	4.38 (3.97-4.77)	4.70 (4.24-5.12)	4.98 (4.47-5.44)	5.33 (4.74-5.82)	5.60 (4.94-6.12)
60-min	1.39 (1.28-1.52)	1.66 (1.52-1.82)	2.02 (1.86-2.21)	2.33 (2.13-2.54)	2.68 (2.45-2.93)	2.97 (2.69-3.23)	3.24 (2.92-3.52)	3.50 (3.14-3.81)	3.82 (3.40-4.17)	4.09 (3.61-4.47)
2-hr	0.816 (0.743-0.898)	0.977 (0.892-1.07)	1.20 (1.10-1.32)	1.39 (1.26-1.53)	1.63 (1.47-1.79)	1.83 (1.64-2.00)	2.01 (1.79-2.20)	2.20 (1.95-2.41)	2.45 (2.15-2.68)	2.66 (2.31-2.91)
3-hr	0.575 (0.525-0.633)	0.689 (0.630-0.759)	0.853 (0.776-0.938)	0.996 (0.904-1.09)	1.18 (1.06-1.29)	1.33 (1.19-1.46)	1.48 (1.32-1.62)	1.64 (1.45-1.80)	1.85 (1.62-2.03)	2.04 (1.76-2.23)
6-hr	0.346 (0.317-0.379)	0.415 (0.380-0.456)	0.513 (0.469-0.562)	0.600 (0.547-0.657)	0.713 (0.645-0.778)	0.808 (0.727-0.881)	0.904 (0.807-0.985)	1.00 (0.887-1.09)	1.14 (0.995-1.24)	1.26 (1.08-1.37)
12-hr	0.202 (0.185-0.222)	0.243 (0.222-0.266)	0.301 (0.275-0.330)	0.354 (0.322-0.388)	0.424 (0.383-0.463)	0.484 (0.434-0.526)	0.545 (0.484-0.593)	0.611 (0.536-0.663)	0.700 (0.604-0.760)	0.779 (0.662-0.845)
24-hr	0.120 (0.112-0.129)	0.145 (0.135-0.157)	0.183 (0.169-0.197)	0.212 (0.196-0.229)	0.252 (0.233-0.272)	0.284 (0.262-0.306)	0.317 (0.291-0.342)	0.351 (0.322-0.378)	0.398 (0.362-0.429)	0.434 (0.394-0.469)
2-day	0.069 (0.064-0.075)	0.084 (0.078-0.090)	0.104 (0.097-0.112)	0.121 (0.112-0.130)	0.143 (0.132-0.154)	0.161 (0.148-0.173)	0.179 (0.164-0.192)	0.198 (0.181-0.213)	0.223 (0.204-0.241)	0.243 (0.221-0.262)
3-day	0.049 (0.045-0.052)	0.059 (0.055-0.063)	0.073 (0.068-0.078)	0.084 (0.078-0.091)	0.100 (0.092-0.107)	0.112 (0.103-0.120)	0.125 (0.115-0.134)	0.137 (0.126-0.148)	0.155 (0.142-0.167)	0.169 (0.154-0.182)
4-day	0.039 (0.036-0.041)	0.046 (0.043-0.050)	0.057 (0.054-0.062)	0.066 (0.062-0.071)	0.078 (0.072-0.084)	0.088 (0.081-0.094)	0.097 (0.090-0.104)	0.107 (0.099-0.115)	0.121 (0.111-0.130)	0.132 (0.120-0.142)
7-day	0.025 (0.024-0.027)	0.030 (0.028-0.032)	0.037 (0.035-0.040)	0.043 (0.040-0.045)	0.050 (0.046-0.053)	0.056 (0.052-0.060)	0.062 (0.057-0.066)	0.068 (0.063-0.073)	0.077 (0.070-0.082)	0.083 (0.076-0.089)
10-day	0.020 (0.019-0.022)	0.024 (0.023-0.026)	0.029 (0.027-0.031)	0.033 (0.031-0.035)	0.038 (0.036-0.041)	0.042 (0.039-0.045)	0.047 (0.043-0.050)	0.051 (0.047-0.054)	0.057 (0.052-0.061)	0.061 (0.056-0.065)
20-day	0.013 (0.013-0.014)	0.016 (0.015-0.017)	0.019 (0.018-0.020)	0.021 (0.020-0.023)	0.024 (0.023-0.026)	0.027 (0.025-0.029)	0.029 (0.027-0.031)	0.032 (0.030-0.034)	0.035 (0.033-0.038)	0.038 (0.035-0.041)
30-day	0.011 (0.010-0.012)	0.013 (0.012-0.014)	0.015 (0.014-0.016)	0.017 (0.016-0.018)	0.019 (0.018-0.020)	0.021 (0.020-0.022)	0.023 (0.021-0.024)	0.024 (0.023-0.026)	0.027 (0.025-0.028)	0.028 (0.026-0.030)
45-day	0.009 (0.009-0.010)	0.011 (0.010-0.012)	0.013 (0.012-0.013)	0.014 (0.013-0.015)	0.016 (0.015-0.016)	0.017 (0.016-0.018)	0.018 (0.017-0.019)	0.019 (0.018-0.020)	0.021 (0.019-0.022)	0.022 (0.020-0.023)
60-day	0.008 (0.008-0.009)	0.010 (0.009-0.010)	0.011 (0.010-0.012)	0.012 (0.011-0.013)	0.013 (0.013-0.014)	0.014 (0.014-0.015)	0.015 (0.015-0.016)	0.016 (0.015-0.017)	0.018 (0.017-0.019)	0.019 (0.017-0.020)





¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

PDS-based intensity-duration-frequency (IDF) curves


Latitude: 35.7286°, Longitude: -78.6836°




[Back to Top](#)

Maps & aerials

Small scale terrain




Large scale terrain



Large scale map




Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)



NCSU APICULTURE FACILITY

RALEIGH, NC 27603

EXH-1.0 - EXISTING DRAINAGE AREA MAP

FEBRUARY 20, 2024



STEWART




N/F
STATE OF NORTH CAROLINA
DB 8489 PG 2026
PIN: 0791790073
47.77 AC

N/F
STATE OF NORTH CAROLINA
DB 8489 PG 2023
PIN: 0791780255
15.49 AC/674838.47 SF

N/F
EDGAR H HOBBS
DB 2877 PG 458
PIN: 0791770870
24.82 AC

LEGEND:

	DRAINAGE TO E (DRAINAGE AREA 1)	3.57 AC
	DRAINAGE TO S (DRAINAGE AREA 2)	0.51 AC
	PRE DEVELOPMENT FLOW PATH	



NCSU APICULTURE FACILITY

RALEIGH, NC 27603


EXH-2.0 - PROPOSED DRAINAGE AREA MAP

FEBRUARY 20, 2024



STEWART

L:\Projects\2022\C22062 - NCSU Apiculture Facility\CALCS AND DATA\Erosion Control\04.05.XX - Erosion Control Package\CAD Files\2024.05.08 - C22062.CX.XX Erosion Control Pre and Post DAs.dwg May 20, 2024 - 2:00pm



IMPERVIOUS AREA LEGEND AND CALCULATIONS:

	EXISTING DRIVEWAYS: 14,198 SF / 0.326 AC
	EXISTING CONCRETE: 2,173 SF / 0.0499 AC
	EXISTING BUILDINGS: 6,813 SF / 0.156 AC
TOTAL IMPERVIOUS AREA: 23,184 SF / 0.532 AC	
TOTAL PERVIOUS AREA: 660,708 SF / 15.168 AC	
TOTAL PARCEL AREA: 683,892 SF / 15.700 AC	
PERCENT IMPERVIOUS: 3.39% IMPERVIOUS COVER	

biloba Architecture, PLLC


 8801 JM Keynes Drive
 Suite 365
 Charlotte, NC 28262
 704.248.2922
 www.biloba.co

STEWART
 Civil, Landscape Architecture and Structural Engineer
 Stewart Inc.
 Raleigh 223 S. West Street, Suite 1100
 Raleigh, NC 27603
 NC Certificate of Licensure: C-1051

Plumbing, Mechanical, and Electrical Engineer:
 RMF Engineering
 8381 Arco Corporate Dr Suite 300
 Raleigh, NC 27617
 NC Certificate of Licensure: C-1125

**Preliminary-
 Not For
 Construction**

Drawn	CO
Checked	BAH
Date	FEBRUARY 14, 2024
Revisions	



Copyright 2023. All rights reserved. Printed or electronic drawings and documentation may not be reproduced in any form without written permission from Biloba Architecture, PLLC.

NCSU Apiculture Facility
 Raleigh, NC
 SCO ID No.: 22-24494
 Code: 42124 Item: 315
 NCSU: 202220007

Project Number 132
 Title

EXISTING IMPERVIOUS

Sheet
SW1.00

Plate
 of

L:\Projects\2022\C22062 - NCSU Apiculture Facility\CALCS AND DATA\Erosion Control\2024.05.XX - Erosion Control Package\CAD Files\2024.05.08 - C22062.CX.XX Erosion Control Pre and Post DAs.dwg Jul 01, 2024 - 3:54pm



IMPERVIOUS AREA LEGEND AND CALCULATIONS:

	PROPOSED DRIVEWAYS: 23,769 SF / 0.546 AC
	PROPOSED CONCRETE: 12,855 SF / 0.0987 AC
	PROPOSED BUILDINGS: 11,983 SF / 0.275 AC
TOTAL IMPERVIOUS AREA: 36,534 SF / 0.839 AC	
TOTAL PERVIOUS AREA: 647,358 SF / 14.861 AC	
TOTAL PARCEL AREA: 683,892 SF / 15.700 AC	
PERCENT IMPERVIOUS: 5.34% IMPERVIOUS COVER	
IMPERVIOUS DELTA: 13,350 SF INCREASE	


biloba Architecture, PLLC
 think | design
 8801 JM Keynes Drive
 Suite 365
 Charlotte, NC 28262
 704.248.2922
 www.biloba.co

STEWART
 Civil, Landscape Architecture and Structural Engineer
 Stewart Inc.
 Raleigh 223 S. West Street, Suite 1100
 Raleigh, NC 27603
 NC Certificate of Licensure: C-1051
 NC LA Corporate License: C-303

Plumbing, Mechanical, and Electrical Engineer:
 RME Engineering
 8081 Arco Corporate Dr Suite 300
 Raleigh, NC 27617
 NC Certificate of Licensure: C-1125

**Preliminary-
Not For
Construction**

Drawn	CO
Checked	BAH
Date	FEBRUARY 14, 2024
Revisions	




Copyright 2023. All rights reserved. Printed or electronic drawings and documentation may not be reproduced in any form without written permission from Biloba Architecture, PLLC.

NCSU Apiculture Facility
 Raleigh, NC
 SCO ID No.: 23-24494
 Code: 42124 Item: 315
 NCSU: 202220007

Project Number	132
Title	PROPOSED IMPERVIOUS
Sheet	SW2.00
Plate	

L:\Projects\2022\C22082 - NCSU Apiculture Facility\CALCS AND DATA\Erosion Control\2024_05.XX - Erosion Control Package\CAD Files\2024_05_08 - C22082-CX.XX Erosion Control Pre and Post DAs.dwg, May 20, 2024 - 1:59pm



LINETYPE LEGEND:	
SYMBOL	DESCRIPTION
	LIMITS OF DISTURBANCE
	PROPERTY LINE
	EASEMENT
	SETBACK
	RIPARIAN BUFFER (50')
	TREE PROTECTION FENCE
	ACCESSIBLE ROUTE

EROSION CONTROL LEGEND:	
SYMBOL	DESCRIPTION
	BLOCK & GRAVEL INLET PROTECTION
	SILT FENCE & WIRE INLET PROTECTION
	HORSESHOE INLET PROTECTION
	SILT FENCE OUTLET
	CHECK DAM
	FLARED END SECTION
	SEDIMENT TRAP
	RIP RAP DISSIPATER
	TEMPORARY CONSTRUCTION ENTRANCE
	SILT FENCE
	DIVERSION DITCH
	100 YEAR FLOOD ELEVATION

	DIVERSION DITCH - 1 DRAINAGE AREA
	DIVERSION DITCH - 2 DRAINAGE AREA


biloba Architecture, PLLC

 8801 JM Keynes Drive
 Suite 365
 Charlotte, NC 28262
 704.248.2922
 www.biloba.co

STEWART
 Civil, Landscape Architecture and Structural Engineer
 Stewart Inc.
 Raleigh 223 S. West Street, Suite 1100
 Raleigh, NC 27603
 NC Certificate of Licensure: C-1051
 Plumbing, Mechanical, and Electrical Engineer:
 RMF Engineering
 8081 Arco Corporate Dr Suite 300
 Raleigh, NC 27617
 NC Certificate of Licensure: C-1125

**Preliminary-
 Not For
 Construction**

Drawn	CO
Checked	BAH
Date	FEBRUARY 14, 2024
Revisions	



Copyright 2023. All rights reserved. Printed or electronic drawings and documentation may not be reproduced in any form without written permission from Biloba Architecture, PLLC.

NCSU Apiculture Facility
 Raleigh, NC
 SCO ID No.: 22-24494
 Code: 42124 Item: 315
 NCSU: 202220007

Project Number 132
**DRAINAGE AREAS FOR
 DIVERSION DITCHES**

Sheet
EC1.00

Plate
 of



STEWART

Diversion Channel Dimension Table

Channel	Bottom Width (Y)	Sideslope (M)	Top Width (TW)	Bottom Width (BW)	Lining	Channel Depth (D)	Velocity
DD-01	5.00 FT	3 :1	14.00 FT	5.00 FT	STRAW SINGLE NET BLANKET	1.50 FT	0.42 FT/S
DD-02	5.00 FT	3 :1	14.00 FT	5.00 FT	STRAW SINGLE NET BLANKET	1.50 FT	0.58 FT/S



STEWART

PRE-DEV

TIME OF CONCENTRATION (PER NRCS TR-55 METHOD)

ANALYSIS POINT #1

2/19/2024

SHEET FLOW			
	SEGMENT ID	1.1	1.1
1	SURFACE DESCRIPTION (table 3-1)	Pavement	Grass
2	MANNING'S ROUGHNESS COEFFICIENT, n (table 3-1)	0.011	0.150
3	FLOW LENGTH, L - ft (less than 300 ft)	64	236
4	TWO-YEAR 24-hr RAINFALL DEPTH, P2 - in (per local rainfall data)	3.24	3.24
5	LAND SLOPE, s - ft/ft	0.052	0.036
6	CALCULATION STEP	0.010	0.255

hrs 0.572366

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} s^{0.4}}$$

SHALLOW CONCENTRATED FLOW				
	SEGMENT ID	2.1	2.1	2.1
7	SURFACE DESCRIPTION (PAVED OR UNPAVED)	Unpaved	Paved	Unpaved
8	FLOW LENGTH, L - ft	42.52	27.24	281.38
9	WATERCOURSE SLOPE, s - ft/ft	0.0048	0.019	0.0296
10	AVERAGE VELOCITY, V (fig 3-1)	1.2	2.8	2.8
11	CALCULATION STEP	0.010	0.003	0.028
	SHALLOW CONCENTRATED TOTAL T _c - HOURS	0.010	0.003	0.028

hrs

$$T_t = \frac{L}{3600 V}$$

CHANNEL FLOW		
	SEGMENT ID	3.1
12	CROSS SECTIONAL FLOW AREA, a - ft ²	0
13	WETTED PERIMETER, p _w - ft	0
14	HYDRAULIC RADIUS, r = a/p _w - ft	0
15	CHANNEL SLOPE, s - ft/ft	0
16	MANNING'S ROUGHNESS COEFFICIENT, n	0
17	CALCULATE VELOCITY, ft/s ²	
	$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$	
18	FLOW LENGTH, L - ft	0
19	CALCULATE T _t	0
	$T_t = \frac{L}{3600 V}$	
20	CHANNEL FLOW TOTAL T _c - HOURS	0.000
	WATERSHED AREA TOTAL T _c - HOURS	0.306

hrs

MINIMUM TIME OF CONCENTRATION FOR HYDROGRAPHS IS 5 MIN. **18.3** min



STEWART

PRE-DEV

TIME OF CONCENTRATION (PER NRCS TR-55 METHOD)

ANALYSIS POINT #2

2/19/2024

SHEET FLOW			
	SEGMENT ID	1.1	1.2
1	SURFACE DESCRIPTION (table 3-1)	Pavement	Grass
2	MANNING'S ROUGHNESS COEFFICIENT, n (table 3-1)	0.011	0.150
3	FLOW LENGTH, L - ft (less than 300 ft)	10	290
4	TWO-YEAR 24-hr RAINFALL DEPTH, P2 - in (per local rainfall data)	3.24	3.24
5	LAND SLOPE, s - ft/ft	0.020	0.010
6	CALCULATION STEP	0.003	0.501

hrs 0.196927

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} s^{0.4}}$$

SHALLOW CONCENTRATED FLOW			
	SEGMENT ID	2.1	2.2
7	SURFACE DESCRIPTION (PAVED OR UNPAVED)	Unpaved	Paved
8	FLOW LENGTH, L - ft	49.62	21.59
9	WATERCOURSE SLOPE, s - ft/ft	0.0176	0.0405
10	AVERAGE VELOCITY, V (fig 3-1)	2.1	3.2
11	CALCULATION STEP	0.007	0.002
	SHALLOW CONCENTRATED TOTAL T _c - HOURS	0.007	0.002

hrs 0.39381

$$T_t = \frac{L}{3600 V}$$

CHANNEL FLOW			
	SEGMENT ID	3.1	
12	CROSS SECTIONAL FLOW AREA, a - ft ²	2.454	
13	WETTED PERIMETER, p _w - ft	0.625	
14	HYDRAULIC RADIUS, r = a/p _w - ft	3.926	
15	CHANNEL SLOPE, s - ft/ft	0.005	
16	MANNING'S ROUGHNESS COEFFICIENT, n	0.013	
17	CALCULATE VELOCITY, ft/s ²	20.17	
	$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$		
18	FLOW LENGTH, L - ft	26	
19	CALCULATE T _t	0.000	hrs
	$T_t = \frac{L}{3600 V}$		
20	CHANNEL FLOW TOTAL T _c - HOURS	0.000	
	WATERSHED AREA TOTAL T _c - HOURS	0.513	

MINIMUM TIME OF CONCENTRATION FOR HYDROGRAPHS IS 5 MIN. 30.8 min



STEWART

POST-DEV

TIME OF CONCENTRATION (PER NRCS TR-55 METHOD)

ANALYSIS POINT #1

2/19/2024

SHEET FLOW			
	SEGMENT ID	1.1	1.2
1	SURFACE DESCRIPTION (table 3-1)	Pavement	Grass
2	MANNING'S ROUGHNESS COEFFICIENT, n (table 3-1)	0.011	0.150
3	FLOW LENGTH, L - ft (less than 300 ft)	45	34
4	TWO-YEAR 24-hr RAINFALL DEPTH, P2 - in (per local rainfall data)	3.24	3.24
5	LAND SLOPE, s - ft/ft	0.005	0.032
6	CALCULATION STEP	0.018	0.057

hrs 1.109367

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} s^{0.4}}$$

SHALLOW CONCENTRATED FLOW			
	SEGMENT ID	2.1	
7	SURFACE DESCRIPTION (PAVED OR UNPAVED)	Unpaved	
8	FLOW LENGTH, L - ft	384.5	
9	WATERCOURSE SLOPE, s - ft/ft	0.038	
10	AVERAGE VELOCITY, V (fig 3-1)	3.2	
11	CALCULATION STEP	0.034	hrs
	SHALLOW CONCENTRATED TOTAL T _c - HOURS	0.034	2.034392 #REF!

$$T_t = \frac{L}{3600 V}$$

CHANNEL FLOW			
	SEGMENT ID	3.1	3.2
12	CROSS SECTIONAL FLOW AREA, a - ft ²	3.1415	2.4543
13	WETTED PERIMETER, p _w - ft	1.5707	3.92699
14	HYDRAULIC RADIUS, r = a/p _w - ft	2.000	0.625
15	CHANNEL SLOPE, s - ft/ft	0.033	0.029
16	MANNING'S ROUGHNESS COEFFICIENT, n	0.01	0.013
17	CALCULATE VELOCITY, ft/s ²	42.97	14.27
	$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$		
18	FLOW LENGTH, L - ft	27	49
19	CALCULATE T _t	0.000	0.001
	$T_t = \frac{L}{3600 V}$		
20	CHANNEL FLOW TOTAL T _c - HOURS	0.000	0.001
	WATERSHED AREA TOTAL T _c - HOURS	0.111	

hrs

MINIMUM TIME OF CONCENTRATION FOR HYDROGRAPHS IS 5 MIN. 6.7 min



STEWART

POST-DEV

TIME OF CONCENTRATION (PER NRCS TR-55 METHOD)

ANALYSIS POINT #2

2/19/2024

SHEET FLOW			
	SEGMENT ID	1.1	1.2
1	SURFACE DESCRIPTION (table 3-1)	Pavement	Grass
2	MANNING'S ROUGHNESS COEFFICIENT, n (table 3-1)	0.011	0.150
3	FLOW LENGTH, L - ft (less than 300 ft)	10	290
4	TWO-YEAR 24-hr RAINFALL DEPTH, P2 - in (per local rainfall data)	3.24	3.24
5	LAND SLOPE, s - ft/ft	0.020	0.010
6	CALCULATION STEP	0.003	0.501

hrs 0.196927

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} s^{0.4}}$$

SHALLOW CONCENTRATED FLOW			
	SEGMENT ID	2.1	2.2
7	SURFACE DESCRIPTION (PAVED OR UNPAVED)	Unpaved	Paved
8	FLOW LENGTH, L - ft	49.62	21.59
9	WATERCOURSE SLOPE, s - ft/ft	0.0176	0.0405
10	AVERAGE VELOCITY, V (fig 3-1)	2.1	3.2
11	CALCULATION STEP	0.007	0.002
	SHALLOW CONCENTRATED TOTAL T _c - HOURS	0.007	0.002

hrs 0.39381

$$T_t = \frac{L}{3600 V}$$

CHANNEL FLOW			
	SEGMENT ID	3.1	
12	CROSS SECTIONAL FLOW AREA, a - ft ²	2.454	
13	WETTED PERIMETER, p _w - ft	0.625	
14	HYDRAULIC RADIUS, r = a/p _w - ft	3.926	
15	CHANNEL SLOPE, s - ft/ft	0.005	
16	MANNING'S ROUGHNESS COEFFICIENT, n	0.013	
17	CALCULATE VELOCITY, ft/s ²	20.17	
	$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$		
18	FLOW LENGTH, L - ft	26	
19	CALCULATE T _t	0.000	hrs
	$T_t = \frac{L}{3600 V}$		
20	CHANNEL FLOW TOTAL T _c - HOURS	0.000	
	WATERSHED AREA TOTAL T _c - HOURS	0.513	

MINIMUM TIME OF CONCENTRATION FOR HYDROGRAPHS IS 5 MIN. 30.8 min

Stormwater Impact Analysis
Admin Site Review

For the proposed
NCSU Apiculture Facility

Raleigh, North Carolina

Prepared for
North Carolina State University

Prepared By
Stewart



STEWART

July 1, 2024

Stormwater Impact Analysis

For

NCSU Apiculture Facility

Raleigh, North Carolina

Prepared for:

North Carolina State University

Prepared by:

**Stewart
223 S. West Street, Suite 1100
Raleigh, NC 27603
919.380.8750**



Stewart Project No. C22062

Submitted July 1, 2024

Table of Contents

Table of Contents & Narrative

- 1. Site Information**
 - a. QUAD Map**
 - b. FEMA Map**
 - c. NRCS Soils Map**
 - d. Rainfall Data**
 - e. Drainage Area Map**

- 2. Stormwater Peak Flow Analysis**
 - a. Hydraflow Peak Discharge (Pre / Post Development for the 2 and 10-year storm events)**

- 3. Nutrient Calculations**
 - a. Nutrient Calculation Worksheet**

- 4. Swale Design**
 - a. Sizing Calculations**

STORMWATER IMPACT ANALYSIS

NCSU APICULTURE FACILITY

RALEIGH, NORTH CAROLINA

EXECUTIVE SUMMARY

This Stormwater Impact Analysis report has been prepared to specifically address the requirements of the City of Raleigh Stormwater Management Design Manual in order to quantify the impact of proposed development on downstream systems. The report summarizes the pre- and post-development peak flow discharge calculations along with the Nutrient Export associated with the added development of NCSU Apiculture Facility.

Site Information

The project site is located at 4327 Inwood Rd, Raleigh, NC 27603 (PIN 0791780255). The total area of the parcel is 15.70 acres. There are currently 3 existing structures on the property.

The Project Area used for stormwater analysis is equal to the disturbed area for 4327 Inwood Road. It includes the parcel area and portions of the surrounding public rights-of-way. It was analyzed as one site.

The total Project Area for the stormwater analysis is 4.09 acres of varying cover types. Analysis Point #1 consists of 3.65 acres while Analysis Point #2 consists of 0.43 acres.

There are no existing wetlands or streams on the site. The latest version of the United States Department of Agriculture Soil Conservation Service Soil Survey of Wake County, North Carolina map indicates that the on-site soils are Cecil sandy loam, 2 to 6 percent slopes (CeB) which is classified as Hydrologic Soil Group A. Per FEMA Flood Insurance Rate Map 3720079100K, the project is within Zone X and no 100-yr Floodplain is present.

Proposed Improvements

Proposed development of the site will include one building with 7 parking spaces, gravel driveways, sidewalks and mulch pathways. The redevelopment of the site results in an increase in impervious cover of 18,295 sf.

This increase in impervious cover will be mitigated with vegetated swales.

Design Procedure

The existing site has two points of discharge (Analysis Point). The first resides to the east of the proposed developed area and eventually flows south to Swift Creek. The second runs along the eastern ditch of Inwood Road before connecting into Swift Creek. These points are used for both the existing and proposed conditions. The drainage area is 3.65 acres for Analysis Point #1. The drainage area is 0.43 acres for Analysis Point #2.

The Peak Flow analysis and routing is done with Hydraflow Hydrographs. The SCS Method is used to formulate the hydrographs. The Nitrogen Export for the site is calculated using the Apportioning Method.

Overall Results

The peak flow analysis calculations are below. The drainage areas used for peak flow calculations is shown in the drainage maps in Appendix 01 attached. Please see the corresponding appendices for detailed calculations.

Peak Flow Analysis

The tables below show the pre- and post-development peak flows for the required 2 and 10-year storms during the 24-hour storm event for the parcel.

Peak Flow Analysis								
	Drainage Area (ac)	Composite Curve Number	2-yr Peak Flow		Percent Increase	10-yr Peak Flow		Percent Increase
			Pre (cfs)	Post (cfs)		Pre (cfs)	Post (cfs)	
Analysis Point 1	3.65	51	0.13	0.031	-76%	2.43	2.107	-13%
Analysis Point 2	0.43	55	0.036	0.016	-56%	0.277	0.23	-17%

As is shown, the peak flow for the post developed condition has been mitigated with on-site detention to control the peak flows for the 2-yr and 10-yr 24-hour storm events.

Total Nitrogen Export

This project will also two treatment swales for nutrient removal. Please see Appendix 3 for Nutrient Calculations.

Conclusions


In conclusion the peak flow for the proposed condition has been controlled by means of on-site stormwater control measures. The post condition runoff is less than the pre-developed condition for the required 2-yr, and 10-yr, 24 hour storm events. Nutrient Treatment is being achieved through the addition of treatment swales and buydown.

Submitted 1st of July 2024 by **STEWART**

Christina Oliver, EI
Jason Cheramie, PE

Appendix 1


- 1. Site Information**
 - a. QUAD Map**
 - b. FEMA Map**
 - c. Soils Map**
 - d. Rainfall Data**
 - e. Drainage Area Maps**



Produced by the United States Geological Survey
North American Datum of 1983 (NAD83)
World Geodetic System of 1984 (WGS84). Projection and
1 000 meter grid/Universal Transverse Mercator, Zone 17S
Data is provided by The National Map (TNM), is the best available at the time of map
generation, and includes data content from supporting themes of Elevation,
Hydrography, Geographic Names, Boundaries, Transportation, Structures, Land Cover,
and Orthoimagery. Refer to associated Federal Geographic Data Committee (FGDC)
Metadata for additional source data information.

This map is not a legal document. Boundaries may be generalized for this map scale.
Private lands within government reservations may not be shown. Obtain permission
before entering private lands. Temporal changes may have occurred since these data
were collected and some data may no longer represent actual surface conditions.

Learn About The National Map: <https://nationalmap.gov>



CONTOUR INTERVAL 10 FEET
NORTH AMERICAN VERTICAL DATUM OF 1988
CONTOUR SMOOTHNESS - Medium

USER DEFINED CONTENT



QUADRANGLE LOCATION



ADJOINING QUADRANGLES




7.5-MINUTE TOPO, NC
2024

National Flood Hazard Layer FIRMMette



78°40'49"W 35°43'38"N



1:6,000

78°40'11"W 35°43'9"N

Basemap Imagery Source: USGS National Map 2023

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone D
GENERAL STRUCTURES		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		Cross Sections with 1% Annual Chance Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
		Coastal Transect Baseline
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped

The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards


The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **2/19/2024 at 1:32 PM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

Custom Soil Resource Report Soil Map



Soil Map may not be valid at this scale.



MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features

-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Wake County, North Carolina
 Survey Area Data: Version 25, Oct 2, 2023

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 24, 2022—May 9, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
CeB	Cecil sandy loam, 2 to 6 percent slopes	8.4	78.3%
CeC	Cecil sandy loam, 6 to 10 percent slopes	0.0	0.0%
PaC	Pacolet sandy loam, 6 to 10 percent slopes	2.3	21.7%
Totals for Area of Interest		10.7	100.0%



NOAA Atlas 14, Volume 2, Version 3
Location name: Raleigh, North Carolina, USA*
Latitude: 35.7286°, Longitude: -78.6836°
Elevation: 397 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

PF tabular





PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.408 (0.374-0.446)	0.477 (0.437-0.521)	0.549 (0.503-0.599)	0.610 (0.558-0.665)	0.674 (0.614-0.734)	0.721 (0.654-0.786)	0.764 (0.689-0.832)	0.800 (0.718-0.873)	0.842 (0.749-0.918)	0.875 (0.772-0.957)
10-min	0.652 (0.598-0.712)	0.763 (0.700-0.834)	0.878 (0.806-0.959)	0.975 (0.893-1.06)	1.07 (0.978-1.17)	1.15 (1.04-1.25)	1.21 (1.09-1.32)	1.27 (1.14-1.38)	1.33 (1.18-1.45)	1.38 (1.22-1.51)
15-min	0.815 (0.747-0.890)	0.959 (0.879-1.05)	1.11 (1.02-1.21)	1.23 (1.13-1.35)	1.36 (1.24-1.48)	1.45 (1.32-1.58)	1.53 (1.38-1.67)	1.60 (1.44-1.75)	1.68 (1.49-1.83)	1.73 (1.53-1.89)
30-min	1.12 (1.02-1.22)	1.32 (1.22-1.45)	1.58 (1.45-1.72)	1.79 (1.64-1.95)	2.02 (1.84-2.20)	2.19 (1.99-2.39)	2.35 (2.12-2.56)	2.49 (2.24-2.72)	2.67 (2.37-2.91)	2.80 (2.47-3.06)
60-min	1.39 (1.28-1.52)	1.66 (1.52-1.82)	2.02 (1.86-2.21)	2.33 (2.13-2.54)	2.68 (2.45-2.93)	2.97 (2.69-3.23)	3.24 (2.92-3.52)	3.50 (3.14-3.81)	3.82 (3.40-4.17)	4.09 (3.61-4.47)
2-hr	1.63 (1.49-1.80)	1.95 (1.78-2.14)	2.40 (2.19-2.64)	2.79 (2.53-3.06)	3.26 (2.94-3.58)	3.65 (3.28-4.00)	4.03 (3.59-4.41)	4.41 (3.90-4.82)	4.90 (4.30-5.36)	5.31 (4.62-5.82)
3-hr	1.73 (1.58-1.90)	2.07 (1.89-2.28)	2.56 (2.33-2.82)	2.99 (2.72-3.29)	3.54 (3.19-3.88)	4.00 (3.59-4.38)	4.46 (3.96-4.88)	4.93 (4.35-5.39)	5.57 (4.86-6.09)	6.12 (5.28-6.70)
6-hr	2.07 (1.90-2.28)	2.49 (2.28-2.73)	3.08 (2.81-3.37)	3.60 (3.28-3.94)	4.27 (3.86-4.66)	4.84 (4.36-5.28)	5.42 (4.83-5.90)	6.02 (5.31-6.55)	6.84 (5.96-7.44)	7.54 (6.50-8.22)
12-hr	2.44 (2.24-2.68)	2.93 (2.68-3.21)	3.64 (3.32-3.98)	4.28 (3.89-4.68)	5.12 (4.62-5.58)	5.84 (5.23-6.35)	6.58 (5.84-7.15)	7.36 (6.46-7.99)	8.44 (7.29-9.16)	9.39 (7.98-10.2)
24-hr	2.90 (2.69-3.12)	3.49 (3.25-3.77)	4.39 (4.08-4.74)	5.10 (4.72-5.50)	6.07 (5.60-6.54)	6.84 (6.30-7.36)	7.62 (7.00-8.21)	8.43 (7.73-9.09)	9.55 (8.71-10.3)	10.4 (9.48-11.3)
2-day	3.35 (3.12-3.60)	4.04 (3.76-4.34)	5.04 (4.68-5.42)	5.83 (5.40-6.26)	6.90 (6.38-7.41)	7.74 (7.14-8.33)	8.61 (7.92-9.26)	9.51 (8.72-10.2)	10.7 (9.80-11.6)	11.7 (10.6-12.6)
3-day	3.55 (3.31-3.81)	4.27 (3.98-4.58)	5.30 (4.93-5.69)	6.11 (5.68-6.55)	7.22 (6.69-7.74)	8.10 (7.48-8.69)	9.00 (8.29-9.66)	9.93 (9.12-10.7)	11.2 (10.2-12.0)	12.2 (11.1-13.1)
4-day	3.75 (3.50-4.02)	4.50 (4.20-4.82)	5.56 (5.19-5.95)	6.40 (5.95-6.84)	7.55 (7.00-8.07)	8.46 (7.83-9.05)	9.40 (8.66-10.1)	10.4 (9.52-11.1)	11.7 (10.7-12.5)	12.7 (11.6-13.6)
7-day	4.35 (4.07-4.64)	5.19 (4.86-5.54)	6.33 (5.92-6.76)	7.24 (6.76-7.72)	8.48 (7.90-9.04)	9.47 (8.79-10.1)	10.5 (9.70-11.2)	11.5 (10.6-12.3)	12.9 (11.9-13.9)	14.1 (12.9-15.1)
10-day	4.96 (4.65-5.29)	5.90 (5.53-6.29)	7.10 (6.65-7.57)	8.05 (7.52-8.56)	9.32 (8.69-9.92)	10.3 (9.60-11.0)	11.3 (10.5-12.1)	12.4 (11.4-13.2)	13.7 (12.7-14.7)	14.8 (13.6-15.8)
20-day	6.65 (6.24-7.09)	7.86 (7.37-8.37)	9.29 (8.71-9.90)	10.4 (9.76-11.1)	12.0 (11.2-12.7)	13.2 (12.3-14.0)	14.4 (13.3-15.3)	15.6 (14.4-16.6)	17.2 (15.9-18.4)	18.5 (17.1-19.8)
30-day	8.26 (7.78-8.77)	9.72 (9.14-10.3)	11.3 (10.6-12.0)	12.6 (11.8-13.3)	14.2 (13.3-15.1)	15.4 (14.4-16.4)	16.7 (15.6-17.7)	17.9 (16.7-19.1)	19.6 (18.2-20.9)	20.8 (19.3-22.3)
45-day	10.5 (10.0-11.1)	12.4 (11.7-13.0)	14.1 (13.4-14.9)	15.5 (14.7-16.4)	17.3 (16.4-18.2)	18.7 (17.6-19.7)	20.0 (18.8-21.1)	21.3 (20.0-22.5)	23.0 (21.5-24.3)	24.3 (22.7-25.7)
60-day	12.6 (12.0-13.3)	14.7 (14.0-15.5)	16.7 (15.8-17.6)	18.2 (17.2-19.2)	20.1 (19.0-21.2)	21.6 (20.4-22.8)	23.0 (21.7-24.3)	24.3 (22.9-25.7)	26.1 (24.5-27.6)	27.4 (25.7-29.1)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical


PDS-based depth-duration-frequency (DDF) curves
Latitude: 35.7286°, Longitude: -78.6836°




[Back to Top](#)

Maps & aerials

Small scale terrain




Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)



NOAA Atlas 14, Volume 2, Version 3
Location name: Raleigh, North Carolina, USA*
Latitude: 35.7286°, Longitude: -78.6836°
Elevation: 397 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

PF tabular





PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	4.90 (4.49-5.35)	5.72 (5.24-6.25)	6.59 (6.04-7.19)	7.32 (6.70-7.98)	8.09 (7.37-8.81)	8.65 (7.85-9.43)	9.17 (8.27-9.98)	9.60 (8.62-10.5)	10.1 (8.99-11.0)	10.5 (9.26-11.5)
10-min	3.91 (3.59-4.27)	4.58 (4.20-5.00)	5.27 (4.84-5.75)	5.85 (5.36-6.38)	6.44 (5.87-7.02)	6.89 (6.25-7.51)	7.28 (6.56-7.93)	7.61 (6.83-8.30)	7.99 (7.10-8.71)	8.27 (7.30-9.04)
15-min	3.26 (2.99-3.56)	3.84 (3.52-4.19)	4.44 (4.08-4.85)	4.94 (4.52-5.38)	5.44 (4.96-5.93)	5.82 (5.28-6.34)	6.14 (5.53-6.68)	6.40 (5.74-6.98)	6.70 (5.96-7.31)	6.92 (6.10-7.56)
30-min	2.23 (2.05-2.44)	2.65 (2.43-2.90)	3.16 (2.90-3.45)	3.58 (3.27-3.90)	4.03 (3.67-4.39)	4.38 (3.97-4.77)	4.70 (4.24-5.12)	4.98 (4.47-5.44)	5.33 (4.74-5.82)	5.60 (4.94-6.12)
60-min	1.39 (1.28-1.52)	1.66 (1.52-1.82)	2.02 (1.86-2.21)	2.33 (2.13-2.54)	2.68 (2.45-2.93)	2.97 (2.69-3.23)	3.24 (2.92-3.52)	3.50 (3.14-3.81)	3.82 (3.40-4.17)	4.09 (3.61-4.47)
2-hr	0.816 (0.743-0.898)	0.977 (0.892-1.07)	1.20 (1.10-1.32)	1.39 (1.26-1.53)	1.63 (1.47-1.79)	1.83 (1.64-2.00)	2.01 (1.79-2.20)	2.20 (1.95-2.41)	2.45 (2.15-2.68)	2.66 (2.31-2.91)
3-hr	0.575 (0.525-0.633)	0.689 (0.630-0.759)	0.853 (0.776-0.938)	0.996 (0.904-1.09)	1.18 (1.06-1.29)	1.33 (1.19-1.46)	1.48 (1.32-1.62)	1.64 (1.45-1.80)	1.85 (1.62-2.03)	2.04 (1.76-2.23)
6-hr	0.346 (0.317-0.379)	0.415 (0.380-0.456)	0.513 (0.469-0.562)	0.600 (0.547-0.657)	0.713 (0.645-0.778)	0.808 (0.727-0.881)	0.904 (0.807-0.985)	1.00 (0.887-1.09)	1.14 (0.995-1.24)	1.26 (1.08-1.37)
12-hr	0.202 (0.185-0.222)	0.243 (0.222-0.266)	0.301 (0.275-0.330)	0.354 (0.322-0.388)	0.424 (0.383-0.463)	0.484 (0.434-0.526)	0.545 (0.484-0.593)	0.611 (0.536-0.663)	0.700 (0.604-0.760)	0.779 (0.662-0.845)
24-hr	0.120 (0.112-0.129)	0.145 (0.135-0.157)	0.183 (0.169-0.197)	0.212 (0.196-0.229)	0.252 (0.233-0.272)	0.284 (0.262-0.306)	0.317 (0.291-0.342)	0.351 (0.322-0.378)	0.398 (0.362-0.429)	0.434 (0.394-0.469)
2-day	0.069 (0.064-0.075)	0.084 (0.078-0.090)	0.104 (0.097-0.112)	0.121 (0.112-0.130)	0.143 (0.132-0.154)	0.161 (0.148-0.173)	0.179 (0.164-0.192)	0.198 (0.181-0.213)	0.223 (0.204-0.241)	0.243 (0.221-0.262)
3-day	0.049 (0.045-0.052)	0.059 (0.055-0.063)	0.073 (0.068-0.078)	0.084 (0.078-0.091)	0.100 (0.092-0.107)	0.112 (0.103-0.120)	0.125 (0.115-0.134)	0.137 (0.126-0.148)	0.155 (0.142-0.167)	0.169 (0.154-0.182)
4-day	0.039 (0.036-0.041)	0.046 (0.043-0.050)	0.057 (0.054-0.062)	0.066 (0.062-0.071)	0.078 (0.072-0.084)	0.088 (0.081-0.094)	0.097 (0.090-0.104)	0.107 (0.099-0.115)	0.121 (0.111-0.130)	0.132 (0.120-0.142)
7-day	0.025 (0.024-0.027)	0.030 (0.028-0.032)	0.037 (0.035-0.040)	0.043 (0.040-0.045)	0.050 (0.046-0.053)	0.056 (0.052-0.060)	0.062 (0.057-0.066)	0.068 (0.063-0.073)	0.077 (0.070-0.082)	0.083 (0.076-0.089)
10-day	0.020 (0.019-0.022)	0.024 (0.023-0.026)	0.029 (0.027-0.031)	0.033 (0.031-0.035)	0.038 (0.036-0.041)	0.042 (0.039-0.045)	0.047 (0.043-0.050)	0.051 (0.047-0.054)	0.057 (0.052-0.061)	0.061 (0.056-0.065)
20-day	0.013 (0.013-0.014)	0.016 (0.015-0.017)	0.019 (0.018-0.020)	0.021 (0.020-0.023)	0.024 (0.023-0.026)	0.027 (0.025-0.029)	0.029 (0.027-0.031)	0.032 (0.030-0.034)	0.035 (0.033-0.038)	0.038 (0.035-0.041)
30-day	0.011 (0.010-0.012)	0.013 (0.012-0.014)	0.015 (0.014-0.016)	0.017 (0.016-0.018)	0.019 (0.018-0.020)	0.021 (0.020-0.022)	0.023 (0.021-0.024)	0.024 (0.023-0.026)	0.027 (0.025-0.028)	0.028 (0.026-0.030)
45-day	0.009 (0.009-0.010)	0.011 (0.010-0.012)	0.013 (0.012-0.013)	0.014 (0.013-0.015)	0.016 (0.015-0.016)	0.017 (0.016-0.018)	0.018 (0.017-0.019)	0.019 (0.018-0.020)	0.021 (0.019-0.022)	0.022 (0.020-0.023)
60-day	0.008 (0.008-0.009)	0.010 (0.009-0.010)	0.011 (0.010-0.012)	0.012 (0.011-0.013)	0.013 (0.013-0.014)	0.014 (0.014-0.015)	0.015 (0.015-0.016)	0.016 (0.015-0.017)	0.018 (0.017-0.019)	0.019 (0.017-0.020)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical


PDS-based intensity-duration-frequency (IDF) curves Latitude: 35.7286°, Longitude: -78.6836°



[Back to Top](#)

Maps & aerials

Small scale terrain




Large scale terrain



Large scale map




Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)



N/F
STATE OF NORTH CAROLINA
DB 8489 PG 2026
PIN: 0791790073
47.77 AC

N/F
STATE OF NORTH CAROLINA
DB 8489 PG 2023
PIN: 0791780255
15.49 AC/674838.47 SF

N/F
EDGAR H HOBBS
DB 2877 PG 458
PIN: 0791770870
24.82 AC

LEGEND:		
	DRAINAGE TO E (DRAINAGE AREA 1)	3.65 AC
	DRAINAGE TO S (DRAINAGE AREA 2)	0.43 AC
	PRE DEVELOPMENT FLOW PATH	



NCSU APICULTURE FACILITY


RALEIGH, NC 27603

EXH-1.0 - EXISTING DRAINAGE AREA MAP

FEBRUARY 20, 2024



STEWART



DRAINAGE AREA 1
3.57 ACRES

N/F
STATE OF NORTH CAROLINA
DB 8489 PG 2026
PIN: 0791790073
47.77 AC

N/F
STATE OF NORTH CAROLINA
DB 8489 PG 2023
PIN: 0791780255
15.49 AC/674838.47 SF

N/F
EDGAR H HOBBS
DB 2877 PG 458
PIN: 0791770870
24.82 AC

DRAINAGE AREA 2
.51 ACRES

LEGEND:

-  DRAINAGE TO E (DRAINAGE AREA 1) 3.57 AC
-  DRAINAGE TO S (DRAINAGE AREA 2) 0.51 AC
-  PRE DEVELOPMENT FLOW PATH



NCSU APICULTURE FACILITY

RALEIGH, NC 27603

EXH-2.0 - PROPOSED DRAINAGE AREA MAP

FEBRUARY 20, 2024



STEWART

Appendix 2

- 2. Stormwater Peak Flow Analysis**
 - a. Hydraflow Peak Discharge (Pre / Post Development for the 2 and 10-year storm events)**

Watershed Model Schematic

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023



Legend

<u>Hyd.</u>	<u>Origin</u>	<u>Description</u>
1	SCS Runoff	PRE WS 1 (Analysis #1)
2	SCS Runoff	PRE WS 2 (Analysis #2)

Hydrograph Return Period Recap

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SCS Runoff	-----	-----	0.130	-----	-----	2.430	4.630	6.570	8.716	PRE WS 1 (Analysis #1)
2	SCS Runoff	-----	-----	0.036	-----	-----	0.277	0.476	0.647	0.835	PRE WS 2 (Analysis #2)

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	0.130	2	742	2,129	-----	-----	-----	PRE WS 1 (Analysis #1)
2	SCS Runoff	0.036	2	744	386	-----	-----	-----	PRE WS 2 (Analysis #2)
C22062 PRE Hydraflow.gpw					Return Period: 2 Year			Tuesday, 02 / 20 / 2024	

Hydrograph Report

Hyd. No. 1

PRE WS 1 (Analysis #1)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.130 cfs
Storm frequency	= 2 yrs	Time to peak	= 742 min
Time interval	= 2 min	Hyd. volume	= 2,129 cuft
Drainage area	= 3.700 ac	Curve number	= 51
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 18.40 min
Total precip.	= 3.24 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



TR55 Tc Worksheet

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Hyd. No. 1

PRE WS 1 (Analysis #1)

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.011	0.150	0.011	
Flow length (ft)	= 63.6	236.4	0.0	
Two-year 24-hr precip. (in)	= 3.24	3.24	0.00	
Land slope (%)	= 5.20	3.60	0.00	
Travel Time (min)	= 0.57	+ 15.32	+ 0.00	= 15.89
Shallow Concentrated Flow				
Flow length (ft)	= 42.52	27.24	281.38	
Watercourse slope (%)	= 0.48	1.90	2.96	
Surface description	= Unpaved	Paved	Unpaved	
Average velocity (ft/s)	=1.12	2.80	2.78	
Travel Time (min)	= 0.63	+ 0.16	+ 1.69	= 2.49
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.023	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				18.40 min

Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Tuesday, 02 / 20 / 2024

Hyd. No. 2

PRE WS 2 (Analysis #2)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.036 cfs
Storm frequency	= 2 yrs	Time to peak	= 744 min
Time interval	= 2 min	Hyd. volume	= 386 cuft
Drainage area	= 0.400 ac	Curve number	= 55
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 30.79 min
Total precip.	= 3.24 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



TR55 Tc Worksheet

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Hyd. No. 2

PRE WS 2 (Analysis #2)

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.011	0.150	0.011	
Flow length (ft)	= 10.4	289.5	0.0	
Two-year 24-hr precip. (in)	= 3.24	3.24	0.00	
Land slope (%)	= 2.00	1.00	0.00	
Travel Time (min)	= 0.20	+ 30.07	+ 0.00	= 30.27
Shallow Concentrated Flow				
Flow length (ft)	= 49.62	21.59	0.00	
Watercourse slope (%)	= 1.76	4.05	0.00	
Surface description	= Unpaved	Unpaved	Unpaved	
Average velocity (ft/s)	=2.14	3.25	0.00	
Travel Time (min)	= 0.39	+ 0.11	+ 0.00	= 0.50
Channel Flow				
X sectional flow area (sqft)	= 2.45	0.00	0.00	
Wetted perimeter (ft)	= 0.63	0.00	0.00	
Channel slope (%)	= 0.50	0.00	0.00	
Manning's n-value	= 0.013	0.015	0.015	
Velocity (ft/s)	=20.26	0.00	0.00	
Flow length (ft)	{{0}}26.0	0.0	0.0	
Travel Time (min)	= 0.02	+ 0.00	+ 0.00	= 0.02
Total Travel Time, Tc				30.79 min

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	2.430	2	728	10,670	-----	-----	-----	PRE WS 1 (Analysis #1)
2	SCS Runoff	0.277	2	736	1,522	-----	-----	-----	PRE WS 2 (Analysis #2)
C22062 PRE Hydraflow.gpw					Return Period: 10 Year			Tuesday, 02 / 20 / 2024	

Hydrograph Report

Hyd. No. 1

PRE WS 1 (Analysis #1)

Hydrograph type	= SCS Runoff	Peak discharge	= 2.430 cfs
Storm frequency	= 10 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 10,670 cuft
Drainage area	= 3.700 ac	Curve number	= 51
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 18.40 min
Total precip.	= 5.11 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484




Hydrograph Report

Hyd. No. 2

PRE WS 2 (Analysis #2)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.277 cfs
Storm frequency	= 10 yrs	Time to peak	= 736 min
Time interval	= 2 min	Hyd. volume	= 1,522 cuft
Drainage area	= 0.400 ac	Curve number	= 55
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 30.79 min
Total precip.	= 5.11 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Watershed Model Schematic

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023



Legend

<u>Hyd.</u>	<u>Origin</u>	<u>Description</u>
1	SCS Runoff	POST WS 1 (Analysis #1)
2	SCS Runoff	POST WS 2 (Analysis #2)

Hydrograph Return Period Recap

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SCS Runoff	-----	-----	0.031	-----	-----	2.107	4.677	6.979	9.552	POST WS 1 (Analysis #1)
2	SCS Runoff	-----	-----	0.016	-----	-----	0.230	0.437	0.626	0.840	POST WS 2 (Analysis #2)

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	0.031	2	806	1,025	-----	-----	-----	POST WS 1 (Analysis #1)
2	SCS Runoff	0.016	2	758	291	-----	-----	-----	POST WS 2 (Analysis #2)
C22062 POST Hydraflow.gpw					Return Period: 2 Year			Tuesday, 02 / 20 / 2024	

Hydrograph Report

Hyd. No. 1

POST WS 1 (Analysis #1)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.031 cfs
Storm frequency	= 2 yrs	Time to peak	= 806 min
Time interval	= 2 min	Hyd. volume	= 1,025 cuft
Drainage area	= 3.570 ac	Curve number	= 47
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.70 min
Total precip.	= 3.24 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



TR55 Tc Worksheet

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Hyd. No. 1

POST WS 1 (Analysis #1)

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.011	0.150	0.011	
Flow length (ft)	= 45.1	34.4	0.0	
Two-year 24-hr precip. (in)	= 3.24	3.24	0.00	
Land slope (%)	= 0.50	3.18	0.00	
Travel Time (min)	= 1.11	+ 3.44	+ 0.00	= 4.55
Shallow Concentrated Flow				
Flow length (ft)	= 384.50	0.00	0.00	
Watercourse slope (%)	= 3.80	0.00	0.00	
Surface description	= Unpaved	Paved	Unpaved	
Average velocity (ft/s)	=3.15	0.00	0.00	
Travel Time (min)	= 2.04	+ 0.00	+ 0.00	= 2.04
Channel Flow				
X sectional flow area (sqft)	= 3.14	2.45	0.00	
Wetted perimeter (ft)	= 1.57	3.93	6.00	
Channel slope (%)	= 3.30	2.90	3.00	
Manning's n-value	= 0.010	0.013	0.026	
Velocity (ft/s)	=43.07	14.25	0.00	
Flow length (ft)	{{0}}27.0	49.0	150.0	
Travel Time (min)	= 0.01	+ 0.06	+ 0.00	= 0.07
Total Travel Time, Tc				6.70 min

Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Tuesday, 02 / 20 / 2024


Hyd. No. 2

POST WS 2 (Analysis #2)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.016 cfs
Storm frequency	= 2 yrs	Time to peak	= 758 min
Time interval	= 2 min	Hyd. volume	= 291 cuft
Drainage area	= 0.500 ac	Curve number	= 51
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 30.80 min
Total precip.	= 3.24 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

POST WS 2 (Analysis #2)

Hyd. No. 2 -- 2 Year



TR55 Tc Worksheet

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Hyd. No. 2

POST WS 2 (Analysis #2)

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.011	0.150	0.011	
Flow length (ft)	= 10.4	289.5	0.0	
Two-year 24-hr precip. (in)	= 3.24	3.24	0.00	
Land slope (%)	= 2.00	1.00	0.00	
Travel Time (min)	= 0.20	+ 30.07	+ 0.00	= 30.27
Shallow Concentrated Flow				
Flow length (ft)	= 49.62	21.59	0.00	
Watercourse slope (%)	= 1.76	4.05	0.00	
Surface description	= Unpaved	Unpaved	Unpaved	
Average velocity (ft/s)	=2.14	3.25	0.00	
Travel Time (min)	= 0.39	+ 0.11	+ 0.00	= 0.50
Channel Flow				
X sectional flow area (sqft)	= 2.45	0.00	0.00	
Wetted perimeter (ft)	= 0.63	0.00	0.00	
Channel slope (%)	= 0.50	0.00	0.00	
Manning's n-value	= 0.013	0.015	0.015	
Velocity (ft/s)	=20.26	0.00	0.00	
Flow length (ft)	{{0}}26.0	0.0	0.0	
Travel Time (min)	= 0.02	+ 0.00	+ 0.00	= 0.02
Total Travel Time, Tc				30.80 min

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	2.107	2	722	7,470	-----	-----	-----	POST WS 1 (Analysis #1)
2	SCS Runoff	0.230	2	736	1,460	-----	-----	-----	POST WS 2 (Analysis #2)
C22062 POST Hydraflow.gpw					Return Period: 10 Year			Tuesday, 02 / 20 / 2024	

Hydrograph Report

Hyd. No. 1

POST WS 1 (Analysis #1)

Hydrograph type	= SCS Runoff	Peak discharge	= 2.107 cfs
Storm frequency	= 10 yrs	Time to peak	= 722 min
Time interval	= 2 min	Hyd. volume	= 7,470 cuft
Drainage area	= 3.570 ac	Curve number	= 47
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.70 min
Total precip.	= 5.11 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Tuesday, 02 / 20 / 2024


Hyd. No. 2

POST WS 2 (Analysis #2)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.230 cfs
Storm frequency	= 10 yrs	Time to peak	= 736 min
Time interval	= 2 min	Hyd. volume	= 1,460 cuft
Drainage area	= 0.500 ac	Curve number	= 51
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 30.80 min
Total precip.	= 5.11 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

POST WS 2 (Analysis #2)

Hyd. No. 2 -- 10 Year



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	4.677	2	720	12,896	-----	-----	-----	POST WS 1 (Analysis #1)
2	SCS Runoff	0.437	2	736	2,365	-----	-----	-----	POST WS 2 (Analysis #2)
C22062 POST Hydraflow.gpw					Return Period: 25 Year			Tuesday, 02 / 20 / 2024	

Hydrograph Report

Hyd. No. 1

POST WS 1 (Analysis #1)

Hydrograph type	= SCS Runoff	Peak discharge	= 4.677 cfs
Storm frequency	= 25 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 12,896 cuft
Drainage area	= 3.570 ac	Curve number	= 47
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.70 min
Total precip.	= 6.14 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Tuesday, 02 / 20 / 2024

Hyd. No. 2

POST WS 2 (Analysis #2)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.437 cfs
Storm frequency	= 25 yrs	Time to peak	= 736 min
Time interval	= 2 min	Hyd. volume	= 2,365 cuft
Drainage area	= 0.500 ac	Curve number	= 51
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 30.80 min
Total precip.	= 6.14 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	6.979	2	720	17,752	-----	-----	-----	POST WS 1 (Analysis #1)
2	SCS Runoff	0.626	2	734	3,154	-----	-----	-----	POST WS 2 (Analysis #2)
C22062 POST Hydraflow.gpw					Return Period: 50 Year		Tuesday, 02 / 20 / 2024		

Hydrograph Report

Hyd. No. 1

POST WS 1 (Analysis #1)

Hydrograph type	= SCS Runoff	Peak discharge	= 6.979 cfs
Storm frequency	= 50 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 17,752 cuft
Drainage area	= 3.570 ac	Curve number	= 47
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.70 min
Total precip.	= 6.93 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Tuesday, 02 / 20 / 2024

Hyd. No. 2

POST WS 2 (Analysis #2)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.626 cfs
Storm frequency	= 50 yrs	Time to peak	= 734 min
Time interval	= 2 min	Hyd. volume	= 3,154 cuft
Drainage area	= 0.500 ac	Curve number	= 51
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 30.80 min
Total precip.	= 6.93 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	9.552	2	720	23,257	-----	-----	-----	POST WS 1 (Analysis #1)
2	SCS Runoff	0.840	2	734	4,033	-----	-----	-----	POST WS 2 (Analysis #2)
C22062 POST Hydraflow.gpw					Return Period: 100 Year			Tuesday, 02 / 20 / 2024	

Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Tuesday, 02 / 20 / 2024

Hyd. No. 1

POST WS 1 (Analysis #1)

Hydrograph type	= SCS Runoff	Peak discharge	= 9.552 cfs
Storm frequency	= 100 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 23,257 cuft
Drainage area	= 3.570 ac	Curve number	= 47
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.70 min
Total precip.	= 7.74 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2023

Tuesday, 02 / 20 / 2024

Hyd. No. 2

POST WS 2 (Analysis #2)

Hydrograph type	= SCS Runoff	Peak discharge	= 0.840 cfs
Storm frequency	= 100 yrs	Time to peak	= 734 min
Time interval	= 2 min	Hyd. volume	= 4,033 cuft
Drainage area	= 0.500 ac	Curve number	= 51
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 30.80 min
Total precip.	= 7.74 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484



Appendix 3

- 3. Nutrient Calculations**
 - a. Nutrient Calculation Worksheet**

TN Export and Offset Payment Calculation Worksheet

Complete the **YELLOW** fields on both pages according to the directions. Calculations will be made automatically.

Project Name: **NCSU Apiculture** Date: **7/1/2024**

CALCULATING TOTAL TN EXPORT FROM SITE

Determine the **Total TN Export from Site** by entering the area for each type of land use in Column 2.

NOTE: Additional Impervious Surface Area (ISA) is the difference between Existing Conditions ISA and Post-Construction ISA. If the difference is negative, then enter ZERO for Additional ISA.

Column 1	Column 2	Column 3	Column 4	Column 5
Type of Land Cover	Site Area (acres)	TN Export Coeff. (lbs/ac/yr)	TN Export by Land Use (lbs/yr)	TN Export from Site (lbs/ac/yr)
Permanently Preserved Undisturbed Open Space (forest, unmown meadow, etc)	13.54	0.60	8.12	
Permanently Preserved Managed Open Space (grass, landscaped areas, etc.)	1.40	1.20	1.68	
Existing Conditions - Impervious Surface Area (roads, parking lots, roofs, driveways, etc.)	0.13	10.60	1.38	
Additional Impervious Surface Area (See NOTE above)	0.42	21.20	8.90	
TOTAL	15.49		20.09	1.30

If the project contributes greater than 3.6 lbs/ac/yr of nutrients, but less than 10.0 lbs/ac/yr (6.0 lbs/ac/yr - residential), the following options are available:

- 1) Install BMPs to remove enough nutrients to bring the development activity to 3.6 lbs/ac/yr or below.
- 2) Do a combination of BMPs and an offset payment to achieve a 3.6 lbs/ac/yr export.
- 3) Submit a "No Practical Alternatives" summary stating why BMPs could not be configured and incorporated into the design and pay a one-time nutrient offset fee.

If the computed export is greater than 10.0 lbs/ac/yr (6.0 - residential), then the project must incorporate BMPs to bring the development's export down to 10.0 lbs/ac/yr (6.0 lbs/ac/yr - residential). Then, the project may use one of the three options above.

TN Export and Offset Payment Calculation Worksheet

Project Name: **NCSU Apiculture** Date: **1-Jul-24**

CALCULATING TN REDUCTION THROUGH THE USE ON BMPs

Enter the correlating TN Removal Rate in Column 2 for each BMPs proposed. Enter appropriate name of BMP in Column 5.

Row	Column 1 TN Export from Site	Column 2 Removal Rate	Column 3 Nitrogen Loading		Column 5 Type of BMPs Proposed
A	1.30		1.30	Series 1	
B				Series 2	
C				Series 3	
D				Series 4	
E				Series 5	

CALCULATED OFFSET PAYMENT

Total from Column 3 (above)	1.30	lbs/ac/yr
Minimum TN Export w/o Payment	3.6	lbs/ac/yr
TN Removal Not Achieved	0	lbs/ac/yr
Offset Payment Fee	\$750	per lb
Total Drainage Area to Device	15.49	acres
Total Fee for Project	\$0.00	

Appendix 4

4. Swale Design
 - a. Sizing Calculations



STORMWATER MANAGEMENT PERMIT APPLICATION FOR
401 CERTIFICATION APPLICATION FORM

GRASSED SWALE SUPPLEMENT

This form must be filled out, printed and submitted.

The Required Items Checklist (Part III) must also be filled out, printed and submitted along with this form.

I. PROJECT INFORMATION

Project name	NCSU Apiculture Facility
Contact name	Jason Cheramie
Phone number	984-514-0069
Date	June 28, 2024
Drainage area number	Swale 1

II. DESIGN INFORMATION

Site Characteristics	
Drainage area	159,137.20 ft ²
Impervious area	9,887.22 ft ²
Percent impervious	6.2% %
Design rainfall depth	1.00 inch
Peak Flow Calculations	
10-yr storm runoff depth	3.24 in
10-yr storm intensity	in/hr
Post-development 10-yr storm peak flow	1.47 ft ³ /sec
Velocity	
Maximum non-erosive velocity (peak 10-year storm)	4.50 ft/sec
Soil characteristics (enter "x" below)	
Sand/silt (easily erodible)	x
Clay mix (erosion resistant)	
Grass Type (enter "x" below)	
Bermuda	
Tall fescue	x
Bahiagrass	
Kentucky bluegrass	
Grass-legume mixture	
Swale type: Fill out <i>one</i> of the options below:	
Option 1: Curb Outlet Swale:	n (Y or N)
Maximum velocity:	

Swale Characteristics

Swale Shape: Enter an "x" in the appropriate cell below:

Trapezoidal	x
Parabolic	
V-shaped	
Width of the bottom of the swale	5.00 ft
Width of the top of the swale	14.00 ft

Additional Information

Is the swale sized for all runoff from ultimate build-out?	y (Y or N)	OK
Is the BMP located in a proposed drainage easement with a recorded access easement to a public Right of Way (ROW)?	n (Y or N)	Insufficient ROW
What is the distance from the bottom of the swale to the SHWT?	12.00 ft	OK
What is the ground level elevation?	348.00 fmsl	
What is the elevation of the bottom of the swale?	346.00 fmsl	
What is the SHWT elevation?	334.00 fmsl	
What is the longitudinal slope of the swale?	1.90 %	OK
What is the depth of freeboard?	0.50 ft	OK



STORMWATER MANAGEMENT PERMIT APPLICATION FOR
401 CERTIFICATION APPLICATION FORM

GRASSED SWALE SUPPLEMENT

This form must be filled out, printed and submitted.

The Required Items Checklist (Part III) must also be filled out, printed and submitted along with this form.

I. PROJECT INFORMATION

Project name	NCSU Apiculture Facility
Contact name	Jason Cheramie
Phone number	984-514-0069
Date	June 28, 2024
Drainage area number	Swale 2

II. DESIGN INFORMATION

Site Characteristics	
Drainage area	159,137.20 ft ²
Impervious area	9,887.22 ft ²
Percent impervious	6.2% %
Design rainfall depth	1.00 inch
Peak Flow Calculations	
10-yr storm runoff depth	3.24 in
10-yr storm intensity	in/hr
Post-development 10-yr storm peak flow	1.47 ft ³ /sec
Velocity	
Maximum non-erosive velocity (peak 10-year storm)	4.50 ft/sec
Soil characteristics (enter "x" below)	
Sand/silt (easily erodible)	x
Clay mix (erosion resistant)	
Grass Type (enter "x" below)	
Bermuda	
Tall fescue	x
Bahiagrass	
Kentucky bluegrass	
Grass-legume mixture	
Swale type: Fill out <i>one</i> of the options below:	
Option 1: Curb Outlet Swale:	n (Y or N)
Maximum velocity:	

Swale Characteristics

Swale Shape: Enter an "x" in the appropriate cell below:

Trapezoidal	x
Parabolic	
V-shaped	
Width of the bottom of the swale	5.00 ft
Width of the top of the swale	14.00 ft


Additional Information

Is the swale sized for all runoff from ultimate build-out?	y (Y or N)	OK
Is the BMP located in a proposed drainage easement with a recorded access easement to a public Right of Way (ROW)?	n (Y or N)	Insufficient ROW
What is the distance from the bottom of the swale to the SHWT?	8.00 ft	OK
What is the ground level elevation?	344.00 fmsl	
What is the elevation of the bottom of the swale?	342.00 fmsl	
What is the SHWT elevation?	334.00 fmsl	
What is the longitudinal slope of the swale?	3.00 %	OK
What is the depth of freeboard?	0.50 ft	OK

STATE OF NORTH CAROLINA

NORTH CAROLINA STATE UNIVERSITY

APICULTURE BUILDING



ASBESTOS ABATEMENT SPECIFICATIONS

MATRIX HEALTH & SAFETY CONSULTANTS, LLC
Todd E. Daugherty
NC Asbestos Designer No 40353

January 7, 2025

TABLE OF CONTENTS

Page Number

TECHNICAL SPECIFICATIONS

01043 Project Coordination.....	01043-1
01092 Codes and Regulations	01092-1
01410 Air Monitoring - Industrial Hygiene Firm Services	01410-1
01503 Temporary Facilities	01503-1
01513 Negative Pressure System	01513-1
01526 Work Area Preparation	01526-1
01560 Worker Protection	01560-1
01562 Respiratory Protection	01562-1
01563 Decontamination Units	01563-1
01711 Project Decontamination	01711-1
01714 Work Area Clearance	01714-1
02080 Asbestos Removal	02080-1
02084 Disposal of Asbestos-Containing Waste Material	02084-1

Appendices

Appendix A Prework Asbestos Inspection Checklist.....	Appendix A-1
Appendix B Decontamination Area Arrangement.....	Appendix B-1
Apiculture Building – Report of Survey to Identify Asbestos-Containing Materials	

DRAWINGS

N/A

SECTION 01043

PROJECT COORDINATION

1.01 GENERAL

- A. All asbestos abatement contractors will be licensed general contractors in either the specialty interior, building, unclassified or asbestos categories by the North Carolina Licensing Board of General Contractors and limited for the bid amount.
- B. The contractor shall be responsible for inspecting the site prior to bidding to confirm the scope of the work. Any quantities listed by the designer in the plans, specifications or survey are done so as approximations. The actual quantities of asbestos-containing material to be encountered is the responsibility of the contractor.
- C. The contractor shall furnish and is responsible for all costs including, but not limited to: permit fees, containment preparation, labor, materials, services, insurance, bonding, and equipment necessary to carry out the abatement operations and disposal of all asbestos material in accordance with the plans and specifications, the EPA and OSHA regulations, and any applicable state and local government regulations.
- D. The contractor/employer has and assumes the responsibility of proceeding in such a manner that he offers his employees a workplace free of recognized hazards causing or likely to cause death or serious injury. The contractor shall be responsible for performing this abatement and disposal so that airborne asbestos fiber levels do not exceed established levels.
- E. The contractor will be responsible for all costs associated with employee monitoring to meet the OSHA requirements.
- F. The contractor is responsible for all costs, including additional visits, should the designer and/or the industrial hygiene firm determine that the contractor failed a final inspection. Notification and scheduling of the final inspection during the project is the responsibility of the contractor. The contractor will allow a minimum notice of 72 hours unless a different time frame is agreed upon by the designer and the contractor.
- G. Contractor shall coordinate all asbestos removal activities with the owner and designer. Owner shall have continuous use of areas not included in the scope of this project.

1.02 PERSONNEL

A. Supervisor

1. All supervisors shall be accredited by the Health Hazards Control Unit (HHCU).
2. All supervisors on the project shall have five years experience in the administration and supervision of asbestos abatement projects including work practices, protective measures for building and personnel, disposal procedures, etc.
3. One supervisor shall be provided for every 10 workers inside the containment. A minimum of one supervisor shall be provided per project.
4. The contractor shall have at least one employee on the job site in either a foreman or supervisor's position who is bilingual in the appropriate languages when employing workers who do not speak fluent English.
5. A minimum of one supervisor per company shall have attended a 24 hour respiratory protection course.

B. Worker

1. All workers shall be accredited by the HHCU.

C. Competent Person

1. A competent person, as defined in the OSHA asbestos standard 29 CFR 1926.1101, employed by the contractor must be outside the work area at all times to monitor activity, ensure containment security, provide information to visitors, and provide access to the work area.

D. Employees

1. The contractor is responsible for the behavior of workers within his employment. If at any time during the contracted work, any of his employees are judged to exhibit behavior unfitting for the area or judged to be a nuisance by the owner or designer, the contractor shall remove them immediately from the project.
2. The contractor shall be responsible for compliance with the following concerning employee behavior:
 - a. Under no circumstances are alcohol, drugs or any other type of controlled substances permitted on state property.
 - b. All workers are restricted to the construction project site only.

- c. All vehicles must be parked in areas prearranged with the owner.
 - d. All workers must conform to the following basic dress code when in public areas of the project confines: long pants, shirts, no tank tops, no shorts, no bare backs.
 - e. The contractor is responsible for disposal of all trash brought on state property by his employees, including drink cans, bottles or other food containers and wrappers.
3. Failure to adhere to these rules could result in criminal prosecution and/or removal from the State property.

1.03 MEETINGS

- A. Pre-construction - Prior to beginning work on the project, an asbestos pre-construction meeting will be held at the site. The purpose of the pre-construction meeting shall be to coordinate scheduling, operation, and overall logistics for execution of the project. Contractor's project manager and supervisor are required to attend.
- B. Progress meetings - Progress meetings will be held to document compliance with project schedule and project specifications. Progress meetings will also address job problems and owner concerns. Contractor's project manager and supervisor are required to attend each progress meeting.

1.04 PRE-JOB SUBMITTALS

- A. Submit complete set of pre-job submittals to the designer at least 10 days prior to start of work. Work is prohibited until submittal package has been reviewed and approved by designer. A copy of the approved submittals shall be kept in a three-ring binder (project log) by the contractor at the project site in the clean room or in the on-site office of the contractor.
 - 1. Notifications: Provide copies of Asbestos Permit Application and Notification for Demolition/Renovation (DEHNR 3768), which provide written notice to all required agencies, including North Carolina HHCU. Provide notification letters to local EMS, fire and police departments.
 - 2. Employee List: Provide copies of lists of supervisors and workers, along with their accreditation, to be utilized on the project.
 - 3. Permits: Provide copies of approval of a waste disposal site in compliance with 40 CFR 61.154.

4. Medical: Include individually signed forms by each worker to be utilized on the project documenting that each is actively involved in a company employee medical surveillance program.
5. Respirator Training: Copies of most recent fit testing records, individually signed for each worker to be utilized on the project.
6. Project Schedule: Time schedule for the project, outlining the proposed start, setup, clearances, etc. for the project.
7. Initial Exposure Assessment: As required by the OSHA construction asbestos standard 29 CFR 1926.1101.
8. Any other programs or training as outlined by the OSHA and EPA standards.

1.05 POST-JOB SUBMITTALS

- A. Submit complete set of post-job submittals to the designer following the final completion of the work. Requests for final payment will not be approved until the submittal package has been reviewed and approved by the designer.
 1. Affidavits: Contractor's affidavit of payment of debts and claims, affidavit of release of liens, and consent of surety company to final payment.
 2. Manifest: North Carolina Asbestos Waste Shipment Record (DEHNR 3787) receipt from landfill operator which acknowledges the contractor's delivery(s) of waste material. Include date, quantity of material delivered and signature of authorized representative of landfill. Also, include name of waste transporter.
 3. Daily Log: A copy of all daily logs showing the following: name, date, entering and leaving time, company or agency represented, reason for entry for all persons entering the work area, employee's daily air monitoring data as required by the OSHA standard and written comments by inspectors, industrial hygienists, designers and visitors.
 4. Worker Submittals: Provide copies of accreditations, social security numbers, and medicals for all new workers utilized on the project.
 5. Special Reports: All documents generated under Section 01043.1.06.

1.06 SPECIAL REPORTS

- A. General: Except as otherwise indicated, submit special reports to designer within one day of occurrence requiring special report, with copies to others affected by occurrence. Also keep a copy in the project log book.
- B. Reporting Unusual Events: When an event of unusual and significant nature occurs at site (examples: failure of negative pressure system, rupture of temporary

enclosures), prepare and submit a special report to the designer immediately, listing chain of events, persons participating, response by contractor's personnel, evaluation of results or effects, and similar pertinent information. When such events are known or predictable in advance, advise designer in advance at earliest possible date.

- C. Reporting Accidents: Prepare and submit reports of significant accidents, at site and anywhere else work is in progress. Record and document date and actions; comply with industry standards for reporting accidents. For this purpose, a significant accident is defined to include events where personal injury is sustained, or property loss of substance is sustained, or where the event posed a significant threat of loss or personal injury.

1.07 CONTINGENCY PLAN

- A. Contingency Plan: Prepare a contingency plan for emergencies including fire, accident, power failure, negative pressure system failure, supplied air system failure (if applicable), evacuation of injured persons for both life threatening and non-life threatening, or any other event that may require modification or abridgment of decontamination or work area isolation procedures. Include in plan specific procedures for decontamination or work area isolation. Note that nothing in this specification should impede safe exiting or providing of adequate medical attention in the event of an emergency. Keep these plans in the on-site office.
- B. Post outside/in clean room of Personnel Decontamination Unit:
 - 1. Telephone numbers and locations of emergency services including but not limited to, fire, ambulance, doctor, hospital, police, power company, telephone company and the North Carolina HHCU.
 - 2. A copy of Material Safety Data Sheets (MSDS) for any chemicals used during the asbestos project.
 - 3. The contractor shall post asbestos signs in each appropriate language as per the OSHA 29 CFR 1926.1101 standard.

SECTION 01092

CODES AND REGULATIONS

1.01 REFERENCE SPECIFICATIONS

The contractor shall assume full responsibility and liability for compliance with all applicable federal, state and local regulations pertaining to work practices, hauling, disposal, and protection of workers, visitors to the site, and persons occupying areas adjacent to the site.

Unless modified by these project specifications, all specifications for stripping, removal, repair and disposal work shall conform to the following specifications and standards, as applicable, as if completely reproduced herein.

- A. The following regulations published by the Environmental Protection Agency (EPA):
 - 1. "National Emissions Standards for Hazardous Air Pollutants Asbestos," 40 CFR Part 61, Subpart M.
 - 2. "General Provisions," 40 CFR Part 61, Subpart A.
 - 3. "Guidance for Controlling Asbestos-Containing Materials in Buildings" June 1985. (EPA # 560/5-85-024).
 - 4. "Asbestos-Containing Materials in Schools," 40 CFR Part 763, Subpart E including appendices.

- B. The following regulations published by the U.S. Department of Labor, OSHA:
 - 1. "Occupational Exposure to Asbestos, Tremolite, Anthophyllite, and Actinolite; Final Rules," Title 29, Part 1910, Section 1001 and Part 1926, Section 1101 of the Code of Federal Regulations.
 - 2. "Respiratory Protection," Title 29, Part 1910, Section 134 of the Code of Federal Regulations.
 - 3. Construction Industry, Title 29, Part 1926, of the Code of Federal Regulations.
 - 4. "Access to Employee Exposure and Medical Records," Title 29, Part 1910, Section 20 of the Code of Federal Regulations.
 - 5. "Hazard Communication," Title 29, Part 1926, Section 59 of the Code of Federal Regulations.

6. "Specifications for Accident Prevention Signs and Tags," Title 29, Part 1910, Section 145 of the Code of Federal Regulations.
- C. The following regulations published by North Carolina state agencies:
1. North Carolina Asbestos Hazard Management Program Rules as adopted by 15A NCAC 19C .0600.
 2. "North Carolina Occupational Safety and Health Standards for the Construction Industry," 29 CFR Part 1926 as adopted by T13 NCAC 07F .0201, and shipyard T13:07F.0500.
 3. North Carolina General Statutes, Chapter 95, 97, 130.
- D. The following documents published by the American National Standards Institute:
1. "Fundamentals Governing the Design and Operation of Local Exhaust Systems," Z9.2-1979.
 2. "American National Standard for Respiratory Protection Respiratory Use - Physical Qualifications for Personnel," Z88.6-1984.
 3. "Practices for Respiratory Protection," Z88.2-1992.

1.02 NOTICES

- A. The contractor shall notify the following offices in writing within the time frame specified by the NESHAP regulations prior to beginning any asbestos removal operations.

1. State Agencies

NC Department of Health and Human Services – OEEB
 Division of Public Health
 Health Hazard Control Unit
(Regular Mail)

1912 Mail Service Center
 Raleigh, N.C. 27699-1912
 Phone: (919) 733-0820
 Fax: (919) 733-8493

(UPS, Fed Ex, etc.)
 NCDHHS
 Health Hazard Control Unit
 NCDHHS/Public Health
 Room D-1
 5505 Six Forks Road
 Raleigh, N.C. 27609-3806

N.C. Department of Labor
 Division of Occupational Safety and Health
 319 Chapanoke Road, Suite 105
 Raleigh, N.C. 27603-3432
 Telephone: 1-800-LABOR-NC or (919) 662-4602
 Fax: (919) 662-4625

2. Emergency Departments

Notify the local emergency medical services, police and fire departments in writing of the type and scope of work being performed and request these departments make an inspection prior to beginning the work.

3. Licenses

Maintain current licenses for contractor and accreditation for workers and supervisors as required by applicable State or local jurisdictions for the removal, transporting, disposal or other regulated activity relative to the work of this contract.

4. Contractor is responsible for payment of all permit fees required for this project.

SECTION 01410

AIR MONITORING - INDUSTRIAL HYGIENE FIRM

1.01 GENERAL

- A. The owner shall be responsible for the coordination and contracting of an industrial hygiene firm. Services of the industrial hygiene firm will be paid by the owner.
- B. Air monitoring shall be done under the direct supervision of a North Carolina accredited supervising air monitor (SAM), except for sampling performed by the contractor to satisfy OSHA requirements.
- C. SAM shall be accredited per the Asbestos Hazard Management Program rules.
- D. Air monitor shall be accredited as per the Asbestos Hazard Management Program rules and work under the direct supervision of a SAM.
- E. The SAM representing each firm shall have taken a 24-hour respiratory protection course that is either NIOSH, AIHA or HHCU recognized.
- F. The industrial hygiene firm shall submit copies of their N.C. accreditation's and documentation on respiratory protection training to the designer prior to the award of the contract.
- G. If specific project activities are assigned to an air monitor, the SAM is expected to be in direct control and responsible for industrial hygiene work completed on the project. The SAM shall approve and sign all air monitoring results performed by the air monitor. The SAM signature must be an original. No rubber stamp signature shall be accepted.
- H. Employees of the HHCU shall have right of entry into the project. The HHCU's SAM shall have final authority over the industrial hygiene firm on the project.

1.02 DESCRIPTION OF WORK

- A. The industrial hygiene firm shall offer expertise to the designer and contractor, but is not directly responsible for the performance of the job.
- B. At the job site, the industrial hygiene firm is expected to observe, be aware, and comment on general work site conditions and activities as they relate to the specifications and profession of industrial hygiene, and make recommendations in writing to the designer and contractor.
- C. The industrial hygiene firm is responsible for overseeing the protection of the environment from contamination, protection of persons in adjacent areas, and assurance that the areas are acceptable for occupancy.

- D. The industrial hygiene firm has the authority to direct the contractor relative to safety and environmental concerns. This includes stopping the work if necessary. All directions and comments made by the industrial hygiene firm to the contractor shall be written with a copy to the designer.
- E. The industrial hygiene firm shall furnish the contractor a copy of his field report within 24 hours of the visit. Copies of field notes and reports of observations shall be kept in project log book.
- F. The SAM shall review and make comments to the designer on the submittals listed in Section 01043.
- G. The SAM shall approve any change in contractor's respiratory protection. This includes a review of the historical data.
- H. The industrial hygiene firm is to conform to the contractor's schedule and shall respond to necessary changes, provided an advance notice is given as outlined in Section 01043.
- I. The industrial hygiene firm's project monitor shall furnish designer and contractor with a pager or mobile phone number where he can be reached quickly at all times.
- J. The industrial hygiene firm shall notify the designer and contractor, in writing, of any failed clearance visits.
- K. At the completion of the project, the industrial hygiene firm shall prepare a report describing the assessment of the project, all air monitoring data, acceptance letters, calibration records, and a description of the project as it proceeded to completion and submit four copies of the report to the designer.

1.03 AIR MONITORING

- A. Ambient Air Monitoring: The purpose of ambient air monitoring by the industrial hygiene firm will be to detect discrepancies in the work area isolation such as:
 - 1. Contamination of the building outside of the work area with airborne asbestos fibers.
 - 2. Failure of filtration or rupture in the negative pressure system.
 - 3. Confirm the work practices established by the contractor and respiratory protection provided for employees are adequate.
- B. Work Area Airborne Fiber Levels: The owner's industrial hygiene firm will monitor airborne fiber levels in the work area. The purpose of this air monitoring will be to detect airborne fiber levels which may challenge the ability of the work area isolation procedures to protect the balance of the building or outside of the building from contamination by airborne fibers.

- C. Work Area Clearance: To determine if the elevated airborne fiber levels encountered during abatement operations have been reduced to an acceptable level, the industrial hygiene firm will sample and analyze air per Section 01714.
- D. In accordance with AHMB Program Rules, the SAM shall develop an Abatement Project Monitoring Plan which complies with EPA and OSHA analytical criteria and will provide a valid representation of airborne fiber concentrations both inside and outside the work area. This program is not intended to satisfy the contractor's requirement for sampling under the OSHA regulation. All personnel and area sampling conducted by the industrial hygiene firm shall be personally observed. Air sampling pumps shall not be left unattended for extended periods of time.
1. The SAM shall submit a written project monitoring plan to the designer with a copy to the contractor. The following information shall be required for the submittal.
 - a. The name, address and telephone number of the industrial hygiene firm.
 - b. The name, address, telephone number and NIOSH's PAT designation and proficiency data for the laboratory analyzing the air samples. Analysis of all samples collected shall be by a laboratory currently proficient in NIOSH's "Proficiency Analytical Testing Program for Laboratory Quality Control" for asbestos. The acceptable sampling and analysis method is NIOSH 7400, latest revision.
Persons performing phase contrast microscopy (PCM) analysis at the asbestos removal location shall be proficient in the American Industrial Hygiene Association's Asbestos Analyst Registry Program [AAR].
 - c. A proposed air sampling strategy which shall include: a projected number of air samples, locations, the types of air samples to be collected (personal, area, ambient), how the air samples are to be collected (TWA, ceiling, other), the equipment to be used (pumps, calibration equipment, filters, other), and how the samples will be transported to the laboratory.
 1. All personal air samples will be collected in such a manner as to comply with OSHA collection and analytical regulations and to provide a valid representation of airborne fiber levels. The samples collected by the industrial hygiene firm on personnel do not satisfy the contractor's responsibility under OSHA.
 2. All final area air sampling will comply with all State and Federal requirements in measuring airborne asbestos following an abatement action.

3. Air samples will be analyzed and results made available as per the AHMB Program Rules. Copies of all air sampling results shall be signed by the SAM and a copy posted at the job site. These copies shall include the following: sample number, sample location, activity represented by sample, flow rate, sample time, comments and sample results. A statement will be included on each submission that the requirements of this contract have been met as they apply to the activities of the SAM.
 4. If TWA samples are being collected by the contractor for the purpose of reducing respiratory protection requirements, the industrial hygiene firm shall directly observe the conditions and work practices represented by each sample and make appropriate notes in the bound book on site. The SAM shall review all TWA air sampling results which are used for reducing respiratory protection requirements before accepting the results.
- E. Supplemental air monitoring may be conducted inside and outside the work area by the HHCU. This supplemental sampling does not fulfill air monitoring responsibilities required by OSHA, EPA or this contract.

SECTION 01503
TEMPORARY FACILITIES

1.01 GENERAL

- A. Provide temporary connection to existing building utilities or provide temporary facilities as required herein or as necessary to carry out the work.
- B. Use qualified tradesmen for installation of temporary services and facilities. Locate, modify and extend temporary services and facilities where they will serve the project adequately and result in minimum interference with the performance of the work.
- C. The owner's maintenance personnel shall lock and tag out all electrical and HVAC equipment in the asbestos abatement area. The contractor shall verify that the power and HVAC have been locked and tagged out prior to beginning work.
- D. The owner shall move all furniture, books, computers, records, equipment, etc. prior to the contractor's arrival date as specified.

1.02 WATER SERVICE

If a sufficient amount of water is not available onsite, the asbestos abatement contractor may be required to provide water to be utilized for the duration of the asbestos abatement project

- A. Owner shall supply a source of water. Contractor bears all expense of heating and getting water to the work and decontamination areas.
- B. Supply hot and cold water to the decontamination unit in accordance with Section 01563. Hot water shall be supplied at a minimum temperature of 100 degrees Fahrenheit.
- C. After completion of use, connections and fittings shall be removed without damage or alteration to existing water piping and equipment.

1.03 ELECTRICAL SERVICE

If a sufficient amount of power is not available onsite, asbestos abatement contractor shall provide alternate power source/generators in sufficient capacity to perform asbestos abatement activities for the duration project including air monitoring and clearance activities

- A. General: Comply with applicable NEMA, NEC and UL standards and governing state and local regulations for materials and layout of temporary electric service.

- B. Ground Fault Protection: Provide receptacle outlets equipped with ground fault circuit interrupters, reset button and pilot light, for plug-in connection of power tools and equipment.
- C. Provide a weatherproof, grounded temporary electric power service and distribution system of sufficient size, capacity and power characteristics to accommodate performance of work during the construction period.
- D. Install temporary lighting adequate to provide sufficient illumination for safe work and traffic conditions in every area of work.
- E. Provide services of an electrician, on a standby basis, to service electrical needs during the abatement process.
- F. Provide additional power service and distribution service, consisting of individual dedicated 15 amp 120 volt circuits to electrical drops with receptacle outlets equipped with ground fault interrupt protection, color coded for the exclusive use of the industrial hygiene firm. Provide a minimum of five drops per containment inside work area.

1.04 FIRST AID

- A. A minimum of one first aid kit shall be located in the clean room. Additional first aid kits as the contractor feels is adequate or is required by law shall be located throughout the work area.

1.05 FIRE EXTINGUISHERS

- A. Comply with the applicable recommendations of NFPA Standard 10 - "Standard for Portable Fire Extinguishers." Locate fire extinguishers where they are most convenient and effective for their intended purpose, but provide not less than one extinguisher in each work area equipment room and one in the clean room of the personnel decontamination unit.

1.06 TOILET FACILITIES

- A. Provide temporary toilet facilities to be used by contractor's employees. Location of toilet facilities shall be approved by owner.

1.07 PARKING

- A. Park only in areas designated by the owner.

1.08 BUILDING SECURITY

- A. Maintain personnel on-site at all times any portion of the work areas are open or not properly secured. Secure work areas completely at the end of each day.

1.09 STORAGE

- A. Supply temporary storage required for storage of equipment and materials for duration of project. Trailer and storage dumpsters will be maintained in areas designated by the owner.

SECTION 01513

NEGATIVE PRESSURE SYSTEM

1.01 GENERAL

- A. High efficiency particulate air (HEPA) filter exhaust systems equipped with new HEPA filters for each containment shall be used. Exhaust equipment and systems shall comply with ANSI Z9.2-79 and used according to manufacturer's recommendations.
- B. A system of HEPA-equipped air filtration devices shall be configured so that a pressure differential is established between the work area and the surrounding area (-0.02 to -0.04" water column). A continuous chart-recorded manometer shall be used to confirm this condition.
- C. Additional air filtration devices shall be provided inside the work area for emergency standby as well as for circulation of dead air spaces.
- D. The pressure differential is maintained at all times after preparation is complete and until the final visual inspection and air tests confirm the area is clean and acceptable for occupancy and the designer confirms verbally with written follow-up to discontinue the use of the negative pressure system.
- E. Air shall be exhausted outside the building. Any variations must be approved by the designer. Locations of negative air exhaust shall be approved by owner and designer. Contractor shall install templates (5/8" fire rated plywood) for exhaust of negative air. Contractor is responsible for removal and replacement of windows required for negative air exhaust.
- F. The contractor shall check daily for leaks and log his checks in the bound log book. This includes checks internal to air-moving devices.
- G. There shall be a minimum of four air changes per hour in any containment.

SECTION 01526

WORK AREA PREPARATION

1.01 GENERAL

- A. Before work begins in an area, a decontamination unit must be in operation as outlined in Section 01563.
- B. Completely isolate the work area from other parts of the building so as to prevent contamination beyond the isolated area.
- C. Temporary facilities shall be addressed as outlined in Section 01503.

Full Containment – Original Structure

Ceiling Texture

Sink Mastic

- D. The contractor shall set up a work area, load out, and decontamination area as shown in the plans and specifications. Any variations must be approved by the designer. The decontamination facility outside of the work area shall consist of a change room, shower room and equipment room as described in Section 01563.
- F. **Critical Barriers:** The contractor shall thoroughly seal (2-layers of 6-mil polyethylene sheeting) the work area for the duration of the work by completely sealing off all individual openings and fixtures in the work area, including, but not limited to, heating and ventilation ducts, doorways, corridors, windows, skylights and lighting, with polyethylene sheeting taped securely in place. If the contractor is using sealant materials to fill in small holes or cracks, the material shall have appropriate fire ratings.
- G. The contractor shall wet clean and/or HEPA vacuum all items and equipment in the work area suspected of being contaminated with asbestos, but not in direct contact with the asbestos material and either secure these items in place with polyethylene sheeting or have them removed from the work area.
- H. **Floors:** apply two layers of 6 mil (minimum) polyethylene plastic sheeting with joints overlapped 24 inches and taped securely. Plastic shall be carried up walls a minimum of 12 inches and secured.
- I. **Walls and Ceilings:** (Where Applicable) Contractor shall pre-clean wall and ceilings and any surface sheeting will be adhered to. Apply two layers of 6 mil (minimum) polyethylene plastic sheeting with joints lapped 24 inches and taped securely. Plastic shall be lapped over floor coverings and taped securely.
- J. **Alternate to Walls and Ceilings:** (Only applicable to non-porous materials) Contractor may only install critical barriers however walls, floors and ceilings shall be cleaned during full negative pressure enclosure asbestos abatement

activities. All debris generated from cleaning shall be disposed of as asbestos-containing materials.

- K. Floors and walls shall be installed in such a manner that they may be removed independently of each other and the critical barriers.
- L. Entrances and exits from the work area will have triple barriers of polyethylene plastic sheeting so that the work area is always closed off by one barrier when workers enter or exit.
- M. No water may be left standing on the floor at the end of the work day.
- N. Floor surfaces, walls, finishes or coverings, etc., that in the contractor's opinion will likely be damaged by water or that may become contaminated with asbestos, shall have additional protective preparation as the contractor sees appropriate, at his cost, to protect the original condition of the surfaces.
- O. Any costs associated with physical damage caused by water or securing polyethylene sheeting to areas inside or outside the abatement area shall be the contractor's responsibility.
- P. The contractor shall establish and mark emergency and fire exits from the work area. Emergency procedures shall have priority over established decontamination entry and exit procedures. Audible and visible fire and emergency evacuation alarms shall be installed so as to be heard and seen throughout the entire work area.
- Q. Integrity of these seals shall be regularly checked and maintained by the contractor.
- R. After work area preparation, the contractor shall notify the designer verbally with written follow-up that he is ready for a prework inspection.

SECTION 01560

WORKER PROTECTION

1.01 GENERAL

- A. Provide worker protection as required by OSHA, state and local standards applicable to the work. Contractor is solely responsible for enforcing worker protection requirements at least equal to those specified in this Section.
- B. Each time the work area is entered the contractor shall require all persons to remove all street clothes in the changing room of the personnel decontamination unit and put on new disposable coverall, new head cover, and a clean respirator. Proceed through shower room to equipment room and put on work boots.
- C. Workers shall not eat, drink, smoke, chew gum or chew tobacco in the work area, the equipment room, the load out area, or the clean room.

1.02 WORKER TRAINING

- A. Train all workers in accordance with 29 CFR 1926 and North Carolina state regulations regarding the dangers inherent in handling asbestos, breathing asbestos dust, proper work procedures and personal and area protective measures.

1.03 MEDICAL EXAMINATIONS

- A. Provide medical examinations for all workers. Examination shall as a minimum meet OSHA requirements as set forth in 29 CFR 1926 and N.C. Workmen's Compensation Act Dusty Trades Examination Record (DEHNR Form 2796).

1.04 PROTECTIVE CLOTHING

- A. Provide disposable full-body coveralls and disposable head covers, and require that they be worn by all workers in the work area. Provide a sufficient number for all required changes, for all workers in the work area.
- B. Boots: Provide work boots with non-skid soles and, where required by OSHA, foot protection for all workers.
- C. Gloves: Provide work gloves to all workers and require that they be worn at the appropriate times. Do not remove gloves from work area. Dispose of work gloves as asbestos-contaminated waste at the completion of the project.

1.05 ADDITIONAL PROTECTIVE EQUIPMENT

- A. Type C respirators, disposable coveralls, head covers and footwear covers shall be provided by the contractor for the owner, the designer, Industrial hygiene firm and other authorized representatives who may inspect the job site.

1.06 DECONTAMINATION PROCEDURES

- A. Require that all workers use the following decontamination procedure as a minimum requirement whenever leaving the work area:
 - 1. Remove disposable coveralls, disposable head covers, and disposable footwear covers or boots in the equipment room.
 - 2. Still wearing respirators, proceed to showers. Showering is mandatory. Care must be taken to follow reasonable procedures in removing the respirator to avoid asbestos fibers while showering. The following procedure is required as a minimum:
 - a. Thoroughly wet body including hair and face.
 - b. With respirator still in place thoroughly wash body, hair, respirator face piece, and all exterior parts of the respirator.
 - c. Take a deep breath, hold it and/or exhale slowly, completely wet hair, face and respirator. While still holding breath, remove respirator and hold it away from face before starting to breathe.
 - d. Carefully wash face piece of respirator inside and out.
 - e. Shower completely with soap and water; rinse thoroughly.
 - f. Rinse shower room walls and floor prior to exit.
 - g. Proceed from shower to changing (clean) room and change into street clothes or new disposable work items.
 - 3. After showering, each employee shall inspect, clean and repair his respirator as needed. The respirator shall be dried, placed in a suitable storage bag and properly stored.

SECTION 01562

RESPIRATORY PROTECTION

1.01 DESCRIPTION OF WORK

- A. Instruct and train each worker involved in asbestos abatement in proper respirator use and require that each worker always wear a respirator, properly fitted on the face, in the work area from the start of any operation which may cause airborne asbestos fibers until the work area is completely decontaminated. Use respiratory protection appropriate for the fiber level encountered in the workplace or as required for other toxic or oxygen-deficient situations encountered.

1.02 GENERAL

- A. Provide workers with personally issued and marked respiratory equipment approved by NIOSH and MSHA and suitable for the asbestos exposure level in the work areas according to OSHA Standard 29 CFR 1926.1101 and other possible contaminants employees might be exposed to during the project.
- B. Provide respiratory protection from the time the first operation involved in the project requires contact with asbestos-containing materials (including construction of decontamination units, construction of airtight barriers/barricades, and placing of plastic sheeting on walls) until acceptance of final air clearance test results by the industrial hygiene firm.
- C. The minimum respiratory protection for the project during gross removal of friable materials shall be a full-face powered air purifying respirator. The minimum respiratory protection for the project is a half-face negative pressure respirator.
- D. The designer may, under certain circumstances, allow the contractor to downgrade respiratory protection during the final cleaning phase. However, the eight-hour TWA air sampling data must document the exposure level, and the SAM must write a letter to the designer allowing the contractor to reduce respiratory protection.
- E. Respirator fit testing shall be performed as a minimum at the beginning of the project, at any change in respiratory protection equipment, and at any time during the project if requested by the employee or SAM. Fit testing is to be performed by one of the methods listed in the 29 CFR 1926.1101, Appendix C.
- F. If supplied air respirators are used, the contractor shall provide a minimum of Grade "D" breathing air as set forth in the Compressed Gas Association's "Commodity Specifications for Air," G-7.1. The contractor shall test for Grade "D" breathing air initially and daily thereafter. Daily testing is not needed if the contractor has an air purification system which has CO and organic purging capabilities as well as a continuous CO monitor and alarm calibrated at 10 ppm. The system must be calibrated at least once a week or when it is moved.

- G. Provide emergency backup air supply, egress SCBA or egress HEPA filters for each worker in work area at all times when Type-C (supplied air) respirators are required. Breathing air system shall provide one hour of reserve air, calculated for maximum crew size for emergency evacuation.
- H. Where Type C respirators are utilized, the contractor is required to have an employee in the vicinity of the source of air. The contractor shall take into account the location of the fresh air intake to ensure no pollutant source is in the vicinity. The audible alarm shall be located where the employees inside and outside containment can hear the alarm.
- I. Do not allow the use of single-use, disposable or quarter-face respirators for any purpose.
- J. The contractor may submit a new exposure assessment (as per 29 CFR 1926.1101) to the SAM with a request to downgrade to less protective respirators. The SAM will make a recommendation to the designer, who will issue a decision in writing to the contractor approving or denying his request. If the contractor disagrees with the decision, then the representative air sampling data may be reviewed by the HHCU for a final decision.

SECTION 01563

DECONTAMINATION UNITS

1.01 DESCRIPTION OF WORK

- A. Provide separate personnel and equipment/loadout decontamination facilities. Require that the personnel decontamination unit be the only means of ingress and egress for the work area. Require that all materials exit the work area through the equipment/loadout decontamination unit. Contractor shall comply with 29 CFR 1926.1101, specifically paragraph (j) Hygiene facilities and practices for employees.

1.02 GENERAL

Provide separate personnel decontamination units and equipment/loadout decontamination units when practical. When personnel decontamination units and equipment / loadout decontamination units are located outside the building, the decontamination units shall be constructed inside a plywood shell. The plywood shell shall be constructed of UL-labeled, fire-treated lumber and plywood. 5/8" non-com ptd. MDO plywood on 3-5/8" non-com studs.

- A. Personnel Decontamination Unit
 - 1. Provide a Personnel Decontamination Unit consisting of a serial arrangement of connected rooms or spaces, changing room, shower room, equipment room. Each shall be separated by a minimum of three curtain doorways. Require all persons without exception to pass through this decontamination unit for entry into and exiting from the work area for any purpose. Do not allow parallel routes for entry or exit. Do not remove equipment or materials through Personnel Decontamination Unit.
 - 2. Provide temporary lighting within decontamination units as necessary to reach an adequate lighting level.
 - 3. Maintain floor of changing room dry and clean at all times. Do not allow the overflow water from the shower to escape the shower room.
 - 4. Damp wipe all surfaces twice after each shift change with a disinfectant solution.
 - 5. Provide hot and cold water, drainage and standard fixtures including an elevated shower head as necessary for a complete and operable shower. A water hose and bucket is not an acceptable shower.
 - 6. Arrange water shut off and drain pump operation controls so that a single individual can shower without assistance from either inside or outside of the work area.

7. Pump shower waste water to drain. Provide 20 micron and 5 micron waste water filters in line to drain. Change filters daily or more often if necessary.
8. If the decontamination area is located within an area containing friable asbestos on overhead ceilings, ducts, piping, etc., provide the area with a minimum 5/8 inch plywood "ceiling" with two layers of polyethylene sheeting covering the top of the "ceiling."
9. Visual Barrier: Where the decontamination area is immediately adjacent to and within view of occupied areas or the exterior of the building, provide a visual barrier of opaque plastic sheeting so that worker privacy is maintained and work procedures are not visible to building occupants. Where the area adjacent to the decontamination area is accessible to the public, construct a solid barrier on the public side of the sheeting to protect the sheeting. Construct barrier with wood or metal studs, max. 16 inches on center, covered with minimum 5/8 inch fire treated plywood.
10. Exterior decontamination units shall be constructed in a manner which accommodates the entrance to be locked at the end of shifts or when contractor is not on-site.

B. Equipment Decontamination Units:

1. Provide an equipment decontamination unit consisting of a serial arrangement of rooms, clean room, holding area, and washroom, each room separated by a minimum of three curtain doorways, for removal of equipment and material from work area. Do not allow personnel to enter or exit work area through equipment decontamination unit.
2. Washroom: Provide washroom for cleaning of bagged or drummed asbestos-containing waste materials passed from the work area.
3. Holding Area: Provide holding area as a drop location for sealed drums and bagged asbestos-containing materials passed from the washroom.
4. Clean Room: Provide clean room to isolate the holding area from the building exterior or occupied areas.
5. Equipment or Material: Obtain all equipment or material from the work area through the equipment decontamination unit according to the following procedure:
 - a. When passing contaminated equipment, sealed plastic bags, drums or containers into the washroom, close all doorways of the equipment decontamination unit, other than the doorway between the work area and the washroom. Keep all outside personnel clear of the equipment decontamination unit.

- b. Once inside the washroom, wet-clean the bags and/or equipment.
 - c. When cleaning is complete, insert bagged material into a clean bag/drum during the pass between the washroom and holding area. Close all doorways except the doorway between the washroom and holding area.
 - d. Workers from the building exterior enter the clean room then the holding area to remove decontaminated equipment and/or containers for disposal. Require these workers to wear full protective clothing and respiratory protection as described in Section 01562.
- C. Use of Elevator:
- 1. **Use of elevators will not be permitted during this project.**
- D. Decontamination Unit Contamination:
- 1. If the air quality in the decontamination unit exceeds 0.01 fibers per cc analyzed by PCM or 70 structures per mm squared analyzed by TEM or its integrity is diminished through use as determined by the designer or industrial hygiene firm, no employee shall use the unit until corrective steps are taken and approved by the designer and industrial hygiene firm.

SECTION 01711

PROJECT DECONTAMINATION

1.01 GENERAL

- A. Carry out a first cleaning of all surfaces of the work area including plastic sheeting, tools, scaffolding and/or staging by use of damp-cleaning and mopping and/or a high efficiency particulate air (HEPA) filter vacuum until there is no visible debris from removed materials or residue on plastic sheeting or other surfaces. Do not perform dry-dusting or dry-sweeping.
- B. Equipment shall be cleaned and all contaminated materials removed before removing polyethylene from the walls and floors.
- C. The contractor shall replace all prefilters and clean the inside and outside of the HEPA exhaust units.
- D. After polyethylene sheets have been removed from walls and floors, but are still remaining on all windows, doors and the critical components, the contractor shall clean all surfaces in the work area, including ducts, electrical conduits, steel beams, roof deck, etc., with amended water and/or HEPA-filtered vacuum.
- E. After cleaning the work area, the contractor shall allow the area to thoroughly dry and then wet-clean and/or HEPA vacuum all surfaces in work area again.
- F. At the completion of the cleaning operation, the contractor's supervisor shall perform a complete visual inspection of the work area to ensure that the work area is dust- and fiber-free. If the supervisor believes he is ready for a final project decontamination inspection, he shall notify the designer.
- G. The designer shall contact the industrial hygiene firm and advise the firm of the final project decontamination inspection requested by the contractor. Work area clearance is described in section 01714.
- H. Final project decontamination inspection includes the visual inspection and air monitoring clearance.
- I. Visual inspection for acceptance shall be performed after all areas are dry.
- J. The industrial hygiene firm shall perform the final visual inspection and conduct the final air clearance. Any discrepancies found shall be documented in the form of a punch list.
- K. Final air sampling shall not commence until the visual inspection is completed and passed.
- L. If the industrial hygiene firm or the designer finds that the work area has not been adequately decontaminated, cleaning and/or air monitoring shall be repeated at

the contractor's expense, including additional industrial hygiene fees, until the work area is in compliance.

- M. After the work area is found to be in compliance, all entrances and exits shall be unsealed and the plastic sheeting, tape and any other trash and debris shall be disposed of in sealable plastic bags (6 mil minimum) and disposed of as outlined in Section 02084.
- N. Contractor shall remove all polyethylene sheeting , tape, and any trash or debris after hours or on weekends.
- O. All HEPA unit intakes and exhausts shall be wrapped with six mil polyethylene before leaving the work area.
- P. After the industrial hygiene firm has approved the final project decontamination and the contractor has completed the tear down for occupancy by others, the designer shall perform the project final inspection as outlined in the general conditions.
- Q. Any residual asbestos that may be present after removing critical barriers, that in the designer's judgment should have been cleaned during the precleaning phase prior to installing critical barriers, shall be cleaned and cleared at the contractor's expense.
- R. There shall be appropriate seals totally enclosing the inspection area to keep it separate from clean areas or other areas where abatement is or will be in progress. Once an area has been accepted and passed air tests, loss of the critical barrier integrity or escape of asbestos into an already clean area shall void previous acceptance and tests. Additional visual and final air clearance sampling shall be required at the contractor's expense.

SECTION 01714

WORK AREA CLEARANCE

1.01 GENERAL

- A. Notification and scheduling of the final inspection during the project is the responsibility of the contractor.

1.02 FINAL CLEARANCE TESTING

- A. After the second cleaning operation and after the area is completely dry, the following procedure test shall be performed:
1. A final visual inspection shall be conducted by the industrial hygiene firm. The inspection shall be conducted following the guidelines set forth in the American Society for Testing and Materials, Standard Practices for Visual Inspection of Asbestos Abatement Projects, Designation: E1368.90. If the work area is found visibly clean, air samples will be collected by the industrial hygiene firm.
 2. During the air testing, the accredited air monitor shall cause disruptive air currents as described in the EPA-AHERA regulations (40 CFR Part 763, Subpart E, Appendix A).
 3. Clearance samples analyzed by Phase Contrast Microscopy (PCM) (minimum of five samples using NIOSH 7400 Method). The maximum flow rate shall be 12 liters per minute, with a minimum sample size of 2000 liters for each sample. Clearance Criteria shall be less than 0.01 f/cc for all samples.
 4. Clearance samples analyzed by Transmission Electron Microscopy (TEM), using the Mandatory Transmission Electron Microscopy Method described in 40 CFR Part 763, Subpart E, Appendix F. Clearance criteria shall be an arithmetic mean less than or equal to 70 structures per square millimeter or a z-test less than or equal to 1.65. Clearance sample turn around shall be 24 hours after TEM samples are collected.

Work Area

Full Negative Pressure Enclosures

Clearance Criteria

PCM

5. The industrial hygiene firm shall immediately report the final air sampling clearance results to the designer.
6. The use of the negative pressure system may be discontinued after the industrial hygiene firm instructs the contractor that he has passed the final project decontamination inspection.

SECTION 02080

ASBESTOS REMOVAL

1.01 GENERAL

- A. Prior to starting asbestos removal, the contractor's equipment, work area and decontamination units will be inspected and approved by the designer.
- B. All loose asbestos material removed in the work area shall be adequately wet, bagged, sealed and labeled properly before personnel breaks or end of shift.
- C. All plastic sheeting, tape, cleaning material, clothing and all other disposable material or items used in the work area shall be packed into sealable plastic bags (6 mil minimum) and treated as contaminated material.
- D. All material shall be double-bagged.
- E. All excess water (except shower water) shall be combined with removed material or other absorptive material and properly disposed of as per EPA regulations. Contractor shall not place water in storm drains, onto lawns, or into ditches, creeks, streams, rivers or oceans.

1.02. SCOPE OF WORK

- A. Scope of work for this project includes the removal of asbestos-containing materials utilizing a full negative pressure enclosure.

**Note: Drywall and joint compound contains less than <1% chrysotile asbestos. Drywall and joint compound will be removed during the demolition phase of this project.

Full Negative Pressure Enclosure

Ceiling Texture - Throughout

Sink Mastic – Kitchen and Classroom

1.03 ACM PRODUCTS TO BE REMOVED

- A. Full Negative Pressure Enclosure
 - 1. Spray asbestos-containing materials with a fine mist of amended water prior to removal procedures. Do not over saturate to cause excess pooling. Mist asbestos-containing materials continuously during the removal process.
 - 2. Contractor shall carefully hand scrape/cut and remove manageable sections of asbestos-containing materials and place it directly into bags for disposal. Do not allow asbestos debris to accumulate on floor.

3. Contractor shall continue misting asbestos-containing materials with amended water throughout the removal process.
5. Clean work area as required by section 01711.

Structural Demolition with Drywall and Joint Compound (<1% Chrysotile Asbestos)

1. Structural demolition activities shall not start until successful completion of the PCM air clearance in the facility.
2. Demolition contractor shall retain, at a minimum, OSHA Class III asbestos trained personnel to operate the water hose during demolition activities. It is the responsibility of the OSHA Class III trained individuals to maintain drywall and joint compound adequately wet during demolition activities.

SECTION 02084

DISPOSAL OF ASBESTOS-CONTAINING WASTE MATERIAL

1.01 GENERAL

- A. All asbestos materials and miscellaneous asbestos contaminated debris shall be properly sealed and protected, and the loadout vehicle/dumpster shall be locked, while located on the facility site and then transported to a predesignated disposal site in accordance with 40 CFR 61.150 and DOT 49 CFR Parts 100-399.
- B. An enclosed vehicle will be used to haul waste material to the disposal site. No rental vehicles or trailers shall be used. Vehicle selection, vehicle covers and work practices shall assure that no asbestos becomes airborne during the loading, transport and unloading activity, and that material is placed in the waste site without breaking any seals.
- C. Waste disposal polyethylene bags (6 mil) and containers, non-porous (steel/plastic) drums or equivalent, with labels, appropriate for storing asbestos waste during transportation to the disposal site shall be used. In addition to the OSHA labeling requirements, all containers shall be labeled with the name of the waste generator and the location at which the waste was generated.
- D. The contractor shall transport the containers and bags of waste material to the approved waste disposal site. The sealed plastic bags shall be placed into the burial site unless the bags have been broken or damaged. Upon the landfill's approval damaged bags shall be left in the non-porous containers and the entire contaminated package shall be buried. Uncontaminated containers may be reused.
- E. Workers loading and unloading the asbestos will wear respirators and disposable clothing when handling material. Asbestos warning signs shall be posted during loading and unloading of asbestos waste.
- F. The contractor shall use the HHCU's Waste Shipment Record for disposal records as per 40 CFR 61.150 and distribute a copy of all waste shipment records to the designer and the HHCU after the completion of the project.

APPENDIX A

PREWORK ASBESTOS INSPECTION CHECKLIST

Name of State Facility: _____

Project Name: _____

Project ID Number: _____

Date of Inspection: _____ Pass: _____ Fail: _____

A.	DOCUMENTS	YES	NO
	1) Asbestos Removal Permit/NESHAP Notification	_____	_____
	2) Accreditation Documents for Workers & Supervisors	_____	_____
	3) Asbestos Plans and Specifications	_____	_____
	4) Air Monitoring Data	_____	_____
	5) Waste Shipment Records	_____	_____
	6) Sign-in Sheets and Bound Book for Comments	_____	_____
	7) Calibration Record for Grade "D" Air	_____	_____
	8) Items listed in Section 01043 of Specification	_____	_____
B.	PPE SUPPLIES		
	1) Tyvek Clothing	_____	_____
	2) Rubber Boots	_____	_____
	3) Respirators with HEPA Filters	_____	_____
C.	CLEAN ROOM		
	1) Entry Curtains	_____	_____
	2) Emergency Phone Numbers Posted	_____	_____
	3) First Aid Kit	_____	_____
	4) Asbestos Signs	_____	_____
	5) Decontamination Procedures Posted	_____	_____
	6) Fire Extinguisher	_____	_____
D.	SHOWER ROOM		
	1) Polyethylene Curtains	_____	_____
	2) Hot/Cold Water & Operational	_____	_____
	3) Soap & Towels	_____	_____
	4) Waste Water Filter Pump Operational	_____	_____
	5) Extra Five Micron Size Filters	_____	_____
	6) Filtered Waste Water to Sanitary Sewer	_____	_____

E. WORK AREA	YES	NO
1) Removable Items Out of Area	_____	_____
2) Non-removable Items Protected	_____	_____
3) Critical Barriers Installed	_____	_____
4) Polyethylene Curtains	_____	_____
5) Polyethylene on Walls/Floors as Specified	_____	_____
6) HVAC off	_____	_____
7) Air Filtration Devices in Place and Operational	_____	_____
8) Air Exhausted to Outside	_____	_____
9) Electricity Locked and Tagged Out	_____	_____
10) Temporary Power Installed with GFCI	_____	_____
11) Fire Extinguishers	_____	_____
12) Emergency and Fire Exits Marked	_____	_____
13) Audible Alarms Operational	_____	_____
14) Toilet Available	_____	_____

F. EQUIPMENT		
1) Safety Equipment	_____	_____
2) HEPA Vacuums	_____	_____
3) Waste Disposal Bags	_____	_____
4) Airless Sprayer with Water Source	_____	_____
5) Cleaning Equipment	_____	_____
6) Glove Bags	_____	_____
7) Emergency Power Generator (if required)	_____	_____
8) Temporary Lighting	_____	_____


G. OTHER		
1) _____	_____	_____
2) _____	_____	_____
3) _____	_____	_____
4) _____	_____	_____

Asbestos Design Consultant

Date

Asbestos Contractor's Representative

Date





MATRIX

Health & Safety Consultants, L.L.C.

September 10, 2024

North Carolina State University
Design and Construction
Facilities Division
2701 Sullivan Drive
Raleigh, North Carolina 27607

Attention: Ms. Melissa Diamond

Subject: Report of Survey to Identify
Asbestos-Containing Materials
Apiculture Building
4325 Inwood Road
Raleigh, North Carolina 27603
Matrix Job No.: 2408127

Dear Ms. Diamond:

Matrix Health and Safety Consultants, L.L.C. (Matrix) is pleased to present this report of the survey to identify asbestos-containing materials in the Apiculture Building located at 4325 Inwood Road in Raleigh, North Carolina. This report presents known project information, survey procedures, survey results and recommended response actions.

PROJECT INFORMATION

Matrix understands that the facility is scheduled for demolition in the near future. In order to facilitate demolition activities, Matrix performed a survey to identify asbestos-containing materials which are required to be removed prior to renovation or demolition activities in accordance with the Environmental Protection Agency (EPA) National Emissions Standards for Hazardous Air Pollutants (NESHAP).

SURVEY PROCEDURES

The survey was performed on August 30, 2024 by Matrix Inspector Todd E. Daugherty (North Carolina Asbestos Inspector No. 11650). The survey began with a walk-through of the subject area observing accessible areas for the presence of suspect asbestos-containing materials (ACM). Both friable and non-friable suspect asbestos-containing materials were considered during the course of the survey. Friable materials are those materials which can be pulverized or reduced to powder by hand pressure. A sampling strategy was determined and bulk samples of suspect ACM were obtained. Suspect ACM's were grouped based on material homogeneity. A homogeneous area is an area which contains materials that seem by texture, color and wear to be uniform and applied during the same general time period.

To determine the presence or absence of asbestos content in the suspect materials, samples were collected and transported to Eurofins CEI in Cary, North Carolina under chain-of-custody documentation for laboratory analysis. The collected samples were placed into individual sample containers, sealed and a unique identification number was assigned to the sample container at the time of collection. The identification included the sample collection date and location.

ANALYSIS PROCEDURES

The collected asbestos samples were analyzed using Polarized Light Microscopy (PLM) in conjunction with dispersion staining techniques using EPA Method 600/R-93/116. The bulk laboratory analysis provided the asbestos content (positive or negative), percentage of asbestos, asbestos type and identification of other non-asbestos fibers. The results of the laboratory analysis are presented in the attached Asbestos Bulk Sampling Record.

ASBESTOS SURVEY RESULTS

NCSU – Apiculture Building

ASBESTOS-CONTAINING MATERIAL	PERCENT ASBESTOS TYPE OF ASBESTOS	LOCATION
Spray-Applied Ceiling Texture	<1% - 2% Chrysotile	Throughout
White Sink Mastic	5% Chrysotile	Kitchen and Classroom
Drywall and Joint Compound	Joint Compound: 2% Chrysotile Drywall: NAD Composite: <1% Chrysotile	Throughout

ASBESTOS RECOMMENDATIONS

The National Emissions Standard for Hazardous Air Pollutants (NESHAP) requires the removal of asbestos-containing materials likely to be disturbed prior to renovation or demolition activities. Matrix recommends removal of the asbestos-containing materials identified in this report prior to beginning renovation or demolition activities which would disturb their integrity. Matrix recommends that asbestos removal be performed by a qualified asbestos abatement contractor, using North Carolina accredited personnel, in accordance with applicable federal, state, and local regulations governing the removal of asbestos-containing materials.

Current EPA regulations do not regulate the removal of building materials with trace amounts (<1%) of asbestos. However, OSHA regards materials with any amount of asbestos to be a potential exposure hazard if the material is disturbed. Therefore, work practices specified in the OSHA Standard (CFR 29 1962.1101) must be followed if the materials are disturbed, removed or demolished. Proper training and personal protection measures are also required as specified in the OSHA Standards

QUALIFICATIONS

This report summarizes Matrix’s evaluation of the conditions observed at the subject facility during the course of the facility survey. Our findings are based upon our observations at the facility and analyses of the samples obtained at the time of this survey. Additional asbestos-containing materials may exist (undetected) in other portions of the facility due to inaccessibility or due to an undetectable change in materials. These surveys were limited to those materials likely to be disturbed during the scheduled renovations. Any conditions discovered which deviate from the data contained in this report should be presented to us for our evaluation.

Matrix appreciates the opportunity to have provided these services. We would be glad to discuss any of the results contained in this report, at your convenience. If there are any questions concerning this report or results, please contact us.

Sincerely,

MATRIX HEALTH AND SAFETY CONSULTANTS, L.L.C.



Todd E. Daugherty
 Project Principal
 North Carolina Asbestos Inspector No. 11650

Attachments: Asbestos Bulk Sampling Record
 Laboratory Report

ASBESTOS BULK SAMPLING RECORD
North Carolina State University
Apiculture Building

SAMPLE FIELD ID NO.	SAMPLE LOCATION	TYPE OF MATERIAL	TYPE OF ASBESTOS	PERCENTAGE
AP-01	Exterior	Door Caulk	NAD	
AP-02	Exterior	Door Caulk	NAD	
AP-03	Roof	Roof Shingle	NAD	
AP-04	Roof	Roof Shingle	NAD	
AP-05	Roof	Roof Felt	NAD	
AP-06	Roof	Roof Felt	NAD	
AP-07	Exterior	Window Caulk	NAD	
AP-08	Exterior	Window Caulk	NAD	
AP-09	Exterior	Mastic on HVAC Duct	NAD	
AP-10	Exterior	Mastic on HVAC Duct	NAD	
AP-11	2-Story Section	Spray-Applied Ceiling Texture	Chrysotile	<1%
AP-12	2-Story Section	Spray-Applied Ceiling Texture	Chrysotile	<1%
AP-13	2-Story Section	Spray-Applied Ceiling Texture	Chrysotile	<1%
AP-14	2- Story Section	Drywall and Joint Compound	Chrysotile	Joint Compound: 2% Drywall: NAD Composite: <1%
AP-15	2-Story Section	Drywall and Joint Compound	Chrysotile	Joint Compound: 2% Drywall: NAD Composite: <1%
AP-16	2-Story Section	Drywall and Joint Compound	Chrysotile	Joint Compound: 2% Drywall: NAD Composite: <1%
AP-17	Kitchen	White Sink Mastic	Chrysotile	5%
AP-18	Classroom	White Sink Mastic	Chrysotile	5%
AP-19	Kitchen	Wood Floor Glue	NAD	
AP-20	Living Room	Wood Floor Glue	NAD	
AP-21	One Story Sections	Spray-Applied Ceiling Texture	Chrysotile	2%
AP-22	One Story Sections	Spray-Applied Ceiling Texture	Chrysotile	2%
AP-23	One Story Sections	Spray-Applied Ceiling Texture	Chrysotile	2%
AP-24	One Story Sections	Drywall and Joint Compound	Chrysotile	Joint Compound: 2% Drywall: NAD Composite: <1%
AP-25	One Story Sections	Drywall and Joint Compound	Chrysotile	Joint Compound: 2% Drywall: NAD Composite: <1%
AP-26	One Story Sections	Drywall and Joint Compound	Chrysotile	Joint Compound: 2% Drywall: NAD Composite: <1%
AP-27	Basement	Cinder Block Filler	NAD	
AP-28	Basement	Cinder Block Filler	NAD	
AP-29	Basement	1' x 1' Ceiling Tile	NAD	
AP-30	Basement	1' x 1' Ceiling Tile	NAD	
AP-31	Attic	Attic Insulation	NAD	
AP-32	Attic	Attic Insulation	NAD	

NAD = No Asbestos Detected

Analysis Method: PLM with Dispersion Staining



CEI

Asbestos Report Summary

By: POLARIZING LIGHT MICROSCOPY

PROJECT: NCSU Apiculture Building

LAB CODE: B2416837

METHOD: EPA 600 / R-93 / 116 and EPA 40 CFR Appendix E to Subpart E of Part 763

Client ID	Layer	Lab ID	Color	Sample Description	ASBESTOS %
AP-01		B2416837.01	White	Door Caulk	None Detected
AP-02		B2416837.02	White	Door Caulk	None Detected
AP-03		B2416837.03	Black	Roof Shingle	None Detected
AP-04	Layer 1	B2416837.04	Black	Roof Shingle	None Detected
	Layer 2	B2416837.04	Black	Roof Shingle	None Detected
AP-05		B2416837.05	Black	Roof Felt	None Detected
AP-06		B2416837.06	Black	Roof Felt	None Detected
AP-07		B2416837.07	White	Window Caulking	None Detected
AP-08		B2416837.08	White	Window Caulking	None Detected
AP-09		B2416837.09	White	Mastic	None Detected
AP-10		B2416837.10	White	Mastic	None Detected
AP-11		B2416837.11	White	Ceiling Texture	Chrysotile <1%
AP-12		B2416837.12	White	Ceiling Texture	Chrysotile <1%
AP-13		B2416837.13	White	Ceiling Texture	Chrysotile <1%
AP-14	Layer 1	B2416837.14	White	Joint Compound	Chrysotile 2%
	Layer 2	B2416837.14	White,Brown	Drywall	None Detected
	Layer 3	B2416837.14	White,Brown	Drywall/Joint Compound (Composite)	Chrysotile <1%
AP-15	Layer 1	B2416837.15	White	Joint Compound	Chrysotile 2%
	Layer 2	B2416837.15	White,Brown	Drywall	None Detected
	Layer 3	B2416837.15	White,Brown	Drywall/Joint Compound (Composite)	Chrysotile <1%
AP-16	Layer 1	B2416837.16	White	Joint Compound	Chrysotile 2%
	Layer 2	B2416837.16	White,Brown	Drywall	None Detected
	Layer 3	B2416837.16	White,Brown	Drywall/Joint Compound (Composite)	Chrysotile <1%
AP-17		B2416837.17	White	Sink Mastic	Chrysotile 5%
AP-18		B2416837.18	White	Sink Mastic	Chrysotile 5%
AP-19		B2416837.19	Yellow	Floor Glue	None Detected
AP-20		B2416837.20	Yellow	Floor Glue	None Detected
AP-21		B2416837.21	White,Tan	Ceiling Texture	Chrysotile 2%
AP-22		B2416837.22	White,Tan	Ceiling Texture	Chrysotile 2%



CEI

Asbestos Report Summary

By: POLARIZING LIGHT MICROSCOPY

PROJECT: NCSU Apiculture Building

LAB CODE: B2416837

METHOD: EPA 600 / R-93 / 116 and EPA 40 CFR Appendix E to Subpart E of Part 763

Client ID	Layer	Lab ID	Color	Sample Description	ASBESTOS %
AP-23		B2416837.23	White, Tan	Ceiling Texture	Chrysotile 2%
AP-24	Layer 1	B2416837.24	White	Joint Compound	Chrysotile 2%
	Layer 2	B2416837.24	White, Brown	Drywall	None Detected
	Layer 3	B2416837.24	White, Brown	Drywall/Joint Compound (Composite)	Chrysotile <1%
AP-25	Layer 1	B2416837.25	White	Joint Compound	Chrysotile 2%
	Layer 2	B2416837.25	White, Brown	Drywall	None Detected
	Layer 3	B2416837.25	White, Brown	Drywall/Joint Compound (Composite)	Chrysotile <1%
AP-26	Layer 1	B2416837.26	White	Joint Compound	Chrysotile 2%
	Layer 2	B2416837.26	White, Brown	Drywall	None Detected
	Layer 3	B2416837.26	White, Brown	Drywall/Joint Compound (Composite)	Chrysotile <1%
AP-27		B2416837.27	Light Blue, White	Cb Filler	None Detected
AP-28		B2416837.28	Light Blue, White	Cb Filler	None Detected
AP-29		B2416837.29	Brown	1x1 Ceiling Tile	None Detected
AP-30		B2416837.30	Brown	1x1 Ceiling Tile	None Detected
AP-31		B2416837.31	Yellow	Insulation	None Detected
AP-32		B2416837.32	Yellow	Insulation	None Detected

ASBESTOS BULK ANALYSIS

By: POLARIZING LIGHT MICROSCOPY

Client: Matrix Health & Safety Consultants
 2900 Yonkers Road
 Raleigh, NC 27604

Lab Code: B2416837
Date Received: 08-30-24
Date Analyzed: 09-03-24
Date Reported: 09-03-24

Project: NCSU Apiculture Building

ASBESTOS BULK PLM, EPA 600/R-93/116 METHOD and EPA 40 CFR Appendix E Subpart E to Part 763

Client ID Lab ID	Lab Description	Lab Attributes	NON-ASBESTOS COMPONENTS				ASBESTOS %
			Fibrous		Non-Fibrous		
AP-01 B2416837.01	Door Caulk	Homogeneous White Non-fibrous Bound	100%	Caulk	None Detected		
			<1%	Silicates			
AP-02 B2416837.02	Door Caulk	Homogeneous White Non-fibrous Bound	100%	Caulk	None Detected		
			<1%	Silicates			
AP-03 B2416837.03	Roof Shingle	Heterogeneous Black Non-fibrous Bound	50%	Fiberglass	40%	Tar	None Detected
					10%	Gravel	
AP-04 Layer 1 B2416837.04	Roof Shingle	Heterogeneous Black Non-fibrous Bound	50%	Fiberglass	40%	Tar	None Detected
					10%	Gravel	
Layer 2 B2416837.04	Roof Shingle	Heterogeneous Black Non-fibrous Bound	50%	Fiberglass	40%	Tar	None Detected
					10%	Gravel	
AP-05 B2416837.05	Roof Felt	Heterogeneous Black Fibrous Bound	70%	Cellulose	30%	Tar	None Detected
AP-06 B2416837.06	Roof Felt	Heterogeneous Black Fibrous Bound	70%	Cellulose	30%	Tar	None Detected

ASBESTOS BULK ANALYSIS

By: POLARIZING LIGHT MICROSCOPY

Client: Matrix Health & Safety Consultants
 2900 Yonkers Road
 Raleigh, NC 27604

Lab Code: B2416837
Date Received: 08-30-24
Date Analyzed: 09-03-24
Date Reported: 09-03-24

Project: NCSU Apiculture Building

ASBESTOS BULK PLM, EPA 600/R-93/116 METHOD and EPA 40 CFR Appendix E Subpart E to Part 763

Client ID Lab ID	Lab Description	Lab Attributes	NON-ASBESTOS COMPONENTS			ASBESTOS %
			Fibrous	Non-Fibrous		
AP-07 B2416837.07	Window Caulking	Homogeneous White Non-fibrous Bound	100%	Caulk		None Detected
AP-08 B2416837.08	Window Caulking	Homogeneous White Non-fibrous Bound	100%	Caulk		None Detected
AP-09 B2416837.09	Mastic	Homogeneous White Non-fibrous Bound	<1% Cellulose	100% Binder		None Detected
AP-10 B2416837.10	Mastic	Homogeneous White Non-fibrous Bound	<1% Cellulose	100% Binder		None Detected
AP-11 B2416837.11	Ceiling Texture	Heterogeneous White Non-fibrous Bound	85% 10% 5%	Binder Vermiculite Paint		<1% Chrysotile
AP-12 B2416837.12	Ceiling Texture	Heterogeneous White Non-fibrous Bound	85% 10% 5%	Binder Vermiculite Paint		<1% Chrysotile
AP-13 B2416837.13	Ceiling Texture	Heterogeneous White Non-fibrous Bound	85% 10% 5%	Binder Vermiculite Paint		<1% Chrysotile

ASBESTOS BULK ANALYSIS

By: POLARIZING LIGHT MICROSCOPY

Client: Matrix Health & Safety Consultants
 2900 Yonkers Road
 Raleigh, NC 27604

Lab Code: B2416837
Date Received: 08-30-24
Date Analyzed: 09-03-24
Date Reported: 09-03-24

Project: NCSU Apiculture Building

ASBESTOS BULK PLM, EPA 600/R-93/116 METHOD and EPA 40 CFR Appendix E Subpart E to Part 763

Client ID Lab ID	Lab Description	Lab Attributes	NON-ASBESTOS COMPONENTS				ASBESTOS %
			Fibrous		Non-Fibrous		
AP-14 Layer 1 B2416837.14	Joint Compound	Heterogeneous			58%	Binder	2% Chrysotile
		White			35%	Calc Carb	
		Non-fibrous			5%	Paint	
		Bound					
Layer 2 B2416837.14	Drywall	Heterogeneous	20%	Cellulose	80%	Gypsum	None Detected
		White,Brown					
		Fibrous					
		Bound					
Layer 3 B2416837.14	Drywall/Joint Compound (Composite)	Heterogeneous	20%	Cellulose	75%	Gypsum	<1% Chrysotile
		White,Brown			5%	Calc Carb	
		Fibrous			<1%	Paint	
		Bound					
2% Chrysotile found in joint compound only; <1% overall.							
AP-15 Layer 1 B2416837.15	Joint Compound	Heterogeneous			58%	Binder	2% Chrysotile
		White			35%	Calc Carb	
		Non-fibrous			5%	Paint	
		Bound					
Layer 2 B2416837.15	Drywall	Heterogeneous	20%	Cellulose	80%	Gypsum	None Detected
		White,Brown					
		Fibrous					
		Bound					
Layer 3 B2416837.15	Drywall/Joint Compound (Composite)	Heterogeneous	20%	Cellulose	75%	Gypsum	<1% Chrysotile
		White,Brown			5%	Calc Carb	
		Fibrous			<1%	Paint	
		Bound					
2% Chrysotile found in joint compound only; <1% overall.							
AP-16 Layer 1 B2416837.16	Joint Compound	Heterogeneous			58%	Binder	2% Chrysotile
		White			35%	Calc Carb	
		Non-fibrous			5%	Paint	
		Bound					

ASBESTOS BULK ANALYSIS

By: POLARIZING LIGHT MICROSCOPY

Client: Matrix Health & Safety Consultants
 2900 Yonkers Road
 Raleigh, NC 27604

Lab Code: B2416837
Date Received: 08-30-24
Date Analyzed: 09-03-24
Date Reported: 09-03-24

Project: NCSU Apiculture Building

ASBESTOS BULK PLM, EPA 600/R-93/116 METHOD and EPA 40 CFR Appendix E Subpart E to Part 763

Client ID Lab ID	Lab Description	Lab Attributes	NON-ASBESTOS COMPONENTS			ASBESTOS %	
			Fibrous	Non-Fibrous			
Layer 2 B2416837.16	Drywall	Heterogeneous White,Brown Fibrous Bound	20%	Cellulose	80%	Gypsum	None Detected
Layer 3 B2416837.16	Drywall/Joint Compound (Composite)	Heterogeneous White,Brown Fibrous Bound	20%	Cellulose	75%	Gypsum	<1% Chrysotile
					5%	Calc Carb	
					<1%	Paint	
2% Chrysotile found in joint compound only; <1% overall.							
AP-17 B2416837.17	Sink Mastic	Homogeneous White Non-fibrous Bound			95%	Binder	5% Chrysotile
AP-18 B2416837.18	Sink Mastic	Homogeneous White Non-fibrous Bound			95%	Binder	5% Chrysotile
AP-19 B2416837.19	Floor Glue	Homogeneous Yellow Non-fibrous Bound	<1%	Cellulose	100%	Mastic	None Detected
AP-20 B2416837.20	Floor Glue	Homogeneous Yellow Non-fibrous Bound	<1%	Cellulose	100%	Mastic	None Detected
AP-21 B2416837.21	Ceiling Texture	Heterogeneous White,Tan Non-fibrous Bound			83%	Binder	2% Chrysotile
					10%	Vermiculite	
					5%	Paint	

ASBESTOS BULK ANALYSIS

By: POLARIZING LIGHT MICROSCOPY

Client: Matrix Health & Safety Consultants
 2900 Yonkers Road
 Raleigh, NC 27604

Lab Code: B2416837
Date Received: 08-30-24
Date Analyzed: 09-03-24
Date Reported: 09-03-24

Project: NCSU Apiculture Building

ASBESTOS BULK PLM, EPA 600/R-93/116 METHOD and EPA 40 CFR Appendix E Subpart E to Part 763

Client ID Lab ID	Lab Description	Lab Attributes	NON-ASBESTOS COMPONENTS			ASBESTOS %	
			Fibrous	Non-Fibrous			
AP-22 B2416837.22	Ceiling Texture	Heterogeneous	83%	Binder	2% Chrysotile		
		White, Tan	10%	Vermiculite			
		Non-fibrous	5%	Paint			
		Bound					
AP-23 B2416837.23	Ceiling Texture	Heterogeneous	83%	Binder	2% Chrysotile		
		White, Tan	10%	Vermiculite			
		Non-fibrous	5%	Paint			
		Bound					
AP-24 Layer 1 B2416837.24	Joint Compound	Heterogeneous	58%	Binder	2% Chrysotile		
		White	35%	Calc Carb			
		Non-fibrous	5%	Paint			
		Bound					
Layer 2 B2416837.24	Drywall	Heterogeneous	20%	Cellulose	80%	Gypsum	None Detected
		White, Brown					
		Fibrous					
		Bound					
Layer 3 B2416837.24	Drywall/Joint Compound (Composite)	Heterogeneous	20%	Cellulose	75%	Gypsum	<1% Chrysotile
		White, Brown			5%	Calc Carb	
		Fibrous			<1%	Paint	
		Bound					
2% Chrysotile found in joint compound only; <1% overall.							
AP-25 Layer 1 B2416837.25	Joint Compound	Heterogeneous	58%	Binder	2% Chrysotile		
		White	35%	Calc Carb			
		Non-fibrous	5%	Paint			
		Bound					
Layer 2 B2416837.25	Drywall	Heterogeneous	20%	Cellulose	80%	Gypsum	None Detected
		White, Brown					
		Fibrous					
		Bound					

ASBESTOS BULK ANALYSIS

By: POLARIZING LIGHT MICROSCOPY

Client: Matrix Health & Safety Consultants
 2900 Yonkers Road
 Raleigh, NC 27604

Lab Code: B2416837
Date Received: 08-30-24
Date Analyzed: 09-03-24
Date Reported: 09-03-24

Project: NCSU Apiculture Building

ASBESTOS BULK PLM, EPA 600/R-93/116 METHOD and EPA 40 CFR Appendix E Subpart E to Part 763

Client ID Lab ID	Lab Description	Lab Attributes	NON-ASBESTOS COMPONENTS				ASBESTOS %
			Fibrous		Non-Fibrous		
Layer 3 B2416837.25	Drywall/Joint Compound (Composite)	Heterogeneous White,Brown Fibrous Bound	20%	Cellulose	75%	Gypsum 5% Calc Carb <1% Paint	<1% Chrysotile
2% Chrysotile found in joint compound only; <1% overall.							
AP-26 Layer 1 B2416837.26	Joint Compound	Heterogeneous White Non-fibrous Bound			58% 35% 5%	Binder Calc Carb Paint	2% Chrysotile
Layer 2 B2416837.26	Drywall	Heterogeneous White,Brown Fibrous Bound	20%	Cellulose	80%	Gypsum	None Detected
Layer 3 B2416837.26	Drywall/Joint Compound (Composite)	Heterogeneous White,Brown Fibrous Bound	20%	Cellulose	75%	Gypsum 5% Calc Carb <1% Paint	<1% Chrysotile
2% Chrysotile found in joint compound only; <1% overall.							
AP-27 B2416837.27	Cb Filler	Heterogeneous Light Blue,White Non-fibrous Bound			75% 20% 5%	Paint Binder Silicates	None Detected
AP-28 B2416837.28	Cb Filler	Heterogeneous Light Blue,White Non-fibrous Bound			75% 20% 5%	Paint Binder Silicates	None Detected
AP-29 B2416837.29	1x1 Ceiling Tile	Homogeneous Brown Fibrous Loosely Bound	100%	Cellulose			None Detected

ASBESTOS BULK ANALYSIS

By: POLARIZING LIGHT MICROSCOPY

Client: Matrix Health & Safety Consultants
 2900 Yonkers Road
 Raleigh, NC 27604

Lab Code: B2416837
Date Received: 08-30-24
Date Analyzed: 09-03-24
Date Reported: 09-03-24

Project: NCSU Apiculture Building

ASBESTOS BULK PLM, EPA 600/R-93/116 METHOD and EPA 40 CFR Appendix E Subpart E to Part 763

Client ID Lab ID	Lab Description	Lab Attributes	NON-ASBESTOS COMPONENTS			ASBESTOS %	
			Fibrous	Non-Fibrous			
AP-30 B2416837.30	1x1 Ceiling Tile	Heterogeneous Brown Fibrous Loosely Bound	95%	Cellulose	5%	Paint	None Detected
AP-31 B2416837.31	Insulation	Homogeneous Yellow Fibrous Loosely Bound	100%	Fiberglass			None Detected
AP-32 B2416837.32	Insulation	Homogeneous Yellow Fibrous Loosely Bound	100%	Fiberglass			None Detected

LEGEND: Non-Anth = Non-Asbestiform Anthophyllite
Non-Trem = Non-Asbestiform Tremolite
Calc Carb = Calcium Carbonate

METHOD: EPA 600 / R-93 / 116 and EPA 40 CFR Appendix E to Subpart E of Part 763

REPORTING LIMIT: <1% by visual estimation

REPORTING LIMIT FOR POINT COUNTS: 0.25% by 400 Points or 0.1% by 1,000 Points

REGULATORY LIMIT: >1% by weight

Due to the limitations of the EPA 600/R-93/116 method, nonfriable organically bound materials (NOBs) such as vinyl floor tiles can be difficult to analyze via polarized light microscopy (PLM). EPA recommends that all NOBs analyzed by PLM, and found not to contain asbestos, be further analyzed by Transmission Electron Microscopy (TEM). Please note that PLM analysis of dust and soil samples for asbestos is not covered under NVLAP accreditation. *Estimated measurement of uncertainty is available on request.*

This report relates only to the samples tested or analyzed and may not be reproduced, except in full, without written approval by Eurofins CEI. Eurofins CEI makes no warranty representation regarding the accuracy of client submitted information in preparing and presenting analytical results. Interpretation of the analytical results is the sole responsibility of the client. Samples were received in acceptable condition unless otherwise noted. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government.

Information provided by customer includes customer sample ID and sample description.

ANALYST:


Nicholas Moore

APPROVED BY:


Tianbao Bai, Ph.D., CIH
Laboratory Director



NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

[Designer shall incorporate this document into the specification in its entirety.]

1.0 Purpose

- A. The following guidelines apply to North Carolina State University's ("NC State") requirements specific to the needs of NC State. It is the goal of NC State to identify specific needs relevant to working on a public university campus that will help the Contractor gain more knowledge and be fully aware of NC State's expectations while working on campus.
- B. References include the following:
 - 1. NC State Transportation's Contractor Parking Policies:
<http://www2.acs.ncsu.edu/trans/parking/specialty.html>
 - 2. NC State University, Environmental Health and Public Safety, Fire Protection Department Hot Work Permit Procedures. Contractor shall access the following website to obtain hot work permits: <https://fls.epsi.ncsu.edu/forms/hot-work-permit-request/>

2.0 General Requirements

- A. The Owner's Representative - NC State will designate a Project Manager to act as the Owner's Representative in all matters pertaining to construction contracts. All official contacts, decisions, directions, problem resolution, coordination and other liaison activities required from NC State will be through the Project Manager. This requirement does not modify the responsibilities of the Designer as stated in the General Conditions of the Contract.
- B. Contractor, at its expense, shall conduct a background check for each of its employees, as well as for the employees of its subcontractors, who will perform any function or activity under this Agreement. NC State may withhold consent for any of Contractor's employees to be placed on a NC State assignment at its sole discretion.
- C. Behavior policy - All construction personnel shall be respectful of all members of the NC State community. Any incidents of disrespect, verbal abuse, threatening statements, unwelcome comments, unwelcome interaction or any form of harassment from any construction personnel toward any member of NC State community is strictly prohibited. Any such act shall constitute sufficient cause for NC State to remove any individual permanently from the project and all NC State property. In addition, any of the Contractor(s) project personnel who ignore or refuse to take action on any requirements of the contract documents or ignore or refuse to take immediate action to correct any endangerment to the health and safety of the public (as solely determined by NC State)

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

shall be permanently removed from the project and NC State property. If in the sole determination of NC State it is in the best interest of the project and NC State to have any of the Contractor(s) personnel removed from the project, then the Contractor shall do so upon request by NC State. Such actions taken by NC State shall not constitute grounds for a delay claim. NC State will not be responsible for any delays caused to the project due to any individual being removed from the project by NC State.

D. Protection of Work, Property, and Public:

1. The single prime Contractor, Construction Manager at Risk or Project Expediter (on a multi prime project), henceforth referred to as "the Contractor," shall ensure that campus streets connecting to the project are protected from mud, sand, and stones/gravel. Streets and adjacent property sites shall be kept free from run-off, litter and/or debris in any form from the project site. Mud, litter and/or debris from the construction site that appears on adjacent property sites shall be removed immediately. All mud collected on vehicle tires shall be removed before leaving the construction area. Should any mud or debris from the project site collect on the streets, it shall be removed immediately to prevent any hazards to vehicular or pedestrian traffic as well as from entering the storm sewer system. In any event, all streets and property sites adjacent to the project site shall be cleaned of construction related debris, dust, litter and mud daily. The Contractor, in the preparation of bids, shall account for the daily cleaning of adjacent streets and property sites. The Contractor(s) is prohibited from discharging any waste products from concrete trucks or from concrete coring work, or any other unsuitable materials, fluids or other products on the site or into the storm sewer system. Should the Contractor fail to comply with these requirements, NC State reserves the right, with twenty-four (24) hours prior notice to the Contractor, to clean and or remove mud, trash, litter, debris or any unauthorized discharge from the project site and/or the adjacent streets or properties. In such case, the cost of the cleaning and/or removal or mobilization for cleaning and/or removal shall be deducted from the Contractor's contract.
2. The Contractor shall repair any damage (including but not limited to: scratches, cuts, dings, holes, track marks, etc.) of any kind made to existing hardscapes (asphalt/concrete roadway and drives, curb and gutter, brick sidewalks, etc.) by heavy equipment or other causes. Repairs shall consist of a complete, full depth removal and replacement of the affected asphalt, concrete or brick hardscapes at the Contractor's expense, or as otherwise determined by the Owner, to include the full width of the road, parking lot, walk or curb that is affected. The Contractor is strongly encouraged to be mindful of this while working around and off-loading equipment in areas of new construction adjacent to existing areas, which are not in the original scope of work to be renovated or repaved. In

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

general, equipment shall be off-loaded inside of assigned staging areas, and the Contractor shall take protective measures as needed, including protective plywood or other means to prevent damage of the hardscape surface. The slightest damage will result in full hardscape replacement at the Contractor's expense.

3. Blasting on NC State property is prohibited.
 4. Each Contractor doing excavation work is responsible for locating all existing underground utilities prior to commencing excavation. The Contractor shall be responsible for the associated cost of any utility interruption and repair due to his excavation if utility location was not requested, location procedures performed and followed prior to commencing excavation. The Contractor shall immediately notify NC State and restore the service of any utility disrupted due to excavation or any Contractor action whatever the circumstance. NC State reserves the right to immediately restore the service of any utility disrupted due to actions of the Contractor and deduct the cost of such restoration from the Contractor's contract.
 5. For emergency situations during construction, the Contractor shall furnish NC State with the names, pager numbers, and telephone numbers (day and night) of the Contractor's project manager and superintendent prior to beginning work. The numbers shall remain current or be updated as required for the duration of the project. The Contractor shall contact NC State via cell phone immediately in the event of an emergency. NC State will only provide security, as it deems prudent and necessary for its own protection. The Contractor shall be responsible for the security and safety of the project within the project limits. NC State must approve any "watchman" service instituted by the Contractor.
 6. NC State will conduct normal operations during the duration of the project. The Contractor shall coordinate with NC State to minimize any disruptions to the functions of NC State.
- E. Working Hours - The Contractor may establish a work schedule of his own choosing. The Contractor shall submit to NC State and to the Designer his regular daily work schedule and shall notify NC State in writing one week in advance of any deviations from the schedule. There are no restrictions regarding work hours. NC State reserves the right to limit the Contractor's activities when they conflict with NC State operations. These operations include but are not limited to the following: examination periods (typically for two weeks in December and two weeks in May), graduation (typically for one weekend in December and May), athletic events, and student move in/move out days. During these times, the Contractor may be required to cease all construction activities, limit activities to on-site only, modify working hours or restrict noise-making activities as determined by NC State.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

- F. Contractor Daily Reports - The Contractor shall keep construction daily reports and provide, at NC State's request or on a minimum weekly basis, copies of these daily reports. The Contractor shall either use the company's standard daily report or use a template provided by NC State. The daily report shall at a minimum include the following information:
1. Project name, SCO Project ID#, NC State Project #
 2. Report #
 3. Date and time report was generated
 4. Weather data: overhead conditions, precipitation (if so, how much), temperature (high and low), impact on progress
 5. Sediment and erosion control
 6. Work performed (include all major trades)
 7. Number of workers on site
 8. Major equipment deliveries
 9. Major equipment working on site
 10. Difficulties encountered that may cause delay
 11. Days of no work and reason
- G. Meetings - The contractor shall at a minimum conduct weekly coordination meeting to review construction progress and any issues that need to be resolved. Contractor shall invite NC State and Designer as well as any required subcontractors.
- H. Inspection of the work - NC State will conduct the following inspections, as applicable, which shall be included in the construction schedule: in-wall inspections, above ceiling inspections, generator test, fire pump test, fire sprinkler main drain tests, pre-final inspections, 100% test of the fire detection and alarm system, third-party materials testing/special inspections/commissioning and a final inspection for project acceptance. Any inspections that are not satisfactory shall be repeated at no cost to NC State and shall not be cause for a time extension. All inspections will be conducted by NC State at the same time as the Designer's inspection and a punch list generated. The Contractor shall give the Designer and NC State a minimum of fourteen (14) calendar days prior notice that the systems have been verified by the Contractor to be complete, fully functional and ready for inspection. The following general guidelines apply to the above ceiling inspections:
1. The systems must be complete, including but not limited to controls, insulation, labeling, tagging, fireproofing, fire stopping, wiring, light fixtures installed, and all piping in place.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

2. Ceiling grid may be installed as required, framing for hard ceilings shall be in place, and access door locations shall be framed and noted.

Under no circumstance shall any ceiling or wall area be covered prior to the above ceiling inspection. All punch list items generated from the inspections shall be completed by the Contractor and verified by the Designer and NC State. Any re-inspection costs, including but not limited to Designer, NC State, State Construction Office (SCO) or third party personnel, that result from punch list items not being 100% complete shall be at the expense of the Contractor.

- I. Use of the Premises - Parking is extremely limited at NC State. Parking for personal vehicles on campus is not provided. Contractors must limit parking of company vehicles and storage of materials to within the limits of the construction site and staging area. The Contractor is required to follow NC State Transportation's Contractor Parking Policies (see web link on page one of this document).
- J. Utilities - It is imperative that all campus utilities and all other campus services are maintained at all times except for scheduled interruptions. Required utility interruptions shall be scheduled with and requested through NC State at least fourteen (14) days in advance for minor outages and thirty (30) days in advance for major outages. NC State is the sole determiner of the utility outage being major or minor. Major outages include but are not limited to those that affect an entire floor of a building, all of a building, all or parts of several buildings, all or parts of an area, and any high voltage outage. No utility interruption, regardless of the advance notice given, shall be undertaken without expressed, specific approval from NC State. If requested by NC State, utility outages shall be performed after hours and/or at night, or over the weekend, or during holidays. No extra payment will be made for such work. NC State personnel will perform certain activities in connection with utility outages such as operating existing electrical switches, turning existing water and steam valves, placing existing building systems back in operation, operating existing fire alarm systems, etc. NC State will bear the expense of the work of their personnel. When the Contractor requires an additional or extra outage to complete their work because of a shortage of or improper materials, shortage of labor, poor coordination, failure to finish the work during the outage scheduled length of time, the Contractor will pay all expenses incurred for NC State's services for an additional outage(s). No service disruptions shall take place until barricades (if applicable) and signs are in place to notify and/or protect the public. Barricades must be maintained at all times and signs shall be neat and legible, hand-made signs are not acceptable. Signs for utility outage notice shall be written and placed as directed by NC State seven (7) workdays prior to the outage. NC State may determine the utility service cannot be interrupted for the length of time or frequency requested by the Contractor. In such case the Contractor shall include in his bid provisions for temporary utility services for the duration of the outage at no cost to NC State.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

- K. Survey of New and Existing Sub-surface Utilities - Perform field location surveys of new utilities installed as well as existing utilities uncovered during the construction phase. Conventional survey standards are to be utilized during the collection of field data. All work shall be performed by qualified personnel under the supervision of a Professional Land Surveyor. Accuracy Standards: horizontal and vertical location shall be +/- 0.25'. Survey (NAD83-North Carolina State Plane Coordinates) shall tie to NC State's horizontal & vertical control monuments.
1. Utility Drawing Set (Hard Copy)
 - a) Cover Sheet - All projects require a cover sheet with the following information -
 - (1) NC State Project Name
 - (2) NC State Project Number
 - (3) NC State Building Name (s)
 - (4) NC State Building Number or Utility Zone Number (s)
 - (5) Project Phase (i.e. Schematic Design, Design Development, 100% Bid Documents, or Record Set)
 - (6) Sheet Name with discipline letter preceding sheet number (i.e. A100 for an Architectural Plan).
 - (7) Drawing Index
 - (8) Site Map
 - (9) For interior renovations, a hatched key plan indicating the extent of work
 - b) Drawing Sizes – sheet sizes shall not exceed 36” x 48” and shall not be less than 24” x 36” in size.
 - c) Include licensing seal and certification on 100% bid documents and record set documents.
 2. Utility Drawing Set (Electronic Copy)
 - a) Format shall be .pdf.
 - b) Submission is required at each project phase.
 - c) File naming shall be as follows:
 - (1) Typical file naming shall be as follows -
bldg #_ncsu project number_date_phase.pdf or
utility zone #_ncsu project number_date_phase.pdf
 - (2) Example: 799Z_201300001_10-31-12_sd.pdf

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

- (3) For projects with multiple buildings or utility zones, the lowest number shall be used in file name.
3. Electronic Source CADD Files (Record Set and first Construction Document Submittal)
 - a) Electronic files of all drawings shall include source drawings, font libraries, custom line styles/codes, plot style tables and other digital CADD related information.
 - b) The files shall be in AutoCAD .dwg format; the AutoCAD version shall be within the last 2 years of the current release.
 - c) Drawings shall be drawn at a scale of 1 to 1 in model space. Interior spaces shall be in Architectural inches. Exterior space shall be in US survey foot.
 - d) For exterior projects use NAD 83 North Carolina State plane coordinates.
 - e) All external references shall be bound as inserts or inserted directly as a block into the drawing. X-refs of any kind are not acceptable.
 - f) Remove licensing seals from drawing files.
 - g) Drawings shall be purged and audited.
 - h) Submission shall not include backup .bak files or .zip files.
 - i) Site, Civil, and Survey drawings shall use the NC State mapping drawing template, which includes NC State standard layers, linetypes and block symbols. The current version can be downloaded at www.ncsu.edu/facilities/con_guidelines/NCSU_CIV-SRV_TEMPLATE.dwg
4. Utility Submission
 - a) Hard Copy - The Drawing Set shall be submitted on bond paper.
 - b) Electronic Files for the Record Drawing Set and Source CADD Files shall be accompanied by a transmittal with a listing of the included documents and the following information:
 - (1) NC State Project Number
 - (2) NC State Project Name
 - (3) NC State Building Number(s)
 - (4) NC State Building Name (s)
 - (5) NC State Project Manager's Name and Phone Number
 - (6) Submitting Professional's Name and Address
 - c) Electronic Files shall be submitted on a CD or DVD
 - (1) A .pdf file of the transmittal shall be included on each disk.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

- L. The following outline lists the utilities to be located and the data to be collected. Photographs shall be at a minimum resolution of 2200 x 1700. Digital photographs can be submitted in TIFF, JPG, or RAW file formats. File naming shall be all lower case text. File naming shall be as follows: bldg#_ncsu project number_util_photo#.file extension. For example: 135_201300001_util_1.jpg
1. Steam Tunnel and Lines
 - a) Location and elevations of the tunnel slab and top of tunnel centerlines.
 - b) Location and size of steam and condensation pipes in the tunnel, including changes in directions, expansion loops and anchors.
 - c) Top of pipe of any direct buried steam and condensation pipes, including changes in directions, expansion loops and anchors.
 - d) List the construction material for the tunnels.
 - e) Provide digital photographs of the tunnel, piping and expansions areas.
 2. Water Lines - (Domestic, Fire Main, Chilled, Hot Water, & Reuse Waterlines)
 - a) Locations, size and elevations at the top of installed water lines, including changes in direction.
 - b) Locations of valves and a valve type designation, meters, fire department connections, post indicator valves, hydrants, reducers, manholes, and backflow device.
 - c) Provide digital photographs of bends and valves.
 3. Electric and Communication Duct Banks and Direct Buried Conduit
 - a) Location and elevations of the duct bank top and bottom.
 - b) Location and elevations of conduit runs in the duct bank.
 - c) Location and elevations of any direct buried conduit or concrete duct bank.
 - d) Location and elevations of manhole rims, transformers, pedestals, switches, poles, overhead lines, junction boxes, panels, generators, and meter boxes.
 - e) Provide digital photographs of the tunnel and conduit configuration.
 4. Gas
 - a) Location and elevations of top of pipe and any change in direction.
 - b) Location and elevations of meters, pressure reducing stations, test stations, generators, and valves.
 5. Storm and Sanitary Sewer
 - a) Provide invert elevations for incoming and outgoing piping at manholes.
 - b) Provide top elevation of manhole cover.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

- c) Note if manhole rims are in the center of the structure or not. Measure the offset, pipe sizes, material types and the direction of the flow.
 - d) Provide digital photographs of structures.
 - 6. Existing Utilities
 - a) Locate and provide elevations consistent with new utility requirements of any existing utilities exposed during excavation of trenches for new utilities.
 - b) Provide digital photographs of the crossing or conflict.
 - 7. Deliverables for Surveys
 - a) The subsurface location data and platting shall be continuous throughout the project.
 - b) All data and plats are due to NC State within two-weeks of the backfilling of utilities or completion of the associated construction task.
- M. Traffic Movement and Interruptions - Road and sidewalk blockages shall be scheduled fourteen (14) days in advance and made only after NC State has approved them. Appropriate detours shall be planned, subject to approval by NC State, giving consideration to the handicapped access. No excavations shall take place prior to placing proper barricades, lighting, and other devices as shall be required. The Contractor shall install warning signs, barricades and detour information signs to maintain traffic flow as directed by NC State. If required, flagmen shall direct traffic around the construction area or detour area. Contractors are reminded of the presence on campus of handicapped students, staff and faculty. All barricades, temporary walkways, excavations, and stockpiled materials shall be placed and/or constructed in such a manner as to accommodate, adequately warn, and protect this segment of the campus population. The Contractor shall make requests for approval for any street, alley, driveway or any access way to be closed at least ten (10) work days prior to the date for the desired closing. The Contractor shall close no street, alley, driveway or access-way without prior approval by NC State. Pedestrian and vehicle traffic way-finding around the construction limits must be maintained in a clean and safe condition at all times.
- N. Fire Alarm Shutdowns - When requesting fire alarm shutdowns to support construction activities, the contractor shall provide advanced notice as determined by the NC State Project Manager. The contractor shall also be required to reimburse NC State for all costs associated with the fire alarm shutdown as follows:
 - 1. During normal business hours (Monday – Friday, 7:00 AM – 5:00 PM): \$75.00 per disconnect and \$75.00 per reconnect for a total of \$150.00.
 - 2. After normal working hours (Monday – Friday, 5:01 PM – 6:59 AM; Saturday – Sunday): \$150.00 per disconnect and \$150.00 per reconnect for a total of \$300.00.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

3. If at any time the fire alarm system is not in operation after normal working hours then the contractor shall be required to employ a Fire Watch for the unprotected portion of the building, using NC State Fire Marshal's approved Fire Watch company (hourly rates vary but should not exceed \$35.00 per hour.)
- O. Hot Work Permits - When the Contractor is performing work that produces heat, flame, or sparks on or in an existing building or other structure the Contractor is required to obtain a "hot work" permit from NC State Environmental Health and Public Safety, Fire Protection Department. The department's requirements for the hot work program and permit can be found at the web link on the first page of this document. The EH&PS Hot Work Policy (rev. May 1, 2022) is appended to the end of this section.
- P. Cleanliness and Site Maintenance - The Contractor(s) shall be responsible for keeping the project limits area, the project site, and the project itself clean and free of accumulated construction debris and trash. To that extent, the Contractor(s) shall be responsible for cleaning their work areas weekly at a minimum and the proper disposal of their construction debris and trash. The construction site and staging areas shall be cleaned as previously noted; however, should trash, litter or debris from the project site migrate to any adjacent campus areas it shall be removed immediately. Grass in the construction site shall be mowed as often as required to maintain a neat appearance or as requested by NC State but in no case less than once per month. Should the Contractor(s), in the sole judgment of NC State fail to comply with these requirements, then NC State reserves the right to proceed with cleaning within the project limits area, immediate project site, the interior of the project or, if applicable, the adjacent areas to the project as it deems necessary. The cost of the cleaning and/or the mobilization cost of cleaning will be deducted from the Contractor(s) contract.
- Q. Storage of construction materials and equipment - Storage of construction materials and equipment shall be limited to the staging area. Should the Contractor fail to remove any material stored or equipment outside the staging area within twenty-four (24) hours of notification received from NC State, NC State shall have the right to remove and dispose of such materials from the campus. NC State will deduct the cost of such removal and disposal from the Contractor(s) contract. The offending Contractor(s) shall be responsible for any delay to the project resulting from NC State having to remove and dispose of such materials or equipment.
- R. Construction site - A construction fence shall be installed around the perimeter of the project limits. The fence shall be constructed of heavy-duty chain link material, have a minimum height of six feet and shall have a continuous top tubular rail. Swing gates shall be included at every access to the enclosed area. The fence shall have an integral visual barrier or shall have shading type material applied and maintained for the duration of the

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

project. Locks for the gates shall be interlocked with a padlock provided by NC State in order to allow access by NC State or other emergency personnel in case of an emergency.

- S. Inspection and Audit - Contractor's "records" shall upon reasonable notice be open to inspection and subject to audit and/or reproduction during normal business working hours. An NC State representative or an outside representative engaged by NC State may perform such audits. NC State or its designee may conduct such audits or inspections throughout the term of this contract and for a period of three years after final payment or longer if required by law.
1. Contractor's records as referred to in this contract shall include any and all information, materials and data of every kind and character, including without limitation, records, books, documents, subscriptions, recordings, agreements, purchase orders, leases, contracts, commitments, arrangements, notes, daily diaries, superintendent reports, drawings, receipts, vouchers and memoranda, and any and all other agreements, sources of information and matters that may in NC State's judgment have any bearing on or pertain to any matters, rights, duties or obligations under or covered by any Contract Document. Such records shall include (hard copy, as well as computer readable data if it can be made available): written policies and procedures; time sheets; payroll registers; payroll records; cancelled payroll checks; subcontract files (including proposals of successful and unsuccessful bidders, bid recaps, etc.); original estimates; estimating work sheets; correspondence; change order files (including documentation covering negotiated settlements); back charge logs and supporting documentation; invoices and related payment documentation; general ledger entries detailing cash and trade discounts earned; insurance rebates and dividends; and any other Contractor records which may have a bearing on matters of interest to NC State in connection with the Contractor's dealings with NC State (all foregoing hereinafter referred to as "records") to the extent necessary to adequately permit evaluation and verification of:
 - a) Contractor compliance with contract requirements,
 - b) Compliance with NC State's business ethics policies, and
 - c) Compliance with provisions for pricing change orders, invoices or claims submitted by the Contractor or any of his payees.
- T. Changes in the Work - Overhead shall also include all general conditions of the contract and all general requirements such as project management, scheduling, home office expense, engineering and layout, reproduction expenses, shop drawing processing and coordination, supervision, coordination, small tools, all vehicle expenses, temporary facilities, safety provisions, as built drawings, estimating, and general overhead.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

1. The change order cost break down shall include: labor (number of hours and \$/hr) and material (quantity and \$/unit), including such breakdowns for work performed by the general contractor and all subcontractors. Unit prices shall only be allowed as stipulated in Article 19 of the contract General Conditions. Cost extensions shall be clearly shown for the labor and material prior to any mark-ups. The cost extensions shall be added into a labor and material subtotal. The labor shall then show a percentage for labor burden, while the materials shall show the applicable sales tax. These subtotals shall then be shown as a total for labor and material costs. The labor and material cost shall then show the allowed mark-up, and a final total. Subcontractor quotes shall be presented in the same format on the subcontractor's letterhead. Each item totaled on the Contractor's summary sheet shall be separated in the back up documentation by a colored sheet of paper. For change orders that delete any part of the work within the change order and/or contain deductive costs, the back up shall show the original material and labor for the deleted work or costs. If the change order contains both adds and deducts for the same type of work then the material unit and labor unit costs shown on the back up for the deleted work and the added work shall be the same and the net difference shown. Deductive change orders shall show the proper reduction in OH&P and the bond. The Contractor shall also provide HUB utilization information on NC State's Hub Utilization form. Failure by the Contractor to provide the information requested in this paragraph shall result in rejection of the change order by the designer and a request for re-submittal. Delay in the processing of the change order due to lack of proper submittal by the Contractor in accordance with this paragraph, or due to errors in the change order calculations shall not constitute grounds for a time extension or basis for a claim.
2. For all proposed change orders, the procedure will be for the designer to request proposals for the change order work in writing. The Contractor will provide such proposal and supporting data in suitable format and as required in General Condition Article 19 – Changes in the Work, paragraph “c”, “d”, and “e”. The designer shall verify correctness and determine that the Contractor's proposed costs are equitable. After receipt of the Contractor's proposal and if the proposal is correct and it is agreed to by the designer and NC State that the cost is equitable then NC State shall prepare a change order and forward it to the Contractor for his signature. If the change order proposal is incorrect, or the cost has not been agreed upon by the designer and NC State then the designer shall notify the Contractor that the proposal is rejected and the proposal shall be re-submitted. If the proposal is rejected because the cost are deemed not to be equitable then the contracting parties shall negotiate and agree upon the equitable value of the change and the proposal shall be resubmitted with costs

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

- determined under General Condition Article 19 – Changes in the Work Paragraph “e”.
3. Once proposed change orders have been reviewed and approved by the Contractor, Designer and NC State, the change order shall be processed for signatures electronically through the State Construction Office (SCO) web-based Interscope program. Directions for using Interscope shall be provided at the Pre-construction Conference.
 4. If for whatever reason Interscope cannot be used for processing change orders, change orders shall be processed in hard copy format in accordance with General Condition Article 19 – Changes in the Work. The change order shall contain a brief description of the work on the 1st page of the SCO form and again on the second sheet of the form under “DESCRIPTION OF CHANGE”. On the second sheet there shall also be a brief description of the reason for the change along with a cause code listed. Each item totaled on the Contractor’s summary sheet shall be separated in the back up documentation by a colored sheet of paper. After receipt of the change order executed by the Contractor, the designer shall, certify the change order by his signature and forward the change order and all supporting data to NC State for signature. NC State shall execute the change order and forward to the State Construction Office for final approval. The State Construction Office shall review and upon approval execute the change order and keep one copy. The remaining copies are sent to the designer for distribution to NC State (two copies with original signatures) and to the Contractor (two copies). The Contractor shall forward a copy to his Surety. In the case of an emergency or extenuating circumstances, the approval of the changes may be obtained verbally by telephone or field order approved by all parties.
 5. The Contractor shall also provide HUB utilization information on NC State’s Hub Utilization form.
 6. Failure by the Contractor to provide the information requested in this paragraph shall result in rejection of the change order by the designer and a request for re-submittal. Delay in the processing of the change order due to lack of proper submittal by the Contractor in accordance with this paragraph or due to errors in the change order calculations shall not constitute grounds for a time extension or basis for a claim.
- U. A time extension due to Weather - A rain day is defined as any day that rain exceeds one tenth of one inch (0.1"). The Contractor may only be entitled to extension of the contract period for the number of rain days that exceed the normal number of rain days for any given month. For the purpose of determining extent of delay attributable to unusual weather, a determination shall be made by comparing the weather for the contract period with the preceding five (5) year climatic range average during the same time interval

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

based on statistics kept at NC State's Marine, Earth and Atmospheric Sciences department located on NC State's campus and on daily weather logs kept on the jobsite by the Contractor, reflecting the effect of the weather on progress of the work and initialed by the designer's representative. Time extensions for weather delays do not entitle the Contractor to "extended overhead" recovery and are in all other ways non-compensable.

Notwithstanding the immediately preceding paragraph, not all rain days above the normal number of rain days will warrant a contract time extension. Justification for the request for rain related contract time extensions must also be based on the effect of the rain on critical path work activity in progress during the period of the request and additionally be predicated on the Contractor's diligent prosecution of the work. No additional rain days shall be granted for building projects after the building has been "dried-in" as determined by the designer. The contract time extension request must incorporate work logs kept at the jobsite by the project superintendent showing the effect of the weather on the progress of the critical path work and the critical path schedule, both initialed by the designer's project representative.

Requests for contract time extensions based on rain days must be received by the designer on or before the 20th day of the month immediately following the month in which the rain occurred. The request must include all required documentation. All parties to this contract agree that the Contractor has no right to claim a contract time extension if the request is not received by the designer in strict accordance with the procedure set forth in this paragraph.

For other types of weather delays, the Contractor is granted one (1) day of contract extension for each day NC State is closed due to weather.

V. Final Inspection and Acceptance

1. In addition to all other contract inspection requirements, the following items shall be completed prior to scheduling a final inspection:
 - a) Training of NC State's Facilities Operations personnel shall be conducted with approved Operation and Maintenance Manuals (O&M's) provided at the training sessions.
 - b) Deliver to NC State one copy of all approved shop drawings (submittals) for the project.
 - c) Stairs: prior to final inspection, the Contractor shall submit to the Designer and NC State for review and approval as-built survey drawings of each set of stairs (exterior and interior) constructed as part of this contract. As-built survey drawings shall include dimensions of each riser and each tread and shall bear the seal of a licensed surveyor registered in

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

the State of North Carolina. The Designer shall determine that the stairs are in full compliance with the current State of North Carolina Building Code, and if not in compliance, the Contractor, at his expense, shall make all required corrections, resurvey and resubmit as-builts for re-review and approval by the Designer and NC State.

2. The Contractor shall complete the following list, indicating the date of completion, prior to scheduling a final inspection and recommending acceptance of the project to NCSU. Items 1 and 2 must be completed prior to “substantial completion” as defined in Supplementary General Conditions 3.0 Article 23 “Time of completion - the Contractor shall coordinate with NC State the completion of some items on the list as required:

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

Project Acceptance Checklist (also to be used for Beneficial Occupancy when applicable)

Project Name:

Code: **Item:**

Note: All items must be checked off with dates & initialed

accordingly

	Initial & Date
I. Pre-final Inspections	
A. Critical Items Check List:	
1. NCSU Environmental Health Safety Department certification of fume hoods	
2. NCSU Fire Marshall's inspection of life safety systems (FAS, Sprinkler System, Emergency Generator, Fire Pumps etc)	
3. Fire Extinguishers installed or delivered to NC State	
4. Roof & window water tests (when required)	
5. Date to coordinate NCSU Fac Ops Lock Shop to install locks and test in conjunction with Life Safety	
6. State Construction Office electrical inspection(s) complete	
7. Fire alarm inspection and certification by installer and design engineer complete	
8. Fire alarm inspected & approved by NCSU Electronics Shop & Fire Marshall	
9. Elevator inspection by Dept. of Labor, approval to operate the elevator obtained	
10. Demonstration of operation of fire pumps to NCSU Fire Marshall	
11. Operation of emergency and stand by power circuits verified	
12. Operation of emergency generator verified	
13. Dept. of Health water test results and approvals delivered to designer	
14. Dept. of Labor pressure vessel inspections and certificates issued and displayed.	
15. Endorsement of surety for beneficial occupancy (if applicable)	
16. Endorsement of Contractor's insurance company for beneficial occupancy (if applicable)	
17. Approval of SCO for beneficial occupancy (if applicable)	
18. Date for insurance transfers established	
II. Training and instruction of Facility Operations Personnel on Equipment	
A. Record of Instruction Sessions:	
Plumbing	
HVAC/ Controls	
Electrical	
Fire Alarm	
B. NC State O & M Manuals and pressure vessels info delivered to NC State	
III. Pre-Final Inspection	
A. Pre-final Punch list Certified as Complete by the Designer:	
General	
Mechanical	
Plumbing	
Electrical (including fire alarm system)	
IV. Final Inspections with SCO	
A. Date of Final Acceptance Inspection with SCO	
1. Date SCO punch list items complete	

All items complete and verified by the Designer

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

Signed _____ Date: _____

W. Request for Payment – In addition to General Conditions Article 31 – Requests for Payments, Contractor payment applications shall have the following information clearly shown on the front page: NC State project number, Code & Item, State Construction Office Project Identification Number. No payment may be made for stored materials that are not stored within the project limits or on property owned by the State of North Carolina. Exception may be considered for material stored in a third-party, bonded warehouse with all appropriate documentation provided to NC State. Designer must verify that material is stored in a bonded warehouse and that the stored material is identified as NC State property. No payment shall be certified/approved by the Designer and forwarded to NC State for payment if not accompanied by the following:

1. A letter from the surety company consenting to the progress payment in the amount requested. The amount of the payment shall be shown on the letter.
2. A completed sales tax statement and form.
3. An updated CPM schedule.
4. MBE Appendix "E" Form with accurate subcontract amounts and amounts paid.
5. NC State project code, item number, project number and the State Construction Office ID number on the 1st sheet.
6. Pay applications without the information listed shown shall be considered incomplete and cannot be approved.
7. "Schedule of values" shall include payment line items for various commissioning activities.

No final payment shall be approved by the Designer and/or forwarded to NC State if not accompanied by the following:

8. Certificate of Compliance signed by the Designer of Record.
9. Certificate of Completion signed by the Designer of Record.
10. Completed Tax Statement and Form.
11. Consent of Surety for Final Payment.
12. Contractor's Affidavit of Payment of Debts and Claims.
13. Contractor's Affidavit for Release of Liens.
14. Contractor's General Guarantee.
15. Contractor's statement of any special or extended warranties.
16. MBE Appendix "E" Form with accurate subcontract amounts and amounts paid.

* NC State shall have 30 days from the time that correct and complete payment requests are received to pay the Contractor.

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements



Office of Finance and Administration
Emergency Preparedness and Strategic Initiatives
Fire and Life Safety
<https://epsi.ncsu.edu/fire-and-life-safety/>

Campus Box 7220
Raleigh, NC 27695-7220
P: 919.515.2568
firesafetyhelp@ncsu.edu

Hot Work Permit Program

May 1, 2022

Hot Work

Hot work is defined by the 2018 NC Building Code: Fire Prevention Code as, operations including cutting welding, Thermite welding, brazing, soldering, grinding, thermal spraying, thawing pipe, installation of torch-applied roof systems or other similar activities.

Hot Work Area

The area exposed to sparks, hot slag, radiant heat, or convective heat as a result of the hot work.

Hot Work Equipment

Electric, or gas welding, or cutting equipment used for the hot work.

Hot Work Permits

Permits shall be issued by a responsible person at the facility under the hot work program permitting welding or other hot work to be done in locations referred to in section 3501.3 and pre-permitted locations by the fire code official.

(3501.3: Restricted areas. Hot work shall only be conducted in areas designed or authorized for that purpose by the personnel responsible for the Hot Work Program. Hot work shall **NOT** be conducted in the following areas unless approval has been obtained from the fire code official (NCSU Fire & Life Safety):

1. Areas where an existing sprinkler system have been impaired.
2. Areas where there exists the potential of an explosive atmosphere, such as locations where flammable gases, liquids, or vapors are present.
3. Areas where readily ignited materials, such as storage of large quantities of bulk sulfur, baled paper, cotton, lint, dust, or loose combustible materials.
4. On board ships at dock or ships under construction or repair.
5. At other locations specified by the fire code official (NCSU F&LS).


Hot work permits, issued by an approved responsible person under the Hot Work Program, shall be available for review by the fire code official (NCSU F&LS) at the time the work is conducted and for 48 hours after the work is completed. A permit for hot work operations shall not be issued unless the individuals in charge

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

of performing such operations are capable of performing the hot work safely. The individual responsible for the hot work area, temporary or fixed, shall maintain a log of pre-work checks in accordance with NCFE Section 3504.3.1. The reports shall be maintained on the premises for not less than 48 hours after the work is completed.

Visible hazard identification signs shall be provided where required by the fire code official (NCSU F&LS). Where the hot work area is accessible to persons other than the operator of the hot work equipment, conspicuous signs shall be posted to warn others before they enter the hot work area. Examples of the sign(s) include:



CAUTION
HOT WORK IN PROGRESS
STAY CLEAR

Hot work areas, temporary or fixed, shall not contain combustibles. If combustibles cannot be removed from the area they shall be shielded to prevent heat or sparks from igniting them. Openings in walls, floors, ceilings, ducts, shafts, etc. shall be covered to prevent the passage of sparks to adjacent or hidden spaces containing combustible materials. Welding curtains shall be required for welding in exposed (outdoor) work areas and fixed work areas. Fixed hot work areas shall have non-combustible floor surfaces. Hot work shall **NOT** be performed on containers or equipment that contain or have contained flammable liquids, gases or solids until the container or equipment have been thoroughly cleaned, inerted or purged. "Hot Tapping" shall be allowed on tanks or pipe lines where such work is to be performed by approved (trained/certified) personnel. Automatic sprinkler protection shall not be impaired while hot work is being performed. Non-combustible barriers shall be in place for hot work near active sprinkler heads and piping. The University Fire Marshal for NC State EH&S shall approve hot work in areas where fire sprinklers are impaired or non-existent. A dedicated fire watch shall be established by a responsible person trained in the use of portable fire extinguishers during hot work. Not less than one portable extinguisher with a minimum rating of 2-A 20-B:C shall be readily accessible within 30 feet of the hot work area. Extinguishers may **NOT** be removed from mounted locations in NC State buildings for standby use during hot work. Before hot work is permitted and not less than once per day while the permit is active the hot work area shall be inspected by the person responsible for authorizing the hot work operations (NCSU F&LS) to guarantee the area remains safe for hot

NC State University Design and Construction Guidelines

Division 01 NC State's Requirements

work. A pre-work hot work area check shall be conducted prior to the hot work starting to ensure that all equipment in use is safe, hazards are recognized and protected (or removed), and proper signage or other protective measures are in place. The following shall be determined in the pre-work check:

1. Hot work equipment to be used shall be in satisfactory condition and in good repair.
2. Hot work site is clear of combustibles or combustibles are protected.
3. Exposed construction is of non-combustible materials or protected if combustibles are present.
4. Openings are protected.
5. Floors are clear.
6. No exposed combustibles are on the opposite side of partitions, walls, floors, or ceilings affected by the hot work.
7. A fire watch is in place.
8. Approved actions have been taken to prevent accidental activation of suppression or detection systems.
9. Fire extinguisher(s) are operable and available.

Hot work permits can be obtained the day of the hot work commencing by contacting the NC State Fire & Life Safety Office at 919-515-2568, alternatively an individual may call 919-515-3000 (NC State Univ. Police) and request a hot work permit response from the Fire & Life Safety Office. A representative from the office will report to the location requested as soon as possible to issue the hot work permit. During the issuance of the permit the hot work area will be established, the equipment will be inspected, and the work to be completed will be reviewed. Hot Work permits will be issued for up to 72 hours for hot work not involving welding in temporary work areas. Welding work in a temporary hot work area will be permitted on a daily basis. For extended operations beyond 72 hours, a fixed hot work area can be established and the permit issued for a longer period of time. Extended hot work operations will require a daily check-in with the Fire & Life Safety Office to confirm continued work and site conditions. If a Fire Alarm Interruption is desired to minimize the risk of activating the fire detection system there is a 3-day notice required by NC State University Facilities Operations/Energy Systems. The NC State Project Manager will have to pursue the Fire Alarm Interruption before the work can be scheduled or the Hot Work Permit requested. Fire Alarm devices will still have to be protected during the hot work to prevent contamination of the devices. Protective measures must be removed daily when the work period ends for the day and there is not a fire watch in place. Hot work requiring a permit over a weekend or during a University

NC State University Design and Construction Guidelines


Division 01 NC State's Requirements

closure needs to be planned for, approved, and permitted before the close of business on the last day prior to the weekend or closure. An after-hours hot work permit request will result in a 2-hour minimum charge to the project from the Fire & Life Safety Office (\$42/hr.).

The issued hot work permit must be conspicuously posted in the space where the hot work is being performed. The permit must be maintained by the person performing the hot work or on-site for 48 hours after the work is completed. A 30-minute post work inspection is required of all hot work by the person performing the hot work. The area must be checked for hot surfaces, embers, slag, or other heated materials resulting from the hot work.

NC State Fire & Life Safety (Environmental Health & Safety)
2610 Wolf Village Way
Campus Box 7220
919-515-2568
firesafetyhelp@ncsu.edu

Jon Brann
Fire & Life Safety Manager
University Fire Marshal
NC State Environmental Health and Safety
919-513-2120
jbrann@ncsu.edu



NC State University Design and Construction Guidelines

Division 01 NC State's Requirements



HOT WORK PERMIT

Environmental Health and Safety
Fire & Life Safety Section

Fire & Life Safety Office 919-515-2568
University Police 919-515-3000
EMERGENCY: DIAL 911

Building: _____

Location: _____ Issue Date: ____/____/____

Issued to: _____ Expiration Date: ____/____/____

Only work documented on this permit is allowed to take place.

Welding	Soldering	Hot Work Information	Cutting	Grinding	Y	N	N/A
Has an inspection been done of the unit/equipment to be worked on?							
Where inspected, was it found to be free of corrosives, toxics, and flammable materials?							
Is there an adequate supply of fresh air?							
Do the unit/equipment and atmospheric conditions permit safe work?							
Has the unit/equipment been secured from utility connections?							
Has the equipment been adequately protected? (Specify):							
Have combustible materials been removed from the area?							
Are nearby sewers protected, if applicable to the work being performed?							
Required fire protection (Circle): Extinguisher Welder's blanket/curtains Special Fire Watch Disconnect							
May underground or overhead obstructions or utilities be encountered?							
Are there any radiation concerns or precautions to follow?							
Have MSDS sheets been referenced for adverse reactions to the work being performed?							
Are any special procedures required during the work (pyrophorics, asbestos, confined space)?							
Is it permissible to use: Electrical equip. Y N Diesel equip. Y N Gasoline equip. Y N Propane equip. Y N							
Is welding permitted?							
Notes:							

Cooking Information

Fuel Supply: _____

Fire Extinguisher type and size: _____

Will there be grease fried foods? Y N

Valid Pressurized Liquid Extinguisher on site ('Purple K')? Y N

Permit recipient: _____ Issued by: _____

Contact #: _____ Title: _____

NC State University Design and Construction Guidelines

Division 01 Temporary Facilities

1.0 Purpose

- A. The following guidelines for the use of temporary facilities during construction shall be incorporated into the Construction Documents.

2.0 General Requirements

- A. Project Signs – Project signs are not allowed. Directional signs for material deliveries are allowed within the construction area, if required, and shall be 4' wide x 2' high maximum, black and white only. The NCSU Project Manager shall approve the design of the sign and the sign text. **[Designer shall coordinate with NCSU PM for a sample layout of temporary construction sign.]**
- B. **[Designer shall provide detailed pedestrian detour plans as part of the contract documents** and show quantity, location, and layout of pedestrian detour signs on the detour plan.] Sidewalks shall remain open and accessible during construction. Should sidewalks require closure, an accessible and safe temporary (concrete, asphalt or plywood) pedestrian path around construction shall be required if an alternative accessible route is not close by. Temporary paths shall be shown on the contract documents clearly showing path and type of construction.
- C. The construction site shall be secured. Contract documents shall clearly indicate limits of construction and location of the construction fence. The fence shall be constructed of heavy-duty chain link material, have a minimum height of six feet and shall have a continuous top tubular rail. Swing gates shall be included at every access to the enclosed area and shall be lockable. The fence shall have an integral visual barrier or shall have shading type material applied and maintained for the duration of the project. Locks for the gates shall be interlocked with a padlock provided by NCSU in order to allow access by NCSU or other emergency personnel in case of emergency.
- D. Walks, Root Zones, and Lawn Protection - A permit, issued by NC State Grounds Management, is required for vehicular access to brick and landscape areas. For single loads up to 9000 lbs., a $\frac{3}{4}$ " minimum plywood base shall be placed over brick paving, root zones of trees, and lawn areas to be protected from vehicular work traffic at a construction site. For single loads over 9000 lbs., two layers of $\frac{3}{4}$ " plywood is required. Root zones and lawn areas shall not be covered with plywood for more than 3 consecutive days.
- E. For projects of duration longer than 3 days or requiring multiple heavy loads into a construction landscape protection zone, a construction entry road shall be included in the contract documents **[Designer must show on the contract drawings, including a detailed cross section]** to indicate access route for heavy loads into the site. This construction entry shall consist of 10' x 16' oak logging mats on 6" coarse, chipped, hardwood placed on a permeable structural, filter fabric, top-dressed with an additional 10" of hardwood mulch. Mulch and logging mats shall be supplemented throughout the project to keep the access area structurally functional. At the end of the project the

NC State University Design and Construction Guidelines

Division 01 Temporary Facilities

logging mats shall be offered to Facilities Operations for salvage or disposed of off site at the discretion of the Owner.

- F. All pruning of existing plant materials, including roots and limbs, for construction clearances shall be done by a trained, licensed, insured arborist and according to standards set forth in the National Arborist Association publication "Standards for the Pruning for Shade Trees". All pruning shall be coordinated with and inspected by NC State Grounds Management. **[The Designer and University Landscape Architect shall assess the necessity for this work during the design phase and determine whether work will be performed by contractor or NC State Grounds Management. Designer shall identify on contract drawings who will perform pruning.]**

- G. Transportation/Parking. **[Designer shall incorporate latest NC State Transportation Guidelines for Parking, Traffic Control and Road Closures.]**

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

[The designer shall incorporate this document into the specification in its entirety.]

1.0 Purpose

- A. The purpose of this guideline is to define NC State contractor safety requirements. This guideline is intended to be a supplement to the General Conditions of the contract.
- B. The Designer or Construction Manager shall incorporate this document into the Project Manual in its entirety.
- C. Contractors and subcontractors are responsible for the safety of their employees and all persons on and around a work site. Contractors are solely responsible for the development and implementation of their safety programs. This document does not relieve the duty and responsibility of contractors, subcontractors, their agents, employees, and other persons performing portions of the work on a project to comply with federal, state, and/or local laws or regulations that relate to work site safety.

2.0 Scope

- A. This document provides contractors with the University's specific requirements that must be incorporated into the contractor's Site-Specific Safety Plan. This document is not designed or intended to replace the contractor's safety program, nor to address every possible safety, environmental, or health hazard associated with the contractor's work. In the event that the contractor's safety program includes a requirement or practice that is more stringent than set forth herein, the more stringent shall be followed. This document does not relieve the contractor of this obligation to: (1) control the means and methods by which its employees and any subcontractors perform work, and (2) independently ascertain what health and safety practices are necessary for the performance of the work.
- B. No specific requirements herein shall be construed to limit, replace, or supersede applicable provisions of federal, state, or local laws or regulations. [Occupational Safety and Health Administration \(OSHA\) Regulations; Standard Number 29 CFR 1926](#) are the foundation of these Guidelines.
- C. Deliverables
 - 1. Competent Person Designation (see attached form) (4.0/C)
 - 2. Verification of OSHA 30 or OSHA 10 compliance, based on project requirements. (4.0/D/1/b)
 - 3. Contractor Site Specific Safety Plan (SSSP). (4.0/I)
 - 4. Summary of the Daily Safety Inspections documented as part of regular project

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

meeting minutes. For projects bid through Construction Services summaries of Daily Safety Inspections will be documented as agreed upon at the pre-construction meeting. (4.0/F/1)

5. Regular (min. monthly) Safety Reports. (4.0/F/2)
6. Traffic Control Plans (when impact exists) (4.0/QQ/1)

3.0 Reference Materials

- A. The following reference materials are required to be available upon request at every job site:
 1. OSHA Regulations published by NC Department of Labor (DOL) (Available at (800) NC-LABOR, <http://www.nclabor.com/pubs.htm>).
 2. Safety Data Sheets (SDS) for all chemical products the contractor has brought to the worksite.
 3. The written Safety Plan of the Contractor or Subcontractor.
 4. Site inspection documentation.
 5. Worksite employee training records.
 6. Mishap reports and investigations.

4.0 General Responsibilities

- A. The contractor must notify the NC State Project Manager in writing at least 10 days prior to:
 1. Utilizing powder-actuated tools
 2. Starting operations that will produce excessive odor, dust, and noise affecting occupied buildings or work near air intakes
 3. Using a combustion engine indoors
 4. Using a mobile crane or tower crane (50-day notice is required)
 5. Breaking ground for an excavation or trench
 6. Using a laser
 7. Using any source of radioactive material
 8. Working with lead or asbestos-containing materials
 9. Performing energized electrical work
 10. Working on or near active underground utility infrastructure (steam, chilled water, natural gas, water, etc.)
 11. Entering electrical distribution assets

Violation of any safety, security, or environmental requirement may result in the permanent removal of the contractor or their employees from the NC State premises.

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

B. Construction Management

1. The contractor is responsible for compliance with all federal, state, and local laws, regulations, standards, executive orders, etc. applicable in part or whole pertaining to the scope of work.
2. Contractors are responsible for compliance with all applicable NC State safety practices, procedures, policies, standards, and requirements.
3. Contractors are responsible for providing qualified and competent personnel to perform activities under the scope of work. Contractors must provide documentation of training prior to beginning work on-site.
4. Contractors are responsible for ensuring that subcontractors, their agents, employees, visitors, and other persons performing portions of the work on a project comply with federal, state, and/or local laws or regulations that relate to work site safety.
5. Contractors are responsible for ensuring that subcontractors are informed of and comply with all applicable requirements within the scope of work.

C. Competent Person Designation

1. Contractors shall designate a competent person for activities as specified in OSHA 29 CFR 1926. Such activities include, but are not limited to, the following activities, as applicable to the job:
 - a. general provisions
 - b. ionizing/non-ionizing radiation
 - c. gases, vapors, fumes, mists, dust
 - d. ventilation
 - e. hazard communication
 - f. lead
 - g. asbestos
 - h. personal protective equipment
 - i. hearing conservation
 - j. respiratory protection
 - k. rigging and material handling equipment
 - l. welding, cutting, brazing
 - m. electrical
 - n. scaffold
 - o. fall protection
 - p. cranes (overhead and mobile)
 - q. motor vehicles and equipment
 - r. excavations
 - s. concrete and masonry
 - t. steel erection
 - u. demolition

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

- v. stairways and ladders
 - w. toxic and hazardous substances.
 - 2. OSHA 29 CFR 1926.32(f) "Competent person" means one who is capable of identifying existing and predictable hazards in the surroundings or working conditions that are unsanitary, hazardous, or dangerous to employees, and who has authorization to take prompt corrective measures to eliminate them.
- D. Contractor Safety Personnel
 - 1. Safety Representative
 - a. For all projects contractors must designate a Safety Representative prior to the start of the project. The Safety Representative may be the Project Superintendent and is responsible for all safety concerns related to the construction operations.
 - b. For formally contracted projects (>\$500k), the Safety Representative must have completed, at a minimum, an OSHA 30-hour Construction Safety Course. For informally contracted projects (<\$500k), the Safety Representative must have completed, at a minimum, an OSHA 10-hour Construction Safety Course.
 - c. The Safety Representative must actively monitor the job site for safety issues on a daily basis. The Safety Representative may have additional site duties outside the scope of safety; when the safety representative is not on the project site, a competent designee must be assigned to monitor safety on the site.
 - 2. Safety Professional
 - a. **When appropriate, the contractor shall provide a full-time safety professional assigned to the project. The duties of the full-time safety professional must be strictly limited to safety-related activities, with no additional job site duties.**
 - b. Safety professionals must have one or more of the following credentials: a professional certification (beyond an OSHA 30-hour course), a college or professional degree related to safety and health, or significant previous experience and skills necessary to thoroughly understand the health and safety hazard and controls relevant to the project. The designation and adequacy of qualifications of the full-time safety professional shall be reviewed and accepted by the University prior to the commencement of the work.
 - c. Project-specific requirements for a full-time safety professional will be addressed in the contract documents and discussed during the Pre-Bid Meeting.
- E. Daily Pre-Job Meetings
 - 1. A pre-job meeting (i.e. "Tailgate" or "toolbox" meeting) shall be held at the

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

beginning of each work period (normally in the morning before leaving the yard or work staging area). The pre-job meeting should include a discussion of the scope of work to be completed, associated hazards, and means and methods to mitigate the hazards. The pre-job meeting must be led by the supervisor or other competent person.

F. Safety Inspections

1. Daily Inspections: The Contractor shall perform daily job inspections and correct any unsafe conditions or actions. A summary of these inspections will be reviewed as a portion of and captured in the minutes of the weekly Owner, Designer, and Contractor job meetings.
2. Monthly Inspections: For projects with a duration of more than one calendar month (4 weeks), the safety inspection must be documented and include, at a minimum, the name of the person performing the inspection, the date, a checklist of items observed, any identified safety concerns, and actions taken to address identified concerns.
3. University Project Visits: The NC State Project Manager, or another owner representative, may perform unscheduled visits to project sites to address adherence to the Contractor Safety Requirements or Site-Specific Safety Plans. Any safety concerns identified will be reported to the responsible contractor for prompt mitigation.

G. Mishap Reporting: All mishaps occurring on the project site must be investigated to determine causes and actions must be taken to prevent recurrence. Mishaps resulting in a recordable injury requiring medical treatment or damage to NC State property must be reported in writing to the NC State Project Manager as soon as possible but no later than 24 hours from occurrence; the Project Manager shall be notified immediately of mishaps resulting in life-threatening injury.

H. The Contractor shall address safety concerns at regularly scheduled meetings with subcontractors.

1. Contractor Site-Specific Safety Plan (SSSP) - The Contractor must develop and implement an SSSP. The SSSP is a comprehensive safety plan for his or her employees, which covers all aspects of onsite construction operations and activities associated with the contract. This plan must comply with all applicable health and safety regulations and any project-specific requirements. The SSSP must be submitted to, reviewed, and accepted by NC State before beginning any on-site work activities.
2. As applicable to the project, these items must be included in the SSSP:
 - a. Scope of Work
 - b. Emergency Procedures
 - c. 24-hour emergency points of contact

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

- d. Identification of Designated Competent On-Site Personnel (per OSHA requirements)
- e. Designated On-Site Safety Personnel
- f. Safety orientation program
- g. Site logistics Plan: address public (student, faculty, staff, visitor) safety, traffic plan, equipment and lay-down areas, site security, dust containment, etc.
- h. Minimum PPE requirements
- i. Hazard Assessment (for defined project tasks) - include hazard identification and mitigation
- j. Mishap reporting and investigation procedures
- k. Safety inspection/audit procedures
- l. Sub-contractor requirements

5.0 General Requirements

- A. Asbestos - If asbestos-containing materials are uncovered during construction, NC State must be notified immediately. Do not attempt to remove the material. Contractors shall comply with provisions of the [State Construction Office Asbestos Abatement Guidelines and Policies](#) and the [NC State Asbestos Management Plan](#).
 - 1. If asbestos-containing material is present in any building material and is in good condition (i.e. non-friable) and will not be disturbed during construction, the material may be left in place. If asbestos-containing material is disturbed during construction activities, then it shall be removed; removal shall be performed by appropriately qualified and accredited personnel and in accordance with federal, state, and local regulations.
- B. Compressed Gas Cylinders
 - 1. Compressed gas cylinders shall be properly used, stored, and maintained as per federal, state, and local requirements.
 - 2. Cylinders shall not be stored in a location in which they are subject to mobile equipment traffic (including vehicles) unless adequately protected.
- C. Confined Space Entry
 - 1. Contractors required to enter a confined space at NC State must have and implement a written confined space entry program in accordance with OSHA 1926 Subpart AA Confined Spaces in Construction or OSHA 1910.146 permit required confined spaces, as applicable.
 - 2. Controlling contractors (those with overall responsibility for construction at the work site) must ensure space entry coordination when more than one entity enters the space.
 - 3. Each contractor must have a competent person who will identify confined spaces associated with the scope of their work. Before entry into a permit-required confined space, contractors must obtain the following information from the controlling contractor (when there is no controlling contractor, the contractor will obtain the information from the NC State Project Manager):

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

- a. The location of each known permit space associated with the project scope;
 - b. The known hazards or potential hazards that make it a permit space;
 - c. Any precautions needed to be taken based on the known hazards or potential hazards.
4. Each contractor performing work in a permit space must perform a hazard assessment specific to the work to be performed and establish corresponding hazard controls.
 5. A competent person from each contractor performing work in a permit space must complete and sign [Appendix F](#) to the [NC State Confined Space Entry Program](#).
- D. Contaminated Soil - If soil or any materials appear to be contaminated, the NC State Project Manager must be notified immediately. The NC State Project Manager will contact NC State EHS for assistance at (919) 515-7915.
- E. Electrical Power Lines (Overhead) - The contractor shall have a trained and knowledgeable observer (signal person) within sight of the operator and the overhead lines that will effectively provide guidance and clearance information to the operator as the equipment may approach the minimum approach distances. Advising the operator shall be the signal person's one and only task. When conducting any work with a crane, derrick, or hoist in the vicinity of any overhead electric power transmission or distribution line, the contractor shall observe all clearance requirements dictated by all applicable OSHA rules, as specifically contained within 29 CFR 1910 - Standards for General Industry, CFR 1926 - Standards for Construction, IEEE C2 - NEC, NFPA 70 - NEC, the NCSBC, ANSI standards, and other applicable NC State safety guidelines and requirements. Further, no crane, derrick, or hoist operator or contractor shall conduct any operation at any distance closer than 20 feet to any electric power line lower than 200 kV or closer than 35 feet to any electric power transmission line at voltages higher than 200 kV and lower than 250 kV, unless the requirements of OSHA 1926 Sub CC for preventing encroachment/electrocution are strictly followed.
- F. Elevators/Material Hoists
1. Any persons operating elevators/hoists must be trained to do so. Documentation shall be kept onsite.
 2. No elevator/hoist with a defect shall be used.
 3. Elevator/hoist safety devices shall not be overridden or made inoperable.
- G. Emergency Equipment- The following shall not be moved, blocked, disabled, or rendered inaccessible unless authorized by NC State:
1. Fire equipment
 2. First aid equipment, fire blankets, stretchers, eyewash fountains, and safety showers
 3. Fire protection, hydrants, and detection systems
- H. Emergency Medical Treatment - To receive immediate assistance for emergency medical treatment call 911.
- I. Environmental and Chemical Requirements

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

1. Contractors must provide NC State with a list of all chemicals to be used on NC State property and maintain a copy on-site of the SDS for each chemical prior to being brought on-site. Each chemical container must be labeled clearly with the identity of the chemical and any associated hazards in accordance with the OSHA Hazard Communication Standard (1910.1200).
 2. Contractors must follow the safety procedures recommended by the manufacturer or seller of any chemicals, tools, equipment, or other materials. Contractors are to remove all empty containers, excess chemicals, and chemical waste from NC State property.
 3. For all chemical incidents, contractors shall call 911 and also notify the NC State Project Manager.
- J. Excavation and Trenches - Before doing any excavation work, the Contractor must locate all utilities by calling the local utility locator service and NC State.
- K. Excavations
1. Underground Facilities Locate. Contractors shall ensure underground installations and facilities are identified by calling 811 (Call Before You Dig) before performing any excavating activity. Note: excavation includes movement or removal of earth, rock, or other materials in or on the ground by use of manual or mechanized equipment. This is required for any project with earth-moving activities before you dig so that underground facilities can be identified and avoided. Detailed instructions and requirements can be found at nc811.org.
 2. Competent Person. Trench and excavation work must be performed under the direction of a competent person. Responsibilities include: classifying soil, inspecting protective systems, monitoring water removal, and conducting site inspections.
 3. Cave-In Protective Systems. A protective system is required by OSHA-1926 Subpart P for trenches and excavations that are 5 feet or more in-depth OR if the competent person has examined the ground and finds an indication of a potential cave-in. Protective systems typically include sloping/benching, shoring, or shielding. To determine what protective systems are appropriate, the competent person must first determine the soil type: Stable Rock, Type A, Type B, or Type C soil. Type C soil is the least cohesive and therefore, the least stable. No work shall be permitted in excavations where water has accumulated unless the integrity of the excavation has been protected.
 4. Excavations >20 feet in depth or that cannot comply with OSHA requirements require written approval by a Registered Professional Engineer (RPE).
 5. A ladder, stairway, ramp, or other means of access must be provided within the excavation when excavations are >4 feet in depth.
 6. Barricades (stop-logs) shall be provided where vehicles or mobile equipment are used near or adjacent to excavations.
 7. Spoil piles must be placed a minimum of 2 feet from the edge of the excavation.
 8. Air monitoring must be performed if the excavation is >4 feet in depth and there is a potential for a hazardous atmosphere to exist.
- L. Exit Routes

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

1. Exit routes must be maintained at all times during construction.
 2. Lighting and marking must be adequate and appropriate.
 3. Exit routes must be kept free of explosive or highly flammable furnishings.
 4. Exit routes must be free and unobstructed. No materials or equipment may be placed, either permanently or temporarily, within the exit route. The exit access must not go through a room that can be locked, such as a bathroom, to reach an exit or exit discharge, nor may it lead into a dead-end corridor. Stairs or a ramp must be provided where the exit route is not substantially level. No materials shall be stored in a stairwell.
- M. Explosives: Blasting on university property is prohibited.
- N. Fall Prevention. A fall hazard is any condition on a walking-working surface that exposes an employee to a risk of a fall on the same level or to a lower level. Examples of fall hazards include, but are not limited to: floor openings, hoist areas, roofs, leading edges, scaffolding, ramps, etc.
1. Preventing or protecting falls from height may be necessary at any height given the circumstances, but is required when an employee is at a height of 6 feet or more above a lower level.
 2. Contractor work generally falls within construction industry applications, where acceptable methods depend on the type of work being performed: unprotected sides or edges, roof work, leading edge, etc. In all cases, contractors shall comply with the respective OSHA standards.
 3. Contractors shall ensure that every employee required to work at unprotected heights (greater than 6 feet) is trained in fall hazard recognition and prevention.
 4. **Guardrail System.** A guardrail system provides the highest level of protection and is always preferred. The system must be capable of supporting 200 lbs. in any direction and still maintain its integrity. The individual heights of the components must conform to the following minimum standards:
 - a. The top rail of the system must be at a height of 42" (+ or – 3");
 - b. the mid rail must be at a height of 21" with a 3" variation possible;
 - c. the toe board must have a minimum vertical height of 3.5".

Note: The building code has more stringent requirements for permanent installations.
 5. **Personal Fall Protection Systems.** At times, it is necessary to work in areas where guardrails cannot be constructed; in these instances, a personal fall protection system must be used. Personal Fall Protection Systems are systems (including all components) that provide protection from falling or that safely arrest a fall. Examples include travel restraint and personal fall arrest. All components of this system shall meet the applicable design requirements as specified in OSHA 1910, 1926, or ANSI Z359. All components shall be inspected by the wearer prior to each use and at least annually by a competent person. No employee may use a personal fall protection system without proper training and an understanding of proper use and safe application of the system.
 - a. **Travel Restraint System.** A travel restraint system is a combination of an anchorage, anchorage connector, lanyard (or other means of connection),

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

and body support that the wearer uses to eliminate the possibility of going over the edge of a walking-working surface. Anchorages for travel restraint systems shall have a strength capable of sustaining static loads of at least 1,000 lbs. (per person) or two times the foreseeable forces for certified anchorages. Anchorage connectors, lanyards (or other means of connection), and body support devices shall be used in accordance with the manufacturer's requirements. The system shall be installed so that a fall cannot occur; therefore, a rescue plan is not required.

- b. **Personal Fall Arrest System.** A personal fall arrest system is a system used to safely arrest a user in a fall from a walking-working surface. It includes an anchorage, anchorage connector, and a full-body harness. The means of connection may include a lanyard, deceleration device, lifeline, or a suitable combination of these. Equipment must be worn and used in accordance with the manufacturer's requirements. Anchorages for personal fall arrest systems shall have a strength capable of sustaining static loads of at least 5,000 lbs. (per person) or two times the maximum arresting force for certified anchorages. The system shall be installed so that should a fall occur, the wearer will not contact the lower level or any other obstruction. Since there is a potential for a fall to occur, a rescue plan written by a qualified person is required.
- c. **Warning Line System.** A warning line may be used for construction roofing work when closer to the fall hazard than 15ft, but no closer than 6ft and in conjunction with one of the following: a guardrail system, a safety net system, a personal fall protection system, or a safety monitoring system. A warning line system shall conform to regulatory requirements and enclose all authorized employees conducting work protected by the Warning Line System. Refer to OSHA 1926.502(f).

O. Fire Protection and Prevention

1. The contractor shall be responsible for the development and maintenance of an effective fire protection and prevention program at the job site throughout all phases of the construction. Contractors shall perform inspections on fire extinguishers monthly. Contractors shall immediately replace fire extinguishers that do not pass inspection.
2. Fire cutoffs shall be retained in buildings undergoing alterations or demolition until operations necessitate their removal.
3. If work requires the disabling of Fire Protection Devices, then the Contractor must request a Fire Alarm Disconnect; through the appropriate NC State process; beginning with the Project Manager. No alarm shall be disabled at any time by the Contractor.

P. Hand and Power Tools

1. All hand and power tools and similar equipment, whether furnished by the employer or the employee, shall be maintained in a safe condition. Any tool found not in proper working order, or that develops a defect during use, shall be immediately removed from service and not used until properly repaired.
2. All tools shall be used, operated, and maintained in accordance with OSHA and manufacturer requirements.

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

- Q. Hot Work Permits - A Hot Work Permit is required when any indoor or outdoor work will involve hot work, defined as operations including cutting, welding, thermitic welding, brazing, soldering, grinding, thermal spraying, thawing pipe, installation of torch-applied roof systems or other similar activities. Requirements for Contractors performing this work are contained in the NC State Hot Work Permit Program which is a part of the specifications package and can also be found in the [Hot Work Permit Form](#).
- R. Housekeeping
1. The Contractor must maintain a clean and orderly project job site. The Contractor shall maintain NC State's pathways free of rocks, mud, and other miscellaneous construction debris. The Contractor shall prevent the accumulation of dirt, dust, and/or other debris on NC State's roadways. The Contractor shall clean the travelways on a daily basis. (Refer to project specifications for requirements.)
 2. Waste material and debris must be removed from the work and access areas at least once a day. Waste material and debris should not be thrown from one level to another but should be carried down, lowered in containers, or deposited in a disposal chute.
 3. Materials must be neatly piled, stacked, or otherwise stored to prevent tipping or collapsing. Materials must be carefully stacked and located so they do not block aisles, doors, fire extinguishers, safety showers, eyewash stations, fixed ladders, or stairways.
 4. Material to be lifted by crane or other hoisting devices must not be stored under overhead power lines.
 5. No materials may be stored on penthouses, roofs, or other areas until a specific area is assigned by NC State for a specific project.
 6. Adverse Weather: If NC State becomes aware of an adverse weather event, the NC State Project Manager shall notify the construction superintendent, and the contractor shall perform a job site review to ensure any debris or construction materials are secured and protected from the elements.
- S. Illumination - Construction areas, ramps, runways, corridors, offices, shops, and storage areas shall be lit to not less than the minimum illumination intensities required by OSHA.
- T. Ladders - All ladders must meet OSHA requirements.
- U. Lasers
1. Lasers must comply with the OSHA Construction Industry Standards.
 2. Lasers must be low-power (<5mw) devices with visible beams. Lasers to be used must bear a label indicating this maximum power output. Lasers that do not bear this label shall not be used.
 3. "Laser in use" signs shall be posted according to OSHA requirements.
 4. Lasers must be used in a manner that will not risk exposure to others.
- V. Lead
1. Lead may be found in certain painted surfaces. A check for lead presence should be conducted prior to certain activities such as grinding, sanding, or burning over

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

painted surfaces. If lead-containing paint is disturbed or a material is questionable the NC State Project Manager must be notified immediately. Do not attempt to remove the material.

2. Hot Work over lead-painted surfaces is generally not permitted.

W. Lock Out/Tag Out

1. All contractors that work on energized equipment with any hazardous energy source are required to have a hazardous energy control (i.e. lockout tagout) program. The program shall specify policies and procedures for de-energizing, verifying de-energizing, and securing the source potential using energy isolating devices and applying locks/tags or implementing other forms of hazardous energy control as specified in OSHA standards. Types of potential energy sources include, but are not limited to:

- a. Electrical (refer to the section of these requirements titled "Electrical")
- b. Pneumatic
- c. Hydraulic
- d. Thermal
- e. Kinetic (motion)
- f. Hazardous gas, liquid, air
- g. Radiation
- h. Lasers

2. When multiple contractors are performing work on the same project, hazardous energy control procedures shall be coordinated by the controlling entity which includes establishing device standardization.

3. Contractors shall ensure site personnel are trained on the hazardous energy control program.

4. Central [Utility Plant \(CUP\) - Lockout Tagout Procedure](#)

- a. Contractors with the need to perform LOTO operations within the operating CUP shall be trained in accordance with the procedure and comply with applicable sections of the procedure. The contractor is responsible for providing this training; a copy of this procedure will be provided to the contractor.
- b. Contractor management shall ensure that authorized personnel are assigned to perform work in which they are qualified.
- c. Contractor management shall comply with applicable sections of the procedure.

X. Mobile Cranes, Tower Cranes, etc. (Reference OSHA 1926 Subpart CC).

1. Prior to the setup or operation of any crane on university property, the NC State Project Manager (or another point of contact) shall be notified; notification must be made with as much lead time as possible, but no fewer than fifty (50) working days
2. Cranes shall be set up and operated in compliance with the manufacturer and applicable OSHA requirements.
3. Contractors are responsible for ensuring ground conditions are capable of

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

supporting the equipment and load, which will include performing underground facilities/utilities location (i.e. 811 calls) as well as factual confirmation of necessary compaction capacities. This confirmation is to be by third-party inspection services, at the expense of the contractor.

4. No lifts may occur over occupied spaces unless a registered structural engineer evaluates and certifies that the building can withstand the impact of a load being dropped on the building as a worst-case scenario. If it is determined that the building cannot withstand the impact without compromising the structure, areas of the building within the load fall zone must be evacuated during the duration of the lift. This evacuation process must be a part of the lift plan and managed by the contractor.
5. The crane contractor shall provide equipment documentation, including the annual inspection and the last monthly inspection. Documentation must be signed.
6. Crane operators shall be certified by an Accredited Crane Operator Certification Agency for the type of equipment operated. Examples of such agencies, include, but are not limited to:
 - a. National Commission for the Certification of Crane Operators (NCCCO)
 - b. National Center for Construction Education and Research (NCCER)
 - c. Operating Engineers Certification Program (OECF)
 - d. Electrical Industry Certifications Association (EICA)

Additionally, the crane operator's employer must attest that the operator was evaluated to verify the operator demonstrates skills and knowledge to safely operate the equipment as well as the ability to recognize and avert risk, as required under 29 CFR 1926.1427 (f).

7. All rigging personnel and signal persons shall be qualified in accordance with OSHA 1926 Subpart CC.
8. Crane Lift Plan. A lift plan is required for any lift in a location not under the exclusive control of the contractor, including lifts affecting NC State property, structures, employees, students, or visitors. Each lift plan must be developed by a qualified person and include at least the following:
 - a. The identity of the controlling entity, meaning the employer with the overall responsibility for construction operations associated with the crane lift.
 - b. Identify a lift director (i.e. primary signal person) and method of communication (hand signals, radio, etc.).
 - c. Contractors conducting crane operations are required to obtain required FAA permits according to 14 CFR Part 77; to be submitted with the lift plan.
 - d. Equipment positioning locations, including load staging and movement and paths to and from the working position.
 - e. Equipment specifications including load and reach capacities.
 - f. Current qualifications, certifications, and licenses of operators and

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

riggers.

- g. For lifts involving more than one crane, the lift plan shall encompass all cranes.
- h. Fall Zone: The contractor shall identify the Fall Zone. The Fall Zone is the area (including but not limited to the area directly beneath the load) in which it is reasonably foreseeable that partially or completely suspended materials could fall. Spaces within the Fall Zone (including buildings, foot traffic, vehicle traffic, etc.) shall be barricaded to control access. The Fall Zone shall be cleared of personnel not participating in the lift.
- i. Wind limitations.
- j. Ground and subsurface stability at crane and load placement locations. The contractor must ensure a qualified person evaluates the crane set-up location to ensure ground conditions are sufficient. (See X., 3. above).
- k. Other conditions or factors that may affect the safety of the lift.
- l. A pre-lift meeting must be completed immediately before the lift and shall include all personnel involved with the lift and a thorough review of the elements and specifics of the lift plan and personnel assignments.
- m. Specify the distance to the closest energized lines and the applicable minimum approach distance of any lift component.
- n. Where items positioned by a crane lift are rigged at heights above easy reach height, the lift plan shall include safe attachment and de-attachment procedures and the control of exposure to fall hazards.
- o. The contractor must provide documentation of annual and monthly inspections for the previous 3 months. 1926.1412(f) & .1412(e).

Y. Electrical

- 1. Electrical Contractor shall ensure that their personnel using electrically powered equipment are trained to recognize electrical hazards, inspect and maintain electrically powered equipment, and on safe work procedures to prevent exposure to electric shock.
- 2. Premises Electrical Equipment. All electrical installations must comply with the National Electrical Code® (NEC®). Work associated with electrical equipment installed in accordance with the NEC® will be conducted in accordance with the NFPA 70E® Standard for Electrical Safety in the Workplace. NC State's goal is to minimize exposure to shock and arc flash hazards during the installation, repair, maintenance, and operation of electrical equipment, components, and systems.
 - a. Electrical power sources shall be de-energized, verified, and locked out prior to working on electrical equipment except when de-energization creates a greater hazard and a properly executed Energized Electrical Work Permit (EWP) has been completed.
 - b. Contractors performing electrical work must have their own energized electrical work program that includes a permit process.
- 3. Power Generation & Distribution: Work by Qualified Persons and Unqualified Persons working on or near power generation or distribution equipment is

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

addressed in OSHA 29CFR1910.269. It includes work on or directly associated with installations used for the generation, control, transformation, transmission, and distribution of electricity. Any work involving the NC State distribution system shall be coordinated by the NC State Project Manager (or other university contact person) in collaboration with the Facilities Division Power Systems group.

- a. Work involving the NC State electrical distribution system shall only be performed after authorization by the Facilities Division Power Systems group in accordance with the Power Systems Switching Procedure.
 - b. System Check-In/Out: Prior to entering any primary enclosure (substation, transformer, manhole, switch, switching station, etc.) of the NC State Power System the NC State Project Manager or other designated person shall send a text or email to group-powersystementry@ncsu.edu with the work location and brief description of the tasks to be performed (photos are welcomed). When exiting the enclosure, check out with NC State Power Systems using the same method. This is only for unescorted access. For example, if you're with a member of the Power Systems team there's no need to check in/out, but if that team member has to leave your work site, you're expected to check in and check out.
4. The contractor will follow all requirements as noted in NFPA 70E.
- Z. Mobile Elevating Work Platforms (MEWPs)
1. General Requirements.
 - a. MEWPs shall be operated in accordance with the manufacturer's requirements and specifications.
 - b. Employees must always stand firmly on the floor of the MEWP and must not sit or climb on the edge of guardrails, or use planks, ladders, or other devices for a work position. The guardrail system of the platform must not be used to support materials, other work platforms, or employees.
 - c. A personal fall arrest/restraint system shall be used in accordance with the manufacturer's requirements. A scissor lift with approved guardrails may be used without a personal fall arrest system when specified by the manufacturer, however, if there are designated anchor points, the use of a fall arrest/restraint system is required.
 - d. The MEWP must be used only in accordance with the manufacturer's operating instructions and safety rules.
 - e. The designed rated capacity for a given angle of elevation must not be exceeded.
 - f. At least 10 ft distance must be maintained away from overhead power lines with a nominal voltage of 50kV or less; 20 ft for power lines over 50kV (or if the voltage is unknown). Note: qualified workers using appropriately insulated MEWPs may approach closer than 10 ft when following provisions specified in OSHA 1910.268, 1910.269, and 1926 Subpart V, as applicable.
 - g. The manufacturer's rated load capacity must not be exceeded. The load and its distribution on the platform must be in accordance with the

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

manufacturer's specifications. The rated load capacity must not be exceeded when loads are transferred to the platform at elevated heights. Only employees, their tools, and necessary materials must be on or in the platform.

- h. A trained spotter with no other job duties is required when a MEWP is driven; the spotter will assess conditions that could pose a hazard to the operation (for example, drop-offs, holes, slopes, inadequate surface and support, obstructions, pedestrians, vehicles, debris, electric lines, etc.) and stop operations and alert the operator. The operator shall halt operations until hazards are adequately controlled.

2. Training

- a. Only personnel who have received training to operate the specific type(s) of MEWPs are authorized to operate them on NC State property.
- b. Training must include inspection, application, and operation of MEWPs (including recognition and avoiding hazards associated with their operation). Operators are only authorized to use MEWPs of the specific model for which they are trained and evaluated.
- c. Training must be provided by a person who has knowledge regarding the laws, regulations, safe use practices, manufacturer's requirements, and recognition and avoidance of hazards, and is familiar with the specific type(s) of MEWPs. Note: Personnel may not operate rented equipment unless qualified to operate the specific equipment; the rental provider or other authorized evaluator must provide familiarization training to satisfy this requirement.

3. Inspection, Maintenance, and Testing

- a. Each MEWP must be inspected, maintained, repaired, and kept in proper working condition in accordance with the manufacturer's operating or maintenance and repair manual or manuals. Maintenance inspections shall be completed at intervals no less frequent than annually.
- b. Before use, visual equipment inspections and a functional check must be performed before each shift in accordance with the manufacturer's operating manual. Any MEWP found not to be in a safe operating condition must be removed from service until repaired. All repairs must be made by an authorized person in accordance with the manufacturer's operating or maintenance and repair manual or manuals.
- c. Before and during use, visual worksite inspections must be performed and include workplace risk assessment. The workplace risk assessment includes identifying and evaluating hazards (for example, drop-offs, holes, slopes, inadequate surface and support, obstructions, pedestrians, vehicles, debris, electric lines, etc.) and establishing effective control measures. Uncontrolled hazardous situations must be corrected prior to the initial or continued use of the MEWP.

AA. Noise/Vibration

- 1. Noise-producing equipment, such as power drills, jackhammers, welders, etc., can create sound levels of 80dB(A) or greater in and around a construction area.

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

Notify the NC State Project Manager in advance to determine the appropriate times to operate high noise/vibration equipment for that project's location.

2. Appropriate personal protective equipment shall be used when working around high-noise/vibration equipment.

BB. Overhead Work

1. Work must not be performed above other personnel, including other contractor employees. Affected areas must be roped off or barricaded and marked to prohibit traffic.
2. Contractors must not climb on the heating and air-conditioning ductwork, plumbing steam piping, sprinkler piping, electrical cable trays, fixtures, or furniture or use as work platforms.
3. Contractors are expected to comply with OSHA fall protection requirements.

CC. Paints and Solvents - Contractors must provide the following safeguards:

1. Adequate ventilation must be maintained at all times when paints or solvents are being used. Refer to [NC State Odor Prevention and Dust Control in Occupied Buildings](#) for additional information.
2. Contractor personnel must use proper respiratory protection and protective clothing when the toxicity of the material requires such protection.
3. Flammable solvents and materials must be used with extreme caution when possible sources of ignition exist.
4. Flammable paints and solvents must be stored in an approved flammable liquid storage cabinet when storage is required inside buildings. Acids and flammables must never be stored together. If an approved flammable liquid storage cabinet is not available, flammable paints and solvents must be removed from the building.
5. Flammable liquids must be dispensed in a safety can with a flash screen bearing a Factory Mutual or Underwriters Laboratory (UL) approval.

DD. Personal Protective Clothing and Equipment - The contractor shall determine this minimum level of protective equipment to be worn on the job site (example: hard hat, eye protection, safety vest, gloves, and safety shoes); NC State expects contractors to conform to industry accepted minimum PPE standards, for example, hard hats, safety glasses, and protective toe footwear. Any additional safety equipment required by a specific activity shall also be worn and shall meet or exceed OSHA standards. This applies to ALL persons entering the job site.

EE. Powder-Actuated Tools

1. Powder-actuated tools are not to be used on NC State property unless specific approval is obtained from NC State prior to usage.
2. If approved, powder-actuated tools must be used in accordance with OSHA and manufacturer regulations.

FF. Power Vehicle Equipment

1. Only trained operators are allowed to use power vehicles on NC State property. Contractor management will be expected to provide proof of training if requested.
2. Generally, LP gas-powered trucks are not to be used inside NC State buildings. Prior approval from NC State is required.

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

3. The design of the LP gas-fueled industrial truck for use within NC State buildings must comply with the following:
 - a. LP gas-fueled industrial trucks must comply with NFPA 505-1982.
 - b. If trucks are in continuous use in a populated area, they must be equipped with a catalytic converter.
 - c. LP gas containers must not exceed the nominal 45 pounds of LP gas.
4. The following conditions and requirements will govern the use of LP gas-fueled vehicles inside the confines of NC State buildings and structures:
 - a. LP gas-fueled trucks must be removed from the building and parked at the end of each workday and not left unattended while in use. When the job requiring the vehicle is complete, the vehicle must be removed from the job site.
 - b. Trucks and tanks must not be refueled inside buildings.
 - c. All areas where LP gas-fueled trucks are used must be well ventilated.
5. All LP cylinders must be stored outside and secured by a chain in an upright position.

GG. Roof Safety

1. The contractor shall request authorization from NC State prior to accessing a roof.
2. During all rooftop operations, the contractor must provide fall protection measures in accordance with OSHA.
3. A Hot Work Permit and at least two appropriate fire extinguishers of the correct ABC type are required when performing hot work on roofs. Other persons acting as a Fire Watch shall be in place on the roof and on the floor(s) directly below the operation.

HH. Sanitation

1. Drinking Water - An adequate supply of water, meeting the U.S. Public Health Service Drinking Water Standards, shall be provided.
2. Washing Facilities
 - a. The contractor shall provide adequate washing facilities for employees engaged in the application of paints, coating, herbicides, or insecticides, or in other operations where contaminants may be harmful to the employees. Such facilities shall be close to the work site and shall be so equipped as to enable employees to remove such substances.
 - b. Hand soap or similar cleansing agents shall be provided.
 - c. Individual hand towels, cloth or paper, warm air blowers, or clean individual sections of continuous cloth toweling, shall be provided.
3. Toilet facilities shall be provided for employees according to OSHA requirements.

II. Scaffolding

1. The contractor shall erect, use, and dismantle scaffolding in accordance with OSHA and manufacturer regulations.
2. Competent Person. Scaffolds must be erected and dismantled under the

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

direction of a competent person. Responsibilities include, but are not limited to:

- a. Supervise and direct scaffold erection, moving, dismantling, or alteration.
 - b. Determine the feasibility and safety of providing fall protection for employees erecting or dismantling supported scaffolds. Employers are required to provide fall protection for employees erecting or dismantling supported scaffolds where the installation and use of such protection is feasible and does not create a greater hazard.
 - c. Inspect scaffold and scaffold components for visible defects before each work shift and after any occurrence that could affect a scaffold's structural integrity and ensure identified deficiencies are corrected,
 - d. Determine if it is safe for employees to work on scaffolds during storms or high winds.
3. **Access.** When scaffold platforms are more than 2 feet (0.6 m) above or below a point of access, portable ladders, hook-on ladders, attachable ladders, stair towers (scaffold stairways/towers), stairway-type ladders (such as ladder stands), ramps, walkways, integral prefabricated scaffold access, or direct access from another scaffold, structure, personnel hoist, or similar surface shall be used. Cross Braces shall not be used as a means of access.
 4. **Fall Protection.** Each employee on a scaffold more than 10 feet (3.1 m) above a lower level shall be protected from falling to that lower level; each employee on a suspended scaffold shall be protected by a personal fall arrest system attached to an independent anchorage.
 5. **Falling Object Protection.** Where the potential for tools, materials, or other equipment could fall from a scaffold, the area below must be barricaded, and personnel not permitted to enter the area OR effective means shall be implemented to prevent objects from falling.
- JJ. **Signs, Tags, and Barricades (references 1926 Sub G and ANSI Z535)**
1. **Signs and Tags:** Each sign and tag must include a signal word, symbol, and text.
 - a. **Signal words:**
 - (1) DANGER = the hazard will most likely result in serious injury or death;
 - (2) WARNING = the hazard could result in serious injury or death;
 - (3) CAUTION = the hazard would not likely result in serious injury or death;
 - (4) NOTICE = indicates important information, but is not directly hazard-related;Symbols or graphics are used to bridge language barriers and draw attention to the message.
 - b. Text is used to convey the safety message in a clear, concise manner.
 2. **Barricades.** Barricades must be installed for situations where a physical obstruction is necessary to deter the passage of people, vehicles, or equipment. When used, barricades must be installed at all points of access.
 - a. Barricades associated with traffic control in a public roadway must comply with the Federal Manual of Uniform Traffic Control Devices and the North Carolina Supplement. Coordinate with the NC State Transportation

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

Office.

- b. Barricades may take many forms on construction sites, but when used, they must clearly indicate the intent of the barricade. All barricades are required to include a sign that includes the name of the person responsible for the barricaded area, method for contacting the responsible person (ex. phone number), and clear and concise text describing the purpose of the barricade.

(1) CAUTION Tape Barricades should be used when the hazardous condition is not likely to cause serious physical harm but could result in injury. Standard CAUTION Tape must be used, which includes yellow tape with the word "CAUTION" in black letters. Personnel may enter the barricaded area only when implementing precautions to address the identified hazard.

(2) DANGER Tape Barricades are used when a serious or imminent danger may exist. Standard DANGER Tape must be used, which includes red tape with the word "DANGER" in black letters. Only personnel specifically authorized by the person responsible for the barricaded area may enter the barricaded area.

- KK. Silica (Respirable Crystalline Silica) – The following requirements apply to all operations involving exposure to respirable crystalline silica. Examples of such operations include: cutting, grinding, drilling, or crushing brick, block, concrete, stone, rock, mortar, and other materials that contain crystalline silica.

1. Contractors shall comply with OSHA standard 29 CFR 1926.1153 including taking all necessary steps to comply with the established exposure limits.
2. Contractors must have a written Exposure Control Plan specific to their operations in accordance with 29 CFR 1926.1153 that includes specific details for controlling exposure to NC State personnel and the public. A copy of this plan shall be made available to NC State EHS and/or the university Project Manager upon request.
3. Tasks performed indoors or in an enclosed area shall have effective exhaust ventilation to minimize the accumulation of visible airborne dust. In situations where ventilation is exhausted in an area with the potential to expose people to dust must incorporate effective HEPA filtration; such areas include but are not limited to, inside a building or outside where people may be present.
4. When a building ventilation system services an area where work with the potential for generating respirable crystalline silica exists, the building air returns shall be blanked or closed while such work is in progress. Contractors must coordinate this with the university project manager.
5. Contractors must establish a "Temporary Restricted Area" for tasks that require the use of respiratory protection in accordance with 29 CFR 1926.1153.
 - a. A *Temporary Restricted Area* is an area demarcated by the employer where an employee is required to wear respiratory protection.
 - b. *Temporary Restricted Areas* must be designated with signs, barriers, or other effective means that will ensure unauthorized persons do not enter. If such work is performed in *occupied* buildings, dust barriers shall be

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

installed as necessary to isolate the restricted area. Refer to [NC State Odor Prevention and Dust Control in Occupied Buildings](#) for additional information.

LL. Smoking and Open Flames

1. Smoking is not allowed in any NC State buildings, including roofs, penthouses, electrical/mechanical rooms, and basements or within 25 feet of any building entrance or exit.
2. The use of open flames is strictly prohibited in areas where flammable liquids, gases, or highly combustible materials are stored, handled, or processed.
3. The use of open flames, where allowed, requires a Hot Work Permit.

MM. Tarpaulins - When tarpaulins are required for the deflection of hot slag, dust, paint drippings, etc., or as a security barrier, they must be flame resistant and in good condition, free of holes and worn edges.

NN. Tar Pots (tar kettles) - Tar Pots are not allowed on roofs. The contractor must notify the NC State Project Manager prior to using tar pots and obtain a Hot Work permit.

OO. Temporary Heating - When heaters are used in confined spaces, special care shall be taken to provide sufficient ventilation to ensure proper combustion, maintain the health and safety of workmen, and limit temperature rise in the area.

PP. Temporary Lighting - The contractor shall submit a lighting plan for night work, underground work, and any other worksites without adequate lighting.

QQ. Temporary Traffic Control

1. All traffic control shall be approved by NC State and meet the Institute for Transportation Research and Education (ITRE) Work Zone Safety Guidelines for Construction, Maintenance, and Utility Operations. A traffic control plan shall be provided by the contractor and approved prior to commencement.
2. The contractor shall provide warning signs, barriers, barricades, etc., in accordance with the construction plans and specifications or whenever such protection is needed.
3. Where signs and barricades do not provide adequate protection, particularly along a road, walkway, or main aisle, flagmen shall be used.
4. Review with the crew, each person's responsibility regarding the traffic control set-up (e.g. sign installation, lane closure setup, etc.).
5. Review traffic control devices to be used at the site. Assure that traffic control set-up is properly installed. The installer shall document what traffic control set-up was used (including the sign types and sign locations) and how it was installed.

RR. Vehicle Operation

1. All equipment shall have operational backup alarms. Equipment shall not be utilized until such device is functioning properly.
2. All vehicles shall be operated in accordance with OSHA and manufacturer regulations.

NC State University Design and Construction Guidelines

Division 01 Contractor Safety Requirements

- SS. Vertical Lifts - All contractors' platforms or vertical lifts must meet OSHA and manufacturer requirements.

NC State University Design and Construction Guidelines

Division 02 Waste Materials Management – Reuse, Recycling, & Hazardous Waste

1.1 Purpose

- A. The following guidelines define waste management and disposal responsibilities for both hazardous and non-hazardous construction and demolition (C&D) wastes. The guidelines also address performance and reporting requirements.

2.0 General Requirements

A. Definitions

1. Construction & Demolition Waste: Building and site improvement materials, and other solid waste resulting from construction, demolition, renovation, or repair operations. Material stream also includes brick, concrete, asphalt, and aggregate.
2. Special Waste: Solid wastes that require special handling and management.
3. Hazardous Waste: Any solid waste that is ignitable, corrosive, reactive, or toxic; a listed hazardous material or containing a listed hazardous material per Title 40 Code of Federal Regulations Parts 260-270.
4. Universal Waste: Hazardous wastes that have been provided specific exemptions (40 CFR 273) to encourage recycling. Universal wastes are limited to recalled or cancelled pesticides and intact batteries, lamps, and mercury containing devices. State regulations prohibit the crushing of fluorescent lamps.
5. Salvage: Recovery of waste for reuse in the existing facility, a different facility, subsequent sale as State Surplus property, or other reuse efforts.
6. Recycle: Recovery of waste for processing and preparation into products or raw materials.
7. Yard waste: A solid waste consisting solely of vegetative matter resulting from landscaping maintenance.

B. Performance Goals and Requirements

1. All hazardous and non-hazardous generated waste shall be managed in accordance with local, state, and federal regulations.
2. Seventy-five percent (75%) of a project's non-hazardous waste must be diverted from landfill disposal through reuse and recycling.
3. One hundred percent (100%) of yard waste must be diverted from landfill disposal through reuse and recycling.
4. The Designer must complete the Designer Waste Information Form (<http://go.ncsu.edu/wasteinfoform>) and identify regulated wastes, as well as materials, fixtures, and equipment that are to be salvaged for reuse or recycled. The location of the staging area as well as the responsible party for removal, delivery, and/or pick up must also be included.
5. The completed **Designer Waste Information Form must be included in the Construction Documents** that go out for review and bid.
6. The Contractor must provide a Waste Management Plan (<http://go.ncsu.edu/wastemanagementplan>) to NC State for approval prior to implementing work. The plan shall include details on how the hazardous and non-hazardous generated waste will be managed in accordance with local, state, and federal regulations. Contractor must also provide all

NC State University Design and Construction Guidelines

Division 02 Waste Materials Management – Reuse, Recycling, & Hazardous Waste

materials, personnel, and protective equipment necessary to remove and store wastes in accordance with the plan. The Contractor must coordinate salvage or reuse efforts identified on the Designer Waste Information Form with NC State and/or the non-profit entity.

C. Reporting Requirements

1. Hazardous Waste

a) The Contractor must provide NC State with a copy of all hazardous, universal, and special waste disposal certifications and/or manifests for all waste shipped.

2. Non-Hazardous C&D Waste

a) All reuse, recycling, and landfilled materials are to be tracked and complied on NC State's tracking forms, which can be found at <https://recycling.ncsu.edu/wp-content/uploads/sites/3/2018/04/CD-Tracking-forms-for-upload.pdf>. The completed form, with weight tickets/invoices attached, is considered a required close-out document and must be submitted before final payment is issued.

3.0 Management of Hazardous, Universal, and Special Wastes

A. Hazardous, universal, and special wastes must be managed separately from other C&D wastes.

B. Disposal must be coordinated with NC State Environmental Health & Safety.

C. Special wastes include:

1. Paints, varnish, solvents, sealers, thinners, resins, roofing cement, adhesives, lubricants, and caulk, or drums and containers that once held these materials.
2. Treated wood including lumber, posts, ties, decks, and utility poles (creosote, arsenic, chromium, pentachlorophenol).
3. Asbestos, PCBs, mercury, or lead containing materials
4. Used oil
5. Lead acid batteries
6. Medical wastes

D. Waste disposal responsibility falls to one of two parties: the Contractor or NC State, as defined in the NC State Environmental Health and Safety's document:

Management of Building Demolition Debris available at: <http://go.ncsu.edu/demodebris>

1. Containers used for waste storage must be United States Department of Transportation approved. The Contractor must supply bins, tanks or tank trucks. Containers must remain closed at all times except when material is being added. NC State will provide containers for items collected by NC State.
2. Hazardous waste containers must have labels that clearly identify waste streams. Different waste streams cannot be combined in a shared container. The Contractor must identify the initial accumulation date on

NC State University Design and Construction Guidelines

Division 02 Waste Materials Management – Reuse, Recycling, & Hazardous Waste

- the hazardous waste label when waste is first placed in the container.
3. Waste containers must be stored in a secured, covered, and well identified area of the construction site. Hazardous waste cannot be stored for more than 90 days. Any waste stored for more than six days must be inspected, and the inspection documented, weekly.
 4. Spill response supplies must be on-site and adequate to contain 110% of any accumulated waste. Portable fire extinguishers must also be readily available. If a spill occurs, Contractor must contact NC State immediately and proceed with spill containment and clean up.
 5. The Contractor must provide NC State with a copy of all hazardous, universal, and special waste disposal certifications and/or manifests for all waste shipped.

4.0 Management of Non-Hazardous Waste

A. Priority 1 - Salvage of Construction and Demolition Waste for Reuse

1. Salvaged materials should first be evaluated for use in University construction projects. NC State Surplus Property Services should be considered if there are reusable materials that have resale value and are no longer needed by the University. Contact Waste Reduction and Recycling (ajbensle@ncsu.edu) for assistance with disposition.

Examples of Salvageable material include:

- a) Furniture and electronics
 - b) Cabinets and shelves that are not built-in
 - c) Sinks and water fountains
 - d) Paper towel dispensers
 - e) Newer light fixtures
 - f) Dry erase boards, chalkboards, and cork boards
 - g) Solid wood panel doors
 - h) Brick pavers
2. Contact vendors about take-back programs to recycle materials their company provides. These materials include, but are not limited to ceiling tiles, carpet tiles, and cubicle walls.
 3. Coordinate with the Project Manager to utilize the [NC State Construction Shop](#) for the careful removal of salvageable items prior to contractor demolition. An estimate for the Construction Shop's work must be received during design and must be initiated prior to the project going out to bid.

B. Priority 2 - Recycling of Construction and Demolition Waste

1. If materials are not a salvageable for reuse, they must be source separated to the greatest extent possible and recycled.
2. Common source separated materials for recycling include:
 - a) Cardboard
 - b) Bottles and cans
 - c) Scrap metal and wire

NC State University Design and Construction Guidelines

Division 02 Waste Materials Management – Reuse, Recycling, & Hazardous Waste

- d) Rigid plastics
- e) Untreated/unpainted dimensional lumber
- f) Gypsum board (unpainted)
- g) Concrete
- h) Asphalt (pavement and shingles)
- i) Aggregate
- j) Brick and CMU

3. 100% of the following materials must be recycled:

- a) Cardboard
- b) Bottles and cans
- c) Scrap metal and wire
- d) Concrete
- e) Asphalt (pavement and shingles)
- f) Aggregate
- g) Brick and CMU
- h) Designer shall coordinate with Waste Reduction and Recycling office during design to properly coordinate selective demolition requirements and recycling goals.**

C. Priority 3 - Disposal of Construction and Demolition Waste

- 1. If material/s cannot be salvaged for reuse or source separated and recycled, they must be sent to a C&D recycling and reclamation facility. Materials are not to be sent directly to a landfill or a facility that does not sort and recycle.

D. All solid waste management facilities must be permitted to operate by NCDEQ in accordance with [15A NCAC 13B .0201](#).

E. University Contract Pricing

- 1. When available, the contractor may utilize University contract pricing for related facility tip costs or recycling rebates. In order to utilize contracts, contractor must coordinate with the University project manager and Waste Reduction and Recycling office.

F. University Rolloff Services

- 1. Depending upon the scale of the work, dumpster services can be provided for Informal or Formal construction projects. Coordinate with NCSU Waste Reduction and Recycling to provide 17-20 cubic yard rolloffs. Rental and contact information; <https://recycling.ncsu.edu/rentals/>

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Owner-furnished/Contractor-installed (OFICI) products.
4. Owner-furnished/Owner-installed (OFOI) products.
5. Owner-furnished/Contractor-coordinated (OFCC) products.
6. Contractor's use of site and premises.
7. Work restrictions.
8. Specification and Drawing conventions.

1.2 PROJECT INFORMATION

A. Project Identification: Apiculture Facility. SCO ID 22-24494-01A.

1. Project Location: 4325 Inwood Road. Raleigh, NC. 27603.

B. Owner: State of North Carolina through North Carolina State University.

1. Owner's Representative (Design): Melissa Diamond. mrdiamon@ncsu.edu.
2. Owner's Representative (Construction): Stephanie McArthur. slmcarth@ncsu.edu

C. Architect: Biloba Architecture, PLLC.

D. Architect's Consultants: Architect has retained the following design professionals, who have prepared designated portions of the Contract Documents:

1. Civil and Structural Engineer, Landscape Architect : Stewart, Inc.
2. Plumbing, Mechanical, Electrical Engineer: RMF Engineering.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of Project is defined by the Contract Documents and consists of the following:

1. New steel framed building and associated sitework and other Work indicated in the Contract Documents.

B. Type of Contract:

1. Project will be constructed under a single prime contract.

1.4 OWNER-FURNISHED/CONTRACTOR-INSTALLED (OFICI) PRODUCTS

- A. Owner's Responsibilities: Owner will furnish products indicated and perform the following, as applicable:
1. Provide to Contractor Owner-reviewed Product Data, Shop Drawings, and Samples.
 2. Provide for delivery of Owner-furnished products to Project site.
 3. Upon delivery, inspect, with Contractor present, delivered items.
 - a. If Owner-furnished products are damaged, defective, or missing, arrange for replacement.
 4. Obtain manufacturer's inspections, service, and warranties.
 5. Inform Contractor of earliest available delivery date for Owner-furnished products.
- B. Contractor's Responsibilities: The Work includes the following, as applicable:
1. Designate delivery dates of Owner-furnished products in Contractor's construction schedule, utilizing Owner-furnished earliest available delivery dates.
 2. Review Owner-reviewed Product Data, Shop Drawings, and Samples, noting discrepancies and other issues in providing for Owner-furnished products in the Work.
 3. Receive, unload, handle, store, protect, and install Owner-furnished products.
 4. Make building services connections for Owner-furnished products.
 5. Protect Owner-furnished products from damage during storage, handling, and installation and prior to Final Completion.
 6. Repair or replace Owner-furnished products damaged following receipt.
- C. Owner-Furnished/Contractor-Installed (OFICI) Products:
1. Toilet Tissue Dispenser.
 2. Paper Towel dispenser.
 3. Soap Dispenser.
 4. Interior Signage.
 5. Exterior Signage.

1.5 OWNER-FURNISHED/OWNER INSTALLED (OFOI) PRODUCTS

- A. Contractor's Responsibilities: The Work includes the following, as applicable:
1. Designate delivery dates of Owner-furnished products in Contractor's construction schedule, utilizing Owner-furnished earliest available delivery dates.
 2. Review Owner-reviewed Product Data, Shop Drawings, and Samples, noting discrepancies and other issues in providing for Owner-furnished products in the Work.

3. Protect Owner-furnished products from damage during storage, handling, and installation and prior to Final Completion.
4. Repair or replace Owner-furnished products damaged following receipt.
- 5.

B. Owner-Furnished/Owner-Installed (OFOI) Products:

1. Fine Grading
2. Landscaping
3. Trash and recycling bins.
4. Other Items as Indicated.

1.6 OWNER-FURNISHED/CONTRACTOR COORDINATED (OFCC) PRODUCTS

A. Contractor's Responsibilities: The Work includes the following, as applicable:

1. Designate delivery dates of Owner-furnished products in Contractor's construction schedule, utilizing Owner-furnished earliest available delivery dates.
2. Review Owner-reviewed Product Data, Shop Drawings, and Samples, noting discrepancies and other issues in providing for Owner-furnished products in the Work.
3. Protect Owner-furnished products from damage during storage, handling, and installation and prior to Final Completion.
4. Repair or replace Owner-furnished products damaged following receipt.
5. Provide utilities, coordinating connections with the manufacturer.
- 6.

B. Owner-Furnished/Contractor Coordinated (OFCC) Products:

1. Insect Rearing Rooms (Incubator). Contractor is to coordinate installation with the Owner-provided products, including coordinating and providing utility connections and locations.

1.7 CONTRACTOR'S USE OF SITE AND PREMISES

- A. Restricted Use of Site: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.
- B. Limits on Use of Site: Limit use of Project site to areas within the Contract limits indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
- C. Condition of Existing Grounds: Maintain portions of existing grounds, landscaping, and hardscaping affected by construction operations throughout construction period. Repair damage caused by construction operations.

Final Completion

1.8 WORK RESTRICTIONS

- A. Comply with restrictions on construction operations.
 - 1. Comply with limitations on use of public streets, work on public streets, rights of way, and other requirements of authorities having jurisdiction.
- B. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7:00 a.m. to 5:00 p.m., Monday through Friday, unless otherwise indicated.
- C. Smoking and Controlled Substance Restrictions: Use of tobacco products , alcoholic beverages, and other controlled substances on Owner's property is not permitted.
- D. Employee Identification: Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.
- E. Employee Screening: Comply with Owner's requirements for screening of Contractor personnel working on Project site.
 - 1. Maintain list of approved screened personnel with Owner's representative.

1.9 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 - 2. Text Color: Text used in the Specifications, including units of measure, manufacturer and product names, and other text may appear in multiple colors or underlined as part of a hyperlink; no emphasis is implied by text with these characteristics.
 - 3. Hypertext: Text used in the Specifications may contain hyperlinks. Hyperlinks may allow for access to linked information that is not residing in the Specifications. Unless otherwise indicated, linked information is not part of the Contract Documents.
 - 4. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 00 Contracting Requirements: General provisions of the Contract, including General and Supplementary Conditions, apply to all Sections of the Specifications.
- C. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.

- D. NCSU Division 01 General Requirements apply to the Work of all Sections in the Specifications.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 012100 - ALLOWANCES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements governing allowances.
- B. Types of allowances include the following:
 - 1. Quantity allowances.
- C. Related Requirements:
 - 1. Section 012200 "Unit Prices" for procedures for using unit prices, including adjustment of quantity allowances when applicable.

1.2 ACTION SUBMITTALS

- A. Submit proposals for purchase of products or systems included in allowances in the form specified for Change Orders.

1.3 INFORMATIONAL SUBMITTALS

- A. Submit invoices or delivery slips to show actual quantities of materials delivered to the site for use in fulfillment of each allowance.
- B. Submit time sheets and other documentation to show labor time and cost for installation of allowance items that include installation as part of the allowance.

1.4 QUANTITY ALLOWANCES

- A. Unless otherwise indicated, Contractor's costs for receiving and handling at Project site, labor, installation, overhead and profit, and similar costs related to products and materials ordered by Owner or selected by Architect under allowance shall be included as part of the Contract Sum and not part of the allowance.

1.5 ADJUSTMENT OF ALLOWANCES

- A. Allowance Adjustment: To adjust allowance amounts, prepare a Change Order proposal based on the difference between purchase amount and the allowance, multiplied by final measurement of work-in-place where applicable. If applicable, include reasonable allowances for cutting losses, tolerances, mixing wastes, normal product imperfections, and similar margins.

1. Include installation costs in purchase amount only where indicated as part of the allowance.
 2. If requested, prepare explanation and documentation to substantiate distribution of overhead costs and other markups.
 3. Submit substantiation of a change in scope of Work, if any, claimed in Change Orders related to unit-cost allowances.
 4. Owner reserves the right to establish the quantity of work-in-place by independent quantity survey, measure, or count.
- B. Submit claims for increased costs because of a change in scope or nature of the allowance described in the Contract Documents, whether for the purchase order amount or Contractor's handling, labor, installation, overhead, and profit.
1. Do not include Contractor's or subcontractor's indirect expense in the Change Order cost amount unless it is clearly shown that the nature or extent of Work has changed from what could have been foreseen from information in the Contract Documents.
 2. No change to Contractor's indirect expense is permitted for selection of higher- or lower-priced materials or systems of the same scope and nature as originally indicated.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine products covered by an allowance promptly on delivery for damage or defects. Return damaged or defective products to manufacturer for replacement.

3.2 PREPARATION

- A. Coordinate materials and their installation for each allowance with related materials and installations to ensure that each allowance item is completely integrated and interfaced with related work.

3.3 SCHEDULE OF ALLOWANCES

- A. Allowance No. 1: Quantity Allowance: Include 100 cu. yd. of unsatisfactory soil excavation and disposal off-site and replacement with satisfactory soil material from off-site, as specified in Section 312000 "Earth Moving."
1. Coordinate quantity allowance adjustment with unit-price requirements in Section 012200 "Unit Prices."

END OF SECTION

SECTION 012200 - UNIT PRICES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for unit prices.
- B. Related Requirements:
 - 1. Section 012100 "Allowances" for procedures for using unit prices to adjust quantity allowances.

1.2 DEFINITIONS

- A. Unit price is an amount incorporated into the Agreement, applicable during the duration of the Work as a price per unit of measurement for materials, equipment, or services, or a portion of the Work, added to or deducted from the Contract Sum by appropriate modification, if the scope of Work or estimated quantities of Work required by the Contract Documents are increased or decreased.

1.3 PROCEDURES

- A. Unit prices include all necessary material, plus cost for delivery, installation, insurance, applicable taxes, overhead, and profit.
- B. Measurement and Payment: See individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.
- C. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.
- D. List of Unit Prices: A schedule of unit prices is included in Part 3. Specification Sections referenced in the schedule contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

- A. Unit Price No. 1: Removal of unsatisfactory soil and replacement with satisfactory soil material.
1. Description: Unsatisfactory soil excavation and disposal off-site and replacement with satisfactory fill material or engineered fill from off-site, as required, in accordance with Section 312000 "Earth Moving."
 2. Unit of Measurement: One cubic yard of soil excavated, based on in-place surveys of volume before and after removal.
 3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Section 012100 "Allowances."

END OF SECTION

SECTION 012300 - ALTERNATES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for alternates.

1.2 DEFINITIONS

- A. Alternate: An amount proposed by bidders and stated on the Bid Form for certain work defined in the bidding requirements that may be added to or deducted from the base bid amount if the Owner decides to accept a corresponding change either in the amount of construction to be completed or in the products, materials, equipment, systems, or installation methods described in the Contract Documents.
 - 1. Alternates described in this Section are part of the Work only if enumerated in the Agreement.
 - 2. The cost or credit for each alternate is the net addition to or deduction from the Contract Sum to incorporate alternates into the Work. No other adjustments are made to the Contract Sum.

1.3 PROCEDURES

- A. Coordination: Revise or adjust affected adjacent work as necessary to completely integrate work of the alternate into Project.
 - 1. Include as part of each alternate, miscellaneous devices, accessory objects, and similar items incidental to or required for a complete installation whether or not indicated as part of alternate.
- B. Execute accepted alternates under the same conditions as other work of the Contract.
- C. Schedule: A schedule of alternates is included at the end of this Section. Specification Sections referenced in schedule contain requirements for materials necessary to achieve the work described under each alternate.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF ALTERNATES

- A. Alternate No. 1A: Owner Preferred Door Hardware.

1. Base Bid: Provide door hardware by any of the manufacturers listed as specified in Section 08 7100 "Door Hardware."
 2. Alternate: Provide door hardware by the specific manufacturers listed in the "Door Hardware Schedule" as specified in Section 08 7100 "Door Hardware."
- B. Alternate No. 1B: Owner Preferred Brand Controller.
1. Base Bid: Provide controller by any of the manufacturers listed.
 2. Alternate: Provide 300TLF Controller by Digital Security Controls.
- C. Alternate No. 1C: Owner Preferred Controls.
1. Base Bid: Provide controls by any of the manufacturers listed.
 2. Alternate: Provide Controls by Johnson Controls, Inc.
- D. Alternate No. 1D: Owner Preferred Controls.
1. Base Bid: Provide controls by any of the manufacturers listed.
 2. Alternate: Provide Controls by Schneider Electric.
- E. Alternate No. 2: Barnquilt Custom Panels.
1. Base Bid: Omit barnquilt panels as indicated on the Drawings.
 2. Alternate: Provide barnquilt panels as indicated on the Drawings and as Specified in 10 1423 "Panel Signage."
- F. Alternate No. 3: Moveable Glass Wall.
1. Base Bid: Omit moveable glass wall as indicated on the Drawings. Provide metal framed gypsum wall and doors as indicated for base bid.
 2. Alternate: Provide moveable glass wall as indicated on the Drawings.
- G. Alternate No. 4: Ceramic Wall Tile.
1. Base Bid: Omit ceramic wall tile where indicated on the Drawings. Provide high-performance coatings as indicated for base bid.
 2. Alternate: Provide ceramic wall tile as indicated on the Drawings.
- H. Alternate No. 5: Toilet Room 107C.
1. Base Bid: Omit ceramic tile finishes and plumbing fixtures in Room 107C as indicated on the Drawings.
 2. Alternate: Provide fully complete Toilet Room 107C as indicated on the Drawings.
- I. Alternate No. 6: Emergency Generator.
1. Base Bid: Omit emergency generator and equipment as indicated on the Drawings. Generator docking station is base bid.
 2. Alternate: Provide emergency generator as indicated on the Drawings and as specified in Section 26 3214 "Engine Generators."

- J. Alternate No. 7: Polished Concrete.
1. Base Bid: Omit concrete polishing. Provide concrete finish as indicated on the Structural Drawings and as Specified in 03 3000 "Cast-In-Place Concrete."
 2. Alternate: Polish concrete as indicated on the Drawings and as specified in Section 03 3543 "Polished Concrete Finishing."
- K. Alternate No. 8: FRP and PVC Roll Flooring.
1. Base Bid: Omit FRP and PVC roll flooring where indicated on the Drawings as part of the Alternate.
 2. Alternate: Provide FRP and resinous flooring where indicated on the Drawings as being provided as part of the alternate.
- L. Alternate No. 9: AHU Screening.
1. Base Bid: Omit AHU Screening as indicated on the Drawings.
 2. Alternate: Provide AHU screening where indicated on the Drawings as being provided as part of the alternate.
- M. Alternate No. 10: Existing House and Septic Demolition
1. Base Bid: Omit demolition of the existing house, partial basement infill, and septic decommissioning.
 2. Alternate: Perform asbestos abatement per the report, demolish existing house, infill the partial basement, and decommission existing septic system as indicated on the Civil Drawings.
- N. Alternate No. 11: Laboratory Casework.
1. Base Bid: Omit Laboratory Casework in Room 104. Utilities shall be capped at the nearest ceiling or wall for ease of future installation.
 2. Alternate: Provide laboratory casework and all utility connections as indicated on the Drawings and as specified in Section 12 3553.13 "Metal Laboratory Casework."

END OF SECTION

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
 - 1. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
 - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
 - 2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Contractor or Owner.

1.3 ACTION SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use form acceptable to Architect.
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation method cannot be provided, if applicable.
 - b. Coordination of information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitutions with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes, such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.

- d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. Certificates and qualification data, where applicable or requested.
 - g. List of similar installations for completed projects, with project names and addresses as well as names and addresses of architects and owners.
 - h. Material test reports from a qualified testing agency, indicating and interpreting test results for compliance with requirements indicated.
 - i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
 - j. Detailed comparison of Contractor's construction schedule using proposed substitutions with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
 - k. Cost information, including a proposal of change, if any, in the Contract Sum.
 - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents, except as indicated in substitution request, is compatible with related materials and is appropriate for applications indicated.
 - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
- a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
 - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.4 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.5 PROCEDURES

- A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

1.6 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Requested substitution provides sustainable design characteristics that specified product provided for compliance with IgCC requirements.
 - c. Requested substitution provides sustainable design characteristics that specified product provided for compliance with ASHRAE 189.1 requirements.
 - d. Substitution request is fully documented and properly submitted.
 - e. Requested substitution will not adversely affect Contractor's construction schedule.
 - f. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - g. Requested substitution is compatible with other portions of the Work.
 - h. Requested substitution has been coordinated with other portions of the Work.
 - i. Requested substitution provides specified warranty.
 - j. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Not allowed.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.2 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on Architect's standard form.
 - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.

1.3 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request or 20 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.

1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.

1.4 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Work Change Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on form provided as part of web-based Project management software.

1.5 FIELD ORDER

- A. Field Order: Architect may issue a Field Order on SCO's standard form. Field Orders instruct Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 1. Field Order contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

1.2 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
 - 1. Coordinate line items in the schedule of values with items required to be indicated as separate activities in Contractor's construction schedule.
 - 2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Arrange schedule of values consistent with format of AIA Document G703.
 - 2. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
 - 3. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site.
 - 4. Overhead Costs: Show cost of temporary facilities and other major cost items that are not direct cost of actual work-in-place as separate line items.
 - 5. Schedule of Values Revisions: Revise the schedule of values when Change Orders or Construction Change Directives result in a change in the Contract Sum. Include at least one separate line item for each Change Order and Construction Change Directive.

1.3 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.

- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
 3. Include amounts of Change Orders issued before last day of construction period covered by application.
- E. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt. One copy shall include waivers of lien and similar attachments if required.
1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- F. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
1. List of subcontractors.
 2. Schedule of values.
 3. Contractor's construction schedule (preliminary if not final).
 4. Products list (preliminary if not final).
 5. Submittal schedule (preliminary if not final).
 6. List of Contractor's staff assignments.
 7. List of Contractor's principal consultants.
 8. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 9. Initial progress report.
 10. Report of preconstruction conference.
 11. Certificates of insurance and insurance policies.
 12. Performance and payment bonds.
 13. Data needed to acquire Owner's insurance.
- G. Application for Payment at Final Completion: After Architect issues the Certificate of Final Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 2. This application shall reflect Certificate(s) of Final Completion issued previously for Owner occupancy of designated portions of the Work.
- H. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 3. Updated final statement, accounting for final changes to the Contract Sum.
 4. Evidence that claims have been settled.
 5. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Final Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
 6. Final liquidated damages settlement statement.
 7. Other forms as required by State Construction Office.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. General coordination procedures.
 - 2. Coordination drawings.
 - 3. RFIs.
 - 4. Digital project management procedures.
 - 5. Project meetings.
- B. Related Requirements:
 - 1. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.

1.2 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
 - 1. Name, address, telephone number, and email address of entity performing subcontract or supplying products.
 - 2. Number and title of related Specification Section(s) covered by subcontract.
 - 3. Drawing number and detail references, as appropriate, covered by subcontract.

1.3 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations included in different Sections that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.

- B. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
1. Preparation of Contractor's construction schedule.
 2. Preparation of the schedule of values.
 3. Installation and removal of temporary facilities and controls.
 4. Delivery and processing of submittals.
 5. Progress meetings.
 6. Preinstallation conferences.
 7. Project closeout activities.
 8. Startup and adjustment of systems.

1.4 COORDINATION DRAWINGS

- A. Coordination Drawings, General: Prepare coordination drawings according to requirements in individual Sections, and additionally where installation is not completely indicated on Shop Drawings, where limited space availability necessitates coordination, or if coordination is required to facilitate integration of products and materials fabricated or installed by more than one entity.
1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:
 - a. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
 - b. Indicate dimensions shown on Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternative sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.
- B. Coordination Drawing Organization: Organize coordination drawings as follows:
1. Floor Plans and Reflected Ceiling Plans: Show architectural and structural elements, and mechanical, plumbing, fire-protection, fire-alarm, and electrical Work. Show locations of visible ceiling-mounted devices relative to acoustical ceiling grid. Supplement plan drawings with section drawings where required to adequately represent the Work.
 2. Review: Architect will review coordination drawings to confirm that, in general, the Work is being coordinated, but not for the details of the coordination, which are Contractor's responsibility. If Architect determines that coordination drawings are not being prepared in sufficient scope or detail, or are otherwise deficient, Architect will so inform Contractor, who shall make suitable modifications and resubmit.

- C. Coordination Digital Data Files: Prepare coordination digital data files according to the following requirements:
1. File Submittal Format: Submit or post coordination drawing files using PDF format.
 2. Architect will furnish Contractor one set of digital data files of Drawings for use in preparing coordination digital data files.
 - a. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Drawings.
 - b. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.

1.5 REQUEST FOR INFORMATION (RFI)

- A. General: Immediately on discovery of the need for additional information, clarification, or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
1. Architect will return without response those RFIs submitted to Architect by other entities controlled by Contractor.
 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
1. Owner name.
 2. Owner's Project number.
 3. Name of Architect.
 4. Architect's Project number.
 5. Date.
 6. Name of Contractor.
 7. RFI number, numbered sequentially.
 8. RFI subject.
 9. Specification Section number and title and related paragraphs, as appropriate.
 10. Drawing number and detail references, as appropriate.
 11. Field dimensions and conditions, as appropriate.
 12. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 13. Contractor's signature.
 14. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
- C. RFI Forms: Software-generated form with substantially the same content as indicated above, acceptable to Architect.

- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.
1. The following Contractor-generated RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for approval of Contractor's means and methods.
 - d. Requests for coordination information already indicated in the Contract Documents.
 - e. Requests for adjustments in the Contract Time or the Contract Sum.
 - f. Requests for interpretation of Architect's actions on submittals.
 - g. Incomplete RFIs or inaccurately prepared RFIs.
 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt by Architect of additional information.
 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within five days of receipt of the RFI response.
- E. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within three days if Contractor disagrees with response.

1.6 DIGITAL PROJECT MANAGEMENT PROCEDURES

- A. Use of Architect's Digital Data Files: Digital data files of Architect's CAD drawings will be provided by Architect for Contractor's use during construction.
1. Digital data files may be used by Contractor in preparing coordination drawings, Shop Drawings, and Project record Drawings.
 2. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Contract Drawings.
 3. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.
 4. The following digital data files will be furnished for each appropriate discipline:
 - a. Floor plans.
 - b. Reflected ceiling plans.
- B. PDF Document Preparation: Where PDFs are required to be submitted to Architect, prepare as follows:

1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
2. Name file with submittal number or other unique identifier, including revision identifier.
3. Certifications: Where digitally submitted certificates and certifications are required, provide a digital signature with digital certificate on where indicated.

1.7 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.
- B. Preconstruction Conference: Architect will schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.
 1. Attendees: Authorized representatives of Owner Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Responsibilities and personnel assignments.
 - b. Tentative construction schedule.
 - c. Critical work sequencing and long lead items.
 - d. Designation of key personnel and their duties.
 - e. Lines of communications.
 - f. Use of web-based Project software.
 - g. Procedures for processing field decisions and Change Orders.
 - h. Procedures for RFIs.
 - i. Procedures for testing and inspecting.
 - j. Procedures for processing Applications for Payment.
 - k. Submittal procedures.
 - l. Preparation of Record Documents.
 - m. Use of the premises.
 - n. Work restrictions.
 - o. Working hours.
 - p. Responsibility for temporary facilities and controls.
 - q. Procedures for moisture and mold control.
 - r. Procedures for disruptions and shutdowns.
 - s. Construction waste management and recycling.
 - t. Equipment deliveries and priorities.
 - u. First aid.
 - v. Security.
 - w. Progress cleaning.
 - x. Other items included on the State Construction Office Agenda.

3. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity when required by other sections and when required for coordination with other construction.
1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
 2. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
 3. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
 4. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress meetings at weekly intervals.
1. Coordinate dates of meetings with preparation of payment requests.
 2. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - 1) Review schedule for next period.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.

- 5) Off-site fabrication.
 - 6) Access.
 - 7) Site use.
 - 8) Temporary facilities and controls.
 - 9) Progress cleaning.
 - 10) Quality and work standards.
 - 11) Status of correction of deficient items.
 - 12) Field observations.
 - 13) Status of RFIs.
 - 14) Status of Proposal Requests.
 - 15) Pending changes.
 - 16) Status of Change Orders.
 - 17) Pending claims and disputes.
 - 18) Documentation of information for payment requests.
4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
- a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Contractor's Construction Schedule.
 - 2. Construction schedule updating reports.

1.2 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction Project. Activities included in a construction schedule consume time and resources.
 - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- C. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- D. Event: The starting or ending point of an activity.
- E. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
 - 2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
 - 3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.

1.3 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:

1. Working electronic copy of schedule file.
 2. PDF file.
 3. Two paper copies, of sufficient size to display entire period or schedule, as required.
- B. Startup Network Diagram: Of size required to display entire network for entire construction period. Show logic ties for activities.
- C. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
1. Submit a working digital copy of schedule, using software indicated, and labeled to comply with requirements for submittals.
- D. CPM Reports: Concurrent with CPM schedule, submit each of the following reports. Format for each activity in reports shall contain activity number, activity description, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.
1. Activity Report: List of activities sorted by activity number and then early start date, or actual start date if known.
 2. Logic Report: List of preceding and succeeding activities for each activity, sorted in ascending order by activity number and then by early start date, or actual start date if known.
 3. Total Float Report: List of activities sorted in ascending order of total float.
- E. Construction Schedule Updating Reports: Submit with Applications for Payment.

1.4 COORDINATION

- A. Coordinate Contractor's Construction Schedule with the schedule of values, list of subcontracts, submittal schedule, progress reports, payment requests, and other required schedules and reports.
1. Secure time commitments for performing critical elements of the Work from entities involved.
 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

1.5 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.
- B. Time Frame: Extend schedule from date established for commencement of the Work to date of final completion.

1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each floor or separate area as a separate numbered activity for each main element of the Work. Comply with the following:
1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
 2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
 3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with submittal schedule.
 4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
 5. Commissioning Time: Include no fewer than 15 days for commissioning.
 6. Final Completion: Indicate completion in advance of date established for Final Completion, and allow time for Architect's administrative procedures necessary for certification of Final Completion.
 7. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
1. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
 2. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Limitations of continued occupancies.
 - c. Uninterruptible services.
 - d. Partial occupancy before Final Completion.
 - e. Use-of-premises restrictions.
 - f. Provisions for future construction.
 - g. Seasonal variations.
 - h. Environmental control.
- E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Final Completion, and final completion, and the following interim milestones:
1. Temporary enclosure and space conditioning.
- F. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:

1. Unresolved issues.
 2. Unanswered Requests for Information.
 3. Rejected or unreturned submittals.
 4. Notations on returned submittals.
 5. Pending modifications affecting the Work and the Contract Time.
- G. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
 3. As the Work progresses, indicate final completion percentage for each activity.
- H. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule. Indicate changes to working hours, working days, crew sizes, equipment required to achieve compliance, and date by which recovery will be accomplished.
- I. Distribution: Distribute copies of approved schedule to Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
1. Post copies in Project meeting rooms and temporary field offices.
 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.
- 1.6 CPM SCHEDULE REQUIREMENTS
- A. Prepare network diagrams using AON (activity-on-node) format.
- B. Startup Network Diagram: Submit diagram within 14 days of date established for the Notice of Award. Outline significant construction activities for the first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.
- C. CPM Schedule: Prepare Contractor's Construction Schedule using a time-scaled CPM network analysis diagram for the Work.
1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than 14 days after date established for the Notice to Proceed.

- a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing all work within applicable completion dates.
 2. Conduct educational workshops to train and inform key Project personnel, including subcontractors' personnel, in proper methods of providing data and using CPM schedule information.
 3. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
 4. Use "one workday" as the unit of time for individual activities. Indicate nonworking days and holidays incorporated into the schedule to coordinate with the Contract Time.
- D. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the startup network diagram, prepare a skeleton network to identify probable critical paths.
1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:
 - a. Preparation and processing of submittals.
 - b. Mobilization and demobilization.
 - c. Purchase of materials.
 - d. Delivery.
 - e. Fabrication.
 - f. Utility interruptions.
 - g. Installation.
 - h. Work by Owner that may affect or be affected by Contractor's activities.
 - i. Testing and inspection.
 - j. Commissioning.
 - k. Punch list and final completion.
 - l. Activities occurring following final completion.
 2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
 3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.
 4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.
 - a. Subnetworks on separate sheets are permissible for activities clearly off the critical path.

- E. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using a network fragment to demonstrate the effect of the proposed change on the overall Project schedule.
- F. Initial Issue of Schedule: Prepare initial network diagram from a sorted activity list indicating straight "early start-total float." Identify critical activities. Prepare tabulated reports showing the following:
1. Contractor or subcontractor and the Work or activity.
 2. Description of activity.
 3. Main events of activity.
 4. Immediate preceding and succeeding activities.
 5. Early and late start dates.
 6. Early and late finish dates.
 7. Activity duration in workdays.
 8. Total float or slack time.
 9. Average size of workforce.
 10. Dollar value of activity (coordinated with the schedule of values).
- G. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:
1. Identification of activities that have changed.
 2. Changes in early and late start dates.
 3. Changes in early and late finish dates.
 4. Changes in activity durations in workdays.
 5. Changes in the critical path.
 6. Changes in total float or slack time.
 7. Changes in the Contract Time.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Submittal schedule requirements.
2. Administrative and procedural requirements for submittals.

1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."

1.3 SUBMITTAL SCHEDULE

- A. Submittal Schedule: Submit, as an action submittal, a list of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

1.4 SUBMITTAL FORMATS

A. Submittal Information: Include the following information in each submittal:

1. Project name.
2. Date.
3. Name of Architect.
4. Name of Contractor.
5. Name of firm or entity that prepared submittal.
6. Names of subcontractor, manufacturer, and supplier.
7. Unique submittal number, including revision identifier. Include Specification Section number with sequential alphanumeric identifier and alphanumeric suffix for resubmittals.
8. Category and type of submittal.
9. Submittal purpose and description.

10. Number and title of Specification Section, with paragraph number and generic name for each of multiple items.
 11. Drawing number and detail references, as appropriate.
 12. Indication of full or partial submittal.
 13. Location(s) where product is to be installed, as appropriate.
 14. Other necessary identification.
 15. Remarks.
 16. Signature of transmitter.
- B. Options: Identify options requiring selection by Architect.
- C. Deviations and Additional Information: On each submittal, clearly indicate deviations from requirements in the Contract Documents, including minor variations and limitations; include relevant additional information and revisions, other than those requested by Architect on previous submittals. Indicate by highlighting on each submittal or noting on attached separate sheet.
- D. Submittals for Utilizing Web-Based Project Management Software: Prepare submittals as PDF files or other format indicated by Project management software.

1.5 SUBMITTAL PROCEDURES

- A. Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
1. Web-Based Project Management Software: Prepare submittals in PDF form, and upload to web-based Project management software website. Enter required data in web-based software site to fully identify submittal.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
 3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 2. Resubmittal Review: Allow 15 days for review of each resubmittal.

- D. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
- E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

1.6 SUBMITTAL REQUIREMENTS

- A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 - 1. If information must be specially prepared for submittal because standard published data are unsuitable for use, submit as Shop Drawings, not as Product Data.
 - 2. Mark each copy of each submittal to show which products and options are applicable.
 - 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
 - h. Availability and delivery time information.
 - 4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams that show factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
 - 5. Submit Product Data before Shop Drawings, and before or concurrent with Samples.
- B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data unless submittal based on Architect's digital data drawing files is otherwise permitted.

1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Compliance with specified standards.
 - d. Notation of coordination requirements.
 - e. Notation of dimensions established by field measurement.
 - f. Relationship and attachment to adjoining construction clearly indicated.
 - g. Seal and signature of professional engineer if specified.

- C. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other materials.
 1. Transmit Samples that contain multiple, related components, such as accessories together in one submittal package.
 2. Identification: Permanently attach label on unexposed side of Samples that includes the following:
 - a. Project name and submittal number.
 - b. Generic description of Sample.
 - c. Product name and name of manufacturer.
 - d. Sample source.
 - e. Number and title of applicable Specification Section.
 - f. Specification paragraph number and generic name of each item.
 3. Paper Transmittal: Include paper transmittal, including complete submittal information indicated.
 4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
 - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
 5. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units, showing the full range of colors, textures, and patterns available.
 - a. Number of Samples: Submit one full set(s) of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.

6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
 - a. Number of Samples: Submit three sets of Samples. Architect will retain two Sample sets; remainder will be returned.
 - 1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
 - 2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
- D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
- E. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- F. Design Data: Prepare and submit written and graphic information indicating compliance with indicated performance and design criteria in individual Specification Sections. Include list of assumptions and summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Number each page of submittal.
- G. Certificates:
 1. Certificates and Certifications Submittals: Submit a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity. Provide a notarized signature where indicated.
 2. Installer Certificates: Submit written statements on manufacturer's letterhead, certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
 3. Manufacturer Certificates: Submit written statements on manufacturer's letterhead, certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.

4. Material Certificates: Submit written statements on manufacturer's letterhead, certifying that material complies with requirements in the Contract Documents.
5. Product Certificates: Submit written statements on manufacturer's letterhead, certifying that product complies with requirements in the Contract Documents.
6. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.

H. Test and Research Reports:

1. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for substrate preparation and primers required.
2. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
3. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
4. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
5. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
6. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
 - a. Name of evaluation organization.
 - b. Date of evaluation.
 - c. Time period when report is in effect.
 - d. Product and manufacturers' names.
 - e. Description of product.
 - f. Test procedures and results.
 - g. Limitations of use.

1.7 DELEGATED DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

1. If criteria indicated are insufficient to perform services or certification required, submit a written request for additional information to Architect.
 - B. Delegated Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF file paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.
- 1.8 CONTRACTOR'S REVIEW
- A. Action Submittals and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
 - B. Contractor's Approval: Indicate Contractor's approval for each submittal with a uniform approval stamp. Include name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.
 1. Architect will not review submittals received from Contractor that do not have Contractor's review and approval.
- 1.9 ARCHITECT'S REVIEW
- A. Action Submittals: Architect will review each submittal, indicate corrections or revisions required, and return.
 1. PDF Submittals: Architect will indicate, via markup on each submittal, the appropriate action.
 2. Submittals by Web-Based Project Management Software: Architect will indicate, on Project management software website, the appropriate action.
 - B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
 - C. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.
 - D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.

- E. Architect will return without review submittals received from sources other than Contractor.
- F. Submittals not required by the Contract Documents will be returned by Architect without action.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspection services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and quality-control requirements for individual work results are specified in their respective Specification Sections. Requirements in individual Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and quality-control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-assurance and quality-control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.

1.3 DEFINITIONS

- A. Experienced: When used with an entity or individual, "experienced," unless otherwise further described, means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.
- B. Field Quality-Control Tests and Inspections: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- C. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, subcontractor, or sub-subcontractor, to perform a particular construction operation, including installation, erection, application, assembly, and similar operations.
 - 1. Use of trade-specific terminology in referring to a Work result does not require that certain construction activities specified apply exclusively to specific trade(s).

- D. Mockups: Physical assemblies of portions of the Work constructed to establish the standard by which the Work will be judged. Mockups are not Samples.
1. Mockups are used for one or more of the following:
 - a. Verify selections made under Sample submittals.
 - b. Demonstrate aesthetic effects.
 - c. Demonstrate the qualities of products and workmanship.
 - d. Demonstrate successful installation of interfaces between components and systems.
 - e. Perform preconstruction testing to determine system performance.
 2. Product Mockups: Mockups that may include multiple products, materials, or systems specified in a single Section.
 3. In-Place Mockups: Mockups constructed on-site in their actual final location as part of permanent construction.
- E. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria. Unless otherwise indicated, copies of reports of tests or inspections performed for other than the Project do not meet this definition.
- F. Product Tests: Tests and inspections that are performed by a nationally recognized testing laboratory (NRTL) according to 29 CFR 1910.7, by a testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program (NVLAP), or by a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- G. Source Quality-Control Tests and Inspections: Tests and inspections that are performed at the source (e.g., plant, mill, factory, or shop).
- H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. The term "testing laboratory" has the same meaning as the term "testing agency."
- I. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work, to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- J. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work, to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Contractor's quality-control services do not include contract administration activities performed by Architect.

1.4 DELEGATED DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated Design Services Statement: Submit a statement signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.

1.5 CONFLICTING REQUIREMENTS

- A. Conflicting Standards and Other Requirements: If compliance with two or more standards or requirements is specified and the standards or requirements establish different or conflicting requirements for minimum quantities or quality levels, inform the Architect regarding the conflict and obtain clarification prior to proceeding with the Work. Refer conflicting requirements that are different, but apparently equal, to Architect for clarification before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified is the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.6 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.
- C. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility submitted to authorities having jurisdiction before starting work on the following systems:
1. Seismic-force-resisting system, designated seismic system, or component listed in the Statement of Special Inspections.
 2. Primary wind-force-resisting system or a wind-resisting component listed in the Statement of Special Inspections.

- D. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- E. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 - 1. Specification Section number and title.
 - 2. Entity responsible for performing tests and inspections.
 - 3. Description of test and inspection.
 - 4. Identification of applicable standards.
 - 5. Identification of test and inspection methods.
 - 6. Number of tests and inspections required.
 - 7. Time schedule or time span for tests and inspections.
 - 8. Requirements for obtaining samples.
 - 9. Unique characteristics of each quality-control service.
- F. Reports: Prepare and submit certified written reports and documents as specified.

1.7 CONTRACTOR'S QUALITY-CONTROL PLAN

- A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities and to coordinate Owner's quality-assurance and quality-control activities. Coordinate with Contractor's Construction Schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
 - 1. Project quality-control manager may also serve as Project superintendent.
- C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.
- D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
 - 1. Contractor-performed tests and inspections, including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections. Distinguish source quality-control tests and inspections from field quality-control tests and inspections.
 - 2. Special inspections required by authorities having jurisdiction and indicated on the Statement of Special Inspections.
 - 3. Owner-performed tests and inspections indicated in the Contract Documents.

- E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring the Work into compliance with standards of workmanship established by Contract requirements and approved mockups.
- F. Monitoring and Documentation: Maintain testing and inspection reports, including log of approved and rejected results. Include Work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming Work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

1.8 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, telephone number, and email address of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.
 - 9. Test and inspection results and an interpretation of test results.
 - 10. Record of temperature and weather conditions at time of sample-taking and testing and inspection.
 - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 - 12. Name and signature of laboratory inspector.
 - 13. Recommendations on retesting and reinspecting.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
 - 1. Name, address, telephone number, and email address of technical representative making report.
 - 2. Statement on condition of substrates and their acceptability for installation of product.
 - 3. Statement that products at Project site comply with requirements.
 - 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 - 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 - 6. Statement of whether conditions, products, and installation will affect warranty.
 - 7. Other required items indicated in individual Specification Sections.

- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
1. Name, address, telephone number, and email address of factory-authorized service representative making report.
 2. Statement that equipment complies with requirements.
 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 4. Statement of whether conditions, products, and installation will affect warranty.
 5. Other required items indicated in individual Specification Sections.

1.9 QUALITY ASSURANCE

- A. Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units. As applicable, procure products from manufacturers able to meet qualification requirements, warranty requirements, and technical or factory-authorized service representative requirements.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, applying, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that is similar in material, design, and extent to those indicated for this Project.
- F. Testing and Inspecting Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspection indicated, as documented in accordance with ASTM E329, and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
- G. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

- H. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect, demonstrate, repair, and perform service on installations of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following Contractor's responsibilities, including the following:
1. Provide test specimens representative of proposed products and construction.
 2. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 3. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
 4. Build site-assembled test assemblies and mockups, using installers who will perform same tasks for Project.
 5. When testing is complete, remove test specimens and test assemblies, and mockups; do not reuse products on Project.
 6. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect, with copy to Contractor. Interpret tests and inspections, and state in each report whether tested and inspected Work complies with or deviates from the Contract Documents.
- J. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
1. Build mockups of size indicated.
 2. Build mockups in location indicated or, if not indicated, as directed by Architect.
 3. Notify Architect seven days in advance of dates and times when mockups will be constructed.
 4. Employ supervisory personnel who will oversee mockup construction. Employ workers who will be employed to perform same tasks during the construction at Project.
 5. Demonstrate the proposed range of aesthetic effects and workmanship.
 6. Obtain Architect's approval of mockups before starting corresponding Work, fabrication, or construction.
 - a. Allow seven days for initial review and each re-review of each mockup.
 7. Promptly correct unsatisfactory conditions noted by Architect's preliminary review, to the satisfaction of the Architect, before completion of final mockup.
 8. Approval of mockups by the Architect does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 9. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 10. Demolish and remove mockups when directed unless otherwise indicated.

1.10 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspection they are engaged to perform.
 2. Costs for retesting and reinspecting construction that replaces or is necessitated by Work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities, whether specified or not, to verify and document that the Work complies with requirements.
1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
 2. Engage a qualified testing agency to perform quality-control services.
 - a. Contractor will not employ same entity engaged by Owner, unless agreed to in writing by Owner.
 3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspection will be performed.
 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
 5. Testing and inspection requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- D. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 2. Determine the locations from which test samples will be taken and in which in-situ tests are conducted.
 3. Conduct and interpret tests and inspections, and state in each report whether tested and inspected Work complies with or deviates from requirements.

4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 6. Do not perform duties of Contractor.
- E. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."
- F. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- G. Contractor's Associated Requirements and Services: Cooperate with agencies and representatives performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
1. Access to the Work.
 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 3. Adequate quantities of representative samples of materials that require testing and inspection. Assist agency in obtaining samples.
 4. Facilities for storage and field curing of test samples.
 5. Delivery of samples to testing agencies.
 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 7. Security and protection for samples and for testing and inspection equipment at Project site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality-control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspection.
1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- I. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents as a component of Contractor's quality-control plan. Coordinate and submit concurrently with Contractor's Construction Schedule. Update and submit with each Application for Payment.
1. Schedule Contents: Include tests, inspections, and quality-control services, including Contractor- and Owner-retained services, commissioning activities, and other Project-required services paid for by other entities.

2. Distribution: Distribute schedule to Owner, Architect, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
 1. Date test or inspection was conducted.
 2. Description of the Work tested or inspected.
 3. Date test or inspection results were transmitted to Architect.
 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's and authorities' having jurisdiction reference during normal working hours.
 1. Submit log at Project closeout as part of Project Record Documents.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspection, sample-taking, and similar services, repair damaged construction and restore substrates and finishes.
 1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.3 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.
- C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.
 - 1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.4 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."
- B. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. This information is believed to be accurate as of the date of the Contract Documents.
- C. ICC - International Code Council; www.iccsafe.org.
- D. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the respective entities listed.
- E. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list. This information is subject to change and is believed to be accurate as of the date of the Contract Documents.
- F. ADAAG – Americans with Disabilities Act (ADA).
- G. ABA – Architectural Barriers Act.
- H. FED-STD - Federal Standard; (See FS).
- I. FS - Federal Specification; Available from DLA Document Services; www.quicksearch.dla.mil.
- J. Available from Defense Standardization Program; www.dsp.dla.mil.
- K. Available from General Services Administration; www.gsa.gov.
- L. Available from National Institute of Building Sciences/Whole Building Design Guide; www.wbdg.org/ccb.

- M. State Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the respective entities listed.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 014339 - MOCKUPS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Integrated exterior mockups.

1.2 DEFINITIONS

- A. Integrated Exterior Mockups: Mockups of the exterior envelope constructed on-site as freestanding temporary built elements, consisting of multiple products, assemblies, and subassemblies.

1.3 ACTION SUBMITTALS

- A. Shop Drawings: For integrated exterior mockups.

1.4 COORDINATION

- A. Coordinate schedule for construction of mockups, so construction, testing, and review of mockups do not impact Project schedule.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Mockup Testing Performance Requirements: Perform tests using design pressures and performance criteria indicated for assemblies and products that are specified in other Sections and incorporated into integrated exterior mockups.

2.2 INTEGRATED EXTERIOR MOCKUPS

- A. Construct integrated exterior mockups according to approved mockup Shop Drawings. Construct mockups to demonstrate constructability, coordination of trades, and sequencing of Work; and to ensure materials, components, subassemblies, assemblies, and interfaces integrate into a system complying with indicated performance and aesthetic requirements.
- B. Design and construct foundation and superstructure to support free-standing integrated exterior mockups.

- C. Build integrated exterior mockups using installers and construction methods that will be used in completed construction.
- D. Use specified products that have been approved by Architect. Coordinate installation of materials and products specified in individual Specification Sections that include Work included in integrated exterior mockups.
- E. The Work of integrated exterior mockups includes, but is not limited to, the following:
 - 1. Cold-formed metal framing and sheathing.
 - 2. Air and weather barriers.
 - 3. Thermal insulation.
 - 4. Flashing and sheet metal trim.
 - 5. Joint sealants.
 - 6. Metal wall panels.
 - 7. Aluminum-framed entrances and storefront.
 - 8. Glazing.
- F. Provide and document modifications to construction details and interfaces between components and systems required to properly sequence the Work, or to pass performance testing requirements. Obtain Architect's approval for modifications.
- G. Retain approved mockups constructed in place. Incorporate fully into the Work.

END OF SECTION

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.
- B. Related Requirements:
 - 1. Section 011000 "Summary" for work restrictions and limitations on utility interruptions.
 - 2. Division 01 NCSU Guidelines apply to this Section.

1.2 USE CHARGES

- A. Installation, removal, and use charges for temporary facilities to be included in the Contract Sum unless otherwise indicated. Allow other entities engaged in the Project to use temporary services and facilities without cost, including, but not limited to, Architect, testing agencies, and authorities having jurisdiction.

1.3 INFORMATIONAL SUBMITTALS

- A. Site Utilization Plan: Show temporary facilities, temporary utility lines and connections, staging areas, construction site entrances, vehicle circulation, and parking areas for construction personnel.
- B. Project Identification and Temporary Signs: Show fabrication and installation details, including plans, elevations, details, layouts, typestyles, graphic elements, and message content.
- C. Erosion- and Sedimentation-Control Plan: Show compliance with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.
- D. Erosion and Sedimentation Control Plan: Show compliance with requirements of 2003 EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.
- E. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire-prevention program.
 - 1. NCSU Division 01 Contractor Safety Requirements apply to this Section.

- F. Moisture- and Mold-Protection Plan: Describe procedures and controls for protecting materials and construction from water absorption and damage and mold. Describe delivery, handling, storage, installation, and protection provisions for materials subject to water absorption or water damage.
1. Indicate procedures for discarding water-damaged materials, protocols for mitigating water intrusion into completed Work, and requirements for replacing water-damaged Work.
 2. Indicate sequencing of work that requires water, such as sprayed fire-resistive materials, plastering, and terrazzo grinding, and describe plans for dealing with water from these operations. Show procedures for verifying that wet construction has dried sufficiently to permit installation of finish materials.
 3. Indicate methods to be used to avoid trapping water in finished work.

1.4 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.5 PROJECT CONDITIONS

- A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 TEMPORARY FACILITIES

- A. Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.

2.2 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.

1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
 2. Heating, Cooling, and Dehumidifying Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.
 3. Permanent HVAC System: If Owner authorizes use of permanent HVAC system for temporary use during construction, provide filter with MERV of 8 at each return-air grille in system and remove at end of construction
- C. Air-Filtration Units: Primary and secondary HEPA-filter-equipped portable units with four-stage filtration. Provide single switch for emergency shutoff. Configure to run continuously.

PART 3 - EXECUTION

3.1 TEMPORARY FACILITIES, GENERAL

- A. Conservation: Coordinate construction and use of temporary facilities with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.
1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. See other Sections for disposition of salvaged materials that are designated as Owner's property.

3.2 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.3 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
- B. Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.
1. Connect temporary sewers to private system indicated as directed by authorities having jurisdiction.

- C. Install water service and distribution piping in sizes and pressures adequate for construction.
- D. Sanitary Facilities: Provide temporary toilets, wash facilities, safety shower and eyewash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.
- E. Temporary Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.
 - 1. Provide temporary dehumidification systems when required to reduce ambient and substrate moisture levels to level required to allow installation or application of finishes and their proper curing or drying.
- F. Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.
 - 1. Install electric power service underground unless otherwise indicated.
- G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

3.4 SUPPORT FACILITIES INSTALLATION

- A. Comply with the following:
 - 1. Provide construction for temporary field offices, shops, and sheds located within construction area or within 30 feet of building lines that is noncombustible in accordance with ASTM E136. Comply with NFPA 241.
 - 2. Utilize designated area within existing building for temporary field offices.
 - 3. Maintain support facilities until Architect schedules Final Completion inspection. Remove before Final Completion. Personnel remaining after Final Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.
- B. Temporary Roads and Paved Areas: Construct and maintain temporary roads and paved areas adequate for construction operations. Locate temporary roads and paved areas within construction limits indicated on Drawings.
 - 1. Provide dust-control treatment that is nonpolluting and nontracking. Reapply treatment as required to minimize dust.

- C. Traffic Controls: Comply with requirements of authorities having jurisdiction.
 - 1. Protect existing site improvements to remain, including curbs, pavement, and utilities.
 - 2. Maintain access for fire-fighting equipment and access to fire hydrants.
- D. Parking: Provide temporary offsite parking areas for construction personnel.
- E. Storage and Staging: Use designated areas of Project site for storage and staging needs.
- F. Dewatering Facilities and Drains: Comply with requirements of authorities having jurisdiction. Maintain Project site, excavations, and construction free of water.
 - 1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining properties or endanger permanent Work or temporary facilities.
 - 2. Remove snow and ice as required to minimize accumulations.
- G. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.
 - 1. Identification Signs: Provide Project identification signs as indicated on Drawings.
 - 2. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.
 - a. Provide temporary, directional signs for construction personnel and visitors.
 - 3. Maintain and touch up signs, so they are legible at all times.
- H. Waste Disposal Facilities: Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."
- I. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.
 - 1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

3.5 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
 - 1. Where access to adjacent properties is required in order to affect protection of existing facilities, obtain written permission from adjacent property owner to access property for that purpose.

- B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
- C. Temporary Erosion and Sedimentation Control: Comply with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent and requirements specified in Section 311000 "Site Clearing."
- D. Stormwater Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.
- E. Tree and Plant Protection: Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from damage from construction operations. Protect tree root systems from damage, flooding, and erosion.
- F. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals, so Project will be free of pests and their residues at Final Completion. Perform control operations lawfully, using materials approved by authorities having jurisdiction.
- G. Site Enclosure Fence: Before construction operations begin, furnish and install site enclosure fence in a manner that will prevent people from easily entering site except by entrance gates.
 - 1. Extent of Fence: As required to enclose entire Project site or portion determined sufficient to accommodate construction operations.
 - 2. Maintain security by limiting number of keys and restricting distribution to authorized personnel. Furnish one set of keys to Owner.
- H. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each workday.
- I. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.
- J. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.
 - 1. Where heating or cooling is needed and permanent enclosure is incomplete, insulate temporary enclosures.

- K. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.
1. Prohibit smoking in construction areas. Comply with additional limits on smoking specified in other Sections.
 2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition in accordance with requirements of authorities having jurisdiction.
 3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.

3.6 MOISTURE AND MOLD CONTROL

- A. Moisture and Mold Protection: Protect stored materials and installed Work in accordance with Moisture and Mold Protection Plan.
- B. Exposed Construction Period: Before installation of weather barriers, when materials are subject to wetting and exposure and to airborne mold spores, protect as follows:
1. Protect porous materials from water damage.
 2. Protect stored and installed material from flowing or standing water.
 3. Keep porous and organic materials from coming into prolonged contact with concrete.
 4. Remove standing water from decks.
 5. Keep deck openings covered or dammed.
- C. Partially Enclosed Construction Period: After installation of weather barriers but before full enclosure and conditioning of building, when installed materials are still subject to infiltration of moisture and ambient mold spores, protect as follows:
1. Do not load or install drywall or other porous materials or components, or items with high organic content, into partially enclosed building.
 2. Keep interior spaces reasonably clean and protected from water damage.
 3. Periodically collect and remove waste containing cellulose or other organic matter.
 4. Discard or replace water-damaged material.
 5. Do not install material that is wet.
 6. Discard and replace stored or installed material that begins to grow mold.
 7. Perform work in a sequence that allows wet materials adequate time to dry before enclosing the material in gypsum board or other interior finishes.
- D. Controlled Construction Period: After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:
1. Control moisture and humidity inside building by maintaining effective dry-in conditions.

2. Use temporary or permanent HVAC system to control humidity within ranges specified for installed and stored materials.
3. Comply with manufacturer's written instructions for temperature, relative humidity, and exposure to water limits.

3.7 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal.
 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
- C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Final Completion.
- D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Final Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
 1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
 2. At Final Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 017700 "Closeout Procedures."

END OF SECTION

SECTION 015639 - TEMPORARY TREE AND PLANT PROTECTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes general protection and pruning of existing trees and plants that are affected by execution of the Work, whether temporary or permanent construction.
- B. Related Requirements:
 - 1. Section 015000 "Temporary Facilities and Controls" for temporary site fencing.
 - 2. Section 311000 "Site Clearing" for removing existing trees and shrubs.

1.3 DEFINITIONS

- A. Caliper: Diameter of a trunk measured by a diameter tape at a height 6 inches above the ground for trees up to and including 4-inch size at this height and as measured at a height of 12 inches above the ground for trees larger than 4-inch size.
- B. Caliper (DBH): Diameter breast height; diameter of a trunk as measured by a diameter tape at a height 54 inches above the ground line as measured at a height of 12 inches above the ground.
- C. Plant-Protection Zone: Area surrounding individual trees, groups of trees, shrubs, or other vegetation to be protected during construction and indicated on Drawings.
- D. Tree-Protection Zone: Area surrounding individual trees or groups of trees to be protected during construction and indicated on Drawings and defined by a circle concentric with each tree with a radius 12 times the tree's caliper size and with a minimum radius of 96 inches unless otherwise indicated.
- E. Vegetation: Trees, shrubs, groundcovers, grass, and other plants.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Review methods and procedures related to temporary tree and plant protection including, but not limited to, the following:
 - a. Tree-service firm's personnel, and equipment needed to make progress and avoid delays.
 - b. Quality-control program.
 - c. Coordination of Work and equipment movement with the locations of protection zones.
 - d. Trenching by hand or with air spade within protection zones.
 - e. Field quality control.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings:
 - 1. Include plans, elevations, sections, and locations of protection-zone fencing and signage, showing relation of equipment-movement routes and material storage locations with protection zones.
 - 2. Detail fabrication and assembly of protection-zone fencing and signage.
 - 3. Indicate extent of trenching by hand or with air spade within protection zones.
- C. Tree Pruning Schedule: Written schedule detailing scope and extent of pruning of trees to remain that interfere with or are affected by construction.
 - 1. Species and size of tree.
 - 2. Location on site plan. Include unique identifier for each.
 - 3. Reason for pruning.
 - 4. Description of pruning to be performed.
 - 5. Description of maintenance following pruning.

1.6 INFORMATIONAL SUBMITTALS

- A. Existing Conditions: Documentation of existing trees and plantings indicated to remain, which establishes preconstruction conditions that might be misconstrued as damage caused by construction activities.
 - 1. Use sufficiently detailed photographs or video recordings.
 - 2. Include plans and notations to indicate specific wounds and damage conditions of each tree or other plants designated to remain.
- B. Quality-control program.

1.7 QUALITY ASSURANCE

- A. Quality-Control Program: Prepare a written program to systematically demonstrate the ability of personnel to properly follow procedures and handle materials and equipment during the Work without damaging trees and plantings. Include dimensioned diagrams for placement of protection zone fencing and signage, instructions given to workers on the use and care of protection zones, and enforcement of requirements for protection zones.

1.8 FIELD CONDITIONS

- A. The following practices are prohibited within protection zones:
 - 1. Storage of construction materials, debris, or excavated material.
 - 2. Moving or parking vehicles or equipment.
 - 3. Foot traffic.
 - 4. Erection of sheds or structures.
 - 5. Impoundment of water.
 - 6. Excavation or other digging unless otherwise indicated.
 - 7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.
- B. Do not direct vehicle or equipment exhaust toward protection zones.
- C. Prohibit heat sources, flames, ignition sources, and smoking within or near protection zones and organic mulch.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Backfill Soil: Planting soil of suitable moisture content and granular texture for placing around tree; free of stones, roots, plants, sod, clods, clay lumps, pockets of coarse sand, concrete slurry, concrete layers or chunks, cement, plaster, building debris, and other extraneous materials harmful to plant growth.
 - 1. Mixture: Well-blended mix of two parts stockpiled soil to one part planting soil.
 - 2. Planting Soil: Planting soil as specified in Section 329113 "Soil Preparation"
- B. Organic Mulch: Free from deleterious materials and suitable as a top dressing for trees and shrubs, consisting of one of the following:
 - 1. Type: Shredded hardwood.
 - 2. Size Range: 3 inches maximum.
 - 3. Color: Natural.

- C. Protection-Zone Fencing: Fencing fixed in position and meeting one of the following requirements: Previously used materials may be used when approved by Designer.
1. Chain-Link Protection-Zone Fencing: Polymer-coated steel or polymer-coated galvanized-steel fencing fabricated from minimum 2-inch opening, 0.148-inch- diameter wire chain-link fabric; with pipe posts, minimum 2-3/8-inch- OD line posts, and 2-7/8-inch- OD corner and pull posts; with 1-5/8-inch- OD top rails and 0.177-inch- diameter bottom tension wire; with tie wires, hog ring ties, and other accessories for a complete fence system.
 - a. Height: 72 inches to 96 inches.
 - b. Polymer-Coating Color: Black.
 2. Wood Protection-Zone Fencing: Constructed of two 2-by-4-inch horizontal rails, with 4-by-4-inch preservative-treated wood posts spaced not more than 96 inches apart, and lower rail set halfway between top rail and ground.
 - a. Height: 48 inches.
 3. Plastic Protection-Zone Fencing: Plastic construction fencing constructed of high-density extruded and stretched polyethylene fabric with 2-inch maximum opening in pattern and weighing a minimum of 0.4 lb/ft.; remaining flexible from minus 60 to plus 200 deg F; inert to most chemicals and acids; minimum tensile yield strength of 2000 psi and ultimate tensile strength of 2680 psi; secured with plastic bands or galvanized-steel or stainless-steel wire ties; and supported by tubular or T-shape galvanized-steel posts spaced not more than 96 inches apart.
 - a. Height: 48 inches.
 - b. Color: High-visibility orange, nonfading.
 4. Gates: Single- or double- swing access gates matching material and appearance of fencing, to allow for maintenance activities within protection zones; leaf width 36 inches.
- D. Protection-Zone Signage: Shop-fabricated, rigid plastic or metal sheet with attachment holes prepunched and reinforced; legibly printed with nonfading lettering and as follows:
1. Size and Text: As shown on Drawings.
 2. Lettering: 3-inch- high minimum, black characters on white background.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Erosion and Sedimentation Control: Examine the site to verify that temporary erosion- and sedimentation-control measures are in place. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.

3.2 PREPARATION

- A. Locate and clearly identify trees, shrubs, and other vegetation to remain or to be relocated. Flag or tie a 1-inch blue vinyl tape around each tree trunk at 54 inches above the ground.
- B. Protect tree root systems from damage caused by runoff or spillage of noxious materials while mixing, placing, or storing construction materials. Protect root systems from ponding, eroding, or excessive wetting caused by dewatering operations.
- C. Tree-Protection Zones: Mulch areas inside tree-protection zones and other areas indicated. Do not exceed indicated thickness of mulch.
 - 1. Apply 6-inch uniform thickness of organic mulch unless otherwise indicated. Do not place mulch within 6 inches of tree trunks.

3.3 PROTECTION ZONES

- A. Protection-Zone Fencing: Install protection-zone fencing along edges of protection zones before materials or equipment are brought on the site and construction operations begin in a manner that will prevent people from easily entering protected areas except by entrance gates. Construct fencing so as not to obstruct safe passage or visibility at vehicle intersections where fencing is located adjacent to pedestrian walkways or in close proximity to street intersections, drives, or other vehicular circulation.
 - 1. Chain-Link Fencing: Install to comply with ASTM F 567 and with manufacturer's written instructions.
 - 2. Posts: Set or drive posts into ground one-third the total height of the fence without concrete footings. Where a post is located on existing paving or concrete to remain, provide appropriate means of post support acceptable to Designer.
 - 3. Access Gates: Install as required; adjust to operate smoothly, easily, and quietly; free of binding, warp, excessive deflection, distortion, nonalignment, misplacement, disruption, or malfunction throughout entire operational range. Confirm that latches and locks engage accurately and securely without forcing or binding.
- B. Protection-Zone Signage: Install protection-zone signage in visibly prominent locations in a manner approved by Designer. Install one sign spaced approximately every 50 feet on protection-zone fencing, but no fewer than four signs with each facing a different direction.
- C. Maintain protection zones free of weeds and trash.
- D. Maintain protection-zone fencing and signage in good condition as acceptable to Designer and remove when construction operations are complete and equipment has been removed from the site.
 - 1. Do not remove protection-zone fencing, even temporarily, to allow deliveries or equipment access through the protection zone.

3.4 EXCAVATION

- A. General: Excavate at edge of protection zones and for trenches indicated within protection zones according to requirements in Section 312000 "Earth Moving" unless otherwise indicated.
- B. Trenching within Protection Zones: Where utility trenches are required within protection zones, excavate under or around tree roots by hand or with air spade, or tunnel under the roots by drilling, auger boring, or pipe jacking. Do not cut main lateral tree roots or taproots; cut only smaller roots that interfere with installation of utilities. Cut roots as required for root pruning. If excavating by hand, use narrow-tine spading forks to comb soil and expose roots.
- C. Redirect roots in backfill areas where possible. If encountering large, main lateral roots, expose roots beyond excavation limits as required to bend and redirect them without breaking. If encountered immediately adjacent to location of new construction and redirection is not practical, cut roots approximately 3 inches back from new construction and as required for root pruning.
- D. Do not allow exposed roots to dry out before placing permanent backfill. Provide temporary earth cover or pack with peat moss and wrap with burlap. Water and maintain in a moist condition. Temporarily support and protect roots from damage until they are permanently relocated and covered with soil.

3.5 ROOT PRUNING

- A. Prune tree roots that are affected by temporary and permanent construction.
- B. Tree roots shall not be pruned or cut unless their removal is unavoidable or absolutely necessary. The Designer shall be notified prior to any operation known or suspected to involve cutting of more than two roots, three inches or more in diameter; and/or four roots between two and three inches in diameter.
 - 1. The Designer shall be notified immediately in the event that roots in excess of that described above are cut, torn, ripped, or otherwise injured.
- C. Upon approval by the Designer, prior to any excavation, removal of sidewalk, or other activity that will result in removal of soil and tree roots, all tree roots within a designated area will be pruned to a depth of 14 inches. Pruning shall occur with a Dosko Root Pruner, or equivalent, in accessible areas, and by hand in areas inaccessible to the root pruning machine. All other root pruning shall be done by hand with approved tools.
- D. Removal of roots greater than one –inch-diameter or parts of roots that are injured or diseased should be performed as follows:
 - 1. Preserve the root bark ridge (similar in structure and function to a branch bark ridge). Directional root pruning is the recommendation technique and should be used during hand excavation around tree roots. Roots are similar to branches in their response to pruning practices. With directional root pruning, objectionable and severely injured roots are properly cut to a lateral root, if possible, that is growing downward or in a favorable direction.

2. All roots needing to be pruned or removed shall be cut cleanly with sharp hand tools, with oversight by the Designer. No wound dressings shall be used.
3. Recommended root pruning tools:
 - a. Scissor-type lopper.
 - b. Scissor-type pruner.
 - c. Large and small hand saws.
 - d. Wound scriber.
 - e. Trowel or small shovel.
 - f. Garden Fork.
 - g. Hand broom.

E. Root Pruning Near Sidewalks:

1. Root pruning should be done carefully, by hand, to achieve the objective of reducing future sidewalk problems as well as preserving the trees. Removing anchoring roots or causing injuries in anchoring roots and root flares can cause future decay and windthrow hazards. Indiscriminate cutting of vigorous roots results in their resprouting so that several more new roots may grow from the cut end, back under the sidewalk, thereby reducing the time between sidewalk repairs. Roots can be managed in the ground without significant harm to trees, if care is taken to avoid injuries that lead to root and trunk decay.
2. Directional root pruning is recommended because it considers the tree's response to root pruning and decay. With directional root pruning, roots are cut to a large lateral, if possible, that is growing downward or in a more favorable direction. The pruned root ends will be less likely to resprout, since a large lateral can assume the new terminal role of the root.
3. Proper removal of selected roots or parts of roots can direct roots away from sidewalks in the future. Procedures for root pruning directly next to sidewalks are as follows:
4. Hand-dig a trench six to eight inches in depth at the edge of the planting strip and sidewalk.
5. Remove all roots less than two inches diameter in this trench back to a desirable lateral root, preserving the root bark ridge. If careful excavation does not reveal a desirable lateral root within 12 inches of the exposed root in question, then the exposed root shall be pruned properly so that a minimal amount of root is removed.
6. Small root bundles, the source of future sidewalk problems, should also be removed at this time.

F. All roots between two and four inches in diameter should be examined by the Designer in terms of their role in anchoring the tree.

1. All roots that contribute significantly to anchorage should be preserved. Remove all other roots in this size range to sound, downward growing lateral roots that are at least one half the size of the root being removed.
2. All roots larger than four inches in diameter are to be preserved unless their removal is absolutely necessary. Preservation of large roots may require:
 - a. Reducing the sidewalk width near the root flare; and/or
 - b. Ramping or bridging the sidewalk over the roots to allow for root growth.

3.6 CROWN PRUNING

- A. Prune branches that are affected by temporary and permanent construction. Prune branches as needed to complete the project.
 - 1. Prune to remove only injured, broken, dying, or dead branches unless otherwise indicated. Do not prune for shape unless otherwise indicated.
 - 2. Do not remove or reduce living branches to compensate for root loss caused by damaging or cutting root system.
 - 3. Pruning Standards: Prune trees according to ANSI A300 (Part 1).
 - a. Type of Pruning: Cleaning, raising, reducing, and thinning where indicated.
 - b. Specialty Pruning: Structural, restoration, vista, espalier, pollarding, palm, and utility where indicated.
- B. Unless otherwise acceptable to Designer, do not cut tree leaders.
- C. Cut branches with sharp pruning instruments; do not break or chop.
- D. Do not paint or apply sealants to wounds.
- E. Provide subsequent maintenance pruning during Contract period as recommended by Designer.
- F. Chip removed branches and spread over areas identified by Designer.

3.7 REGRADING

- A. Lowering Grade: Where new finish grade is indicated below existing grade around trees, slope grade beyond the protection zone. Maintain existing grades within the protection zone.
- B. Lowering Grade within Protection Zone: Where new finish grade is indicated below existing grade around trees, slope grade away from trees as recommended by Designer unless otherwise indicated.
 - 1. Root Pruning: Prune tree roots exposed by lowering the grade. Do not cut main lateral roots or taproots; cut only smaller roots. Cut roots as required for root pruning.
- C. Raising Grade: Where new finish grade is indicated above existing grade around trees, slope grade beyond the protection zone. Maintain existing grades within the protection zone.
- D. Minor Fill within Protection Zone: Where existing grade is 2 inches or less below elevation of finish grade, fill with backfill soil. Place backfill soil in a single uncompacted layer and hand grade to required finish elevations.

3.8 REPAIR AND REPLACEMENT

- A. General: Repair or replace trees, shrubs, and other vegetation indicated to remain or to be relocated that are damaged by construction operations at Contractors's cost, in a manner approved by Designer.
 - 1. Submit details of proposed pruning and repairs.
 - 2. Replace trees and other plants that cannot be repaired and restored to full-growth status, as determined by Designer.

- B. Trees: Remove and replace trees indicated to remain that are considered dead or in an unhealthy condition before the end of the corrections period or are damaged during construction operations that Designer determines are incapable of restoring to normal growth pattern.
 - 1. Small Trees: Provide new trees of same size and species as those being replaced for each tree that measures 4 inches or smaller in caliper size.
 - 2. Large Trees: Provide one new tree(s) of 6-inch caliper size for each 6-inch increment of caliper size of tree being replaced.
 - a. Species: As selected by Designer.
 - 3. Plant and maintain new trees as specified in Section 329300 "Plants."

- C. Excess Mulch: Rake mulched area within protection zones, being careful not to injure roots. Rake to loosen and remove mulch that exceeds a 4-inch uniform thickness to remain.

- D. Soil Aeration: Where directed by Designer, aerate surface soil compacted during construction. Aerate 10 feet beyond drip line and no closer than 36 inches to tree trunk. Drill 2-inch- diameter holes a minimum of 12 inches deep at 24 inches o.c. Backfill holes with an equal mix of augered soil and sand.

3.9 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Disposal: Remove excess excavated material, displaced trees, trash, and debris and legally dispose of them off Owner's property.

END OF SECTION 015639

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.
- B. Related Requirements:
 - 1. Section 012500 "Substitution Procedures" for requests for substitutions.

1.2 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Salvaged items or items reused from other projects are not considered new products. Items that are manufactured or fabricated to include recycled content materials are considered new products, unless indicated otherwise.
 - 3. Comparable Product: Product by named manufacturer that is demonstrated and approved through the comparable product submittal process described in Part 2 "Comparable Products" Article, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation. Published attributes and characteristics of basis-of-design product establish salient characteristics of products.

1. Evaluation of Comparable Products: In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements for purposes of evaluating comparable products of additional manufacturers named in the specification. Manufacturer's published attributes and characteristics of basis-of-design product also establish salient characteristics of products for purposes of evaluating comparable products.
- C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications; submit a comparable product request or substitution request, if applicable.
- D. Comparable Product Request Submittal: An action submittal requesting consideration of a comparable product, including the following information:
1. Identification of basis-of-design product or fabrication or installation method to be replaced, including Specification Section number and title and Drawing numbers and titles.
 2. Data indicating compliance with the requirements specified in Part 2 "Comparable Products" Article.
- E. Basis-of-Design Product Specification Submittal: An action submittal complying with requirements in Section 013300 "Submittal Procedures."
- F. Substitution: Refer to Section 012500 "Substitution Procedures" for definition and limitations on substitutions.
- 1.3 QUALITY ASSURANCE
- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
- 1.4 PRODUCT DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, and handle products, using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

1.5 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
1. Manufacturer's Warranty: Written standard warranty form furnished by individual manufacturer for a particular product and issued in the name of the Owner or endorsed by manufacturer to Owner.
 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner and issued in the name of the Owner or endorsed by manufacturer to Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 2. Specified Form: When specified forms are included in the Project Manual, prepare a written document, using indicated form properly executed.
 3. See other Sections for specific content requirements and particular requirements for submitting special warranties.

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 3. Owner reserves the right to limit selection to products with warranties meeting requirements of the Contract Documents.
 4. Where products are accompanied by the term "as selected," Architect will make selection.
 5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- B. Product Selection Procedures:

1. Sole Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Sole product may be indicated by the phrase "Subject to compliance with requirements, provide the following."
2. Sole Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - a. Sole manufacturer/source may be indicated by the phrase "Subject to compliance with requirements, provide products by the following."
3. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated.
 - a. Limited list of products may be indicated by the phrase "Subject to compliance with requirements, provide one of the following."
4. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed or an unnamed product that complies with requirements.
 - a. Non-limited list of products is indicated by the phrase "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following."
 - b. Provision of an unnamed product is not considered a substitution, if the product complies with requirements.
5. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated.
 - a. Limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, provide products by one of the following."
6. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed or a product by an unnamed manufacturer that complies with requirements.
 - a. Non-limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following."

2. Detailed comparison of significant qualities of proposed product with those of the named basis-of-design product. Significant product qualities include attributes, such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
 3. Evidence that proposed product provides specified warranty.
 4. List of similar installations for completed projects, with project names and addresses and names and addresses of architects and owners, if requested.
 5. Samples, if requested.
- B. Architect's Action on Comparable Products Submittal: If necessary, Architect will request additional information or documentation for evaluation, as specified in Section 013300 "Submittal Procedures."
1. Form of Approval of Submittal: As specified in Section 013300 "Submittal Procedures."
 2. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- C. Submittal Requirements, Single-Step Process: When acceptable to Architect, incorporate specified submittal requirements of individual Specification Section in combined submittal for comparable products. Approval by the Architect of Contractor's request for use of comparable product and of individual submittal requirements will also satisfy other submittal requirements.

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work, including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Field engineering.
 - 3. Installation.
 - 4. Cutting and patching.
 - 5. Progress cleaning.
 - 6. Starting and adjusting.
 - 7. Protection of installed construction.
 - 8. Correction of the Work.

- B. Related Requirements:
 - 1. Section 011000 "Summary" for coordination of Owner-furnished products, and limits on use of Project site.
 - 2. Section 017700 "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, replacing defective work, and final cleaning.

1.2 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of subsequent work.

- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of subsequent work.

1.3 INFORMATIONAL SUBMITTALS

- A. Certified Surveys: Submit two copies signed by land surveyor.

- B. Certificates: Submit certificate signed by land surveyor, certifying that location and elevation of improvements comply with requirements.

1.4 CLOSEOUT SUBMITTALS

- A. Final Property Survey: Submit 10 copies showing the Work performed and record survey data.

1.5 QUALITY ASSURANCE

- A. Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing land-surveying services of the kind indicated.
- B. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
 - 1. Structural Elements: When cutting and patching structural elements, or when encountering the need for cutting and patching of elements whose structural function is not known, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection.
 - 2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
 - 3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
 - 4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- C. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of specified products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Comply with requirements specified in other Sections.
 - 1. For projects requiring compliance with sustainable design and construction practices and procedures, use products for patching that comply with sustainable design requirements.
- B. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, and other construction affecting the Work.
 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, gas service piping, and water-service piping; underground electrical services; and other utilities.
 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
 1. Description of the Work, including Specification Section number and paragraph, and Drawing sheet number and detail, where applicable.
 2. List of detrimental conditions, including substrates.
 3. List of unacceptable installation tolerances.
 4. Recommended corrections.
- D. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Existing Utility Information: Furnish information to local utility that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.
- B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect in accordance with requirements in Section 013100 "Project Management and Coordination."

3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks and existing conditions. If discrepancies are discovered, notify Architect promptly.
- B. Engage a land surveyor experienced in laying out the Work, using the following accepted surveying practices:
 - 1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
 - 2. Establish limits on use of Project site.
 - 3. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
 - 4. Inform installers of lines and levels to which they must comply.
 - 5. Check the location, level and plumb, of every major element as the Work progresses.
 - 6. Notify Architect when deviations from required lines and levels exceed allowable tolerances.
 - 7. Close site surveys with an error of closure equal to or less than the standard established by authorities having jurisdiction.
- C. Site Improvements: Locate and lay out site improvements, including pavements, grading, fill and topsoil placement, utility slopes, and rim and invert elevations.

- D. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.
- E. Record Log: Maintain a log of layout control work. Record deviations from required lines and levels. Include beginning and ending dates and times of surveys, weather conditions, name and duty of each survey party member, and types of instruments and tapes used. Make the log available for reference by Architect.

3.4 FIELD ENGINEERING

- A. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.
 - 1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect. Report lost or destroyed permanent benchmarks or control points promptly. Report the need to relocate permanent benchmarks or control points to Architect before proceeding.
 - 2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.
- B. Benchmarks: Establish and maintain a minimum of two permanent benchmarks on Project site, referenced to data established by survey control points. Comply with authorities having jurisdiction for type and size of benchmark.
 - 1. Record benchmark locations, with horizontal and vertical data, on Project Record Documents.
 - 2. Where the actual location or elevation of layout points cannot be marked, provide temporary reference points sufficient to locate the Work.
 - 3. Remove temporary reference points when no longer needed. Restore marked construction to its original condition.
- C. Certified Survey: On completion of foundation walls, major site improvements, and other work requiring field-engineering services, prepare a certified survey showing dimensions, locations, angles, and elevations of construction and sitework.
- D. Final Property Survey: Engage a land surveyor to prepare a final property survey showing significant features (real property) for Project. Include on the survey a certification, signed by land surveyor, that principal metes, bounds, lines, and levels of Project are accurately positioned as shown on the survey.
 - 1. Show boundary lines, monuments, streets, site improvements and utilities, existing improvements and significant vegetation, adjoining properties, acreage, grade contours, and the distance and bearing from a site corner to a legal point.

3.5 INSTALLATION

- A. Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb, and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
 - 3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
 - 4. Maintain minimum headroom clearance of 96 inches in occupied spaces and 90 inches in unoccupied spaces, unless otherwise indicated on Drawings.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure satisfactory results as judged by Architect. Maintain conditions required for product performance until Final Completion.
- D. Conduct construction operations, so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy of type expected for Project.
- E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on-site and placement in permanent locations.
- F. Tools and Equipment: Select tools or equipment that minimize production of excessive noise levels.
- G. Templates: Obtain and distribute to the parties involved templates for Work specified to be factory prepared and field installed. Check Shop Drawings of other portions of the Work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions with manufacturer.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
 - 2. Allow for building movement, including thermal expansion and contraction.
 - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

- I. Joints: Make joints of uniform width. Where joint locations in exposed Work are not indicated, arrange joints for the best visual effect, as judged by Architect. Fit exposed connections together to form hairline joints.

3.6 CUTTING AND PATCHING

- A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Temporary Support: Provide temporary support of Work to be cut.
- C. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- D. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 3. Concrete: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 4. Excavating and Backfilling: Comply with requirements in applicable Sections where required by cutting and patching operations.
 5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 6. Proceed with patching after construction operations requiring cutting are complete.
- E. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as practicable, as judged by Architect. Provide materials and comply with installation requirements specified in other Sections, where applicable.
 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.

2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.
 - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
 - b. Restore damaged pipe covering to its original condition.
- F. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.7 PROGRESS CLEANING

Final Completion

- A. Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, in accordance with regulations.
 - a. Use containers intended for holding waste materials of type to be stored.
 4. Coordinate progress cleaning for joint-use areas where Contractor and other contractors are working concurrently.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where Work is in progress to the level of cleanliness necessary for proper execution of the Work.
 1. Remove liquid spills promptly.
 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces in accordance with written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Final Completion.

- G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section 017419 "Construction Waste Management and Disposal."
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Final Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to ensure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.8 STARTING AND ADJUSTING

- A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- B. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.
- C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

3.9 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Final Completion.
- B. Protection of Existing Items: Provide protection and ensure that existing items to remain undisturbed by construction are maintained in condition that existed at commencement of the Work.
- C. Comply with manufacturer's written instructions for temperature and relative humidity.

3.10 CORRECTION OF THE WORK

- A. Repair or remove and replace damaged, defective, or nonconforming Work. Restore damaged substrates and finishes.

1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Repair Work previously completed and subsequently damaged during construction period. Repair to like-new condition.
- C. Restore permanent facilities used during construction to their specified condition.
- D. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- E. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- F. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

END OF SECTION

SECTION 017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
 - 1. Salvaging nonhazardous construction waste.
 - 2. Recycling nonhazardous construction waste.
 - 3. Disposing of nonhazardous construction waste.
- B. Related Requirements:
 - 1. Section 311000 "Site Clearing" for disposition of waste resulting from site clearing and removal of above- and below-grade improvements.
 - 2. Division 02 NCSU Reuse, Recycling, and Waste applies to this Section.

1.2 DEFINITIONS

- A. Construction Waste: Building, structure, and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.
- B. Demolition Waste: Building, structure, and site improvement materials resulting from demolition operations.
- C. Disposal: Removal of demolition or construction waste and subsequent salvage, sale, recycling, or deposit in landfill, incinerator acceptable to authorities having jurisdiction, or designated spoil areas on Owner's property.
- D. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.
- E. Salvage: Recovery of demolition or construction waste and subsequent sale or reuse in another facility.

1.3 ACTION SUBMITTALS

- A. Waste Management Plan: Submit plan within 7 days of date established for the Notice to Proceed.

1.4 INFORMATIONAL SUBMITTALS

- A. Waste Reduction Progress Reports: Concurrent with each Application for Payment, submit report. Include the following information:

1. Material category.
 2. Generation point of waste.
 3. Total quantity of waste in tons.
 4. Quantity of waste salvaged, both estimated and actual in tons.
 5. Quantity of waste recycled, both estimated and actual in tons.
 6. Total quantity of waste recovered (salvaged plus recycled) in tons.
 7. Total quantity of waste recovered (salvaged plus recycled) as a percentage of total waste.
- B. Waste Reduction Calculations: Before request for Final Completion, submit calculated end-of-Project rates for salvage, recycling, and disposal as a percentage of total waste generated by the Work.
- C. Recycling and Processing Facility Records: Indicate receipt and acceptance of recyclable waste by recycling and processing facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.
- D. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.

1.5 WASTE MANAGEMENT PLAN

- A. General: Develop a waste management plan according to requirements in this Section. Plan shall consist of waste identification, waste reduction work plan, and cost/revenue analysis. Indicate quantities by weight or volume, but use same units of measure throughout waste management plan.
- B. Waste Identification: Indicate anticipated types and quantities of site-clearing and construction waste generated by the Work. Include estimated quantities and assumptions for estimates.
- C. Waste Reduction Work Plan: List each type of waste and whether it will be salvaged, recycled, or disposed of in landfill or incinerator. Include points of waste generation, total quantity of each type of waste, quantity for each means of recovery, and handling and transportation procedures.
1. Recycled Materials: Include list of local receivers and processors and type of recycled materials each will accept. Include names, addresses, and telephone numbers.
 2. Disposed Materials: Indicate how and where materials will be disposed of. Include name, address, and telephone number of each landfill and incinerator facility.
 3. Handling and Transportation Procedures: Include method that will be used for separating recyclable waste including sizes of containers, container labeling, and designated location where materials separation will be performed.

PART 2 - EXECUTION

2.1 PLAN IMPLEMENTATION

- A. General: Implement approved waste management plan. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
- B. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work.
 - 1. Distribute waste management plan to everyone concerned within three days of submittal return.
 - 2. Distribute waste management plan to entities when they first begin work on-site. Review plan procedures and locations established for salvage, recycling, and disposal.
- C. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged and recycled.
 - 2. Comply with Section 015000 "Temporary Facilities and Controls" for controlling dust and dirt, environmental protection, and noise control.

2.2 RECYCLING CONSTRUCTION WASTE, GENERAL

- A. General: Recycle paper and beverage containers used by on-site workers.
- B. Recycling Incentives: Revenues, savings, rebates, tax credits, and other incentives received for recycling waste materials shall accrue to Contractor.
- C. Preparation of Waste: Prepare and maintain recyclable waste materials according to recycling or reuse facility requirements. Maintain materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process.
- D. Procedures: Separate recyclable waste from other waste materials, trash, and debris. Separate recyclable waste by type at Project site to the maximum extent practical according to approved construction waste management plan.
 - 1. Provide appropriately marked containers or bins for controlling recyclable waste until removed from Project site. Include list of acceptable and unacceptable materials at each container and bin.
 - a. Inspect containers and bins for contamination and remove contaminated materials if found.

2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
3. Stockpile materials away from construction area. Do not store within drip line of remaining trees.
4. Store components off the ground and protect from the weather.
5. Remove recyclable waste from Owner's property and transport to recycling receiver or processor as often as required to prevent overfilling bins.

2.3 RECYCLING CONSTRUCTION WASTE

A. Packaging:

1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in a dry location.
2. Polystyrene Packaging: Separate and bag materials.
3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.

B. Wood Materials:

1. Clean Cut-Offs of Lumber: Grind or chip into small pieces.
2. Clean Sawdust: Bag sawdust that does not contain painted or treated wood.

C. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location.

1. Clean Gypsum Board: Grind scraps of clean gypsum board using small mobile chipper or hammer mill. Screen out paper after grinding.

D. Paint: Seal containers and store by type.

2.4 DISPOSAL OF WASTE

A. General: Except for items or materials to be salvaged or recycled, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. General: Except for items or materials to be salvaged or recycled, remove waste materials and legally dispose of at designated spoil areas on OwnerTM's property.

- C. Burning: Do not burn waste materials.

END OF SECTION

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for Contract closeout, including, but not limited to, the following:
 - 1. Final Completion procedures.
 - 2. List of incomplete items.
 - 3. Submittal of Project warranties.
 - 4. Final cleaning.
- B. Related Requirements:
 - 1. Section 017823 "Operation and Maintenance Data" for additional operation and maintenance manual requirements.
 - 2. Section 017839 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
 - 3. Section 017900 "Demonstration and Training" for requirements to train Owner's maintenance personnel to adjust, operate, and maintain products, equipment, and systems.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of cleaning agent.
- B. Contractor's List of Incomplete Items: Initial submittal at Final Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.3 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.
- C. Field Report: For pest-control inspection.

1.4 Final Completion PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's "punch list"), indicating the value of each item on the list and reasons why the Work is incomplete.

- B. Submittals Prior to Final Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Final Completion. List items below that are incomplete at time of request.
1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction, permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 2. Submit closeout submittals specified in other Division 01 Sections, including Project Record Documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.
 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number.
 5. Submit testing, adjusting, and balancing records.
 6. Submit sustainable design submittals not previously submitted.
 7. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- C. Procedures Prior to Final Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Final Completion. List items below that are incomplete at time of request.
1. Advise Owner of pending insurance changeover requirements.
 2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
 3. Complete startup and testing of systems and equipment.
 4. Perform preventive maintenance on equipment used prior to Final Completion.
 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 017900 "Demonstration and Training."
 6. Advise Owner of changeover in utility services.
 7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
 8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
 9. Complete final cleaning requirements.
 10. Touch up paint and otherwise repair and restore marred exposed finishes to eliminate visual defects.

- D. Inspection: Submit a written request for inspection to determine Final Completion a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Final Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1.5 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining Final Completion, complete the following:
1. Submit a final Application for Payment in accordance with Section 012900 "Payment Procedures."
 2. Certified List of Incomplete Items: Submit certified copy of Architect's Final Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list will state that each item has been completed or otherwise resolved for acceptance.
 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
 4. Submit pest-control final inspection report.
- B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1.6 LIST OF INCOMPLETE ITEMS

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
1. Organize list of spaces in sequential order, starting with exterior areas first, listed by room or space number.
 2. Organize items applying to each space by major element, including categories for ceilings, individual walls, floors, equipment, and building systems.
 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Page number.

4. Submit list of incomplete items in the following format:
 - a. Web-Based Project Software Upload: Utilize software feature for creating and updating list of incomplete items (punch list).

1.7 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
- C. Warranty Electronic File: Provide warranties and bonds in PDF format. Assemble complete warranty and bond submittal package into a single electronic PDF file with bookmarks enabling navigation to each item. Provide bookmarked table of contents at beginning of document.
 1. Submit by uploading to web-based project software site.
- D. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
 1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
1. Complete the following cleaning operations before requesting inspection for certification of Final Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site of rubbish, waste material, litter, and other foreign substances.
 - b. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
 - c. Remove debris and surface dust from limited-access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
 - d. Clean flooring, removing debris, dirt, and staining; clean in accordance with manufacturer's instructions.
 - e. Vacuum and mop concrete.
 - f. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean in accordance with manufacturer's instructions if visible soil or stains remain.
 - g. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
 - h. Remove labels that are not permanent.
 - i. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
 - j. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
 - k. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
 - l. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.
 - m. Clean luminaires, lamps, globes, and reflectors to function with full efficiency.
 - n. Clean strainers.
 - o. Leave Project clean and ready for occupancy.
- C. Pest Control: Comply with pest control requirements in Section 015000 "Temporary Facilities and Controls." Prepare written report.
- D. Construction Waste Disposal: Comply with waste-disposal requirements in Section 017419 "Construction Waste Management and Disposal."

3.2 CORRECTION OF THE WORK

- A. Complete repair and restoration operations required by "Correction of the Work" Article in Section 017300 "Execution" before requesting inspection for determination of Final Completion.

END OF SECTION

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Operation and maintenance documentation directory manuals.
 - 2. Systems and equipment operation manuals.
 - 3. Systems and equipment maintenance manuals.
 - 4. Product maintenance manuals.

1.2 CLOSEOUT SUBMITTALS

- A. Submit operation and maintenance manuals indicated. Provide content for each manual as specified in individual Specification Sections, and as reviewed and approved at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
 - 1. Architect will comment on whether content of operation and maintenance submittals is acceptable.
 - 2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operation and maintenance manuals in the following format:
 - 1. Submit by uploading to web-based project software site. Enable reviewer comments on draft submittals.
- C. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Final Completion and at least 15 days before commencing demonstration and training. Architect will return copy with comments.
 - 1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's comments and prior to commencing demonstration and training.
- D. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

1.3 FORMAT OF OPERATION AND MAINTENANCE MANUALS

- A. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.

1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
2. File Names and Bookmarks: Bookmark individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

1.4 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

- A. Organization of Manuals: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
 1. Title page.
 2. Table of contents.
 3. Manual contents.
- B. Title Page: Include the following information:
 1. Subject matter included in manual.
 2. Name and address of Project.
 3. Name and address of Owner.
 4. Date of submittal.
 5. Name and contact information for Contractor.
 6. Name and contact information for Architect.
 7. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
 8. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

1.5 SYSTEMS AND EQUIPMENT OPERATION MANUALS

- A. Systems and Equipment Operation Manual: Assemble a complete set of data indicating operation of each system, subsystem, and piece of equipment not part of a system. Include information required for daily operation and management, operating standards, and routine and special operating procedures.
- B. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
 2. Performance and design criteria if Contractor has delegated design responsibility.
 3. Operating standards.
 4. Operating procedures.
 5. Operating logs.
 6. Wiring diagrams.
 7. Control diagrams.
 8. Piped system diagrams.
 9. Precautions against improper use.
 10. License requirements including inspection and renewal dates.
- C. Descriptions: Include the following:
1. Product name and model number. Use designations for products indicated on Contract Documents.
 2. Manufacturer's name.
 3. Equipment identification with serial number of each component.
 4. Equipment function.
 5. Operating characteristics.
 6. Limiting conditions.
 7. Performance curves.
 8. Engineering data and tests.
 9. Complete nomenclature and number of replacement parts.
- D. Operating Procedures: Include the following, as applicable:
1. Startup procedures.
 2. Equipment or system break-in procedures.
 3. Routine and normal operating instructions.
 4. Regulation and control procedures.
 5. Instructions on stopping.
 6. Normal shutdown instructions.
 7. Seasonal and weekend operating instructions.
 8. Required sequences for electric or electronic systems.
 9. Special operating instructions and procedures.
- E. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.

- F. Piped Systems: Diagram piping as installed, and identify color coding where required for identification.

1.6 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

- A. Systems and Equipment Maintenance Manuals: Assemble a complete set of data indicating maintenance of each system, subsystem, and piece of equipment not part of a system. Include manufacturers' maintenance documentation, preventive maintenance procedures and frequency, repair procedures, wiring and systems diagrams, lists of spare parts, and warranty information.
- B. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranties and bonds, as described below.
- C. Manufacturers' Maintenance Documentation: Include the following information for each component part or piece of equipment:
 - 1. Standard maintenance instructions and bulletins; include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
 - a. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
 - 2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
 - 3. Identification and nomenclature of parts and components.
 - 4. List of items recommended to be stocked as spare parts.
- D. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:
 - 1. Test and inspection instructions.
 - 2. Troubleshooting guide.
 - 3. Precautions against improper maintenance.
 - 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - 5. Aligning, adjusting, and checking instructions.
- E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.

- F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.
 - G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.
 - H. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.
- 1.7 PRODUCT MAINTENANCE MANUALS
- A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
 - B. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
 - C. Product Information: Include the following, as applicable:
 - 1. Product name and model number.
 - 2. Manufacturer's name.
 - 3. Color, pattern, and texture.
 - 4. Material and chemical composition.
 - 5. Reordering information for specially manufactured products.
 - D. Maintenance Procedures: Include manufacturer's written recommendations and the following:
 - 1. Inspection procedures.
 - 2. Types of cleaning agents to be used and methods of cleaning.
 - 3. List of cleaning agents and methods of cleaning detrimental to product.
 - 4. Schedule for routine cleaning and maintenance.
 - 5. Repair instructions.
 - E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
 - F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for Project Record Documents, including the following:
 - 1. Record Drawings.
- B. Related Requirements:
 - 1. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

1.2 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit one set(s) of marked-up record prints.

1.3 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
 - 1. Preparation: Mark record prints to show the actual installation, where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Accurately record information in an acceptable drawing technique.
 - c. Record data as soon as possible after obtaining it.
 - d. Record and check the markup before enclosing concealed installations.
 - e. Cross-reference record prints to corresponding photographic documentation.
 - 2. Content: Types of items requiring marking include, but are not limited to, the following:
 - a. Dimensional changes to Drawings.
 - b. Revisions to details shown on Drawings.

- c. Depths of foundations.
 - d. Locations and depths of underground utilities.
 - e. Revisions to routing of piping and conduits.
 - f. Revisions to electrical circuitry.
 - g. Actual equipment locations.
 - h. Duct size and routing.
 - i. Locations of concealed internal utilities.
 - j. Changes made by Change Order or Construction Change Directive.
 - k. Changes made following Architect's written orders.
 - l. Details not on the original Contract Drawings.
 - m. Field records for variable and concealed conditions.
 - n. Record information on the Work that is shown only schematically.
3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
 4. Mark record prints with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

1.4 MAINTENANCE OF RECORD DOCUMENTS

- A. Maintenance of Record Documents: Store Record Documents in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain Record Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 017900 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Instruction in operation and maintenance of systems, subsystems, and equipment.

1.2 INFORMATIONAL SUBMITTALS

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
 - 1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.

1.3 QUALITY ASSURANCE

- A. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 014000 "Quality Requirements," experienced in operation and maintenance procedures and training.

1.4 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.
- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data have been reviewed and approved by Architect.

1.5 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
 - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
 - a. System, subsystem, and equipment descriptions.
 - b. Performance and design criteria if Contractor is delegated design responsibility.
 - c. Operating standards.
 - d. Regulatory requirements.
 - e. Equipment function.
 - f. Operating characteristics.
 - g. Limiting conditions.
 - h. Performance curves.
 - 2. Documentation: Review the following items in detail:
 - a. Emergency manuals.
 - b. Systems and equipment operation manuals.
 - c. Systems and equipment maintenance manuals.
 - d. Product maintenance manuals.
 - e. Project Record Documents.
 - f. Identification systems.
 - g. Warranties and bonds.
 - h. Maintenance service agreements and similar continuing commitments.
 - 3. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.
 - e. Control sequences.
 - f. Safety procedures.
 - g. Instructions on stopping.
 - h. Normal shutdown instructions.
 - i. Operating procedures for emergencies.
 - j. Operating procedures for system, subsystem, or equipment failure.
 - k. Seasonal and weekend operating instructions.
 - l. Required sequences for electric or electronic systems.

- m. Special operating instructions and procedures.
- 4. Adjustments: Include the following:
 - a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
- 5. Troubleshooting: Include the following:
 - a. Diagnostic instructions.
 - b. Test and inspection procedures.
- 6. Maintenance: Include the following:
 - a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning.
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
- 7. Repairs: Include the following:
 - a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.

1.6 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."
- B. Set up instructional equipment at instruction location.

1.7 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.

- C. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION

SECTION 031000 - CONCRETE FORMING AND ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Form-facing material for cast-in-place concrete.
- 2. Form liners.
- 3. Shoring, bracing, and anchoring.

B. Related Requirements:

- 1. Section 321313 "Concrete Paving" for formwork related to concrete pavement and walks.

1.3 DEFINITIONS

- A. Form-Facing Material: Temporary structure or mold for the support of concrete while the concrete is setting and gaining sufficient strength to be self-supporting.
- B. Formwork: The total system of support of freshly placed concrete, including the mold or sheathing that contacts the concrete, as well as supporting members, hardware, and necessary bracing.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1. Review the following:

- a. Special inspection and testing and inspecting agency procedures for field quality control.
- b. Construction, movement, contraction, and isolation joints
- c. Forms and form-removal limitations.
- d. Shoring and reshoring procedures.
- e. Anchor rod and anchorage device installation tolerances.

1.5 ACTION SUBMITTALS

A. Product Data: For each of the following:

1. Exposed surface form-facing material.
2. Concealed surface form-facing material.
3. Forms for cylindrical columns.
4. Form liners.
5. Form ties.
6. Waterstops.
7. Form-release agent.

B. Sustainable Design Submittals:

1. Environmental Product Declaration: For each product.
2. Health Product Declaration: For each product.
3. Sourcing of Raw Materials: Corporate sustainability report for each manufacturer.
4. Laboratory Test Reports: For liquid floor treatments and curing and sealing compounds, indicating compliance with requirements for low-emitting materials.

C. Shop Drawings: Prepared by, and signed and sealed by, a qualified professional engineer responsible for their preparation, detailing fabrication, assembly, and support of forms.

1. For exposed vertical concrete walls, indicate dimensions and form tie locations.
2. Indicate dimension and locations of construction and movement joints required to construct the structure in accordance with ACI 301.
 - a. Location of construction joints is subject to approval of the Architect.
3. Indicate location of waterstops.
4. Indicate form liner layout and form line termination details.
5. Indicate proposed schedule and sequence of stripping of forms, shoring removal, and reshoring installation and removal.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For testing and inspection agency.

B. Research Reports: For insulating concrete forms indicating compliance with International Code Council Acceptance Criteria AC308.

C. Field quality-control reports.

D. Minutes of preinstallation conference.

1.7 QUALITY ASSURANCE

A. Testing and Inspection Agency Qualifications: An independent agency qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Form Liners: Store form liners under cover to protect from sunlight.
- B. Waterstops: Store waterstops under cover to protect from moisture, sunlight, dirt, oil, and other contaminants.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Concrete Formwork: Design, engineer, erect, shore, brace, and maintain formwork, shores, and reshores in accordance with ACI 301, to support vertical, lateral, static, and dynamic loads, and construction loads that might be applied, until structure can support such loads, so that resulting concrete conforms to the required shapes, lines, and dimensions.
 - 1. Design wood panel forms in accordance with APA's "Concrete Forming Design/Construction Guide."
 - 2. Design formwork to limit deflection of form-facing material to 1/240 of center-to-center spacing of supports.
- B. Design, engineer, erect, shore, brace, and maintain insulating concrete forms in accordance with ACI 301, to support vertical, lateral, static, and dynamic loads, and construction loads that might be applied, until structure can support such loads, so that resulting concrete conforms to the required shapes, lines, and dimensions.
 - 1. Design cross ties to transfer the effects of the following loads to the cast-in-place concrete core:
 - a. Wind Loads: As indicated on Drawings.
 - 1) Horizontal Deflection Limit: Not more than 1/240 of the wall height.

2.2 FORM-FACING MATERIALS

- A. As-Cast Surface Form-Facing Material:
 - 1. Provide continuous, true, and smooth concrete surfaces.
 - 2. Furnish in largest practicable sizes to minimize number of joints.
 - 3. Acceptable Materials: As required to comply with Surface Finish designations specified in Section 033000 "Cast-In-Place Concrete, and as follows:
 - a. Plywood, metal, or other approved panel materials.
 - b. Exterior-grade plywood panels, suitable for concrete forms, complying with DOC PS 1, and as follows:
 - 1) APA Structural 1 Plyform, B-B or better; mill oiled and edge sealed.
 - 2) APA Plyform Class I, B-B or better; mill oiled and edge sealed.

- B. Concealed Surface Form-Facing Material: Lumber, plywood, metal, plastic, or another approved material.
 - 1. Provide lumber dressed on at least two edges and one side for tight fit.
- C. Forms for Cylindrical Columns, Pedestals, and Supports: Metal, glass-fiber-reinforced plastic, paper, or fiber tubes that produce surfaces with gradual or abrupt irregularities not exceeding specified formwork surface class.
 - 1. Provide forms with sufficient wall thickness to resist plastic concrete loads without detrimental deformation.
- D. Form Liners:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Architectural Polymers, Inc.
 - b. Fitzgerald Formliners.
 - c. Sika Corporation.
 - d. Spec Formliners, Inc.
 - 2. Face Pattern: Smooth.

2.3 WATERSTOPS

- A. Flexible Rubber Waterstops: U.S. Army Corps of Engineers CRD-C 513, for embedding in concrete to prevent passage of fluids through joints, with factory fabricated corners, intersections, and directional changes.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. Williams Products, Inc.
 - 2. Profile: Flat dumbbell with center bulb.
 - 3. Dimensions: 4 inches by 3/16 inch thick; nontapered.
- B. Flexible PVC Waterstops: U.S. Army Corps of Engineers CRD-C 572, for embedding in concrete to prevent passage of fluids through joints, with factory fabricate corners, intersections, and directional changes.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BoMetals, Inc.
 - b. Sika Corporation.
 - c. Vinylex Waterstop & Accessories.
 - 2. Profile: Flat dumbbell with center bulb.

3. Dimensions: 4 inches by 3/16 inch thick; nontapered.
- C. Self-Expanding Butyl Strip Waterstops: Manufactured rectangular or trapezoidal strip, butyl rubber with sodium bentonite or other hydrophilic polymers, for adhesive bonding to concrete, 3/4 by 1 inch.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Carlisle Coatings & Waterproofing Inc.
 - b. CETCO, a Minerals Technologies company.
 - c. Concrete Sealants Inc.
 - d. Sika Corporation.
- D. Self-Expanding Rubber Strip Waterstops: Manufactured rectangular or trapezoidal strip, bentonite-free hydrophilic polymer-modified chloroprene rubber, for adhesive bonding to concrete, 3/8 by 3/4 inch.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Adeka Corporation.
 - b. CETCO, a Minerals Technologies company.
 - c. GCP Applied Technologies Inc.
 - d. Sika Corporation.

2.4 RELATED MATERIALS

- A. Reglets: Fabricate reglets of not less than 0.022-inch- thick, galvanized-steel sheet. Temporarily fill or cover face opening of reglet to prevent intrusion of concrete or debris.
- B. Dovetail Anchor Slots: Hot-dip galvanized-steel sheet, not less than 0.034-inch- thick, with bent tab anchors. Temporarily fill or cover face opening of slots to prevent intrusion of concrete or debris.
- C. Chamfer Strips: Wood, metal, PVC, or rubber strips, 3/4 by 3/4 inch, minimum.
- D. Rustication Strips: Wood, metal, PVC, or rubber strips, kerfed for ease of form removal.
- E. Form-Release Agent: Commercially formulated form-release agent that does not bond with, stain, or adversely affect concrete surfaces and does not impair subsequent treatments of concrete surfaces.
1. Formulate form-release agent with rust inhibitor for steel form-facing materials.
 2. Form release agent for form liners shall be acceptable to form liner manufacturer.
- F. Form Ties: Factory-fabricated, removable or snap-off, glass-fiber-reinforced plastic or metal form ties designed to resist lateral pressure of fresh concrete on forms and to prevent spalling of concrete on removal.

1. Furnish units that leave no corrodible metal closer than 1 inch to the plane of exposed concrete surface.
2. Furnish ties that, when removed, leave holes no larger than 1 inch in diameter in concrete surface.
3. Furnish ties with integral water-barrier plates to walls indicated to receive dampproofing or waterproofing.

PART 3 - EXECUTION

3.1 INSTALLATION OF FORMWORK

- A. Comply with ACI 301.
- B. Construct formwork, so concrete members and structures are of size, shape, alignment, elevation, and position indicated, within tolerance limits of ACI 117 and to comply with the Surface Finish designations specified in Section 033000 "Cast-In-Place Concrete" for as-cast finishes.
- C. Limit concrete surface irregularities as follows:
 1. Surface Finish-1.0: ACI 117 Class D, 1 inch.
 2. Surface Finish-2.0: ACI 117 Class B, 1/4 inch.
 3. Surface Finish-3.0: ACI 117 Class A, 1/8 inch.
- D. Construct forms tight enough to prevent loss of concrete mortar.
 1. Minimize joints.
 2. Exposed Concrete: Symmetrically align joints in forms.
- E. Construct removable forms for easy removal without hammering or prying against concrete surfaces.
 1. Provide crush or wrecking plates where stripping may damage cast-concrete surfaces.
 2. Provide top forms for inclined surfaces steeper than 1.5 horizontal to 1 vertical.
 3. Install keyways, reglets, recesses, and other accessories, for easy removal.
- F. Do not use rust-stained, steel, form-facing material.
- G. Set edge forms, bulkheads, and intermediate screed strips for slabs to achieve required elevations and slopes in finished concrete surfaces.
 1. Provide and secure units to support screed strips
 2. Use strike-off templates or compacting-type screeds.
- H. Provide temporary openings for cleanouts and inspection ports where interior area of formwork is inaccessible.
 1. Close openings with panels tightly fitted to forms and securely braced to prevent loss of concrete mortar.
 2. Locate temporary openings in forms at inconspicuous locations.

- I. Chamfer exterior corners and edges of permanently exposed concrete.
 - J. At construction joints, overlap forms onto previously placed concrete not less than 12 inches.
 - K. Form openings, chases, offsets, sinkages, keyways, reglets, blocking, screeds, and bulkheads required in the Work.
 - 1. Determine sizes and locations from trades providing such items.
 - 2. Obtain written approval of Architect prior to forming openings not indicated on Drawings.
 - L. Construction and Movement Joints:
 - 1. Construct joints true to line with faces perpendicular to surface plane of concrete.
 - 2. Install so strength and appearance of concrete are not impaired, at locations indicated or as approved by Architect.
 - 3. Place joints perpendicular to main reinforcement.
 - 4. Locate joints for beams, slabs, joists, and girders in the middle third of spans.
 - a. Offset joints in girders a minimum distance of twice the beam width from a beam-girder intersection.
 - 5. Locate horizontal joints in walls and columns at underside of floors, slabs, beams, and girders and at the top of footings or floor slabs.
 - 6. Space vertical joints in walls as indicated on Drawings.
 - a. Locate joints beside piers integral with walls, near corners, and in concealed locations where possible.
 - M. Provide temporary ports or openings in formwork where required to facilitate cleaning and inspection.
 - 1. Locate ports and openings in bottom of vertical forms, in inconspicuous location, to allow flushing water to drain.
 - 2. Close temporary ports and openings with tight-fitting panels, flush with inside face of form, and neatly fitted, so joints will not be apparent in exposed concrete surfaces.
 - N. Clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, and other debris just before placing concrete.
 - O. Retighten forms and bracing before placing concrete, as required, to prevent mortar leaks and maintain proper alignment.
 - P. Coat contact surfaces of forms with form-release agent, according to manufacturer's written instructions, before placing reinforcement.
- 3.2 INSTALLATION OF EMBEDDED ITEMS
- A. Place and secure anchorage devices and other embedded items required for adjoining work that is attached to or supported by cast-in-place concrete.

1. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
2. Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of AISC 303.
3. Install reglets to receive waterproofing and to receive through-wall flashings in outer face of concrete frame at exterior walls, where flashing is shown at lintels, shelf angles, and other conditions.
4. Install dovetail anchor slots in concrete structures, as indicated on Drawings.
5. Clean embedded items immediately prior to concrete placement.

3.3 INSTALLATION OF WATERSTOPS

- A. Flexible Waterstops: Install in construction joints and at other joints indicated to form a continuous diaphragm.
1. Install in longest lengths practicable.
 2. Locate waterstops in center of joint unless otherwise indicated on Drawings.
 3. Allow clearance between waterstop and reinforcing steel of not less than 2 times the largest concrete aggregate size specified in Section 033000 "Cast-In-Place Concrete."
 4. Secure waterstops in correct position at 12 inches on center.
 5. Field fabricate joints in accordance with manufacturer's instructions using heat welding.
 - a. Miter corners, intersections, and directional changes in waterstops.
 - b. Align center bulbs.
 6. Clean waterstops immediately prior to placement of concrete.
 7. Support and protect exposed waterstops during progress of the Work.
- B. Self-Expanding Strip Waterstops: Install in construction joints and at other locations indicated on Drawings, according to manufacturer's written instructions, by adhesive bonding, mechanically fastening, and firmly pressing into place.
1. Install in longest lengths practicable.
 2. Locate waterstops in center of joint unless otherwise indicated on Drawings.
 3. Protect exposed waterstops during progress of the Work.

3.4 REMOVING AND REUSING FORMS

- A. Formwork for sides of beams, walls, columns, and similar parts of the Work that does not support weight of concrete may be removed after cumulatively curing at not less than 50 deg F for 24 hours after placing concrete. Concrete has to be hard enough to not be damaged by form-removal operations, and curing and protection operations need to be maintained.
1. Leave formwork for beam soffits, joists, slabs, and other structural elements that support weight of concrete in place until concrete has achieved at least 70 percent of its 28-day design compressive strength.
 2. Remove forms only if shores have been arranged to permit removal of forms without loosening or disturbing shores.

- B. Clean and repair surfaces of forms to be reused in the Work.
 - 1. Split, frayed, delaminated, or otherwise damaged form-facing material are unacceptable for exposed surfaces.
 - 2. Apply new form-release agent.
- C. When forms are reused, clean surfaces, remove fins and laitance, and tighten to close joints.
 - 1. Align and secure joints to avoid offsets.
 - 2. Do not use patched forms for exposed concrete surfaces unless approved by Architect.

3.5 SHORING AND RESHORING INSTALLATION

- A. Comply with ACI 318 and ACI 301 for design, installation, and removal of shoring and reshoring.
 - 1. Do not remove shoring or reshoring until measurement of slab tolerances is complete.
- B. In multistory construction, extend shoring or reshoring over a sufficient number of stories to distribute loads in such a manner that no floor or member will be excessively loaded or will induce tensile stress in concrete members without sufficient steel reinforcement.
- C. Plan sequence of removal of shores and reshore to avoid damage to concrete. Locate and provide adequate reshoring to support construction without excessive stress or deflection.

3.6 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a special inspector and qualified testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Inspections:
 - 1. Inspect formwork for shape, location, and dimensions of the concrete member being formed.
 - 2. Inspect insulating concrete forms for shape, location, and dimensions of the concrete member being formed.

END OF SECTION 031000

SECTION 032000 - CONCRETE REINFORCING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Steel reinforcement bars.
- 2. Welded-wire reinforcement.

B. Related Requirements:

- 1. Section 033816 "Unbonded Post-Tensioned Concrete" for reinforcing related to post-tensioned concrete.
- 2. Section 034100 "Precast Structural Concrete" for reinforcing used in precast structural concrete.
- 3. Section 321313 "Concrete Paving" for reinforcing related to concrete pavement and walks.

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1. Review the following:

- a. Special inspection and testing and inspecting agency procedures for field quality control.
- b. Construction contraction and isolation joints.
- c. Steel-reinforcement installation.

1.4 ACTION SUBMITTALS

- A. Product Data: For the following:

- 1. Each type of steel reinforcement.
- 2. Bar supports.
- 3. Mechanical splice couplers.

- B. Sustainable Design Submittals:

- 1. Environmental Product Declaration: For each product.

2. Health Product Declaration: For each product.
3. Sourcing of Raw Materials: Corporate sustainability report for each manufacturer.

C. Shop Drawings: Comply with ACI SP-066:

1. Include placing drawings that detail fabrication, bending, and placement.
2. Include bar sizes, lengths, materials, grades, bar schedules, stirrup spacing, bent bar diagrams, bar arrangement, location of splices, lengths of lap splices, details of mechanical splice couplers, details of welding splices, tie spacing, hoop spacing, and supports for concrete reinforcement.

D. Construction Joint Layout: Indicate proposed construction joints required to build the structure.

1. Location of construction joints is subject to approval of the Architect.

1.5 INFORMATIONAL SUBMITTALS

A. Welding certificates.

1. Reinforcement To Be Welded: Welding procedure specification in accordance with AWS D1.4/D1.4M

B. Material Test Reports: For the following, from a qualified testing agency:

1. Steel Reinforcement:
 - a. For reinforcement to be welded, mill test analysis for chemical composition and carbon equivalent of the steel in accordance with ASTM A706/A706M.
2. Mechanical splice couplers.

C. Field quality-control reports.

D. Minutes of preinstallation conference.

1.6 QUALITY ASSURANCE

A. Testing Agency Qualifications: An independent agency qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated.

B. Welding Qualifications: Qualify procedures and personnel in accordance with AWS D1.4/D 1.4M.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Steel Reinforcement: Deliver, store, and handle steel reinforcement to prevent bending and damage.

1. Store reinforcement to avoid contact with earth.

PART 2 - PRODUCTS

2.1 STEEL REINFORCEMENT

- A. Recycled Content of Steel Products: Post-consumer recycled content plus one-half of pre-consumer recycled content not less than 25 percent.
- B. Reinforcing Bars: ASTM A615/A615M, Grade 60, deformed.
- C. Low-Alloy Steel Reinforcing Bars: ASTM A706/A706M, deformed.
- D. Plain-Steel Welded-Wire Reinforcement: ASTM A1064/A1064M, plain, fabricated from as-drawn steel wire into flat sheets.

2.2 REINFORCEMENT ACCESSORIES

- A. Joint Dowel Bars: ASTM A615/A615M, Grade 60, plain-steel bars, cut true to length with ends square and free of burrs.
- B. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded-wire reinforcement in place.
 - 1. Manufacture bar supports from steel wire, plastic, or precast concrete in accordance with CRSI's "Manual of Standard Practice," of greater compressive strength than concrete and as follows:
 - a. For concrete surfaces exposed to view, where legs of wire bar supports contact forms, use CRSI Class 1 plastic-protected steel wire, all-plastic bar supports, or CRSI Class 2 stainless steel bar supports.
- C. Mechanical Splice Couplers: ACI 318 Type 1, same material of reinforcing bar being spliced; tension-compression type.
- D. Steel Tie Wire: ASTM A1064/A1064M, annealed steel, not less than 0.0508 inch in diameter.
 - 1. Finish: Plain.

2.3 FABRICATING REINFORCEMENT

- A. Fabricate steel reinforcement according to CRSI's "Manual of Standard Practice."

PART 3 - EXECUTION

3.1 PREPARATION

- A. Protection of In-Place Conditions:

1. Do not cut or puncture vapor retarder.
2. Repair damage and reseal vapor retarder before placing concrete.

B. Clean reinforcement of loose rust and mill scale, earth, ice, and other foreign materials that reduce bond to concrete.

3.2 INSTALLATION OF STEEL REINFORCEMENT

A. Comply with CRSI's "Manual of Standard Practice" for placing and supporting reinforcement.

B. Accurately position, support, and secure reinforcement against displacement.

1. Locate and support reinforcement with bar supports to maintain minimum concrete cover.
2. Do not tack weld crossing reinforcing bars.

C. Preserve clearance between bars of not less than 1 inch, not less than one bar diameter, or not less than 1-1/3 times size of large aggregate, whichever is greater.

D. Provide concrete coverage in accordance with ACI 318.

E. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.

F. Splices: Lap splices as indicated on Drawings.

1. Bars indicated to be continuous, and all vertical bars shall be lapped not less than 36 bar diameters at splices, or 24 inches, whichever is greater.
2. Stagger splices in accordance with ACI 318.
3. Mechanical Splice Couplers: Install in accordance with manufacturer's instructions.
4. Weld reinforcing bars in accordance with AWS D1.4/D 1.4M, where indicated on Drawings.

G. Install welded-wire reinforcement in longest practicable lengths.

1. Support welded-wire reinforcement in accordance with CRSI "Manual of Standard Practice."
 - a. For reinforcement less than W4.0 or D4.0, continuous support spacing shall not exceed 12 inches.
2. Lap edges and ends of adjoining sheets at least one wire spacing plus 2 inches for plain wire.
3. Offset laps of adjoining sheet widths to prevent continuous laps in either direction.
4. Lace overlaps with wire.

3.3 JOINTS

A. Construction Joints: Install so strength and appearance of concrete are not impaired, at locations indicated or as approved by Architect.

1. Place joints perpendicular to main reinforcement.

2. Continue reinforcement across construction joints unless otherwise indicated.
3. Do not continue reinforcement through sides of strip placements of floors and slabs.

B. Doweled Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or asphalt coat one-half of dowel length, to prevent concrete bonding to one side of joint.

3.4 INSTALLATION TOLERANCES

A. Comply with ACI 117.

3.5 FIELD QUALITY CONTROL

A. Special Inspections: Owner will engage a special inspector and qualified testing and inspecting agency to perform field tests and inspections and prepare test reports.

B. Inspections:

1. Steel-reinforcement placement.
2. Steel-reinforcement mechanical splice couplers.
3. Steel-reinforcement welding.

END OF SECTION 032000

SECTION 033000 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Cast-in-place concrete, including concrete materials, mixture design, placement procedures, and finishes.

B. Related Requirements:

- 1. Section 031000 "Concrete Forming and Accessories" for form-facing materials, form liners, insulating concrete forms, and waterstops.
- 2. Section 032000 "Concrete Reinforcing" for steel reinforcing bars and welded-wire reinforcement.
- 3. Section 312000 "Earth Moving" for drainage fill under slabs-on-ground.
- 4. Section 321313 "Concrete Paving" for concrete pavement and walks.
- 5. Section 033543 "Polished Concrete" for concrete finishing and aggregate.
 - a. Polished concrete is Alternate 7.

1.3 DEFINITIONS

- A. Cementitious Materials: Portland cement alone or in combination with fly ash.
- B. Water/Cement Ratio (w/cm): The ratio by weight of water to cementitious materials.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

- 1. Require representatives of each entity directly concerned with cast-in-place concrete to attend, including the following:
 - a. Contractor's superintendent.
 - b. Independent testing agency responsible for concrete design mixtures.
 - c. Ready-mix concrete manufacturer.
 - d. Concrete Subcontractor.
 - e. Owner
 - f. Structural Engineer

2. Review the following:
 - a. Testing and inspecting agency procedures for field quality control.
 - b. Construction joints, control joints, isolation joints, and joint-filler strips.
 - c. Semirigid joint fillers.
 - d. Vapor-retarder installation.
 - e. Anchor rod and anchorage device installation tolerances.
 - f. Cold and hot weather concreting procedures.
 - g. Concrete finishes and finishing.
 - h. Curing procedures.
 - i. Forms and form-removal limitations.
 - j. Shoring and reshoring procedures.
 - k. Methods for achieving specified floor and slab flatness and levelness.
 - l. Floor and slab flatness and levelness measurements.
 - m. Concrete repair procedures.
 - n. Concrete protection.
 - o. Initial curing and field curing of field test cylinders (ASTM C31/C31M.)
 - p. Protection of field cured field test cylinders.

1.5 ACTION SUBMITTALS

A. Product Data: For each of the following.

1. Portland cement.
2. Fly ash.
3. Aggregates.
4. Admixtures:
 - a. Include limitations of use, including restrictions on cementitious materials, supplementary cementitious materials, air entrainment, aggregates, temperature at time of concrete placement, relative humidity at time of concrete placement, curing conditions, and use of other admixtures.
5. Vapor retarders.
6. Floor and slab treatments.
7. Liquid floor treatments.
8. Curing materials.
9. Joint fillers.
10. Repair materials.

B. Sustainable Design Submittals:

1. Environmental Product Declaration: For each product.
2. Health Product Declaration: For each product.
3. Sourcing of Raw Materials: Corporate sustainability report for each manufacturer.
4. Laboratory Test Reports: For liquid floor treatments and curing and sealing compounds, indicating compliance with requirements for low-emitting materials.

C. Design Mixtures: For each concrete mixture, include the following:

1. Mixture identification.
2. Minimum 28-day compressive strength.
3. Durability exposure class.
4. Maximum w/cm.
5. Calculated equilibrium unit weight, for lightweight concrete.
6. Slump limit.
7. Air content.
8. Nominal maximum aggregate size.
9. Indicate amounts of mixing water to be withheld for later addition at Project site if permitted.
10. Intended placement method.
11. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

D. Shop Drawings:

1. Construction Joint Layout: Indicate proposed construction joints required to construct the structure.
 - a. Location of construction joints is subject to approval of the Engineer of Record.

E. Concrete Schedule: For each location of each Class of concrete indicated in "Concrete Mixtures" Article, including the following:

1. Concrete Class designation.
2. Location within Project.
3. Exposure Class designation.
4. Formed Surface Finish designation and final finish.
5. Final finish for floors.
6. Curing process.
7. Floor treatment if any.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For the following:

1. Installer: Include copies of applicable ACI certificates.
2. Ready-mixed concrete manufacturer.
3. Testing agency: Include copies of applicable ACI certificates.

B. Material Certificates: For each of the following, signed by manufacturers:

1. Cementitious materials.
2. Admixtures.
3. Curing compounds.
4. Floor and slab treatments.
5. Bonding agents.
6. Adhesives.
7. Vapor retarders.
8. Semirigid joint filler.

9. Joint-filler strips.
10. Repair materials.

C. Material Test Reports: For the following, from a qualified testing agency:

1. Portland cement.
2. Fly ash.
3. Aggregates.

D. Floor surface flatness and levelness measurements report, indicating compliance with specified tolerances.

E. Research Reports:

1. For concrete admixtures in accordance with ICC's Acceptance Criteria AC198.
2. For sheet vapor retarder/termite barrier, showing compliance with ICC AC380.

F. Minutes of preinstallation conference.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: A qualified installer who employs Project personnel qualified as an ACI-certified Flatwork Technician and Finisher and a supervisor who is a certified ACI Flatwork Concrete Finisher/Technician and certified by the Concrete Policy Council (CPC).

1. Post-Installed Concrete Anchors Installers: ACI-certified Adhesive Anchor Installer.

B. Ready-Mixed Concrete Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C94/C94M requirements for production facilities and equipment.

1. Manufacturer certified in accordance with NRMCA's "Certification of Ready Mixed Concrete Production Facilities."

1.8 DELIVERY, STORAGE, AND HANDLING

A. Comply with ASTM C94/C94M and ACI 301.

1.9 FIELD CONDITIONS

A. Cold-Weather Placement: Comply with ACI 301 and ACI 306.1 and as follows.

1. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
2. When average high and low temperature is expected to fall below 40 deg F for three successive days, maintain delivered concrete mixture temperature within the temperature range required by ACI 301.
3. Do not use frozen materials or materials containing ice or snow.

4. Do not place concrete in contact with surfaces less than 35 deg F, other than reinforcing steel.
5. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mixture designs.

B. Hot-Weather Placement: Comply with ACI 301 and ACI 305.1, and as follows:

1. Maintain concrete temperature at time of discharge to not exceed 95 deg F.
2. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade uniformly moist without standing water, soft spots, or dry areas.

PART 2 - PRODUCTS

2.1 CONCRETE, GENERAL

- A. ACI Publications: Comply with ACI 301 unless modified by requirements in the Contract Documents.

2.2 CONCRETE MATERIALS

- A. Regional Materials: Concrete shall be manufactured within 100 miles of Project site from aggregates and cementitious materials that have been extracted, harvested, or recovered, as well as manufactured, within 100 miles of Project site.

B. Source Limitations:

1. Obtain all concrete mixtures from a single ready-mixed concrete manufacturer for entire Project.
2. Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant.
3. Obtain aggregate from single source.
4. Obtain each type of admixture from single source from single manufacturer.

C. Cementitious Materials:

1. Portland Cement: ASTM C150/C150M, Type I/II, gray.
2. Fly Ash: ASTM C618, Class C or F.

- D. Normal-Weight Aggregates: ASTM C33/C33M, Class 3M coarse aggregate or better, graded. Provide aggregates from a single source.

1. Alkali-Silica Reaction: Comply with one of the following:

- a. Expansion Result of Aggregate: Not more than 0.04 percent at one-year when tested in accordance with ASTM C1293.
- b. Expansion Results of Aggregate and Cementitious Materials in Combination: Not more than 0.10 percent at an age of 16 days when tested in accordance with ASTM C1567.

- c. Alkali Content in Concrete: Not more than 4 lb./cu. yd. for moderately reactive aggregate or 3 lb./cu. yd. for highly reactive aggregate, when tested in accordance with ASTM C1293 and categorized in accordance with ASTM C1778, based on alkali content being calculated in accordance with ACI 301.
 2. Maximum Coarse-Aggregate Size: 3/4 inch nominal.
 3. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.
 4. Aggregate in Polished Concrete (Alternate 7): Class D (Large) aggregate with little or no fine aggregate exposure.
- E. Lightweight Aggregate: ASTM C330/C330M, 3/4-inch nominal maximum aggregate size.
- F. Air-Entraining Admixture: ASTM C260/C260M.
- G. Chemical Admixtures: Certified by manufacturer to be compatible with other admixtures that do not contribute water-soluble chloride ions exceeding those permitted in hardened concrete. Do not use calcium chloride or admixtures containing calcium chloride.
1. Water-Reducing Admixture: ASTM C494/C494M, Type A.
 2. Retarding Admixture: ASTM C494/C494M, Type B.
 3. Water-Reducing and -Retarding Admixture: ASTM C494/C494M, Type D.
 4. High-Range, Water-Reducing Admixture: ASTM C494/C494M, Type F.
 5. High-Range, Water-Reducing and -Retarding Admixture: ASTM C494/C494M, Type G.
 6. Plasticizing and Retarding Admixture: ASTM C1017/C1017M, Type II.
- H. Water and Water Used to Make Ice: ASTM C94/C94M, potable.

2.3 VAPOR RETARDERS

- A. Sheet Vapor Retarder, Class A: ASTM E1745, Class A; not less than 15 mils thick. Include manufacturer's recommended adhesive or pressure-sensitive tape.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Barrier-Bac; Intoplast Group.
 - b. ISI Building Products.
 - c. Poly-America, L.P.
 - d. Reef Industries, Inc.
 - e. Stego Industries, LLC.
 - f. Tex-Trude.
 - g. W.R. Meadows, Inc.

2.4 LIQUID FLOOR TREATMENTS

- A. Penetrating Liquid Floor Treatment: Clear, chemically reactive, waterborne solution of inorganic silicate or silicate materials and proprietary components; odorless; that penetrates, hardens, and densifies concrete surfaces.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Corporation.
 - b. ChemMasters, Inc.
 - c. ChemTec International.
 - d. Concrete Sealers USA.
 - e. Dayton Superior.
 - f. Euclid Chemical Company (The); an RPM company.
 - g. Kaufman Products, Inc.
 - h. Laticrete International, Inc.
 - i. Nox-Crete Products Group.
 - j. PROSOCO, Inc.
 - k. SpecChem, LLC.
 - l. US SPEC, Division of US MIX Company.
 - m. Vexcon Chemicals Inc.
 - n. V-Seal Concrete Sealers & Specialty Coatings.
 - o. W.R. Meadows, Inc.

2. Products shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

2.5 CURING MATERIALS

- A. Evaporation Retarder: Waterborne, monomolecular film forming, manufactured for application to fresh concrete.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Corporation.
 - b. Bon Tool Co.
 - c. ChemMasters, Inc.
 - d. Dayton Superior.
 - e. Euclid Chemical Company (The); an RPM company.
 - f. Kaufman Products, Inc.
 - g. Lambert Corporation.
 - h. Laticrete International, Inc.
 - i. Metalcrete Industries.
 - j. Nox-Crete Products Group.
 - k. Sika Corporation.
 - l. SpecChem, LLC.
 - m. TK Products.
 - n. Vexcon Chemicals Inc.
 - o. W.R. Meadows, Inc.

- B. Moisture-Retaining Cover: ASTM C171, polyethylene film burlap-polyethylene sheet.
 1. Color:

- a. Ambient Temperature Below 50 deg F: Black.
 - b. Ambient Temperature between 50 deg F and 85 deg F: Any color.
 - c. Ambient Temperature Above 85 deg F: White.
- C. Water: Potable or complying with ASTM C1602/C1602M.
- D. Clear, Waterborne, Membrane-Forming, Non-dissipating Curing Compound: ASTM C309, Type 1, Class B, certified by curing compound manufacturer to not interfere with bonding of floor covering.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Anti-Hydro International, Inc.
 - b. BASF Corporation.
 - c. ChemMasters, Inc.
 - d. Dayton Superior.
 - e. Euclid Chemical Company (The); an RPM company.
 - f. Kaufman Products, Inc.
 - g. Lambert Corporation.
 - h. Laticrete International, Inc.
 - i. Metalcrete Industries.
 - j. Nox-Crete Products Group.
 - k. SpecChem, LLC.
 - l. TK Products.
 - m. Vexcon Chemicals Inc.
 - n. W.R. Meadows, Inc.
- E. Clear, Waterborne, Membrane-Forming, Curing and Sealing Compound: ASTM C1315, Type 1, Class A.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ChemMasters, Inc.
 - b. Concrete Sealers USA.
 - c. Dayton Superior.
 - d. Euclid Chemical Company (The); an RPM company.
 - e. Kaufman Products, Inc.
 - f. Lambert Corporation.
 - g. Laticrete International, Inc.
 - h. Metalcrete Industries.
 - i. Nox-Crete Products Group.
 - j. Right Pointe.
 - k. SpecChem, LLC.
 - l. TK Products.
 - m. Vexcon Chemicals Inc.
 - n. W.R. Meadows, Inc.

2. Products shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

2.6 RELATED MATERIALS

- A. Expansion- and Isolation-Joint-Filler Strips: ASTM D1751, asphalt-saturated cellulosic fiber.
- B. Semirigid Joint Filler: Two-component, semirigid, 100 percent solids, epoxy resin with a Type A shore durometer hardness of 80 in accordance with ASTM D2240.
- C. Bonding Agent: ASTM C1059/C1059M, Type II, non-redispersible, acrylic emulsion or styrene butadiene.

2.7 REPAIR MATERIALS

- A. Repair Underlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch and that can be feathered at edges to match adjacent floor elevations.
 1. Cement Binder: ASTM C150/C150M portland cement or hydraulic or blended hydraulic cement, as defined in ASTM C219.
 2. Primer: Product of underlayment manufacturer recommended for substrate, conditions, and application.
 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch or coarse sand, as recommended by underlayment manufacturer.
 4. Compressive Strength: Not less than 4,100 psi at 28 days when tested in accordance with ASTM C109/C109M.
- B. Repair Overlayment: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/4 inch and that can be filled in over a scarified surface to match adjacent floor elevations.
 1. Cement Binder: ASTM C150/C150M portland cement or hydraulic or blended hydraulic cement, as defined in ASTM C219.
 2. Primer: Product of topping manufacturer recommended for substrate, conditions, and application.
 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch or coarse sand as recommended by topping manufacturer.
 4. Compressive Strength: Not less than 5,000 psi at 28 days when tested in accordance with ASTM C109/C109M.

2.8 CONCRETE MIXTURES, GENERAL

- A. Prepare design mixtures for each type and strength of concrete, proportioned on the basis of laboratory trial mixture or field test data, or both, in accordance with ACI 301.

1. Use a qualified testing agency for preparing and reporting proposed mixture designs, based on laboratory trial mixtures.
- B. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement in concrete as follows:
 1. Fly Ash: 15 percent by mass.
- C. Admixtures: Use admixtures in accordance with manufacturer's written instructions.
 1. Use water-reducing, high-range water-reducing, or plasticizing admixture in concrete, as required, for placement and workability.
 2. Use water-reducing and -retarding admixture when required by high temperatures, low humidity, or other adverse placement conditions.
 3. Use water-reducing admixture in pumped concrete, concrete for parking structure slabs, and concrete with a w/cm below 0.50.

2.9 CONCRETE MIXTURES

- A. Class A: Normal-weight concrete used for footings, grade beams, and tie beams.
 1. Exposure Class: ACI 318 F0, S0, W0, C0.
 2. Minimum Compressive Strength: 3,000 psi at 28 days.
 3. Maximum w/cm: 0.55.
 4. Slump Limit: 4 inches, plus or minus 1 inch, before adding high-range water-reducing or plasticizing admixtures at the Project site (8 inches, plus or minus 1 inch thereafter).
 5. Air Content: 2.0 percent, plus or minus 1.5 percent at point of delivery for concrete containing 3/4 inch nominal maximum aggregate size.
 6. Limit water-soluble, chloride-ion content in hardened concrete to 1.00 percent by weight of cement.
- B. Class C: Normal-weight concrete used for interior slabs-on-ground.
 1. Exposure Class: ACI 318 F0, S0, W0, C0.
 2. Minimum Compressive Strength: 4,500 psi at 28 days.
 3. Maximum w/cm: 0.55.
 4. Minimum Cementitious Materials Content: 540 lb/cu. yd.
 5. Slump Limit: 4 inches, plus or minus 1 inch, before adding high-range water-reducing or plasticizing admixtures at the Project site (8 inches, plus or minus 1 inch thereafter).
 6. Air Content: Do not use an air-entraining admixture or allow total air content to exceed 3 percent for concrete used in trowel-finished floors.
 7. Limit water-soluble, chloride-ion content in hardened concrete to 1.00 percent by weight of cement.
 8. See Polished Concrete Specification (03 35 43) for aggregate and finishing requirements. Aggregate in Polished Concrete (Alternate 7): Class D (Large) aggregate with little or no fine aggregate exposure.
- C. Class F: Normal-weight concrete used for exterior slabs-on-ground, concrete toppings/pads over slabs-on-ground, exterior pads, and balcony topping slabs.

1. Exposure Class: ACI 318 F2, S0, W1, C0.
2. Minimum Compressive Strength: 4,500 psi at 28 days.
3. Maximum w/cm: 0.45.
4. Minimum Cementitious Materials Content: 540 lb/cu. yd.
5. Slump Limit: 4 inches, plus or minus 1 inch.
6. Air Content:
 - a. Exposure Classes F2 and F3: 6 percent, plus or minus 1.5 percent at point of delivery for concrete containing 3/4-inch nominal maximum aggregate size.
7. Limit water-soluble, chloride-ion content in hardened concrete to 1.00 percent by weight of cement.

2.10 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, mix, and deliver concrete in accordance with ASTM C94/C94M, and furnish batch ticket information.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verification of Conditions:
 1. Before placing concrete, verify that installation of concrete forms, accessories, and reinforcement, and embedded items is complete and that required inspections have been performed.
 2. Do not proceed until unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Provide reasonable auxiliary services to accommodate field testing and inspections, acceptable to testing agency, including the following:
 1. Daily access to the Work.
 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 3. Secure space for storage, initial curing, and field curing of test samples, including source of water and continuous electrical power at Project site during site curing period for test samples.
 4. Security and protection for test samples and for testing and inspection equipment at Project site.

3.3 INSTALLATION OF EMBEDDED ITEMS

- A. Place and secure anchorage devices and other embedded items required for adjoining Work that is attached to or supported by cast-in-place concrete.

1. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
2. Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of ANSI/AISC 303.
3. Install reglets to receive waterproofing and to receive through-wall flashings in outer face of concrete frame at exterior walls, where flashing is shown at lintels, shelf angles, and other conditions.

3.4 INSTALLATION OF VAPOR RETARDER

- A. Sheet Vapor Retarders: Place, protect, and repair sheet vapor retarder in accordance with ASTM E1643 and manufacturer's written instructions.
1. Install vapor retarder with longest dimension parallel with direction of concrete pour.
 2. Face laps away from exposed direction of concrete pour.
 3. Lap vapor retarder over footings and grade beams not less than 6 inches, sealing vapor retarder to concrete.
 4. Lap joints 6 inches and seal with manufacturer's recommended tape.
 5. Terminate vapor retarder at the top of floor slabs, grade beams, and pile caps, sealing entire perimeter to floor slabs, grade beams, foundation walls, or pile caps.
 6. Seal penetrations in accordance with vapor retarder manufacturer's instructions.
 7. Protect vapor retarder during placement of reinforcement and concrete.
 - a. Repair damaged areas by patching with vapor retarder material, overlapping damages area by 6 inches on all sides, and sealing to vapor retarder.

3.5 JOINTS

- A. Construct joints true to line, with faces perpendicular to surface plane of concrete.
- B. Construction Joints: Coordinate with floor slab pattern and concrete placement sequence.
1. Install so strength and appearance of concrete are not impaired, at locations indicated on Drawings or as approved by the Engineer of Record.
 2. Place joints perpendicular to main reinforcement.
 - a. Continue reinforcement across construction joints unless otherwise indicated.
 - b. Do not continue reinforcement through sides of strip placements of floors and slabs.
 3. Form keyed joints as indicated. Embed keys at least 1-1/2 inches into concrete.
 4. Locate joints for beams, slabs, joists, and girders at third points of spans. Offset joints in girders a minimum distance of twice the beam width from a beam-girder intersection.
 5. Locate horizontal joints in walls and columns at underside of floors, slabs, beams, and girders and at the top of footings or floor slabs.
 6. Space vertical joints in walls as indicated on Drawings. Unless otherwise indicated on Drawings, locate vertical joints beside piers integral with walls, near corners, and in concealed locations where possible.
 7. Use a bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.

- C. Control Joints in Slabs-on-Ground: Form weakened-plane control joints, sectioning concrete into areas as indicated. Construct control joints for a depth equal to at least one-fourth of concrete thickness as follows:
1. Sawed Joints: Form control joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- wide joints into concrete when cutting action does not tear, abrade, or otherwise damage surface and before concrete develops random cracks.
- D. Isolation Joints in Slabs-on-Ground: After removing formwork, install joint-filler strips at slab junctions with vertical surfaces, such as column pedestals, foundation walls, grade beams, and other locations, as indicated.
1. Extend joint-filler strips full width and depth of joint, terminating flush with finished concrete surface unless otherwise indicated on Drawings.
 2. Terminate full-width joint-filler strips not less than 1/2 inch or more than 1 inch below finished concrete surface, where joint sealants, specified in Section 079200 "Joint Sealants," are indicated.
 3. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.
- E. Doweled Joints:
1. Install dowel bars and support assemblies at joints where indicated on Drawings.
 2. Lubricate or asphalt coat one-half of dowel bar length to prevent concrete bonding to one side of joint.

3.6 CONCRETE PLACEMENT

- A. Before placing concrete, verify that installation of formwork, reinforcement, embedded items, and vapor retarder is complete and that required inspections are completed.
1. Immediately prior to concrete placement, inspect vapor retarder for damage and deficient installation, and repair defective areas.
 2. Provide continuous inspection of vapor retarder during concrete placement and make necessary repairs to damaged areas as Work progresses.
- B. Notify Engineer of Record and testing and inspection agencies 24 hours prior to commencement of concrete placement.
- C. Do not add water to concrete during delivery, at Project site, or during placement unless approved by Engineer of Record in writing, but not to exceed the amount indicated on the concrete delivery ticket.
1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- D. Before test sampling and placing concrete, water may be added at Project site, subject to limitations of ACI 301, but not to exceed the amount indicated on the concrete delivery ticket.

1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- E. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete is placed on concrete that has hardened enough to cause seams or planes of weakness.
1. If a section cannot be placed continuously, provide construction joints as indicated.
 2. Deposit concrete to avoid segregation.
 3. Deposit concrete in horizontal layers of depth not to exceed formwork design pressures and in a manner to avoid inclined construction joints.
 4. Consolidate placed concrete with mechanical vibrating equipment in accordance with ACI 301.
 - a. Do not use vibrators to transport concrete inside forms.
 - b. Insert and withdraw vibrators vertically at uniformly spaced locations to rapidly penetrate placed layer and at least 6 inches into preceding layer.
 - c. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity.
 - d. At each insertion, limit duration of vibration to time necessary to consolidate concrete, and complete embedment of reinforcement and other embedded items without causing mixture constituents to segregate.
- F. Deposit and consolidate concrete for floors and slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.
1. Do not place concrete floors and slabs in a checkerboard sequence.
 2. Consolidate concrete during placement operations, so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
 3. Maintain reinforcement in position on chairs during concrete placement.
 4. Screed slab surfaces with a straightedge and strike off to correct elevations.
 5. Level concrete, cut high areas, and fill low areas.
 6. Slope surfaces uniformly to drains where required.
 7. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, before excess bleedwater appears on the surface.
 8. Do not further disturb slab surfaces before starting finishing operations.

3.7 FINISHING FORMED SURFACES

A. As-Cast Surface Finishes:

1. ACI 301 Surface Finish SF-1.0: As-cast concrete texture imparted by form-facing material.
 - a. Patch voids larger than 1-1/2 inches wide or 1/2 inch deep.
 - b. Remove projections larger than 1 inch.
 - c. Tie holes do not require patching.
 - d. Surface Tolerance: ACI 117 Class D.
 - e. Apply to concrete surfaces not exposed to public view.
2. ACI 301 Surface Finish SF-2.0: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams.

- a. Patch voids larger than 3/4 inch wide or 1/2 inch deep.
 - b. Remove projections larger than 1/4 inch.
 - c. Patch tie holes.
 - d. Surface Tolerance: ACI 117 Class B.
 - e. Locations: Apply to concrete surfaces as indicated.
3. ACI 301 Surface Finish SF-3.0:
- a. Patch voids larger than 3/4 inch wide or 1/2 inch deep.
 - b. Remove projections larger than 1/8 inch.
 - c. Patch tie holes.
 - d. Surface Tolerance: ACI 117 Class A.
 - e. Locations: Apply to concrete surfaces as indicated.

B. Related Unformed Surfaces:

1. At tops of walls, horizontal offsets, and similar unformed surfaces adjacent to formed surfaces, strike off smooth and finish with a color and texture matching adjacent formed surfaces.
2. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces unless otherwise indicated.

3.8 FINISHING FLOORS AND SLABS

- A. Comply with ACI 302.1R recommendations for screeding, restraightening, and finishing operations for concrete surfaces. Do not wet concrete surfaces.
- B. See Polished Concrete Specification (03 35 43) for finishing requirements.
- C. Float Finish: (Interior - Base Bid; Alternate – Polished)
1. When bleedwater sheen has disappeared and concrete surface has stiffened sufficiently to permit operation of specific float apparatus, consolidate concrete surface with power-driven floats or by hand floating if area is small or inaccessible to power-driven floats.
 2. Repeat float passes and restraightening until surface is left with a uniform, smooth, granular texture and complies with ACI 117 (ACI A117M) tolerances for conventional concrete.
 3. Apply float finish to surfaces to receive trowel finish and to be covered with fluid-applied or sheet waterproofing, built-up or membrane roofing, or sand-bed terrazzo.
- D. Broom Finish: Apply a broom finish to exterior concrete platforms, steps, ramps, and locations indicated on Drawings.
1. Immediately after float finishing, slightly roughen trafficked surface by brooming with fiber-bristle broom perpendicular to main traffic route.
 2. Coordinate required final finish with Architect before application.

3.9 INSTALLATION OF MISCELLANEOUS CONCRETE ITEMS

- A. Filling In:

1. Fill in holes and openings left in concrete structures after Work of other trades is in place unless otherwise indicated.
 2. Mix, place, and cure concrete, as specified, to blend with in-place construction.
 3. Provide other miscellaneous concrete filling indicated or required to complete the Work.
- B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and by steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.
- C. Equipment Bases and Foundations:
1. Coordinate sizes and locations of concrete bases with actual equipment provided.
 2. Construct concrete bases 4 inches high unless otherwise indicated on Drawings, and extend base not less than 6 inches in each direction beyond the maximum dimensions of supported equipment unless otherwise indicated on Drawings, or unless required for seismic anchor support.
 3. Minimum Compressive Strength: As indicated herein.
 4. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of concrete base.
 5. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete substrate.
 6. Prior to pouring concrete, place and secure anchorage devices.
 - a. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - b. Cast anchor-bolt insert into bases.
 - c. Install anchor bolts to elevations required for proper attachment to supported equipment.

3.10 CONCRETE CURING

- A. Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
1. Comply with ACI 301 and ACI 306.1 for cold weather protection during curing.
 2. Comply with ACI 301 and ACI 305.1 for hot-weather protection during curing.
 3. Maintain moisture loss no more than 0.2 lb/sq. ft. x h, calculated in accordance with ACI 305.1, before and during finishing operations.
- B. Curing Formed Surfaces: Comply with ACI 308.1 as follows:
1. Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces.
 2. If forms remain during curing period, moist cure after loosening forms.
 3. If removing forms before end of curing period, continue curing for remainder of curing period, as follows:
 - a. Continuous Fogging: Maintain standing water on concrete surface until final setting of concrete.
 - b. Continuous Sprinkling: Maintain concrete surface continuously wet.

- c. Absorptive Cover: Pre-dampen absorptive material before application; apply additional water to absorptive material to maintain concrete surface continuously wet.
 - d. Water-Retention Sheeting Materials: Cover exposed concrete surfaces with sheeting material, taping, or lapping seams.
 - e. Membrane-Forming Curing Compound: Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions.
 - 1) Recoat areas subject to heavy rainfall within three hours after initial application.
 - 2) Maintain continuity of coating and repair damage during curing period.
- C. Curing Unformed Surfaces: Comply with ACI 308.1 as follows:
- 1. Begin curing immediately after finishing concrete.
 - 2. Interior Concrete Floors:
 - a. Floors to Receive Floor Coverings Specified in Other Sections: Contractor has option of the following:
 - 1) Absorptive Cover: As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.
 - a) Lap edges and ends of absorptive cover not less than 12-inches.
 - b) Maintain absorptive cover water saturated, and in place, for duration of curing period, but not less than seven days.
 - 2) Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive.
 - a) Immediately repair any holes or tears during curing period, using cover material and waterproof tape.
 - b) Cure for not less than seven days.
 - 3) Ponding or Continuous Sprinkling of Water: Maintain concrete surfaces continuously wet for not less than seven days, utilizing one, or a combination of, the following:
 - a) Water.
 - b) Continuous water-fog spray.
 - b. Floors to Receive Penetrating Liquid Floor Treatments: Contractor has option of the following:
 - 1) Absorptive Cover: As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.

- a) Lap edges and ends of absorptive cover not less than 12 inches.
 - b) Maintain absorptive cover water saturated, and in place, for duration of curing period, but not less than seven days.
- 2) Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive.
- a) Immediately repair any holes or tears during curing period, using cover material and waterproof tape.
 - b) Cure for not less than seven days.
- 3) Ponding or Continuous Sprinkling of Water: Maintain concrete surfaces continuously wet for not less than seven days, utilizing one, or a combination of, the following:
- a) Water.
 - b) Continuous water-fog spray.
- c. Floors to Receive Polished Finish: Contractor has option of the following:
- 1) Absorptive Cover: As soon as concrete has sufficient set to permit application without marring concrete surface, install prewetted absorptive cover over entire area of floor.
 - a) Lap edges and ends of absorptive cover not less than 12 inches.
 - b) Maintain absorptive cover water saturated, and in place, for duration of curing period, but not less than seven days.
- 2) Ponding or Continuous Sprinkling of Water: Maintain concrete surfaces continuously wet for not less than seven days, utilizing one, or a combination of, the following:
- a) Water.
 - b) Continuous water-fog spray.
- d. Floors to Receive Curing Compound:
- 1) Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions.
 - 2) Recoat areas subjected to heavy rainfall within three hours after initial application.
 - 3) Maintain continuity of coating, and repair damage during curing period.
 - 4) Removal: After curing period has elapsed, remove curing compound without damaging concrete surfaces by method recommended by curing compound manufacturer unless manufacturer certifies curing compound does not interfere with bonding of floor covering used on Project.
- e. Floors to Receive Curing and Sealing Compound:

- 1) Apply uniformly to floors and slabs indicated in a continuous operation by power spray or roller in accordance with manufacturer's written instructions.
- 2) Recoat areas subjected to heavy rainfall within three hours after initial application.
- 3) Repeat process 24 hours later and apply a second coat. Maintain continuity of coating, and repair damage during curing period.

3.11 TOLERANCES

- A. Conform to ACI 117.

3.12 APPLICATION OF LIQUID FLOOR TREATMENTS

- A. Penetrating Liquid Floor Treatment: Prepare, apply, and finish penetrating liquid floor treatment in accordance with manufacturer's written instructions.
1. Remove curing compounds, sealers, oil, dirt, laitance, and other contaminants and complete surface repairs.
 2. Do not apply to concrete that is less than seven days' old.
 3. Apply liquid until surface is saturated, scrubbing into surface until a gel forms; rewet; and repeat brooming or scrubbing.
 4. Rinse with water; remove excess material until surface is dry.
 5. Apply a second coat in a similar manner if surface is rough or porous.

3.13 JOINT FILLING

- A. Prepare, clean, and install joint filler in accordance with manufacturer's written instructions.
1. Defer joint filling until concrete has aged at least one month.
 2. Do not fill joints until construction traffic has permanently ceased.
- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joints clean and dry.
- C. Install semirigid joint filler full depth in saw-cut joints and at least 2 inches deep in formed joints.
- D. Overfill joint, and trim joint filler flush with top of joint after hardening.

3.14 CONCRETE SURFACE REPAIRS

- A. Defective Concrete:
1. Repair and patch defective areas when approved by Architect.
 2. Remove and replace concrete that cannot be repaired and patched to Architect's approval.
- B. Patching Mortar: Mix dry-pack patching mortar, consisting of 1 part portland cement to 2-1/2 parts fine aggregate passing a No. 16 sieve, using only enough water for handling and placing.

- C. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.
1. Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch in any dimension to solid concrete.
 - a. Limit cut depth to 3/4 inch.
 - b. Make edges of cuts perpendicular to concrete surface.
 - c. Clean, dampen with water, and brush-coat holes and voids with bonding agent.
 - d. Fill and compact with patching mortar before bonding agent has dried.
 - e. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.
 2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement, so that, when dry, patching mortar matches surrounding color.
 - a. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching.
 - b. Compact mortar in place and strike off slightly higher than surrounding surface.
 3. Repair defects on concealed formed surfaces that will affect concrete's durability and structural performance as determined by Architect.
- D. Repairing Unformed Surfaces:
1. Test unformed surfaces, such as floors and slabs, for finish, and verify surface tolerances specified for each surface.
 - a. Correct low and high areas.
 - b. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.
 2. Repair finished surfaces containing surface defects, including spalls, popouts, honeycombs, rock pockets, crazing, and cracks in excess of 0.01 inch wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width, and other objectionable conditions.
 3. After concrete has cured at least 14 days, correct high areas by grinding.
 4. Correct localized low areas during, or immediately after, completing surface-finishing operations by cutting out low areas and replacing with patching mortar.
 - a. Finish repaired areas to blend into adjacent concrete.
 5. Correct other low areas scheduled to remain exposed with repair topping.
 - a. Cut out low areas to ensure a minimum repair topping depth of 1/4 inch to match adjacent floor elevations.
 - b. Prepare, mix, and apply repair topping and primer in accordance with manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.

6. Repair defective areas, except random cracks and single holes 1 inch or less in diameter, by cutting out and replacing with fresh concrete.
 - a. Remove defective areas with clean, square cuts, and expose steel reinforcement with at least a 3/4-inch clearance all around.
 - b. Dampen concrete surfaces in contact with patching concrete and apply bonding agent.
 - c. Mix patching concrete of same materials and mixture as original concrete, except without coarse aggregate.
 - d. Place, compact, and finish to blend with adjacent finished concrete.
 - e. Cure in same manner as adjacent concrete.
 7. Repair random cracks and single holes 1 inch or less in diameter with patching mortar.
 - a. Groove top of cracks and cut out holes to sound concrete, and clean off dust, dirt, and loose particles.
 - b. Dampen cleaned concrete surfaces and apply bonding agent.
 - c. Place patching mortar before bonding agent has dried.
 - d. Compact patching mortar and finish to match adjacent concrete.
 - e. Keep patched area continuously moist for at least 72 hours.
- E. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.
- F. Repair materials and installation not specified above may be used, subject to Architect's approval.

3.15 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports.
1. Testing agency shall be responsible for providing curing container for composite samples on Site and verifying that field-cured composite samples are cured in accordance with ASTM C31/C31M.
 2. Testing agency shall immediately report to Architect, Contractor, and concrete manufacturer any failure of Work to comply with Contract Documents.
 3. Testing agency shall report results of tests and inspections, in writing, to Owner, Architect, Contractor, and concrete manufacturer within 48 hours of inspections and tests.
 - a. Test reports shall include reporting requirements of ASTM C31/C31M, ASTM C39/C39M, and ACI 301, including the following as applicable to each test and inspection:
 - 1) Project name.
 - 2) Name of testing agency.
 - 3) Names and certification numbers of field and laboratory technicians performing inspections and testing.
 - 4) Name of concrete manufacturer.
 - 5) Date and time of inspection, sampling, and field testing.
 - 6) Date and time of concrete placement.

- 7) Location in Work of concrete represented by samples.
 - 8) Date and time sample was obtained.
 - 9) Truck and batch ticket numbers.
 - 10) Design compressive strength at 28 days.
 - 11) Concrete mixture designation, proportions, and materials.
 - 12) Field test results.
 - 13) Information on storage and curing of samples before testing, including curing method and maximum and minimum temperatures during initial curing period.
 - 14) Type of fracture and compressive break strengths at seven days and 28 days.
- B. Batch Tickets: For each load delivered, submit three copies of batch delivery ticket to testing agency, indicating quantity, mix identification, admixtures, design strength, aggregate size, design air content, design slump at time of batching, and amount of water that can be added at Project site.
- C. Inspections:
1. Headed bolts and studs.
 2. Verification of use of required design mixture.
 3. Concrete placement, including conveying and depositing.
 4. Curing procedures and maintenance of curing temperature.
 5. Verification of concrete strength before removal of shores and forms from beams and slabs.
- D. Concrete Tests: Testing of composite samples of fresh concrete obtained in accordance with ASTM C 172/C 172M shall be performed in accordance with the following requirements:
1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mixture exceeding 5 cu. yd., but less than 25 cu. yd., plus one set for each additional 50 cu. yd. or fraction thereof.
 - a. When frequency of testing provides fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.
 2. Slump: ASTM C143/C143M:
 - a. One test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 - b. Perform additional tests when concrete consistency appears to change.
 3. Air Content: ASTM C231/C231M pressure method, for normal-weight concrete; ASTM C173/C173M volumetric method, for structural lightweight concrete.
 - a. One test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 4. Concrete Temperature: ASTM C1064/C1064M:
 - a. One test hourly when air temperature is 40 deg F and below or 80 deg F and above, and one test for each composite sample.

5. Unit Weight: ASTM C567/C567M fresh unit weight of structural lightweight concrete.
 - a. One test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 6. Compression Test Specimens: ASTM C31/C31M:
 - a. Cast and laboratory cure two sets of four 6-inch by 12-inch or 4-inch by 8-inch cylinder specimens for each composite sample.
 7. Compressive-Strength Tests: ASTM C39/C39M.
 - a. Test one set of two laboratory-cured specimens at seven days and three sets of two specimens at 28 days.
 - b. A compressive-strength test shall be the average compressive strength from a set of two specimens obtained from same composite sample and tested at age indicated.
 8. When strength of field-cured cylinders is less than 85 percent of companion laboratory-cured cylinders, Contractor shall evaluate operations and provide corrective procedures for protecting and curing in-place concrete.
 9. Strength of each concrete mixture will be satisfactory if every average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength, and no compressive-strength test value falls below specified compressive strength by more than 500 psi if specified compressive strength is 5,000 psi, or no compressive strength test value is less than 10 percent of specified compressive strength if specified compressive strength is greater than 5,000 psi.
 10. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
 11. Additional Tests:
 - a. Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Engineer of Record.
 - b. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C42/C42M or by other methods as directed by Engineer of Record.
 - 1) Acceptance criteria for concrete strength shall be in accordance with ACI 301, section 1.6.6.3.
 12. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.
 13. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.
- E. Measure floor and slab flatness and levelness in accordance with ASTM E1155 within 24 hours of completion of floor finishing and promptly report test results to Architect.

3.16 PROTECTION

A. Protect concrete surfaces as follows:

1. Protect from petroleum stains.
2. Diaper hydraulic equipment used over concrete surfaces.
3. Prohibit vehicles from interior concrete slabs.
4. Prohibit use of pipe-cutting machinery over concrete surfaces.
5. Prohibit placement of steel items on concrete surfaces.
6. Prohibit use of acids or acidic detergents over concrete surfaces.
7. Protect liquid floor treatment from damage and wear during the remainder of construction period. Use protective methods and materials, including temporary covering, recommended in writing by liquid floor treatments installer.
8. Protect the concrete slab in accordance with the slab protection provisions in section 03 35 43–Polished Concrete.

END OF SECTION 033000

SECTION 033543 - POLISHED CONCRETE FINISHING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Polished concrete finishing, including staining.
2. Concrete for polished concrete, including concrete materials, mixture design, placement procedures, initial finishing, and curing is specified in Section 033000 "Cast-in-Place Concrete."

B. Related Requirements:

1. Section 012300 "Alternates" for polished concrete provided as an alternate.
2. Section 033000 "Cast-in-Place Concrete" for concrete not designated as polished concrete.

1.2 DEFINITIONS

- A. Design Reference Sample: Sample designated by Architect in the Contract Documents that reflects acceptable surface quality and appearance of polished concrete.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Before submitting design mixtures, review concrete design mixture and examine procedures for ensuring quality of concrete materials. Require representatives of each entity directly concerned with polished concrete to attend, including the following:
 - a. Contractor's superintendent.
 - b. Owner.
 - c. Structural Engineer.
 - d. Independent testing agency responsible for concrete design mixtures.
 - e. Ready-mix concrete manufacturer.
 - f. Cast-in-place concrete subcontractor.
 - g. Polished concrete finishing Subcontractor.
2. Review construction joints, concrete repair procedures, concrete finishing, and protection of polished concrete.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Polishing Schedule: Submit plan showing polished concrete surfaces and schedule of polishing operations for each area of polished concrete before start of polishing operations. Include locations of all joints, including construction joints.
- C. Samples for Initial Selection: For each type of product requiring color selection.
- D. Samples for Verification: For each type of exposed color.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Material Certificates: For each of the following, signed by manufacturers:
 - 1. Repair materials.
 - 2. Stain materials.
 - 3. Liquid floor treatments.

1.6 QUALITY ASSURANCE

- A. Field Sample Panels: After approval of verification sample and before casting concrete, produce field sample panels to demonstrate the approved range of selections made under Sample submittals. Produce a minimum of three sets of full-scale panels, approximately 48 by 48 inches minimum, to demonstrate the expected range of finish, color, and appearance variations.
 - 1. Locate panels as indicated or, if not indicated, as directed by Architect.
 - 2. Maintain field sample panels during construction in an undisturbed condition as a standard for judging the completed Work.
 - 3. Demolish and remove field sample panels when directed.
- B. Mockups: Before casting concrete, build mockups to verify selections made under Sample submittals and to demonstrate typical joints, surface finish, tolerances, and standard of workmanship. Build mockups to comply with the following requirements, using materials indicated for the completed Work:
 - 1. Build mockups in the location and of the size indicated or, if not indicated, as directed by Architect.
 - 2. Demonstrate curing, finishing, and protecting of polished concrete.
 - 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 FIELD CONDITIONS

- A. Traffic Control: Maintain access for vehicular and pedestrian traffic as required for other construction activities.

PART 2 - PRODUCTS

2.1 LIQUID FLOOR TREATMENTS

- A. Penetrating Liquid Floor Treatments for Polished Concrete Finish: Clear, waterborne solution of inorganic silicate or silicate materials and proprietary components; odorless; that penetrates, hardens, and is suitable for polished concrete surfaces.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Advanced Floor Products.
 - b. AmeriPolish.
 - c. ARDEX Americas.
 - d. AWRC Corporation.
 - e. Euclid Chemical Company (The); an RPM company.
 - f. H&C® Decorative Concrete Products; a brand of Sherwin-Williams Co.
 - g. Laticrete International, Inc.
 - h. MAPEI Corporation.
 - i. Moxie International.
 - j. NewLook International, Inc.
 - k. Nox-Crete Products Group.
 - l. PROSOCO, Inc.
 - m. QuestMark.
 - n. Vexcon Chemicals Inc.
 - o. Insert manufacturer's name.

PART 3 - EXECUTION

3.1 POLISHING

- A. Polish: Level 3: High sheen, 800 grit.
- B. Apply polished concrete finish system to cured and prepared slabs to match accepted mockup.
 - 1. Machine grind floor surfaces to receive polished finishes level and smooth and to depth required to reveal aggregate to match approved mockup.
 - 2. Apply penetrating liquid floor treatment for polished concrete in polishing sequence and according to manufacturer's written instructions, allowing recommended drying time between successive coats.

3. Apply penetrating stain for polished concrete in polishing sequence and according to manufacturer's written instructions.
4. Continue polishing with progressively finer-grit diamond polishing pads to gloss level, to match approved mockup.
5. Control and dispose of waste products produced by grinding and polishing operations.
6. Neutralize and clean polished floor surfaces.

END OF SECTION

SECTION 051200 - STRUCTURAL STEEL FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Structural steel.
2. Shear stud connectors.
3. Shrinkage-resistant grout.

B. Related Requirements:

1. Section 051213 "Architecturally Exposed Structural Steel Framing" for additional requirements for architecturally exposed structural steel.
2. Section 053100 "Steel Decking" for field installation of shear stud connectors through deck.
3. Section 055000 "Metal Fabrications" for miscellaneous steel fabrications and other steel items not defined as structural steel.
4. Section 099600 "High-Performance Coatings" for painting requirements.

1.3 DEFINITIONS

- A. Structural Steel: Elements of the structural frame indicated on Drawings and as described in ANSI/AISC 303 "Code of Standard Practice for Steel Buildings and Bridges".

1.4 COORDINATION

- A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.
- B. Coordinate installation of anchorage items to be embedded in or attached to other construction without delaying the Work. Provide setting diagrams, sheet metal templates, instructions, and directions for installation.

1.5 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.6 ACTION SUBMITTALS

A. Product Data:

1. Structural-steel materials.
2. High-strength, bolt-nut-washer assemblies.
3. Shear stud connectors.
4. Anchor rods.
5. Threaded rods.
6. Shop primer.
7. Shrinkage-resistant grout.

B. Sustainable Design Submittals:

1. Environmental Product Declaration: For each product.
2. Health Product Declaration: For each product.
3. Sourcing of Raw Materials: Corporate sustainability report for each manufacturer.

C. Shop Drawings: Show fabrication of structural-steel components.

1. Include details of cuts, connections, splices, camber, holes, and other pertinent data.
2. Include embedment Drawings.
3. Indicate welds by standard AWS symbols, distinguishing between shop and field welds, and show size, length, and type of each weld. Show backing bars that are to be removed and supplemental fillet welds where backing bars are to remain.
4. Indicate type, size, and length of bolts, distinguishing between shop and field bolts. Identify pretensioned and slip-critical, high-strength bolted connections.

D. Delegated-Design Submittal: For structural-steel connections indicated on Drawings to comply with design loads, include analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.7 INFORMATIONAL SUBMITTALS

A. Qualification Data:

1. For Fabricator, see either 1.8.A.1 or 1.8.A.2 for informational submittals needed to satisfy qualification requirements.
2. For Erector, see either 1.8.B.1 or 1.8.B.2 for informational submittals needed to satisfy qualification requirements.

B. Welding certificates, as used by either the Fabricator or the Erector.

C. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.

D. Mill test reports for structural-steel materials, including chemical and physical properties.

E. Product Test Reports: For the following:

1. Bolts, nuts, and washers, including mechanical properties and chemical analysis.
2. Direct-tension indicators.
3. Tension-control, high-strength, bolt-nut-washer assemblies.
4. Shear stud connectors.

1.8 QUALITY CONTROL

A. Fabricator Qualifications: The Fabricator must meet at least one of the two following requirements.

1. A Fabricator that participates in the AISC Quality Certification Program and is designated an AISC-Certified Plant, Category BU or is accredited by the IAS Fabricator Inspection Program for Structural Steel (Accreditation Criteria 172). The Fabricator shall also have a minimum of 5 years of experience in fabricating structural steel like that indicated for this project (with a record of successful service performance) and sufficient capacity to fabricate the structural steel without delaying the work. Qualification requirements shall be satisfied by submittal of the following:
 - a. Completed project history for Fabricator, specifically focused on projects whose structural steel is like that for this project. Project history shall include Owner and Structural Engineer (as well as primary contacts) for each project listed. This qualification requirement shall be submitted as part of the bidding process.
 - b. Current AISC or IAS certification documents.
2. A Fabricator that has an established and maintained quality control program to ensure that the work is performed in accordance with the requirements in ANSI/AISC 303 “Code of Standard Practice for Steel Buildings and Bridges”, ANSI/AISC 360 “Specification for Structural Steel Buildings”, and the Contract Documents. Program shall at a minimum address inspection of the items noted in ANSI/AISC 360 N2. The Fabricator shall also have a minimum of 5 years of experience in fabricating structural steel like that indicated for this project (with a record of successful service performance) and sufficient capacity to fabricate the structural steel without delaying the work. Qualification requirements shall be satisfied by submittal of the following:
 - a. Completed project history for Fabricator, specifically focused on projects whose structural steel is like that for this project. Project history shall include Owner and Structural Engineer (as well as primary contacts) for each project listed. This qualification requirement shall be submitted as part of the bidding process.
 - b. A written quality control manual that shall include (at a minimum) procedures for material control, inspection, and non-conformances.
 - c. Quality Control Inspector (QCI) qualifications.

B. Erector Qualifications: The Erector must meet at least one of the two following requirements.

1. An Erector who participates in the AISC Quality Certification Program and is designated an AISC-Certified Erector, Category CSE. The Erector shall also have a minimum of 5 years of experience in erecting structural steel like that indicated for this project (with a record of successful service performance) and sufficient capacity to erect the structural steel without delaying the work. Qualification requirements shall be satisfied by submittal of the following:

- a. Completed project history for Erector, specifically focused on projects whose structural steel is like that for this project. Project history shall include Owner and Structural Engineer (as well as primary contacts) for each project listed. This qualification requirement shall be submitted as part of the bidding process.
 - b. Current AISC certification documents.
2. An Erector that has an established and maintained quality control program to ensure that the work is performed in accordance with the requirements in ANSI/AISC 303 “Code of Standard Practice for Steel Buildings and Bridges”, ANSI/AISC 360 “Specification for Structural Steel Buildings”, and the Contract Documents. Program shall at a minimum address inspection of the items noted in ANSI/AISC 360 N2. The Erector shall also have a minimum of 5 years of experience in erecting structural steel like that indicated for this project (with a record of successful service performance) and sufficient capacity to erect the structural steel without delaying the work. Qualification requirements shall be satisfied by submittal of the following:
- a. Completed project history for Erector, specifically focused on projects whose structural steel is like that for this project. Project history shall include Owner and Structural Engineer (as well as primary contacts) for each project listed. This qualification requirement shall be submitted as part of the bidding process.
 - b. A written quality control manual that shall include (at a minimum) procedures for material control, inspection, and non-conformances.
 - c. Quality Control Inspector (QCI) qualifications.
- C. Welding Qualifications: Qualify procedures and personnel in accordance with AWS D1.1/D1.1M.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Store materials to permit easy access for inspection and identification. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers. Protect steel members and packaged materials from corrosion and deterioration.
1. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures. Repair or replace damaged materials or structures as directed.
- B. Store fasteners in a protected place in sealed containers with manufacturer's labels intact.
1. Fasteners may be repackaged provided Owner's testing and inspecting agency observes repackaging and seals containers.
 2. Clean and re-lubricate bolts and nuts that become dry or rusty before use.
 3. Comply with manufacturers' written recommendations for cleaning and lubricating ASTM F3125/F3125M, Grade F1852 bolt assemblies and for retesting bolt assemblies after lubrication.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Comply with applicable provisions of the following specifications and documents:
 - 1. ANSI/AISC 303 "Code of Standard Practice for Steel Buildings and Bridges".
 - 2. ANSI/AISC 360 "Specification for Structural Steel Buildings".
 - 3. RCSC's "Specification for Structural Joints Using High-Strength Bolts".
- B. Connection Design Information:
 - 1. Design connections and final configuration of member reinforcement at connections in accordance with ANSI/AISC 303 by fabricator's qualified professional engineer.
 - a. Use Load and Resistance Factor Design; data are given at factored-load level.
- C. Moment Connections: Type PR, partially restrained.
- D. Construction: As indicated.

2.2 STRUCTURAL-STEEL MATERIALS

- A. W-Shapes: ASTM A992/A992M.
- B. Channels, Angles: ASTM A36/A36M.
- C. Plate and Bar: ASTM A36/A36M, and ASTM A572/A572M, Grade 50 as indicated.
- D. Cold-Formed Hollow Structural Sections: ASTM A500/A500M, Grade B structural tubing.
- E. Steel Pipe: ASTM A500/A500M, Grade B.
 - 1. Weight Class: Standard, or as indicated.
 - 2. Finish: Black except where indicated to be galvanized.
- F. Welding Electrodes: Comply with AWS requirements.

2.3 BOLTS AND CONNECTORS

- A. High-Strength A325 Bolts, Nuts, and Washers: ASTM F3125/F3125M, Grade A325, Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers; all with plain finish.
- B. High-Strength A490 Bolts, Nuts, and Washers: ASTM F3125/F3125M, Grade A490, Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers; all with plain finish.

- C. Shear Stud Connectors: ASTM A108, AISI C-1015 through C-1020, headed-stud type, cold-finished carbon steel; AWS D1.1/D1.1M, Type B.

2.4 RODS

- A. Unheaded Anchor Rods: ASTM F1554, Grade 36, or Grades 55 and 105 as indicated on the Drawings.

- 1. Configuration: Straight.
- 2. Nuts: ASTM A563 heavy-hex carbon steel.
- 3. Plate Washers: ASTM A36/A36M carbon steel.
- 4. Washers: ASTM F436, Type 1, hardened carbon steel.
- 5. Finish: Hot-dip zinc coating, ASTM A153/A153M, Class C.

- B. Headed Anchor Rods: ASTM F1554, Grade 36, or Grades 55 and 105 as indicated on the Drawings.

- 1. Configuration: Straight.
- 2. Nuts: ASTM A563 heavy-hex carbon steel.
- 3. Plate Washers: ASTM A36/A36M carbon steel.
- 4. Washers: ASTM F436, Type 1, hardened carbon steel.
- 5. Finish: Hot-dip zinc coating, ASTM A153/A153M, Class C.

- C. Threaded Rods: ASTM A36/A36M.

- 1. Nuts: ASTM A 63 heavy-hex carbon steel.
- 2. Washers: ASTM F436, Type 1, hardened carbon steel.
- 3. Finish: Hot-dip zinc coating, ASTM A153/A153M, Class C.

2.5 PRIMER

- A. Steel Primer:

- 1. Fabricator's standard lead- and chromate-free, non-asphaltic, rust-inhibiting primer complying with MPI#79 and compatible with topcoat.

- B. Galvanized-Steel Primer: MPI#134.

- 1. Etching Cleaner: MPI#25, for galvanized steel.
- 2. Galvanizing Repair Paint: ASTM A780/A780M.

2.6 SHRINKAGE-RESISTANT GROUT

- A. Non-metallic, Shrinkage-Resistant Grout: ASTM C1107/C1107M, factory-packaged, non-metallic aggregate grout, non-corrosive and non-staining, mixed with water to consistency suitable for application and a 30-minute working time.

2.7 FABRICATION

- A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate in accordance with ANSI/AISC 303 and to ANSI/AISC 360.
 - 1. Camber structural-steel members where indicated.
 - 2. Fabricate beams with rolling camber up.
 - 3. Identify high-strength structural steel in accordance with ASTM A6/A6M and maintain markings until structural-steel framing has been erected.
 - 4. Mark and match-mark materials for field assembly.
 - 5. Complete structural-steel assemblies, including welding of units, before starting shop-priming operations.
- B. Thermal Cutting: Perform thermal cutting by machine to greatest extent possible.
 - 1. Plane thermally cut edges to be welded to comply with requirements in AWS D1.1/D1.1M.
- C. Bolt Holes: Cut, drill, or punch standard bolt holes perpendicular to metal surfaces.
- D. Finishing: Accurately finish ends of columns and other members transmitting bearing loads.
- E. Cleaning: Clean and prepare steel surfaces that are to remain unpainted in accordance with SSPC-SP 1.
- F. Shear Stud Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Weld using automatic end welding of headed-stud shear connectors in accordance with AWS D1.1/D1.1M and manufacturer's written instructions.
- G. Steel Wall-Opening Framing: Select true and straight members for fabricating steel wall-opening framing to be attached to structural-steel frame. Straighten as required to provide uniform, square, and true members in completed wall framing. Build up welded framing, weld exposed joints continuously, and grind smooth.
- H. Holes: Provide holes required for securing other work to structural steel and for other work to pass through steel members.
 - 1. Cut, drill, or punch holes perpendicular to steel surfaces. Do not thermally cut bolt holes or enlarge holes by burning.
 - 2. Baseplate Holes: Cut, drill, mechanically thermal cut, or punch holes perpendicular to steel surfaces.
 - 3. Weld threaded nuts to framing and other specialty items indicated to receive other work.
- I. Inspection Requirements: Quality control inspection tasks shall be performed by the Fabricator's QCI in accordance with ANSI/AISC 360 N5.4 (Inspection of Welding), N5.6 (Inspection of High-Strength Bolting), and N5.7 (Inspection of Galvanized Structural Steel Main Members). Tasks in Tables N5.4-1 through N5.4-3 and Tables N5.6-1 through N5.6-3 listed for quality control (QC) are those inspections performed by the QCI(s) to ensure that the work is performed in accordance with the Contract Documents.

1. Non-destructive testing (NDT) of welded joints provided during fabrication shall be performed by either an independent and qualified testing agency or the qualified QCI(s). All testing reports shall be submitted to the Owner for review.
 - a. Conduct NDT of all welded joints primarily supporting gravity loads (i.e. cantilevers). Reduction in the rate of NDT per N5.5e is prohibited.
 - b. For Risk Category II structures, conduct NDT of 10% of remaining CJP groove welds for materials 5/16" thick and greater per ANSI/AISC 360 N5.5b.
 - c. For Risk Category III and IV structures, conduct NDT of all remaining CJP groove welds for materials 5/16" thick and greater per ANSI/AISC 360 N5.5b.
 - d. Conduct NDT of all welded joints subject to fatigue, where required by ANSI/AISC 360 Appendix 3, Table A-3.1. Reduction in the rate of NDT per N5.5e is prohibited.

- J. Special Inspections: Where special inspections are required by the Contract Documents, the Owner will engage the Special Inspector to perform an audit of the fabrication and quality control practices employed by the Fabricator. Where the Fabricator is qualified through the option noted in 1.8.A.1, the requirement for this audit during fabrication shall be waived.
 1. The Fabricator shall meet all requirements of ANSI/AISC 303 8.5 to accommodate an audit of the fabrication shop.
 2. Prior to the commencement of fabrication, the Special Inspector shall submit to the Owner for review a written plan identifying the frequency and extent of visits to the fabrication shop.
 3. At a minimum, the audit by the Special Inspector shall include review of the following:
 - a. The Fabricator's quality control manual and procedures for material control, inspection, and non-conformances.
 - b. Material test reports for all members, fasteners, and consumables.
 - c. The steel fabrication process including member fit-up, material selection, welding procedures and personnel, etc. Records need to be maintained for all material sources, members using the noted materials, consumables used, welder(s) employed, dates of completion, and when the QCI completed the inspection.
 - d. Inspections representing a sampling of the before, during, and after QA tasks noted in ANSI/AISC 360 N5.5, N5.6, and N5.8.

- K. At the completion of fabrication, the Fabricator shall submit a certificate of compliance to the Owner stating that the materials supplied and work performed by the Fabricator are in accordance with the Contract Documents. All testing/inspection reports generated as part of 2.7.I or 2.7.J shall also be submitted for review at the completion of fabrication.

2.8 SHOP CONNECTIONS

- A. High-Strength Bolts: Shop install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for type of bolt and type of joint specified.
 1. Joint Type: Snug tightened.

- B. Weld Connections: Comply with AWS D1.1/D1.1M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.

1. Assemble and weld built-up sections by methods that maintain true alignment of axes without exceeding tolerances in ANSI/AISC 303 for mill material.

2.9 GALVANIZING

- A. Hot-Dip Galvanized Finish: Apply zinc coating by the hot-dip process to structural steel in accordance with ASTM A123/A123M.
 1. Fill vent and drain holes that are exposed in the finished Work unless they function as weep holes, by plugging with zinc solder and filing off smooth.
 2. Galvanize items as indicated on the Drawings.

2.10 SHOP PRIMING

- A. Shop prime steel surfaces, except the following:
 1. Surfaces embedded in concrete or mortar. Extend priming of partially embedded members to a depth of 2 inches.
 2. Surfaces to be field welded.
 3. Surfaces of high-strength bolted, slip-critical connections.
 4. Surfaces to receive sprayed fire-resistive materials (applied fireproofing).
 5. Galvanized surfaces.
- B. Surface Preparation of Steel: Clean surfaces to be painted. Remove loose rust and mill scale and spatter, slag, or flux deposits. Prepare surfaces in accordance with the following specifications and standards:
 1. SSPC-SP 2.
 2. SSPC-SP 3.
- C. Priming: Immediately after surface preparation, apply primer in accordance with manufacturer's written instructions and at rate recommended by SSPC to provide a minimum dry film thickness of 1.5 mils. Use priming methods that result in full coverage of joints, corners, edges, and exposed surfaces.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify, with certified steel erector present, elevations of concrete- and masonry-bearing surfaces and locations of anchor rods, bearing plates, and other embedments for compliance with requirements.
 1. Prepare a certified survey of existing conditions. Include bearing surfaces, anchor rods, bearing plates, and other embedments showing dimensions, locations, angles, and elevations.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Provide temporary shores, guys, braces, and other supports during erection to keep structural steel secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural steel, connections, and bracing are in place unless otherwise indicated on Drawings.
 - 1. Do not remove temporary shoring supporting composite deck construction and structural-steel framing until cast-in-place concrete has attained its design compressive strength.

3.3 ERECTION

- A. Set structural steel accurately in locations and to elevations indicated and in accordance with ANSI/AISC 303 and ANSI/AISC 360.
- B. Base Plates, Bearing Plates, and Leveling Plates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, and roughen surfaces prior to setting plates. Clean bottom surface of plates.
 - 1. Set plates for structural members on wedges, shims, or setting nuts as required.
 - 2. Weld plate washers to top of baseplate.
 - 3. Snug-tighten anchor rods after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before packing with grout.
 - 4. Promptly pack shrinkage-resistant grout solidly between bearing surfaces and plates, so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure. Comply with manufacturer's written installation instructions for grouting.
- C. Maintain erection tolerances of structural steel within ANSI/AISC 303.
- D. Align and adjust various members that form part of complete frame or structure before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that are in permanent contact with members. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.
 - 1. Level and plumb individual members of structure. Slope roof framing members to slopes indicated on Drawings.
 - 2. Make allowances for difference between temperature at time of erection and mean temperature when structure is completed and in service.
- E. Splice members only where indicated.
- F. Do not use thermal cutting during erection.
- G. Do not enlarge unfair holes in members by burning or using drift pins. Ream holes that must be enlarged to admit bolts.

- H. Inspection Requirements: Quality control inspection tasks shall be performed by the Erector's QCI in accordance with ANSI/AISC 360 N5.4 (Inspection of Welding), N5.6 (Inspection of High-Strength Bolting), and N5.7 (Inspection of Galvanized Structural Steel Main Members). Tasks in Tables N5.4-1 through N5.4-3 and Tables N5.6-1 through N5.6-3 listed for quality control (QC) are those inspections performed by the QCI(s) to ensure that the work is performed in accordance with the Contract Documents.
1. Non-destructive testing (NDT) of welded joints provided during erection shall be performed by an independent and qualified testing agency (see 3.3.J). All testing reports shall be submitted to the Owner for review.
 - a. Conduct NDT of all welded joints primarily supporting gravity loads (i.e. cantilevers). Reduction in the rate of NDT per N5.5e is prohibited.
 - b. For Risk Category II structures, conduct NDT of 10% of remaining CJP groove welds for materials 5/16" thick and greater per ANSI/AISC 360 N5.5b.
 - c. For Risk Category III and IV structures, conduct NDT of all remaining CJP groove welds for materials 5/16" thick and greater per ANSI/AISC 360 N5.5b.
 - d. Conduct NDT of all welded joints subject to fatigue, where required by ANSI/AISC 360 Appendix 3, Table A-3.1. Reduction in the rate of NDT per N5.5e is prohibited.
 - I. Special Inspections: Where special inspections are required by the Contract Documents, the Owner will engage a Special Inspector to perform the tasks noted in the Statement of Special Inspections during erection. These inspections shall be considered to satisfy the quality assurance requirements of ANSI/AISC 360 Chapter N.
 - J. Testing Agency: The Owner will engage an independent and qualified testing agency to perform tests and inspections.
 1. Bolted Connections: Inspect and test bolted connections in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts".
 2. Welded Connections: Visually inspect field welds in accordance with AWS D1.1/D1.1M. Non-destructive testing (NDT) methods (as required) are as follows:
 - a. Liquid Penetrant Inspection: ASTM E165/E165M.
 - b. Magnetic Particle Inspection: ASTM E709, performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration are not acceptable.
 - c. Ultrasonic Inspection: ASTM E164.
 - d. Radiographic Inspection: ASTM E94/E94M.
 - K. At the completion of erection, the approved Erector shall submit a certificate of compliance to the Owner stating that the materials supplied and work performed by the Erector are in accordance with the Contract Documents.

3.4 FIELD CONNECTIONS

- A. High-Strength Bolts: Install high-strength bolts in accordance with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for bolt and joint type specified.
1. Joint Type: Snug tightened.

- B. Weld Connections: Comply with AWS D1.1/D1.1M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.
 - 1. Comply with ANSI/AISC 303 and ANSI/AISC 360 for bearing, alignment, adequacy of temporary connections, and removal of paint on surfaces adjacent to field welds.
 - 2. Assemble and weld built-up sections by methods that maintain true alignment of axes without exceeding tolerances in ANSI/AISC 303 for mill material.

3.5 PROTECTION

- A. Galvanized Surfaces: Clean areas where galvanizing is damaged or missing, and repair galvanizing to comply with ASTM A780/A780M.
- B. Touchup Painting: Immediately after erection, clean exposed areas where primer is damaged or missing, and paint with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.
 - 1. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning or SSPC-SP 3 power-tool cleaning.
- C. Touchup Priming: Cleaning and touchup priming are specified in Section 099600 "High-Performance Coatings."

END OF SECTION 051200

SECTION 052100 - STEEL JOIST FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. K-series steel joists.
 - 2. K-series steel joist substitutes.
 - 3. Steel joist accessories.

1.3 DEFINITIONS

- A. SJI's "Specifications": Steel Joist Institute's "Standard Specifications, Load Tables and Weight Tables for Steel Joists and Joist Girders."
- B. Special Joists: Steel joists or joist girders requiring modification by manufacturer to support nonuniform, unequal, or special loading conditions that invalidate load tables in SJI's "Specifications."

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of joist, accessory, and product.
- B. Shop Drawings:
 - 1. Include layout, designation, number, type, location, and spacing of joists.
 - 2. Include joining and anchorage details; bracing, bridging, and joist accessories; splice and connection locations and details; and attachments to other construction.
 - 3. Indicate locations and details of bearing plates to be embedded in other construction.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For manufacturer.
- B. Welding certificates.
- C. Manufacturer certificates.

- D. Mill Certificates: For each type of bolt.
- E. Comprehensive engineering analysis of special joists signed and sealed by the qualified professional engineer responsible for its preparation.
- F. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A manufacturer certified by SJI to manufacture joists complying with applicable standard specifications and load tables in SJI's "Specifications."
 - 1. Manufacturer's responsibilities include providing professional engineering services for designing special joists to comply with performance requirements.
- B. Welding Qualifications: Qualify field-welding procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle joists as recommended in SJI's "Specifications."
- B. Protect joists from corrosion, deformation, and other damage during delivery, storage, and handling.

1.8 SEQUENCING

- A. Deliver steel bearing plates to be built into cast-in-place concrete and masonry construction.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Canam Steel Corporation; Canam Group, Inc.
 - 2. CMC Joist & Deck.
 - 3. Gooder-Henrichsen Co.
 - 4. New Millennium Building Systems, LLC.
 - 5. Structures of U.S.A., Inc.
 - 6. Valley Joist.
 - 7. Vulcraft; Nucor Vulcraft Group.

2.2 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Provide special joists and connections capable of withstanding design loads indicated on Drawings.
1. Use LRFD; data are given at factored-load level.
 2. Design special joists to withstand design loads with live-load deflections no greater than the following:
 - a. Floor Joists: Vertical deflection of $1/360$ of the span.
 - b. Roof Joists: Vertical deflection of $1/240$ of the span.
- B. Recycled Content of Steel Products: Post-consumer recycled content plus one-half of pre-consumer recycled content not less than 50 percent.

2.3 STEEL JOISTS

- A. K-Series Steel Joist: Manufactured steel joists of type indicated according to "Standard Specification for Open Web Steel Joists, K-Series" in SJI's "Specifications," with steel-angle top- and bottom-chord members, underslung ends, and parallel top chord.
1. Joist Type: K-series steel joists and KCS-type K-series steel joists.
 2. K-Series Steel Joist Substitutes: Manufacture according to "Standard Specifications for Open Web Steel Joists, K-Series" in SJI's "Specifications," with steel-angle or -channel members.
 3. Provide holes in chord members for connecting and securing other construction to joists.
 4. Top-Chord Extensions: Extend top chords of joists with SJI's Type S top-chord extensions where indicated on Drawings, complying with SJI's "Specifications."
 5. Extended Ends: Extend bearing ends of joists with SJI's Type R extended ends where indicated on Drawings, complying with SJI's "Specifications."
 6. Camber joists according to SJI's "Specifications."
 7. Equip bearing ends of joists with manufacturer's standard beveled ends or sloped shoes if joist slope exceeds $1/4$ inch per 12 inches.
- B. Long-Span Steel Joist: Manufactured steel joists according to "Standard Specification for Longspan Steel Joists, LH-Series and Deep Longspan Steel Joists, DLH-Series" in SJI's "Specifications," with steel-angle top- and bottom-chord members; of joist type and end and top-chord arrangements as follows:
1. Joist Type: LH-series long-span steel joists and DLH-series long-span steel joists.
 2. End Arrangement: Underslung.
 3. Top-Chord Arrangement: Parallel.
 4. Provide holes in chord members for connecting and securing other construction to joists.
 5. Camber long-span steel joists according to SJI's "Specifications."
 6. Equip bearing ends of joists with manufacturer's standard beveled ends or sloped shoes if joist slope exceeds $1/4$ inch per 12 inches.

2.4 STEEL JOIST GIRDERS

- A. Manufactured joist girders according to "Standard Specification for Joist Girders" in SJI's "Specifications," with steel-angle top- and bottom-chord members; with end and top-chord arrangements as follows:
1. End Arrangement: Underslung with bottom-chord extensions.
 2. Top-Chord Arrangement: Parallel.
 3. Provide holes in chord members for connecting and securing other construction to joist girders.
 4. Camber joist girders according to SJI's "Specifications."
 5. Equip bearing ends of joists with manufacturer's standard beveled ends or sloped shoes if joist slope exceeds 1/4 inch per 12 inches.

2.5 PRIMERS

- A. Primer:
1. SSPC-Paint 15, or manufacturer's standard shop primer complying with performance requirements in SSPC-Paint 15.

2.6 STEEL JOIST ACCESSORIES

- A. Bridging:
1. Provide bridging anchors and number of rows of horizontal or diagonal bridging of material, size, and type required by SJI's "Specifications" for type of joist, chord size, spacing, and span. Furnish additional erection bridging if required for stability.
- B. Fabricate steel bearing plates from ASTM A36/A36M steel with integral anchorages of sizes and thicknesses indicated on Drawings. Hot-dip zinc coat according to ASTM A123/A123M.
- C. High-Strength Bolts, Nuts, and Washers: ASTM F3125/F3125M, Grade A325, Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers.
1. Finish: Plain.
- D. Welding Electrodes: Comply with AWS standards.
- E. Galvanizing Repair Paint: ASTM A780/A780M.
- F. Furnish miscellaneous accessories including splice plates and bolts required by joist manufacturer to complete joist assembly.

2.7 CLEANING AND SHOP PAINTING

- A. Clean and remove loose scale, heavy rust, and other foreign materials from fabricated joists and accessories by hand-tool cleaning, SSPC-SP 2 or power-tool cleaning, SSPC-SP 3.

- B. Do not prime paint joists and accessories to receive sprayed fire-resistive materials.
- C. Apply one coat of shop primer to joists and joist accessories to be primed to provide a continuous, dry paint film not less than 1 mil thick.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine supporting substrates, embedded bearing plates, and abutting structural framing for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Do not install joists until supporting construction is in place and secured.
- B. Install joists and accessories plumb, square, and true to line; securely fasten to supporting construction according to SJI's "Specifications," joist manufacturer's written instructions, and requirements in this Section.
 - 1. Before installation, splice joists delivered to Project site in more than one piece.
 - 2. Space, adjust, and align joists accurately in location before permanently fastening.
 - 3. Install temporary bracing and erection bridging, connections, and anchors to ensure that joists are stabilized during construction.
 - 4. Delay rigidly connecting bottom-chord extensions to columns or supports until dead loads are applied.
- C. Field weld joists to supporting steel bearing plates and framework. Coordinate welding sequence and procedure with placement of joists. Comply with AWS requirements and procedures for welding, appearance and quality of welds, and methods used in correcting welding work.
- D. Bolt joists to supporting steel framework using high-strength structural bolts. Comply with RCSC's "Specification for Structural Joints Using High-Strength Bolts" for high-strength structural bolt installation and tightening requirements.
- E. Install and connect bridging concurrently with joist erection, before construction loads are applied. Anchor ends of bridging lines at top and bottom chords if terminating at walls or beams.

3.3 REPAIRS

- A. Repair damaged galvanized coatings on galvanized items with galvanized repair paint according to ASTM A780/A780M and manufacturer's written instructions.
- B. Touchup Painting:

1. Immediately after installation, clean, prepare, and prime or re-prime field connections, rust spots, and abraded surfaces of prime-painted joists, bearing plates, abutting structural steel, and accessories.
 - a. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning or SSPC-SP 3 power-tool cleaning.
 - b. Apply a compatible primer of same type as primer used on adjacent surfaces.

3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Visually inspect field welds according to AWS D1.1/D1.1M.
- C. Visually inspect bolted connections.
- D. Prepare test and inspection reports.

END OF SECTION 052100

SECTION 053100 - STEEL DECKING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Roof deck.

B. Related Requirements:

- 1. Section 051200 "Structural Steel Framing" for shop- and field-welded shear connectors.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of deck, accessory, and product indicated.

B. Sustainable Design Submittals:

- 1. Product Data: For recycled content, indicating post-consumer and pre-consumer recycled content and cost.

C. Shop Drawings:

- 1. Include layout and types of deck panels, anchorage details, reinforcing channels, pans, cut deck openings, special jointing, accessories, and attachments to other construction.

1.4 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

- B. Product Certificates: For each type of steel deck.

- C. Product Test Reports: For tests performed by a qualified testing agency, indicating that each of the following complies with requirements:

- 1. Power-actuated mechanical fasteners.

1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM E329 for testing indicated.
- B. Welding Qualifications: Qualify procedures and personnel according to AWS D1.3/D1.3M, "Structural Welding Code - Sheet Steel."

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Protect steel deck from corrosion, deformation, and other damage during delivery, storage, and handling.
- B. Stack steel deck on platforms or pallets and slope to provide drainage. Protect with a waterproof covering and ventilate to avoid condensation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. AISI Specifications: Comply with calculated structural characteristics of steel deck according to AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members."
- B. Fire-Resistance Ratings: Comply with ASTM E119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.
- C. Recycled Content of Steel Products: Post-consumer recycled content plus one-half of pre-consumer recycled content not less than 25 percent.

2.2 ROOF DECK

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Canam Steel Corporation; Canam Group, Inc.
 - 2. Cordeck.
 - 3. DACS, Inc.
 - 4. Epic Metals Corporation.
 - 5. Marlyn Steel Decks, Inc.
 - 6. New Millennium Building Systems, LLC.
 - 7. Nucor Corp.
 - 8. Roof Deck, Inc.
 - 9. Valley Joist.

- B. Roof Deck: Fabricate panels, without top-flange stiffening grooves, to comply with "SDI Specifications and Commentary for Steel Roof Deck," in SDI Publication No. 31, and with the following:
1. Galvanized-Steel Sheet: ASTM A653/A653M, Structural Steel (SS), Grade 33, G60 zinc coating.
 2. Deck Profile: As indicated.
 3. Profile Depth: As indicated.
 4. Design Uncoated-Steel Thickness: As indicated.
 5. Span Condition: As indicated.
 6. Side Laps: Overlapped or interlocking seam at Contractor's option.

2.3 ACCESSORIES

- A. General: Provide manufacturer's standard accessory materials for deck that comply with requirements indicated.
- B. Mechanical Fasteners: Corrosion-resistant, low-velocity, power-actuated or pneumatically driven carbon-steel fasteners; or self-drilling, self-threading screws.
- C. Side-Lap Fasteners: Corrosion-resistant, hexagonal washer head; self-drilling, carbon-steel screws, No. 10 minimum diameter.
- D. Flexible Closure Strips: Vulcanized, closed-cell, synthetic rubber.
- E. Miscellaneous Sheet Metal Deck Accessories: Steel sheet, minimum yield strength of 33,000 psi, not less than 0.0359-inch design uncoated thickness, of same material and finish as deck; of profile indicated or required for application.
- F. Column Closures, End Closures, Z-Closures, and Cover Plates: Steel sheet, of same material, finish, and thickness as deck unless otherwise indicated.
- G. Weld Washers: Uncoated steel sheet, shaped to fit deck rib, 0.0747 inch thick, with factory-punched hole of 3/8-inch minimum diameter.
- H. Flat Sump Plates: Single-piece steel sheet, 0.0747 inch thick, of same material and finish as deck. For drains, cut holes in the field.
- I. Galvanizing Repair Paint: ASTM A780/A780M.
- J. Repair Paint: Manufacturer's standard rust-inhibitive primer of same color as primer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine supporting frame and field conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

- A. Install deck panels and accessories according to applicable specifications and commentary in SDI Publication No. 31, manufacturer's written instructions, and requirements in this Section.
- B. Install temporary shoring before placing deck panels if required to meet deflection limitations.
- C. Locate deck bundles to prevent overloading of supporting members.
- D. Place deck panels on supporting frame and adjust to final position with ends accurately aligned and bearing on supporting frame before being permanently fastened. Do not stretch or contract side-lap interlocks.
- E. Place deck panels flat and square and fasten to supporting frame without warp or deflection.
- F. Cut and neatly fit deck panels and accessories around openings and other work projecting through or adjacent to deck.
- G. Provide additional reinforcement and closure pieces at openings as required for strength, continuity of deck, and support of other work.
- H. Comply with AWS requirements and procedures for manual shielded metal arc welding, appearance and quality of welds, and methods used for correcting welding work.
- I. Mechanical fasteners may be used in lieu of welding to fasten deck. Locate mechanical fasteners and install according to deck manufacturer's written instructions.

3.3 ROOF DECK INSTALLATION

- A. Fasten roof deck panels to steel supporting members as indicated.
- B. Side-Lap and Perimeter Edge Fastening: Fasten side laps and perimeter edges of panels between supports as indicated.
- C. End Bearing: Install deck ends over supporting frame with a minimum end bearing of 1-1/2 inches, with end joints as follows:
 - 1. End Joints: Lapped 2 inches minimum or butted at Contractor's option.
- D. Roof Sump Pans and Sump Plates: Install over openings provided in roof deck and mechanically fasten flanges to top of deck. Space mechanical fasteners not more than 12 inches apart with at least one fastener at each corner.
 - 1. Install reinforcing channels or zees in ribs to span between supports and mechanically fasten.

- E. Miscellaneous Roof Deck Accessories: Install ridge and valley plates, finish strips, end closures, and reinforcing channels according to deck manufacturer's written instructions. Mechanically fasten to substrate to provide a complete deck installation.
 - 1. Weld cover plates at changes in direction of roof deck panels unless otherwise indicated.
- F. Flexible Closure Strips: Install flexible closure strips over partitions, walls, and where indicated. Install with adhesive according to manufacturer's written instructions to ensure complete closure.

3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Field welds will be subject to inspection.
- C. Prepare test and inspection reports.

3.5 PROTECTION

- A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on both surfaces of deck with galvanized repair paint according to ASTM A780/A780M and manufacturer's written instructions.

END OF SECTION 053100

SECTION 054000 - COLD-FORMED METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Exterior non-load-bearing wall framing.

1.2 ACTION SUBMITTALS

A. Product Data: For the following:

1. Cold-formed steel framing materials.
2. Exterior non-load-bearing wall framing.
3. Vertical deflection clips.
4. Single deflection track.
5. Double deflection track.
6. Post-installed anchors.
7. Power-actuated anchors.

B. Sustainable Design Submittals:

1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

C. Shop Drawings:

1. Include layout, spacings, sizes, thicknesses, and types of cold-formed steel framing; fabrication; and fastening and anchorage details, including mechanical fasteners.
2. Indicate reinforcing channels, opening framing, supplemental framing, strapping, bracing, bridging, splices, accessories, connection details, and attachment to adjoining work.

D. Delegated-Design Submittal: For cold-formed metal framing, signed by a North Carolina registered engineer.

1.3 INFORMATIONAL SUBMITTALS

A. Product certificates.

B. Product test reports.

C. Research Reports:

1. For post-installed anchors, from ICC-ES or other qualified testing agency acceptable to authorities having jurisdiction.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Cold-Formed Steel Framing Standards: Unless more stringent requirements are indicated, framing complies with AISI S100 and ASTM C955.

2.2 COLD-FORMED STEEL FRAMING MATERIALS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Framing Members, General: Comply with ASTM C955 for conditions indicated.
- C. Steel Sheet: ASTM A1003/A1003M, Structural Grade, Type H, metallic coated, of grade and coating designation as follows:
 1. Grade: ST33H.
 2. Coating: G60, A60, AZ50, or GF30.
- D. Steel Sheet for Vertical Deflection Clips: ASTM A653/A653M, structural steel, zinc coated, of grade and coating as follows:
 1. Grade: 33.
 2. Coating: G60.

2.3 EXTERIOR NON-LOAD-BEARING WALL FRAMING

- A. Steel Studs: Manufacturer's standard C-shaped steel studs, of web depths indicated, punched, with stiffened flanges, and as follows:
 1. Minimum Base-Metal Thickness: 0.0329 inch.
 2. Flange Width: 2 inches.
 3. Section Properties: <Insert minimum allowable calculated section modulus, moment of inertia, and allowable moment>.
- B. Vertical Deflection Clips, Exterior: Manufacturer's standard head clips, capable of accommodating upward and downward vertical displacement of primary structure through positive mechanical attachment to stud web.
- C. Single Deflection Track: Manufacturer's single, deep-leg, U-shaped steel track; unpunched, with unstiffened flanges, of web depth to contain studs while allowing free vertical movement, with flanges designed to support horizontal loads and transfer them to the primary structure.

- D. Double Deflection Tracks: Manufacturer's double, deep-leg, U-shaped steel tracks, consisting of nested inner and outer tracks; unpunched, with unstiffened flanges.

2.4 FRAMING ACCESSORIES

- A. Fabricate steel-framing accessories from ASTM A1003/A1003M, Structural Grade, Type H, metallic coated steel sheet, of same grade and coating designation used for framing members.
- B. Provide accessories of manufacturer's standard thickness and configuration, unless otherwise indicated.

2.5 ANCHORS, CLIPS, AND FASTENERS

- A. Anchor Bolts: ASTM F1554, Grade 36, threaded carbon-steel hex-headed bolts, carbon-steel nuts, and flat, hardened-steel washers; zinc coated by hot-dip process according to ASTM A153/A153M, Class C.
- B. Post-Installed Anchors: Fastener systems with bolts of same basic metal as fastened metal, if visible, unless otherwise indicated; with working capacity greater than or equal to the design load, according to an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC01 as appropriate for the substrate.
 - 1. Uses: Securing cold-formed steel framing to structure.
 - 2. Type: Torque-controlled expansion anchor.
 - 3. Material for Exterior or Interior Locations and Where Stainless Steel Is Indicated: Alloy Group 1 stainless steel bolts, ASTM F593, and nuts, ASTM F594.
- C. Power-Actuated Anchors: Fastener systems with working capacity greater than or equal to the design load, according to an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.
- D. Mechanical Fasteners: ASTM C1513, corrosion-resistant-coated, self-drilling, self-tapping, steel drill screws.
 - 1. Head Type: Low-profile head beneath sheathing; manufacturer's standard elsewhere.

2.6 MISCELLANEOUS MATERIALS

- A. Galvanizing Repair Paint: ASTM A780/A780M.
- B. Shims: Load-bearing, high-density, multimonomer, nonleaching plastic; or cold-formed steel of same grade and metallic coating as framing members supported by shims.

- C. Sill Sealer Gasket: Closed-cell neoprene foam, 1/4 inch thick, selected from manufacturer's standard widths to match width of bottom track or rim track members as required.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Install sill sealer gasket at the underside of wall bottom track or rim track and at the top of foundation wall or slab at stud or joist locations.

3.2 INSTALLATION, GENERAL

- A. Cold-formed steel framing may be shop or field fabricated for installation, or it may be field assembled.
- B. Install cold-formed steel framing according to AISI S200, AISI S202, and manufacturer's written instructions unless more stringent requirements are indicated.
- C. Install cold-formed steel framing and accessories plumb, square, and true to line, and with connections securely fastened.
- D. Install framing members in one-piece lengths unless splice connections are indicated for track or tension members.
- E. Install temporary bracing and supports to secure framing and support loads equal to those for which structure was designed. Maintain braces and supports in place, undisturbed, until entire integrated supporting structure has been completed and permanent connections to framing are secured.
- F. Install insulation, specified in Section 072100 "Thermal Insulation," in framing-assembly members, such as headers, sills, boxed joists, and multiple studs at openings, that are inaccessible on completion of framing work.
- G. Fasten hole-reinforcing plate over web penetrations that exceed size of manufacturer's approved or standard punched openings.

3.3 INSTALLATION OF EXTERIOR NON-LOAD-BEARING WALL FRAMING

- A. Install continuous tracks sized to match studs. Align tracks accurately and securely anchor to supporting structure.
- B. Fasten both flanges of studs to bottom track unless otherwise indicated. Space studs as follows:
 - 1. Stud Spacing: 16 inches As indicated on Drawings.

- C. Set studs plumb, except as needed for diagonal bracing or required for nonplumb walls or warped surfaces and similar requirements.
- D. Isolate non-load-bearing steel framing from building structure to prevent transfer of vertical loads while providing lateral support.
 - 1. Install single deep-leg deflection tracks and anchor to building structure.
 - 2. Install double deep-leg deflection tracks and anchor outer track to building structure.
 - 3. Connect vertical deflection clips to bypassing studs and anchor to building structure.
- E. Install horizontal bridging in wall studs, spaced vertically in rows indicated on Shop Drawings but not more than 48 inches apart. Fasten at each stud intersection.
 - 1. Channel Bridging: Cold-rolled steel channel, welded or mechanically fastened to webs of punched studs.
 - 2. Strap Bridging: Combination of flat, taut, steel sheet straps of width and thickness indicated and stud-track solid blocking of width and thickness to match studs. Fasten flat straps to stud flanges and secure solid blocking to stud webs or flanges.
 - 3. Bar Bridging: Proprietary bridging bars installed according to manufacturer's written instructions.
- F. Top Bridging for Single Deflection Track: Install row of horizontal bridging within 12 inches of single deflection track. Install a combination of bridging and stud or stud-track solid blocking of width and thickness matching studs, secured to stud webs or flanges.
 - 1. Install solid blocking at centers indicated on Shop Drawings.
- G. Install miscellaneous framing and connections, including stud kickers, web stiffeners, clip angles, continuous angles, anchors, and fasteners, to provide a complete and stable wall-framing system.

3.4 INSTALLATION TOLERANCES

- A. Install cold-formed steel framing level, plumb, and true to line to a maximum allowable tolerance variation of 1/8 inch in 10 feet and as follows:
 - 1. Space individual framing members no more than plus or minus 1/8 inch from plan location. Cumulative error are not to exceed minimum fastening requirements of sheathing or other finishing materials.

3.5 REPAIRS

- A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on fabricated and installed cold-formed steel framing with galvanized repair paint according to ASTM A780/A780M and manufacturer's written instructions.

END OF SECTION

SECTION 054400 - COLD-FORMED METAL TRUSSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes cold-formed steel framing in the form of the following:

- 1. Cold-formed steel trusses for roofs.

- B. Related Requirements:

- 1. Section 052100 "Steel Joist Framing" for truss-like, steel floor or roof joists and joist girders.
 - 2. Section 054000 "Cold-Formed Metal Framing" for cold-formed steel studs, joists, and rafters.

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.

- B. Sustainable Design Submittals:

- 1. Product Data: For recycled content, indicating post-consumer and pre-consumer recycled content and cost.

- C. Shop Drawings:

- 1. Include layout, spacings, sizes, thicknesses, and types of cold-formed steel trusses; fabrication; and fastening and anchorage details, including mechanical fasteners.
 - 2. Indicate reinforcing channels, opening framing, supplemental framing, strapping, bracing, bridging, splices, accessories, connection details, and attachment to adjoining work.

- D. Delegated-Design Submittal: For cold-formed steel trusses.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Welding certificates.
- C. Product Test Reports: For each listed product, for tests performed by a qualified testing agency.
 - 1. Steel sheet.
 - 2. Expansion anchors.
 - 3. Power-actuated anchors.
 - 4. Mechanical fasteners.
 - 5. Miscellaneous structural clips and accessories.
- D. Evaluation Reports: For post-installed anchors and power-actuated fasteners, from ICC-ES or other qualified testing agency acceptable to authorities having jurisdiction.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM E329 for testing indicated.
- B. Product Tests: Mill certificates or data from a qualified independent testing agency, or in-house testing with calibrated test equipment, indicating steel sheet complies with requirements, including base-metal thickness, yield strength, tensile strength, total elongation, chemical requirements, and metallic-coating thickness.
- C. Welding Qualifications: Qualify procedures and personnel according to the following:
 - 1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."
 - 2. AWS D1.3/D1.3M, "Structural Welding Code - Sheet Steel."

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Aegis Metal Framing.
 - 2. MarinoWARE.
 - 3. TrusSteel; an ITW company.
 - 4. USA Frametek.

2.2 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design cold-formed steel trusses.

- B. Structural Performance: Provide cold-formed steel trusses capable of withstanding design loads within limits and under conditions indicated.
 - 1. Design Loads: As indicated on Drawings.
 - 2. Deflection Limits: Design trusses to withstand design loads without deflections greater than the following:
 - a. Roof Trusses: Vertical deflection of 1/240 of the span.
 - b. Scissor Roof Trusses: Horizontal deflection of 1-1/4 inches at reactions.
 - 3. Design trusses to provide for movement of truss members located outside the insulated building envelope without damage or overstressing, sheathing failure, connection failure, undue strain on fasteners and anchors, or other detrimental effects when subject to a maximum ambient temperature change of 120 deg F.
- C. Cold-Formed Steel Truss Standards: Unless more stringent requirements are indicated, trusses shall comply with the following:
 - 1. Floor and Roof Systems: AISI S210.
 - 2. Lateral Design: AISI S213.
 - 3. Roof Trusses: AISI S214.
- D. Fire-Resistance Ratings: Comply with ASTM E119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Indicate design designations from UL or from the listings of another qualified testing agency acceptable to authorities having jurisdiction.

2.3 COLD-FORMED STEEL TRUSS MATERIALS

- A. Recycled Content of Steel Products: Post-consumer recycled content plus one-half of pre-consumer recycled content not less than 25 percent.
- B. Steel Sheet: ASTM A1003/A1003M, Structural Grade, Type H, metallic coated, of grade and coating designation as follows:
 - 1. Grade: As required by structural performance.
 - 2. Coating: G60 (Z180), A60 (ZF180), AZ50 (AZ150), or GF30 (ZGF90).

2.4 ROOF TRUSSES

- A. Roof Truss Members: Manufacturer's standard C-shaped steel sections.
 - 1. Connecting Flange Width: 1-5/8 inches, minimum at top and bottom chords connecting to sheathing or other directly fastened construction.
 - 2. Minimum Base-Metal Thickness: 0.0329 inch.

2.5 TRUSS ACCESSORIES

- A. Fabricate steel-truss accessories from steel sheet, ASTM A1003/A1003M, Structural Grade, Type H, metallic coated steel sheet, of same grade and coating designation used for truss members.
- B. Provide accessories of manufacturer's standard thickness and configuration unless otherwise indicated.

2.6 ANCHORS, CLIPS, AND FASTENERS

- A. Steel Shapes and Clips: ASTM A36/A36M, zinc coated by hot-dip process according to ASTM A123/A123M.
- B. Anchor Bolts: ASTM F1554, Grade 36, threaded carbon-steel hex-headed bolts, carbon-steel nuts, and flat, hardened-steel washers; zinc coated by hot-dip process according to ASTM A153/A153M, Class C.
- C. Post-Installed Anchors: Fastener systems with bolts of same basic metal as fastened metal, if visible, unless otherwise indicated; with working capacity greater than or equal to the design load, according to an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC58 or ICC-ES AC308 as appropriate for the substrate.
 - 1. Uses: Securing cold-formed steel trusses to structure.
 - 2. Type: Adhesive anchor.
 - 3. Material for Interior Locations: Carbon-steel components zinc plated to comply with ASTM B633 or ASTM F1941, Class Fe/Zn 5, unless otherwise indicated.
- D. Power-Actuated Fasteners: Fastener systems with working capacity greater than or equal to the design load, according to an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.
- E. Mechanical Fasteners: ASTM C1513, corrosion-resistant-coated, self-drilling, self-tapping steel drill screws.
 - 1. Head Type: Low-profile head beneath sheathing; manufacturer's standard elsewhere.
- F. Welding Electrodes: Comply with AWS standards.

2.7 MISCELLANEOUS MATERIALS

- A. Galvanizing Repair Paint: ASTM A780/A780M.
- B. Shims: Load-bearing, high-density multi-monomer, non-leaching plastic; or cold-formed steel of same grade and metallic coating as truss members supported by shims.

2.8 FABRICATION

- A. Fabricate cold-formed steel trusses and accessories plumb, square, and true to line, and with connections securely fastened, according to referenced AISI's specifications and standards, manufacturer's written instructions, and requirements in this Section.
 - 1. Fabricate trusses using jigs or templates.
 - 2. Cut truss members by sawing or shearing; do not torch cut.
 - 3. Fasten cold-formed steel truss members by welding, screw fastening, clinch fastening, pneumatic pin fastening, or riveting as standard with fabricator.
 - a. Comply with AWS D1.3/D1.3M requirements and procedures for welding, appearance and quality of welds, and methods used in correcting welding work.
 - 4. Fasten other materials to cold-formed steel trusses by welding, bolting, pneumatic pin fastening, or screw fastening, according to Shop Drawings.
- B. Reinforce, stiffen, and brace trusses to withstand handling, delivery, and erection stresses. Lift fabricated trusses by means that prevent damage or permanent distortion.
- C. Tolerances: Fabricate assemblies level, plumb, and true to line to a maximum allowable variation of 1/8 inch in 10 feet (1:960) and as follows:
 - 1. Spacing: Space individual truss members no more than plus or minus 1/8 inch from plan location. Cumulative error shall not exceed minimum fastening requirements of sheathing or other finishing materials.
 - 2. Squareness: Fabricate each cold-formed steel truss to a maximum out-of-square tolerance of 1/8 inch.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, conditions, and abutting trusses and framing for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Before sprayed fire-resistive materials are applied, attach continuous angles, supplementary framing, or tracks to structural members indicated to receive sprayed fire-resistive materials.
- B. After applying sprayed fire-resistive materials, remove only as much of these materials as needed to complete installation of cold-formed steel trusses without reducing thickness of fire-resistive materials below that required to obtain fire-resistance ratings indicated. Protect remaining fire-resistive materials from damage.

3.3 INSTALLATION

- A. Install bridge, and brace cold-formed steel trusses according to AISI S200, AISI S202, AISI S214, and manufacturer's written instructions unless more stringent requirements are indicated.
 - 1. Coordinate with wall framing to align webs of bottom chords and load-bearing studs or continuously reinforce track to transfer loads to structure.
 - 2. Anchor trusses securely at all bearing points.
 - 3. Install continuous bridging and permanently brace trusses as indicated on Shop Drawings and designed according to CFSEI's Technical Note 551e, "Design Guide: Permanent Bracing of Cold-Formed Steel Trusses."
- B. Install cold-formed steel trusses and accessories true to line and location, and with connections securely fastened.
 - 1. Erect trusses with plane of truss webs plumb and parallel to each other. Align and accurately position trusses at required spacings.
 - 2. Erect trusses without damaging truss members or connections.
 - 3. Fasten cold-formed steel trusses by welding or mechanical fasteners.
 - a. Comply with AWS D1.3/D1.3M requirements and procedures for welding, appearance and quality of welds, and methods used in correcting welding work.
 - b. Locate mechanical fasteners, install according to Shop Drawings, and comply with requirements for spacing, edge distances, and screw penetration.
- C. Install temporary bracing and supports to secure trusses and support loads equal to those for which structure was designed. Maintain braces and supports in place, undisturbed, until entire integrated supporting structure has been completed and permanent connections to trusses are secured.
- D. Truss Spacing: As indicated on Drawings.
- E. Do not alter, cut, or remove truss members or connections of trusses.

3.4 ERECTION TOLERANCES

- A. Install cold-formed steel trusses level, plumb, and true to line to a maximum allowable tolerance variation of 1/8 inch in 10 feet (1:960) and as follows:
 - 1. Space individual trusses no more than plus or minus 1/8 inch from plan location. Cumulative error shall not exceed minimum fastening requirements of sheathing or other finishing materials.

3.5 FIELD QUALITY CONTROL

- A. Special Inspections: Owner will engage a qualified special inspector to perform the following special inspections:

1. Cold-Formed Steel Trusses Spanning 60 ft. (18,288 mm) or Longer: Verify temporary installation restraint/bracing and the permanent individual truss member restraint/bracing are installed according to the approved truss submittal package.
- B. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- C. Cold-formed metal trusses will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

3.6 REPAIRS AND PROTECTION

- A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on fabricated and installed cold-formed steel trusses with galvanized repair paint according to ASTM A780/A780M and manufacturer's written instructions.
- B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that cold-formed steel trusses are without damage or deterioration at time of Substantial Completion.

END OF SECTION 054400

SECTION 055000 - METAL FABRICATIONS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Miscellaneous framing and supports.
 - 2. Miscellaneous steel trim.

1.2 ACTION SUBMITTALS

- A. Product Data: For the following:
 - 1. Shop primers.
- B. Shop Drawings: Show fabrication and installation details. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items.

PART 2 - PRODUCTS

2.1 METALS

- A. Metal Surfaces, General: Provide materials with smooth, flat surfaces unless otherwise indicated. For metal fabrications exposed to view in the completed Work, provide materials without seam marks, roller marks, rolled trade names, or blemishes.
- B. Steel Plates, Shapes, and Bars: ASTM A36/A36M.
- C. Steel Tubing: ASTM A500/A500M, cold-formed steel tubing.

2.2 MISCELLANEOUS MATERIALS

2.3 FABRICATION, GENERAL

- A. Shop Assembly: Preassemble items in the shop to greatest extent possible. Disassemble units only as necessary for shipping and handling limitations. Use connections that maintain structural value of joined pieces. Clearly mark units for reassembly and coordinated installation.

- B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.
- C. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work.
- D. Form exposed work with accurate angles and surfaces and straight edges.
- E. Weld corners and seams continuously to comply with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.
- F. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners or welds where possible. Where exposed fasteners are required, use Phillips flat-head (countersunk) fasteners unless otherwise indicated. Locate joints where least conspicuous.
- G. Fabricate seams and other connections that are exposed to weather in a manner to exclude water. Provide weep holes where water may accumulate.
- H. Where units are indicated to be cast into concrete or built into masonry, equip with integrally welded steel strap anchors, not less than 8 inches from ends and corners of units and 24 inches o.c.

2.4 MISCELLANEOUS FRAMING AND SUPPORTS

- A. General: Provide steel framing and supports not specified in other Sections as needed to complete the Work.
- B. Fabricate units from steel shapes, plates, and bars of welded construction unless otherwise indicated. Fabricate to sizes, shapes, and profiles indicated and as necessary to receive adjacent construction.

2.5 MISCELLANEOUS STEEL TRIM

- A. Unless otherwise indicated, fabricate units from steel shapes, plates, and bars of profiles shown with continuously welded joints and smooth exposed edges. Miter corners and use concealed field splices where possible.
- B. Provide cutouts, fittings, and anchorages as needed to coordinate assembly and installation with other work.

1. Provide with integrally welded steel strap anchors for embedding in concrete or masonry construction.
 - C. Galvanize exterior miscellaneous steel trim.
 - D. Prime exterior miscellaneous steel trim with primer specified in Section 099600 "High-Performance Coatings."
- 2.6 GENERAL FINISH REQUIREMENTS
- A. Finish metal fabrications after assembly.
- 2.7 STEEL AND IRON FINISHES
- A. Galvanizing: Hot-dip galvanize items as indicated to comply with ASTM A153/A153M for steel and iron hardware and with ASTM A123/A123M for other steel and iron products.
 1. Do not quench or apply post galvanizing treatments that might interfere with paint adhesion.
 - B. Shop prime iron and steel items not indicated to be galvanized unless they are to be embedded in concrete, sprayed-on fireproofing, or masonry, or unless otherwise indicated.
 1. Shop prime with universal shop primer unless [zinc-rich primer is] [primers specified in Section 099600 "High-Performance Coatings" are] indicated.
 - C. Preparation for Shop Priming: Prepare surfaces to comply with SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning." requirements indicated below:
 1. Items Indicated to Receive Primers Specified in Section 099600 "High-Performance Coatings": SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."
 2. Galvanized-Steel Items: SSPC-SP 16, "Brush-off Blast Cleaning of Coated and Uncoated Galvanized Steel, Stainless Steels, and Non-Ferrous Metals."

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal fabrications. Set metal fabrications accurately in location, alignment, and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.

- B. Fit exposed connections accurately together to form hairline joints. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations. Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.
- C. Field Welding: Comply with the following requirements:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.
- D. Fastening to In-Place Construction: Provide anchorage devices and fasteners where metal fabrications are required to be fastened to in-place construction. Provide threaded fasteners for use with concrete and masonry inserts, toggle bolts, through bolts, lag screws, wood screws, and other connectors.
- E. Provide temporary bracing or anchors in formwork for items that are to be built into concrete, masonry, or similar construction.

3.2 INSTALLATION OF MISCELLANEOUS FRAMING AND SUPPORTS

- A. Install framing and supports to comply with requirements of items being supported, including manufacturers' written instructions and requirements indicated on Shop Drawings.
- B. Anchor supports for ceiling-hung toilet partitions securely to, and rigidly brace from, building structure.

3.3 INSTALLATION OF MISCELLANEOUS STEEL TRIM

- A. Anchor to concrete construction to comply with manufacturer's written instructions.

3.4 REPAIRS

- A. Touchup Painting:
 - 1. Immediately after erection, clean field welds, bolted connections, and abraded areas. Paint uncoated and abraded areas with same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.
- B. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing to comply with ASTM A780/A780M.

END OF SECTION

SECTION 061600 - SHEATHING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Wall sheathing.
 - 2. Roof sheathing.
 - 3. Sheathing joint-and-penetration treatment.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product.
- B. Sustainable Design Submittals:
 - 1. Chain-of-Custody Certificates: For certified wood products. Include statement of costs.
 - 2. Product Data: For composite wood products, indicating that product contains no urea formaldehyde.

1.3 INFORMATIONAL SUBMITTALS

- A. Evaluation Reports: For the following, from ICC-ES:
 - 1. Fire-retardant-treated plywood.

PART 2 - PRODUCTS

2.1 FIRE-RETARDANT-TREATED PLYWOOD

- A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this article that are acceptable to authorities having jurisdiction and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.
- B. Fire-Retardant-Treated Plywood by Pressure Process: Products with a flame-spread index of 25 or less when tested in accordance with ASTM E84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.

1. Exterior Type: Treated materials are to comply with requirements specified above for fire-retardant-treated plywood by pressure process after being subjected to accelerated weathering in accordance with ASTM D2898. Use for exterior locations and where indicated.
 - C. Kiln-dry material after treatment to a maximum moisture content of 15 percent.
 - D. Identify fire-retardant-treated plywood with appropriate classification marking of qualified testing agency.
- 2.2 Application: Treat all plywood unless otherwise indicated. WALL SHEATHING
- A. Paper-Surfaced Gypsum Sheathing: ASTM C1396/C1396M, gypsum sheathing; with water-resistant-treated core and with water-repellent paper bonded to core's face, back, and long edges.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Gypsum.
 - b. Certainteed; SAINT-GOBAIN.
 - c. Georgia-Pacific Gypsum LLC.
 - d. USG Corporation.
 2. Type and Thickness: Type X, 5/8 inch thick.
- 2.3 ROOF SHEATHING
- A. Plywood Sheathing, Roofs: DOC PS 1, sheathing.
- 2.4 SHEATHING JOINT-AND-PENETRATION TREATMENT MATERIALS
- A. Sealant for Paper-Surfaced Gypsum Sheathing: Elastomeric, medium-modulus, neutral-curing silicone joint sealant compatible with joint substrates formed by gypsum sheathing and other materials, recommended by sheathing manufacturer for application indicated and complying with requirements for elastomeric sealants specified in Section 079200 "Joint Sealants."

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Do not use materials with defects that impair quality of sheathing or pieces that are too small to use with minimum number of joints or optimum joint arrangement. Arrange joints so that pieces do not span between fewer than three support members.

- B. Cut panels at penetrations, edges, and other obstructions of work; fit tightly against abutting construction unless otherwise indicated.
- C. Securely attach to substrate by fastening as indicated, complying with the following:
 - 1. Table 2304.10.1, "Fastening Schedule," in the ICC's International Building Code.
 - 2. ICC-ES evaluation report for fastener.
- D. Coordinate wall roof sheathing installation with flashing and joint-sealant installation so these materials are installed in sequence and manner that prevent exterior moisture from passing through completed assembly.
- E. Do not bridge building expansion joints; cut and space edges of panels to match spacing of structural support elements.

3.2 WOOD STRUCTURAL PANEL INSTALLATION

- A. General: Comply with applicable recommendations in APA Form No. E30, "Engineered Wood Construction Guide," for types of structural-use panels and applications indicated.
- B. Fastening Methods: Fasten panels as indicated below:
 - 1. Wall and Roof Sheathing:
 - a. Screw to cold-formed metal framing.
 - b. Space panels 1/8 inch apart at edges and ends.

3.3 GYPSUM SHEATHING INSTALLATION

- A. Comply with GA-253 and with manufacturer's written instructions.
 - 1. Fasten gypsum sheathing to cold-formed metal framing with screws.
 - 2. Install panels with a 3/8-inch gap where non-load-bearing construction abuts structural elements.
 - 3. Install panels with a 1/4-inch gap where they abut masonry or similar materials that might retain moisture, to prevent wicking.
- B. Seal sheathing joints in accordance with sheathing manufacturer's written instructions.
 - 1. Apply elastomeric sealant to joints and fasteners and trowel flat. Apply sufficient amount of sealant to completely cover joints and fasteners after troweling. Seal other penetrations and openings.

END OF SECTION

SECTION 062013 - EXTERIOR FINISH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Engineered wood siding.
2. Engineered wood soffits.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product.
- B. Samples: For each exposed product and for each color and texture specified.

1.3 WARRANTY

- A. Manufacturer's Warranty for Engineered Wood Siding Soffits and Trim: Manufacturer agrees to repair or replace components that fail in materials or workmanship within specified warranty period.
 1. Warranty Period for Siding, Soffits, and Trim : 50 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 ENGINEERED WOOD SIDING

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. reSAWN TIMBER Company.
 2. Nakamoto Forestry
 3. Thermory USA
- B. Engineered Wood Siding:
 1. Type:
 - a. 3/4-inch- thick by 6-inch- wide tongue and groove siding.
- C. Colors, Textures, and Patterns: As indicated by manufacturer's designations.

- D. Colors, Textures, and Patterns: As indicated by manufacturer's designations.

2.2 ENGINEERED WOOD SOFFITS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. reSAWN TIMBER Company.
2. Nakamoto Forestry
3. Thermory USA

- B. Engineered Wood Soffits:

1. Type: 3/4-inch- thick tongue and groove.
2. Colors, Textures, and Patterns: As indicated by manufacturer's designations.

2.3 MISCELLANEOUS MATERIALS

- A. Fasteners for Exterior Finish Carpentry: Provide nails or screws, in sufficient length to penetrate not less than 1-1/2 inches into metal framing substrate.

1. For face-fastening siding, provide fasteners recommended in writing by manufacturer.

- B. Sealants: Latex, complying with ASTM C834 Type OP, Grade NF and applicable requirements in Section 079200 "Joint Sealants," and recommended by sealant and substrate manufacturers for intended application.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Bostik, Inc.
 - b. Franklin International.
 - c. Pecora Corporation.
 - d. Permathane®/Acryl-R®; ITW Polymers Sealants North America.
 - e. Tremco, Inc.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean substrates of projections and substances detrimental to application.

3.2 INSTALLATION, GENERAL

- A. Install exterior finish carpentry level, plumb, true, and aligned with adjacent materials.
 - 1. Use concealed shims where necessary for alignment.
 - 2. Scribe and cut exterior finish carpentry to fit adjoining work.
 - 3. Refinish and seal cuts as recommended by manufacturer.
 - 4. Install to tolerance of 1/8 inch in 96 inches for level and plumb. Install adjoining exterior finish carpentry with 1/32-inch maximum offset for flush installation and 1/16-inch maximum offset for reveal installation.
 - 5. Coordinate exterior finish carpentry with materials and systems in or adjacent to it.
 - 6. Provide cutouts for mechanical and electrical items that penetrate exterior finish carpentry.

3.3 INSTALLATION OF SIDING

- A. Install siding to comply with manufacturer's written instructions and warranty requirements.
- B. Engineered Wood Siding:
 - 1. Install engineered wood siding to comply with manufacturer's written instructions.
 - 2. Install panels with edges over framing.
 - 3. Leave 3/16-inch gap at perimeter, openings, and horizontal panel joints unless otherwise recommended by panel manufacturer.
 - 4. Seal butt joints at inside and outside corners and at trim locations.
 - 5. Install continuous metal flashing at horizontal panel joints.
 - 6. Apply battens and corner trim as indicated.
 - 7. Conceal fasteners to greatest practical extent by placing in grooves of siding pattern or by concealing with applied trim or battens as detailed.
- C. Finish: Apply finish within two weeks of installation.

END OF SECTION

SECTION 064116 - PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Plastic-laminate-clad architectural cabinets.
2. Cabinet hardware and accessories.
3. Wood furring, blocking, shims, and hanging strips for installing plastic-laminate-clad architectural cabinets that are not concealed within other construction.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Sustainable Design Submittals:

1. Chain-of-Custody Certificates: For certified wood products. Include statement of costs.
2. Product Data: For adhesives, indicating that product contains no urea formaldehyde.

C. Shop Drawings.

D. Samples: For each exposed product and for each color and texture specified.

1.3 QUALITY ASSURANCE

A. Manufacturer's Qualifications: Employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

1. Manufacturer's Certification: Licensed participant in AWI's Quality Certification Program.

B. Installer Qualifications: Licensed participant in AWI's Quality Certification Program.

1.4 FIELD CONDITIONS

A. Environmental Limitations without Humidity Control: Do not deliver or install cabinets until building is enclosed, wet-work is complete, and HVAC system is operating and maintaining temperature and relative humidity at levels planned for building occupants during the remainder of the construction period.

- B. Environmental Limitations with Humidity Control: Do not deliver or install cabinets until building is enclosed, wet-work is complete, and HVAC system is operating and maintaining temperature between 60 and 90 deg F and relative humidity between 25 and 55 percent during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS

- A. Quality Standard: Unless otherwise indicated, comply with the Architectural Woodwork Standards for grades of cabinets indicated for construction, finishes, installation, and other requirements.
- B. Architectural Woodwork Standards Grade: Premium.
- C. Type of Construction: Frameless.
- D. Door and Drawer-Front Style: Flush overlay.
1. Reveal Dimension: As indicated.
- E. High-Pressure Decorative Laminate: ISO 4586-3, grades as indicated or if not indicated, as required by quality standard.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
- a. ABET Inc.
- b. Formica Corporation.
- c. Laminart LLC.
- d. Pionite; a Panolam Industries International, Inc. brand.
- e. Wilsonart LLC.
- F. Exposed Surfaces:
1. Plastic-Laminate Grade: HGS.
2. Edges: Grade HGS.
3. Pattern Direction: As indicated.
- G. Concealed Backs of Panels with Exposed Plastic-Laminate Surfaces: High-pressure decorative laminate, ISO 4583-3, grade to match exposed surface.
- H. Drawer Construction: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.
1. Join subfronts, backs, and sides with glued rabbeted joints supplemented by mechanical fasteners.

- I. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As indicated by laminate manufacturer's designations.

2.2 WOOD MATERIALS

- A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

1. Wood Moisture Content: 5 to 10 percent.

- B. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

1. Particleboard (Medium Density): ANSI A208.1, Grade M-2.

2.3 CABINET HARDWARE AND ACCESSORIES

- A. Frameless Concealed Hinges (European Type): ANSI/BHMA A156.9, B01602, 170 degrees of opening.

- B. Wire Pulls: Back mounted, solid metal, 4 inches long, 5/16 inch in diameter.

- C. Adjustable Shelf Standards and Supports: ANSI/BHMA A156.9, B04071; with shelf rests, B04081.

- D. Shelf Rests: ANSI/BHMA A156.9, B04013; metal.

- E. Drawer Slides: ANSI/BHMA A156.9.

1. Heavy-Duty (Grade 1HD-100 and Grade 1HD-200): Side mount.

- a. Type: Full overtravel extension.
- b. Material: Zinc-plated ball bearing slides.
- c. Motion Feature: Soft close dampener.

- F. Exposed Hardware Finishes: For exposed hardware, provide finish that complies with ANSI/BHMA A156.18 for ANSI/BHMA finish number indicated.

1. Satin Stainless Steel: ANSI/BHMA 630.

- G. For concealed hardware, provide manufacturer's standard finish that complies with product class requirements in ANSI/BHMA A156.9.

2.4 MISCELLANEOUS MATERIALS

- A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln-dried to less than 15 percent moisture content.
- B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls and at floors.
- C. Adhesives: Do not use adhesives that contain urea formaldehyde.
- D. Adhesive for Bonding Plastic Laminate: Type I, waterproof type as selected by fabricator to comply with requirements.
 - 1. Adhesive for Bonding Edges: Hot-melt adhesive or adhesive specified above for faces.

2.5 FABRICATION

- A. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.
- B. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Before installation, condition cabinets to humidity conditions in installation areas for not less than 72 hours.
- B. Architectural Woodwork Standards Grade: Install cabinets to comply with quality standard grade of item to be installed.
- C. Anchor cabinets to anchors or blocking built in or directly attached to substrates. Secure with wafer-head cabinet installation screws.
- D. Install cabinets level, plumb, and true in line to a tolerance of 1/8 inch in 96 inches using concealed shims.

1. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.
2. Install cabinets without distortion so doors and drawers fit openings and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.
3. Fasten wall cabinets through back, near top and bottom, and at ends not more than 16 inches o.c. with No. 10 wafer-head screws sized for not less than 1-1/2-inch penetration into wood framing, blocking, or hanging strips.

END OF SECTION

SECTION 064216.10 - MDF WOOD PANELING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Shop finishing.
2. Flush wood paneling (MDF-1, MDF-2).
3. Wood slat paneling (AWP-1).

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include data for fire-retardant treatment from chemical-treatment manufacturer and certification by treating plant that treated materials comply with requirements.

B. Shop Drawings: For flush wood paneling.

1. Include plans, elevations, sections, and attachment details.

C. Samples: For each exposed product and for each color and finish specified.

1.3 INFORMATIONAL SUBMITTALS

A. Research reports.

PART 2 - PRODUCTS

2.1 FLUSH WOOD PANELING (MDF-1, MDF-2)

A. General: Provide manufactured product indicated on Drawings or comparable product.

B. Grade: Premium.

C. Wood Species and Cut: As indicated by Manufacturer's designations.

D. Panel Core Construction: MDF.

1. Thickness: As indicated on Drawings.

- E. Fire-Retardant-Treated Paneling: Panels shall consist of wood-veneer and fire-retardant particleboard or fire-retardant, medium-density fiberboard (MDF). Panels shall have a flame-spread index of 25 or less and a smoke-developed index of 450 or less per ASTM E84, and be listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction.
- F. Assemble panels by gluing and concealed fastening.

2.2 WOOD SLAT PANELING (AWP-1)

- A. General: Provide manufactured product indicated on Drawings or comparable product.
- B. Grade: Premium.
- C. Panel Core Construction: MDF.
 - 1. Thickness: As indicated on Drawings.
- D. Assemble panels by gluing and concealed fastening.

2.3 MATERIALS

- A. Materials, General: Provide materials that comply with requirements of referenced quality standard for each quality grade specified unless otherwise indicated.
- B. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each quality grade specified unless otherwise indicated.
 - 1. MDF: ANSI A208.2, Grade 130.

2.4 INSTALLATION MATERIALS

- A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln-dried to less than 15 percent moisture content.
- B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls.
- C. Installation Adhesive: Product recommended by panel fabricator for each substrate for secure anchorage.

2.5 FABRICATION

- A. Complete fabrication, including assembly, to maximum extent possible, before shipment to Project site.

- B. Shop cut openings, to maximum extent possible, to receive hardware, appliances, plumbing fixtures, electrical work, and similar items.

2.6 SHOP FINISHING

- A. General: Finish paneling at fabrication shop as specified in this Section. Defer only final touchup, cleaning, and polishing until after installation.
- B. Shop Priming: Shop apply the prime coat including backpriming, if any, for transparent-finished paneling specified to be field finished.
- C. Transparent Finish:
 - 1. Grade: Premium.
 - 2. Staining: As indicated on Drawings.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Before installation, condition paneling to humidity conditions in installation areas.
- B. Grade: Install paneling to comply with quality standard grade of paneling to be installed.
- C. Install paneling level, plumb, true in line, and without distortion. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches. Install with no more than 1/16 inch in 96-inch vertical cup or bow and 1/8 inch in 96-inch horizontal variation from a true plane.
 - 1. For flush paneling with revealed joints, install with variations in reveal width, alignment of top and bottom edges, and flushness between adjacent panels not exceeding 1/32 inch.
- D. Anchor paneling to supporting substrate with blind nailing.
 - 1. Do not use face fastening unless covered by trim.
- E. Complete finishing work specified in this Section to extent not completed at shop or before installation of paneling. Fill nail holes with matching filler where exposed.

END OF SECTION

SECTION 064216.11 – PAPER COMPOSITE PANELING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Paper composite panels (PPM-1, PPM-2).

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include data for fire-retardant treatment from chemical-treatment manufacturer and certification by treating plant that treated materials comply with requirements.
- B. Shop Drawings: For paper composite paneling.
 - 1. Include plans, elevations, sections, and attachment details.
- C. Samples: For each exposed product and for each color and finish specified, in manufacturer's or fabricator's standard size.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Evaluation Reports: For fire-retardant-treated materials, from ICC-ES.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Do not deliver paneling until painting and similar operations that might damage paneling have been completed in installation areas. Store paneling in installation areas or in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.6 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install paneling until building is enclosed, wet-work is complete, and HVAC system is operating and will maintain temperature and relative humidity at levels planned for building occupants during the remainder of the construction period.
- B. Field Measurements: Where paneling is indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- C. Established Dimensions: Where paneling is indicated to fit to other construction, establish dimensions for areas where work is to fit. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

PART 2 - PRODUCTS

2.1 PANELING, GENERAL

- A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of flush wood paneling (wood-veneer wall surfacing) indicated for construction, finishes, installation, and other requirements.
 - 1. Provide inspections of fabrication and installation together with labels and certificates from AWI certification program indicating that woodwork complies with requirements of grades specified.
 - 2. The Contract Documents contain requirements that are more stringent than the referenced woodwork quality standard. Comply with requirements of Contract Documents in addition to those of the referenced quality standard.

2.2 MATERIALS

- A. Paper Composite Sheets (PPM-1, PPM-2): Cellulose fiber paper heat pressed with phenolic resin; color consistent throughout thickness.
- B. Manufacturers: Provide products indicated on the Drawings or comparable by Tekstur, Richlite, Paneltech.
- C.
 - 1. Surface Burning Characteristics: Flame spread 30, maximum; smoke developed 30, maximum; when tested in accordance with ASTM E 84.
 - 2. Density: 75.84 pounds per cu ft.
 - 3. Water Absorption: 0.36 percent for 1 inch thickness, unsealed material, 24 hour fully submerged test.

4. Thickness: 5/16" for wall panels. As indicated for countertops.
5. Gloss: Matte
6. Color: As indicated on Drawings.
7. Pattern: As indicated on Drawings.

D. Metal Trim Units: Basis-of-Design Product: Subject to compliance with requirements, provide Schluter Systems L.P; DESIGNBASE-SL at floor and paneling intersections or comparable products by one of the following:

1. Blanke Corporation.
2. Ceramic Tool Company, Inc.

2.3 INSTALLATION MATERIALS

- A. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls.
- B. Installation Adhesive: Product recommended by panel fabricator for each substrate for secure anchorage.

2.4 FABRICATION

- A. Complete fabrication, including assembly, to maximum extent possible, before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.
- B. Shop cut openings, to maximum extent possible, to receive hardware, appliances, plumbing fixtures, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Before installation, condition paneling to humidity conditions in installation areas.
- B. Before installing paneling, examine shop-fabricated work for completion and complete work as required, including removal of packing.

3.2 INSTALLATION

- A. Install paneling level, plumb, true in line, and without distortion. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches. Install with no more than 1/16 inch in 96-inch vertical cup or bow and 1/8 inch in 96-inch horizontal variation from a true plane.
- B. Anchor paneling to supporting substrate with concealed panel-hanger clips.
 - 1. Do not use face fastening unless otherwise indicated.

3.3 ADJUSTING AND CLEANING

- A. Repair damaged and defective paneling, where possible, to eliminate defects. Where not possible to repair, replace paneling. Adjust for uniform appearance.
- B. Clean paneling on exposed surfaces. Touch up shop-applied finishes to restore damaged or soiled areas.

END OF SECTION

SECTION 066400 - PLASTIC PANELING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes plastic sheet paneling.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For plastic paneling and trim accessories, in manufacturer's standard sizes.

PART 2 - PRODUCTS

2.1 PLASTIC SHEET PANELING

- A. Glass-Fiber-Reinforced Plastic Paneling: Gelcoat-finished, glass-fiber-reinforced plastic panels complying with ASTM D5319. Panels are to be USDA accepted for incidental food contact.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Crane Composites, Inc.
 - b. Marlite.
 - c. Nudo Products, Inc.
 - d.
 - 2. Surface-Burning Characteristics: As follows when tested by a qualified testing agency in accordance with ASTM E84. Identify products with appropriate markings of applicable testing agency.
 - a. Flame-Spread Index: 25 or less.
 - b. Smoke-Developed Index: 450 or less.
 - 3. Nominal Thickness: Not less than 0.09 inch.
 - 4. Surface Finish: As indicated by manufacturer's designations.
 - 5. Color: As indicated by manufacturer's designations.

2.2 ACCESSORIES

- A. Trim Accessories: Manufacturer's standard one-piece vinyl extrusions designed to retain and cover edges of panels. Provide division bars, inside corners, and caps as needed to conceal edges.

1. Color: Match panels.
- B. Sealant: Mildew-resistant, single-component, neutral-curing silicone sealant recommended by plastic paneling manufacturer.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean substrates of substances that could impair adhesive bond, including oil, grease, dirt, and dust.
- B. Condition panels by unpacking and placing in installation space before installation according to manufacturer's written recommendations.
- C. Lay out paneling before installing. Locate panel joints to provide equal panels at ends of walls not less than half the width of full panels so that trimmed panels at corners are not less than 12 inches wide.

3.2 INSTALLATION

- A. Install plastic paneling according to manufacturer's written instructions.
- B. Install panels in a full spread of adhesive.
- C. Install trim accessories with adhesive.
- D. Fill grooves in trim accessories with sealant before installing panels, and bed inside corner trim in a bead of sealant.
- E. Maintain uniform space between panels and wall fixtures. Fill space with sealant.
- F. Remove excess sealant and smears as paneling is installed. Clean with solvent recommended by sealant manufacturer and then wipe with clean dry cloths until no residue remains.

END OF SECTION

SECTION 072100 - THERMAL INSULATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Extruded polystyrene foam-plastic board insulation.
2. Glass-fiber blanket insulation.

1.2 ACTION SUBMITTALS

A. Product Data: For the following:

1. Extruded polystyrene foam-plastic board insulation.
2. Glass-fiber blanket insulation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Maximum flame-spread and smoke-developed indexes less than 25 and 450 when tested in accordance with ASTM E84.
- B. Fire Propagation Characteristics: Passes NFPA 285 testing as part of an approved assembly.
- C. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches and wider in width.
- D. Thermal-Resistance Value (R-Value): R-value as indicated on Drawings in accordance with ASTM C518.

2.2 EXTRUDED POLYSTYRENE FOAM-PLASTIC BOARD INSULATION

- A. Extruded Polystyrene Board Insulation, Type VI : ASTM C578, Type VI, 40-psi minimum compressive strength.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. DiversiFoam Products.
 - b. DuPont de Nemours, Inc.

- c. Owens Corning.
- d. The Dow Chemical Company.

2.3 GLASS-FIBER BLANKET INSULATION

- A. Glass-Fiber Blanket Insulation, Unfaced : ASTM C665, Type I; passing ASTM E136 for combustion characteristics.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Certainteed; SAINT-GOBAIN.
 - b. Johns Manville; a Berkshire Hathaway company.
 - c. Knauf Insulation.
 - d. Owens Corning.

2.4 ACCESSORIES

- A. Insulation for Miscellaneous Voids:
 - 1. Glass-Fiber Insulation: ASTM C764, Type II, loose fill; with maximum flame-spread and smoke-developed indexes of 5, per ASTM E84.
 - 2. Spray Polyurethane Foam Insulation: ASTM C1029, Type II, closed cell, with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, per ASTM E84.
- B. Insulation Anchors, Spindles, and Standoffs: As recommended by manufacturer.
- C. Adhesive for Bonding Insulation: Product compatible with insulation and air and water barrier materials, and with demonstrated capability to bond insulation securely to substrates without damaging insulation and substrates.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Comply with insulation manufacturer's written instructions applicable to products and applications.
- B. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.
- C. Install insulation with manufacturer's R-value label exposed after insulation is installed.
- D. Extend insulation to envelop entire area to be insulated. Fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.

- E. Provide sizes to fit applications and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units unless multiple layers are otherwise shown or required to make up total thickness or to achieve R-value.

3.2 INSTALLATION OF CAVITY-WALL INSULATION

- A. Foam-Plastic Board Insulation: Install pads of adhesive spaced approximately 24 inches o.c. both ways on inside face and as recommended by manufacturer.
 - 1. Fit courses of insulation between obstructions, with edges butted tightly in both directions, and with faces flush.
 - 2. Press units firmly against inside substrates.

3.3 INSTALLATION OF INSULATION IN FRAMED CONSTRUCTION

- A. Blanket Insulation: Install in cavities formed by framing members according to the following requirements:
 - 1. Use insulation widths and lengths that fill the cavities formed by framing members. If more than one length is required to fill the cavities, provide lengths that will produce a snug fit between ends.
 - 2. Place insulation in cavities formed by framing members to produce a friction fit between edges of insulation and adjoining framing members.
 - 3. Maintain 3-inch clearance of insulation around recessed lighting fixtures not rated for or protected from contact with insulation.
 - 4. For metal-framed wall cavities where cavity heights exceed 96 inches, support unfaced blankets mechanically and support faced blankets by taping flanges of insulation to flanges of metal studs.
 - 5. Vapor-Retarder-Faced Blankets: Tape joints and ruptures in vapor-retarder facings, and seal each continuous area of insulation to ensure airtight installation.
 - a. Exterior Walls: Set units with facing placed toward as indicated on Drawings.
- B. Miscellaneous Voids: Install insulation in miscellaneous voids and cavity spaces where required to prevent gaps in insulation using the following materials:
 - 1. Spray Polyurethane Insulation: Apply according to manufacturer's written instructions.

END OF SECTION

SECTION 072726 - FLUID-APPLIED MEMBRANE AIR BARRIERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Vapor-permeable, fluid-applied air barriers.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Certificates.
- B. Product Test Reports.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Air-Barrier Performance: Air-barrier assembly and seals with adjacent construction to be capable of performing as a continuous air barrier and as a liquid-water drainage plane flashed to discharge to the exterior incidental condensation or water penetration. Air-barrier assemblies to be capable of accommodating substrate movement and of sealing substrate expansion and control joints, construction material changes, penetrations, and transitions at perimeter conditions without deterioration and air leakage exceeding specified limits.
- B. Air-Barrier Assembly Air Leakage: Maximum 0.04 cfm/sq. ft. of surface area at 1.57 lbf/sq. ft., when tested in accordance with ASTM E2357.
- C. Air Permeance: Maximum 0.004 cfm/sq. ft. of surface area at 1.57 lbf/sq. ft. pressure difference; ASTM E2178.
- D. Ultimate Elongation: Minimum 500 percent; ASTM D412, Die C.

- E. Adhesion to Substrate: Minimum 20lb/sq. in. when tested in accordance with ASTM D4541.
- F. UV Resistance: Can be exposed to sunlight for 360 days in accordance with manufacturer's written instructions.

2.2 HIGH-BUILD AIR BARRIERS, VAPOR PERMEABLE

- A. High-Build, Vapor-Permeable Air Barrier, Synthetic Polymer Type: Synthetic polymer membrane with an installed dry film thickness, according to manufacturer's written instructions, of 35 mils or thicker over smooth, void-free substrates.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. DuPont de Nemours, Inc.
 - b. GCP Applied Technologies Inc.
 - c. Henry Company.
 - d. Tremco Incorporated.
- B. Vapor Permeance: Minimum 12 perms; ASTM E96/E96M, Procedure B, Water Method.

2.3 ACCESSORY MATERIALS

- A. Requirement: Provide primers, transition strips, termination strips, joint reinforcing fabric and strips, joint sealants, counterflashing strips, flashing sheets and metal termination bars, termination mastic, substrate patching materials, adhesives, tapes, foam sealants, lap sealants, and other accessory materials that are recommended in writing by air-barrier manufacturer to produce a complete air-barrier assembly and that are compatible with primary air-barrier material and adjacent construction to which they may seal.

PART 3 - EXECUTION

3.1 SURFACE PREPARATION

- A. Clean, prepare, treat, fill, and seal substrate and joints and cracks in substrate in accordance with manufacturer's written instructions and details. Provide clean, dust-free, and dry substrate for air-barrier application.
- B. Mask off adjoining surfaces not covered by air barrier to prevent spillage and overspray affecting other construction.
- C. Remove fins, ridges, mortar, and other projections and fill honeycomb, aggregate pockets, holes, and other voids in concrete with substrate-patching material.

- D. Remove excess mortar from masonry ties, shelf angles, and other obstructions.
- E. At changes in substrate plane, apply sealant or termination mastic beads at sharp corners and edges to form a smooth transition from one plane to another.
- F. Bridge discontinuous wall-to-wall, deck-to-wall, and deck-to-deck joints with air-barrier accessory material that accommodates joint movement in accordance with manufacturer's written instructions and details.

3.2 INSTALLATION

- A. Install materials in accordance with air-barrier manufacturer's written instructions and details to form a seal with adjacent construction and ensure continuity of air and water barrier.
 - 1. Coordinate the installation of air barrier with installation of roofing membrane and base flashing to ensure continuity of air barrier with roofing membrane.
 - 2. Install transition strip on roofing membrane or base flashing so that a minimum of 3 inches of coverage is achieved over each substrate.
 - 3. Unless manufacturer recommends in writing against priming, apply primer to substrates at required rate and allow it to dry.
 - 4. Apply primer to substrates at required rate and allow it to dry. Limit priming to areas that will be covered by air-barrier material on same day. Reprime areas exposed for more than 24 hours.
- B. Connect and seal exterior wall air-barrier material continuously to roofing-membrane air barrier, concrete below-grade structures, floor-to-floor construction, exterior glazing and window systems, glazed curtain-wall systems, storefront systems, exterior louvers, exterior door framing, and other construction used in exterior wall openings, using accessory materials.
- C. Wall Openings: Prime concealed, perimeter frame surfaces of windows, curtain walls, storefronts, and doors. Apply transition strip so that a minimum of 3 inches of coverage is achieved over each substrate. Maintain 3 inches of full contact over firm bearing to perimeter frames.
- D. Repair punctures, voids, and deficient lapped seams in strips and transition strips. Slit and flatten fishmouths and blisters. Patch with transition strips extending 6 inches beyond repaired areas in strip direction.
- E. High-Build Air Barriers: Apply continuous unbroken air-barrier material to substrates according to the following thickness. Apply air-barrier material in full contact around protrusions such as masonry ties.
 - 1. Vapor-Permeable, High-Build Air Barrier: Total dry film thickness as recommended in writing by manufacturer to comply with performance requirements, but not less than 35 mils, applied in one or more equal coats.
- F. Do not cover air barrier until it has been tested and inspected by testing agency.

- G. Correct deficiencies in or remove air barrier that does not comply with requirements; repair substrates and reapply air-barrier components.

3.3 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Tests: As determined by testing agency from among the following tests:
 - 1. Air-barrier dry film thickness.
 - 2. Air-Leakage-Location Testing: Air-barrier assemblies will be tested for evidence of air leakage in accordance with ASTM E1186, chamber pressurization or depressurization with smoke tracers.
 - 3. Air-Leakage-Volume Testing: Air-barrier assemblies will be tested for air-leakage rate in accordance with ASTM E783.
 - 4. Adhesion Testing: Air-barrier assemblies will be tested for required adhesion to substrate in accordance with ASTM D4541 for each 600 sq. ft. of installed air barrier or part thereof.
- C. Air barriers will be considered defective if they do not pass tests and inspections.
 - 1. Apply additional air-barrier material, in accordance with manufacturer's written instructions, where inspection results indicate insufficient thickness.
 - 2. Remove and replace deficient air-barrier components for retesting as specified above.
- D. Repair damage to air barriers caused by testing; follow manufacturer's written instructions.
- E. Prepare test and inspection reports.

3.4 CLEANING AND PROTECTION

- A. Protect air-barrier system from damage during application and remainder of construction period, in accordance with manufacturer's written instructions.
- B. Remove masking materials after installation.

END OF SECTION

SECTION 074113.16 - STANDING-SEAM METAL ROOF PANELS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Standing-seam metal roof panels.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

B. Sustainable Design Submittals:

1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

- C. Shop Drawings: Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment system, trim, flashings, closures, and accessories; and special details.

- D. Samples: For each type of metal panel and each color indicated.

1.4 INFORMATIONAL SUBMITTALS

- A. Product test reports.

- B. Warranties: Sample of special warranties.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance data.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

- B. UL-Certified, Portable Roll-Forming Equipment: UL-certified, portable roll-forming equipment capable of producing metal panels warranted by manufacturer to be the same as factory-formed products. Maintain UL certification of portable roll-forming equipment for duration of work.

1.7 WARRANTY

- A. Special Warranty: Installer's standard form in which installer agrees to repair or replace components of metal panel systems that fail in workmanship within specified warranty period.

- 1. Warranty Period: Five years from date of Final Completion.

- B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.

- 1. Finish Warranty Period: 20 years from date of Final Completion.

- C. Special Weathertightness Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace standing-seam metal roof panel assemblies that fail to remain weathertight, including leaks, within specified warranty period.

- 1. Warranty Period: 20 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Structural Performance: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E1592:
 - 1. Wind Loads: As indicated on Drawings.
 - 2. Other Design Loads: As indicated on Drawings.
 - 3. Deflection Limits: For wind loads, no greater than 1/240 of the span.
- C. Air Infiltration: Air leakage of not more than 0.06 cfm/sq. ft. when tested according to ASTM E1680 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft..
- D. Water Penetration under Static Pressure: No water penetration when tested according to ASTM E1646 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft..

- E. Hydrostatic-Head Resistance: No water penetration when tested according to ASTM E2140.
- F. Wind-Uplift Resistance: Provide metal roof panel assemblies that comply with UL 580 for wind-uplift-resistance class indicated.
 - 1. Uplift Rating: UL 60.
- G. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

2.2 STANDING-SEAM METAL ROOF PANELS

- A. Provide factory-formed metal roof panels designed to be installed by lapping and interconnecting raised side edges of adjacent panels with joint type indicated and mechanically attaching panels to supports using concealed clips in side laps. Include clips, cleats, pressure plates, and accessories required for weathertight installation.
 - 1. Steel Panel Systems: Unless more stringent requirements are indicated, comply with ASTM E1514.
- B. Vertical-Rib, Seamed-Joint, Standing-Seam Metal Roof Panels : Formed with vertical ribs at panel edges and intermediate stiffening ribs symmetrically spaced between ribs; designed for sequential installation by mechanically attaching panels to supports using concealed clips located under one side of panels, engaging opposite edge of adjacent panels, and mechanically seaming panels together.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CENTRIA, a Nucor Brand?.
 - b. Firestone Building Products.
 - c. Metal Roofing Systems, Inc.
 - d. PAC-CLAD; Petersen Aluminum Corporation; a Carlisle company.
 - 2. Metallic-Coated Steel Sheet: Zinc-coated (galvanized) steel sheet complying with ASTM A653/A653M, G90 coating designation, or aluminum-zinc alloy-coated steel sheet complying with ASTM A792/A792M, Class AZ50 coating designation; structural quality. Prepainted by the coil-coating process to comply with ASTM A755/A755M.
 - a. Nominal Thickness: 0.052 inch.
 - b. Exterior Finish: Two-coat fluoropolymer.
 - c. Color: As indicated by manufacturer's designations.

3. Clips: One-piece fixed to accommodate thermal movement.
4. Material:
 - a. 0.028-inch- nominal thickness, zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet.
5. Joint Type: Double folded.
6. Panel Coverage: 24 inches.
7. Panel Height: 1.5 inches.

2.3 UNDERLAYMENT MATERIALS

- A. Self-Adhering, High-Temperature Underlayment: Provide self-adhering, cold-applied, sheet underlayment, a minimum of 30 mils thick, consisting of slip-resistant, polyethylene-film top surface laminated to a layer of butyl or SBS-modified asphalt adhesive, with release-paper backing. Provide primer when recommended by underlayment manufacturer.
 1. Thermal Stability: Stable after testing at 240 deg F; ASTM D1970.
 2. Low-Temperature Flexibility: Passes after testing at minus 20 deg F; ASTM D1970.
 3. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ATAS International, Inc.
 - b. Carlisle WIP Products; a brand of Carlisle Construction Materials.
 - c. GCP Applied Technologies Inc.
 - d. Henry Company.
 - e. Owens Corning.
- B. Slip Sheet: Manufacturer's recommended slip sheet, of type required for application.

2.4 MISCELLANEOUS MATERIALS

- A. Miscellaneous Metal Subframing and Furring: ASTM C645; cold-formed, metallic-coated steel sheet, ASTM A653/A653M, G90 hot-dip galvanized coating designation or ASTM A792/A792M, Class AZ50 coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.
- B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, copings, fasciae, mullions, sills, corner units, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.
 1. Closures: Provide closures at eaves and ridges, fabricated of same metal as metal panels.

2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
 3. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- thick, flexible closure strips; cut or premolded to match metal panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.
- C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, eaves, rakes, corners, bases, framed openings, ridges, fasciae, and fillers. Finish flashing and trim with same finish system as adjacent metal panels.
- D. Gutters and Downspouts: Formed from same material as roof panels according to SMACNA's "Architectural Sheet Metal Manual." Finish to match metal roof panels.
- E. Panel Fasteners: Self-tapping screws designed to withstand design loads.
- F. Panel Sealants: Provide sealant type recommended by manufacturer that are compatible with panel materials, are nonstaining, and do not damage panel finish.
1. Butyl-Rubber-Based, Solvent-Release Sealant: ASTM C1311.

2.5 FABRICATION

- A. Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.
- B. On-Site Fabrication: Subject to compliance with requirements of this Section, metal panels may be fabricated on-site using UL-certified, portable roll-forming equipment if panels are of same profile and warranted by manufacturer to be equal to factory-formed panels. Fabricate according to equipment manufacturer's written instructions and to comply with details shown.
- C. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel.
- D. Fabricate metal panel joints with factory-installed captive gaskets or separator strips that provide a weathertight seal and prevent metal-to-metal contact, and that minimize noise from movements.
- E. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.

2.6 FINISHES

A. Panels and Accessories:

1. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent polyvinylidene fluoride (PVDF) resin by weight in color coat.
2. Concealed Finish: White or light-colored acrylic or polyester backer finish.

PART 3 - EXECUTION

3.1 PREPARATION

- #### A. Miscellaneous Supports:
- Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C754 and metal panel manufacturer's written recommendations.

3.2 INSTALLATION OF UNDERLAYMENT

- #### A. Self-Adhering Sheet Underlayment:
- Apply primer if required by manufacturer. Comply with temperature restrictions of underlayment manufacturer for installation. Apply at locations indicated on Drawings, wrinkle free, in shingle fashion to shed water, and with end laps of not less than 6 inches staggered 24 inches between courses. Overlap side edges not less than 3-1/2 inches. Roll laps with roller. Cover underlayment within 14 days.
1. Apply over the entire roof surface.
- #### B. Flashings:
- Install flashings to cover underlayment to comply with requirements specified in Section 076200 "Sheet Metal Flashing and Trim."

3.3 INSTALLATION OF STANDING-SEAM METAL ROOF PANELS

- #### A. Standing-Seam Metal Roof Panel Installation:
- Fasten metal roof panels to supports with concealed clips at each standing-seam joint at location, spacing, and with fasteners recommended in writing by manufacturer.
1. Install clips to supports with self-tapping fasteners.
 2. Install pressure plates at locations indicated in manufacturer's written installation instructions.
 3. Seamed Joint: Crimp standing seams with manufacturer-approved, motorized seamer tool so clip, metal roof panel, and factory-applied sealant are completely engaged.
 4. Watertight Installation:

- a. Apply a continuous ribbon of sealant or tape to seal joints of metal panels, using sealant or tape as recommend in writing by manufacturer as needed to make panels watertight.
 - b. Provide sealant or tape between panels and protruding equipment, vents, and accessories.
 - c. At panel splices, nest panels with minimum 6-inch end lap, sealed with sealant and fastened together by interlocking clamping plates.
- B. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.
- C. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently watertight and weather resistant.

3.4 CLEANING AND PROTECTION

- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.

END OF SECTION

SECTION 074213.13 - FORMED METAL WALL PANELS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Concealed-fastener, lap-seam metal wall panels.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

B. Sustainable Design Submittals:

1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

- C. Shop Drawings: Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment system, trim, flashings, closures, and accessories; and special details.

- D. Samples: For each type of metal panel indicated.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

1.5 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Final Completion.

- B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.

1. Finish Warranty Period: 20 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Structural Performance: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E1592:
 1. Wind Loads: As indicated on Drawings.
 2. Other Design Loads: As indicated on Drawings.
 3. Deflection Limits: For wind loads, no greater than 1/240 of the span.
- C. Air Infiltration: Air leakage of not more than 0.06 cfm/sq. ft. when tested according to ASTM E283 at the following test-pressure difference:
 1. Test-Pressure Difference: 6.24 lbf/sq. ft..
- D. Water Penetration under Static Pressure: No water penetration when tested according to ASTM E331 at the following test-pressure difference:
 1. Test-Pressure Difference: 6.24 lbf/sq. ft..
- E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

2.2 CONCEALED-FASTENER, LAP-SEAM METAL WALL PANELS

- A. Provide factory-formed metal panels designed to be field assembled by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners and factory-applied sealant in side laps. Include accessories required for weathertight installation.
- B. Reveal-Joint, Concealed-Fastener Metal Wall Panels : Formed with vertical panel edges and a flat pan between panel edges; with narrow reveal joint between panels.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CENTRIA, a Nucor Brand?.

- b. Morin - A Kingspan Group Company.
 - c. PAC-CLAD; Petersen Aluminum Corporation; a Carlisle company.
2. Metallic-Coated Steel Sheet: Zinc-coated (galvanized) steel sheet complying with ASTM A653/A653M, G90 coating designation, or aluminum-zinc alloy-coated steel sheet complying with ASTM A792/A792M, Class AZ50 coating designation; structural quality. Prepainted by the coil-coating process to comply with ASTM A755/A755M.
- a. Nominal Thickness: 0.052 inch.
 - b. Exterior Finish: Two-coat fluoropolymer.
 - c. Color: As indicated by manufacturer's designations.

2.3 MISCELLANEOUS MATERIALS

- A. Miscellaneous Metal Subframing and Furring: ASTM C645, cold-formed, metallic-coated steel sheet, ASTM A653/A653M, G90 hot-dip galvanized coating designation or ASTM A792/A792M, Class AZ50 aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.
- B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, copings, fasciae, mullions, sills, corner units, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.
1. Closures: Provide closures at eaves and rakes, fabricated of same metal as metal panels.
 2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
 3. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- thick, flexible closure strips; cut or premolded to match metal panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.
- C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, bases, drips, sills, jambs, corners, endwalls, framed openings, rakes, fasciae, parapet caps, soffits, reveals, and fillers. Finish flashing and trim with same finish system as adjacent metal panels.
- D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners with heads matching color of metal panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.
- E. Panel Sealants: Provide sealant type recommended by manufacturer that are compatible with panel materials, are nonstaining, and do not damage panel finish.
1. Butyl-Rubber-Based, Solvent-Release Sealant: ASTM C1311.

2.4 FABRICATION

- A. Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.
- B. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel.
- C. Fabricate metal panel joints with factory-installed captive gaskets or separator strips that provide a weathertight seal and prevent metal-to-metal contact, and that minimize noise from movements.
- D. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.

2.5 FINISHES

- A. Panels and Accessories:
 - 1. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent polyvinylidene fluoride (PVDF) resin by weight in color coat.
 - 2. Concealed Finish: White or light-colored acrylic or polyester backer finish.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C754 and metal panel manufacturer's written recommendations.

3.2 INSTALLATION

- A. Lap-Seam Metal Panels: Fasten metal panels to supports with fasteners at each lapped joint at location and spacing recommended by manufacturer.
 - 1. Lap ribbed or fluted sheets one full rib. Apply panels and associated items true to line for neat and weathertight enclosure.
 - 2. Provide metal-backed washers under heads of exposed fasteners bearing on weather side of metal panels.

3. Install screw fasteners with power tools having controlled torque adjusted to compress washer tightly without damage to washer, screw threads, or panels. Install screws in predrilled holes.
4. Flash and seal panels with weather closures at perimeter of all openings.

B. Watertight Installation:

1. Apply a continuous ribbon of sealant or tape to seal lapped joints of metal panels, using sealant or tape as recommend by manufacturer on side laps of nesting-type panels; and elsewhere as needed to make panels watertight.
2. Provide sealant or tape between panels and protruding equipment, vents, and accessories.
3. At panel splices, nest panels with minimum 6-inch end lap, sealed with sealant and fastened together by interlocking clamping plates.

C. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.

D. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.

3.3 CLEANING

- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.

END OF SECTION

SECTION 074293 - SOFFIT PANELS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Metal soffit panels.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment system, trim, flashings, closures, and accessories; and special details.
- C. Samples: For each type of metal panel indicated.

1.4 INFORMATIONAL SUBMITTALS

- A. Warranties: Samples of special warranties.

1.5 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.
 1. Warranty Period: Two years from date of Final Completion.
- B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.
 1. Finish Warranty Period: 20 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Structural Performance: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E1592:
 - 1. Wind Loads: As indicated on Drawings.
 - 2. Other Design Loads: As indicated on Drawings.
 - 3. Deflection Limits: For wind loads, no greater than 1/240 of the span.
- C. Air Infiltration: Air leakage of not more than 0.06 cfm/sq. ft. when tested according to ASTM E283 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft..
- D. Water Penetration under Static Pressure: No water penetration when tested according to ASTM E331 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft..
- E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

2.2 METAL SOFFIT PANELS

- A. Provide metal soffit panels designed to be installed by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners in side laps. Include accessories required for weathertight installation.
- B. Metal Soffit Panels: Match profile and material of metal roof panels.
 - 1. Finish: Match finish and color of metal roof panels.
 - 2. Sealant: Factory applied within interlocking joint.
- C. Reveal-Joint-Profile Metal Soffit Panels : Solid panels formed with vertical panel edges and a flat pan between panel edges; with recessed reveal joint between panels.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Firestone Building Products.
 - b. Firestone Metal Products.
 - c. PAC-CLAD; Petersen Aluminum Corporation; a Carlisle company.
2. Material: Same material, finish, and color as metal roof panels.
3. Panel Coverage: 12 inches.
4. Panel Height: 0.75 inch.

2.3 MISCELLANEOUS MATERIALS

- A. Miscellaneous Metal Subframing and Furring: ASTM C645, cold-formed, metallic-coated steel sheet, ASTM A653/A653M, G90 hot-dip galvanized coating designation or ASTM A792/A792M, Class AZ50 aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.
- B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.
 1. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- thick, flexible closure strips; cut or premolded to match metal panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.
- C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Finish flashing and trim with same finish system as adjacent metal panels.
- D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners with heads matching color of metal panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.
- E. Panel Sealants: Provide sealant types recommended by manufacturer that are compatible with panel materials, are nonstaining, and do not damage panel finish.
 1. Butyl-Rubber-Based, Solvent-Release Sealant: ASTM C1311.

2.4 FABRICATION

- A. Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.
- B. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel.
- C. Fabricate metal panel joints with factory-installed captive gaskets or separator strips that provide a weathertight seal and prevent metal-to-metal contact, and that minimize noise from movements.
- D. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.

2.5 FINISHES

- A. Panels and Accessories:
 - 1. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent polyvinylidene fluoride (PVDF) resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C754 and metal panel manufacturer's written recommendations.
 - 1. Soffit Framing: Wire tie or clip furring channels to supports, as required to comply with requirements for assemblies indicated.

3.2 INSTALLATION

- A. Metal Soffit Panels: Fasten metal panels to supports with fasteners at each lapped joint at location and spacing recommended by manufacturer.
 - 1. Apply panels and associated items true to line for neat and weathertight enclosure.

2. Provide metal-backed washers under heads of exposed fasteners bearing on weather side of metal panels.
3. Locate and space exposed fasteners in uniform vertical and horizontal alignment. Use proper tools to obtain controlled uniform compression for positive seal without rupture of washer.
4. Install screw fasteners with power tools having controlled torque adjusted to compress washer tightly without damage to washer, screw threads, or panels. Install screws in predrilled holes.

B. Watertight Installation:

1. Apply a continuous ribbon of sealant or tape to seal lapped joints of metal panels, using sealant or tape as recommend by manufacturer on side laps of nesting-type panels and elsewhere as needed to make panels watertight.
2. Provide sealant or tape between panels and protruding equipment, vents, and accessories.
3. At panel splices, nest panels with minimum 6-inch end lap, sealed with sealant and fastened together by interlocking clamping plates.

C. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.

D. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.

3.3 CLEANING

- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.

END OF SECTION

SECTION 076200 - SHEET METAL FLASHING AND TRIM

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Formed roof-drainage sheet metal fabrications.
2. Formed low-slope roof sheet metal fabrications.
3. Formed steep-slope roof sheet metal fabrications.
4. Formed wall sheet metal fabrications.
5. Rain chains and basins.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data:

1. Underlayment materials.
2. Butyl sealant.

B. Sustainable Design Submittals:

1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

C. Shop Drawings: For sheet metal flashing and trim.

1. Include plans, elevations, sections, and attachment details.
2. Detail fabrication and installation layouts, expansion-joint locations, and keyed details. Distinguish between shop- and field-assembled Work.
3. Include identification of material, thickness, weight, and finish for each item and location in Project.
4. Include details for forming, including profiles, shapes, seams, and dimensions.
5. Include details for joining, supporting, and securing, including layout and spacing of fasteners, cleats, clips, and other attachments. Include pattern of seams.
6. Include details of termination points and assemblies.
7. Include details of expansion joints and expansion-joint covers, including showing direction of expansion and contraction from fixed points.
8. Include details of roof-penetration flashing.
9. Include details of edge conditions, including eaves, ridges, valleys, rakes, crickets, flashings, and counterflashings.

10. Include details of special conditions.
11. Include details of connections to adjoining work.

- D. Samples: For each exposed product and for each color and texture specified, 12 inches long by actual width.

1.4 INFORMATIONAL SUBMITTALS

- A. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance data.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Sheet metal flashing and trim assemblies, including cleats, anchors, and fasteners, are to withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim are not to rattle, leak, or loosen, and are to remain watertight.
- B. Sheet Metal Standard for Flashing and Trim: Comply with SMACNA's "Architectural Sheet Metal Manual" requirements for dimensions and profiles shown unless more stringent requirements are indicated.
- C. SPRI Wind Design Standard: Manufacture and install roof edge flashings tested in accordance with ANSI/SPRI/FM 4435/ES-1 and capable of resisting the following design pressure:
 1. Design Pressure: As indicated on Drawings.
- D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes to prevent buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 SHEET METALS

- A. Protect mechanical and other finishes on exposed surfaces from damage by applying stripping, temporary protective film before shipping.

- B. Metallic-Coated Steel Sheet: Provide zinc-coated (galvanized) steel sheet in accordance with ASTM A653/A653M, G90 coating designation; prepainted by coil-coating process to comply with ASTM A755/A755M.
1. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
 2. Surface: Smooth, flat .
 3. Exposed Coil-Coated Finish:
 - a. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent polyvinylidene fluoride (PVDF) resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
 4. Color: As indicated by manufacturer's designations.
 5. Concealed Finish: Pretreat with manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with minimum total dry film thickness of 0.5 mil.

2.3 UNDERLAYMENT MATERIALS

- A. Self-Adhering, High-Temperature Sheet Underlayment: Minimum 30 mils thick, consisting of a slip-resistant polyethylene- or polypropylene-film top surface laminated to a layer of butyl- or SBS-modified asphalt adhesive, with release-paper backing; specifically designed to withstand high metal temperatures beneath metal roofing. Provide primer in accordance with underlayment manufacturer's written instructions.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ATAS International, Inc.
 - b. Carlisle WIP Products; a brand of Carlisle Construction Materials.
 - c. GCP Applied Technologies Inc.
 - d. Henry Company.
 - e. Owens Corning.
 - f. Polyglass U.S.A., Inc.
 - g. Protecto Wrap Company.
 - h. SDP Advanced Polymer Products Inc.

2.4 MISCELLANEOUS MATERIALS

- A. Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal or manufactured item unless otherwise indicated.

- B. Butyl Sealant: ASTM C1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.
- C. Rain Chains: Basis-of-Design Product, provide SEO Toh-L or comparable product by RainChains or Rutland Gutter Supply. Color: Dark Brown.
- D. Rain Chain Basin: Basis-of-Design Product, provide SEO Amane-L or comparable product by RainChains or Rutland Gutter Supply. Color: Black.

2.5 FABRICATION, GENERAL

- A. Custom fabricate sheet metal flashing and trim to comply with details indicated and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required.
 - 1. Fabricate sheet metal flashing and trim in shop to greatest extent possible.
 - 2. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
 - 3. Verify shapes and dimensions of surfaces to be covered and obtain field measurements for accurate fit before shop fabrication.
 - 4. Form sheet metal flashing and trim to fit substrates without excessive oil-canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
 - 5. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners on faces exposed to view.
- B. Fabrication Tolerances:
 - 1. Fabricate sheet metal flashing and trim that is capable of installation to a tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.
 - 2. Fabricate sheet metal flashing and trim that is capable of installation to tolerances specified.
- C. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.
 - 1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
 - 2. Use lapped expansion joints only where indicated on Drawings.
- D. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal in accordance with cited sheet metal standard to provide for proper installation of elastomeric sealant.
- E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.

- F. Fabricate cleats and attachment devices of sizes as recommended by cited sheet metal standard for application, but not less than thickness of metal being secured.
- G. Seams:
 - 1. Fabricate nonmoving seams with flat-lock seams. Form seams and seal with elastomeric sealant unless otherwise recommended by sealant manufacturer for intended use.

2.6 ROOF-DRAINAGE SHEET METAL FABRICATIONS

A. Hanging Gutters:

- 1. Fabricate to cross section required, complete with end pieces, outlet tubes, and other accessories as required.
- 2. Fabricate in minimum 96-inch- long sections.
- 3. Furnish flat-stock gutter brackets and flat-stock gutter spacers and straps fabricated from same metal as gutters, of size recommended by cited sheet metal standard, but with thickness not less than twice the gutter thickness.
- 4. Fabricate expansion joints, expansion-joint covers, gutter bead reinforcing bars, and gutter accessories from same metal as gutters.
- 5. Accessories: Continuous, removable leaf screen with sheet metal frame and hardware cloth screen.
- 6. Gutters with Girth up to 15 Inches: Fabricate from the following materials:
 - a. Galvanized Steel: 0.022 inch thick.

2.7 LOW-SLOPE ROOF SHEET METAL FABRICATIONS

A. Counterflashing: Shop fabricate interior and exterior corners. Fabricate from the following materials:

- 1. Galvanized Steel: 0.022 inch thick.

B. Roof-Penetration Flashing: Fabricate from the following materials:

- 1. Galvanized Steel: 0.028 inch thick.

2.8 STEEP-SLOPE ROOF SHEET METAL FABRICATIONS

A. Drip Edges: Fabricate from the following materials:

- 1. Galvanized Steel: 0.022 inch thick.

B. Eave, Rake, Ridge, and Hip Flashing: Fabricate from the following materials:

- 1. Galvanized Steel: 0.022 inch thick.

2.9 WALL SHEET METAL FABRICATIONS

- A. Opening Flashings in Frame Construction: Fabricate head, sill, jamb, and similar flashings to extend beyond wall openings. Form head and sill flashing with 2-inch-high, end dams. Fabricate from the following materials:
1. Galvanized Steel: 0.022 inch thick.

PART 3 - EXECUTION

3.1 INSTALLATION OF UNDERLAYMENT

- A. Self-Adhering, High-Temperature Sheet Underlayment:
1. Install self-adhering, high-temperature sheet underlayment; wrinkle free.
 2. Prime substrate if recommended by underlayment manufacturer.
 3. Comply with temperature restrictions of underlayment manufacturer for installation; use primer for installing underlayment at low temperatures.
 4. Apply in shingle fashion to shed water, with end laps of not less than 6 inches staggered 24 inches between courses.
 5. Overlap side edges not less than 3-1/2 inches. Roll laps and edges with roller.
 6. Roll laps and edges with roller.
 7. Cover underlayment within 14 days.

3.2 INSTALLATION, GENERAL

- A. Install sheet metal flashing and trim to comply with details indicated and recommendations of cited sheet metal standard that apply to installation characteristics required unless otherwise indicated on Drawings.
1. Install fasteners, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
 2. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of sealant.
 3. Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement.
 4. Install sheet metal flashing and trim to fit substrates and to result in watertight performance.
 5. Install continuous cleats with fasteners spaced not more than 12 inches o.c.
 6. Space individual cleats not more than 12 inches apart. Attach each cleat with at least two fasteners. Bend tabs over fasteners.
 7. Install exposed sheet metal flashing and trim with limited oil-canning, and free of buckling and tool marks.
 8. Do not field cut sheet metal flashing and trim by torch.

- B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.
1. Coat concealed side of sheet metal flashing and trim with bituminous coating where flashing and trim contact wood, ferrous metal, or cementitious construction.
 2. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.
- C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim.
1. Space movement joints at maximum of 10 feet with no joints within 24 inches of corner or intersection.
 2. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with sealant concealed within joints.
 3. Use lapped expansion joints only where indicated on Drawings.
- D. Fasteners: Use fastener sizes that penetrate substrate not less than recommended by fastener manufacturer to achieve maximum pull-out resistance.
- E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.
- F. Seal joints as required for watertight construction.
1. Use sealant-filled joints unless otherwise indicated.
 - a. Embed hooked flanges of joint members not less than 1 inch into sealant.
 - b. Form joints to completely conceal sealant.
 - c. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way.
 - d. Adjust setting proportionately for installation at higher ambient temperatures.
 - 1) Do not install sealant-type joints at temperatures below 40 deg F.
 2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."

3.3 INSTALLATION OF ROOF-DRAINAGE SYSTEM

- A. Install sheet metal roof-drainage items to produce complete roof-drainage system in accordance with cited sheet metal standard unless otherwise indicated. Coordinate installation of roof perimeter flashing with installation of roof-drainage system.
- B. Hanging Gutters:

1. Join sections with joints sealed with sealant.
2. Provide for thermal expansion.
3. Attach gutters at eave or fascia to firmly anchor them in position.
4. Provide end closures and seal watertight with sealant.
5. Slope to downspouts.
6. Install gutter with expansion joints at locations indicated on Drawings, but not exceeding, 50 feet apart. Install expansion-joint caps.
7. Install continuous gutter screens on gutters with noncorrosive fasteners, hinged to swing open for cleaning gutters.

- C. Expansion-Joint Covers: Install expansion-joint covers at locations and of configuration indicated on Drawings. Lap joints minimum of 4 inches in direction of water flow.

3.4 INSTALLATION OF ROOF FLASHINGS

- A. Install sheet metal flashing and trim to comply with performance requirements, sheet metal manufacturer's written installation instructions, and cited sheet metal standard.
1. Provide concealed fasteners where possible, and set units true to line, levels, and slopes.
 2. Install work with laps, joints, and seams that are permanently watertight and weather resistant.
- B. Roof Edge Flashing:
1. Install roof edge flashings in accordance with ANSI/SPRI/FM 4435/ES-1.
 2. Anchor to resist uplift and outward forces in accordance with recommendations in cited sheet metal standard unless otherwise indicated. Interlock bottom edge of roof edge flashing with continuous cleat anchored to substrate at staggered 3-inch centers.
 3. Anchor to resist uplift and outward forces in accordance with recommendations in FM Global Property Loss Prevention Data Sheet 1-49 for FM Approvals' listing for required windstorm classification.
- C. Pipe or Post Counterflashing: Install counterflashing umbrella with close-fitting collar with top edge flared for elastomeric sealant, extending minimum of 4 inches over base flashing. Install stainless steel draw band and tighten.
- D. Counterflashing: Coordinate installation of counterflashing with installation of base flashing.
1. Insert counterflashing in reglets or receivers and fit tightly to base flashing.
 2. Extend counterflashing 4 inches over base flashing.
 3. Lap counterflashing joints minimum of 4 inches.
- E. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with butyl sealant and clamp flashing to pipes that penetrate roof.

3.5 INSTALLATION OF WALL FLASHINGS

- A. Install sheet metal wall flashing to intercept and exclude penetrating moisture in accordance with cited sheet metal standard unless otherwise indicated. Coordinate installation of wall flashing with installation of wall-opening components such as windows, doors, and louvers.
- B. Opening Flashings in Frame Construction: Install continuous head, sill, jamb, and similar flashings to extend beyond wall openings.

3.6 INSTALLATION TOLERANCES

- A. Installation Tolerances: Shim and align sheet metal flashing and trim within installed tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.7 CLEANING

- A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.
- B. Clean off excess sealants.

3.8 PROTECTION

- A. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions.
- B. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures, as determined by Architect.

END OF SECTION

SECTION 079200 - JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Silicone joint sealants.
2. Urethane joint sealants.
3. Mildew-resistant joint sealants.
4. Latex joint sealants.

1.2 ACTION SUBMITTALS

- A. Product data.
- B. Samples: Manufacturer's standard color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.
- C. Joint-sealant schedule.

1.3 INFORMATIONAL SUBMITTALS

- A. Field Quality-Control Reports: For field-adhesion-test reports, for each sealant application tested.
- B. Sample warranties.

1.4 CLOSEOUT SUBMITTALS

- A. Warranty Documentation:
 1. Manufacturers' special warranties.
 2. Installer's special warranties.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Authorized representative who is trained and approved by manufacturer.
- B. Testing Agency Qualifications: Qualified in accordance with ASTM C1021 to conduct the testing indicated.

1.6 WARRANTY

- A. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Two years from date of Final Completion.
- B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Five years from date of Final Completion.
- C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:
 - 1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
 - 2. Disintegration of joint substrates from causes exceeding design specifications.
 - 3. Mechanical damage caused by individuals, tools, or other outside agents.
 - 4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 JOINT SEALANTS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.
- B. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.2 SILICONE JOINT SEALANTS

- A. Silicone, S, NS, 100/50, NT: Single-component, nonsag, plus 100 percent and minus 50 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 100/50, Use NT.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Adfast.
 - b. GE Construction Sealants; Momentive Performance Materials Inc.

- c. Sika Corporation - Building Components.

2.3 URETHANE JOINT SEALANTS

- A. Urethane, S, NS, 25, NT: Single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, urethane joint sealant; ASTM C920, Type S, Grade NS, Class 25, Use NT.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Adfast.
 - b. Bostik; Arkema.
 - c. Pecora Corporation.
 - d. Polymeric Systems, Inc.
 - e. Sherwin-Williams Company (The).

2.4 MILDEW-RESISTANT JOINT SEALANTS

- A. Mildew-Resistant Joint Sealants: Formulated for prolonged exposure to humidity with fungicide to prevent mold and mildew growth.
- B. Silicone, Mildew Resistant, Acid Curing, S, NS, 25, NT: Mildew-resistant, single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, acid-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 25, Use NT.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Adfast.
 - b. GE Construction Sealants; Momentive Performance Materials Inc.
 - c. Pecora Corporation.
 - d. Sika Corporation - Building Components.
 - e. Soudal USA.
 - f. The Dow Chemical Company.
 - g. Tremco Incorporated.

2.5 LATEX JOINT SEALANTS

- A. Acrylic Latex: Acrylic latex or siliconized acrylic latex, ASTM C834, Type OP, Grade NF.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Adfast.
 - b. Everkem Diversified Products, Inc.

- c. Franklin International.
- d. Pecora Corporation.
- e. Sherwin-Williams Company (The).
- f. Tremco Incorporated.

2.6 JOINT-SEALANT BACKING

- A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Adfast.
 - b. Alcot Plastics Ltd.
 - c. Construction Foam Products; a division of Nomaco, Inc.
 - d. Master Builders Solutions.
- B. Cylindrical Sealant Backings: ASTM C1330, Type C (closed-cell material with a surface skin), and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.7 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
 2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:
 - a. Concrete.
 - b. Unglazed surfaces of ceramic tile.
 - c. .
 3. Remove laitance and form-release agents from concrete.
 4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:
 - a. Metal.
 - b. Glass.
 - c. Porcelain enamel.
 - d. Glazed surfaces of ceramic tile.
- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.
- 3.2 INSTALLATION OF JOINT SEALANTS
- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
 - B. Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
 - C. Install sealant backings of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 1. Do not leave gaps between ends of sealant backings.

2. Do not stretch, twist, puncture, or tear sealant backings.
 3. Remove absorbent sealant backings that have become wet before sealant application, and replace them with dry materials.
- D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.
- E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
1. Place sealants so they directly contact and fully wet joint substrates.
 2. Completely fill recesses in each joint configuration.
 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants in accordance with requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
1. Remove excess sealant from surfaces adjacent to joints.
 2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
 3. Provide concave joint profile in accordance with Figure 8A in ASTM C1193 unless otherwise indicated.
 4. Provide flush joint profile at locations indicated on Drawings in accordance with Figure 8B in ASTM C1193.
 5. Provide recessed joint configuration of recess depth and at locations indicated on Drawings in accordance with Figure 8C in ASTM C1193.
 - a. Use masking tape to protect surfaces adjacent to recessed tooled joints.
- G. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.
- H. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Final Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.3 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Tests and Inspections:

1. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:
 - a. Extent of Testing: Test completed and cured sealant joints as follows:
 - 1) Perform 10 tests for the first 1000 ft. of joint length for each kind of sealant and joint substrate.
 - 2) Perform one test for each 1000 ft. of joint length thereafter or one test per each floor per elevation.
 - b. Test Method: Test joint sealants in accordance with Method A, Tail Procedure, in ASTM C1521.
 - 1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.
 - c. Inspect tested joints and report on the following:
 - 1) Whether sealants filled joint cavities and are free of voids.
 - 2) Whether sealant dimensions and configurations comply with specified requirements.
 - 3) Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.
 - d. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.
 - e. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.
2. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

C. Prepare test and inspection reports.

3.4 JOINT SEALANT SCHEDULE

1. Refer to Drawings for Joint Sealant Schedule.

END OF SECTION

SECTION 079219 - ACOUSTICAL JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Acoustical joint sealants.

1.2 ACTION SUBMITTALS

- A. Product data.

PART 2 - PRODUCTS

2.1 ACOUSTICAL JOINT SEALANTS

- A. Acoustical joint-sealant products that effectively reduce airborne sound transmission through perimeter joints and openings in building construction, as demonstrated by testing representative assemblies in accordance with ASTM E90.
- B. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex acoustical sealant complying with ASTM C834.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Accumetric LLC.
 - b. DAP Products Inc.
 - c. GE Construction Sealants; Momentive Performance Materials Inc.
 - d. Hilti, Inc.
 - e. Pecora Corporation.
 - 2. Colors of Exposed Acoustical Joint Sealants: As selected by Architect from manufacturer's full range of colors.
- C. Acoustical Sealant for Concealed Joints: Manufacturer's standard nonsag, nondrying, nonhardening, nonskinning, nonstaining, gunnable, synthetic-rubber acoustical sealant.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. OSI Sealants; Henkel Corporation.
 - b. Pecora Corporation.
 - c. Tremco Incorporated.

- d. USG Corporation.

2.2 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by acoustical joint-sealant manufacturer where required for adhesion of sealant to joint substrates.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine joints indicated to receive acoustical joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing acoustical joint sealants to comply with joint-sealant manufacturer's written instructions.
- B. Joint Priming: Prime joint substrates where recommended by acoustical joint-sealant manufacturer. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF ACOUSTICAL JOINT SEALANTS

- A. Comply with acoustical joint-sealant manufacturer's written installation instructions unless more stringent requirements apply.

- B. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical joint sealant. Install acoustical joint sealants at both faces of partitions, at perimeters, and through penetrations. Comply with ASTM C919, ASTM C1193, and manufacturer's written instructions for closing off sound-flanking paths around or through assemblies, including sealing partitions to underside of floor slabs above acoustical ceilings.
- C. Acoustical Ceiling Areas: Apply acoustical joint sealant at perimeter edge moldings of acoustical ceiling areas in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.

END OF SECTION

SECTION 081113 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior custom hollow-metal doors and frames.
2. Exterior custom hollow-metal doors and frames.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Sustainable Design Submittals:

1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

C. Shop Drawings: Include the following:

1. Elevations of each door type.
2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.

D. Product Schedule: For hollow-metal doors and frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hardware schedule.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Ceco Door; AADG, Inc.; ASSA ABLOY.
2. Curries, AADG, Inc.; ASSA ABLOY Group.
3. National Custom Hollow Metal Doors & Frames.
4. Republic Doors and Frames; a Allegion brand.
5. Security Metal Products; a brand of ASSA ABLOY.
6. Steelcraft; Allegion plc.

2.2 PERFORMANCE REQUIREMENTS

- A. Thermally Rated Door Assemblies: Provide door assemblies with U-factor of not more than 0.50 deg Btu/F x h x sq. ft. when tested in accordance with ASTM C1363 or ASTM E1423.

2.3 INTERIOR CUSTOM HOLLOW-METAL DOORS AND FRAMES

- A. Hollow-Metal Doors and Frames: NAAMM-HMMA 860; ANSI/SDI A250.4, Physical Performance Level A. .

1. Doors:

- a. Type: As indicated in the Door and Frame Schedule on Drawings.
- b. Thickness: 1-3/4 inches.
- c. Face: Uncoated steel sheet, minimum thickness of 0.032 inch.
- d. Edge Construction: Continuously welded with no visible seam.
- e. Core: Steel stiffened.

2. Frames:

- a. Materials: Uncoated steel sheet, minimum thickness of 0.053 inch.
- b. Construction: Full profile welded.

2.4 EXTERIOR CUSTOM HOLLOW-METAL DOORS AND FRAMES

- A. Commercial Doors and Frames: NAAMM-HMMA 861; ANSI/SDI A250.4, Physical Performance Level A.

1. Doors:

- a. Type: As indicated in the Door and Frame Schedule on Drawings.
- b. Thickness: 1-3/4 inches.
- c. Face: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum G60 or A60 coating.
- d. Edge Construction: Continuously welded with no visible seam.
- e. Top Edge Closures: Close top edges of doors with flush closures of same material as face sheets. Seal joints against water penetration.
- f. Bottom Edges: Close bottom edges of doors with end closures or channels of same material as face sheets. Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape.
- g. Core: Steel stiffened.

2. Frames:

- a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, except 0.067 inch for openings exceeding 4 feet wide; with minimum G60 or A60 coating.

- b. Construction: Face welded.

2.5 FRAME ANCHORS

A. Jamb Anchors:

1. Type: Anchors of minimum size and type required by applicable door and frame standard, and suitable for performance level indicated.
2. Quantity: Minimum of three anchors per jamb, with one additional anchor for frames with no floor anchor. Provide one additional anchor for each 24 inches of frame height above 7 feet.
3. Postinstalled Expansion Anchor: Minimum 3/8-inch- diameter bolts with expansion shields or inserts, with manufacturer's standard pipe spacer.

B. Material: ASTM A879/A879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.

1. For anchors built into exterior walls, steel sheet complying with ASTM A1008/A1008M or ASTM A1011/A1011M; hot-dip galvanized in accordance with ASTM A153/A153M, Class B.

2.6 MATERIALS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- C. Hot-Rolled Steel Sheet: ASTM A1011/A1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.
- D. Metallic-Coated Steel Sheet: ASTM A653/A653M, Commercial Steel (CS), Type B.
- E. Inserts, Bolts, and Fasteners: Hot-dip galvanized in accordance with ASTM A153/A153M.
- F. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.
- G. Mineral-Fiber Insulation: ASTM C665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively; passing ASTM E136 for combustion characteristics.
- H. Glazing: Comply with requirements in Section 088000 "Glazing."

2.7 FABRICATION

- A. Door Astragals: Provide overlapping astragal on one leaf of pairs of doors where required by NFPA 80 for fire-performance rating or where indicated. Extend minimum 3/4 inch beyond edge of door on which astragal is mounted or as required to comply with published listing of qualified testing agency.
- B. Hollow-Metal Frames: Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as frames.
1. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
 2. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.
 - a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
 - b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.
- C. Hardware Preparation: Factory prepare hollow-metal doors and frames to receive templated mortised hardware, and electrical wiring; include cutouts, reinforcement, mortising, drilling, and tapping in accordance with ANSI/SDI A250.6, the Door Hardware Schedule on Drawings, and templates.
1. Reinforce doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.
 2. Comply with BHMA A156.115 for preparing hollow-metal doors and frames for hardware.
- D. Glazed Lites: Provide stops and moldings around glazed lites where indicated. Form corners of stops and moldings with mitered hairline joints.
1. Provide stops and moldings flush with face of door, and with square stops unless otherwise indicated.
 2. Multiple Glazed Lites: Provide fixed and removable stops and moldings so that each glazed lite is capable of being removed independently.
 3. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames. Provide loose stops and moldings on inside of hollow-metal doors and frames.
 4. Coordinate rabbet width between fixed and removable stops with glazing and installation types indicated.
 5. Provide stops for installation with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

2.8 STEEL FINISHES

- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.
 - 1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with ANSI/SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces. Touch up factory-applied finishes where spreaders are removed.
- B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

3.2 INSTALLATION

- A. Hollow-Metal Frames: Comply with ANSI/SDI A250.11.
 - 1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces without damage to completed Work.
 - a. Where frames are fabricated in sections, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces. Touch-up finishes.
 - b. Install frames with removable stops located on secure side of opening.
 - 2. Solidly pack mineral-fiber insulation inside frames.
 - 3. Installation Tolerances: Adjust hollow-metal frames to the following tolerances:
 - a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
 - b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
 - c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
 - d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.
- B. Hollow-Metal Doors: Fit and adjust hollow-metal doors accurately in frames, within clearances specified below.

1. Non-Fire-Rated Steel Doors: Comply with ANSI/SDI A250.8.
- C. Glazing: Comply with installation requirements in Section 088000 "Glazing" and with hollow-metal manufacturer's written instructions.

3.3 REPAIR

- A. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.
- B. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint in accordance with manufacturer's written instructions.
- C. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION

SECTION 081416 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Five-ply flush wood veneer-faced doors for transparent finish.
2. Factory finishing flush wood doors.
3. Factory fitting flush wood doors to frames and factory machining for hardware.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product, including the following:

1. Door core materials and construction.
2. Door edge construction
3. Door face type and characteristics.
4. Door louvers.
5. Door trim for openings.
6. Door frame construction.
7. Factory-machining criteria.
8. Factory-finishing specifications.

B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each type of door; construction details not covered in Product Data; and the following:

1. Door schedule indicating door location, type, size, fire protection rating, and swing.
2. Door elevations, dimension and locations of hardware, lite and louver cutouts, and glazing thicknesses.
3. Details of frame for each frame type, including dimensions and profile.
4. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
5. Dimensions and locations of blocking for hardware attachment.
6. Clearances and undercuts.
7. Requirements for veneer matching.

C. Samples: For factory-finished doors.

PART 2 - PRODUCTS

2.1 FLUSH WOOD DOORS AND FRAMES, GENERAL

2.2 SOLID-CORE, FIVE-PLY FLUSH WOOD VENEER-FACED DOORS FOR TRANSPARENT FINISH

A. Interior Doors, Solid-Core Five-Ply Veneer-Faced :

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Lambton Doors.
 - b. Oshkosh Door Company.
 - c. VT Industries, Inc.
2. Performance Grade: ANSI/WDMA I.S. 1A Extra Heavy Duty.
3. Architectural Woodwork Standards Grade: Premium.
4. Faces: Single-ply wood veneer not less than 1/50 inch thick.
 - a. Species: Select white maple.
 - b. Cut: Plain sliced (flat sliced).
 - c. Match between Veneer Leaves: Book match.
 - d. Assembly of Veneer Leaves on Door Faces: Center-balance match.
5. Exposed Vertical and Top Edges: Same species as faces or a compatible species - Architectural Woodwork Standards edge Type A.
 - a. Mineral-Core Doors: At hinge stiles, provide laminated-edge construction with improved screw-holding capability and split resistance. Comply with specified requirements for exposed edges.
 - 1) Screw-Holding Capability: 550 lbf in accordance with WDMA T.M. 10.
6. Core for Non-Fire-Rated Doors:
 - a. ANSI A208.1, Grade LD-1 particleboard.
 - 1) Provide doors with WDMA I.S. 10 structural-composite-lumber cores instead of particleboard cores for doors scheduled to receive exit devices in Section 087100 "Door Hardware."
7. Construction: Five plies, hot-pressed bonded (vertical and horizontal edging is bonded to core), with entire unit abrasive planed before veneering.

2.3 LIGHT FRAMES AND LOUVERS

- A. Wood Beads for Light Openings in Wood Doors: Provide manufacturer's standard wood beads unless otherwise indicated.
 - 1. Wood Species: Same species as door faces.
 - 2. Profile: Flush rectangular beads.

2.4 FABRICATION

- A. Factory fit doors to suit frame-opening sizes indicated.
 - 1. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.
- B. Factory machine doors for hardware that is not surface applied.
 - 1. Locate hardware to comply with DHI-WDHS-3.
 - 2. Comply with final hardware schedules, door frame Shop Drawings, ANSI/BHMA-156.115-W, and hardware templates.
 - 3. Coordinate with hardware mortises in metal frames, to verify dimensions and alignment before factory machining.
 - 4. For doors scheduled to receive electrified locksets, provide factory-installed raceway and wiring to accommodate specified hardware.
- C. Openings: Factory cut and trim openings through doors.
 - 1. Light Openings: Trim openings with moldings of material and profile indicated.
 - 2. Glazing: Factory install glazing in doors indicated to be factory finished. Comply with applicable requirements in Section 088000 "Glazing."
 - 3. Louvers: Factory install louvers in prepared openings.

2.5 FACTORY FINISHING

- A. Comply with referenced quality standard for factory finishing.
 - 1. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
 - 2. Finish faces, all four edges, edges of cutouts, and mortises.
 - 3. Stains and fillers may be omitted on bottom edges, edges of cutouts, and mortises.
- B. Factory finish doors.
- C. Transparent Finish:
 - 1. Architectural Woodwork Standards Grade: Premium.
 - 2. Architectural Woodwork Standards System-11, Polyurethane, Catalyzed.

3. Staining: None required.
4. Sheen: Satin.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Hardware: For installation, see Section 087100 "Door Hardware."
- B. Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.
- C. Install frames level, plumb, true, and straight.
 1. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches.
 2. Anchor frames to anchors or blocking built in or directly attached to substrates.
 - a. Secure with countersunk, concealed fasteners and blind nailing.
 - b. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork.
 - 1) For factory-finished items, use filler matching finish of items being installed.
- D. Factory-Fitted Doors: Align in frames for uniform clearance at each edge.
- E. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

3.2 ADJUSTING

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION

SECTION 083113 - ACCESS DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Access doors and frames.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 ACCESS DOORS AND FRAMES

A. Flush Access Doors with Concealed Flanges :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Babcock-Davis.
 - b. Larsens Manufacturing Company.
 - c. Nystrom.
2. Description: Face of door flush with frame; with concealed flange for plaster installation and concealed hinge.
3. Optional Features: Piano hinges.
4. Metallic-Coated Steel Sheet for Door: Nominal 0.064 inch, 16 gage factory primed.
5. Frame Material: Same material and thickness as door.
6. Latch and Lock: Cam latch, screwdriver operated.

2.2 MATERIALS

- A. Metallic-Coated Steel Sheet: ASTM A653/A653M, Commercial Steel (CS), Type B; with minimum G60 or A60 metallic coating.
- B. Inserts, Bolts, and Anchor Fasteners: Hot-dip galvanized steel according to ASTM A153/A153M or ASTM F2329.

2.3 FABRICATION

- A. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.
- B. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish mounting holes, attachment devices and fasteners of type required to secure access doors to types of supports indicated.
- C. Latch and Lock Hardware:
 - 1. Quantity: Furnish number of latches and locks required to hold doors tightly closed.

2.4 FINISHES

- A. Painted Finishes: Comply with coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.
 - 1. Factory Primed: Apply manufacturer's standard, lead- and chromate-free, universal primer immediately after surface preparation and pretreatment.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with manufacturer's written instructions for installing access doors and frames.
- B. Adjust doors and hardware, after installation, for proper operation.

END OF SECTION

SECTION 083323 - OVERHEAD COILING DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Insulated service doors.

1.2 ACTION SUBMITTALS

A. Product Data: For each type and size of overhead coiling door and accessory.

1. Include construction details, material descriptions, dimensions of individual components, profiles for slats, and finishes.

B. Shop Drawings: For each installation and for special components not dimensioned or detailed in manufacturer's product data.

1. Include points of attachment and their corresponding static and dynamic loads imposed on structure.
2. Show locations of controls, locking devices, detectors or replaceable fusible links, and other accessories.
3. Include diagrams for power, signal, and control wiring.

C. Samples: For each exposed product and for each color and texture specified.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.4 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of doors that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Final Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.
- B. Structural Performance, Exterior Doors: Capable of withstanding the following design wind loads:
 - 1. Design Wind Load: As indicated on Drawings.
 - 2. Testing: According to ASTM E330/E330M or DASMA 108 for garage doors and complying with acceptance criteria of DASMA 108.
- C. Seismic Performance: Overhead coiling doors withstand the effects of earthquake motions determined according to ASCE/SEI 7.

2.2 DOOR ASSEMBLY

- A. Insulated Service Door: Overhead coiling door formed with curtain of interlocking metal slats.
- B. Operation Cycles: Door components and operators capable of operating for not less than 100,000.
- C. Insulated Door Curtain R-Value: 4.5 deg F x h x sq. ft./Btu.
- D. Door Curtain Material: Galvanized steel.
- E. Curtain Jamb Guides: Galvanized steel with exposed finish matching curtain slats.
- F. Hood: Match curtain material and finish.
 - 1. Mounting: As indicated on Drawings.
- G. Manual Door Operator: Manufacturer's standard crank operator.
- H. Curtain Accessories: Equip door with weatherseals push/pull handles pull-down strap pole hook.

2.3 HOODS

- A. General: Form sheet metal hood to entirely enclose coiled curtain and operating mechanism at opening head. Contour to fit end brackets to which hood is attached. Roll and reinforce top and bottom edges for stiffness. Form closed ends for surface-mounted hoods and fascia for any portion of between-jamb mounting that projects beyond wall face. Equip hood with intermediate support brackets as required to prevent sagging.

2.4 LOCKING DEVICES

- A. Locking Device Assembly: Fabricate with cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.
 - 1. Lock Cylinders: As specified in Section 087100 "Door Hardware" and keyed to building keying system.
 - 2. Keys: Three for each cylinder.

2.5 CURTAIN ACCESSORIES

- A. Weatherseals for Exterior Doors: Equip each exterior door with weather-stripping gaskets fitted to entire exterior perimeter of door for a weather-resistant installation unless otherwise indicated.
- B. Pole Hooks: Provide pole hooks and poles for doors more than 84 inches high.

2.6 MANUAL DOOR OPERATORS

- A. General: Equip door with manual door operator by door manufacturer.
- B. Crank Operator: Consisting of crank and crank gearbox, steel crank drive shaft, and gear-reduction unit, of type indicated. Size gears to require not more than 25-lbf force to turn crank. Fabricate gearbox to be oiltight and to completely enclose operating mechanism. Provide manufacturer's standard crank-locking device.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Install overhead coiling doors and operating equipment complete with necessary hardware, anchors, inserts, hangers, and equipment supports; according to manufacturer's written instructions and as specified.

3.2 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain overhead coiling doors.

END OF SECTION

SECTION 083513.13 - MULTIPANEL FOLDING ALUMINUM-FRAMED GLASS DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Multipanel folding aluminum-framed glass doors.

B. Related Requirements:

1. Section 012300 "Alternates" for multipanel folding aluminum-framed glass doors provided as an alternate.

1.2 ACTION SUBMITTALS

A. Product Data:

1. Multipanel folding aluminum-framed glass doors.

B. Shop Drawings:

1. Include plans, elevations, sections, and installation details.
2. Indicate dimensions, configuration of panels, and stacking layout.

C. Samples: For each multipanel folding aluminum-framed glass door and for each color specified.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An installer acceptable to multipanel folding aluminum-framed glass door manufacturer for installation of units required for this Project.

1.5 WARRANTY

A. Manufacturer's Special Warranty: Manufacturer agrees to repair or replace multipanel folding aluminum-framed glass doors that fail(s) in materials or workmanship within specified warranty period.

1. Warranty Period:

- a. Multipanel Folding Aluminum-Framed Glass Doors: 20 year(s) from date of Final Completion.
 - b. Insulating-Glass Units: 10 years from date of Final Completion.
 - c. Laminated Glass: Five years from date of Final Completion.
 - d. Aluminum Finish: 20 years from date of Final Completion.
- B. Special Finish Warranty, Anodized Finishes: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of anodized finishes within specified warranty period.
1. Warranty Period: 10 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. C.R. Laurence Co., Inc.; CRH Americas, Inc.
 2. Euro-Wall Systems, LLC.
 3. Nana Wall Systems, Inc.

2.2 PERFORMANCE REQUIREMENTS

- A. Product Standard: Comply with AAMA/WDMA/CSA 101/I.S.2/A440 for minimum standards of performance, materials, components, accessories, and fabrication unless more stringent requirements are indicated.
1. Product Certification: AAMA certified with label attached to each door.
- B. Performance Class and Grade: AAMA/WDMA/CSA 101/I.S.2/A440 as follows:
1. Minimum Performance Class: Class AW.
 2. Minimum Performance Grade: Grade 40 .

2.3 MULTIPANEL FOLDING ALUMINUM-FRAMED GLASS DOORS

- A. Multipanel Folding Aluminum-Framed Glass Doors: Provide extruded-aluminum-framed multipanel folding glass doors, complete with glazing, threshold, flashings, support, and anchorage devices.
1. Application: Interior, outward opening.
 2. Stack Storage Configuration: As shown on Drawings.

- B. Frames and Door Panels: Fabricated from aluminum extrusions complying with AAMA/WDMA/CSA 101/I.S.2/A440. Provide factory-assembled door panels that are reglazable without dismantling panel framing, and factory-assembled frames.

- 1. Door Panel Design: Narrow stile design, with 10-inch nominal height bottom rail.

2.4 GLAZING

- A. Glass and Glazing: Manufacturer's standard glazing system that produces weathertight seal. Comply with requirements indicated in Section 088000 "Glazing".

2.5 HARDWARE

- A. Provide manufacturer's standard hardware, fabricated from a corrosion-resistant material compatible with door panels and other components, and complying with AAMA 907. Provide hardware designed to smoothly operate, tightly close, and securely lock multipanel folding aluminum-framed glass doors. Size hardware to accommodate panel weights and dimensions. Provide full-perimeter weatherstripping for each door panel.

- B. Refer to Section 087100 "Door Hardware" for hardware for doors.

- C. Panel Support System: Provide panel support system designed for size, weight, and performance requirements of multipanel folding aluminum-framed glass doors indicated. Provide carriers with sealed ball bearings.

- 1. Overhead Supported: Provide multiwheeled overhead carriers suspended from steel or aluminum track, with lower guide system engaged in threshold for smooth operation. Limit track deflection to no more than 0.10 inch between supports when fully loaded.
 - 2. Adjustment: Provide panel support system capable of being adjusted for smooth operation and clearances without needing to remove panels from tracks.
 - 3. Threshold Configuration: Extruded-aluminum threshold with recessed flush profile.

- a. Aluminum Finish: To match panel.

- D. Panel Hinges: Stainless steel, multileaf hinge with painted finish to match exterior. Provide integral hangers and guides for hinges that engage panel support system.

2.6 |ACCESSORIES

- A. Trim: Provide interior and exterior casings, jamb extensions, and other components in material and finish to match door frames.

2.7 FABRICATION

- A. Complete fabrication, assembly, finishing, hardware application, and other work in the factory to greatest extent possible. Disassemble components only as necessary for shipment and installation.

2.8 GENERAL FINISH REQUIREMENTS

- A. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.9 ALUMINUM FINISHES

- A. Color Anodic Finish: AAMA 611, AA-M12C22A42/A44, Class I, 0.018 mm or thicker.
 - 1. Color: As selected by Architect from full range of industry colors and color densities.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with Drawings, Shop Drawings, and manufacturer's written instructions for installing multipanel folding aluminum-framed glass doors, hardware, accessories, and other components.
- B. Install multipanel folding aluminum-framed glass doors level, plumb, square, true to line; without distortion, warp, or rack of frames and panels, and without impeding thermal movement; anchored securely in place to structural support; and in proper relation to wall flashing, vapor retarders, air barriers, water/weather barriers, and other adjacent construction.
- C. Set threshold members in bed of sealant or with gaskets, as indicated, to provide weathertight construction.
- D. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials.

3.2 ADJUSTING

- A. Adjust hardware for proper alignment, smooth operation, and proper latching without unnecessary force or excessive clearance.

- B. Adjust hardware and operable panels to function smoothly, and lubricate as recommended by manufacturer.

END OF SECTION

SECTION 083800 - TRAFFIC DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Food Service Doors.
2. Hardware and accessories.

B. Related Requirements:

1. Section 081113 "Hollow Metal Doors and Frames" for frames for Traffic Doors.

1.2 ACTION SUBMITTALS

A. Product Data: Manufacturer's data sheets on each product to be used, including:

1. Preparation instructions and recommendations.
2. Storage and handling requirements and recommendations.
3. Installation methods.
4. Operation and maintenance data.

B. Shop Drawings: Show fabrication and installation details; include door elevations, head, jamb, and meeting stile details including full or partial gaskets.

1.3 DELIVERY, STORAGE, AND HANDLING

A. Store products in manufacturer's unopened packaging until ready for installation.

1.4 PROJECT CONDITIONS

A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

1.5 WARRANTY

A. Manufacturer's standard two-year warranty that products are free of defects in material and workmanship, guaranteeing to replace (exclusive of freight and labor) parts proven defective within two years after date of shipment to purchaser.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Subject to requirements, available manufacturer's that may be incorporated into the work include, but are not limited to, the following:

1. Carlson Traffic Doors
2. Chase Doors - A Seneca Company
3. Eliason Corporation
4. RubbAir Door - A Division of Eckel Industries

B. TRAFFIC DOORS

1. Traffic Doors: 1-5/16 inch High strength polymer cell core; 1-13/16 inch total thickness; light to medium duty.
2. Facing: Stainless Steel.
3. Window Size: 9 inches wide by 14 inches high.
4. Window Flush
5. Glazing: Clear acrylic.

2.2 HARDWARE AND ACCESSORIES

A. Hinges: Double Action Easy Swing(r) proprietary hinges.

1. Finish: Zinc coated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. Verify jambs plumb and square.
- C. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.2 PREPARATION

- A. Clean surfaces thoroughly prior to installation.

- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.3 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Reinforce hollow metal jambs at hardware locations.

3.4 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION

SECTION 084113 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Aluminum-framed storefront systems.
2. Aluminum-framed entrance door systems.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

B. Shop Drawings: For aluminum-framed entrances and storefronts. Include plans, elevations, sections, full-size details, and attachments to other work.

1. Show connection to and continuity with adjacent thermal, weather, air, and vapor barriers.
2. Include point-to-point wiring diagrams.

C. Samples: For each type of exposed finish required.

1.3 CLOSEOUT SUBMITTALS

A. Operation and maintenance data.

1.4 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of aluminum-framed entrances and storefronts that do not comply with requirements or that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Final Completion.

B. Special Finish Warranty, Anodized Finishes: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of anodized finishes within specified warranty period.

1. Warranty Period: 10 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. General Performance: Comply with performance requirements specified, as determined by testing of aluminum-framed entrances and storefronts representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.
1. Aluminum-framed entrances and storefronts shall withstand movements of supporting structure, including, but not limited to, twist, column shortening, long-term creep, and deflection from uniformly distributed and concentrated live loads.
 2. Failure also includes the following:
 - a. Thermal stresses transferring to building structure.
 - b. Glass breakage.
 - c. Noise or vibration created by wind and thermal and structural movements.
 - d. Loosening or weakening of fasteners, attachments, and other components.
 - e. Failure of operating units.
- B. Structural Loads:
1. Wind Loads: As indicated on Drawings.
 2. Other Design Loads: As indicated on Drawings.
- C. Deflection of Framing Members Supporting Glass: At design wind load, as follows:
1. Deflection Normal to Wall Plane: Limited to 1/175 of clear span for spans of up to 13 feet 6 inches and to 1/240 of clear span plus 1/4 inch for spans greater than 13 feet 6 inches.
 2. Deflection Parallel to Glazing Plane: Limited to amount not exceeding that which reduces glazing bite to less than 75 percent of design dimension and that which reduces edge clearance between framing members and glazing or other fixed components to less than 1/8 inch.
 - a. Operable Units: Provide a minimum 1/16-inch clearance between framing members and operable units.
 3. Cantilever Deflection: Limited to $2L/175$ at unsupported cantilevers.
- D. Structural: Test in accordance with ASTM E330/E330M as follows:
1. When tested at positive and negative wind-load design pressures, storefront assemblies, including entrance doors, do not evidence deflection exceeding specified limits.

2. When tested at 150 percent of positive and negative wind-load design pressures, storefront assemblies, including entrance doors and anchorage, do not evidence material failures, structural distress, or permanent deformation of main framing members exceeding 0.2 percent of span.
 3. Test Durations: As required by design wind velocity, but not less than 10 seconds.
- E. Water Penetration under Static Pressure: Test in accordance with ASTM E331 as follows:
1. No evidence of water penetration through fixed glazing and framing areas, including entrance doors, when tested in accordance with a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than 10 lbf/sq. ft..
- F. Energy Performance: Certified and labeled by manufacturer for energy performance as follows:
1. Thermal Transmittance (U-factor):
 - a. Fixed Glazing and Framing Areas: U-factor for the system of not more than 0.45 Btu/sq. ft. x h x deg F as determined in accordance with NFRC 100.
 - b. Entrance Doors: U-factor of not more than 0.83 Btu/sq. ft. x h x deg F as determined in accordance with NFRC 100.
 2. Solar Heat-Gain Coefficient (SHGC):
 - a. Fixed Glazing and Framing Areas: SHGC for the system of not more than 0.40 as determined in accordance with NFRC 200.
 - b. Entrance Doors: SHGC of not more than 0.40 as determined in accordance with NFRC 200.
 3. Air Leakage:
 - a. Fixed Glazing and Framing Areas: Air leakage for the system of not more than 0.06 cfm/sq. ft. at a static-air-pressure differential of 6.24 lbf/sq. ft. when tested in accordance with ASTM E283.
 - b. Entrance Doors: Air leakage of not more than 1.0 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft..
 4. Condensation Resistance Factor (CRF):
 - a. Fixed Glazing and Framing Areas: CRF for the system of not less than 55 as determined in accordance with AAMA 1503.
 - b. Entrance Doors: CRF of not less than 63 as determined in accordance with AAMA 1503.
- G. Thermal Movements: Allow for thermal movements resulting from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 STOREFRONT SYSTEMS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. EFCO Corporation.
 2. Kawneer North America, an Arconic company.
 3. U.S. Aluminum; a brand of C.R. Laurence.
 4. YKK AP America Inc.
- B. Framing Members: Manufacturer's extruded- or formed-aluminum framing members of thickness required and reinforced as required to support imposed loads.
 1. Exterior Framing Construction: Thermally broken.
 2. Glazing System: Retained mechanically with gaskets on four sides.
 3. Finish: Clear anodic finish.
 4. Fabrication Method: Field-fabricated stick system.
 5. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.
 6. Steel Reinforcement: As required by manufacturer.
- C. Backer Plates: Manufacturer's standard, continuous backer plates for framing members, if not integral, where framing abuts adjacent construction.
- D. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

2.3 ENTRANCE DOOR SYSTEMS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. EFCO Corporation.
 2. Kawneer North America, an Arconic company.
 3. U.S. Aluminum; a brand of C.R. Laurence.
 4. YKK AP America Inc.
- B. Entrance Doors: Manufacturer's standard glazed entrance doors for manual-swing or automatic operation.
 1. Door Construction: 1-3/4-inch overall thickness, with minimum 0.125-inch-thick, extruded-aluminum tubular rail and stile members. Mechanically fasten corners with reinforcing brackets that are deeply penetrated and fillet welded or that incorporate concealed tie rods.
 2. Door Design: As indicated.

3. Glazing Stops and Gaskets: Square, snap-on, extruded-aluminum stops and preformed gaskets.
 - a. Provide nonremovable glazing stops on outside of door.

2.4 ENTRANCE DOOR HARDWARE

2.5 GLAZING

- A. Glazing: Comply with Section 088000 "Glazing."

2.6 MATERIALS

- A. Sheet and Plate: ASTM B209.
- B. Extruded Bars, Rods, Profiles, and Tubes: ASTM B221.
- C. Structural Profiles: ASTM B308/B308M.
- D. Steel Reinforcement:
 1. Structural Shapes, Plates, and Bars: ASTM A36/A36M.
 2. Cold-Rolled Sheet and Strip: ASTM A1008/A1008M.
 3. Hot-Rolled Sheet and Strip: ASTM A1011/A1011M.
- E. Steel Reinforcement Primer: Manufacturer's standard zinc-rich, corrosion-resistant primer complying with SSPC-PS Guide No. 12.00; applied immediately after surface preparation and pretreatment. Select surface preparation methods in accordance with recommendations in SSPC-SP COM, and prepare surfaces in accordance with applicable SSPC standard.
- F. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- G. Recycled Content of Aluminum Components: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

2.7 FABRICATION

- A. Form or extrude aluminum shapes before finishing.
- B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.
- C. Fabricate components that, when assembled, have the following characteristics:
 1. Profiles that are sharp, straight, and free of defects or deformations.

2. Accurately fitted joints with ends coped or mitered.
 3. Physical and thermal isolation of glazing from framing members.
 4. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
 5. Provisions for field replacement of glazing from interior.
 6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.
- D. Mechanically Glazed Framing Members: Fabricate for flush glazing without projecting stops.
- E. Entrance Door Frames: Reinforce as required to support loads imposed by door operation and for installing entrance door hardware.
- F. Entrance Doors: Reinforce doors as required for installing entrance door hardware.
- G. Entrance Door Hardware Installation: Factory install entrance door hardware to the greatest extent possible. Cut, drill, and tap for factory-installed entrance door hardware before applying finishes.
- H. After fabrication, clearly mark components to identify their locations in Project in accordance with Shop Drawings.

2.8 ALUMINUM FINISHES

- A. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Comply with manufacturer's written instructions.
- B. Do not install damaged components.
- C. Fit joints to produce hairline joints free of burrs and distortion.
- D. Rigidly secure nonmovement joints.
- E. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration and to prevent impeding movement of moving joints.
- F. Seal perimeter and other joints watertight unless otherwise indicated.
- G. Metal Protection:
1. Where aluminum is in contact with dissimilar metals, protect against galvanic action by painting contact surfaces with materials recommended by manufacturer for this purpose or by installing nonconductive spacers.

2. Where aluminum is in contact with concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.
- H. Set continuous sill members and flashing in full sealant bed, as specified in Section 079200 "Joint Sealants," to produce weathertight installation.
 - I. Install joint filler behind sealant as recommended by sealant manufacturer.
 - J. Install components plumb and true in alignment with established lines and grades.
- 3.2 INSTALLATION OF GLAZING
- A. Install glazing as specified in Section 088000 "Glazing."
- 3.3 INSTALLATION OF ALUMINUM-FRAMED ENTRANCE DOORS
- A. Install entrance doors to produce smooth operation and tight fit at contact points.
 1. Exterior Doors: Install to produce weathertight enclosure and tight fit at weather stripping.
 2. Field-Installed Entrance Door Hardware: Install surface-mounted entrance door hardware in accordance with entrance door hardware manufacturers' written instructions using concealed fasteners to greatest extent possible.
- 3.4 FIELD QUALITY CONTROL
- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
 - B. Tests and Inspections: Perform the following test on representative areas of aluminum-framed entrances and storefronts.
 1. Water-Spray Test: Before installation of interior finishes has begun, areas designated by Architect shall be tested in accordance with AAMA 501.2 and shall not evidence water penetration.
 - a. Perform a minimum of two tests in areas as directed by Architect.
 2. Air Leakage: ASTM E783 at 1.5 times the rate specified for laboratory testing in "Performance Requirements" Article but not more than 0.09 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft..
 - a. Perform a minimum of two tests in areas as directed by Architect.
 3. Water Penetration: ASTM E1105 at a minimum uniform static-air-pressure differential of 0.67 times the static-air-pressure differential specified for laboratory testing in "Performance Requirements" Article, but not less than 6.24 lbf/sq. ft., and shall not evidence water penetration.

- C. Aluminum-framed entrances and storefronts will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

END OF SECTION

SECTION 087100 - DOOR HARDWARE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Mechanical door hardware for the following:
 - a. Swinging doors.
2. Cylinders for door hardware specified in other Sections.
3. Electrified door hardware.

B. Related Requirements:

1. Section 012300 "Alternates" for owner-preferred brands provided as an alternate.

1.2 PREINSTALLATION MEETINGS

- A. Keying Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For electrified door hardware.
 1. Include diagrams for power, signal, and control wiring.
 2. Include details of interface of electrified door hardware and building safety and security systems.
- C. Door hardware schedule.

1.4 INFORMATIONAL SUBMITTALS

- A. Sample warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance data.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: Supplier of products and an employer of workers trained and approved by product manufacturers and of an Architectural Hardware Consultant who is available during the course of the Work to consult Contractor, Architect, and Owner about door hardware and keying.
1. Scheduling Responsibility: Preparation of door hardware and keying schedule.
 2. Engineering Responsibility: Preparation of data for electrified door hardware, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
- B. Architectural Hardware Consultant Qualifications: A person who is experienced in providing consulting services for door hardware installations that are comparable in material, design, and extent to that indicated for this Project and who is currently certified by DHI as an Architectural Hardware Consultant (AHC).

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period.
1. Warranty Period: Three years from date of Final Completion unless otherwise indicated below:
 - a. Exit Devices: Two years from date of Final Completion.
 - b. Manual Closers: 10 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrified Door Hardware: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Means of Egress Doors: Latches do not require more than 15 lbf to release the latch. Locks do not require use of a key, tool, or special knowledge for operation.
- C. Accessibility Requirements: For door hardware on doors in an accessible route, comply with the USDOJ's "2010 ADA Standards for Accessible Design".

2.2 HINGES

- A. Hinges: BHMA A156.1.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Allegion plc.
- b. McKinney Products Company; an ASSA ABLOY Group company.
- c. Stanley Commercial Hardware; a division of Stanley Security Solutions.

2.3 CONTINUOUS HINGES

- A. Continuous, Gear-Type Hinges: Extruded-aluminum, pinless, geared hinge leaves joined by a continuous extruded-aluminum channel cap; with concealed, self-lubricating thrust bearings.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allegion plc.
 - b. McKinney Products Company; an ASSA ABLOY Group company.
 - c. Stanley Commercial Hardware; a division of Stanley Security Solutions.

2.4 MECHANICAL LOCKS AND LATCHES

- A. Lock Functions: As indicated in door hardware schedule.
- B. Lock Throw: Comply with testing requirements for length of bolts required for labeled fire doors, and as follows:
 1. Mortise Locks: Minimum 3/4-inch latchbolt throw.
 2. Deadbolts: Minimum 1-inch bolt throw.
- C. Lock Backset: 2-3/4 inches unless otherwise indicated.
- D. Lock Trim:
 1. Description: Insert description or manufacturer's design designation.
 2. Levers: Wrought.
 3. Escutcheons (Roses): Cast.
 4. Dummy Trim: Match lever lock trim and escutcheons.
- E. Strikes: Provide manufacturer's standard strike for each lock bolt or latchbolt complying with requirements indicated for applicable lock or latch and with strike box and curved lip extended to protect frame; finished to match lock or latch.
 1. Flat-Lip Strikes: For locks with three-piece antifriction latchbolts, as recommended by manufacturer.
- F. Mortise Locks: BHMA A156.13; Operational Grade 1; stamped steel case with steel or brass parts; Series 1000.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allegion plc.

- b. Corbin Russwin, Inc.; an ASSA ABLOY Group company.
- c. Stanley Commercial Hardware; a division of Stanley Security Solutions.

2.5 EXIT DEVICES AND AUXILIARY ITEMS

A. Exit Devices and Auxiliary Items: BHMA A156.3.

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allegion plc.
 - b. Corbin Russwin, Inc.; an ASSA ABLOY Group company.
 - c. Stanley Commercial Hardware; a division of Stanley Security Solutions.

2.6 LOCK CYLINDERS

A. Lock Cylinders: Tumbler type, constructed from brass or bronze, stainless steel, or nickel silver.

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASSA, Inc.
 - b. Best Access Systems; Stanley Security Solutions, Inc.
 - c. PAMEX Inc.

B. Standard Lock Cylinders: BHMA A156.5; Grade 1 permanent cores; face finished to match lockset.

- 1. Core Type: Small Format, Interchangeable, 7-pin.

C. Construction Cores: Provide construction cores that are replaceable by permanent cores. Provide 10 construction master keys.

2.7 KEYING

A. Keys: Nickel silver.

- 1. Stamping: Permanently inscribe each key with a visual key control number and include the following notation:
 - a. Notation: "DO NOT DUPLICATE."

2.8 OPERATING TRIM

A. Operating Trim: BHMA A156.6; stainless steel unless otherwise indicated.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Burns Manufacturing Incorporated.
 - b. INOX by Unison Hardware, Inc.
 - c. Rockwood Manufacturing Company; an ASSA ABLOY Group company.
 - d. Trimco.

2.9 SURFACE CLOSERS

- A. Surface Closers: BHMA A156.4; rack-and-pinion hydraulic type with adjustable sweep and latch speeds controlled by key-operated valves and forged-steel main arm. Comply with manufacturer's written instructions for size of door closers depending on size of door, exposure to weather, and anticipated frequency of use. Provide factory-sized closers, adjustable to meet field conditions and requirements for opening force.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allegion plc.
 - b. Corbin Russwin, Inc.; an ASSA ABLOY Group company.
 - c. Stanley Commercial Hardware; a division of Stanley Security Solutions.

2.10 MECHANICAL STOPS AND HOLDERS

- A. Wall- and Floor-Mounted Stops: BHMA A156.16.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allegion plc.
 - b. Rockwood Manufacturing Company; an ASSA ABLOY Group company.
 - c. Trimco.

2.11 DOOR GASKETING

- A. Door Gasketing: BHMA A156.22; with resilient or flexible seal strips that are easily replaceable and readily available from stocks maintained by manufacturer.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Hager Companies.
 - b. National Guard Products, Inc.
 - c. Pemko; an ASSA ABLOY Group Company.

- B. Maximum Air Leakage: When tested in accordance with ASTM E283 with tested pressure differential of 0.3-inch wg, as follows:

1. Gasketing on Single Doors: 0.3 cfm/sq. ft. of door opening.
2. Gasketing on Double Doors: 0.50 cfm per ft. of door opening.

2.12 THRESHOLDS

- A. Thresholds: BHMA A156.21; fabricated to full width of opening indicated.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. National Guard Products, Inc.
 - b. Pemko; an ASSA ABLOY Group Company.
 - c. Zero International; an Allegion brand.

2.13 METAL PROTECTIVE TRIM UNITS

- A. Metal Protective Trim Units: BHMA A156.6; fabricated from 0.050-inch- thick stainless steel; with manufacturer's standard machine or self-tapping screw fasteners.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allegion plc.
 - b. Rockwood Manufacturing Company; an ASSA ABLOY Group company.
 - c. Trimco.

2.14 FINISHES

- A. Provide finishes complying with BHMA A156.18 as indicated in door hardware schedule.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Mounting Heights: Mount door hardware units at heights to comply with the following unless otherwise indicated or required to comply with governing regulations.
1. Custom Steel Doors and Frames: HMMA 831.
 2. Wood Doors: DHI's "Recommended Locations for Architectural Hardware for Wood Flush Doors."
- B. Install each door hardware item to comply with manufacturer's written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing work. Do not install surface-mounted items until finishes have been completed on substrates involved.

- C. Hinges: Install types and in quantities indicated in door hardware schedule, but not fewer than the number recommended by manufacturer for application indicated or one hinge for every 30 inches of door height, whichever is more stringent, unless other equivalent means of support for door, such as spring hinges or pivots, are provided.
- D. Lock Cylinders: Install construction cores to secure building and areas during construction period.
 - 1. Furnish permanent cores to Owner for installation.
- E. Boxed Power Supplies: Locate power supplies as indicated or, if not indicated, above accessible ceilings. Verify location with Architect.
 - 1. Configuration: Provide least number of power supplies required to adequately serve doors with electrified door hardware.
- F. Thresholds: Set thresholds for exterior doors and other doors indicated in full bed of sealant complying with requirements specified in Section 079200 "Joint Sealants."
- G. Perimeter Gasketing: Apply to head and jamb, forming seal between door and frame.
 - 1. Do not notch perimeter gasketing to install other surface-applied hardware.
- H. Door Bottoms: Apply to bottom of door, forming seal with threshold when door is closed.

3.2 ADJUSTING

- A. Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.

3.3 DOOR HARDWARE SCHEDULE

A. Hardware Set 1: Each door to have the following:				
2	Gear Hinge	Ives	114XY	CLR
1	Power Transfer	Von Duprin	EPT10	CLR
1	Exit Device	Von Duprin	QEL-LX-RX-99-27-LNL	626
1	Exit Device	Von Duprin	LX-RX-99-27-NL	626
1	Keyed-Removable Mullion	Von Duprin	KR5654	Match Storefront
1	Cylinder	Von Duprin	CYL	626
2	Core	Best		626
1	Power Supply	Von Duprin	PS902	-
2	Closer	LCN	4040XP-72MC	689
2	Door Bottom	Pemko	3452	C

2	Rain Drip	Pemko	346	C
1	Threshold	Pemko	1700	A
1	Door Seals	Pemko	PK52	BL
2	Door Stop	Rockwood	471 x EXP	626

B. Hardware Set 2A: Each door to have the following:

2	Hinge	Ives	5BB1 NRP	626
1	Electric Hinge	Ives	5BB1 NRP TW12	626
1	Exit Device	Von Duprin	QEL-LX-RX-99-27-LNL	626
1	Cylinder	Von Duprin	CYL	626
1	Core	Best		626
1	Closer	LCN	4040XP-72MC	689
1	Door Bottom	Pemko	3452	C
1	Rain Drip	Pemko	346	C
1	Threshold	Pemko	1700	A
1	Door Seals	Pemko	PK52	BL
1	Door Stop	Rockwood	471 x EXP	626

C. Hardware Set 2B: Each door to have the following:

2	Hinge	Ives	5BB1 NRP	626
1	Electric Hinge	Ives	5BB1 NRP TW12	626
1	Exit Device	Von Duprin	LD-99-27-LNL	626
1	Cylinder	Von Duprin	CYL	626
1	Core	Best		626
1	Closer	LCN	4040XP-72MC	689
1	Door Bottom	Pemko	3452	C
1	Rain Drip	Pemko	346	C
1	Threshold	Pemko	1700	A
1	Door Seals	Pemko	PK52	BL
1	Door Stop	Rockwood	471 x EXP	626

D. Hardware Set 3: Each door to have the following:

3	Hinge	Ives	5BB1 NRP	626
1	Exit Device	Von Duprin	99-27-L	626
1	Cylinder	Von DUprin	CYL	626
1	Core	Best		626
1	Closer	LCN	4040XP-72MC	689
1	Door Stop	Rockwood	446	626

Hardware applies for moveable wall alternate and base bid doors

E. Hardware Set 4: Each door to have the following:

2	Hinge	Ives	5BB1 NRP	626
1	Electric Hinge	Ives	5BB1 NRP TW12	626
1	Storeroom Set	Best	45HW-7-D-E-U	626
1	Cylinder	Best		626

1	Core	Best		626
1	Closer	LCN	4040XP-72MC	689
1	Door Bottom	Pemko	3452	C
1	Rain Drip	Pemko	346	C
1	Threshold	Pemko	1700	A
1	Door Seals	Pemko	PK52	BL
1	Door Stop	Rockwood	471 x EXP	626

F. Hardware Set 5: Each door to have the following:

3	Hinge	Ives	5BB1 NRP	626
1	Office Set	Best	45H-7-A-3-S	626
1	Cylinder	Best		626
1	Core	Best		626
1	Door Stop	Rockwood	426 or 446	626

G. Hardware Set 6: Each door to have the following:

3	Hinge	Ives	5BB1 NRP	626
1	Office Set	Best	45H-7-AT-3-S	626
1	Cylinder	Best		626
1	Core	Best		626
1	Door Stop	Rockwood	426	626

H. Hardware Set 7: Each door to have the following:

3	Hinge	Ives	5BB1 NRP	626
1	Passage Set	Best	45H-7-N-3-S	626
1	Door Stop	Rockwood	446	626
1	Threshold	Pemko	1700	A
1	Door Bottom	Pemko	3452	C

I. Hardware Set 8: Each door to have the following:

3	Hinge	Ives	5BB1 NRP	626
1	Door Push/Pull	Rockwood	111-73C/73CL	630
1	Closer	LCN	4040XP-72MC	689
2	Kick Plate	Rockwood	K1062-8" x CSK	626
1	Door Stop	Rockwood	426	626

J. Hardware Set 9: Each door to have the following:

3	Hinge	Ives	5BB1 NRP	626
1	Storeroom Set	Best	45H-7-D-3-S	626
1	Cylinder	Best		626
1	Core	Best		626
2	Kick Plate	Rockwood	K1062-36" x CSK	626
1	Door Stop	Rockwood	426	626

K. Hardware Set 10: Each door to have the following:

6	Hinge	Ives	5BB1 NRP	626
---	-------	------	----------	-----

1	Storeroom Set	Best	45H-7-D-3-S	626
1	Cylinder	Best		626
1	Core	Best		626
1	Door Stop	Rockwood	426	626

L. Hardware Set 11: Each door to have the following:

3	Hinge	Ives	5BB1 NRP	626
1	Office Set	Best	45H-7-AT-3-S-VIN	626
1	Cylinder	Best		626
1	Core	Best		626
2	Flush Bolt	Ives	FB 458	
1	Dust Proof Strike	Ives	DP1	626
2	Kick Plate	Rockwood	K1062-8" x CSK	626
2	Door Stop	Rockwood	426	626

END OF SECTION 087100

SECTION 088000 - GLAZING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Glass products.
2. Insulating glass.
3. Glazing sealants.
4. Miscellaneous glazing materials.

1.2 COORDINATION

- A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances to achieve proper safety margins for glazing retention under each design load case, load case combination, and service condition.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Glass Samples: For each type of glass product other than clear monolithic vision glass; 12 inches square.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Certificates: For glass.
- B. Product test reports.
- C. Sample warranties.

1.5 QUALITY ASSURANCE

- A. Sealant Testing Agency Qualifications: An independent testing agency qualified according to ASTM C1021 to conduct the testing indicated.

1.6 WARRANTY

- A. Manufacturer's Special Warranty for Coated-Glass Products: Manufacturer agrees to replace coated-glass units that deteriorate within specified warranty period. Deterioration of coated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning coated glass contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in coating.
1. Warranty Period: 10 years from date of Final Completion.
- B. Manufacturer's Special Warranty for Laminated Glass: Manufacturer agrees to replace laminated-glass units that deteriorate within specified warranty period. Deterioration of laminated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning laminated glass contrary to manufacturer's written instructions. Defects include edge separation, delamination materially obstructing vision through glass, and blemishes exceeding those allowed by referenced laminated-glass standard.
1. Warranty Period: 10 years from date of Final Completion.
- C. Manufacturer's Special Warranty for Insulating Glass: Manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period. Deterioration of insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is obstruction of vision by dust, moisture, or film on interior surfaces of glass.
1. Warranty Period: 10 years from date of Final Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Glazing shall withstand the following design loads within limits and under conditions indicated determined in accordance with the IBC and ASTM E1300:
1. Design Snow Loads: As indicated on Drawings.
 2. Thermal Loads: Design glazing to resist thermal stress breakage induced by differential temperature conditions and limited air circulation within individual glass lites and insulated glazing units.
- B. Safety Glazing: Where safety glazing is indicated, provide glazing that complies with 16 CFR 1201, Category II.

- C. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:
1. U-Factors: Center-of-glazing values, in accordance with NFRC 100 and based on most current non-beta version of LBL's WINDOW computer program, expressed as Btu/sq. ft. x h x deg F.
 2. SHGC and Visible Transmittance: Center-of-glazing values, in accordance with NFRC 200 and based on most current non-beta version of LBL's WINDOW computer program.
 3. Visible Reflectance: Center-of-glazing values, in accordance with NFRC 300.

2.2 GLASS PRODUCTS, GENERAL

- A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.
1. NGA Publications: "Laminated Glazing Reference Manual" and "Glazing Manual."
 2. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."
- B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction or manufacturer. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.
- C. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass that complies with performance requirements and is not less than thickness indicated.
- D. Strength: Where annealed float glass is indicated, provide annealed float glass, heat-strengthened float glass, or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened float glass is indicated, provide heat-strengthened float glass or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where fully tempered float glass is indicated, provide fully tempered float glass.

2.3 GLASS PRODUCTS

- A. Clear Annealed Float Glass: ASTM C1036, Type I, Class 1 (clear), Quality-Q3.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. AGC Glass Company North America, Inc.
 - b. Cardinal Glass Industries.
 - c. Guardian Glass; SunGuard.
 - d. Pilkington North America.
 - e. Vitro Architectural Glass.
- B. Fully Tempered Float Glass: ASTM C1048, Kind FT (fully tempered), Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.
- C. Reflective- and Low-E-Coated Vision Glass: ASTM C1376.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cardinal Glass Industries.
 - b. Guardian Glass; SunGuard.
 - c. Pilkington North America.
 - d. Viracon, Inc.
 - e. Vitro Architectural Glass.

2.4 INSULATING GLASS

- A. Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified in accordance with ASTM E2190.
1. Sealing System: Dual seal, with manufacturer's standard primary and secondary sealants.
 2. Perimeter Spacer: Manufacturer's standard spacer material and construction .
 - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1) Thermix; a brand of Ensinger USA.
 3. Desiccant: Molecular sieve or silica gel, or a blend of both.

2.5 GLAZING SEALANTS

- A. General:
1. Compatibility: Compatible with one another and with other materials they contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.

2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.

- B. Neutral-Curing Silicone Glazing Sealant, Class 100/50: Complying with ASTM C920, Type S, Grade NS, Use NT.

2.6 GLAZING TAPES

- A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C1281 and AAMA 800 for products indicated below:

1. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
2. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

2.7 MISCELLANEOUS GLAZING MATERIALS

- A. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

- B. Setting Blocks:

1. Silicone with Shore A durometer hardness of 85, plus or minus 5.
2. Type recommended in writing by sealant or glass manufacturer.

- C. Spacers:

1. Neoprene blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.
2. Type recommended in writing by sealant or glass manufacturer.

- D. Edge Blocks:

1. Silicone with Shore A durometer hardness per manufacturer's written instructions.
2. Type recommended in writing by sealant or glass manufacturer.

- E. Cylindrical Glazing Sealant Backing: ASTM C1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

PART 3 - EXECUTION

3.1 GLAZING, GENERAL

- A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.
- B. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass includes glass with edge damage or other imperfections that, when installed, could weaken glass, impair performance, or impair appearance.
- C. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.
- D. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.
- E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- F. Provide spacers for glass lites where length plus width is larger than 50 inches.
- G. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and in accordance with requirements in referenced glazing publications.

3.2 GASKET GLAZING (DRY)

- A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.
- B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.
- C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.

- D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.
- E. Install gaskets so they protrude past face of glazing stops.

3.3 CLEANING AND PROTECTION

- A. Immediately after installation, remove nonpermanent labels and clean surfaces.
- B. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.
 - 1. If, despite such protection, contaminating substances do contact with glass, remove substances immediately as recommended in writing by glass manufacturer. Remove and replace glass that cannot be cleaned without damage to coatings.
- C. Remove and replace glass that is damaged during construction period.

3.4 MONOLITHIC GLASS SCHEDULE

- A. Clear Glass Type (G-1): Annealed Fully tempered float glass.
 - 1. Minimum Thickness: 6 mm.
 - 2. Safety glazing required.

3.5 INSULATING GLASS SCHEDULE

- A. Low-E-Coated, Clear Insulating Glass Type (G-2):
 - 1. Basis of Design: Guardian Sungard SNE50 on Clear
 - 2. Overall Unit Thickness: 1 inch.
 - 3. Minimum Thickness of Each Glass Lite: 6 mm.
 - 4. Outdoor Lite: Annealed Fully tempered float glass.
 - 5. Interspace Content: Argon.
 - 6. Indoor Lite: Fully tempered float glass.
 - 7. Low-E Coating: Pyrolytic on second surface.
 - 8. Safety glazing required.

END OF SECTION

SECTION 089119 - FIXED LOUVERS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes fixed extruded-aluminum louvers.
 - 1. Fixed formed-metal acoustical louvers.
 - 2. Blank-off panels for louvers

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. For louvers specified to bear AMCA seal, include printed catalog pages showing specified models with appropriate AMCA Certified Ratings Seals.
- B. Shop Drawings: For louvers and accessories. Include plans, elevations, sections, details, and attachments to other work. Show frame profiles and blade profiles, angles, and spacing.
- C. Samples: For each type of metal finish required.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Louvers withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated without permanent deformation of louver components, noise or metal fatigue caused by louver-blade rattle or flutter, or permanent damage to fasteners and anchors. Wind pressures are considered to act normal to the face of the building.
 - 1. Wind Loads:
 - a. Determine loads based on pressures as indicated on Drawings.
- B. Louver Performance Ratings: Provide louvers complying with requirements specified, as demonstrated by testing manufacturer's stock units identical to those provided, except for length and width in accordance with AMCA 500-L.

2.2 FIXED EXTRUDED-ALUMINUM LOUVERS

- A. Horizontal Drainable-Blade Louver, Extruded Aluminum:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Airolite Company, LLC (The).
 - b. American Warming and Ventilating; a Mestek Architectural Group company.
 - c. Greenheck Fan Corporation.
 - d. Ruskin Company.
2. Louver Depth: 4 inches.
3. Frame and Blade Nominal Thickness: Not less than 0.080 inch.
4. Mullion Type: Exposed.

2.3 MATERIALS

- A. Aluminum Extrusions: ASTM B221, Alloy 6063-T5, T-52, or T6.
- B. Aluminum Sheet: ASTM B209, Alloy 3003 or 5005, with temper as required for forming, or as otherwise recommended by metal producer for required finish.
- C. Fasteners: Use types and sizes to suit unit installation conditions.
 1. Use tamper-resistant screws for exposed fasteners unless otherwise indicated.
 2. For fastening aluminum, use aluminum or 300 series stainless steel fasteners.
 3. For color-finished louvers, use fasteners with heads that match color of louvers.
- D. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D1187/D1187M.

2.4 FABRICATION

- A. Fabricate frames, including integral sills, to fit in openings of sizes indicated, with allowances made for fabrication and installation tolerances, adjoining material tolerances, and perimeter sealant joints.

2.5 ALUMINUM FINISHES

- A. High-Performance Organic Finish, Two-Coat PVDF: Fluoropolymer finish complying with AAMA 2604 and containing not less than 50 percent PVDF resin by weight in color coat.
 1. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions [for seacoast and severe environments].
 2. Color and Gloss: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Locate and place louvers level, plumb, and at indicated alignment with adjacent work.
- B. Use concealed anchorages where possible. Provide brass or lead washers fitted to screws where required to protect metal surfaces and to make a weathertight connection.
- C. Provide perimeter reveals and openings of uniform width for sealants and joint fillers, as indicated.
- D. Protect unpainted galvanized- and nonferrous-metal surfaces that are in contact with concrete, masonry, or dissimilar metals from corrosion and galvanic action by applying a heavy coating of bituminous paint or by separating surfaces with waterproof gaskets or nonmetallic flashing.

3.2 ADJUSTING

- A. Restore louvers damaged during installation and construction, so no evidence remains of corrective work. If results of restoration are unsuccessful, as determined by Architect, remove damaged units and replace with new units.

END OF SECTION

SECTION 092216 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Non-load-bearing steel framing systems for interior partitions.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Sustainable Design Submittals:

1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

1.3 QUALITY ASSURANCE

- A. Code-Compliance Certification of Studs and Tracks: Provide documentation that framing members are certified according to the product-certification program of the Certified Steel Stud Association the Steel Framing Industry Association the Steel Stud Manufacturers Association or the Supreme Steel Framing System Association.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings, according to ASTM E90 and classified according to ASTM E413 by an independent testing agency.

2.2 FRAMING SYSTEMS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Framing Members, General: Comply with ASTM C645 for conditions indicated.
 1. Steel Sheet Components: Comply with ASTM C645 requirements for metal unless otherwise indicated

2. Protective Coating: Comply with ASTM C645; ASTM A653/A653M, G40; or coating with equivalent corrosion resistance. Galvannealed products are unacceptable.
 - a. Coating demonstrates equivalent corrosion resistance with an evaluation report acceptable to authorities having jurisdiction.
- C. Studs and Track: ASTM C645.
 1. Minimum Base-Steel Thickness: As required by performance requirements for horizontal deflection.
 2. Depth: As indicated on Drawings.
- D. Slip-Type Head Joints: Where indicated, provide one of the following:
 1. Clip System: Clips designed for use in head-of-wall deflection conditions that provide a positive attachment of studs to tracks while allowing 2-inch minimum vertical movement.
 2. Single Long-Leg Track System: ASTM C645 top track with 2-inch- deep flanges in thickness not less than indicated for studs, installed with studs friction fit into top track and with continuous bridging located within 12 inches of the top of studs to provide lateral bracing.
 3. Double-Track System: ASTM C645 top outer tracks, inside track with 2-inch-deep flanges in thickness not less than indicated for studs and fastened to studs, and outer track sized to friction-fit over inner track.
 4. Deflection Track: Steel sheet top track manufactured to prevent cracking of finishes applied to interior partition framing resulting from deflection of structure above; in thickness not less than indicated for studs and in width to accommodate depth of studs.
- E. Hat-Shaped, Rigid Furring Channels: ASTM C645.
 1. Minimum Base-Steel Thickness: 0.0179 inch.
 2. Depth: 7/8 inch.
- F. Z-Shaped Furring: With slotted or nonslotted web, face flange of 1-1/4 inches, wall attachment flange of 7/8 inch, minimum uncoated-steel thickness of 0.0179 inch, and depth required to fit insulation thickness indicated. Provide G-60 coating on exterior applications.

2.3 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards.
 1. Fasteners for Steel Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.
- B. Isolation Strip at Exterior Walls: Provide the following:

1. Asphalt-Saturated Organic Felt: ASTM D226/D226M, Type I (No. 15 asphalt felt), nonperforated.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Installation Standard: ASTM C754.
 1. Gypsum Board Assemblies: Also comply with requirements in ASTM C840 that apply to framing installation.
- B. Install framing and accessories plumb, square, and true to line, with connections securely fastened.
- C. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
- D. Install bracing at terminations in assemblies.
- E. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

3.2 INSTALLING FRAMED ASSEMBLIES

- A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
- B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.
- C. Install studs so flanges within framing system point in same direction.
- D. Install tracks at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.
 1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
 2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install track section (for cripple studs) at head and secure to jamb studs.
 - a. Install two studs at each jamb unless otherwise indicated.
 - b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch clearance from jamb stud to allow for installation of control joint in finished assembly.

- c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.
 3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
 4. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.
- E. Z-Shaped Furring Members:
 1. Erect insulation, specified in Section 072100 "Thermal Insulation," vertically and hold in place with Z-shaped furring members spaced 48 inches o.c.
 2. Except at exterior corners, securely attach narrow flanges of furring members to wall with concrete stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches o.c.
 3. At exterior corners, attach wide flange of furring members to wall with short flange extending beyond corner; on adjacent wall surface, screw-attach short flange of furring channel to web of attached channel. At interior corners, space second member no more than 12 inches from corner and cut insulation to fit.
- F. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch from the plane formed by faces of adjacent framing.

END OF SECTION

SECTION 092400 - CEMENT PLASTERING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Metal lath.
 - 2. Accessories.
 - 3. Base-coat cement plaster.
 - 4. Cement plaster finish coats.

1.2 ACTION SUBMITTALS

- A. Product data.
- B. Samples: For each type of factory-prepared finish coat and for each color and finish texture specified.

PART 2 - PRODUCTS

2.1 METAL LATH

- A. Expanded Metal Lath: ASTM C847; cold-rolled carbon steel sheet, hot-dip galvanized with ASTM A653/A653M G60 zinc coating.
 - 1. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
 - 2. Flat Diamond-Mesh Lath: 2.5 lb/sq. yd..
 - a. Water-Resistive Barrier: Vapor-permeable paper, factory bonded to back of lath; complying with requirements in FS UU-B-790a for Type I, Grade D and with 10-minute water resistance.
 - 1) Provide water-resistive barrier at exterior locations.

2.2 ACCESSORIES

- A. Metal Accessories:
 - 1. Control Joints: Fabricated from zinc; one-piece-type, folded pair of unperforated screeds in M-shaped configuration; with perforated flanges and removable protective tape on exposed face of control joint.

2. Soffit Vent: Fabricated from zinc, three-piece-type, with reinforcing ribs and perforated flanges. Maximum perforation diameter of 3 mm.

2.3 BASE-COAT CEMENT PLASTER

- A. General: Comply with requirements in ASTM C926 for applications indicated.
 1. Aggregate:
 - a. Sand: Use unless otherwise indicated.
- B. Base-Coat Mixes for Use over Metal Lath: Scratch and brown coats for three-coat plasterwork as follows:
 1. Portland Cement Mixes:
 - a. Scratch Coat: For cementitious material, mix 1 part portland cement and 0 to 3/4 parts lime. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
 - b. Brown Coat: For cementitious material, mix 1 part portland cement and 0 to 3/4 parts lime. Use 3 to 5 parts aggregate per part of cementitious material, but not less than volume of aggregate used in scratch coat.

2.4 CEMENT PLASTER FINISH COATS

- A. Job-Mixed Finish-Coat Mix: Comply with requirements in ASTM C926.
 1. Aggregates:
 - a. Sand: Use over base coats containing sand.
 2. Portland Cement Mix: For cementitious material, mix 1 part portland cement and 3/4 to 1-1/2 parts lime. Use 1-1/2 to 3 parts aggregate per part of cementitious material.

2.5 PLASTER MATERIALS

- A. Portland Cement: ASTM C150/C150M, Type I.
 1. Color for Finish Coats: White.
- B. Sand Aggregate: ASTM C897.
 1. Color for Job-Mixed Finish Coats: White.

2.6 MISCELLANEOUS MATERIALS

- A. Water for Mixing and Finishing Plaster: Potable and free of substances capable of affecting plaster set or of damaging plaster, lath, or accessories.
- B. Bonding Compound: ASTM C932.
- C. Fasteners for Attaching Metal Lath to Substrates: ASTM C1063.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Acoustical Sealant: Where indicated on Drawings, seal joints between edges of plasterwork and abutting construction with acoustical sealant.

3.2 INSTALLATION OF METAL LATH

- A. Metal Lath: Install in accordance with ASTM C1063.

3.3 INSTALLATION OF ACCESSORIES

- A. Install in accordance with ASTM C1063 and at locations indicated on Drawings.
- B. Control Joints: Locate as indicated on Drawings.

3.4 APPLICATION OF BASE-COAT CEMENT PLASTER

- A. General: Comply with ASTM C926.
- B. Ceiling/Horizontal Base Coats:
 - 1. Three-Coat Plasterwork Over Metal Lath: Install base-coat mixes for use over metal lath to produce scratch and brown coats with 1/2-inch total thickness.

3.5 APPLICATION OF CEMENT PLASTER FINISH COATS

- A. General: Comply with ASTM C926.

3.6 REPAIR

- A. Repair or replace work to eliminate cracks, dents, blisters, buckles, crazing and check cracking, dry outs, efflorescence, sweat outs, and similar defects and where bond to substrate has failed.

END OF SECTION

SECTION 092900 - GYPSUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.
2. Exterior gypsum board for ceilings and soffits.
3. Tile backing panels.

1.2 ACTION SUBMITTALS

A. Product data.

1. Gypsum board, Type X.
2. Exterior gypsum soffit board.
3. Cementitious backer units.
4. Interior trim.
5. Exterior trim.
6. Joint treatment materials.
7. Sound-attenuation blankets.
8. Acoustical sealant.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E90 and classified according to ASTM E413 by an independent testing agency.

2.2 GYPSUM BOARD, GENERAL

- A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

2.3 INTERIOR GYPSUM BOARD

- A. Gypsum Board, Type X: ASTM C1396/C1396M.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. American Gypsum.
 - b. Georgia-Pacific Gypsum LLC.
 - c. National Gypsum Company.
 - d. USG Corporation.
2. Thickness: 5/8 inch.
 3. Long Edges: Tapered and featured (rounded or beveled) for prefilling.

2.4 EXTERIOR GYPSUM BOARD FOR CEILINGS AND SOFFITS

- A. Exterior Gypsum Soffit Board: ASTM C1396/C1396M, with manufacturer's standard edges.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. American Gypsum.
 - b. Georgia-Pacific Gypsum LLC.
 - c. PABCO Gypsum.
 - d. USG Corporation.
 2. Core: 5/8 inch, Type X.

2.5 TILE BACKING PANELS

- A. Cementitious Backer Units: ANSI A118.9 and ASTM C1288 or ASTM C1325, with manufacturer's standard edges.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. C-Cure.
 - b. National Gypsum Company.
 - c. USG Corporation.
 2. Thickness: 5/8 inch.
 3. Mold Resistance: ASTM D3273, score of 10 as rated according to ASTM D3274.

2.6 TRIM ACCESSORIES

- A. Interior Trim: ASTM C1047.
1. Material: Paper-faced galvanized-steel sheet.
 2. Shapes:
 - a. Cornerbead.
 - b. Expansion (control) joint.

- B. Exterior Trim: ASTM C1047.
 - 1. Material: Hot-dip galvanized-steel sheet, plastic, or rolled zinc.
 - 2. Shapes:
 - a. Cornerbead.
 - b. Expansion (Control) Joint: One-piece, rolled zinc with V-shaped slot and removable strip covering slot opening.

2.7 JOINT TREATMENT MATERIALS

- A. General: Comply with ASTM C475/C475M.
- B. Joint Tape:
 - 1. Interior Gypsum Board: Paper.
 - 2. Exterior Gypsum Soffit Board: Paper.
 - 3. Tile Backing Panels: As recommended by panel manufacturer.
- C. Joint Compound for Interior Gypsum Board: For each coat, use formulation that is compatible with other compounds applied on previous or for successive coats.
 - 1. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use setting-type taping compound.
 - a. Use setting-type compound for installing paper-faced metal trim accessories.
 - 2. Fill Coat: For second coat, use setting-type, sandable topping compound.
 - 3. Finish Coat: For third coat, use drying-type, all-purpose compound.
 - 4. Skim Coat: For final coat of Level 5 finish, use drying-type, all-purpose compound.
- D. Joint Compound for Exterior Applications:
 - 1. Exterior Gypsum Soffit Board: Use setting-type taping compound and setting-type, sandable topping compound.
- E. Joint Compound for Tile Backing Panels:
 - 1. Cementitious Backer Units: As recommended by backer unit manufacturer.

2.8 AUXILIARY MATERIALS

- A. Provide auxiliary materials that comply with referenced installation standards and manufacturer's written instructions.
- B. Steel Drill Screws: ASTM C1002 unless otherwise indicated.

1. Use screws complying with ASTM C954 for fastening panels to steel members from 0.033 to 0.112 inch thick.
 2. For fastening cementitious backer units, use screws of type and size recommended by panel manufacturer.
- C. Sound-Attenuation Blankets: ASTM C665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.
- D. Acoustical Sealant: As specified in Section 079219 "Acoustical Joint Sealants."

PART 3 - EXECUTION

3.1 INSTALLATION AND FINISHING OF PANELS, GENERAL

- A. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- B. Comply with ASTM C840.
- C. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments. Provide 1/4- to 1/2-inch- wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- D. For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
- E. Prefill open joints, rounded or beveled edges, and damaged surface areas.
- F. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.
- G. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C840:
1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
 2. Level 2: Panels that are substrate for tile.
 3. Level 3: Where indicated on Drawings.
 4. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated.
 - a. Primer and its application to surfaces are specified in Section 099123 "Interior Painting."
 5. Level 5: Where indicated on Drawings.
 - a. Primer and its application to surfaces are specified in Section 099123 "Interior Painting."

- H. Cementitious Backer Units: Finish according to manufacturer's written instructions.

3.2 APPLYING TEXTURE FINISHES

- A. Surface Preparation and Primer: Prepare and apply primer to gypsum panels and other surfaces receiving texture finishes. Apply primer to surfaces that are clean, dry, and smooth.

3.3 PROTECTION

- A. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.
- B. Remove and replace panels that are wet, moisture damaged, and mold damaged.

END OF SECTION

SECTION 093013 - CERAMIC TILING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Ceramic mosaic tile.
2. Pressed floor tile.
3. Porcelain tile.
4. Glazed wall tile.
5. Stone thresholds.
6. Waterproof membranes.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples:

1. Each type and composition of tile and for each color and finish required. For ceramic mosaic tile in color blend patterns, provide samples of each color blend.
2. Assembled samples mounted on a rigid panel, with grouted joints, for each type and composition of tile and for each color and finish required.
3. Stone thresholds.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

1.4 QUALITY ASSURANCE

A. Installer Qualifications:

1. Installer is a Five-Star member of the National Tile Contractors Association or a Trowel of Excellence member of the Tile Contractors' Association of America.

PART 2 - PRODUCTS

2.1 PRODUCTS, GENERAL

- A. ANSI Ceramic Tile Standard: Provide Standard-grade tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.

- B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.

2.2 TILE PRODUCTS

A. Factory-Mounted Mosaic Ceramic Tile Type CWT-1: Glazed.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Marazzi Tile, Inc.
 - b. American Olean; a division of Dal-Tile Corporation.
 - c. Crossville, Inc.
 - d. Daltile.
2. Composition: Impervious natural clay or porcelain.
3. Certification: Porcelain tile certified by the Porcelain Tile Certification Agency.
4. Module Size: As indicated by manufacturer's designations.
5. Thickness: As indicated by manufacturer's designations.
6. Face: Pattern of design indicated, with cushion edges.
7. Surface: Smooth, without abrasive admixture.
8. Finish: As indicated by manufacturer's designations glaze.
9. Tile Color and Pattern: As indicated by manufacturer's designations.
10. Grout Color: As selected by Architect from manufacturer's full range.

B. Porcelain Tile Type PFT-1, PFT-2, PFT-3, PTB-1, PTB-2: Unglazed.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Marazzi Tile, Inc.
 - b. Crossville, Inc.
 - c. Daltile.
 - d. Florida Tile, Inc.
2. Certification: Tile certified by the Porcelain Tile Certification Agency.
3. Face Size: As indicated by manufacturer's designations.
4. Face Size Variation: As indicated by manufacturer's designations.
5. Thickness: As indicated by manufacturer's designations.
6. Face: As indicated by manufacturer's designations.
7. Dynamic Coefficient of Friction: As indicated by manufacturer's designations.
8. Tile Color, Glaze, and Pattern: As indicated by manufacturer's designations.
9. Grout Color: As selected by Architect from manufacturer's full range.

C. Glazed Wall Tile Type CWT-2:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Marazzi Tile, Inc.
 - b. American Olean; a division of Dal-Tile Corporation.
 - c. Daltile.
2. Module Size: As indicated by manufacturer's designations.
3. Face Size Variation: As indicated by manufacturer's designations.
4. Thickness: As indicated by manufacturer's designations.
5. Face: Pattern of design indicated, with manufacturer's standard edges.
6. Finish: As indicated by manufacturer's designations glaze.
7. Tile Color and Pattern: As indicated by manufacturer's designations.
8. Grout Color: As selected by Architect from manufacturer's full range.

2.3 THRESHOLDS

- A. General: Fabricate to sizes and profiles indicated or required to provide transition between adjacent floor finishes.
 1. Bevel edges at 1:2 slope, with lower edge of bevel aligned with or up to 1/16 inch above adjacent floor surface. Finish bevel to match top surface of threshold. Limit height of threshold to 1/2 inch or less above adjacent floor surface.
- B. Marble Thresholds: ASTM C503/C503M, with a minimum abrasion resistance of 10 according to ASTM C1353 or ASTM C241/C241M and with honed finish.
 1. Description:
 - a. Match Architect's sample.

2.4 WATERPROOF MEMBRANES

- A. Waterproof Membrane, PVC Sheet: PVC heat-fused on both sides to facings of nonwoven polyester.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Comotite Corporation.
 - b. Noble Company (The).
 2. Nominal Thickness: 0.040 inch.

2.5 SETTING MATERIALS

- A. Portland Cement Mortar (Thickset) Installation Materials: ANSI A108.02.
 - 1. Cleavage Membrane: Asphalt felt, ASTM D226/D226M, Type I (No. 15); or polyethylene sheeting, ASTM D4397, 4.0 mils thick.
- B. Improved Modified Dry-Set Mortar (Thinset): ANSI A118.15.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. ARDEX Americas.
 - b. C-Cure.
 - c. Laticrete International, Inc.
 - d. MAPEI Corporation.
 - 2. Provide prepackaged, dry-mortar mix to which only water must be added at Project site.
 - 3. For wall applications, provide nonsagging mortar.

2.6 GROUT MATERIALS

- A. Water-Cleanable Epoxy Grout: ANSI A118.3, with a VOC content of 65 g/L or less.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. C-Cure.
 - b. Laticrete International, Inc.
 - c. MAPEI Corporation.

2.7 MISCELLANEOUS MATERIALS

- A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting materials for installations indicated.
- B. Metal Edge Strips: Angle or L-shape, height to match tile and setting-bed thickness, metallic or combination of metal and PVC or neoprene base, designed specifically for flooring applications; nickel silver exposed-edge material.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Blanke Corporation.

- b. Ceramic Tool Company, Inc.
- c. Schluter Systems L.P.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
 - 1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
 - 2. Verify that concrete substrates for tile floors installed with bonded mortar bed or thinset mortar comply with surface finish requirements in ANSI A108.01 for installations indicated.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thinset mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.
- B. Where indicated, prepare substrates to receive waterproof membrane by applying a reinforced mortar bed that complies with ANSI A108.1A and is sloped 1/4 inch per foot toward drains.
- C. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

3.3 INSTALLATION

- A. Comply with TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 series "Specifications for Installation of Ceramic Tile" that are referenced in TCNA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.
 - 1. For the following installations, follow procedures in the ANSI A108 series of tile installation standards for providing 95 percent mortar coverage:
 - a. Tile floors in wet areas.

- b. Tile floors consisting of tiles 8 by 8 inches or larger.
- B. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.
- C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.
- D. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.
- E. Where accent tile differs in thickness from field tile, vary setting-bed thickness so that tiles are flush.
- F. Jointing Pattern: Lay tile in grid pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.
- G. Joint Widths: Unless otherwise indicated, install tile with the following joint widths:
 - 1. Ceramic Mosaic Tile: 1/16 inch.
 - 2. Glazed Wall Tile: 1/16 inch.
 - 3. Porcelain Tile: 1/4 inch.
- H. Expansion Joints: Provide expansion joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated. Form joints during installation of setting materials, mortar beds, and tile. Do not saw-cut joints after installing tiles.
 - 1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.
- I. Stone Thresholds: Install stone thresholds in same type of setting bed as adjacent floor unless otherwise indicated.
 - 1. At locations where mortar bed (thickset) would otherwise be exposed above adjacent floor finishes, set thresholds in improved modified dry-set mortar (thinset).
 - 2. Do not extend waterproof membrane under thresholds set in improved modified dry-set mortar. Fill joints between such thresholds and adjoining tile set on waterproof membrane with elastomeric sealant.
- J. Metal Edge Strips: Install where exposed edge of tile flooring meets carpet, wood, or other flooring that finishes flush with or below top of tile and no threshold is indicated.

3.4 INTERIOR CERAMIC TILE INSTALLATION SCHEDULE

A. Interior Floor Installations, Concrete Subfloor:

1. TCNA F115 : Thinset mortar; epoxy grout.
 - a. Ceramic Tile Type: PFT-1, PFT-2, PFT-3.
 - b. Thinset Mortar: Improved modified dry-set mortar.
 - c. Grout: Water-cleanable epoxy grout.
2. TCNA F121 and ANSI A108.1A: Cement mortar bed (thickset) on waterproof membrane.
 - a. Ceramic Tile Type: PFT-2 at Toilet 105C .
 - b. Grout: Water-cleanable epoxy grout.

B. Interior Wall Installations, Wood or Metal Studs or Furring:

1. TCNA W244C or TCNA W244F : Thinset mortar on cementitious backer units or fiber-cement backer board.
 - a. Ceramic Tile Type: CWT-1, CWT-2, PTB-1, PTB-2.
 - b. Thinset Mortar: Improved modified dry-set mortar.
 - c. Grout: Water-cleanable epoxy grout.

C. Shower Receptor and Wall Installations:

1. TCNA B415 : Thinset mortar on waterproof membrane over cementitious backer units or fiber-cement backer board.
 - a. Ceramic Tile Type: CWT-1, CWT-2, PTB-2 at Toilet 105C.
 - b. Thinset Mortar: Improved modified dry-set mortar.
 - c. Grout: Water-cleanable epoxy grout.

END OF SECTION

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes acoustical panels and exposed suspension systems for interior ceilings.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: Class A according to ASTM E 1264.
 - 2. Smoke-Developed Index: 50 or less.

2.2 ACOUSTICAL PANELS APC-1

- A. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
 - 1. American Gypsum.
 - 2. Armstrong World Industries, Inc.
 - 3. United States Gypsum Company.
- B. Acoustical Panel Standard: Manufacturer's standard panels according to ASTM E 1264.
- C. Color: White.
- D. Light Reflectance (LR): 0.85.
- E. Ceiling Attenuation Class (CAC): 35.
- F. Noise Reduction Coefficient (NRC): 0.85.

- G. Articulation Class (AC): 170.
- H. Edge/Joint Detail: Square.
- I. Thickness: 1 inch .
- J. Modular Size: 24 by 24 inches .

2.3 ACOUSTICAL PANELS APC-2

- A. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
 - 1. American Gypsum.
 - 2. Armstrong World Industries, Inc.
 - 3. United States Gypsum Company.
- B. Acoustical Panel Standard: Manufacturer's standard panels according to ASTM E 1264.
- C. Color: White.
- D. Light Reflectance (LR): 0.65.
- E. Ceiling Attenuation Class (CAC): 40.
- F. Edge/Joint Detail: Square.
- G. Thickness: 5/8 inch .
- H. Modular Size: 24 by 24 inches .

2.4 METAL SUSPENSION SYSTEM

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong Prelude XL 15/16" or comparable product by one of the following:
 - 1. CertainTeed Corporation.
 - 2. United States Gypsum Company.
- B. Metal Suspension-System Standard: Manufacturer's standard, direct-hung, metal suspension system and accessories according to ASTM C 635/C 635M.
- C. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- D. Wide-Face, Capped, Double-Web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized, G30 coating designation; with prefinished 15/16-inch- wide metal caps on flanges.

1. Structural Classification: Intermediate -duty system.
2. End Condition of Cross Runners: Override (stepped) or butt-edge type.
3. Face Design: Flat, flush.
4. Cap Material: Cold-rolled steel.
5. Cap Finish: Painted white.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders unless otherwise indicated.
- B. Layout openings for penetrations centered on the penetrating items.

3.2 INSTALLATION

- A. Install acoustical panel ceilings according to ASTM C 636/C 636M and manufacturer's written instructions.
- B. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
 1. Do not use exposed fasteners, including pop rivets, on moldings and trim.
 2. Arrange directionally patterned acoustical panels as follows:
 - a. As indicated on reflected ceiling plans.

END OF SECTION

SECTION 095480 - SUSPENDED PLASTIC PANEL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes ceilings consisting of suspended plastic panels and exposed suspension systems.

1.2 SUBMITTALS

- A. Product Data: For each type of product specified including ceiling units, suspension system and ceiling locking mechanisms
- B. Shop Drawings: Show placement of ceiling components in conjunction with reflective ceiling plan.
- C. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience.
- D. Product Test Reports: Indicate compliance of panel ceilings and components with requirements based on comprehensive testing of current products.

1.3 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced installer who has completed panel ceilings similar in material, design, and extent to that indicated for this Project and with a record of successful in-service performance.
- B. Source Limitations for Ceiling System: Obtain ceiling panel system from one source with resources to provide products of consistent quality in appearance and physical properties without delaying the Work.
- C. Fire Performance Characteristics: Provide glass fiber reinforced plastic panels with surface- burning characteristics as indicated below, as determined by testing assembled materials identical to those required in this Section, in accordance with ASTM E 84, by a testing organization acceptable to authorities having jurisdiction.
 - 1. Class A per ASTM E 84
- D. Acceptability: System shall be approved for use by the following authorities having jurisdiction within their respective authority. Factory Mutual, FDA, USDA, FMRC.
- E. Grid deflection: Not to exceed 1/360 with 6 lbs. per foot loading in 4 foot span.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver panels and suspension system components to Project site in original, unopened packages and store them in a fully enclosed space where they will be protected against damage from moisture, direct sunlight, surface contamination, and other causes.
- B. Handle panels carefully to avoid chipping edges or damaging units in any way.

1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install panel ceilings until spaces are enclosed and weatherproof, wet-work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

1.6 COORDINATION

- A. Coordinate layout and installation of panels and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire- suppression system, and partition assemblies.

1.7 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.
- B. Panels: Full-size units equal to 2.0 percent of amount installed.

PART 2 - PRODUCTS

2.1 ACOUSTICAL PANELS, GENERAL (FRPC-1)

- A. Acceptable manufacturers:
 - 1. Kemlite Company, Inc
 - 2. Nudo Products, Inc
 - 3. Life Science Products
- B. Basis of Design: Nudo Fiberlite FRP.
- C. Ceiling Panels: Solid non-absorbing polymer core with 8mm overall thickness with glassed reinforced smooth polyester thermoset resin faces on both sides of a solid 6 mm thick high density poly core:
 - 1. Thickness: .090 inches.

2. Flame Spread: Class C or less.
3. Edge: Square.
4. Finish: Standard.
5. Size: As indicated.

2.2 SUSPENSION SYSTEMS,

- A. Basis of Design: Armstrong Prelude XL 15/16-inch.
- B. Material: Pultruded fiberglass reinforced ceiling suspension system designed for sanitary use.
 1. USDA accepted.
- C. Rating: Intermediate duty rating complying with ASTM C-635.
- D. Physical characteristics:
 1. Texture and color: smooth white integral finish
- E. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
 1. Zinc-Coated Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
 2. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635, Table 1, Direct Hung) will be less than yield stress of wire, but provide not less than 0.106-inch- diameter wire.
- F. Gasket System: Provide manufacturer's standard system, including gasket type indicated below and related adhesives, tapes, seals, and retention clips, designed to seal out foreign material from and maintain positive pressure in clean room.
 1. Gasket Type: Antimicrobial.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and structural framing to which panel ceilings attach or abut, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage, and other conditions affecting performance of acoustical panel ceilings.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Coordination: Furnish layouts for cast-in-place anchors, clips, and other ceiling anchors whose installation is specified in other Sections.
- B. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

3.3 INSTALLATION

- A. General: Install panel ceilings to comply with publications referenced below per manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."
 - 1. Standard for Ceiling Suspension System Installations: Comply with ASTM C 636.
 - 2. Standard for Ceiling Suspension Systems Requiring Seismic Restraint: Comply with ASTM E 580.
 - 3. CISCA's Recommendations for Acoustical Ceilings: Comply with CISCA's "Recommendations for Direct-Hung Acoustical Tile and Lay-in Panel Ceilings--Seismic Zones 0-2."
- B. Panel and grid cutting and trimming: Cut components in accordance with the manufacturers required process and tools. All edges shall be trimmed of excess trimmings and shavings.
- C. Suspend ceiling hangers from building's structural members and as follows:

- 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
- 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, counter-splaying, or other equally effective means.
- 3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.

Secure wire hangers to ceiling suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure; that are appropriate for substrate; and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.

- 4. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, powder-actuated fasteners, or drilled-in anchors that extend through forms into concrete.
- 5. Do not attach hangers to steel deck tabs. Do not attach hangers to steel roof deck. Attach hangers to structural members.

6. Space hangers not more than 3.5feet apart and provide hangers not more than 8 inches from ends of each member.
- D. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or post-installed anchors.
- E. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
 1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
 2. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet. Miter corners accurately and connect securely.
 3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- F. Install suspension system runners so they are square and securely interlocked with one another. Remove and replace splintered or damaged.
- G. Install panels with undamaged edges and fitted accurately into suspension system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.

3.4 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension system members. Comply with manufacturers written instructions for cleaning and touchup of minor finish damage.
- B. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 095480

SECTION 096513 - RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Thermoset-rubber base.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified.

PART 2 - PRODUCTS

2.1 THERMOSET-RUBBER BASE (RES-1)

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Burke Mercer Flooring Products; a division of Burke Industries Inc.
2. Flexco.
3. Johnsonite; A Tarkett Company.
4. Roppe Corporation, USA.

B. Product Standard: ASTM F 1861, Type TS (rubber, vulcanized thermoset), Group I (solid, homogeneous).

1. Style and Location:

- a. Style B, Cove: .

C. Thickness: 0.125 inch.

D. Height: 4 inches.

E. Lengths: Cut lengths 48 inches long or coils in manufacturer's standard length.

F. Outside Corners: Job formed.

G. Inside Corners: Job formed.

H. Colors: As indicated by manufacturer's designations.

2.2 INSTALLATION MATERIALS

- A. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- C. Do not install resilient products until materials are the same temperature as space where they are to be installed.
- D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.2 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. Job-Formed Corners:
 - 1. Outside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 12 inches in length.
 - a. Form without producing discoloration (whitening) at bends.
 - 2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 12 inches in length.
 - a. Miter or cope corners to minimize open joints.

3.3 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Cover resilient products subject to wear and foot traffic until Final Completion.

END OF SECTION

SECTION 096516 - RESILIENT SHEET FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Vinyl sheet flooring with backing.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color, texture, and pattern specified.

1.3 CLOSEOUT SUBMITTALS

- A. Maintenance data.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are competent in techniques required by manufacturer for resilient sheet flooring installation and seaming method indicated.
 1. Engage an installer who employs workers for this Project who are trained or certified by resilient sheet flooring manufacturer for installation techniques required.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For resilient sheet flooring, as determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

- 2.2 VINYL SHEET FLOORING WITH BACKING (PVCR-1, PVCR-2, PVCRB-1, PVCRB-2)
- A. Products: Subject to compliance with requirements, provide product indicated on the Drawings or comparable product by one of the following:
1. Gerflor; .
 2. IVC US;.
 3. Patcraft; a division of Shaw Industries, Inc; .
 4. Polyflor, Ltd.; distributed by Gerbert Limited; .
 5. Shaw Contract Group; a Berkshire Hathaway company; .
- B. Product Standard: ASTM F 1303.
1. Wear-Layer Thickness: Grade 1.
 2. Overall Thickness: 2.0 mm.
 3. Backing Class: Class A (fibrous).
- C. Wearing Surface: Smooth with embedded abrasives.
- D. Sheet Width: 6.6 feet.
- E. Seamless-Installation Method: Heat welded.
- F. Colors and Patterns: As indicated by manufacturer's designations.
- 2.3 INSTALLATION MATERIALS
- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by resilient sheet flooring manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by flooring and adhesive manufacturers to suit resilient sheet flooring and substrate conditions indicated.
- C. Seamless-Installation Accessories:
1. Heat-Welding Bead: Manufacturer's solid-strand product for heat welding seams.
 - a. Colors: Match flooring.
- D. Integral-Flash-Cove-Base Accessories:
1. Cap Strip: Square metal cap provided or approved by resilient sheet flooring manufacturer.
 2. Corners: Metal inside and outside corners and end stops provided or approved by resilient sheet flooring manufacturer.

- E. Floor Polish: Provide protective, liquid floor-polish products recommended by resilient sheet flooring manufacturer.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Prepare substrates according to resilient sheet flooring manufacturer's written instructions to ensure adhesion of resilient sheet flooring.
- B. Concrete Substrates: Prepare according to ASTM F 710.
 - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
 - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by resilient sheet flooring manufacturer. Do not use solvents.
 - 3. Alkalinity and Adhesion Testing: Perform tests recommended by resilient sheet flooring manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
 - 4. Moisture Testing: Perform tests so that each test area does not exceed 200 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.
 - a. Anhydrous Calcium Chloride Test: ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
 - b. Relative Humidity Test: Using in-situ probes, ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install resilient sheet flooring until materials are the same temperature as space where they are to be installed.
 - 1. At least 48 hours in advance of installation, move flooring and installation materials into spaces where they will be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient sheet flooring.

3.2 RESILIENT SHEET FLOORING INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient sheet flooring.

- B. Unroll resilient sheet flooring and allow it to stabilize before cutting and fitting.
- C. Lay out resilient sheet flooring as follows:
 - 1. Maintain uniformity of flooring direction.
 - 2. Minimize number of seams; place seams in inconspicuous and low-traffic areas, at least 6 inches away from parallel joints in flooring substrates.
 - 3. Match edges of flooring for color shading at seams.
 - 4. Avoid cross seams.
- D. Scribe and cut resilient sheet flooring to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.
- E. Extend resilient sheet flooring into toe spaces, door reveals, closets, and similar openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on resilient sheet flooring as marked on substrates. Use chalk or other nonpermanent marking device.
- G. Install resilient sheet flooring on covers for telephone and electrical ducts and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of flooring installed on covers and adjoining flooring. Tightly adhere flooring edges to substrates that abut covers and to cover perimeters.
- H. Adhere resilient sheet flooring to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- I. Integral-Flash-Cove Base: Cove resilient sheet flooring 6 inches up vertical surfaces. Support flooring at horizontal and vertical junction with cove strip. Butt at top against cap strip.
 - 1. Install metal corners at inside and outside corners.
- J. Floor Polish: Remove soil, adhesive, and blemishes from flooring surfaces before applying liquid floor polish.

END OF SECTION

SECTION 097200 - WALL COVERINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Vinyl wall covering.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show location and extent of each wall-covering type. Indicate pattern placement, seams, and termination points.
- C. Samples: For each type of wall covering and for each color, pattern, texture, and finish specified.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: As determined by testing identical wall coverings applied with identical adhesives to substrates in accordance with test method indicated below by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 1. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - a. Flame-Spread Index: 25 or less.
 - b. Smoke-Developed Index: 50 or less.
 2. Fire-Growth Contribution: No flashover and heat and smoke release when tested in accordance with NFPA 265.

2.2 VINYL WALL COVERING (VWC-1)

- A. Manufacturers: Subject to compliance with requirements, provide products indicated on the Drawings or comparable product by one of the following:
 1. Knoll, Inc.

2. U.S. Vinyl Wallcovering Corporation.
- B. Width: As indicated on Drawings.
- C. Colors, Textures, and Patterns: Vector graphics to be provided by Architect, 100% printed coverage.

2.3 ACCESSORIES

- A. Adhesive: Mildew-resistant, nonstaining, strippable adhesive, for use with specific wall covering and substrate application indicated and as recommended in writing by wall-covering manufacturer.
- B. Primer/Sealer: Mildew resistant, complying with requirements in Section 099123 "Interior Painting" and recommended in writing by primer/sealer and wall-covering manufacturers for intended substrate.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Comply with manufacturer's written instructions for surface preparation.
- B. Clean substrates of substances that could impair bond of wall covering, including dirt, oil, grease, mold, and mildew.
- C. Prepare substrates to achieve a smooth, dry, clean, structurally sound surface free of flaking, unsound coatings, cracks, and defects.
 1. Moisture Content: Maximum of 5 percent on new plaster, concrete, and concrete masonry units when tested with an electronic moisture meter.
 2. Gypsum Board: Apply primer/sealer as recommended in writing by primer/sealer manufacturer and wall-covering manufacturer.
 3. Painted Surfaces:
 - a. Check for pigment bleeding. Apply primer/sealer to areas susceptible to pigment bleeding as recommended in writing by primer/sealer manufacturer.
 - b. Sand gloss, semigloss, and eggshell finishes with fine sandpaper.
- D. Remove hardware and hardware accessories, electrical plates and covers, light fixture trims, and similar items.
- E. Acclimatize wall-covering materials by removing them from packaging in the installation areas not less than 24 hours before installation.

3.2 INSTALLATION OF WALL COVERING

- A. Comply with wall-covering manufacturers' written installation instructions applicable to products and applications indicated.
- B. Cut wall-covering strips in roll number sequence. Change the roll numbers at partition breaks and corners.
- C. Install strips in same order as cut from roll.
- D. Install wall covering without lifted or curling edges and without visible shrinkage.
- E. Match pattern 72 inches above the finish floor.
- F. Install seams vertical and plumb at least 6 inches from outside corners and 6 inches from inside corners unless a change of pattern or color exists at corner. Horizontal seams are not permitted.
- G. Trim edges and seams for color uniformity, pattern match, and tight closure. Butt seams without overlaps or gaps between strips.
- H. Fully bond wall covering to substrate. Remove air bubbles, wrinkles, blisters, and other defects.
- I. Remove excess adhesive at seams, perimeter edges, and adjacent surfaces.
- J. Reinstall hardware and hardware accessories, electrical plates and covers, light fixture trims, and similar items.

END OF SECTION

SECTION 098436 - SOUND-ABSORBING CEILING UNITS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes shop-fabricated, sound-absorbing acoustical panel units tested for acoustical performance.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For unit assembly and installation.
- C. Samples: For each exposed product and for each color and texture specified.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: Units shall comply with "Surface-Burning Characteristics" or "Fire Growth Contribution" Subparagraph below, or both, as determined by testing identical products by UL or another testing and inspecting agency acceptable to authorities having jurisdiction:
 - 1. Surface-Burning Characteristics: Comply with ASTM E 84 or UL 723; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - a. Flame-Spread Index: 25 or less.
 - b. Smoke-Developed Index: 450 or less.
 - 2. Fire Growth Contribution: Comply with acceptance criteria of local code and authorities having jurisdiction when tested according to NFPA 286.

2.2 SOUND-ABSORBING CEILING UNITS

- A. Sound-Absorbing Ceiling Panel (APC-3): Manufacturer's standard panel construction consisting of facing material .
 - 1. Manufacturers: Subject to compliance with requirements, provide products indicated on the Drawings or comparable product by one of the following:
 - a. Acoustical Panel Systems (APS, Inc.).

- b. Acoustical Solutions, Inc.
 - c. Armstrong World Industries.
 - d. Sound Management Group LLC.
 - e. Tectum Inc.
2. Mounting: Back mounted with manufacturer's standard suspension system, secured to substrate.
 3. Core: Manufacturer's standard.
 4. Edge Construction: Manufacturer's standard frame.
 5. Edge Profile: Eased (small radius).
 6. Corner Detail in Elevation: Custom as indicated on Drawings with continuous edge profile indicated.
 7. Facing Material: As indicated on Drawings.
 8. Nominal Overall Panel Thickness: 2 inches .

2.3 MATERIALS

- A. Core Materials: Manufacturer's standard.
- B. Facing Material: As indicated on Drawings.
 1. Applied Treatments: Stain resistance.
- C. Mounting Devices: Concealed on back or top edge of unit, recommended by manufacturer to support weight of unit.

2.4 FABRICATION

- A. Standard Construction: Use manufacturer's standard construction unless otherwise indicated, with facing material applied to face, edges, and back border of dimensionally stable core and with rigid edges to reinforce panel perimeter against warpage and damage.
- B. Measure each area and establish layout of panels and joints of sizes indicated on Drawings within a given area.
- C. Facing Material: Apply fabric facing fully covering visible surfaces of unit; with material stretched straight, on the grain, tight, square, and free from puckers, ripples, wrinkles, sags, blisters, seams, adhesive, or other visible distortions or foreign matter.
 1. Fabrics with Directional or Repeating Patterns or Directional Weave: Mark fabric top and attach fabric in same direction so pattern or weave matches adjacent units.
- D. Dimensional Tolerances of Finished Units: Plus or minus 1/16 inch .

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install units in locations indicated. Unless otherwise indicated, install units with edges in alignment with walls and other units, faces flush, and scribed to fit adjoining work accurately at borders and at penetrations.
- B. Comply with manufacturer's written instructions for installation of units using type of mounting devices indicated. Mount units securely to supporting substrate.
- C. Align fabric pattern and grain with adjacent units.

3.2 CLEANING

- A. Clip loose threads; remove pills and extraneous materials.
- B. Clean panels on completion of installation to remove dust and other foreign materials according to manufacturer's written instructions.

END OF SECTION

SECTION 099113 - EXTERIOR PAINTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Primers.
2. Finish coatings.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each type of topcoat product.

PART 2 - PRODUCTS

2.1 PAINT PRODUCTS, GENERAL

A. Material Compatibility:

1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer based on testing and field experience.
2. For each coat in a paint system, provide products recommended in writing by topcoat manufacturer for use in paint system and on substrate indicated.

B. Colors: As indicated in a color schedule.

2.2 PRIMERS

- A. Exterior, Alkali-Resistant, Water-Based Primer: Pigmented, water-based primer formulated for use on alkaline surfaces, such as exterior plaster, vertical concrete, and masonry.
- B. Water-Based, Galvanized-Metal Primer: Corrosion-resistant, pigmented, acrylic primer; formulated for use on cleaned/etched, exterior, galvanized metal to prepare it for subsequent water-based coatings.

2.3 FINISH COATINGS

- A. Exterior, Water-Based, Light Industrial Coating, Low Sheen: Corrosion-resistant, water-based, pigmented, emulsion coating formulated for resistance to blocking (sticking of two painted surfaces), water, alkalis, moderate abrasion, and mild chemical exposure and for use on exterior, primed, wood and metal surfaces.
- B. Exterior, Water-Based, Light Industrial Coating, Semigloss: Corrosion-resistant, water-based, pigmented, emulsion coating formulated for resistance to blocking (sticking of two painted surfaces), water, alkalis, moderate abrasion, and mild chemical exposure and for use on exterior, primed, wood and metal surfaces.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify suitability of substrates, including surface conditions and compatibility, with finishes and primers.
- B. Proceed with coating application only after unsatisfactory conditions have been corrected.
 - 1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Comply with manufacturer's written instructions applicable to substrates and paint systems indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
 - 1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection.
- C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
 - 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems specified in this Section.

3.3 INSTALLATION

- A. Apply paints in accordance with manufacturer's written instructions.

- B. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

3.4 CLEANING AND PROTECTION

- A. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- B. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- C. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.5 EXTERIOR PAINTING SCHEDULE

- A. Galvanized-Metal Substrates:
 - 1. Water-Based, Light Industrial Coating System :
 - a. Prime Coat: Water-based, galvanized-metal primer.
 - b. Intermediate Coat: Matching topcoat.
 - c. Topcoat: Exterior, water-based, light industrial coating, low sheen semigloss.
- B. Portland Cement Plaster Substrates:
 - 1. Water-Based, Light Industrial Coating System :
 - a. Prime Coat: Exterior, alkali-resistant, water-based primer.
 - b. Intermediate Coat: Matching topcoat.
 - c. Topcoat: Exterior, water-based, light industrial coating, low sheen semigloss.

END OF SECTION

SECTION 099123 - INTERIOR PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Primers.
 - 2. Water-based finish coatings.
 - 3. Dry fall coatings.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include preparation requirements and application instructions.
 - 1. Include preparation requirements and application instructions.
 - 2. Indicate VOC content.
- B. Samples for Verification: For each type of paint system and each color and gloss of topcoat.
 - 1. Submit Samples on rigid backing, 8 inches square.
 - 2. Apply coats on Samples in steps to show each coat required for system.
 - 3. Label each coat of each Sample.
 - 4. Label each Sample for location and application area.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.
 - 1. Maintain containers in clean condition, free of foreign materials and residue.
 - 2. Remove rags and waste from storage areas daily.

1.5 FIELD CONDITIONS

- A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.

- B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures of less than 5 deg F above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Behr Paint Company; Behr Process Corporation.
 - 2. PPG Paints.
 - 3. Sherwin-Williams Company (The).
- B. Source Limitations: Obtain each paint product from single source from single manufacturer.

2.2 PAINT PRODUCTS, GENERAL

- A. Material Compatibility:
 - 1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
 - 2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.
- B. VOC Content: For field applications that are inside the weatherproofing system, paints and coatings shall comply with VOC content limits of authorities having jurisdiction and the following VOC content limits:
 - 1. Flat Paints and Coatings: 50 g/L.
 - 2. Nonflat Paints and Coatings: 150 g/L.
 - 3. Dry-Fog Coatings: 400 g/L.
 - 4. Primers, Sealers, and Undercoaters: 200 g/L.
 - 5. Anticorrosive and Antirust Paints Applied to Ferrous Metals: 250 g/L.
 - 6. Zinc-Rich Industrial Maintenance Primers: 340 g/L.
 - 7. Pretreatment Wash Primers: 420 g/L.
 - 8. Shellacs, Clear: 730 g/L.
 - 9. Shellacs, Pigmented: 550 g/L.
- C. Colors: As indicated in a color schedule.

2.3 PRIMERS

- A. Interior, Institutional Low-Odor/VOC Primer Sealer: Water-based primer sealer with low-odor characteristics and a VOC of less than 10 grams per liter for use on new interior plaster, concrete, and gypsum wallboard surfaces that are subsequently to be painted with latex finish coats.

2.4 WATER-BASED FINISH COATS

- A. Interior, Latex, Institutional Low Odor/VOC, Eggshell: White or colored latex paint with low-odor characteristics and a VOC of less than 10 grams per liter, for use in areas, such as hospitals and other occupied buildings, where the odor and VOC levels of conventional latex products would preclude their use.
- B. Interior, Latex, Institutional Low Odor/VOC, Semigloss: White or colored latex paint with low-odor characteristics and a VOC of less than 10 grams per liter, for use in areas, such as hospitals and other occupied buildings, where the odor and VOC levels of conventional latex products would preclude their use.

2.5 DRY FALL COATINGS

- A. Water Based, Dry Fall for Galvanized Steel, Eggshell: Pigmented, water-based coating for direct application to cleaned, interior galvanized-metal ceiling surfaces and adjacent primed metals.
 - 1. Gloss and Sheen Level: Manufacturer's standard eggshell finish.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
 - 1. Gypsum Board: 12 percent.
 - 2. Plaster: 12 percent.
- C. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.
- D. Verify suitability of substrates, including surface conditions and compatibility, with existing finishes and primers.

E. Proceed with coating application only after unsatisfactory conditions have been corrected.

1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations applicable to substrates and paint systems indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.

C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

D. Steel Substrates: Remove rust, loose mill scale, and shop primer, if any. Clean using methods recommended in writing by paint manufacturer.

E. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and areas where shop paint is abraded. Paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

3.3 INSTALLATION

A. Apply paints according to manufacturer's written instructions.

1. Use applicators and techniques suited for paint and substrate indicated.
2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.

- B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Tint undercoats to match color of topcoat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.
- C. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
- D. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.
- E. Painting Fire-Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:
 - 1. Paint the following work where exposed in equipment rooms:
 - a. Equipment, including panelboards and switch gear.
 - b. Uninsulated metal piping.
 - c. Uninsulated plastic piping.
 - d. Pipe hangers and supports.
 - e. Metal conduit.
 - f. Tanks that do not have factory-applied final finishes.
 - g. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
 - 2. Paint the following work where exposed in occupied spaces:
 - a. Equipment, including panelboards.
 - b. Uninsulated metal piping.
 - c. Uninsulated plastic piping.
 - d. Pipe hangers and supports.
 - e. Metal conduit.
 - f. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
 - g. Other items as directed by Architect.
 - 3. Paint portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets that are visible from occupied spaces.

3.4 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
 - 1. Do not clean equipment with free-draining water and prevent solvents, thinners, cleaners, and other contaminants from entering into waterways, sanitary and storm drain systems, and ground.
 - 2. Dispose of contaminants in accordance with requirements of authorities having jurisdiction.

3. Allow empty paint cans to dry before disposal.
 4. Collect waste paint by type and deliver to recycling or collection facility.
- B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.5 INTERIOR PAINTING SCHEDULE

- A. Steel Substrates:
1. Institutional Low-Odor/VOC Latex System :
 - a. Intermediate Coat: Matching topcoat.
 - b. Topcoat: Interior, latex, institutional low odor/VOC, eggshell.
- B. Galvanized-Metal Substrates:
1. Water-Based Dry-Fall System :
 - a. Prime Coat: Matching topcoat.
 - b. Topcoat: Water-based dry fall for galvanized steel, flat.
- C. Gypsum Board Substrates:
1. Institutional Low-Odor/VOC Latex System :
 - a. Prime Coat: Interior, institutional low-odor/VOC primer sealer.
 - b. Intermediate Coat: Matching topcoat.
 - c. Topcoat: Interior, latex, institutional low odor/VOC, semigloss.

END OF SECTION

SECTION 099611 - HIGH-PERFORMANCE COATINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes surface preparation and application of high-performance coating systems on the following substrates:
 - 1. Exterior Substrates:
 - a. Galvanized steel.
 - 2. Interior Substrates:
 - a. Gypsum board.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each type of coating system and each color and gloss of topcoat indicated.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Behr Paint Company; Behr Process Corporation.
 - 2. PPG Paints.
 - 3. Sherwin-Williams Company (The).

2.2 HIGH-PERFORMANCE COATINGS

- A. Material Compatibility:
 - 1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
 - 2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.
 - 3. Products shall be of same manufacturer for each coat in a coating system.

- B. Colors: As indicated in color schedule.

2.3 EPOXY COATINGS

- A. High-Build Epoxy, Low Gloss: Two-component epoxy, high-solids, low-gloss coating for use on interior or exterior concrete, masonry, and primed metal surfaces.
- B. Interior Epoxy-Modified Latex, Semigloss: Water-based, two-component, epoxy-modified latex paint for use on masonry, gypsum board, and primed metal surfaces.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
 - 1. Gypsum Board: 12 percent.
- C. Verify suitability of substrates, including surface conditions and compatibility, with existing finishes and primers.
- D. Proceed with coating application only after unsatisfactory conditions have been corrected.
 - 1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Comply with manufacturer's written instructions applicable to substrates and coating systems indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted.
 - 1. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
 - 2. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed.
 - 3. Remove surface-applied protection if any.

- C. Clean substrates of substances that could impair bond of coatings, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
 - 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce coating systems indicated.
- D. Galvanized-Steel Substrates: Remove grease and oil residue from galvanized sheet metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied coatings.

3.3 APPLICATION

- A. Apply high-performance coatings in accordance with manufacturer's written instructions.
- B. Apply coatings to produce surface films without cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections. Produce sharp glass lines and color breaks.

3.4 EXTERIOR HIGH-PERFORMANCE COATING SCHEDULE

- A. Galvanized-Steel Substrates:
 - 1. Epoxy System:
 - a. Prime Coat: Primer, epoxy, anti-corrosive, for metal.
 - b. Intermediate Coat: Epoxy, matching topcoat.
 - c. Topcoat: Epoxy, semigloss.

3.5 INTERIOR HIGH-PERFORMANCE COATING SCHEDULE

- A. Gypsum Board Substrates:
 - 1. Epoxy System:
 - a. Prime Coat: Primer sealer, latex, interior.
 - b. Intermediate Coat: Epoxy, matching topcoat.
 - c. Topcoat: Epoxy, semigloss.

END OF SECTION

SECTION 101100 - VISUAL DISPLAY UNITS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Glass markerboards.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For visual display units.

1. Include plans, elevations, sections, details, and attachment to other work.
2. Show locations of panel joints.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 25 or less.
2. Smoke-Developed Index: 50 or less.

2.2 GLASS MARKERBOARDS (M.B.)

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. A-1 Visual Systems.
2. AJW Architectural Products.
3. ASI Visual Display Products.
4. Claridge Products and Equipment, Inc.

B. Glass Markerboard Assembly: Fabricated of 6-mm tempered glass with steel backing for use with magnets.

1. Edge Treatment: Smooth polished edge with rounded corners.

2. Surface: Glossy.
 3. Color: White.
- C. Mounting:
1. Round, stainless steel standoffs, holding glass approximately 1 inch from wall surface; mounted through holes in markerboard.
- D. Marker Tray: Aluminum, attached with .
- E. Size: 48 inches high by width indicated on drawings.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Install visual display surfaces in locations and at mounting heights indicated on Drawings, or if not indicated, at heights indicated below. Keep perimeter lines straight, level, and plumb. Provide grounds, clips, backing materials, adhesives, brackets, anchors, trim, and accessories necessary for complete installation.

END OF SECTION

SECTION 101423 - PANEL SIGNAGE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Panel signs.

B. Related Requirements:

1. Section 01 2300 "Alternates" for panel signage provided as an Alternate.

1.2 ACTION SUBMITTALS

A. Product Data: For panel signs.

B. Shop Drawings: For panel signs.

1. Include fabrication and installation details and attachments to other work.
2. Show graphic elements and layout for each sign at least half size.

C. Samples: For each exposed product and for each color and texture specified.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Thermal Movements: For exterior signs, allow for thermal movements from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 PANEL SIGNS

A. Panel Sign (Barnquilt Custom Panels): Sign with smooth, uniform surfaces; with message and characters having uniform faces, sharp corners, and precisely formed lines and profiles; and as follows:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. ACE Sign Systems, Inc.

- b. ASI Sign Systems, Inc.
 - c. Best Sign Systems, Inc.
 - d. Clarke Systems.
 - e. Mohawk Sign Systems.
2. Solid-Sheet Sign and Returns: Aluminum sheet with finish specified in "Surface Finish and Applied Graphics" Subparagraph and as follows:
 - a. Surface-Applied, Flat Graphics: Applied paint.
 3. Mounting: Surface mounted to wall with projecting, removable studs.
 4. Surface Finish and Applied Graphics:
 - a. Painted Finish and Graphics: Manufacturer's standard, factory-applied exterior-grade sign paint, with graphics to be provided by Architect.
 - b. Both sides of sign to be painted with graphics provided by Architect.

2.3 ACCESSORIES

- A. Fasteners and Anchors: Manufacturer's standard as required for secure anchorage of signs, noncorrosive and compatible with each material joined, and complying with the following unless otherwise indicated:
 1. Use concealed fasteners and anchors unless indicated to be exposed.
 2. For exterior exposure, furnish nonferrous-metal devices unless otherwise indicated.
 3. Exposed Metal-Fastener Components, General:
 - a. Fabricated from same basic metal and finish of fastened metal unless otherwise indicated.
 4. Sign Mounting Fasteners:
 - a. Projecting Studs: Threaded, removable studs with sleeve spacer, screwed into back of sign assembly, unless otherwise indicated.

2.4 FABRICATION

- A. General: Provide manufacturer's standard sign assemblies according to requirements indicated.
 1. Mill joints to a tight, hairline fit. Form assemblies and joints exposed to weather to resist water penetration and retention.
 2. Provide welds and brazes behind finished surfaces without distorting or discoloring exposed side. Clean exposed welded and brazed connections of flux, and dress exposed and contact surfaces.
 3. Conceal connections if possible; otherwise, locate connections where they are inconspicuous.

4. Internally brace signs for stability, to meet structural performance loading without oil-canning or other surface deformation, and for securing fasteners.
5. Provide rabbets, lugs, and tabs necessary to assemble components and to attach to existing work. Drill and tap for required fasteners. Use concealed fasteners where possible; use exposed fasteners that match sign finish.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Install signs using mounting methods indicated and according to manufacturer's written instructions.
 1. Install signs level, plumb, true to line, and at locations and heights indicated, with sign surfaces free of distortion and other defects in appearance.
 2. Install signs so they do not protrude or obstruct according to the accessibility standard.
 3. Before installation, verify that sign surfaces are clean and free of materials or debris that would impair installation.
 4. Corrosion Protection: Coat concealed surfaces of exterior aluminum in contact with grout, concrete, masonry, wood, or dissimilar metals, with a heavy coat of bituminous paint.
- B. Mounting Methods:
 1. Projecting Studs: Using a template, drill holes in substrate aligning with studs on back of sign. Remove loose debris from hole and substrate surface.
 - a. Thin or Hollow Surfaces: Place spacers on studs, place sign in position with spacers pinched between sign and substrate, and install washers and nuts on stud ends projecting through opposite side of surface, and tighten.
 2. Brackets: Remove loose debris from substrate surface and install backbar or bracket supports in position so that signage is correctly located and aligned.
- C. Remove temporary protective coverings and strippable films as signs are installed.

END OF SECTION

SECTION 102113.19 - PLASTIC TOILET COMPARTMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid-plastic toilet compartments.

B. Related Requirements:

1. Section 055000 "Metal Fabrications" for supports that attach ceiling-hung compartments to overhead structural system.
2. Section 092216 "Non-Structural Metal Framing" for blocking.
3. Section 102800 "Toilet, Bath, and Laundry Accessories" for accessories mounted on toilet compartments.

1.2 ACTION SUBMITTALS

A. Product data.

B. Shop Drawings: Plans, elevations, sections, details, and attachment details.

C. Samples: Manufacturer's standard color sheets, showing full range of available colors for each type of toilet compartment.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire Performance: Tested in accordance with, and pass the acceptance criteria of, NFPA 286.

B. Structural Performance: Where grab bars are mounted on toilet compartments, design panels to comply with the following requirements:

1. Panels are able to withstand a concentrated load on grab bar of at least 250 lbf applied at any direction and at any point, without deformation of panel.

C. Regulatory Requirements: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1 for toilet compartments designated as accessible.

2.2 SOLID-PLASTIC TOILET COMPARTMENTS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. ASI Global Partitions.
 - 2. American Sanitary Partition Corporation.
 - 3. Partition Systems International of South Carolina (PSISC); Columbia Systems International of South Carolina LLC.
 - 4. Scranton Products.
- B. Toilet-Enclosure Style: Ceiling hung.
- C. Urinal-Screen Style: Wall hung.
- D. Door, Panel, and Pilaster Construction: Solid, high-density polyethylene (HDPE) material, not less than 1 inch thick, seamless, with eased edges, and with homogenous color throughout thickness of material. Provide with no-sightline system consisting of door and pilaster lapped edges on strike side of door and door and pilaster lapped edges on hinge side of door (unless continuous hinge is used).
 - 1. Integral Hinges: Configure doors and pilasters to receive integral hinges.
 - 2. Color: One color in each room as indicated by manufacturer's designations.
- E. Urinal-Screen Construction: Matching panel construction.
- F. Brackets (Fittings):
 - 1. Full-Height (Continuous) Type: Manufacturer's standard design; stainless steel.

2.3 HARDWARE AND ACCESSORIES

- A. Door Hardware and Accessories: Manufacturer's operating hardware and accessories. Mount with through bolts.
 - 1. Hinges:
 - a. Manufacturer's continuous, cam type that swings to a closed or partially open position, allowing emergency access by lifting door.
 - 1) Material, Continuous Hinge: Stainless steel.
 - 2. Latch and Keeper: Manufacturer's surface-mounted latch unit, designed for emergency access, and with combination rubber-faced door strike and keeper. Provide units that comply with regulatory requirements for accessibility at toilet enclosures designated as accessible.
 - a. Material: Chrome-plated zamac.

3. Coat Hook: Manufacturer's combination hook and rubber-tipped bumper, sized to prevent inswinging door from hitting compartment-mounted accessories.
 - a. Material: Chrome-plated zamac.
 4. Door Bumper: Manufacturer's rubber-tipped bumper at outswinging doors.
 - a. Material: Chrome-plated zamac.
 5. Door Pull: Manufacturer's unit at outswinging doors that complies with regulatory requirements for accessibility. Provide units on both sides of doors at toilet enclosures designated as accessible.
 - a. Material: Chrome-plated zamac.
- B. Anchorages and Fasteners: Manufacturer's standard exposed fasteners of stainless steel, finished to match items they are securing, with theft-resistant-type heads. Provide sex-type bolts for through-bolt applications. For concealed anchors, use stainless steel, hot-dip galvanized steel, or other rust-resistant, protective-coated steel compatible with related materials.

2.4 MATERIALS

- A. Aluminum Castings: ASTM B26/B26M.
- B. Aluminum Extrusions: ASTM B221.
- C. Stainless Steel Sheet: ASTM A240/A240M or ASTM A666, Type 304, stretcher-leveled standard of flatness.
- D. Stainless Steel Castings: ASTM A743/A743M.
- E. Zamac: ASTM B86, commercial zinc-alloy die castings.

2.5 FABRICATION

- A. Fabricate toilet compartment components to sizes indicated. Coordinate requirements and provide cutouts for through-partition toilet accessories where required for attachment of toilet accessories.
- B. Floor-and-Ceiling-Anchored Units: Manufacturer's standard corrosion-resistant anchoring assemblies at pilasters and walls, with leveling adjustment nuts at tops and bottoms of pilasters. Provide shoes and sleeves (caps) at pilasters to conceal anchorage.
- C. Door Size and Swings: Unless otherwise indicated, provide 24-inch- wide, inswinging doors for standard toilet enclosures and 36-inch- wide, outswinging doors with a minimum 32-inch- wide, clear opening for toilet enclosures designated as accessible.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Comply with manufacturer's written installation instructions. Install units rigid, straight, level, and plumb. Secure units in position with manufacturer's recommended anchoring devices.
1. Maximum Clearances:
 - a. Pilasters and Panels or Screens: 1/2 inch.
 - b. Panels or Screens and Walls: 1 inch.
 2. Full-Height (Continuous) Brackets: Secure panels or screens to walls and to pilasters with full-height brackets.
 - a. Locate bracket fasteners, so holes for wall anchors occur in masonry or tile joints.
 - b. Align brackets at pilasters with brackets at walls.
- B. Floor-and-Ceiling-Anchored Units: Secure pilasters to supporting construction and level, plumb, and tighten. Hang doors and adjust, so doors are level and aligned with panels, when doors are in closed position.
- C. Urinal Screens: Attach with anchoring devices to suit supporting structure. Set units level and plumb, rigid, and secured to resist lateral impact.

3.2 ADJUSTING

- A. Hardware Adjustment: Adjust and lubricate hardware in accordance with hardware manufacturer's written instructions for proper operation. Set hinges on inswinging doors to hold doors open approximately 30 degrees from closed position when unlatched. Set hinges on outswinging doors to return doors to fully closed position.

END OF SECTION

SECTION 102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Public-use washroom accessories.
 - 2. Public-use shower room accessories.
 - 3. Childcare accessories.
 - 4. Underlavatory guards.
 - 5. Custodial accessories.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Structural Performance: Design accessories and fasteners to comply with the following requirements:
 - 1. Grab Bars: Installed units are able to resist 250 lbf concentrated load applied in any direction and at any point.
 - 2. Shower Seats: Installed units are able to resist 250 lbf concentrated load applied in any direction and at any point.

2.2 PUBLIC-USE WASHROOM ACCESSORIES

- A. Toilet Tissue Dispenser (TTD):
 - 1. Owner-furnished, contractor installed. Contractor to provide blocking.
- B. Paper Towel (Roll) Dispenser PTD:
 - 1. Owner-furnished, contractor installed. Contractor to provide blocking.
- C. Grab Bar GB-1, GB-2, GB-3:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. AJW Architectural Products.
 - b. Bobrick Washroom Equipment, Inc.
 - c. Bradley Corporation.
2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel, 0.05 inch thick.
 - a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).
4. Outside Diameter: 1-1/2 inches.
5. Configuration and Length: As indicated on Drawings .

D. Sanitary-Napkin Disposal Unit SND:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASI-American Specialties, Inc.,
 - b. Bobrick Washroom Equipment, Inc.
 - c. Bradley Corporation.
2. Mounting: Recessed.
3. Door or Cover: Self-closing, disposal-opening cover and hinged face panel with tumbler lockset.
4. Receptacle: Removable.
5. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

E. Mirror Unit MI:

1. Basis of Design: provide Bobrick B-167 or comparable product by one of the following:
 - a. ASI-American Specialties, Inc.
 - b. Bradley Corporation.
 - c. Kohler Corporation
2. Frame: Etched outer frame, adjustable tilt.
 - a. Corners: Mitered.
3. Size: As indicated on Drawings.
4. Hangers: Manufacturer's standard rigid, tamper and theft resistant.
5. Lighting: LED Backlit

F. Hook RH:

1. Basis of Design: provide Bobrick B9542 or comparable product by one of the following:

- a. ASI-American Specialties, Inc.
 - b. Bradley Corporation.
2. Description: Single-prong unit.
 3. Mounting: Concealed.
 4. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

2.3 PUBLIC-USE SHOWER ROOM ACCESSORIES

A. Shower Curtain Rod SCR:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASI-American Specialties, Inc.
 - b. Bobrick Washroom Equipment, Inc.
 - c. Bradley Corporation.
2. Description: 1-1/4-inch- outside diameter, straight rod.
3. Configuration: As indicated on Drawings
4. Mounting Flanges: Concealed fasteners; in material and finish matching rod.
5. Rod Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

B. Shower Curtain :

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASI-American Specialties, Inc.
 - b. Bobrick Washroom Equipment, Inc.
 - c. Bradley Corporation.
2. Size: Minimum 12 inches wider than opening by 72 inches high.
3. Material: Nylon-reinforced vinyl, minimum 9 oz. or 0.008-inch- thick vinyl, with integral antibacterial and flame-retardant agents.
4. Color: White .
5. Grommets: Corrosion resistant at minimum 6 inches o.c. through top hem.
6. Shower Curtain Hooks: Chrome-plated or stainless steel, spring wire curtain hooks with snap fasteners, sized to accommodate specified curtain rod. Provide one hook per curtain grommet.

C. Folding Shower Seat :

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASI-American Specialties, Inc.
 - b. Bobrick Washroom Equipment, Inc.

- c. Bradley Corporation.
2. Seat: Phenolic or polymeric composite of slat-type or one-piece construction in color as selected by Architect .
3. Mounting Mechanism: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

2.4 CHILDCARE ACCESSORIES

A. Diaper-Changing Station BCS:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Bradley Corporation.
 - b. Gamco Commercial Restroom Accessories; Bobrick Washroom Equipment, Inc.
 - c. Koala Kare Products; Bobrick Washroom Equipment, Inc.
2. Description: Horizontal unit that opens by folding down from stored position and with child-protection strap.
 - a. Engineered to support minimum of 250 lb static load when opened.
3. Mounting: Semirecessed, with unit projecting not more than 1 inch from wall when closed.
4. Operation: By pneumatic shock-absorbing mechanism.
5. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin), exterior shell with rounded plastic corners; HDPE interior in manufacturer's standard color.
6. Liner Dispenser: Provide built-in dispenser for disposable sanitary liners.

2.5 UNDERLAVATORY GUARDS

A. Underlavatory Guard :

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Buckaroos, Inc.
 - b. Plumberex Specialty Products, Inc.
 - c. Truebro; IPS Corporation.
2. Description: Insulating pipe covering for supply and drain piping assemblies that prevents direct contact with and burns from piping; allow service access without removing coverings.
3. Material and Finish: Antimicrobial, molded plastic, white.

2.6 CUSTODIAL ACCESSORIES

A. Custodial Utility Shelf :

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. AJW Architectural Products.
 - b. ASI-American Specialties, Inc.
 - c. Bobrick Washroom Equipment, Inc.
 - d. Bradley Corporation.
 - e. Brey-Krause Manufacturing Co.
 - f. Gamco Commercial Restroom Accessories; Bobrick Washroom Equipment, Inc.
 - g. Tubular Specialties Manufacturing, Inc.
2. Description: Wood shelving units with stainless steel adjustable shelf standards.
3. Size: 30 inches long by 18 inches deep.
4. Material and Finish: Not less than nominal 0.05-inch- thick stainless steel adjustable standards, ASTM A480/A480M No. 4 finish (satin) with 3/4 inch sealed solid hardwood.

B. Custodial Mop and Broom Holder :

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASI-American Specialties, Inc.
 - b. Bobrick Washroom Equipment, Inc.
 - c. Bradley Corporation.
2. Description: Unit with shelf, hooks, holders, and rod suspended beneath shelf.
3. Length: 36 inches.
4. Hooks: Four.
5. Mop/Broom Holders: Three, spring-loaded, rubber hat, cam type.
6. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).
 - a. Shelf: Not less than nominal 0.05-inch- thick stainless steel.
 - b. Rod: Approximately 1/4-inch- diameter stainless steel.

2.7 FABRICATION

- A. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install accessories in accordance with manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
 - 1. Remove temporary labels and protective coatings.
- B. Grab Bars: Install to comply with specified structural-performance requirements.
- C. Shower Seats: Install to comply with specified structural-performance requirements.

END OF SECTION

SECTION 114000 - FOODSERVICE EQUIPMENT

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Walk-in refrigeration equipment.

1.2 COORDINATION

- A. Coordinate foodservice equipment layout and installation with other work, including layout and installation of lighting fixtures, HVAC equipment, and fire-suppression system components.

- B. Coordinate locations and requirements of utility service connections.

- C. Coordinate sizes, locations, and requirements of the following:

1. Overhead equipment supports.
2. Equipment bases.
3. Floor depressions.
4. Insulated floors.
5. Floor areas with positive slopes to drains.
6. Floor sinks and drains serving foodservice equipment.
7. Roof curbs, equipment supports, and penetrations.

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

A. Product Data

1. Walk-in refrigeration equipment.

B. Include the following:

1. Manufacturer's model number.
2. Accessories and components that will be included for Project.
3. Clearance requirements for access and maintenance.
4. Utility service connections for water, drainage, power, and fuel; include roughing-in dimensions.

- C. Shop Drawings: For fabricated equipment. Include plans, elevations, sections, roughing-in dimensions, fabrication details, utility service requirements, and attachments to other work.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: For foodservice facilities.
 - 1. Indicate locations of foodservice equipment and connections to utilities.
 - 2. Key equipment using same designations as indicated on Drawings.
 - 3. Include plans and elevations; clearance requirements for equipment access and maintenance; details of equipment supports; and utility service characteristics.
 - 4. Include details of seismic bracing for equipment.

1.6 FIELD CONDITIONS

- A. Field Measurements: Verify actual dimensions of construction contiguous with foodservice equipment by field measurements before fabrication. Indicate measurements on Coordination Drawings.

1.7 WARRANTY

- A. Refrigeration Compressor Warranty: Manufacturer agrees to repair or replace compressors that fail in materials or workmanship within specified warranty period.
 - 1. Failure includes, but is not limited to, inability to maintain set temperature.
 - 2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. NSF Standards: Provide equipment that bears NSF Certification Mark or UL Classification Mark certifying compliance with applicable NSF standards.
- B. UL Certification: Provide electric and fuel-burning equipment and components that are evaluated by UL for fire, electric shock, and casualty hazards according to applicable safety standards, and that are UL certified for compliance and labeled for intended use.
- C. Regulatory Requirements: Install equipment to comply with the following:
 - 1. ASHRAE 15, "Safety Code for Mechanical Refrigeration."
 - 2. NFPA 70, "National Electrical Code."

- D. Seismic Restraints: Comply with SMACNA's "Kitchen Ventilation Systems and Food Service Equipment Fabrication and Installation Guidelines," Appendix A, "Seismic Restraint Details," unless otherwise indicated.

2.2 WALK-IN REFRIGERATION EQUIPMENT

A. Walk-in Refrigeration Units :

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Walk-In Coolers
 - b. US Cooler
 - c. Thermo-Cool
2. Description: Freezer.
 - a. Wall and Ceiling Panels: Interlocking insulating panels.
 - b. Floors: Field installed; provide manufacturer's standard insulated floor screed.
 - c. Doors:
 - 1) Hinges: Self-closing and spring loaded; three per door.
 - 2) Latch: Edge-mounted, positive-type latch with cylinder lock.
 - 3) Include safety-release handle that opens door from inside when door is locked.
 - d. Door Accessories:
 - 1) Vision port.
 - 2) Pressure relief port.
 - 3) Threshold: Stainless steel, factory installed.
 - 4) Antic condensate heater at freezer doors.
 - e. Vaporproof Lighting Fixtures:
 - 1) Control: Neon pilot light and toggle switch located on exterior of door panel.
 - 2) Quantity: One per compartment, located on door panel.
 - f. Refrigeration System: Remote system with preassembled condensing unit and evaporator assemblies.
 - 1) Exterior Condensing Units: Include winter control, crankcase heater, and enclosed weatherproof housing.
 - 2) Operating Temperature: -10 degrees Fahrenheit.

- g. Temperature Monitoring System: Electronic monitoring and remote audible alarm system that warns when temperatures register 10 deg F above or below set temperature.
- h. Closure Panels and Trim: Include closure panels and trim.
- i. Electrical Service: Equip unit for connection to service indicated on Drawings.

3. Finishes:

- a. Exposed Exterior Finish: Smooth, mill-finished aluminum.
- b. Unexposed Exterior Finish: Stucco-patterned, metallic-coated steel.
- c. Interior Finish: Smooth, mill-finished aluminum.
- d. Closure Panels and Trim: Matched to exposed exterior finish of panels.

2.3 MISCELLANEOUS MATERIALS

- A. Installation Accessories, General: NSF certified for end-use application indicated.
- B. Elastomeric Joint Sealant: ASTM C920; silicone. Type S (single component), Grade NS (nonsag), Class 25, Use NT (nontraffic) related to exposure, and Use M, G, A, or O as applicable to joint substrates indicated.

1. Public Health and Safety Requirements:

- a. Sealant is certified for compliance with NSF standards for end-use application indicated.
- b. Washed and cured sealant complies with the FDA's regulations for use in areas that come in contact with food.

2. Cylindrical Sealant Backing: ASTM C1330, Type C, closed-cell polyethylene, in diameter greater than joint width.

2.4 FINISHES

A. Stainless Steel Finishes:

- 1. Surface Preparation: Remove tool and die marks and stretch lines, or blend into finish.
- 2. Polished Finishes: Grind and polish surfaces to produce uniform finish, free of cross scratches.
 - a. Run grain of directional finishes with long dimension of each piece.
 - b. When polishing is completed, passivate and rinse surfaces. Remove embedded foreign matter and leave surfaces chemically clean.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install foodservice equipment level and plumb, according to manufacturer's written instructions.
 - 1. Connect equipment to utilities.
 - 2. Provide cutouts in equipment, neatly formed, where required to run service lines through equipment to make final connections.
- B. Complete equipment assembly where field assembly is required.
 - 1. Provide closed butt and contact joints that do not require a filler.
 - 2. Grind field welds on stainless steel equipment until smooth and polish to match adjacent finish.
- C. Install equipment with access and maintenance clearances that comply with manufacturer's written installation instructions and with requirements of authorities having jurisdiction.
- D. Install cabinets and similar equipment on bases in a bed of sealant.
- E. Install closure-trim strips and similar items requiring fasteners in a bed of sealant.
- F. Install joint sealant in joints between equipment and abutting surfaces with continuous joint backing unless otherwise indicated. Produce airtight, watertight, vermin-proof, sanitary joints.

3.2 CLEANING AND PROTECTING

- A. After completing installation of equipment, repair damaged finishes.
- B. Clean and adjust equipment as required to produce ready-for-use condition.
- C. Protect equipment from damage during remainder of the construction period.

3.3 DEMONSTRATION

- A. Train Owner's maintenance personnel to adjust, operate, and maintain foodservice equipment.

END OF SECTION

SECTION 114001 - INSECT REARING ROOMS

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. Prefabricated insulated constant temperature rooms for interior use.
 - 1. Insect Rearing Rooms provided by Owner, coordinated by Contractor. Contractor responsible for utility connections.

1.2 DEFINITIONS

- A. Laboratory Use Insect Rearing Room: Specially-constructed walk-in enclosure intended to maintain temperature levels within a given range, and/or to simulate specific environmental conditions.
- B. Temperature Range: Temperature measured at the point where the room controller sensing element is placed and indicated by recording instrument supplied with the room:
 - 1. As measured throughout the storage area during a 24-hour test period with standard load and airflow.
 - 2. Temperature Control Fluctuation (Tolerance): Maximum variation in temperature at the control point in the room over 24 hours.
 - 3. Temperature and Relative Humidity Uniformity: Allowable variation throughout the room from control point setting.
 - a. For the purpose of establishing acceptable uniformity, testing locations cannot be closer than 4 inches from wall, ceiling, flooring or door surfaces, or 24 inches from air outlet.

1.3 ADMINISTRATIVE REQUIREMENTS

- A. Coordination with Electrical: Coordinate location and characteristics of electrical service.
- B. Coordination with Mechanical/Plumbing: Coordinate location and characteristics of water supply services and drainage.
- C. Coordination with Mechanical/HVAC: Coordinate location and characteristics of chamber air exchange services.
- D. Coordination with IT: Coordinate location and characteristics of Ethernet connection.
- E. Preinstallation Meeting: Convene one week before starting work of this section.

1.4 REFERENCE STANDARDS

- A. ADA Standards - 2010 ADA Standards for Accessible Design.
- B. ASTM C920 - Standard Specification for Elastomeric Joint Sealants.
- C. NFPA 70 - National Electrical Code.
- D. UL 508A - Industrial Control Panels
- E. ISO 9001:2015
- F. NSF: National Sanitary Foundation Seal of Approval
- G. UL 723: Underwriters Laboratories - Room Panel Flame Spread
- H. UL 1715: Underwriters Laboratories - Fire Test of Interior Finish Material
- I. EPA final rule (signed Oct 5, 2023)- TT Sector - Industrial Process Refrigeration

1.5 SUBMITTALS

- A. Product Data: Manufacturer's technical data for panels, equipment, control system, hardware, lighting fixtures, shelving, and accessories.
- B. Shop Drawings: Provide detailed information to coordinate installation of constant temperature room(s) with other building construction. In addition to general installation drawings, provide detailed project specific drawings.
- C. HVAC Design Data: Calculations indicating the design heating and cooling loads which support equipment selections.
- D. Structural Design Data: Indicate profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories for ceiling panel supports. Include erection drawings, elevations, and details where applicable.
- E. Designer's Qualification Statement.
- F. Manufacturer's Qualification Statement.
- G. Installer's Qualification Statement.
- H. Operation and Maintenance Data:
 - 1. Provide at least one hardcopy and one electronic copy of sets of instructions sufficient to operate and maintain the insect rearing room. Include in maintenance instructions, electrical and refrigeration schematics.
- I. Warranties: Standard and special warranties specified in this section.

1.6 QUALITY ASSURANCE

- A. Electrical Safety: UL-508A, certified and labeled
- B. Manufacturer Qualifications: ISO 9001:2015 certified
- C. Manufacturer Qualifications:
 - 1. The manufacturer of walk-in rooms in this section must demonstrate a minimum of 40 years of verifiable experience in the production of controlled environment systems.
 - 2. Manufacturer must fully design, build and test all walk-in rooms on site at their facility before shipping to final location to ensure all components are in working order upon arrival. This will ensure that any potential long lead time items are in working condition upon arrival.
 - 3. Require documentation of FAT (Factory Acceptance Testing)
- D. Installer Qualifications: Manufacturer or Company specializing in installation of plant growth rooms with not less than five years of documented experience.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Wrap and crate finished components and assemblies at factory to prevent damage or marring of surfaces during shipping and handling.
- B. Do not deliver materials or assemblies to site until installation spaces are ready to receive rooms.
- C. Store products off ground, under cover, protected from elements and construction operations.
- D. Handle to prevent damage to edges, ends, or surfaces

1.8 FIELD CONDITIONS

- A. Ambient Conditions: Maintain building design temperature and humidity conditions during and after installation of building-interior rooms.

1.9 WARRANTY

- A. Manufacturer shall provide, at their discretion, material and labor to repair, replace, or make adjustments to equipment or system covered under warranty, which is determined to be defective in material, design, or workmanship within the warranty period.
 - 1. Warranty shall not be pro-rated.
 - 2. Warranty shall not be transferable.

3. Exemption: Damage caused by abuse, neglect, or failure to follow manufacturer's written maintenance instructions in Owner's maintenance manual.
 4. Furnish copy of warranty in advance of shipment of unit.
- B. Warranties: Manufacturer's standard form, without monetary limitation, in which manufacturer shall agree to repair or replace components of plant growth room system that are defective in materials, design, or workmanship within specified warranty period.
1. For a period of 2 years from substantial completion, the manufacturer's warranty shall cover the following controlled environment room systems consisting of, but not limited to:
 - a. Insulated metal unit enclosure panels
 - b. Panel finishes
 - c. Insulated panel system hardware, seals, and gaskets
 - d. Mechanical systems
 - e. Control system
 - f. Electrical system
 - g. Other chamber sub-systems as required by this specification
 2. For a period of 2 years from substantial completion, the manufacturer's warranty shall cover the controlled environment room's refrigeration system, consisting of, but not limited to:
 - a. Condensing unit
 - b. Pipework and insulation provided and installed by the controlled environment manufacturer
 - c. Valves
 - d. Pressure controls and system monitoring devices
 - e. Associated electrical wiring

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Basis of Design: Percival Scientific IR-89L5 or equal by:
1. Darwin Chambers
 2. Standex International

2.2 CONTROL SYSTEM

- A. Embedded Control System
1. Industrial grade, highly reliable, solid-state microcontroller architecture
 2. Dual experiment protection via integrated yet independent temperature limit shutdown

3. Ambient temperature monitoring
4. Power Fail event logging
5. Single-board electronic solid-state design
6. Durable 10-key industrial keypad with VFD display and LED indicators
7. Three programming styles: Diurnal, 24 hours, and non-24 hour (elapsed time)
8. Daily Light Integral Programming Mode
9. Programs can be run in ramping or non-ramping modes
10. Programs are created and run in real time
11. Multiple programs can be linked together to simulate natural conditions
12. RTD temperature sensor inputs
13. Three-point temperature calibration
14. Two calibration offsets per input channel
15. Light lifetime maintenance. The controller maintains the accumulated hours that each light output has been activated. The accumulated hours can be reset for each output.
16. Available programmable outputs allow for user specific control requests (i.e. programmable electrical outlets)
17. Controller can be secured with four-level password protection
18. Field-upgradeable I/O expansion modules
19. On-board data logging, exportable to USB drive
20. Firmware updates easily uploaded via included USB thumb drive
21. Industrial-grade membrane key-pad overlay for service
22. System diagnostics menu
23. Scalable analog and digital control outputs
24. XML-based control system commands allow for scalable and customizable user interfaces
25. Compatibility with building automation systems and other types of control systems that support Modbus RTU
26. LAN/WAN/Bluetooth
27. Built-in web server
28. Digital Addressable Lighting Interface (DALI) control allows for light remapping without the need for rewiring
29. Backward compatibility with previous-generation Intellus control systems
30. Compatibility with building automation systems via Modbus RTU
31. Secure, unidirectional connection via SSL to Percival Connect remote data logging software

B. Network Interface

1. pfSense-based gateway and routing interface aids complex IT infrastructure
2. Load balancing (HAProxy) and message queueing ensure communication stability to embedded chamber processor
3. Supports multiple network configurations
 - a. VLAN
 - b. DNS
 - c. DHCP
 - d. Port forwarding
 - e. Rate limiting
4. Preconfigured firewall with transport security.

5. Set to the following cybersecurity standards
 - a. NIST 800-53 Rev. 5 IA-3 and CIS v.8 Device 1.4 DHCP Standards
 - b. CIS v.8 Data 3.10 compatible TLS encryption
 - c. CIS v.8 Control 13.4-6.10 compatible networking logs
 6. Default network configuration (can be changed by IT professional):
 - a. Assumes the client uses DHCP reservation as opposed to fixed addressing per point 2.02.B.5.a .
 - b. WAN assumes client addressing is outside the IP ranges 192.168.1-2.* and/or 192.168.10-11.* .
 7. Traffic monitoring and logging
 8. Chamber parameter data logging
 - a. Default to 1 minute frequency
 - b. Configurable to 20 second logging frequency
 - c. Parameters auto-logged to installed USB thumb drive (note: if storage device is removed, no data is logged)
 9. Web Server
 - a. Accessible via LAN or WAN
 - b. Multiple, password protected user levels
 - c. Facilitates remote control, monitoring and programming of IntellusUltraConnect controller
 - d. Requires no software installation on remote terminals, accessible through all major web browsers
 - e. Tabular presentation of IntellusUltraConnect control system settings and programs
 - f. Customizable email notification system, including alarms and periodic status updates
 - g. Supports up to 5 email addresses
 - h. Supports Percival outbound, and local SMTP email servers
- C. Touchscreen user interface
1. Android-based OS
 2. 10 inch, IPS, high definition (1280 x 800) display
 3. 10-point capacitive touch screen interface
 4. Intuitive, graphical user interface of all primary control system functions
 5. Graphical and tabular views of data
 6. Snapshot trend graph showing most recent 6 hours
 7. Full screen graph displays past 24 hours of chamber performance
 8. User-configurable trend graphs show multiple set points and process values over time
 9. Highly visible alarm display
 10. Customizable, audible buzzer

- D. Chamber control system shall connect with a single, central management system for monitor, control and data logging
- E. Control system shall be compatible with building monitoring systems via native sensor retransmit and dry contacts, or via optionally available equipment such as Modbus and BACnet communication bridges
- F. Remote Connection Software
 - 1. Remote data logging via unidirectional data stream from Intellus to database via SSL
 - 2. Software can be installed remotely, or locally
 - 3. Supports multiple user levels and user accounts
 - 4. Supports simultaneous connection to and data logging from multiple IntellusUltraConnect control systems
 - 5. Software installs a webserver and database on a central PC
 - 6. Clients access the central PC via any major web browser
 - 7. Summary screen provides a tabular overview of all connected chambers
 - 8. Enhanced graphing and data logging tools
 - 9. Ability to link software to IntellusUltraConnect web server
 - 10. Multi-step program import utility for uploading programs from an Excel template
- G. Weather Simulation Software
 - 1. Simulate temperature, relative humidity, lighting, and CO2 levels for a range of dates and global locations
 - 2. Replicate real-time weather conditions in real-time via METAR
 - 3. Apply climate change offsets to simulations based on multiple climate change models (contact Percival for more information)
 - 4. Control lights by spectral quality, day length, and intensity
 - 5. Convenient tool for uploading customer weather simulation profiles
 - 6. Web-based GUI with user-friendly control dashboard and graphing tools
- H. Circadian Simulation Software
 - 1. Access key to web interface to be provided which given latitude, longitude, and day of the year, suggests a 5, 7, or 12-step program to input into the chamber via the tablet interface.
 - 2. Along with the present year, allows simulation of year 2069 and year 2099 following climate change models.
 - 3. Each step consists of a suggested time, along with percentage dimming outputs, and a suggested temperature, humidity, and CO2 level.
 - 4. These steps correspond roughly to the profiles of sunrise, daylight, and sunset throughout a normal day period.
 - 5. Ramping profiles allow gradual changes between each period.
 - 6. Elapsed programming may be used to adjust day length manually.
- I. Control Box Assembly: UL-508A certified and labeled.

2.3 PANELS

- A. Exterior Dimensions: 8'(W) x 9'(D) x 8.5' (H) - Control box adds 7" to chamber depth
- B. Metal Wall Panel Faces:
 - 1. Exterior Wall Panel Face:
 - a. 26 gauge, galvanized steel.
 - b. Finish Texture: Embossed.
 - c. Finish Color: prepainted igloo white QC-5216 (Polyester).
 - 2. Exterior Ceiling Face: 26 gauge, galvalume steel.
 - 3. Interior Wall Panel and Interior Ceiling Face:
 - a. 24 gauge, galvanized steel.
 - b. Finish Texture: Smooth.
 - c. Finish Color: prepainted igloo white QC-5216 (Polyester).
 - 4. Floor: None
- C. Fasteners: Cam-type.
- D. Gaskets: NSF-listed PVC.
- E. Panel Edges: Tongue and groove with embedded Posi-Locs.
- F. Floor: None. Panel Attachment to Floor: Coved vinyl screeds.
- G. Insulation: Polyurethane foamed-in-place with a 97 percent closed cell structure, self extinguishing type.
 - 1. R-Value: Minimum R-29
 - 2. Thickness: Minimum 4 inches.

2.4 DOOR

- A. Door Frame: Fiberglass reinforced plastic.
- B. Hardware:
 - 1. 2 x K-1248 brushed chrome flush hinges
 - 2. Handle 1229C brushed chrome with lock
 - 3. Closer K-1095 flush spring action
- C. Armor Plate Provide in fitting flush-design door similar in construction to wall panels.
- D. Door location and direction of swing as indicated on Drawings.

1. Thickness: Same thickness as wall panels.
2. Size: 36 inches wide by 78 inches high.
3. Gaskets: Magnetic core snap-in perimeter gaskets; on edges and sides of door: 32 inches high, diamond plate kick panel covering the interior and exterior bottom of doors

E. Window: Sealed insulated glass unit; hinged, gasketed cover.

2.5 OBSERVATION WINDOW

A. Window: Sealed insulated glass with light tight cover.

1. Size: 15 inches by 20 inches.

2.6 SHELVING:

A. Four Free standing shelving Units.

1. Number of Tiers per shelving Unit: 5
2. Shelf Type: Wire
3. Shelf size: 24" x 48"
4. Number of shelf Post: 4
5. Post Height: 76"

B. Total Shelving Work Area: 160 ft²

C. Clearance between light fixture and shelf with all five tiers installed: 14-1/2".

D. Finish: Epoxy Green

2.7 LIGHTING

A. System Intensity:

1. Approximately 250 $\mu\text{mol}/\text{m}^2/\text{sec}$ at 6" (15.2 cm)

B. Two independently dimmable LED Colors: Red (660nm) and Full Spectrum white LEDs with color temperature of 5700K, CRI=90.

C. Programming and Control: Each LED color shall be independently dimmable as a percentage of total output. Set point is entered into controller as a percentage, controller scales output voltage to LED drivers.

1. Dimming Range: Minimum 5 percent to 100 percent of light output adjustable in 1 percent increments.
2. Number of dimming channels: ten (two per tier)
3. Photoperiod is programmable is multimodal

D. Linear LED lighting:

1. Horizontally mounted above each shelf (two White LED bars plus one Red LED bar per shelf).
2. LED bars
 - a. 48" Length
 - b. LED life: L80(12K)= 72,000hours
 - c. Red and White LEDs must have Poly Carbonate lens for IP-65 rating
 - d. Heatsink: low profile anodized extruded aluminum
3. LED Driver
 - a. IP-67

2.8 COOLING/HEATING SYSTEM: HOT BYPASS REFRIGERATION SYSTEM AND ELECTRIC HEATERS

A. Condensing Unit:

1. Remote, water cooled with hot-gas bypass, continuous compressor operation, extended life, and precise temperature control.
 - a. Provide a refrigeration system designed to achieve and maintain environmental conditions specified in this Section
 - b. Water Requirements: 170 GPH with water inlet at 65°F and water outlet at 85°F with a pressure drop of 1.8 psig.
 - c. Condensing Unit Components: An industrial type Scroll Compressor, receiver, water-cooled condenser, high and low-pressure controls, suction accumulator, oil separator, oil level sight glass, condenser pressure regulator water valve, service valve ports (high and low side), liquid injection valve, hot gas bypass valve, liquid line dryer, moisture-indicating sight glass, manual shut-off valves, and all interconnecting piping, insulation and wiring.
 - d. Water Cooled Condenser: Provide system with remote water-cooled condenser. Include water-saving pressure regulation valve to provide constant compressor head pressure:
 - 1) Design unit to operate using facility chilled water as heat-transfer medium.
 - e. Accessories including isolation mountings and racks, interconnecting piping, piping insulation, and solenoid valves.

B. Cooling Evaporator Coils: Ceiling-mounted copper tube and aluminum fins.

1. Phenolic Coated Evaporator and any internal copper part related to the refrigeration system.
2. Insect Screens/evaporator fan mesh covers.

- C. Refrigerant Type: must meet EPA final rule (signed Oct 5, 2023)- TT Sector - Industrial Process Refrigeration.
- D. Refrigeration Valves: Solenoid type with extended stem and Rapid Cycle (20 sec).
- E. Evaporators: Ceiling mounted; copper tube and aluminum fins.
- F. Heat Load Notes:
 - 1. Outlets: 180W per duplex
 - 2. Product: 2W /ft² of chamber shelving area
 - 3. Occupancy: 200W
 - 4. Fresh air exchange: assume building air entering the chamber at 77°F and 60%RH

2.9 AIR FLOW

- A. Room is completely conditioned in a ceiling-plenum. Air is circulated via electrical fans inside the cooler unit. The ceiling plenum contains heaters, copper-tubed aluminum finned evaporator coils and dehumidify evaporators.
 - 1. Ceiling Plenum Panels: Stainless steel.
- B. Adjustable Air Diffusers: Conditioned air is circulated behind false wall plenums where it is routed horizontally across the shelves via adjustable air diffusers.
- C. Fresh Air:
 - 1. Forced air exchange system; up to 50 CFM or 6 air exchanges per hour of fresh air.

2.10 TEMPERATURE CONTROL

- A. Temperature Range: 7 to 44 °C, plus or minus 1.0 °C in a horizontal plane
- B. Temperature Control: Plus or minus 0.2 °C at set control point.
- C. Dual adjustable high and low temperature safety controls. Dual (redundant) adjustable high and low temperature safety controls, audible alarms and visual indicators are provided. The controls shutdown all power to the room, activates alarms, and automatically controls the temperature at the safety value. When the temperature returns to the normal range, the system will automatically reset.
- D. Dry-alarm contacts.
- E. Sensing device located in the chamber growth area continuously samples chamber air for accurate controlling and recording independent of lamp radiation.

2.11 HUMIDITY CONTROL

- A. Relative Humidity: 40 to 85 %RH between the temperature range of 15 - 30°C
- B. Humidifier: Ultrasonic.
- C. Dehumidification System:
 - 1. Refrigeration-based
 - 2. Chamber process air is passed over secondary, bare-tube, evaporator coils where moisture condenses
 - 3. Dehumidification coil temperatures are maintained to just above the freezing point via expansion valve(s)
 - 4. Minimum achievable relative humidity levels are based upon dew point
 - 5. Condensation sloughs off into two stainless steel drip pans (ceiling mounted), where it is captured and routed to the main chamber drain system
 - 6. Electric heaters reheat the dried air to replace heat lost from passing over the dehumidification evaporator coil(s).
- D. Sensor: Advanced Electronic RH.
 - 1. Basis of Design: Vaisala Corporation; HMP110C11A1C3A0 Intercap Module: www.vaisala.com.
 - 2. Measurement Range: 0 to 100 percent RH, with accuracy of plus or minus 3 percent RH.
- E. Control: Plus or minus 5 percent RH.
- F. Humidifier Water Requirements:
 - 1. Water Quality: RO or DI.
 - 2. Pressure Minimum: 30 psi.
 - 3. Water Consumption: 1.0 US gal per hour.

2.12 ACCESSORIES

- A. Convenience Outlets: four duplex receptacles.
- B. Fresh Air: Forced air exchange system; up to 50 CFM or 6 air exchanges per hour of fresh air

2.13 ELECTRICAL REQUIREMENTS

- A. Electrical Requirements: 120-208/3/60, 4 wire plus ground. RLA=22, MCA=27, minimum fuse size= 30A.
- B. Disconnect Switch: Lockable.

- C. Condensing Unit Electrical Requirements (independent from chamber): 208/3/60, 3 wire plus ground. RLA=10, MCA=12, minimum fuse size= 20A
- D. Condensing Unit Disconnect Switch: Lockable.

2.14 OTHER UTILITY REQUIREMENTS

- A. Building floor drain required
- B. Ethernet

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that substrates, prepared openings, and roughed-in utilities are ready to receive work and opening dimensions are as indicated on shop drawings.

3.2 INSTALLATION

- A. Assemble and install components in accordance with manufacturer's instructions and approved shop drawings.
- B. Set wall attachments on floor and anchor securely.
- C. Cut holes, install anchors, and seal room panels for plumbing, power, and lighting.
- D. Assemble wall panels; lock in place with cam locks. Brace securely until ceiling panels are installed.
- E. Install ceiling panels; lock into wall panels.
- F. Install sill plate at door opening.
- G. Hang doors. Adjust to operate smoothly.
- H. Seal joints and services through walls with sealant to provide moisture and vapor seal.
- I. Requirements for installation of Refrigeration line Sets:
 - 1. Refrigeration Piping shall be
 - a. ASTM B280 ACR type, hard drawn, type L
 - b. Nitrogenized
 - c. Clean
 - d. Dry
 - e. Capped

- f. Pressure tested to 175psi
 - g. Leak tested
2. Refrigeration Joints and Fittings shall be:
- a. ASME B16.22 wrought-copper
 - b. Copper-to-copper joints shall be brazed with Sil Fox 15a copper-phosphorous brazing alloy, containing a minimum of 15% silver and conforming to AWS A5.8, BCuP5 (15% Ag, 80% Cu, 5% P)
 - c. Dissimilar metals shall be brazed with a silver brazing alloy containing a minimum of 45% silver, conforming to AWS 5.8. BAG-5 (45% Ag, 30% Cu, 25% Zn)
 - d. When brazing refrigeration lines and fittings, inert gas shall be passed through the line at low pressure to prevent scaling and oxidation inside the tubing. Dry nitrogen is preferred.
 - e. Fittings shall be of the long radius type, prohibiting the use of close ruff or street elbows
 - f. Quick connect couplings on refrigeration systems are not allowed
 - g. Service port caps shall be hex. Thumb caps are acceptable.
 - h. Extreme care should be taken to keep line sets clean and dry prior to turnover
3. Line Set Routing and Support Requirements
- a. All vertical refrigerant lines must be supported by strut channel hangers and supports every 10 feet, or as required by local code(s)
 - b. All horizontal refrigerant lines must be supported by strut channel hangers and supports every 5 feet, or as required by local code(s)
 - c. All liquid and suction lines must be clamped securely to the strut channel
 - d. All discharge piping to and from the remote condensers shall also be clamped securely to the strut channel to minimize vibrations
 - e. Clamp assemblies shall be refrigeration cushion clamps (ex. Hydra-Zorb)
 - f. Piping supports shall be installed within 12 inches of each horizontal elbow and equipment connections
 - g. Suction lines shall be sloped toward the compressor to ensure proper oil return at ½ inch per 10 feet of horizontal run
 - h. Suitable P-type oil traps should be located at the base of each suction riser to enhance oil return to the compressor
 - i. Every vertical suction riser greater than 3 feet in height should have a "P" trap at the base to facilitate oil return up the riser
 - j. For long vertical risers in both suction and discharge lines, additional traps are recommended for each full length of pipe (approximately 20 feet) to ensure proper oil movement.
4. Insulation Requirements
- a. Suction piping is required to be insulated in its entirety, including all accessories that are a part of the refrigerant suction piping (valves, vibration isolators, p-traps, clamps, filters)
 - b. Refrigeration hot gas bypass piping shall be insulated its entirety

- c. Refrigeration piping insulation shall be pre-formed tubular, expanded closed-cell elastomeric insulation
 - d. Insulation thickness shall be a minimum of 1 inch thick overall (i.e. ½" wall thickness) and shall be in contact with 100% of the pipe surface
 - e. Insulation must be of the proper size or the piping onto which it is to be installed
 - f. Insulation installed onto horizontal pipe runs will require that an insulation protection shield be installed between the insulation and the pipe hanger
 - g. All seams and joints in the insulation are required to be sealed with the proper adhesive for the product being used, to provide a continuous vapor barrier
 - h. Piping clamps that are in contact with the suction line are required to be covered with insulation
 - i. Insulated piping that passes through a wall is required to be protected in a piping sleeve
5. Line Sizes (from each capsule to its respective condensing unit)
- a. Suction Line "7/8" OD copper ½" minimum wall thickness insulation (Armaflex as described above, or similar)
 - b. Hot Gas Line "1/2" OD copper ½" minimum wall thickness insulation (Armaflex as described above, or similar)
 - c. Liquid Line "3/8" OD copper insulation not necessary
 - d. Dehumidify Liquid Line "3/8" OD copper insulation not necessary

3.3 FIELD QUALITY CONTROL

- A. Test and adjust control equipment to ensure performance conforms to specified requirements.
- B. Operate each room and test full range of functions over a continuous 24 hour period, recording physical data on operating equipment. Continuously record temperature and humidity.
- C. Adjust and re-test any rooms not meeting requirements.

3.4 CLEANING

- A. Remove temporary protection from finished surfaces.
- B. Wash and clean floor, walls, and ceiling inside room and exposed surfaces on the outside.
- C. Clean glass, fixtures, and fittings.

3.5 PROTECTION

- A. Adequately protect installed work from damage until final acceptance by Owner.

END OF SECTION

SECTION 123553.13 - METAL LABORATORY CASEWORK

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Metal laboratory casework.
2. Utility-space framing at backs of base cabinets.
3. Filler and closure panels.
4. Laboratory countertops.
5. Shelves.
6. Laboratory accessories.
7. Water, laboratory gas, and electrical service fittings.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For laboratory casework. Include plans, elevations, sections, and attachments to other work including blocking and reinforcements required for installation.
- C. Samples: For casework finishes and materials requiring color selection.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Bedcolab.
 2. BMC, Inc.
 3. CIF Laboratory Solutions.
 4. Hamilton Laboratory Solutions, LLC.
 5. ICI Scientific.
 6. Kewaunee Scientific Corporation.
 7. Lab Crafters, Inc.
 8. Mott Manufacturing Ltd.

9. Multi-Lab, Inc.

- B. Product Designations: Drawings indicate sizes and configurations of laboratory casework by referencing designated manufacturer's catalog numbers. Other manufacturers' laboratory casework of similar sizes and similar door and drawer configurations and complying with Specifications may be considered. See Section 016000 "Product Requirements."

2.2 CASEWORK, GENERAL

- A. Casework Product Standard: Comply with SEFA 8 M, "Laboratory Grade Metal Casework."
- B. Flammable Liquid Storage: Where cabinets are indicated for solvent or flammable liquid storage, provide units that are listed and labeled as complying with requirements in NFPA 30 by a testing and inspecting agency acceptable to authorities having jurisdiction.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.3 METAL CASEWORK MATERIALS

- A. Steel Sheet: Cold-rolled, commercial steel (CS) sheet, complying with ASTM A1008/A1008M; matte finish; suitable for exposed applications.

2.4 CABINET HARDWARE

- A. General: Provide laboratory casework manufacturer's standard, commercial-quality, heavy-duty hardware complying with requirements indicated for each type.
- B. Hinges: Stainless-steel, five-knuckle hinges complying with BHMA A156.9, Grade 1, with antifriction bearings and rounded tips.
- C. Hinged-Door and Drawer Pulls: Solid-aluminum, stainless steel, or chrome-plated-brass, back-mounted pulls.
- D. Sliding-Door Pulls: Stainless steel or chrome-plated recessed flush pulls.
- E. Door Catches: Nylon-roller spring catches. Provide two catches on doors more than 48 inches high.
- F. Drawer Slides: Manufacturer's standard; complying with ANSI/BHMA A156.9.
- G. Locks: Cam or half-mortise type, brass with chrome-plated finish; complying with BHMA A156.11, Type E07281, Type E07261, Type E07111, or Type E07021.

- 1. Tumbler: Five pin.

2. Lock Locations: Provide on drawers and doors.
3. Keying: Key locks alike within each room; key each room separately.
 - a. Master key for up to 225 key changes.
4. Key Quantity: Minimum of two keys per lock.
5. Master Key System: Key locks to be operable by master key.
 - a. Master Keys: Provide two.

2.5 COUNTERTOP TABLETOP SHELF MATERIALS

- A. Epoxy: Factory-molded, modified epoxy-resin formulation with smooth, nonspecular finish.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Durcon; a Wilsonart Company.
 - b. Prime Industries, Inc.
 2. Physical Properties:
 - a. Flexural Strength: Not less than 10,000 psi.
 - b. Modulus of Elasticity: Not less than 2,000,000 psi.
 - c. Hardness (Rockwell M): Not less than 100.
 - d. Water Absorption (24 Hours): Not more than 0.02 percent.
 - e. Heat Distortion Point: Not less than 260 deg F.
 3. Chemical Resistance: Epoxy-resin material has the following ratings when tested with indicated reagents according to NEMA LD 3, Test Procedure 3.4.5:
 - a. No Effect: Acetic acid (98 percent), acetone, ammonium hydroxide (28 percent), benzene, carbon tetrachloride, dimethyl formamide, ethyl acetate, ethyl alcohol, ethyl ether, methyl alcohol, nitric acid (70 percent), phenol, sulfuric acid (60 percent), and toluene.
 - b. Slight Effect: Chromic acid (60 percent) and sodium hydroxide (50 percent).
 4. Color: Charcoal.

2.6 METAL CABINET FINISH

- A. Chemical-Resistant Finish: Finish complies with acceptance levels of cabinet surface finish tests in SEFA 8 M. Acceptance level for chemical spot test shall be no more than for Level 3 conditions.
 1. Colors for Metal Laboratory Casework Finish: White.

2.7 COUNTERTOPS, TABLETOPS , SHELVES , TROUGHES, AND SINKS

- A. Countertops, General: Provide units with smooth surfaces in uniform plane, free of defects. Make exposed edges and corners straight and uniformly beveled. Provide front and end overhang of 1 inch.
- B. Sinks, General: Provide sizes indicated or laboratory casework manufacturer's closest standard size of equal or greater volume, as approved by Architect.
 - 1. Outlets: Provide with strainers and tailpieces, NPS 1-1/2, unless otherwise indicated.
 - 2. Overflows: Where indicated, provide overflow of standard beehive or open-top design with separate strainer. Height 2 inches less than sink depth. Provide in same material as strainer.
- C. Epoxy Countertops Tabletops and Sinks:
 - 1. Countertop Fabrication: Fabricate with factory cutouts for sinks, holes for service fittings and accessories, and butt joints assembled with epoxy adhesive and concealed metal splines.
 - a. Flat Configuration: 1 inch thick with continuous drip groove on underside 1/2 inch from overhang edge.
 - 1) Edges and Corners: Rounded.
 - 2) Backsplash: Integral coved.
 - 2. Tabletop Fabrication:
 - a. Flat Configuration: 1 inch thick with continuous drip groove on underside at perimeter.
 - 1) Edges and Corners: Rounded.
 - 3. Sink Fabrication: Molded in one piece with smooth surfaces, coved corners, and bottom sloped to outlet; 1/2-inch minimum thickness.
 - a. Provide with polypropylene strainers and tailpieces.
 - b. Provide integral sinks in epoxy countertops, bonded to countertops with invisible joint line.

2.8 LABORATORY ACCESSORIES

- A. Reagent Shelves: Provide as indicated, fabricated from same material as adjacent countertop unless otherwise indicated.
- B. Burette Rods: Aluminum or stainless steel rods, 1/2 inch in diameter and 18 inches long, threaded on one end to fit tapered plug adapter for flush socket receptacle. Provide with tapered plug adapter and receptacle.

- C. Upright Rod Assembly and Metal Crossbar: Aluminum or stainless steel. Two vertical rods and one horizontal crossbar, 3/4 inch in diameter and 36 inches long unless otherwise indicated; two flush socket receptacles and two crossbar clamps. Ends of vertical rods are tapered to fit receptacles; other rod ends are rounded.
- D. Greenlaw Arm Assembly: Aluminum or stainless steel vertical rod, tapered on one end to fit flush socket receptacle. Adjustable crossbar of hardwood with black, acid-resistant finish, secured to upright with adjustable clamp. Provide with receptacle.
- E. Lattice Assembly: Aluminum or stainless steel, vertical and horizontal rod lattice assembly with 3/4-inch- diameter rods at approximately 12 inches o.c. with two flush socket receptacles for mounting.
 - 1. Size: 36 inches wide by 24 inches high.
- F. Plastic or Resin Pegboards: Polypropylene, epoxy, or phenolic-composite pegboards with removable polypropylene pegs and stainless steel drip troughs with drain outlet.
- G. Stainless Steel Pegboards: Stainless steel pegboards with removable polypropylene pegs and stainless steel drip troughs with drain outlet.
- H. Glove Dispenser: Wall mounted, 18 gauge stainless steel, 2 glove box capacity in horizontal orientation.

2.9 WATER AND LABORATORY GAS SERVICE FITTINGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Broen A/S.
 - 2. Chicago Faucets; Geberit Company.
 - 3. WaterSaver Faucet Co.
- B. Service Fittings: Provide units that comply with SEFA 7, "Recommended Practices for Fixtures." Provide fittings complete with washers, locknuts, nipples, and other installation accessories. Include wall and deck flanges, escutcheons, handle extension rods, and similar items.
 - 1. Provide units that comply with "Vandal-Resistant Faucets and Fixtures" recommendations in SEFA 7.
- C. Materials: Fabricated from cast or forged red brass unless otherwise indicated.
 - 1. Reagent-Grade Water Service Fittings: Polypropylene, PVC, or PVDF for parts in contact with water.
- D. Finish: Chromium plated.

1. Provide chemical-resistant powder coating in laboratory casework manufacturer's standard metallic brown, aluminum, white, or other color as approved by Architect.
- E. Water Valves and Faucets: Provide units complying with ASME A112.18.1, with renewable seats, designed for working pressure up to 80 psig.
1. Vacuum Breakers: Provide ASSE 1035 vacuum breakers on water fittings with serrated outlets.
 2. Aerators: Provide aerators on water fittings that do not have serrated outlets.
 3. Self-Closing Valves: Provide self-closing valves where indicated.
- F. Ball Valves: Chrome-plated ball and PTFE seals. Handle requires no more than 5 lbf to operate. Provide units designed for working pressure up to 75 psig, with serrated outlets.
1. Locking Safety Handles: Where ball valves are indicated for fuel-gas use, provide handles that must be [pushed in] [or] [pulled up] before being turned on.
- G. Ground-Key Cocks: Tapered core and handle of one-piece forged brass, ground and lapped, and held in place under constant spring pressure. Provide units designed for working pressure up to 40 psig, with serrated outlets.
- H. Steam Valves: Stainless steel seat and PTFE seat disc. Provide units designed for steam working pressure up to 20 psig, with serrated outlets.
- I. Needle Valves: Provide units with renewable, self-centering, floating cones and renewable seats of stainless steel or Monel metal, with removable serrated outlets.
1. Provide units designed for working pressure up to 60 psig .
- J. Hand of Fittings: Furnish right-hand fittings unless fitting designation is followed by "L."
- K. Remote-Control Valves: Provide needle valves, straight-through or angle type as indicated for fume hoods and where indicated.
- L. Handles: Provide three- or four-wing, molded-plastic or powder-coated-metal handles for valves unless otherwise indicated.
1. Provide lever-type handles for ground-key cocks. Lever handle aligns with outlet when valve is closed and is perpendicular to outlet when valve is fully open.
 2. Provide lever-type handles for ball valves unless otherwise indicated. Lever handle aligns with outlet when valve is closed and is perpendicular to outlet when valve is fully open.
 3. Provide heat-resistant plastic handles for steam valves.
 4. Provide knurled, molded-plastic handles for needle valves.

- M. Service-Outlet Identification: Provide color-coded plastic discs with embossed identification, secured to each service-fitting handle to be tamper resistant. Comply with SEFA 7 for colors and embossed identification.

2.10 ELECTRICAL AND COMMUNICATION SERVICE FITTINGS

- A. Service Fittings, General: Provide units complete with metal housings, receptacles, switches, pilot lights, data communication outlets, cover plates, accessories, and gaskets required for mounting on laboratory casework.
- B. Electrical Wiring Devices: Comply with requirements in Section 262726 "Wiring Devices" for receptacles, switches, pilot lights, cover plates, and accessories.
- C. Electrical Receptacles: General grade. 125 V, 20 A; NEMA WD 6, Configuration 5-20R unless otherwise indicated.
 - 1. GFCI Receptacles: Feed -through type with integral LED indicator light.
 - 2. SPD Receptacles: With LED indicator light and integral SPD in line to ground, line to neutral, and neutral to ground.
 - 3. Color of Receptacles: As selected by Architect unless otherwise indicated or required by NFPA 70.
- D. Switches: Comply with NEMA WD 1, UL 20, and FS W-S-896.
 - 1. Color of Switches: As selected by Architect unless otherwise indicated or required by NFPA 70.
- E. Cover Plates: Provide satin-finish, Type 304, stainless steel cover plates with formed, beveled edges.
- F. Cover-Plate Identification: Use 1/4-inch- high letters unless otherwise indicated. For stainless steel or chrome-plated metal, stamp or etch plate and fill in letters with black enamel.
 - 1. Provide at every cover plate.

PART 3 - EXECUTION

3.1 INSTALLATION OF CABINETS

- A. Comply with installation requirements in SEFA 2. Install level, plumb, and true in line; shim as required using concealed shims. Where laboratory casework abuts other finished work, apply filler strips and scribe for accurate fit, with fasteners concealed where practical.
- B. Base Cabinets: Fasten cabinets to utility-space framing, partition framing, wood blocking, or reinforcements in partitions, with fasteners spaced not more than 16 inches o.c. Bolt adjacent cabinets together with joints flush, tight, and uniform.

1. Where base cabinets are installed away from walls, fasten to floor at toe space at not more than 24 inches o.c. and at sides of cabinets with not less than two fasteners per side.
 - C. Wall Cabinets: Fasten to hanging strips, masonry, partition framing, blocking, or reinforcements in partitions. Fasten each cabinet through back, near top, at not less than 16 inches o.c.
 - D. Install hardware uniformly and precisely.
 - E. Adjust operating hardware so doors and drawers align and operate smoothly without warp or bind and contact points meet accurately. Lubricate operating hardware as recommended by manufacturer.
- 3.2 INSTALLATION OF COUNTERTOPS
- A. Comply with installation requirements in SEFA 2. Abut top and edge surfaces true in plane with flush hairline joints and with internal supports placed to prevent deflection. Locate joints where indicated on Shop Drawings.
 - B. Field Jointing: Where possible, make in same manner as shop-made joints, using dowels, splines, fasteners, adhesives, and sealants recommended by manufacturer. Shop prepare edges for field-made joints.
 - C. Fastening:
 1. Secure countertops, except for epoxy countertops, to cabinets with Z-type fasteners or equivalent, using two or more fasteners at each cabinet front, end, and back.
 2. Secure epoxy countertops to cabinets with epoxy cement, applied at each corner and along perimeter edges at not more than 48 inches o.c.
 3. Where necessary to penetrate countertops with fasteners, countersink heads approximately 1/8 inch and plug hole flush with material equal to countertop in chemical resistance, hardness, and appearance.
 - D. Provide holes and cutouts required for service fittings.
 - E. Seal unfinished edges and cutouts in plastic-laminate countertops with heavy coat of polyurethane varnish.
 - F. Provide scribe moldings for closures at junctures of countertop, curb, and splash with walls as recommended by manufacturer for materials involved. Match materials and finish to adjacent laboratory casework. Use chemical-resistant, permanently elastic sealing compound where recommended by manufacturer.
 - G. Dress joints smooth, remove surface scratches, and clean entire surface.

3.3 INSTALLATION OF SINKS

- A. Comply with installation requirements in SEFA 2.

3.4 INSTALLATION OF LABORATORY ACCESSORIES

- A. Install accessories according to Shop Drawings, installation requirements in SEFA 2, and manufacturer's written instructions.
- B. Securely fasten adjustable shelving supports, stainless steel shelves, and pegboards to partition framing, wood blocking, or reinforcements in partitions.
- C. Install shelf standards plumb and at heights to align shelf brackets for level shelves. Install shelving level and straight, closely fitted to other work where indicated.
- D. Securely fasten pegboards to partition framing, wood blocking, or reinforcements in partitions.

3.5 INSTALLATION OF SERVICE FITTINGS

- A. Comply with requirements in other Sections for installing water and laboratory gas service fittings and electrical devices.
- B. Install fittings in according to Shop Drawings, installation requirements in SEFA 2, and manufacturer's written instructions. Set bases and flanges of sink- and countertop-mounted fittings in sealant recommended by manufacturer of sink or countertop material. Securely anchor fittings to laboratory casework unless otherwise indicated.

3.6 CLEANING AND PROTECTING

- A. Clean finished surfaces, touch up as required, and remove or refinish damaged or soiled areas to match original factory finish, as approved by Architect.
- B. Protect countertop surfaces during construction with 6-mil plastic or other suitable water-resistant covering. Tape to underside of countertop at a minimum of 48 inches o.c.

END OF SECTION

SECTION 123661.19 - QUARTZ AGGLOMERATE COUNTERTOPS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Quartz agglomerate countertops.
2. Quartz agglomerate backsplashes.
3. Quartz agglomerate end splashes.
4. Quartz agglomerate apron fronts.

1.2 ACTION SUBMITTALS

- A. Product Data: For countertop materials.
- B. Shop Drawings: For countertops. Show materials, finishes, edge and backsplash profiles, methods of joining, and cutouts for plumbing fixtures.
- C. Samples: For each type of material exposed to view.

PART 2 - PRODUCTS

2.1 QUARTZ AGGLOMERATE COUNTERTOP MATERIALS

- A. Quartz Agglomerate: Solid sheets consisting of quartz aggregates bound together with a matrix of filled plastic resin and complying with ISFA 3-01.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cambria.
 - b. E. I. du Pont de Nemours and Company.
 - c. Wilsonart LLC.
 2. Colors and Patterns: As indicated by manufacturer's designations.
- B. Particleboard: ANSI A208.1, Grade M-2-Exterior Glue.

2.2 FABRICATION

- A. Fabricate countertops according to quartz agglomerate manufacturer's written instructions and the AWI/AWMAC/WI's "Architectural Woodwork Standards."

1. Grade: Premium.
- B. Configuration:
1. Front: Straight, slightly eased at top.
 2. Backsplash: Straight, slightly eased at corner.
 3. End Splash: Matching backsplash.
- C. Countertops: 1/2-inch- thick, quartz agglomerate with front edge built up with same material.
- D. Backsplashes: 1/2-inch- thick, quartz agglomerate.
- E. Joints:
1. Fabricate countertops without joints.
- F. Cutouts and Holes:
1. Undercounter Plumbing Fixtures: Make cutouts for fixtures[in shop] using template or pattern furnished by fixture manufacturer. Form cutouts to smooth, even curves.

2.3 INSTALLATION MATERIALS

- A. Adhesive: Product recommended by quartz agglomerate manufacturer.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Fasten countertops by screwing through corner blocks of base units into underside of countertop. Predrill holes for screws as recommended by manufacturer.
- B. Fasten subtops to cabinets by screwing through subtops into cornerblocks of base cabinets. Shim as needed to align subtops in a level plane.
- C. Secure countertops to subtops with adhesive according to quartz agglomerate manufacturer's written instructions.
- D. Bond joints with adhesive and draw tight as countertops are set. Mask areas of countertops adjacent to joints to prevent adhesive smears.
- E. Install backsplashes and end splashes by adhering to wall and countertops with adhesive.
- F. Install aprons to backing and countertops with adhesive.

- G. Complete cutouts not finished in shop. Mask areas of countertops adjacent to cutouts to prevent damage while cutting. Make cutouts to accurately fit items to be installed, and at right angles to finished surfaces unless beveling is required for clearance. Ease edges slightly to prevent snipping.
- H. Apply sealant to gaps at walls using silicone sealant.

END OF SECTION

SECTION 220513 - COMMON MOTOR REQUIREMENTS FOR PLUMBING EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on alternating-current power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

1.3 COORDINATION

- A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:
 - 1. Motor controllers.
 - 2. Torque, speed, and horsepower requirements of the load.
 - 3. Ratings and characteristics of supply circuit and required control sequence.
 - 4. Ambient and environmental conditions of installation location.

PART 2 - PRODUCTS

2.1 GENERAL MOTOR REQUIREMENTS

- A. Comply with NEMA MG 1 unless otherwise indicated.
- B. Comply with IEEE 841 for severe-duty motors.

2.2 MOTOR CHARACTERISTICS

- A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.
- B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.

2.3 POLYPHASE MOTORS

- A. Description: NEMA MG 1, Design B, medium induction motor.
- B. Efficiency: Premium efficient, as defined in NEMA MG 1.
- C. Service Factor: 1.15.
- D. Multispeed Motors: Variable torque.
 - 1. For motors with 2:1 speed ratio, consequent pole, single winding.
 - 2. For motors with other than 2:1 speed ratio, separate winding for each speed.
- E. Multispeed Motors: Separate winding for each speed.
- F. Rotor: Random-wound, squirrel cage.
- G. Bearings: Regreasable, shielded, antifriction ball bearings suitable for radial and thrust loading.
- H. Temperature Rise: Match insulation rating.
- I. Insulation: Class F.
- J. Code Letter Designation:
 - 1. Motors 15 HP and Larger: NEMA starting Code F or Code G.
 - 2. Motors Smaller Than 15 HP: Manufacturer's standard starting characteristic.
- K. Enclosure Material: Cast iron for motor frame sizes 324T and larger; rolled steel for motor frame sizes smaller than 324T.

2.4 ADDITIONAL REQUIREMENTS FOR POLYPHASE MOTORS

- A. Motors Used with Reduced-Voltage and Multispeed Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.
- B. Motors Used with Variable-Frequency Controllers:
 - 1. Windings: Copper magnet wire with moisture-resistant insulation varnish, designed and tested to resist transient spikes, high frequencies, and short time rise pulses produced by pulse-width-modulated inverters.
 - 2. Inverter-Duty Motors: Class F temperature rise; Class H insulation.
 - 3. Thermal Protection: Comply with NEMA MG 1 requirements for thermally protected motors.

2.5 SINGLE-PHASE MOTORS

- A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:

1. Permanent-split capacitor.
 2. Split phase.
 3. Capacitor start, inductor run.
 4. Capacitor start, capacitor run.
- B. Multispeed Motors: Variable-torque, permanent-split-capacitor type.
- C. Bearings: Pre-lubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.
- D. Motors 1/20 HP and Smaller: Shaded-pole type.
- E. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION

SECTION 220517 - SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Sleeves.
2. Stack-sleeve fittings.
3. Sleeve-seal systems.
4. Sleeve-seal fittings.
5. Grout.
6. Silicone sealants.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:

1.4 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

PART 2 - PRODUCTS

2.1 SLEEVES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 1. Advance Products & Systems, Inc.
 2. CALPICO, Inc.
 3. GPT; an EnPro Industries Company
- B. Cast-Iron Pipe Sleeves: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop collar.

- C. Steel Pipe Sleeves: ASTM A53/A53M, Type E, Grade B, Schedule 40, anticorrosion coated or galvanized, with plain ends and integral welded waterstop collar.
- D. Galvanized-Steel Sheet Sleeves: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- E. PVC Pipe Sleeves: ASTM D1785, Schedule 40.
- F. Molded-PVC Sleeves: With nailing flange for attaching to wooden forms.
- G. Molded-PE or -PP Sleeves: Removable, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.

2.2 STACK-SLEEVE FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Jay R. Smith Mfg. Co; a Division of Morris Group International
 - 2. Zurn Industries, LLC
- B. Description: Manufactured, Galvanized cast-iron sleeve with integral clamping flange for use in waterproof floors and roofs. Include clamping ring, bolts, and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with setscrews.

2.3 SLEEVE-SEAL SYSTEMS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Advance Products & Systems, Inc.
 - 2. CALPICO, Inc.
 - 3. GPT; an EnPro Industries Company
 - 4. Metraflex Company (The)
 - 5. Proco Products, Inc.
- B. Description:
 - 1. Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.
 - 2. Designed to form a hydrostatic seal of 20 psig minimum.
 - 3. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 4. Pressure Plates: Carbon steel.
 - 5. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, ASTM B633 of length required to secure pressure plates to sealing elements.

2.4 SLEEVE-SEAL FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Advance Products & Systems, Inc.
 2. CALPICO, Inc.
 3. GPT; an EnPro Industries Company
 4. Metraflex Company (The)
 5. Proco Products, Inc.
- B. Description: Manufactured plastic, sleeve-type, water-stop assembly made for imbedding in concrete slab or wall.
- C. Plastic or rubber water-stop collar with center opening to match piping OD.

2.5 GROUT

- A. Description: Non-shrink, for interior and exterior sealing openings in non-fire-rated walls or floors.
- B. Standard: ASTM C1107/C1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

2.6 SILICONE SEALANTS

- A. Silicone, S, NS, 25, NT: Single-component, non-sag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant, ASTM C920, Type S, Grade NS, Class 25, Use NT.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. GE Construction Sealants; Momentive Performance Materials Inc.
 - b. Permthane®/Acryl-R®; ITW Polymers Sealants North America
 - c. Polymeric Systems, Inc.
 - d. Sherwin-Williams Company (The)
 - e. The Dow Chemical Company
- B. Silicone, S, P, 25, T, NT: Single-component, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade P, Class 25, Uses T and NT. Grade P Pourable (self-leveling) formulation is for opening in floors and other horizontal surfaces that are not fire rated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. May National Associates, Inc.; a subsidiary of Sika Corporation
- C. Silicone Foam: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Smooth-On

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION

- A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.
- B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.
 1. Sleeves are not required for core-drilled holes.
- C. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.
 1. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.
 2. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.
 3. Using grout or silicone sealant, seal the space outside of sleeves in slabs and walls without sleeve-seal system.
- D. Install sleeves for pipes passing through interior partitions.
 1. Cut sleeves to length for mounting flush with both surfaces.
 2. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
 3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint.

- E. Fire-Resistance-Rated Penetrations, Horizontal Assembly Penetrations, and Smoke Barrier Penetrations: Maintain indicated fire or smoke rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with fire- and smoke-stop materials. Comply with requirements for firestopping and fill materials specified in Section 07 8413 "Penetration Firestopping."

3.2 STACK-SLEEVE-FITTING INSTALLATION

- A. Install stack-sleeve fittings in new slabs as slabs are constructed.
 - 1. Install fittings that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
 - 2. Secure flashing between clamping flanges for pipes penetrating floors with membrane waterproofing. Comply with requirements for flashing specified in Section 076200 "Sheet Metal Flashing and Trim."
 - 3. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level.
 - 4. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
 - 5. Use silicone sealant to seal the space around outside of stack-sleeve fittings.
- B. Fire-Resistance-Rated Penetrations, Horizontal Assembly Penetrations, and Smoke Barrier Penetrations: Maintain indicated fire or smoke rating of floors at pipe penetrations. Seal pipe penetrations with fire- and smoke-stop materials. Comply with requirements for firestopping specified in Section 07 8413 "Penetration Firestopping."

3.3 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.
- B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a water-tight seal.

3.4 SLEEVE-SEAL-FITTING INSTALLATION

- A. Install sleeve-seal fittings in new walls and slabs as they are constructed.
- B. Assemble fitting components of length to be flush with both surfaces of concrete slabs and walls. Position water-stop flange to be centered in concrete slab or wall.
- C. Secure nailing flanges to concrete forms.
- D. Use grout or silicone sealant to seal the space around outside of sleeve-seal fittings.

3.5 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Leak Test: After allowing for a full cure, test sleeves and sleeve seals for leaks. Repair leaks and retest until no leaks exist.
- B. Sleeves and sleeve seals will be considered defective if they do not pass tests and inspections.
- C. Prepare test and inspection reports.

3.6 SLEEVE AND SLEEVE-SEAL SCHEDULE

- A. Use sleeves and sleeve seals for the following piping-penetration applications:
 - 1. Concrete Walls below Grade:
 - a. Piping Smaller Than NPS 6: Cast-iron pipe sleeves with sleeve-seal system.
 - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
 - 2. Concrete Slabs-on-Grade:
 - a. Piping Smaller Than NPS 6: Cast-iron pipe sleeves with sleeve-seal system.
 - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
 - 3. Interior Partitions:
 - a. Piping Smaller Than NPS 6: Steel pipe sleeves.

END OF SECTION

SECTION 220518 - ESCUTCHEONS FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Escutcheons.
 - 2. Floor plates.

1.3 DEFINITIONS

- A. Existing Piping to Remain: Existing piping that is not to be removed and that is not otherwise indicated to be removed and salvaged, or removed and reinstalled.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. BrassCraft Manufacturing Co.; a Masco company.
 - 2. Dearborn Brass.
 - 3. Jones Stephens Corp.
 - 4. Keeney Manufacturing Company (The).
 - 5. Mid-America Fittings, Inc.
 - 6. ProFlo; a Ferguson Enterprises, Inc. brand.

2.2 ESCUTCHEONS

- A. One-Piece, Steel Type: With polished, chrome-plated finish and setscrew fastener.

- B. One-Piece, Stainless-Steel Type: With polished stainless-steel finish.
- C. One-Piece, Cast-Brass Type: With polished, chrome-plated finish and setscrew fastener.
- D. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped steel with polished, chrome-plated finish and spring-clip fasteners.
- E. One-Piece, Stamped-Steel Type: With polished, chrome-plated finish and spring-clip fasteners.
- F. Split-Plate, Stamped-Steel Type: With polished, chrome-plated finish; concealed hinge; and spring-clip fasteners.

2.3 FLOOR PLATES

- A. Split Floor Plates: Cast brass with concealed hinge.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.
- B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of insulated piping and with OD that completely covers opening.
 - 1. Escutcheons for New Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep pattern.
 - b. Chrome-Plated Piping: One-piece steel with polished, chrome-plated finish.
 - c. Insulated Piping: One-piece steel with polished, chrome-plated finish.
 - d. Insulated Piping: One-piece stainless steel with polished stainless-steel finish.
 - e. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece stainless steel with polished stainless-steel finish.
 - f. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece stainless steel with polished stainless-steel finish.
 - g. Bare Piping in Unfinished Service Spaces: One-piece steel with polished, chrome-plated finish.
 - h. Bare Piping in Equipment Rooms: One-piece steel with polished, chrome-plated finish.
- C. Install floor plates for piping penetrations of equipment-room floors.
- D. Install floor plates with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.
 - 1. New Piping: One-piece, floor plate.

3.2 FIELD QUALITY CONTROL

- A. Using new materials, replace broken and damaged escutcheons and floor plates.

END OF SECTION

SECTION 220519 - METERS AND GAGES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Bimetallic-actuated thermometers.
2. Liquid-in-glass thermometers.
3. Thermowells.
4. Dial-type pressure gages.
5. Gage attachments.
6. Test plugs.
7. Test-plug kits.
8. Sight flow indicators.

B. Related Requirements:

1. Section 22 1113 "Facility Water Distribution Piping" for domestic water meters and combined domestic and fire-protection water-service meters outside the building.
2. Section 22 1119 "Domestic Water Piping Specialties" for water meters.
3. Section 22 1513 "General-Service Compressed-Air Piping" for compressed air gages.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Certificates: For each type of meter and gage.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For meters and gages to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 BIMETALLIC-ACTUATED THERMOMETERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. Ashcroft Inc.
 2. Ernst Flow Industries.
 3. Marsh Bellofram.
 4. Miljoco Corporation.
 5. Nanmac Corporation.
 6. Noshok.
 7. Palmer Wahl Instrumentation Group.
 8. REOTEMP Instrument Corporation.
 9. Tel-Tru Manufacturing Company.
 10. Trerice, H. O. Co.
 11. WATTS.
 12. Weiss Instruments, Inc.
 13. Weksler Glass Thermometer Corp.
 14. WIKA Instrument Corporation.
 15. Winters Instruments - U.S.
- B. Standard: ASME B40.200.
- C. Case: Liquid-filled and sealed types; stainless steel with 3-inch nominal diameter.
- D. Dial: Nonreflective aluminum with permanently etched scale markings and scales in deg F.
- E. Connector Type(s): Union joint, rigid, bottom, with unified-inch screw threads.
- F. Connector Size: 1/2 inch, with ASME B1.1 screw threads.
- G. Stem: 0.25 or 0.375 inch in diameter; stainless steel.
- H. Window: Plain glass.
- I. Ring: Stainless steel.
- J. Element: Bimetal coil.
- K. Pointer: Dark-colored metal.
- L. Accuracy: Plus or minus 1 percent of scale range.

2.2 LIQUID-IN-GLASS THERMOMETERS

- A. Metal-Case, Industrial-Style, Liquid-in-Glass Thermometers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Flo Fab Inc.
 - b. Miljoco Corporation.
 - c. Palmer Wahl Instrumentation Group.
 - d. Tel-Tru Manufacturing Company.
 - e. Trerice, H. O. Co.
 - f. Weiss Instruments, Inc.
 - g. Weksler Glass Thermometer Corp.
 - h. Winters Instruments - U.S.
2. Standard: ASME B40.200.
3. Case: Cast aluminum; 7-inch nominal size unless otherwise indicated.
4. Case Form: Adjustable angle unless otherwise indicated.
5. Tube: Glass with magnifying lens and blue or red organic liquid.
6. Tube Background: Nonreflective aluminum with permanently etched scale markings graduated in deg F.
7. Window: Glass.
8. Stem: Aluminum and of length to suit installation.
 - a. Design for Thermowell Installation: Bare stem.
9. Connector: 1-1/4 inches, with ASME B1.1 screw threads.
10. Accuracy: Plus or minus 1 percent of scale range or one scale division, to a maximum of 1.5 percent of scale range.

2.3 THERMOWELLS

A. Thermowells:

1. Standard: ASME B40.200.
2. Description: Pressure-tight, socket-type fitting made for insertion into piping tee fitting.
3. Material for Use with Copper Tubing: CNR or CUNI.
4. Material for Use with Steel Piping: CRES.
5. Type: Stepped shank unless straight or tapered shank is indicated.
6. External Threads: NPS 1/2, NPS 3/4, or NPS 1, ASME B1.20.1 pipe threads.
7. Internal Threads: 1/2, 3/4, and 1 inch, with ASME B1.1 screw threads.
8. Bore: Diameter required to match thermometer bulb or stem.
9. Insertion Length: Length required to match thermometer bulb or stem.
10. Lagging Extension: Include on thermowells for insulated piping and tubing.
11. Bushings: For converting size of thermowell's internal screw thread to size of thermometer connection.

B. Heat-Transfer Medium: Mixture of graphite and glycerin.

2.4 PRESSURE GAGES

A. Direct-Mounted, Metal-Case, Dial-Type Pressure Gages:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ametek U.S. Gauge.
 - b. Ashcroft Inc.
 - c. Ernst Flow Industries.
 - d. Flo Fab Inc.
 - e. Marsh Bellofram.
 - f. Miljoco Corporation.
 - g. Noshok.
 - h. Palmer Wahl Instrumentation Group.
 - i. REOTEMP Instrument Corporation.
 - j. Tel-Tru Manufacturing Company.
 - k. Trerice, H. O. Co.
 - l. WATTS.
 - m. Weiss Instruments, Inc.
 - n. Weksler Glass Thermometer Corp.
 - o. WIKA Instrument Corporation.
 - p. Winters Instruments - U.S.
2. Standard: ASME B40.100.
3. Case: Liquid-filled type; cast aluminum or drawn steel; 4-1/2-inch nominal diameter.
4. Pressure-Element Assembly: Bourdon tube unless otherwise indicated.
5. Pressure Connection: Brass, with NPS 1/4, ASME B1.20.1 pipe threads and bottom-outlet type unless back-outlet type is indicated.
6. Movement: Mechanical, with link to pressure element and connection to pointer.
7. Dial: Nonreflective aluminum with permanently etched scale markings graduated in psi.
8. Pointer: Dark-colored metal.
9. Window: Glass.
10. Ring: Stainless steel.
11. Accuracy: Grade A, plus or minus 1 percent of middle half of scale range.

2.5 GAGE ATTACHMENTS

- A. Snubbers: ASME B40.100, brass; with NPS 1/4, ASME B1.20.1 pipe threads and piston-type surge-dampening device. Include extension for use on insulated piping.
- B. Valves: Brass ball, with NPS 1/4, ASME B1.20.1 pipe threads.

2.6 TEST PLUGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Flow Design, Inc.
2. Miljoco Corporation.
3. Nexus Valve, Inc.
4. Peterson Equipment Co., Inc.
5. Sisco Manufacturing Company, Inc.
6. Trerice, H. O. Co.
7. WATTS.
8. Weiss Instruments, Inc.
9. Weksler Glass Thermometer Corp.

- B. Description: Test-station fitting made for insertion into piping tee fitting.
- C. Body: Brass or stainless steel with core inserts and gasketed and threaded cap. Include extended stem on units to be installed in insulated piping.
- D. Thread Size: NPS 1/4, ASME B1.20.1 pipe thread.
- E. Minimum Pressure and Temperature Rating: 500 psig at 200 deg F.
- F. Core Inserts: Chlorosulfonated polyethylene synthetic and EPDM self-sealing rubber.

2.7 TEST-PLUG KITS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Flow Design, Inc.
 2. Miljoco Corporation.
 3. Nexus Valve, Inc.
 4. Peterson Equipment Co., Inc.
 5. Sisco Manufacturing Company, Inc.
 6. Trerice, H. O. Co.
 7. WATTS.
 8. Weiss Instruments, Inc.
- B. Furnish one test-plug kit containing two thermometers, one pressure gage and adapter, and carrying case. Thermometer sensing elements, pressure gage, and adapter probes shall be of diameter to fit test plugs and of length to project into piping.
- C. High-Range Thermometer: Small, bimetallic insertion type with 1- to 2-inch-diameter dial and tapered-end sensing element. Dial range shall be at least 0 to 220 deg F.
- D. Pressure Gage: Small, Bourdon-tube insertion type with 2- to 3-inch-diameter dial and probe. Dial range shall be at least 0 to 200 psig.
- E. Carrying Case: Metal or plastic, with formed instrument padding.

2.8 SIGHT FLOW INDICATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. ARCHON Industries, Inc.
 2. Dwyer Instruments, Inc.
 3. Ernst Flow Industries.
 4. John C. Ernst Co., Inc.
 5. KOBOLD Instruments, Inc. - USA.
 6. OPW Engineered Systems; OPW Fluid Transfer Group; a Dover company.
 7. Pentair Valves & Controls; Penberthy Brand.
 8. Rosemount Inc.; Emerson Electric Company.
- B. Description: Piping inline-installation device for visual verification of flow.
- C. Construction: Bronze or stainless-steel body, with sight glass and ball, flapper, or paddle wheel indicator, and threaded or flanged ends.
- D. Minimum Pressure Rating: 125 psig.
- E. Minimum Temperature Rating: 200 deg F.
- F. End Connections for NPS 2 and Smaller: Threaded.
- G. End Connections for NPS 2-1/2 and Larger: Flanged.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install thermowells with socket extending to center of pipe and in vertical position in piping tees.
- B. Install thermowells of sizes required to match thermometer connectors. Include bushings if required to match sizes.
- C. Install thermowells with extension on insulated piping.
- D. Fill thermowells with heat-transfer medium.
- E. Install direct-mounted thermometers in thermowells and adjust vertical and tilted positions.
- F. Install direct-mounted pressure gages in piping tees with pressure gage located on pipe at the most readable position.
- G. Install valve and snubber in piping for each pressure gage for fluids.
- H. Install test plugs in piping tees.

- I. Install thermometers in the following locations:
 - 1. Inlet and outlet of each water heater.
- J. Install pressure gages in the following locations:
 - 1. Building water service entrance into building.
 - 2. Inlet and outlet of each pressure-reducing valve.
 - 3. Suction and discharge of each domestic water pump.

3.2 CONNECTIONS

- A. Install meters and gages adjacent to machines and equipment to allow service and maintenance of meters, gages, machines, and equipment.

3.3 ADJUSTING

- A. Adjust faces of meters and gages to proper angle for best visibility.

3.4 THERMOMETER SCHEDULE

- A. Thermometers at inlet and outlet of each domestic water heater shall be one of the following:
 - 1. Liquid-filled, bimetallic-actuated type.
 - 2. Metal case, industrial-style, liquid-in-glass type.
- B. Thermometer stems shall be of length to match thermowell insertion length.

3.5 THERMOMETER SCALE-RANGE SCHEDULE

- A. Scale Range for Domestic and Industrial Cold-Water Piping: 30 to 240 deg F.
- B. Scale Range for Domestic and Industrial Hot-Water Piping: 30 to 240 deg F.

3.6 PRESSURE-GAGE SCHEDULE

- A. Pressure gages at discharge of each water service into building shall be the following:
 - 1. Liquid-filled, direct-mounted, metal case.
- B. Pressure gages at inlet and outlet of each water pressure-reducing valve shall be the following:
 - 1. Liquid-filled, direct-mounted, metal case.
- C. Pressure gages at suction and discharge of each domestic water pump shall be the following:

1. Liquid-filled, direct-mounted, metal case.

3.7 PRESSURE-GAGE SCALE-RANGE SCHEDULE

- A. Scale Range for Water Service Piping: 0 to 100 psi.
- B. Scale Range for Domestic Water Piping: 0 to 100 psi.

END OF SECTION

SECTION 220523.12 - BALL VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Bronze ball valves.
 - 2. Steel ball valves.
 - 3. Iron ball valves.

1.3 DEFINITIONS

- A. CWP: Cold working pressure.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of valve.
 - 1. Certification that products comply with NSF 61 and NSF 372.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Protect internal parts against rust and corrosion.
 - 2. Protect threads, flange faces, and soldered ends.
 - 3. Set ball valves open to minimize exposure of functional surfaces.
- B. Use the following precautions during storage:
 - 1. Maintain valve end protection.
 - 2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use operating handles or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.
- B. ASME Compliance:
 - 1. ASME B1.20.1 for threads for threaded end valves.
 - 2. ASME B16.1 for flanges on iron valves.
 - 3. ASME B16.5 for flanges on steel valves.
 - 4. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
 - 5. ASME B16.18 for solder-joint connections.
 - 6. ASME B31.9 for building services piping valves.
- C. NSF Compliance: NSF 61 and NSF 372 for valve materials for potable-water service.
- D. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.
- E. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- F. Valve Sizes: Same as upstream piping unless otherwise indicated.
- G. Valve Actuator Types:
 - 1. Gear Actuator: For quarter-turn valves NPS 4 and larger.
 - 2. Handlever: For quarter-turn valves smaller than NPS 4.
- H. Valves in Insulated Piping:
 - 1. Include 2-inch stem extensions.
 - 2. Extended operating handles of nonthermal-conductive material and protective sleeves that allow operation of valves without breaking vapor seals or disturbing insulation.
 - 3. Memory stops that are fully adjustable after insulation is applied.

2.2 BRONZE BALL VALVES

- A. Bronze Ball Valves, Three-Piece with Full Port and Stainless-Steel Trim:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - b. DynaQuip Controls.
 - c. NIBCO INC.

2. Description:
 - a. Standard: MSS SP-110.
 - b. CWP Rating: 600 psig.
 - c. Body Design: Three piece.
 - d. Body Material: Bronze.
 - e. Ends: Threaded.
 - f. Seats: PTFE.
 - g. Stem: Stainless steel.
 - h. Ball: Stainless steel, vented.
 - i. Port: Full.

2.3 STEEL BALL VALVES

A. Steel Ball Valves with Full Port, Class 150:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - b. Bray Controls USA; a division of Bray International, Inc.
 - c. DynaQuip Controls.
 - d. FNW; Ferguson Enterprises, Inc.
 - e. Hammond Valve.
 - f. Jamesbury; Metso.
 - g. Jomar Valve.
 - h. Lance Valves.
 - i. Milwaukee Valve Company.
 - j. NIBCO INC.
 - k. Stockham; a Crane Co. brand.
 - l. Viega LLC.
 - m. WATTS.

2. Description:
 - a. Standard: MSS SP-72.
 - b. CWP Rating: 285 psig.
 - c. Body Design: Split body.
 - d. Body Material: Carbon steel, ASTM A216, Type WCB.
 - e. Ends: Flanged or threaded.
 - f. Seats: PTFE.
 - g. Stem: Stainless steel.
 - h. Ball: Stainless steel, vented.
 - i. Port: Full.

B. Steel Ball Valves with Regular Port, Class 150:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
- b. FNW; Ferguson Enterprises, Inc.
- c. Hammond Valve.
- d. Jamesbury; Metso.
- e. Jomar Valve.
- f. Lance Valves.
- g. Milwaukee Valve Company.
- h. NIBCO INC.
- i. Stockham; a Crane Co. brand.

2. Description:

- a. Standard: MSS SP-72.
- b. CWP Rating: 285 psig.
- c. Body Design: Uni-body.
- d. Body Material: Carbon steel, ASTM A216, Type WCB.
- e. Ends: Flanged or threaded.
- f. Seats: PTFE.
- g. Stem: Stainless steel.
- h. Ball: Stainless steel, vented.
- i. Port: Regular.

2.4 IRON BALL VALVES

A. Iron Ball Valves, Class 125:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. American Valve, Inc.
 - b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - c. Sure Flow Equipment Inc.
 - d. WATTS.
2. Description:
 - a. Standard: MSS SP-72.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Split body.
 - d. Body Material: ASTM A126, gray iron.
 - e. Ends: Flanged or threaded.
 - f. Seats: PTFE.
 - g. Stem: Stainless steel.
 - h. Ball: Stainless steel.
 - i. Port: Full.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.
- D. Install valves in position to allow full stem movement.
- E. Install valve tags. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment" for valve tags and schedules.

3.3 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.
- B. Select valves with the following end connections:
 - 1. For Copper Tubing, NPS 2 and Smaller: Threaded ends except where solder-joint valve-end option or press-end option is indicated in valve schedules below.
 - 2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
 - 3. For Copper Tubing, NPS 5 and Larger: Flanged ends.
 - 4. For Steel Piping, NPS 2 and Smaller: Threaded ends.
 - 5. For Steel Piping, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.

6. For Steel Piping, NPS 5 and Larger: Flanged ends.

3.4 DOMESTIC and industrial HOT- AND COLD-WATER VALVE SCHEDULE

A. Pipe NPS 2 and Smaller:

1. Bronze ball valves, three-piece with full port and stainless-steel trim.

B. Pipe NPS 2-1/2 and Larger:

1. Steel and Iron Valves, NPS 2-1/2 to NPS 4: May be provided with threaded ends instead of flanged ends.
2. Steel ball valves, Class 150 with full port.
3. Iron ball valves, Class 150.

END OF SECTION

SECTION 220523.14 - CHECK VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Bronze swing check valves.
 - 2. Iron swing check valves.

1.3 DEFINITIONS

- A. CWP: Cold working pressure.
- B. EPDM: Ethylene propylene-diene terpolymer rubber.
- C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of valve.
 - 1. Certification that products comply with NSF 61.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Protect internal parts against rust and corrosion.
 - 2. Protect threads, flange faces, grooves, and weld ends.
 - 3. Set check valves in either closed or open position.
- B. Use the following precautions during storage:
 - 1. Maintain valve end protection.
 - 2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use hand-wheels or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.
- B. ASME Compliance:
 - 1. ASME B1.20.1 for threads for threaded end valves.
 - 2. ASME B16.1 for flanges on iron valves.
 - 3. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
 - 4. ASME B16.18 for solder joint.
 - 5. ASME B31.9 for building services piping valves.
- C. AWWA Compliance: Comply with AWWA C606 for grooved-end connections.
- D. Drinking Water System Components - Health Effects and Drinking Water System Components - Lead Content Compliance: NSF 61 and NSF 372.
- E. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.
- F. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- G. Valve Sizes: Same as upstream piping unless otherwise indicated.
- H. Valve Bypass and Drain Connections: MSS SP-45.

2.2 BRONZE SWING CHECK VALVES

- A. Bronze Swing Check Valves with Bronze Disc, Class 125:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. American Valve, Inc.
 - b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - c. Crane; a Crane brand.
 - d. Hammond Valve.
 - e. Jenkins Valves; a Crane Co. brand.
 - f. KITZ Corporation.
 - g. Macomb Groups (The).

- h. Milwaukee Valve Company.
- i. NIBCO INC.
- j. Powell Valves.
- k. Red-White Valve Corp.
- l. Stockham; a Crane Co. brand.
- m. WATTS.

2.Description:

- a. Standard: MSS SP-80, Type 3.
- b. CWP Rating: 200 psig.
- c. Body Design: Horizontal flow.
- d. Body Material: ASTM B62, bronze.
- e. Ends: Threaded or soldered. See valve schedule articles.
- f. Disc: Bronze.

2.3 IRON SWING CHECK VALVES

A. Iron Swing Check Valves with Metal Seats, Class 125:

1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
- b. Crane; a Crane brand.
- c. FNW; Ferguson Enterprises, Inc.
- d. Hammond Valve.
- e. Jenkins Valves; a Crane Co. brand.
- f. KITZ Corporation.
- g. Legend Valve & Fitting, Inc.
- h. Macomb Groups (The).
- i. Milwaukee Valve Company.
- j. NIBCO INC.
- k. Powell Valves.
- l. Red-White Valve Corp.
- m. Stockham; a Crane Co. brand.
- n. Sure Flow Equipment Inc.
- o. WATTS.

2.Description:

- a. Standard: MSS SP-71, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Clear or full waterway.
- d. Body Material: ASTM A126, gray iron with bolted bonnet.
- e. Ends: Flanged or threaded. See valve schedule articles.
- f. Trim: Bronze.
- g. Gasket: Asbestos free.

B. Iron Swing Check Valves with Nonmetallic-to-Metal Seats, Class 125:

1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Crane; a Crane brand.
- b. Stockham; a Crane Co. brand.

2.Description:

- a. Standard: MSS SP-71, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Clear or full waterway.
- d. Body Material: ASTM A126, gray iron with bolted bonnet.
- e. Ends: Flanged or threaded. See valve schedule articles.
- f. Trim: Composition.
- g. Seat Ring: Bronze.
- h. Disc Holder: Bronze.
- i. Disc: PTFE.
- j. Gasket: Asbestos free.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.

- D. Install valves in position to allow full stem movement.
- E. Check Valves: Install check valves for proper direction of flow.
 - 1.Swing Check Valves: In horizontal position with hinge pin level.
- F. Install valve tags. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment" for valve tags and schedules.

3.3 ADJUSTING

- A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valve applications are not indicated, use the following:
 - 1.Pump-Discharge Check Valves:
 - a. NPS 2 and Smaller: Bronze swing check valves with bronze disc.
 - b. NPS 2-1/2 and Larger for Domestic Water: Iron swing check valves with lever and weight or spring check valves.
- B. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.
- C. End Connections:
 - 1.For Copper Tubing, NPS 2 and Smaller: Threaded or soldered or press-ends.
 - 2.For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged or threaded.
 - 3.For Copper Tubing, NPS 5 and Larger: Flanged.

3.5 DOMESTIC HOT- AND COLD-WATER VALVE SCHEDULE

- A. Pipe NPS 2 and Smaller:
 - 1.Bronze swing check valves with bronze disc, Class 125, with soldered or threaded end connections.
- B. Pipe NPS 2-1/2 and Larger:
 - 1.Iron swing check valves with nonmetallic-to-metal seats, Class 125, with threaded or flanged end connections.

END OF SECTION

SECTION 220523.15 - GATE VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Iron gate valves.
 - 2. Chainwheels.

1.3 DEFINITIONS

- A. CWP: Cold working pressure.
- B. NRS: Nonrising stem.
- C. OS&Y: Outside screw and yoke.
- D. RS: Rising stem.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of valve.
 - 1. Certification that products comply with NSF 61 and NSF 372.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Protect internal parts against rust and corrosion.
 - 2. Protect threads, flange faces, grooves, and weld ends.
 - 3. Set gate valves closed to prevent rattling.
- B. Use the following precautions during storage:
 - 1. Maintain valve end protection.

2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use hand-wheels or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.
- B. ASME Compliance:
1. ASME B1.20.1 for threads for threaded end valves.
 2. ASME B16.1 for flanges on iron valves.
 3. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
 4. ASME B16.18 for solder joint.
 5. ASME B31.9 for building services piping valves.
- C. NSF Compliance: NSF 61 and NSP 372 for valve materials for potable-water service.
- D. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.
- E. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- F. Valve Sizes: Same as upstream piping unless otherwise indicated.
- G. RS Valves in Insulated Piping: With 2-inch stem extensions.
- H. Valve Bypass and Drain Connections: MSS SP-45.

2.2 IRON GATE VALVES

- A. Iron Gate Valves, NRS, Class 150:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - b. Crane; a Crane brand.
 - c. Flo Fab Inc.
 - d. Hammond Valve.
 - e. Jenkins Valves; a Crane Co. brand.
 - f. KITZ Corporation.

- g. Legend Valve & Fitting, Inc.
- h. Macomb Groups (The).
- i. Milwaukee Valve Company.
- j. NIBCO INC.
- k. Powell Valves.
- l. Red-White Valve Corp.
- m. Stockham; a Crane Co. brand.
- n. WATTS.
- o. Zurn Industries, LLC.

2. Description:

- a. Standard: MSS SP-70, Type I.
- b. CWP Rating: 200 psig.
- c. Body Material: Gray iron with bolted bonnet.
- d. Ends: Flanged.
- e. Trim: Bronze.
- f. Disc: Solid wedge.
- g. Packing and Gasket: Asbestos free.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.

- D. Install valves in position to allow full stem movement.
- E. Install valve tags. Comply with requirements in Section 22 0553 "Identification for Plumbing Piping and Equipment" for valve tags and schedules.

3.3 ADJUSTING

- A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. Use gate valves for shutoff service only.
- B. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.

3.5 DOMESTIC HOT- AND COLD-WATER VALVE SCHEDULE

- A. Pipe NPS 2-1/2 and Larger: Iron gate valves, NRS, Class 125 with flanged ends.

END OF SECTION

SECTION 220529 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Metal pipe hangers and supports.
2. Trapeze pipe hangers.
3. Thermal hanger-shield inserts.
4. Fastener systems.
5. Pipe-positioning systems.
6. Equipment supports.

B. Related Requirements:

1. Section 05 5000 "Metal Fabrications" for structural-steel shapes and plates for trapeze hangers for pipe and equipment supports.
2. Section 22 0516 "Expansion Fittings and Loops for Plumbing Piping" for pipe guides and anchors.
3. Section 22 0548.13 "Vibration Controls for Plumbing Piping and Equipment" for vibration isolation devices.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Show fabrication and installation details and include calculations for the following:

1. Trapeze pipe hangers.
2. Metal framing systems.
3. Fiberglass strut systems.
4. Pipe stands.
5. Equipment supports.

C. Delegated-Design Submittal: For trapeze hangers indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Detail fabrication and assembly of trapeze hangers.

2. Include design calculations for designing trapeze hangers.

1.4 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.
- B. Pipe Welding Qualifications: Qualify procedures and operators according to 2015 ASME Boiler and Pressure Vessel Code, Section IX.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 01 4000 "Quality Requirements," to design trapeze pipe hangers and equipment supports.
- B. Structural Performance: Hangers and supports for plumbing piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

2.2 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
 2. Galvanized Metallic Coatings: Pregalvanized, hot-dip galvanized, or electro-galvanized.
 3. Nonmetallic Coatings: Plastic coated or epoxy powder coated.
 4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
- B. Copper Pipe and Tube Hangers:
 1. Description: MSS SP-58, Types 1 through 58, copper-coated-steel, factory-fabricated components.
 2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-coated steel.

2.3 TRAPEZE PIPE HANGERS

- A. Description: MSS SP-58, Type 59, shop- or field-fabricated pipe-support assembly, made from structural-carbon-steel shapes, with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.4 THERMAL HANGER-SHIELD INSERTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Buckaroos, Inc.
 2. CADDY; nVent.
 3. Carpenter & Paterson, Inc.
 4. National Pipe Hanger Corporation.
 5. Pipe Shields Inc.
 6. Piping Technology & Products, Inc.
 7. Rilco Manufacturing Co., Inc.
 8. Value Engineered Products, Inc.
- B. Insulation-Insert Material for Cold Piping: ASTM C552, Type II cellular glass with 100-psig or ASTM C591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength and vapor barrier.
- C. Insulation-Insert Material for Hot Piping: ASTM C552, Type II cellular glass with 100-psig or ASTM C591, Type VI, Grade 1 polyisocyanurate with 125-psig minimum compressive strength.
- D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- F. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.5 FASTENER SYSTEMS

- A. Mechanical-Expansion Anchors: Insert-wedge-type anchors, for use in hardened portland cement concrete, with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-line; Eaton, Electrical Sector.
 - b. Empire Tool and Manufacturing Co., Inc.
 - c. Hilti, Inc.
 - d. ITW Ramset/Red Head; Illinois Tool Works, Inc.
 - e. MKT Fastening, LLC.

2. Indoor Applications: Zinc-coated or stainless steel.
3. Outdoor Applications: Stainless steel.

2.6 PIPE-POSITIONING SYSTEMS

- A. Description: IAPMO PS 42 positioning system composed of metal brackets, clips, and straps for positioning piping in pipe spaces; for plumbing fixtures in commercial applications.

2.7 EQUIPMENT SUPPORTS

- A. Description: Welded, shop- or field-fabricated equipment support made from structural-carbon-steel shapes.

2.8 MATERIALS

- A. Aluminum: ASTM B221.
- B. Carbon Steel: ASTM A1011/A1011M.
- C. Structural Steel: ASTM A36/A36M carbon-steel plates, shapes, and bars; black and galvanized.
- D. Stainless Steel: ASTM A240/A240M.
- E. Grout: ASTM C1107/C1107M, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with requirements in Section 07 8413 "Penetration Firestopping" for firestopping materials and installation, for penetrations through fire-rated walls, ceilings, and assemblies.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components, so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-58. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.

- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-58. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
 - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size, or install intermediate supports for smaller-diameter pipes as specified for individual pipe hangers.
 - 2. Field fabricate from ASTM A36/A36M carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.
- C. Thermal Hanger-Shield Installation: Install in pipe hanger or shield for insulated piping.
- D. Fastener System Installation:
 - 1. Install mechanical-expansion anchors in concrete, after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- E. Pipe-Positioning-System Installation: Install support devices to make rigid supply and waste piping connections to each plumbing fixture.
- F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- H. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- I. Install lateral bracing with pipe hangers and supports to prevent swaying.
- J. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms, and install reinforcing bars through openings at top of inserts.
- K. Load Distribution: Install hangers and supports, so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- L. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- M. Insulated Piping:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating Above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating Below Ambient Air Temperature: Use thermal hanger-shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.

2. Install MSS SP-58, Type 39 protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - a. Option: Thermal hanger-shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
3. Install MSS SP-58, Type 40 protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. Option: Thermal hanger-shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
6. Thermal Hanger Shields: Install with insulation of same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment, and make bearing surface smooth.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.4 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.5 PAINTING

- A. Touchup: Clean field welds and abraded, shop-painted areas. Paint exposed areas immediately after erecting hangers and supports. Use same materials as those used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.

- B. Touchup: Cleaning and touchup painting of field welds, bolted connections, and abraded, shop-painted areas on miscellaneous metal are specified in Section 09 9123 "Interior Painting."
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas, and apply galvanizing-repair paint to comply with ASTM A780/A780M.

3.6 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-58 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finishes.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and metal trapeze pipe hangers and attachments for general service applications.
- F. Use stainless-steel pipe hangers and stainless-steel attachments for hostile environment applications.
- G. Use copper-plated pipe hangers and copper attachments for copper piping and tubing.
- H. Use padded hangers for piping that is subject to scratching.
- I. Use thermal hanger-shield inserts for insulated piping and tubing.
- J. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
 - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
 - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
 - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
 - 5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
 - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
 - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.

8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
 12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
 14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
 16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
 17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction occurs.
 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction occurs.
 19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction occurs but vertical adjustment is unnecessary.
 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction occurs and vertical adjustment is unnecessary.
 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation, in addition to expansion and contraction, is required.
- K. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- L. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment of up to 6 inches for heavy loads.
 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11 split pipe rings.
 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.

- M. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable-Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- N. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 3. Thermal Hanger-Shield Inserts: For supporting insulated pipe.
- O. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.

4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load, and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- P. Comply with MSS SP-58 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- Q. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- R. Use mechanical-expansion anchors instead of building attachments where required in concrete construction.
- S. Use pipe-positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

END OF SECTION

SECTION 220548.13 - VIBRATION CONTROLS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Elastomeric isolation pads.
2. Elastomeric isolation mounts.
3. Restrained elastomeric isolation mounts.
4. Housed-spring isolators.
5. Pipe-riser resilient support.
6. Elastomeric hangers.
7. Spring hangers.
8. Snubbers.
9. Restraint accessories.
10. Post-installed concrete anchors.
11. Concrete inserts.
12. Vibration isolation equipment bases.

B. Related Requirements:

1. Section 23 0548.13 "Vibration Controls for HVAC" for devices for HVAC equipment and systems.

1.3 DEFINITIONS

- A. IBC: International Building Code.
- B. OSHPD: Office of Statewide Health Planning and Development (for the State of California owned and regulated medical facilities).

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
2. Include load rating for each wind-load-restraint fitting and assembly.

3. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of vibration isolation device component.
4. Annotate to indicate application of each product submitted and compliance with requirements.
5. Interlocking Snubbers: Include ratings for horizontal, vertical, and combined loads.

B. Shop Drawings:

1. Detail fabrication and assembly of equipment bases. Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
2. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show coordination of vibration isolation device installation for plumbing piping and equipment with other systems and equipment in the vicinity, including other supports and restraints, if any.
- B. Qualification Data: For testing agency.
- C. Welding certificates.
- D. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct testing indicated, be an NRTL as defined by OSHA in 29 CFR 1910.7 and be acceptable to authorities having jurisdiction.
- B. Welding Qualifications: Qualify procedures and personnel in accordance with AWS D1.1/D1.1M, "Structural Welding Code - Steel."

PART 2 - PRODUCTS

2.1 ELASTOMERIC ISOLATION PADS

A. Elastomeric Isolation Pads:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation.

- d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund.
 - g. Mason Industries, Inc.
 - h. Novia; A Division of C&P.
 - i. Vibration Eliminator Co., Inc.
 - j. Vibration Isolation.
 - k. Vibration Management Corp.
 - l. Vibration Mountings & Controls, Inc.
2. Fabrication: Single or multiple layers of sufficient durometer stiffness for uniform loading over pad area.
 3. Size: Factory or field cut to match requirements of supported equipment.
 4. Minimum deflection as indicated on Drawings.
 5. Pad Material: Oil- and water-resistant rubber.
 6. Infused nonwoven cotton or synthetic fibers.
 7. Load-bearing metal plates adhered to pads.
 8. Sandwich-Core Material: Resilient and elastomeric.
 - a. Infused nonwoven cotton or synthetic fibers.

2.2 ELASTOMERIC ISOLATION MOUNTS

A. Elastomeric Isolation Mounts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation.
 - d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund.
 - g. Mason Industries, Inc.
 - h. Novia; A Division of C&P.
 - i. Vibration Eliminator Co., Inc.
 - j. Vibration Isolation.
 - k. Vibration Management Corp.
 - l. Vibration Mountings & Controls, Inc.
2. Mounting Plates:
 - a. Top Plate: Encapsulated steel load transfer top plates, factory drilled and threaded with threaded studs or bolts.
 - b. Baseplate: Encapsulated steel bottom plates with holes provided for anchoring to support structure.
3. Minimum deflection as indicated on Drawings.

4. Elastomeric Material: Molded, oil-resistant rubber, neoprene, or other elastomeric material.

2.3 HOUSED-SPRING ISOLATORS

A. Freestanding, Laterally Stable, Open-Spring Isolators in Two-Part Telescoping Housing:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation.
 - d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund.
 - g. Mason Industries, Inc.
 - h. Vibration Eliminator Co., Inc.
 - i. Vibration Isolation.
 - j. Vibration Management Corp.
 - k. Vibration Mountings & Controls, Inc.
2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
6. Minimum deflection as indicated on Drawings.
7. Two-Part Telescoping Housing: A steel top and bottom frame separated by an elastomeric material and enclosing the spring isolators.
 - a. Drilled base housing for bolting to structure with an elastomeric isolator pad attached to the underside. Bases shall limit floor load to 500 psi.
 - b. Top housing with elastomeric pad.

2.4 RESTRAINED-SPRING ISOLATORS

A. Freestanding, Laterally Stable, Open-Spring Isolators with Vertical-Limit Stop Restraint:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation.
 - d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund.

- g. Mason Industries, Inc.
 - h. Novia; A Division of C&P.
 - i. Vibration Eliminator Co., Inc.
 - j. Vibration Isolation.
 - k. Vibration Management Corp.
 - l. Vibration Mountings & Controls, Inc.
2. Housing: Steel housing with vertical-limit stops to prevent spring extension due to weight being removed.
 - a. Base with holes for bolting to structure with an elastomeric isolator pad attached to the underside. Bases shall limit floor load to 500 psi.
 - b. Top plate with elastomeric pad.
 - c. Internal leveling bolt that acts as blocking during installation.
3. Restraint: Limit stop as required for equipment and authorities having jurisdiction.
4. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
5. Minimum Additional Travel: 50 percent of the required deflection at rated load.
6. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
7. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
8. Minimum deflection as indicated on Drawings.

2.5 HOUSED-RESTRAINED-SPRING ISOLATORS

- A. Freestanding, Steel, Open-Spring Isolators with Vertical-Limit Stop Restraint in Two-Part Telescoping Housing:
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation.
 - d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund.
 - g. Mason Industries, Inc.
 - h. Vibration Eliminator Co., Inc.
 - i. Vibration Isolation.
 - j. Vibration Management Corp.
 - k. Vibration Mountings & Controls, Inc.
 2. Two-Part Telescoping Housing: A steel top and bottom frame separated by an elastomeric material and enclosing the spring isolators. Housings are equipped with adjustable snubbers to limit vertical movement.
 - a. Drilled base housing for bolting to structure with an elastomeric isolator pad attached to the underside. Bases shall limit floor load to 500 psi.

- b. Threaded top housing with adjustment bolt and cap screw to fasten and level equipment.
3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
6. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
7. Minimum deflection as indicated on Drawings.

2.6 PIPE-RISER RESILIENT SUPPORT

- A. All-Directional, Acoustical Pipe Anchor Consisting of Two Steel Tubes Separated by a Minimum 1/2-inch- Thick Neoprene.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. California Dynamics Corporation.
 - b. Kinetics Noise Control, Inc.
 - c. Mason Industries, Inc.
 - d. Vibration Eliminator Co., Inc.
 - e. Vibration Management Corp.
 2. Vertical-Limit Stops: Steel and neoprene vertical-limit stops arranged to prevent vertical travel in both directions.
 3. Maximum Load Per Support: 500 psi on isolation material providing equal isolation in all directions.
 4. Minimum deflection as indicated on Drawings.

2.7 ELASTOMERIC HANGERS

- A. Elastomeric Mount in a Steel Frame with Upper and Lower Steel Hanger Rods:
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation.
 - d. Kinetics Noise Control, Inc.
 - e. Mason Industries, Inc.
 - f. Novia; A Division of C&P.
 - g. Vibration Eliminator Co., Inc.
 - h. Vibration Isolation.
 - i. Vibration Mountings & Controls, Inc.

2. Frame: Steel, fabricated with a connection for an upper threaded hanger rod and an opening on the underside to allow for a maximum of 30 degrees of angular lower hanger-rod misalignment without binding or reducing isolation efficiency.
3. Damping Element: Molded, oil-resistant rubber, neoprene, or other elastomeric material with a projecting bushing for the underside opening preventing steel-to-steel contact.
4. Minimum deflection as indicated on Drawings.

2.8 SPRING HANGERS

A. Combination Coil-Spring and Elastomeric-Insert Hanger with Spring and Insert in Compression:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation.
 - d. Kinetics Noise Control, Inc.
 - e. Mason Industries, Inc.
 - f. Novia; A Division of C&P.
 - g. Vibration Eliminator Co., Inc.
 - h. Vibration Isolation.
 - i. Vibration Management Corp.
 - j. Vibration Mountings & Controls, Inc.
2. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
6. Minimum deflection as indicated on Drawings.
7. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
8. Elastomeric Element: Molded, oil-resistant rubber or neoprene. Steel-washer-reinforced cup to support spring and bushing projecting through bottom of frame.
9. Adjustable Vertical Stop: Steel washer with neoprene washer "up-stop" on lower threaded rod.
10. Self-centering hanger rod cap to ensure concentricity between hanger rod and support spring coil.

2.9 SNUBBERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. CADDY; nVent.

2. Kinetics Noise Control, Inc.
3. Mason Industries, Inc.
4. Vibration Management Corp.
5. Vibration Mountings & Controls, Inc.

B. Description: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.

1. Post-Installed Concrete Anchor Bolts: Secure to concrete surface with post-installed concrete anchors. Anchors to be prequalified in accordance with ACI 355.2 testing and designated in accordance with ACI 318-11 Appendix D for 2012 IBC (2018 NC Building Code).
2. Preset Concrete Inserts: Prequalified in accordance with ICC-ES AC446 testing.
3. Anchors in Masonry: Design in accordance with TMS 402.
4. Resilient Isolation Washers and Bushings: Oil- and water-resistant neoprene.
5. Resilient Cushion: Maximum 1/4-inch air gap, and minimum 1/4 inch thick.

2.10 RESTRAINTS - RIGID TYPE

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. B-line; Eaton, Electrical Sector.
2. CADDY; nVent.
3. California Dynamics Corporation.
4. Hilti, Inc.
5. Isolation Technology, Inc.
6. TOLCO.
7. Unistrut; Atkore International.
8. Vibration Mountings & Controls, Inc.

B. Description: Shop- or field-fabricated bracing assembly made of AISI S110-07-S1 slotted steel channels, ANSI/ASTM A53/A53M steel pipe as per NFPA 13, or other rigid steel brace member. Includes accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; rated in tension, compression, and torsion forces.

2.11 POST-INSTALLED CONCRETE ANCHORS

A. Mechanical Anchor Bolts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-line; Eaton, Electrical Sector.
 - b. Hilti, Inc.
 - c. Mason Industries, Inc.
 - d. Powers Fasteners.
 - e. Simpson Strong-Tie Co., Inc.

- f. Unistrut; Atkore International.
 2. Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E488/E488M.
- B. Adhesive Anchor Bolts:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-line; Eaton, Electrical Sector.
 - b. Hilti, Inc.
 - c. Mason Industries, Inc.
 - d. Powers Fasteners.
 - e. Simpson Strong-Tie Co., Inc.
 - f. Unistrut; Atkore International.
 2. Drilled-in and capsule anchor system containing PVC or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E488/E488M.
- C. Expansion-type anchor bolts are not permitted for equipment in excess of 10 hp that is not vibration isolated.
1. Undercut expansion anchors are permitted.

2.12 CONCRETE INSERTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. B-line; Eaton, Electrical Sector.
 2. Hilti, Inc.
 3. Mason Industries, Inc.
 4. Powers Fasteners.
 5. Simpson Strong-Tie Co., Inc.
 6. Unistrut; Atkore International.
- B. Provide preset concrete inserts that are prequalified in accordance with ICC-ES AC466 testing.
- C. Comply with ANSI/MSS SP-58.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and equipment to receive vibration isolation devices for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Multiple Pipe Supports: Secure pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
- B. Hanger-Rod Stiffeners: Install where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to wind load forces.
- C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength is adequate to carry static forces within specified loading limits.

3.3 INSTALLATION OF VIBRATION-CONTROL DEVICES

- A. Provide vibration-control devices for systems and equipment where indicated in Equipment Schedules or Vibration-Control Device Schedules, where indicated on Drawings, or where the Specifications indicate they are to be installed on specific equipment and systems.
- B. Coordinate location of embedded connection hardware with supported equipment attachment and mounting points and with requirements for concrete reinforcement and formwork specified in Section 03 3000 "Cast-in-Place Concrete."
- C. Installation of vibration isolators must not cause any stresses, misalignment or change of position of equipment or piping.
- D. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- E. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- F. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.
- G. Post-Installed Concrete Anchors:

1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify Project structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
3. Mechanical-Type Anchor Bolts: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
4. Adhesive-Type Anchor Bolts: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
5. Set anchors to manufacturer's recommended torque, using a torque wrench.
6. Install zinc-coated steel anchors for interior and stainless-steel anchors for exterior applications.

3.4 ACCOMMODATION OF DIFFERENTIAL MOTION

- A. Provide flexible connections in piping systems where they cross structural joints and other point where differential movement may occur. Provide adequate flexibility to accommodate differential movement as determined in accordance with ASCE/SEI 7. Comply with requirements in Section 22 1116 "Domestic Water Piping" and Section 22 1119 "Domestic Water Piping Specialties" for piping flexible connections.

3.5 ADJUSTING

- A. Adjust isolators after system is at operating weight.
- B. Adjust limit stops on restrained-spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.

3.6 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Tests and Inspections:
 1. Perform tests and inspections.
 2. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.

3. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless post-connection testing has been approved), and with at least seven days' advance notice.
 4. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
 5. Test no fewer than four of each type and size of installed anchors and fasteners selected by Architect.
 6. Test to 90 percent of rated proof load of device.
 7. Measure isolator restraint clearance.
 8. Measure isolator deflection.
 9. Verify snubber minimum clearances.
 10. Test and adjust restrained-air-spring isolator controls and safeties.
- D. Remove and replace malfunctioning units and retest as specified above.
- E. Units will be considered defective if they do not pass tests and inspections.
- F. Prepare test and inspection reports.

END OF SECTION

SECTION 220553 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Equipment labels.
- 2. Pipe labels.
- 3. Valve tags.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- D. Valve numbering scheme.
- E. Valve Schedules: For each piping system to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

- A. Metal Labels for Equipment:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Brady Corporation.
 - b. Brimar Industries, Inc.
 - c. Carlton Industries, LP.
 - d. Champion America.
 - e. Craftmark Pipe Markers.

- f. emedco.
 - g. Kolbi Pipe Marker Co.
 - h. LEM Products Inc.
 - i. Marking Services, Inc.
 - j. Seton Identification Products; a Brady Corporation company.
2. Material and Thickness: Brass, 0.032-inch, stainless steel, 0.025-inch, aluminum, 0.032-inch or anodized aluminum, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 3. Letter Color: White.
 4. Background Color: Black.
 5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
 6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
 7. Fasteners: Stainless-steel rivets or self-tapping screws.
 8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- B. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), and the Specification Section number and title where equipment is specified.
- C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 WARNING SIGNS AND LABELS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Brady Corporation.
 2. Brimar Industries, Inc.
 3. Carlton Industries, LP.
 4. Champion America.
 5. Craftmark Pipe Markers.
 6. emedco.
 7. LEM Products Inc.
 8. Marking Services Inc.
 9. National Marker Company.
 10. Seton Identification Products; a Brady Corporation company.
 11. Stranco, Inc.
- B. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.

- C. Letter Color: White.
- D. Background Color: Red.
- E. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- F. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- G. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- H. Fasteners: Stainless-steel rivets or self-tapping screws.
- I. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- J. Label Content: Include caution and warning information plus emergency notification instructions.

2.3 PIPE LABELS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Actioncraft Products, Inc.; a division of Industrial Test Equipment Co., Inc.
 - 2. Brady Corporation.
 - 3. Brimar Industries, Inc.
 - 4. Carlton Industries, LP.
 - 5. Champion America.
 - 6. Craftmark Pipe Markers.
 - 7. emedco.
 - 8. Kolbi Pipe Marker Co.
 - 9. LEM Products Inc.
 - 10. Marking Services Inc.
 - 11. Seton Identification Products; a Brady Corporation company.
- B. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.
- C. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.
- D. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- E. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings; also include pipe size and an arrow indicating flow direction.

1. Flow-Direction Arrows: Integral with piping-system service lettering to accommodate both directions or as separate unit on each pipe label to indicate flow direction.
2. Lettering Size: Size letters according to ASME A13.1 for piping.

2.4 VALVE TAGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Actioncraft Products, Inc.; a division of Industrial Test Equipment Co., Inc.
 2. Brady Corporation.
 3. Brimar Industries, Inc.
 4. Carlton Industries, LP.
 5. Champion America.
 6. Craftmark Pipe Markers.
 7. emedco.
 8. Kolbi Pipe Marker Co.
 9. LEM Products Inc.
 10. Marking Services Inc.
 11. Seton Identification Products; a Brady Corporation company.
- B. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
1. Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 2. Fasteners: Brass wire-link chain.
- C. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
1. Valve-tag schedule shall be included in operation and maintenance data.

2.5 WARNING TAGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Brady Corporation.
 2. Brimar Industries, Inc.
 3. Champion America.
 4. Craftmark Pipe Markers.
 5. emedco.
 6. Kolbi Pipe Marker Co.
 7. LEM Products Inc.
 8. Marking Services Inc.
 9. Seton Identification Products; a Brady Corporation company.

- B. Description: Preprinted or partially preprinted accident-prevention tags of plasticized card stock with matte finish suitable for writing.
1. Size: Approximately 4 by 7 inches.
 2. Fasteners: Brass grommet and wire.
 3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
 4. Color: Safety yellow background with black lettering.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

3.4 PIPE LABEL INSTALLATION

- A. Piping Color Coding: Painting of piping is specified in Section 09 9123 "Interior Painting."
- B. Pipe Label Locations: Locate pipe labels where piping and hangers are exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
1. Near each valve and control device.
 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 5. Near major equipment items and other points of origination and termination.

6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
 7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
- C. Directional Flow Arrows: Arrows shall be used to indicate direction of flow in pipes, including pipes where flow is allowed in both directions.
- D. Pipe Label Color Schedule:
1. Domestic Cold-Water Piping
 - a. Background: Dark green.
 - b. Letter Colors: White.
 2. Domestic Hot and Recirculating Hot Water Piping
 - a. Background: Dark yellow (gold).
 - b. Letter Colors: Black.
 3. Sanitary Waste and Vent Piping:
 - a. Background Color: Same as surrounding area.
 - b. Letter Color: White/Black.

3.5 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves, valves within factory-fabricated equipment units, shutoff valves, faucets, convenience and lawn-watering hose connections, and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:
1. All Valve-Tag Size and Shape: 1-1/2 inches, round.
 2. All Valve-Tags are bronze with engraved letters.

3.6 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION

SECTION 220719 - PLUMBING PIPING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes insulating the following plumbing piping services:
 - 1. Domestic cold-water piping.
 - 2. Domestic hot-water piping.
 - 3. Domestic recirculating hot-water piping.
 - 4. Supplies and drains for handicap-accessible lavatories and sinks.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory and field applied if any).
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
 - 1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
 - 2. Detail attachment and covering of heat tracing inside insulation.
 - 3. Detail insulation application at pipe expansion joints for each type of insulation.
 - 4. Detail insulation application at elbows, fittings, flanges, valves, and specialties for each type of insulation.
 - 5. Detail removable insulation at piping specialties, equipment connections, and access panels.
 - 6. Detail application of field-applied jackets.
 - 7. Detail application at linkages of control devices.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.
- C. Field quality-control reports.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products in accordance with ASTM E84 by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
 - 1. Insulation Installed Indoors: Flame-spread index of 25 or less and smoke-developed index of 50 or less.
 - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less and smoke-developed index of 150 or less.
- C. Comply with the following applicable standards and other requirements specified for miscellaneous components:
 - 1. Supply and Drain Protective Shielding Guards: ICC A117.1.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 22 0529 "Hangers and Supports for Plumbing Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- C. Coordinate installation and testing of heat tracing.

1.8 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

- A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," "Outdoor, Aboveground Piping Insulation Schedule," and "Outdoor, Underground Piping Insulation Schedule" articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come into contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested in accordance with ASTM C871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable in accordance with ASTM C795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- F. Flexible Elastomeric: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C534/C534M, Type I for tubular materials.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Aeroflex USA.
 - b. Armacell LLC.
 - c. K-Flex USA.
- G. Mineral-Fiber, Preformed Pipe: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C547.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Johns Manville; a Berkshire Hathaway company.
 - b. Knauf Insulation.
 - c. Manson Insulation Inc.
 - d. Owens Corning.
 - 2. Preformed Pipe Insulation: Type I, Grade A with factory-applied ASJ.
 - 3. 850 deg F.
 - 4. Factory fabricate shapes in accordance with ASTM C450 and ASTM C585.
 - 5. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

2.2 INSULATING CEMENTS

- A. Mineral-Fiber Insulating Cement: Comply with ASTM C195.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Ramco Insulation, Inc.

2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.

- B. Flexible Elastomeric and Polyolefin Adhesive: Solvent-based adhesive.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Aeroflex USA.
- b. Armacell LLC.
- c. Foster Brand; H. B. Fuller Construction Products.
- d. K-Flex USA.

2. Flame-spread index shall be 25 or less and smoke-developed index shall be 50 or less as tested in accordance with ASTM E84.
3. Wet Flash Point: Below 0 deg F.
4. Service Temperature Range: 40 to 200 deg F.
5. Color: [Black] <Insert color>.

- C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Childers Brand; H. B. Fuller Construction Products.
- b. Foster Brand; H. B. Fuller Construction Products.

- D. Phenolic Adhesive: Solvent-based resin adhesive, with a service temperature range of minus 75 to plus 300 deg F.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Childers Brand; H. B. Fuller Construction Products.
- b. Foster Brand; H. B. Fuller Construction Products.

- E. ASJ Adhesive and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A, for bonding insulation jacket lap seams and joints.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Childers Brand; H. B. Fuller Construction Products.
 - b. Foster Brand; H. B. Fuller Construction Products.
 - c. Mon-Eco Industries, Inc.

F. PVC Jacket Adhesive: Compatible with PVC jacket.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Dow Consumer Solutions.
 - b. Johns Manville; a Berkshire Hathaway company.
 - c. P.I.C. Plastics, Inc.
 - d. Speedline Corporation.

2.4 MASTICS AND COATINGS

A. Materials shall be compatible with insulation materials, jackets, and substrates.

B. Vapor-Retarder Mastic, Water Based: Suitable for indoor use on below-ambient services.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Childers Brand; H. B. Fuller Construction Products.
 - b. Foster Brand; H. B. Fuller Construction Products.
 - c. Knauf Insulation.
 - d. Vimasco Corporation.
2. Water-Vapor Permeance: Comply with ASTM E96/E96M or ASTM F1249.
3. Service Temperature Range: 0 to plus 180 deg F.
4. Comply with MIL-PRF-19565C, Type II, for permeance requirements, with supplier listing on DOD QPD - Qualified Products Database.
5. Color: White.

C. Breather Mastic: Water based; suitable for indoor and outdoor use on above-ambient services.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Childers Brand; H. B. Fuller Construction Products.
 - b. Foster Brand; H. B. Fuller Construction Products.
 - c. Knauf Insulation.
 - d. Mon-Eco Industries, Inc.

- e. Vimasco Corporation.
2. Water-Vapor Permeance: ASTM E96/E96M, greater than 1.0 perm at manufacturer's recommended dry film thickness.
3. Service Temperature Range: 0 to plus 180 deg F.
4. Color: White.

2.5 LAGGING ADHESIVES

- A. Adhesives shall comply with MIL-A-3316C, Class I, Grade A, and shall be compatible with insulation materials, jackets, and substrates.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Childers Brand; H. B. Fuller Construction Products.
 - b. Foster Brand; H. B. Fuller Construction Products.
 - c. Vimasco Corporation.
 2. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over pipe insulation.
 3. Service Temperature Range: 20 to plus 180 deg F.
 4. Color: White.

2.6 SEALANTS

- A. Materials shall be as recommended by the insulation manufacturer and shall be compatible with insulation materials, jackets, and substrates.
- B. Joint Sealants:
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Childers Brand; H. B. Fuller Construction Products.
 - b. Foster Brand; H. B. Fuller Construction Products.
 - c. Mon-Eco Industries, Inc.
 - d. Pittsburgh Corning Corporation.
 2. Permanently flexible, elastomeric sealant.
 3. Service Temperature Range: Minus 58 to plus 176 deg F.
 4. Color: White or gray.
- C. ASJ Flashing Sealants and PVC Jacket Flashing Sealants:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Childers Brand; H. B. Fuller Construction Products.
2. Fire- and water-resistant, flexible, elastomeric sealant.
3. Service Temperature Range: Minus 40 to plus 250 deg F.
4. Color: White.

2.7 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C1136, Type I.

2.8 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C1136, Type I, unless otherwise indicated.
- B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Johns Manville; a Berkshire Hathaway company.
 - b. P.I.C. Plastics, Inc.
 - c. Proto Corporation.
 - d. Speedline Corporation.
 2. Adhesive: As recommended by jacket material manufacturer.
 3. Color: Color-code jackets based on system.
 4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
 - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

2.9 TAPES

- A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C1136.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. 3M Industrial Adhesives and Tapes Division.
 - b. Avery Dennison Corporation, Specialty Tapes Division.
 - c. Ideal Tape Co., Inc., an American Biltrite Company.
 - d. Knauf Insulation.
2. Width: 3 inches.
3. Thickness: 11.5 mils.
4. Adhesion: 90 ounces force/inch in width.
5. Elongation: 2 percent.
6. Tensile Strength: 40 lbf/inch in width.
7. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.

B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. 3M Industrial Adhesives and Tapes Division.
 - b. Ideal Tape Co., Inc., an American Biltrite Company.
2. Width: 2 inches.
3. Thickness: 6 mils.
4. Adhesion: 64 ounces force/inch in width.
5. Elongation: 500 percent.
6. Tensile Strength: 18 lbf/inch in width.

2.10 PROTECTIVE SHIELDING GUARDS

A. Protective Shielding Pipe Covers:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Buckaroos, Inc.
 - b. Just Manufacturing.
 - c. McGuire Manufacturing.
 - d. MVG Molded Products.
 - e. Plumberex Specialty Products, Inc.
 - f. Truebro.
 - g. Zurn Industries, LLC.
2. Description: Manufactured plastic wraps for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with Americans with Disabilities Act (ADA) requirements.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
 - 1. Verify that systems to be insulated have been tested and are free of defects.
 - 2. Verify that surfaces to be insulated are clean and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Clean and prepare surfaces to be insulated. Before insulating, apply a corrosion coating to insulated surfaces as follows:
 - 1. Stainless Steel: Coat 300 series stainless steel with an epoxy primer 5 mils thick and an epoxy finish 5 mils thick if operating in a temperature range of between 140 and 300 deg F. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
 - 2. Carbon Steel: Coat carbon steel operating at a service temperature of between 32 and 300 deg F with an epoxy coating. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
- C. Coordinate insulation installation with the tradesman installing heat tracing. Comply with requirements for heat tracing that apply to insulation.
- D. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless steel surfaces, use demineralized water.

3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping, including fittings, valves, and specialties.
- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and of thicknesses required for each item of pipe system, as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.

- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- G. Keep insulation materials dry during storage, application, and finishing. Replace insulation materials that get wet.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
 - 1. Install insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends attached to structure with vapor-barrier mastic.
 - 3. Install insert materials and insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
 - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- L. Install insulation with factory-applied jackets as follows:
 - 1. Draw jacket tight and smooth.
 - 2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward-clinching staples along both edges of strip, spaced 4 inches o.c.
 - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward-clinching staples along edge at 4 inches o.c.
 - a. For below-ambient services, apply vapor-barrier mastic over staples.
 - 4. Cover joints and seams with tape, in accordance with insulation material manufacturer's written instructions, to maintain vapor seal.
 - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.
- M. Cut insulation in a manner to avoid compressing insulation more than 25 percent of its nominal thickness.
- N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

- O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches in similar fashion to butt joints.
- P. For above-ambient services, do not install insulation to the following:
 - 1. Vibration-control devices.
 - 2. Testing agency labels and stamps.
 - 3. Nameplates and data plates.
 - 4. Cleanouts.

3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
 - 1. Seal penetrations with flashing sealant.
 - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
 - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
 - 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.
- C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
 - 1. Seal penetrations with flashing sealant.
 - 2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
 - 3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
 - 4. Seal jacket to wall flashing with flashing sealant.
- D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
 - 1. Comply with requirements in Section 07 8413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.
- F. Insulation Installation at Floor Penetrations:

1. Pipe: Install insulation continuously through floor penetrations.
2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 07 8413 "Penetration Firestopping."

3.5 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials, except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, Mechanical Couplings, and Unions:
 1. Install insulation over fittings, valves, strainers, flanges, mechanical couplings, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
 2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as that of adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
 3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as that used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
 4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as that used for adjacent pipe. Overlap adjoining pipe insulation by not less than 2 times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
 5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than 2 times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers, so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
 6. Insulate flanges, mechanical couplings, and unions, using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than 2 times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Stencil or label the outside insulation jacket of each union with the word "union" matching size and color of pipe labels.
 7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
 8. For services not specified to receive a field-applied jacket, except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing, using PVC tape.

- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.
- D. Install removable insulation covers at locations indicated. Installation shall conform to the following:
 - 1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as that of adjoining pipe insulation.
 - 2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union at least 2 times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless steel or aluminum bands. Select band material compatible with insulation and jacket.
 - 3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
 - 4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
 - 5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

3.6 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

- A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- B. Insulation Installation on Pipe Flanges:
 - 1. Install pipe insulation to outer diameter of pipe flange.
 - 2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
 - 3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as that of pipe insulation.
 - 4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- C. Insulation Installation on Pipe Fittings and Elbows:
 - 1. Install mitered sections of pipe insulation.
 - 2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed valve covers manufactured of same material as that of pipe insulation when available.
2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
3. Install insulation to flanges as specified for flange insulation application.
4. Secure insulation to valves and specialties, and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.7 INSTALLATION OF MINERAL-FIBER INSULATION

A. Insulation Installation on Straight Pipes and Tubes:

1. Secure each layer of preformed pipe insulation to pipe with wire or bands, and tighten bands without deforming insulation materials.
2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward-clinched staples at 6 inches o.c.
4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive, as recommended by insulation material manufacturer, and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as that of straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as that of straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.

4. Install insulation to flanges as specified for flange insulation application.

3.8 FIELD-APPLIED JACKET INSTALLATION

- A. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints. Seal with manufacturer's recommended adhesive.
 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

3.9 FINISHES

- A. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.
- B. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.
- C. Do not field paint aluminum or stainless steel jackets.

3.10 FIELD QUALITY CONTROL

- A. Owner will engage a qualified testing agency to perform tests and inspections.
- B. Engage a qualified testing agency to perform tests and inspections.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections.
- E. Tests and Inspections: Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three locations of straight pipe, three locations of threaded fittings, two locations of threaded strainers, three locations of threaded valves, and three locations of flanged valves for each pipe service defined in the "Piping Insulation Schedule, General" Article.
- F. All insulation applications will be considered defective if they do not pass tests and inspections.
- G. Prepare test and inspection reports.

3.11 PIPING INSULATION SCHEDULE, GENERAL

- A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.

- B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
1. Drainage piping located in crawl spaces.
 2. Underground piping.
 3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

3.12 INDOOR PIPING INSULATION SCHEDULE

A. Domestic Cold Water:

1. NPS 1 and Smaller: Insulation shall be the following:
 - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
2. NPS 1-1/4 and Larger: Insulation shall be the following:
 - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.

B. Domestic Hot and Recirculated Hot Water:

1. NPS 1-1/4 and Smaller: Insulation shall be the following:
 - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
2. NPS 1-1/2 and Larger: Insulation shall be the following:
 - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.

C. Floor Drains, Traps, and Sanitary Drain Piping within 10 Feet of Drain Receiving Condensate and Equipment Drain Water below 60 Deg F:

1. All Pipe Sizes: Insulation shall be one of the following:
 - a. Flexible Elastomeric: 1 inch thick.
 - b. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.

D. Hot Service Drains:

1. All Pipe Sizes: Insulation shall be the following:
 - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.

E. Hot Service Vents:

1. All Pipe Sizes: Insulation shall be the following:
 - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.

3.13 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping, Concealed:
 - 1. None.
- D. Piping, Exposed:
 - 1. PVC, Color-Coded by System: 30 mils thick.

END OF SECTION

SECTION 221116 - DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Copper tube and fittings.
 - 2. Ductile-iron pipe and fittings.
 - 3. Piping joining materials.
 - 4. Transition fittings.

1.3 ACTION SUBMITTALS

- A. Product Data:
 - 1. Pipe and tube.
 - 2. Fittings.
 - 3. Joining materials.
 - 4. Transition fittings.
- B. Sustainable Design Submittals:

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Piping layout, or BIM model, drawn to scale, showing the items described in this Section, and coordinated with all building trades.
- B. System purging and disinfecting activities report.
- C. Field quality-control reports.

1.5 FIELD CONDITIONS

- A. Interruption of Existing Water Service: Do not interrupt water service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary water service according to requirements indicated:

1. Notify Architect and Owner no fewer than two business days in advance of proposed interruption of water service.
2. Do not interrupt water service without Owner's written permission.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

- A. Potable-water piping and components shall comply with NSF 14, NSF 61, and NSF 372.

2.2 COPPER TUBE AND FITTINGS

- A. Drawn-Temper Copper Tube: ASTM B88, Type K and ASTM B88, Type L.
- B. Annealed-Temper Copper Tube: ASTM B88, Type K and ASTM B88, Type L.
- C. Cast-Copper, Solder-Joint Fittings: ASME B16.18, pressure fittings.
- D. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, pressure fittings.
- E. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.
- F. Cast Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body, with ball-and-socket, metal-to-metal seating surfaces and solder-joint or threaded ends.
- G. Wrought Copper Unions: ASME B16.22.

2.3 DUCTILE-IRON PIPE AND FITTINGS

- A. Mechanical-Joint, Ductile-Iron Pipe:
 1. AWWA C151/A21.51, with mechanical-joint bell and plain spigot end unless grooved or flanged ends are indicated.
 2. Glands, Gaskets, and Bolts: AWWA C111/A21.11, ductile- or gray-iron glands, rubber gaskets, and steel bolts.

2.4 PIPING JOINING MATERIALS

- A. Pipe-Flange Gasket Materials:
 1. AWWA C110/A21.10, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free unless otherwise indicated.
 2. Full-face or ring type unless otherwise indicated.
- B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.
- C. Solder Filler Metals: ASTM B32, lead-free alloys.

- D. Flux: ASTM B813, water flushable.
- E. Brazing Filler Metals: AWS A5.8M/A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing unless otherwise indicated.

2.5 TRANSITION FITTINGS

A. General Requirements:

- 1. Same size as pipes to be joined.
- 2. Pressure rating at least equal to pipes to be joined.
- 3. End connections compatible with pipes to be joined.

B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.

C. Sleeve-Type Transition Coupling: AWWA C219.

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Cascade Waterworks Mfg. Co.
 - b. Dresser, Inc.
 - c. Ford Meter Box Company, Inc. (The).
 - d. Jay R. Smith Mfg Co; a division of Morris Group International.
 - e. JCM Industries, Inc.
 - f. Romac Industries, Inc.
 - g. Smith-Blair, Inc.
 - h. Viking Johnson.

D. Plastic-to-Metal Transition Fittings:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Aquatherm.
 - b. Charlotte Pipe and Foundry Company.
 - c. Harvel Plastics, Inc.
 - d. Sioux Chief Manufacturing Company, Inc.
 - e. Spears Manufacturing Company.
 - f. Uponor.
- 2. Description:
 - a. CPVC or PVC one-piece fitting with manufacturer's Schedule 80 equivalent dimensions.
 - b. One end with threaded brass insert and one solvent-cement-socket or threaded end.

- E. Plastic-to-Metal Transition Unions:
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Aquatherm.
 - b. Colonial Engineering, Inc.
 - c. NIBCO INC.
 - d. Spears Manufacturing Company.
 2. Description:
 - a. CPVC or PVC four-part union.
 - b. Brass threaded end.
 - c. Solvent-cement-joint or threaded plastic end.
 - d. Rubber O-ring.
 - e. Union nut.

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS

- A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.
- B. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.
- C. Fitting Option: Extruded-tee connections and brazed joints may be used on aboveground copper tubing.
- D. Under-building-slab, domestic and industrial water, building-service piping, NPS 2.5 and smaller shall be the following:
 1. Annealed-temper copper tube, ASTM B88, Type K; wrought-copper, solder-joint fittings; and brazed. Avoid fittings below slab.
- E. Under-building-slab, domestic water, building-service piping, NPS 4 to NPS 8 and larger, shall be one of the following:
 1. Mechanical-joint, ductile-iron pipe; standard-pattern, mechanical-joint fittings; and mechanical joints.
- F. Aboveground domestic and industrial water piping, NPS 2.5 and smaller, shall be:
 1. Drawn-temper copper tube, ASTM B88, Type L; wrought-copper, solder-joint fittings; and soldered joints.
- G. Aboveground domestic and industrial water piping, NPS 2-1/2 to NPS 4, shall be the following:

1. Drawn-temper copper tube, ASTM B88, Type L; wrought-copper, solder-joint fittings; and soldered joints.

3.2 EARTHWORK

- A. Comply with requirements in Section 31 2000 "Earth Moving" for excavating, trenching, and backfilling.

3.3 INSTALLATION OF PIPING

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install copper tubing under building slab according to CDA's "Copper Tube Handbook."
- C. Install ductile-iron piping under building slab with restrained joints according to AWWA C600 and AWWA M41.
- D. Install valves according to the following:
 1. Section 22 0523.12 "Ball Valves for Plumbing Piping."
 2. Section 22 0523.14 "Check Valves for Plumbing Piping."
 3. Section 22 0523.15 "Gate Valves for Plumbing Piping."
- E. Install water-pressure-reducing valves downstream from shutoff valves. Comply with requirements for pressure-reducing valves in Section 22 1119 "Domestic Water Piping Specialties."
- F. Install domestic and industrial water piping level and plumb.
- G. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- H. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- I. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.
- J. Install piping to permit valve servicing.
- K. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than the system pressure rating used in applications below unless otherwise indicated.
- L. Install piping free of sags and bends.
- M. Install fittings for changes in direction and branch connections.

- N. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.
- O. Install pressure gauges on suction and discharge piping for each plumbing pump and packaged booster pump. Comply with requirements for pressure gauges in Section 22 0519 "Meters and Gages for Plumbing Piping."
- P. Install thermostats in hot-water circulation piping. Comply with requirements for thermostats in Section 22 1123 "Domestic Water Pumps."
- Q. Install thermometers on inlet and outlet piping from each water heater. Comply with requirements for thermometers in Section 22 0519 "Meters and Gages for Plumbing Piping."
- R. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 22 0517 "Sleeves and Sleeve Seals for Plumbing Piping."
- S. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 22 0517 "Sleeves and Sleeve Seals for Plumbing Piping."
- T. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 22 0518 "Escutcheons for Plumbing Piping."

3.4 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- C. Brazed Joints for Copper Tubing: Comply with CDA's "Copper Tube Handbook," "Braze Joints" chapter.
- D. Soldered Joints for Copper Tubing: Apply ASTM B813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B828 or CDA's "Copper Tube Handbook."
- E. Flanged Joints: Select appropriate asbestos-free, nonmetallic gasket material in size, type, and thickness suitable for domestic water service. Join flanges with gasket and bolts according to ASME B31.9.
- F. Joints for Dissimilar-Material Piping: Make joints using adapters compatible with materials of both piping systems.

3.5 INSTALLATION OF TRANSITION FITTINGS

- A. Install transition couplings at joints of dissimilar piping.
- B. Transition Fittings in Underground Domestic Water Piping:
 - 1. Fittings for NPS 1-1/2 and Smaller: Fitting-type coupling.

2. Fittings for NPS 2 and Larger: Sleeve-type coupling.

C. Transition Fittings in Aboveground Domestic Water Piping NPS 2 and Smaller: Plastic-to-metal transition fittings or unions.

3.6 INSTALLATION OF HANGERS AND SUPPORTS

A. Comply with requirements for hangers, supports, and anchor devices in Section 22 0529 "Hangers and Supports for Plumbing Piping and Equipment."

B. Install hangers for copper and ductile iron tubing and piping, with maximum horizontal spacing and minimum rod diameters, to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

C. Support horizontal piping within 12 inches of each fitting.

D. Support vertical runs of copper and ductile iron tubing and piping to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.7 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties.

B. When installing piping adjacent to equipment and machines, allow space for service and maintenance.

C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.

D. Connect domestic and industrial water piping to water-service piping with shutoff valve; extend and connect to the following:

1. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.

2. Plumbing Fixtures: Cold- and hot-water-supply piping in sizes indicated, but not smaller than that required by plumbing code.

3. Equipment: Cold- and hot-water-supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

3.8 IDENTIFICATION

A. Identify system components. Comply with requirements for identification materials and installation in Section 22 0553 "Identification for Plumbing Piping and Equipment."

3.9 ADJUSTING

- A. Perform the following adjustments before operation:
1. Close drain valves, hydrants, and hose bibbs.
 2. Open shutoff valves to fully open position.
 3. Open throttling valves to proper setting.
 4. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
 - a. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide hot-water flow in each branch.
 - b. Adjust calibrated balancing valves to flows indicated.
 5. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
 6. Remove and clean strainer screens. Close drain valves and replace drain plugs.
 7. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and are clean and ready for use.
 8. Check plumbing specialties and verify proper settings, adjustments, and operation.

3.10 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
1. Piping Inspections:
 - a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.
 - b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
 - 1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.
 - 2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.
 - c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
 - d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
 2. Piping Tests:
 - a. Fill domestic and industrial water piping. Check components to determine that they are not air bound and that piping is full of water.
 - b. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.

- c. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.
 - d. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow it to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.
 - e. Hydrostatic testing and documentation of test results for polypropylene piping to be in accordance with the manufacturer's instructions and submitted to the manufacturer upon successful completion per warranty requirements.
 - f. Repair leaks and defects with new materials, and retest piping or portion thereof until satisfactory results are obtained.
 - g. Prepare reports for tests and for corrective action required.
- B. Domestic water piping will be considered defective if it does not pass tests and inspections.
- C. Prepare test and inspection reports.

3.11 CLEANING

- A. Clean and disinfect potable domestic water piping as follows:
1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
 2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:
 - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Fill and isolate system according to either of the following:
 - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
 - 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.
 - c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
 - d. Repeat procedures if biological examination shows contamination.
 - e. Submit water samples in sterile bottles to authorities having jurisdiction.
- B. Clean non-potable domestic water piping as follows:
1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
 2. Use purging procedures prescribed by authorities having jurisdiction or; if methods are not prescribed, follow procedures described below:

- a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.
- C. Prepare and submit reports of purging and disinfecting activities. Include copies of water-sample approvals from authorities having jurisdiction.
- D. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

END OF SECTION

SECTION 221119 - DOMESTIC WATER PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Vacuum breakers.
2. Backflow preventers.
3. Water pressure-reducing valves.
4. Balancing valves.
5. Temperature-actuated, water mixing valves.
6. Strainers for domestic water piping.
7. Outlet boxes.
8. Hose stations.
9. Hose bibbs.
10. Wall hydrants.
11. Drain valves.
12. Water-hammer arresters.
13. Trap-seal primer device.
14. Trap-seal primer systems.
15. Flexible connectors.
16. Water meters.

B. Related Requirements:

1. Section 22 0519 "Meters and Gauges for Plumbing Piping" for thermometers, pressure gauges, and flow meters in domestic water piping.
2. Section 22 1116 "Domestic Water Piping" for water meters.
3. Section 22 4716 "Pressure Water Coolers" for water filters for water coolers.

1.3 DEFINITIONS

- A. AMI: Advanced Metering Infrastructure.
- B. AMR: Automatic Meter Reading.
- C. FKM: A family of fluoroelastomer materials defined by ASTM D1418.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For domestic water piping specialties.
 - 1. Include diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

- A. Test and inspection reports.
- B. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For domestic water piping specialties to include in emergency, operation, and maintenance manuals.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR PIPING SPECIALTIES

- A. Domestic water piping specialties intended to convey or dispense water for human consumption are to comply with the SDWA, requirements of authorities having jurisdiction, and NSF 61 and NSF 372, or to be certified in compliance with NSF 61 and NSF 372 by an American National Standards Institute (ANSI)-accredited third-party certification body that the weighted average lead content at wetted surfaces is less than or equal to 0.25 percent.

2.2 PERFORMANCE REQUIREMENTS

- A. Minimum Working Pressure for Domestic Water Piping Specialties: 125 psig unless otherwise indicated.

2.3 VACUUM BREAKERS

- A. Hose-Connection Vacuum Breakers:
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - b. Cash Acme, A Division of Reliance Worldwide Corporation.
 - c. Champion - Arrowhead.
 - d. Legend Valve & Fitting, Inc.

- e. MIFAB, Inc.
 - f. WATTS.
 - g. Woodford Manufacturing Company.
 - h. Zurn Industries, LLC.
2. Standard: ASSE 1011.
 3. Body: Bronze, nonremovable, with manual drain.
 4. Outlet Connection: Garden-hose threaded complying with ASME B1.20.7.
 5. Finish: Chrome or nickel plated.
- B. Laboratory-Faucet Vacuum Breakers:
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - b. WATTS.
 - c. Zurn Industries, LLC.
 2. Standard: ASSE 1035.
 3. Size: NPS 1/4 or NPS 3/8 matching faucet size.
 4. Body: Bronze.
 5. End Connections: Threaded.
 6. Finish: Chrome plated.

2.4 BACKFLOW PREVENTERS

- A. Reduced-Pressure-Principle Backflow Preventers:
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Ames Fire & Waterworks; A WATTS Brand.
 - b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - c. FEBCO; A WATTS Brand.
 - d. WATTS.
 - e. Zurn Industries, LLC.
 2. Standard: ASSE 1013.
 3. Operation: Continuous-pressure applications.
 4. Pressure Loss: 12 psig maximum, through middle third of flow range.
 5. Body: Bronze for NPS 2 and smaller; ductile or cast iron with interior lining that complies with AWWA C550 or that is FDA approved or stainless steel for NPS 2-1/2 and larger.
 6. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
 7. Configuration: Designed for horizontal, straight-through, flow.
 8. Accessories:

- a. Valves NPS 2 and Smaller: Ball type with threaded ends on inlet and outlet.
- b. Valves NPS 2-1/2 and Larger: Outside-screw and yoke-gate type with flanged ends on inlet and outlet.
- c. Air-Gap Fitting: ASME A112.1.2, matching backflow-preventer connection.

B. Backflow-Preventer Test Kits:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Ames Fire & Waterworks; A WATTS Brand.
 - b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - c. FEBCO; A WATTS Brand.
 - d. WATTS.
 - e. Zurn Industries, LLC.
2. Description: Factory calibrated, with gauges, fittings, hoses, and carrying case with test-procedure instructions.

2.5 WATER PRESSURE-REDUCING VALVES

A. Water Regulators:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - b. Cash Acme, A Division of Reliance Worldwide Corporation.
 - c. WATTS.
 - d. Zurn Industries, LLC.
2. Standard: ASSE 1003.
3. Pressure Rating: Initial working pressure of 150 psig.
4. Body: Bronze with chrome-plated finish for NPS 2 and smaller; bronze for NPS 2-1/2 and NPS 3.
5. Valves for Booster Heater Water Supply: Include integral bypass.
6. End Connections: Threaded or solder for NPS 2 and smaller; flanged or solder for NPS 2-1/2 and NPS 3.

2.6 BALANCING VALVES

A. Copper-Alloy Calibrated Balancing Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Bell & Gossett; a Xylem brand.
 - b. IMI Hydronic Engineering Inc.
 - c. Nexus Valve, Inc.
 - d. NIBCO INC.
 - e. WATTS.
2. Type: Ball or Y-pattern globe valve with two readout ports and memory-setting indicator.
 3. Body: Bronze.
 4. Size: Same as connected piping, but not larger than NPS 2.
 5. Accessories: Meter hoses, fittings, valves, differential pressure meter, and carrying case.

B. Memory-Stop Balancing Valves:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - b. Crane; a Crane brand.
 - c. Hammond Valve.
 - d. Jenkins Valves; a Crane Co. brand.
 - e. Milwaukee Valve Company.
 - f. NIBCO INC.
 - g. Red-White Valve Corp.
 - h. Stockham; a Crane Co. brand.
2. Standard: MSS SP-110 for two-piece, copper-alloy ball valves.
3. Pressure Rating: 400-psig minimum CWP.
4. Size: NPS 2 or smaller.
5. Body: Copper alloy.
6. Port: Standard or full port.
7. Ball: Chrome-plated brass or stainless steel.
8. Seats and Seals: Replaceable.
9. End Connections: Solder joint or threaded.
10. Handle: Vinyl-covered steel with memory-setting device.

2.7 TEMPERATURE-ACTUATED, WATER MIXING VALVES

A. Water-Temperature Limiting Devices:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Acorn Engineering Company; a Division of Morris Group International.
 - b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - c. Cash Acme, A Division of Reliance Worldwide Corporation.
 - d. Leonard Valve Company.
 - e. POWERS; A WATTS Brand.
 - f. Symmons Industries, Inc.

- g. TACO Comfort Solutions, Inc.
 - h. WATTS.
 - i. Zurn Industries, LLC.
- 2. Standard: ASSE 1070.
 - 3. Pressure Rating: 125 psig.
 - 4. Type: Thermostatically controlled, water mixing valve.
 - 5. Material: Bronze body with corrosion-resistant interior components.
 - 6. Connections: Threaded union inlets and outlet.
 - 7. Accessories: Check stops on hot- and cold-water supplies, and adjustable, temperature-control handle.
 - 8. Tempered-Water Setting: 90 deg F.
 - 9. Tempered-Water Design Flow Rate: 20 gpm.
 - 10. Valve Finish: Chrome plated.

B. Primary, Thermostatic, Water Mixing Valves:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Acorn Engineering Company; a Division of Morris Group International.
 - b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
 - c. Cash Acme, A Division of Reliance Worldwide Corporation.
 - d. Lawler Manufacturing Company, Inc.
 - e. Leonard Valve Company.
 - f. POWERS; A WATTS Brand.
 - g. Symmons Industries, Inc.
 - h. WATTS.
 - i. Zurn Industries, LLC.
- 2. Standard: ASSE 1017.
- 3. Pressure Rating: 125 psig minimum unless otherwise indicated.
- 4. Type: Cabinet-type, thermostatically controlled, water mixing valve.
- 5. Material: Bronze body with corrosion-resistant interior components.
- 6. Connections: Threaded union inlets and outlet.
- 7. Accessories: Manual temperature control, check stops on hot- and cold-water supplies, and adjustable, temperature-control handle.
- 8. Valve Finish: Rough bronze.
- 9. Piping Finish: Copper.
- 10. Cabinet: Factory fabricated, stainless steel, for surface mounting and with hinged, stainless steel door.

C. Individual-Fixture, Water Tempering Valves:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Acorn Engineering Company; a Division of Morris Group International.
 - b. Lawler Manufacturing Company, Inc.

- c. Leonard Valve Company.
 - d. POWERS; A WATTS Brand.
 - e. Zurn Industries, LLC.
2. Standard: ASSE 1016, thermostatically controlled, water tempering valve.
 3. Pressure Rating: 125 psig minimum unless otherwise indicated.
 4. Material: Bronze body with corrosion-resistant interior components.
 5. Temperature Control: Adjustable.
 6. Connections: Threaded inlets and outlet.
 7. Finish: Chrome plated.

2.8 STRAINERS FOR DOMESTIC WATER PIPING

A. Y-Pattern Strainers:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Keckley Company.
 - b. Titan Flow Control, Inc.
 - c. WATTS.
 - d. Zurn Industries, LLC.
2. Pressure Rating: 125 psig minimum unless otherwise indicated.
3. Body: Bronze for NPS 2 and smaller; cast iron with interior lining that complies with AWWA C550 or that is FDA approved, epoxy coated and for NPS 2-1/2 and larger.
4. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
5. Screen: Stainless steel with round perforations unless otherwise indicated.
6. Perforation Size:
 - a. Strainers NPS 2 and Smaller: 0.033 inch.
 - b. Strainers NPS 2-1/2 to NPS 4: 0.045 inch.
7. Drain: Factory-installed, hose-end drain valve.

2.9 OUTLET BOXES

A. Clothes Washer Outlet Boxes:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Acorn Engineering Company; a Division of Morris Group International.
 - b. Guy Gray, IPS Corporation.
 - c. LSP Products Group.
 - d. Oatey.
 - e. Sioux Chief Manufacturing Company, Inc.

- f. Symmons Industries, Inc.
 - g. Water-Tite, IPS Corporation.
2. Mounting: Recessed.
 3. Material and Finish: Stainless steel box and faceplate.
 4. Faucet: Combination valved fitting or separate hot- and cold-water valved fittings complying with ASME A112.18.1. Include garden-hose thread complying with ASME B1.20.7 on outlets.
 5. Drain Outlet Connection: NPS 2.
 6. Accessory: Water hammer arresters.
 7. Supply Shutoff Fittings: NPS 1/2 gate, globe, or ball valves and NPS 1/2 copper, water tubing.
 8. Drain: NPS 2 standpipe and P-trap for direct waste connection to drainage piping.
 9. Inlet Hoses: Two 60-inch- long, rubber, household clothes washer inlet hoses with female, garden-hose-thread couplings. Include rubber washers.
 10. Drain Hose: One 48-inch- long, rubber, household clothes washer drain hose with hooked end.

B. Icemaker Outlet Boxes:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Guy Gray, IPS Corporation.
 - b. LSP Products Group.
 - c. Oatey.
 - d. Sioux Chief Manufacturing Company, Inc.
 - e. Water-Tite, IPS Corporation.
2. Mounting: Recessed.
3. Material and Finish: Stainless steel box and faceplate.
4. Faucet: Valved fitting complying with ASME A112.18.1. Include NPS 1/2 or smaller copper tube outlet.
5. Accessory: Water hammer arrestor.
6. Supply Shutoff Fitting: NPS 1/2 gate, globe, or ball valve and NPS 1/2 copper, water tubing.

2.10 HOSE STATIONS

A. Hot- and Cold-Water Hose Stations:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. ARCHON Industries, Inc.
 - b. Armstrong International, Inc.
 - c. Cooney Brothers, Inc.
 - d. DynaFluid Ltd.

- e. Leonard Valve Company.
 - f. Strahman Valves, Inc.
 - g. T&S Brass and Bronze Works, Inc.
2. Standard: ASME A112.18.1.
 3. Faucet Type: Thermostatic mixing valve.
 4. Cabinet: Stainless steel enclosure with exposed valve handles, hose connection, and hose rack. Include thermometer in front.
 5. Hose-Rack Material: Stainless steel.
 6. Body Material: Bronze with stainless steel wetted parts.
 7. Body Finish: Rough bronze.
 8. Mounting: Wall, with reinforcement.
 9. Supply Fittings: Two NPS 3/4 gate, globe, or ball valves and check valves and NPS 3/4 copper, water tubing. Omit check valves if check stops are included with fitting.
 10. Hose: Manufacturer's standard, for service fluid, temperature, and pressure; 25 feet long.
 11. Nozzle: With hand-squeeze, on-off control.
 12. Vacuum Breaker: Integral or factory-installed, nonremovable, manual-drain-type, hose-connection vacuum breaker complying with ASSE 1011 or backflow preventer complying with ASSE 1052; and garden-hose thread complying with ASME B1.20.7 on outlet.

2.11 HOSE BIBBS

A. Hose Bibbs:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. MIFAB, Inc.
 - c. Prier Products, Inc.
 - d. WATTS.
 - e. Woodford Manufacturing Company.
 - f. Zurn Industries, LLC.
2. Standard: ASME A112.18.1 for sediment faucets.
3. Body Material: Bronze.
4. Seat: Bronze, replaceable.
5. Supply Connections: NPS 1/2 or NPS 3/4 threaded or solder-joint inlet.
6. Outlet Connection: Garden-hose thread complying with ASME B1.20.7.
7. Pressure Rating: 125 psig.
8. Vacuum Breaker: Integral, nonremovable, drainable, hose-connection vacuum breaker complying with ASSE 1011.
9. Finish for Equipment Rooms: Rough bronze, or chrome or nickel plated.
10. Finish for Service Areas: Chrome or nickel plated.
11. Finish for Finished Rooms: Chrome or nickel plated.
12. Operation for Equipment Rooms: Wheel handle or operating key.
13. Operation for Service Areas: Wheel handle.
14. Operation for Finished Rooms: Operating key.
15. Include operating key with each operating-key hose bibb.

16. Include wall flange with each chrome- or nickel-plated hose bibb.

2.12 WALL HYDRANTS

A. Nonfreeze Wall Hydrants:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. Josam Company.
 - c. MIFAB, Inc.
 - d. Prier Products, Inc.
 - e. WATTS.
 - f. Woodford Manufacturing Company.
 - g. Zurn Industries, LLC.
2. Standard: ASME A112.21.3M for concealed-outlet, self-draining wall hydrants.
3. Pressure Rating: 125 psig.
4. Operation: Loose key.
5. Casing and Operating Rod: Of length required to match wall thickness. Include wall clamp.
6. Inlet: NPS 3/4 or NPS 1.
7. Outlet, Concealed: With integral vacuum breaker and garden-hose thread complying with ASME B1.20.7.
8. Box: Deep, flush mounted with cover.
9. Box and Cover Finish: Rough bronze.
10. Nozzle and Wall-Plate Finish: Rough bronze.
11. Operating Keys: Two with each wall hydrant.

2.13 DRAIN VALVES

A. Ball-Valve-Type, Hose-End Drain Valves:

1. Standard: MSS SP-110 for standard-port, two-piece ball valves.
2. Pressure Rating: 400-psig minimum CWP.
3. Size: NPS 3/4.
4. Body: Copper alloy.
5. Ball: Chrome-plated brass.
6. Seats and Seals: Replaceable.
7. Handle: Vinyl-covered steel.
8. Inlet: Threaded or solder joint.
9. Outlet: Threaded, short nipple with garden-hose thread complying with ASME B1.20.7 and cap with brass chain.

B. Stop-and-Waste Drain Valves:

1. Standard: MSS SP-110 for ball valves or MSS SP-80 for gate valves.

2. Pressure Rating: 200-psig minimum CWP or Class 125.
3. Size: NPS 3/4.
4. Body: Copper alloy or ASTM B62 bronze.
5. Drain: NPS 1/8 side outlet with cap.

2.14 WATER-HAMMER ARRESTERS

A. Water-Hammer Arresters:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. AMTROL, Inc.
 - b. Jay R. Smith Mfg Co; a division of Morris Group International.
 - c. Josam Company.
 - d. MIFAB, Inc.
 - e. Precision Plumbing Products.
 - f. Sioux Chief Manufacturing Company, Inc.
 - g. WATTS.
 - h. Zurn Industries, LLC.
2. Standard: ASSE 1010 or PDI-WH 201.
3. Type: Metal bellows.
4. Size: ASSE 1010, Sizes AA and A through F, or PDI-WH 201, Sizes A through F.

2.15 TRAP-SEAL PRIMER DEVICE

A. Supply-Type, Trap-Seal Primer Device:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. Josam Company.
 - c. MIFAB, Inc.
 - d. Precision Plumbing Products.
 - e. Sioux Chief Manufacturing Company, Inc.
 - f. WATTS.
 - g. Zurn Industries, LLC.
2. Standard: ASSE 1018.
3. Pressure Rating: 125 psig minimum.
4. Body: Bronze.
5. Inlet and Outlet Connections: NPS 1/2 threaded, union, or solder joint.
6. Gravity Drain Outlet Connection: NPS 1/2 threaded or solder joint.
7. Finish: Chrome plated, or rough bronze for units used with pipe or tube that is not chrome finished.

B. Drainage-Type, Trap-Seal Primer Device:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. MIFAB, Inc.
 - c. Precision Plumbing Products.
 - d. Zurn Industries, LLC.
2. Standard: ASSE 1044, lavatory P-trap with NPS 3/8 minimum, trap makeup connection.
3. Size: NPS 1-1/4 minimum.
4. Material: Chrome-plated, cast brass.

2.16 TRAP-SEAL PRIMER SYSTEMS

A. Trap-Seal Primer Systems:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Precision Plumbing Products.
 - b. Sioux Chief Manufacturing Company, Inc.
 - c. Zurn Industries, LLC.
2. Standard: ASSE 1044.
3. Inlet Size: NPS 3/4, ASTM B88, Type L; copper, water tubing.
4. Cabinet: Surface-mounted steel box with stainless steel cover.
5. Electric Controls: 24-hour timer, solenoid valve, and manual switch for 120 V ac power.
 - a. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
6. Vacuum Breaker: ASSE 1001.
7. Number Outlets: See drawings.
8. Size Outlets: NPS 1/2.

2.17 FLEXIBLE CONNECTORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Flex-Hose Co., Inc.
2. Mason Industries, Inc.
3. Metraflex Company (The).

- B. Bronze-Hose Flexible Connectors: Corrugated-bronze tubing with bronze wire-braid covering and ends brazed to inner tubing.
 - 1. Working-Pressure Rating: Minimum 200 psig.
 - 2. End Connections NPS 2 and Smaller: Threaded copper pipe or plain-end copper tube.
 - 3. End Connections NPS 2-1/2 and Larger: Flanged copper alloy.
- C. Stainless Steel-Hose Flexible Connectors: Corrugated-stainless steel tubing with stainless steel wire-braid covering and ends welded to inner tubing.
 - 1. Working-Pressure Rating: Minimum 200 psig.
 - 2. End Connections NPS 2 and Smaller: Threaded steel-pipe nipple.
 - 3. End Connections NPS 2-1/2 and Larger: Flanged steel nipple.

PART 3 - EXECUTION

3.1 INSTALLATION OF PIPING SPECIALTIES

- A. Backflow Preventers: Install in each water supply to mechanical equipment and systems and to other equipment and water systems that may be sources of contamination. Comply with authorities having jurisdiction.
 - 1. Locate backflow preventers in same room as connected equipment or system.
 - 2. Install drain for backflow preventers with atmospheric-vent drain connection with air-gap fitting, fixed air-gap fitting, or equivalent positive pipe separation of at least two pipe diameters in drain piping and pipe-to-floor drain. Locate air-gap device attached to or under backflow preventer. Simple air breaks are unacceptable for this application.
 - 3. Do not install bypass piping around backflow preventers.
- B. Water Regulators: Install with inlet and outlet shutoff valves and bypass with memory-stop balancing valve. Install pressure gauges on inlet and outlet.
- C. Balancing Valves: Install in locations where they can easily be adjusted. Set at indicated design flow rates.
- D. Temperature-Actuated, Water Mixing Valves: Install with check stops or shutoff valves on inlets and with shutoff valve on outlet.
 - 1. Install cabinet-type units recessed in or surface mounted on wall as specified.
- E. Y-Pattern Strainers: For water, install on supply side of each water pressure-reducing valve and pump.
- F. Outlet Boxes: Install boxes recessed in wall or surface mounted on wall. Install 1-1/2-by-3-1/2-inch fire-retardant-treated-wood blocking, wall reinforcement between studs. Comply with requirements for fire-retardant-treated-wood blocking in Section 061000 "Rough Carpentry."
- G. Hose Stations: Install with check stops or shutoff valves on inlets and with thermometer on outlet.

1. Install cabinet-type units recessed in or surface mounted on wall as specified. Install 1-1/2-by-3-1/2-inch fire-retardant-treated-wood blocking, wall reinforcement between studs. Comply with requirements for fire-retardant-treated-wood blocking in Section 061000 "Rough Carpentry."

- H. Water-Hammer Arresters: Install in water piping in accordance with PDI-WH 201.
- I. Supply-Type, Trap-Seal Primer Device: Install with outlet piping pitched down toward drain trap a minimum of 1 percent, and connect to floor-drain body, trap, or inlet fitting. Adjust valve for proper flow.
- J. Drainage-Type, Trap-Seal Primer Device: Install as lavatory trap with outlet piping pitched down toward drain trap a minimum of 1 percent, and connect to floor-drain body, trap, or inlet fitting.
- K. Trap-Seal Primer Systems: Install with outlet piping pitched down toward drain trap a minimum of 1 percent, and connect to floor-drain body, trap, or inlet fitting. Adjust system for proper flow.

3.2 PIPING CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. When installing piping specialties adjacent to equipment and machines, allow space for service and maintenance.

3.3 ELECTRICAL CONNECTIONS

- A. Connect wiring in accordance with Section 26 0519 "Low-Voltage Electrical Power Conductors and Cables."
- B. Ground equipment in accordance with Section 26 0526 "Grounding and Bonding for Electrical Systems."
- C. Install electrical devices furnished by manufacturer, but not factory mounted, in accordance with NFPA 70 and NECA 1.

3.4 CONTROL CONNECTIONS

- A. Connect control wiring in accordance with Section 26 0523 "Control-Voltage Electrical Power Cables."

3.5 IDENTIFICATION

- A. Plastic Labels for Equipment: Install engraved plastic-laminate equipment nameplate or sign on or near each of the following:
 1. Vacuum breakers.

2. Backflow preventers.
3. Water pressure-reducing valves.
4. Balancing valves.
5. Temperature-actuated, water mixing valves.
6. Outlet boxes.
7. Hose stations.
8. Wall hydrants.
9. Trap-seal primer device.
10. Trap-seal primer systems.

- B. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit. Nameplates and signs are specified in Section 22 0553 "Identification for Plumbing Piping and Equipment."

3.6 ADJUSTING

- A. Set field-adjustable pressure set points of water pressure-reducing valves.
- B. Set field-adjustable flow set points of balancing valves.
- C. Set field-adjustable temperature set points of temperature-actuated, water mixing valves.
- D. Adjust each pressure vacuum breaker, reduced-pressure-principle backflow preventer, double-check, backflow-prevention assembly and double-check, detector-assembly backflow preventer in accordance with manufacturer's written instructions, authorities having jurisdiction and the device's reference standard.

3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform the following tests and inspections with the assistance of a factory-authorized service representative.
1. Test each pressure vacuum breaker, reduced-pressure-principle backflow preventer, double-check, backflow-prevention assembly and double-check, detector-assembly backflow preventer according to authorities having jurisdiction and the device's reference standard.
 2. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
 3. Operational Test: After electrical circuitry has been energized, start units to confirm unit operation.
 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

- D. Domestic water piping specialties will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports.

END OF SECTION

SECTION 221123.21 - INLINE, DOMESTIC-WATER PUMPS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. In-line, sealless centrifugal pumps.
2. Horizontally mounted, in-line, close-coupled centrifugal pumps.

B. Related Requirements:

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include construction materials, rated capacities, certified performance curves with operating points plotted on curves, operating characteristics, electrical characteristics, and furnished specialties and accessories.

B. Sustainable Design Submittals:

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Detail pumps and adjacent equipment. Show support locations, type of support, weight on each support, required clearances, and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Structural members to which pumps will be attached.
2. Size and location of initial access modules for acoustical tile.

- B. Seismic Qualification Data: Certificates, for inline, domestic-water pumps, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

- C. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For inline, domestic-water pumps to include in operation and maintenance manuals.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Retain shipping flange protective covers and protective coatings during storage.
- B. Protect bearings and couplings against damage.
- C. Comply with pump manufacturer's written instructions for handling.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. UL Compliance: UL 778 for motor-operated water pumps.
- C. Drinking Water System Components - Health Effects and Drinking Water System Components - Lead Content Compliance: NSF 61 and NSF 372.

2.2 IN-LINE, SEALLESS CENTRIFUGAL PUMPS

- A. Description: Factory-assembled and -tested, in-line, close-coupled, canned-motor, sealless, overhung-impeller centrifugal pumps.
- B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Flo Fab Inc.
 - 2. Grundfos Pumps Corp.
 - 3. TACO Comfort Solutions, Inc.
 - 4. WILO USA LLC - WILO Canada Inc.
- C. Capacities and Characteristics: See Drawing P701.
- D. Pump Construction:
 - 1. Pump and Motor Assembly: Hermetically sealed, replaceable-cartridge type with motor and impeller on common shaft and designed for installation with pump and motor shaft horizontal.

2. Minimum Working Pressure: 125 psig.
3. Maximum Continuous Operating Temperature: 220 deg F.
4. Casing: Bronze, with threaded or companion-flange connections.
5. Impeller: Stainless steel.
6. Motor: Single speed.

2.3 MOTORS

- A. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 22 0513 "Common Motor Requirements for Plumbing Equipment."
 1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.

2.4 CONTROLS

- A. Thermostats: Electric; adjustable for control of hot-water circulation] <Insert application> pump.
 1. Type: Water-immersion temperature sensor, for installation in piping.
 2. Range: 65 to 200 deg F.
 3. Enclosure: NEMA 250, Type 4X.
 4. Operation of Pump: On or off.
 5. Transformer: Provide if required.
 6. Power Requirement: 120 V ac.
 7. Settings: Start pump at 105 deg F and stop pump at 120 deg F.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in for domestic-water-piping system to verify actual locations of piping connections before pump installation.

3.2 PUMP INSTALLATION

- A. Comply with HI 1.4.
- B. Mount pumps in orientation complying with manufacturer's written instructions.
- C. Install pressure switches in water-supply piping.
- D. Install thermostats in hot-water return piping.
- E. Install time-delay relays in piping between water heaters and hot-water storage tanks.

3.3 PIPING CONNECTIONS

- A. Comply with requirements for piping specified in Section 22 1116 "Domestic Water Piping." Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Where installing piping adjacent to inline, domestic-water pumps, allow space for service and maintenance.
- C. Connect domestic-water piping to pumps. Install suction and discharge piping equal to or greater than size of pump nozzles.
- D. Install shutoff valve and strainer on suction side of each pump, and check, shutoff, and throttling valves on discharge side of each pump. Install valves same size as connected piping. Comply with requirements for strainers specified in Section 22 1119 "Domestic Water Piping Specialties." Comply with requirements for valves specified in the following:
 - 1. Section 22 0523.12 "Ball Valves for Plumbing Piping."
 - 2. Install pressure gauge at suction of each pump and pressure gauge at discharge of each pump. Install at integral pressure-gauge tappings where provided or install pressure-gauge connectors in suction and discharge piping around pumps. Comply with requirements for pressure gauges and snubbers specified in Section 22 0519 "Meters and Gages for Plumbing Piping."

3.4 CONTROL CONNECTIONS

- A. Install control and electrical power wiring to field-mounted control devices.
- B. Connect control wiring between temperature controllers and devices.
- C. Interlock pump between water heater and hot-water storage tank with water heater burner and time-delay relay.

3.5 IDENTIFICATION

- A. Identify system components. Comply with requirements for identification specified in Section 22 0553 "Identification for Plumbing Piping and Equipment" for identification of pumps.

3.6 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections with the assistance of a factory-authorized service representative.
- E. Tests and Inspections:

1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
 2. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- F. Inline, domestic-water pump will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.

3.7 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
1. Complete installation and startup checks according to manufacturer's written instructions.
 2. Check piping connections for tightness.
 3. Clean strainers on suction piping.
 4. Perform the following startup checks for each pump before starting:
 - a. Verify bearing lubrication.
 - b. Verify that pump is free to rotate by hand and that pump for handling hot liquid is free to rotate with pump hot and cold. If pump is bound or drags, do not operate until cause of trouble is determined and corrected.
 - c. Verify that pump is rotating in the correct direction.
 5. Prime pump by opening suction valves and closing drains, and prepare pump for operation.
 6. Start motor.
 7. Open discharge valve slowly.
 8. Adjust temperature settings on thermostats.
 9. Adjust timer settings.

3.8 ADJUSTING

- A. Adjust inline, domestic-water pumps to function smoothly, and lubricate as recommended by manufacturer.
- B. Adjust initial temperature set points.
- C. Set field-adjustable switches and circuit-breaker trip ranges as indicated.

END OF SECTION

SECTION 221316 - SANITARY WASTE AND VENT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Hub-and-spigot, cast-iron soil pipe and fittings.
2. Hubless, cast-iron soil pipe and fittings.
3. ABS pipe and fittings.
4. PVC pipe and fittings.

B. Related Requirements:

1. Section 22 6600 "Chemical-Waste Systems for Laboratory and Healthcare Facilities" for chemical-waste and vent piping systems.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:
- C. Shop Drawings: For hubless, single-stack drainage system. Include plans, elevations, sections, and details.

1.4 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.5 FIELD CONDITIONS

- A. Interruption of Existing Sanitary Waste Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
 1. Notify Architect and Owner no fewer than two days in advance of proposed interruption of sanitary waste service.

2. Do not proceed with interruption of sanitary waste service without Owner's written permission.

1.6 WARRANTY

- A. Listed manufacturers to provide labeling and warranty of their respective products.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Components and installation shall be capable of withstanding the following minimum working pressure unless otherwise indicated:
 1. Soil, Waste, and Vent Piping: 10-foot head of water.

2.2 PIPING MATERIALS

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.3 HUB-AND-SPIGOT, CAST-IRON SOIL PIPE AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. AB & I Foundry; a part of the McWane family of companies.
 2. Charlotte Pipe and Foundry Company.
 3. NewAge Casting.
 4. Tyler Pipe; a part of McWane family of companies.
- B. Pipe and Fittings: ASTM A 74, Service class.
- C. Gaskets: ASTM C 564, rubber.
- D. Caulking Materials: ASTM B 29, pure lead and oakum or hemp fiber.

2.4 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. AB & I Foundry; a part of the McWane family of companies.
 2. Charlotte Pipe and Foundry Company.

3. NewAge Casting.
 4. Tyler Pipe; a part of McWane family of companies.
- B. Pipe and Fittings: ASTM A 888 or CISPI 301.
- C. CISPI, Hubless-Piping Couplings:
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. ANACO-Husky.
 - b. Charlotte Pipe and Foundry Company.
 - c. Dallas Specialty & Mfg. Co.
 - d. Fernco Inc.
 - e. Ideal Clamp Products, Inc.
 - f. Josam Company.
 - g. Matco-Norca.
 - h. MIFAB, Inc.
 - i. Mission Rubber Company, LLC; a division of MCP Industries.
 - j. NewAge Casting.
 - k. Tyler Pipe; a subsidiary of McWane Inc.
 2. Standards: ASTM C 1277 and CISPI 310.
 3. Description: Stainless-steel corrugated shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.

2.5 ABS PIPE AND FITTINGS

- A. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping and "NSF-sewer" for plastic sewer piping.
- B. Solid-Wall ABS Pipe: ASTM D 2661, Schedule 40.
- C. Cellular-Core ABS Pipe: ASTM F 628, Schedule 40.
- D. ABS Socket Fittings: ASTM D 2661, made to ASTM D 3311, drain, waste, and vent patterns.
- E. Solvent Cement: ASTM D 2235.

2.6 PVC PIPE AND FITTINGS

- A. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping and "NSF-sewer" for plastic sewer piping.
- B. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.

- C. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.
- D. Adhesive Primer: ASTM F 656.
- E. Solvent Cement: ASTM D 2564.

2.7 SPECIALTY PIPE FITTINGS

A. Transition Couplings:

- 1. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
- 2. Unshielded, Nonpressure Transition Couplings:
 - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1) Dallas Specialty & Mfg. Co.
 - 2) Fernco Inc.
 - 3) Froet Industries LLC.
 - 4) Mission Rubber Company, LLC; a division of MCP Industries.
 - 5) Plastic Oddities.
 - b. Standard: ASTM C 1173.
 - c. Description: Elastomeric, sleeve-type, reducing or transition pattern. Include shear ring and corrosion-resistant-metal tension band and tightening mechanism on each end.
 - d. End Connections: Same size as and compatible with pipes to be joined.
 - e. Sleeve Materials:
 - 1) For Cast-Iron Soil Pipes: ASTM C 564, rubber.
 - 2) For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
 - 3) For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.
- 3. Shielded, Nonpressure Transition Couplings:
 - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1) Cascade Waterworks Mfg. Co.
 - 2) Mission Rubber Company, LLC; a division of MCP Industries.
 - b. Standard: ASTM C 1460.
 - c. Description: Elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.

- d. End Connections: Same size as and compatible with pipes to be joined.

PART 3 - EXECUTION

3.1 EARTH MOVING

- A. Comply with requirements for excavating, trenching, and backfilling specified in Section 31 2000 "Earth Moving."

3.2 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems.
 1. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations.
 2. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends.
 1. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical.
 2. Use long-turn, double Y-branch and 1/8-bend fittings if two fixtures are installed back to back or side by side with common drain pipe.
 - a. Straight tees, elbows, and crosses may be used on vent lines.
 3. Do not change direction of flow more than 90 degrees.

4. Use proper size of standard increasers and reducers if pipes of different sizes are connected.
 - a. Reducing size of waste piping in direction of flow is prohibited.
- K. Lay buried building waste piping beginning at low point of each system.
 1. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream.
 2. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
 3. Maintain swab in piping and pull past each joint as completed.
- L. Install soil and waste and vent piping at the following minimum slopes unless otherwise indicated:
 1. Building Sanitary Waste: 2 percent downward in direction of flow for piping NPS 3 and smaller; 1 percent downward in direction of flow for piping NPS 4 and larger.
 2. Horizontal Sanitary Waste Piping: 2 percent downward in direction of flow.
 3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- M. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
 1. Install encasement on underground piping according to ASTM A 674 or AWWA C105/A 21.5.
- N. Install aboveground ABS piping according to ASTM D 2661.
- O. Install aboveground PVC piping according to ASTM D 2665.
- P. Install underground ABS and PVC piping according to ASTM D 2321.
- Q. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.
- R. Install sleeves for piping penetrations of walls, ceilings, and floors.
 1. Comply with requirements for sleeves specified in Section 22 0517 "Sleeves and Sleeve Seals for Plumbing Piping."
- S. Install sleeve seals for piping penetrations of concrete walls and slabs.
 1. Comply with requirements for sleeve seals specified in Section 22 0517 "Sleeves and Sleeve Seals for Plumbing Piping."
- T. Install escutcheons for piping penetrations of walls, ceilings, and floors.
 1. Comply with requirements for escutcheons specified in Section 22 0518 "Escutcheons for Plumbing Piping."

3.3 JOINT CONSTRUCTION

- A. Join hub-and-spigot, cast-iron soil piping with gasket joints according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for compression joints.
- B. Join hubless, cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-piping coupling joints.
- C. Plastic, Nonpressure-Piping, Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
 - 1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
 - 2. ABS Piping: Join according to ASTM D 2235 and ASTM D 2661 appendixes.
 - 3. PVC Piping: Join according to ASTM D 2855 and ASTM D 2665 appendixes.

3.4 SPECIALTY PIPE FITTING INSTALLATION

- A. Transition Couplings:
 - 1. Install transition couplings at joints of piping with small differences in ODs.
 - 2. In Waste Drainage Piping: Unshielded, nonpressure transition couplings.

3.5 INSTALLATION OF HANGERS AND SUPPORTS

- A. Comply with requirements for seismic-restraint devices specified in Section 22 0548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Comply with requirements for pipe hanger and support devices and installation specified in Section 22 0529 "Hangers and Supports for Plumbing Piping and Equipment."
 - 1. Install carbon-steel pipe hangers for horizontal piping in noncorrosive environments.
 - 2. Install stainless-steel pipe hangers for horizontal piping in corrosive environments.
 - 3. Install carbon-steel pipe support clamps for vertical piping in noncorrosive environments.
 - 4. Install stainless-steel pipe support clamps for vertical piping in corrosive environments.
 - 5. Vertical Piping: MSS Type 8 or Type 42, clamps.
 - 6. Install individual, straight, horizontal piping runs:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
 - c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.
 - 7. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
 - 8. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Install hangers for cast-iron soil piping, with maximum horizontal spacing and minimum rod diameters, to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

- D. Install hangers for ABS and PVC piping, with maximum horizontal spacing and minimum rod diameters, to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- E. Support horizontal piping and tubing within 12 inches of each fitting and coupling.
- F. Support vertical runs of cast iron soil piping to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- G. Support vertical runs of ABS and PVC piping to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.6 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.
- C. Connect waste and vent piping to the following:
 - 1. Plumbing Fixtures: Connect waste piping in sizes indicated, but not smaller than required by plumbing code.
 - 2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
 - 3. Plumbing Specialties: Connect waste and vent piping in sizes indicated, but not smaller than required by plumbing code.
 - 4. Install test tees (wall cleanouts) in conductors near floor and floor cleanouts with cover flush with floor.
 - 5. Comply with requirements for cleanouts and drains specified in Section 22 1319 "Sanitary Waste Piping Specialties."
 - 6. Equipment: Connect waste piping as indicated.
 - a. Provide shutoff valve if indicated and union for each connection.
 - b. Use flanges instead of unions for connections NPS 2-1/2 and larger.
- D. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.
- E. Make connections according to the following unless otherwise indicated:
 - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
 - 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.

3.7 IDENTIFICATION

- A. Identify exposed sanitary waste and vent piping.
- B. Comply with requirements for identification specified in Section 22 0553 "Identification for Plumbing Piping and Equipment."

3.8 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
 - 1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 - 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary waste and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
 - 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired.
 - a. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
 - 2. Leave uncovered and unconcealed new, altered, extended, or replaced waste and vent piping until it has been tested and approved.
 - a. Expose work that was covered or concealed before it was tested.
 - 3. Roughing-in Plumbing Test Procedure: Test waste and vent piping except outside leaders on completion of roughing-in.
 - a. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water.
 - b. From 15 minutes before inspection starts to completion of inspection, water level must not drop.
 - c. Inspect joints for leaks.
 - 4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight.
 - a. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg.

- b. Use U-tube or manometer inserted in trap of water closet to measure this pressure.
 - c. Air pressure must remain constant without introducing additional air throughout period of inspection.
 - d. Inspect plumbing fixture connections for gas and water leaks.
5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
 6. Prepare reports for tests and required corrective action.

3.9 CLEANING AND PROTECTION

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect sanitary waste and vent piping during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.
- D. Exposed ABS and PVC Piping: Protect plumbing vents exposed to sunlight with two coats of water-based latex paint.
- E. Repair damage to adjacent materials caused by waste and vent piping installation.

3.10 PIPING SCHEDULE

- A. Flanges and unions may be used on aboveground pressure piping unless otherwise indicated.
- B. Aboveground, soil and waste piping NPS 4 and smaller shall be any of the following:
 1. Hubless, cast-iron soil pipe and fittings; CISPI hubless-piping couplings; and coupled joints.
 2. Solid-wall ABS pipe, ABS socket fittings, and solvent-cemented joints.
 3. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
 4. Dissimilar Pipe-Material Couplings: Unshielded, nonpressure transition couplings.
- C. Aboveground, vent piping NPS 4 and smaller shall be any of the following:
 1. Hubless, cast-iron soil pipe and fittings; CISPI hubless-piping couplings; and coupled joints.
 2. Solid-wall ABS pipe, ABS socket fittings, and solvent-cemented joints.
 3. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
 4. Dissimilar Pipe-Material Couplings: Unshielded, nonpressure transition couplings.
- D. Underground, soil, waste, and vent piping NPS 4 and smaller shall be any of the following:
 1. Service class, cast-iron soil piping; gaskets; and gasketed joints.
 2. Solid wall ABS pipe, ABS socket fittings, and solvent-cemented joints.
 3. Solid wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
 4. Dissimilar Pipe-Material Couplings: Unshielded, nonpressure transition couplings.

END OF SECTION

SECTION 221319 - SANITARY WASTE PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Cleanouts.
2. Miscellaneous sanitary drainage piping specialties.

B. Related Requirements:

1. Section 07 6200 "Sheet Metal Flashing and Trim" for metal roof flashing assemblies.
2. Section 07 7200 "Roof Accessories" for preformed flashings.
3. Section 07 8413 "Penetration Firestopping" for through-penetration firestop assemblies.

1.3 DEFINITIONS

- A. ABS: Acrylonitrile butadiene styrene.
- B. PVC: Polyvinyl chloride.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings:
 1. Show fabrication and installation details for frost-resistant vent terminals.

1.5 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For sanitary waste piping specialties to include in emergency, operation, and maintenance manuals.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTIONS

- A. Sanitary waste piping specialties shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14 for plastic sanitary waste piping specialty components.

2.2 CLEANOUTS

A. Cast-Iron Exposed Cleanouts:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. Josam Company.
 - c. MIFAB, Inc.
 - d. Tyler Pipe; a subsidiary of McWane Inc.
 - e. WATTS.
 - f. Zurn Industries, LLC.
- 2. Standard: ASME A112.36.2M.
- 3. Size: Same as connected drainage piping
- 4. Body Material: Hubless, cast-iron soil pipe test tee as required to match connected piping.
- 5. Closure: Countersunk cast-iron plug.
- 6. Closure Plug Size: Same as or not more than one size smaller than cleanout size.

B. Cast-Iron Exposed Floor Cleanouts:

- 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. Josam Company.
 - c. MIFAB, Inc.
 - d. Sioux Chief Manufacturing Company, Inc.
 - e. WATTS.
 - f. Zurn Industries, LLC.
- 2. Standard: ASME A112.36.2M for cast-iron soil pipe with cast-iron ferrule and threaded, adjustable housing cleanout.
- 3. Size: Same as connected branch.
- 4. Type: Cast-iron soil pipe with cast-iron ferrule and threaded, adjustable housing.
- 5. Body or Ferrule: Cast iron.

6. Clamping Device: Required.
7. Outlet Connection: Inside calk.
8. Closure: Brass plug with straight threads and gasket.
9. Adjustable Housing Material: Cast iron with setscrews or other device.
10. Frame and Cover Material and Finish: Stainless steel.
11. Frame and Cover Shape: Round.
12. Top-Loading Classification: Light Duty.
13. Riser: ASTM A74, Service Class, cast-iron drainage pipe fitting and riser to cleanout.

C. Cast-Iron Wall Cleanouts:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. Josam Company.
 - c. MIFAB, Inc.
 - d. WATTS.
 - e. Zurn Industries, LLC.
2. Standard: ASME A112.36.2M. Include wall access.
3. Size: Same as connected drainage piping.
4. Body: Hubless, cast-iron soil pipe test tee as required to match connected piping.
5. Closure Plug:
 - a. Brass.
 - b. Countersunk head.
 - c. Drilled and threaded for cover attachment screw.
 - d. Size: Same as or not more than one size smaller than cleanout size.
6. Wall Access, Frame and Cover: Round, stainless steel wall-installation frame and cover.

2.3 MISCELLANEOUS SANITARY DRAINAGE PIPING SPECIALTIES

A. Open Drains (Hub Drains):

1. Description: Shop or field fabricate from ASTM A74, Service Class, hub-and-spigot, cast-iron soil-pipe fittings. Include P-trap, hub-and-spigot riser section; and where required, increaser fitting joined with ASTM C564 rubber gaskets.
2. Size: Same as connected waste piping.

B. Floor-Drain, Trap-Seal Primer Fittings:

1. Description: Cast iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
2. Size: Same as floor drain outlet with NPS 1/2 side inlet.

C. Air-Gap Fittings:

1. Standard: ASME A112.1.2, for fitting designed to ensure fixed, positive air gap between installed inlet and outlet piping.
 2. Body: Bronze or cast iron.
 3. Inlet: Opening in top of body.
 4. Outlet: Larger than inlet.
 5. Size: Same as connected waste piping and with inlet large enough for associated indirect waste piping.
- D. Sleeve Flashing Device:
1. Description: Manufactured, cast-iron fitting, with clamping device that forms sleeve for pipe floor penetrations of floor membrane. Include galvanized-steel pipe extension in top of fitting that will extend 2 inches above finished floor and galvanized-steel pipe extension in bottom of fitting that will extend through floor slab.
 2. Size: As required for close fit to riser or stack piping.
- E. Stack Flashing Fittings:
1. Description: Counterflashing-type, cast-iron fitting, with bottom recess for terminating roof membrane, and with threaded or hub top for extending vent pipe.
 2. Size: Same as connected stack vent or vent stack.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:
1. Size same as drainage piping up to NPS 4. Use NPS 4 for larger drainage piping unless larger cleanout is indicated.
 2. Locate at each change in direction of piping greater than 45 degrees.
 3. Locate at minimum intervals of 50 feet for piping NPS 4 and smaller and 100 feet for larger piping.
 4. Locate at base of each vertical soil and waste stack.
- B. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.
- C. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.
- D. Assemble open drain fittings and install with top of hub 2 inches above floor.
- E. Install floor-drain, trap-seal primer fittings on inlet to floor drains that require trap-seal primer connection.
1. Exception: Fitting may be omitted if trap has trap-seal primer connection.
 2. Size: Same as floor drain inlet.

- F. Install air-gap fittings on draining-type backflow preventers and on indirect-waste piping discharge into sanitary drainage system.
- G. Install sleeve and sleeve seals with each riser and stack passing through floors with waterproof membrane.
- H. Install traps on plumbing specialty drain outlets. Omit traps on indirect wastes unless trap is indicated.

3.2 PIPING CONNECTIONS

- A. Comply with requirements in Section 22 1316 "Sanitary Waste and Vent Piping" for piping installation requirements. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment, to allow service and maintenance.

3.3 LABELING AND IDENTIFYING

- A. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit.
 - 1. Nameplates and signs are specified in Section 22 0553 "Identification for Plumbing Piping and Equipment."

3.4 PROTECTION

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION

SECTION 221319.13 - SANITARY DRAINS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Floor drains.
 - 2. Trench drains.

1.3 DEFINITIONS

- A. ABS: Acrylonitrile-butadiene styrene.
- B. FRP: Fiberglass-reinforced plastic.
- C. HDPE: High-density polyethylene.
- D. PE: Polyethylene.
- E. PP: Polypropylene.
- F. PVC: Polyvinyl chloride.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 DRAIN ASSEMBLIES

- A. Sanitary drains shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14 for plastic sanitary piping specialty components.

2.2 FLOOR DRAINS

A. Cast-Iron Floor Drains (FD-1):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Commercial Enameling Company.
 - b. Jay R. Smith Mfg Co; a division of Morris Group International.
 - c. Josam Company.
 - d. MIFAB, Inc.
 - e. Prier Products, Inc.
 - f. Sioux Chief Manufacturing Company, Inc.
 - g. Wade; a subsidiary of McWane Inc.
 - h. WATTS.
 - i. Zurn Industries, LLC.
2. Standard: ASME A112.6.3.
3. Pattern: Floor drain.
4. Body Material: Gray iron.
5. Seepage Flange: Required.
6. Anchor Flange: Required.
7. Clamping Device: Required.
8. Outlet: Bottom.
9. Backwater Valve: Not required.
10. Coating on Interior and Exposed Exterior Surfaces:
11. Sediment Bucket: Not required.
12. Top or Strainer Material: Stainless steel.
13. Top of Body and Strainer Finish: Stainless steel.
14. Top Shape: Round.
15. Top Loading Classification: Medium Duty.
16. Funnel: If noted on drawings.
17. Inlet Fitting: Gray iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
18. Trap Material: Cast iron.
19. Trap Pattern: Standard P-trap.
20. Trap Features: Trap-seal primer valve drain connection.

B. Cast-Iron Floor Drains (FD-2):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Commercial Enameling Company.
 - b. Jay R. Smith Mfg Co; a division of Morris Group International.
 - c. Josam Company.
 - d. MIFAB, Inc.
 - e. Prier Products, Inc.

- f. Sioux Chief Manufacturing Company, Inc.
 - g. Wade; a subsidiary of McWane Inc.
 - h. WATTS.
 - i. Zurn Industries, LLC.
2. Standard: ASME A112.6.3.
 3. Pattern: Floor drain.
 4. Body Material: Gray iron.
 5. Seepage Flange: Required.
 6. Anchor Flange: Required.
 7. Clamping Device: Required.
 8. Outlet: Bottom.
 9. Backwater Valve: Not required.
 10. Coating on Interior and Exposed Exterior Surfaces:
 11. Sediment Bucket: Not required.
 12. Top or Strainer Material: Stainless steel.
 13. Top of Body and Strainer Finish: Stainless steel.
 14. Top Shape: Square.
 15. Top Loading Classification: Medium Duty.
 16. Funnel: If noted on drawings.
 17. Inlet Fitting: Gray iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
 18. Trap Material: Cast iron.
 19. Trap Pattern: Standard P-trap.
 20. Trap Features: Trap-seal primer valve drain connection.

2.3 TRENCH DRAINS

A. Trench Drains (TD-1):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Commercial Enameling Company.
 - b. Jay R. Smith Mfg Co; a division of Morris Group International.
 - c. Josam Company.
 - d. MIFAB, Inc.
 - e. Prier Products, Inc.
 - f. Sioux Chief Manufacturing Company, Inc.
 - g. Wade; a subsidiary of McWane Inc.
 - h. WATTS.
 - i. Zurn Industries, LLC.
2. Standard: ASME A112.6.3 for trench drains.
3. Material: Ductile or gray iron.
4. Flange: Anchor.
5. Clamping Device: Required.
6. Outlet: Bottom.

7. Grate Material: Ductile iron.
8. Grate Finish: Painted.
9. Top Loading Classification: Medium Duty.
10. Trap Material: Cast iron.
11. Trap Pattern: Standard P-trap.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install floor drains at low points of surface areas to be drained. Set grates of drains flush with finished floor, unless otherwise indicated.
 1. Position floor drains for easy access and maintenance.
 2. Set floor drains below elevation of surrounding finished floor to allow floor drainage.
 3. Set with grates depressed according to the following drainage area radii:
 - a. Radius, 30 Inches or Less: Equivalent to 1 percent slope, but not less than 1/4-inch total depression.
 - b. Radius, 30 to 60 Inches: Equivalent to 1 percent slope.
 - c. Radius, 60 Inches or Larger: Equivalent to 1 percent slope, but not greater than 1-inch total depression.
 4. Install floor-drain flashing collar or flange, so no leakage occurs between drain and adjoining flooring.
 - a. Maintain integrity of waterproof membranes where penetrated.
 5. Install individual traps for floor drains connected to sanitary building drain, unless otherwise indicated.
- B. Install trench drains at low points of surface areas to be drained.
 1. Set grates of drains flush with finished surface, unless otherwise indicated.
- C. Comply with ASME A112.3.1 for installation of stainless-steel channel drainage systems.
 1. Install on support devices, so that top will be flush with adjacent surface.
- D. Install plastic channel drainage system components on support devices, so that top will be flush with adjacent surface.
- E. Install open drain fittings with top of hub 2 inches above floor.

3.2 CONNECTIONS

- A. Comply with requirements in Section 22 1316 "Sanitary Waste and Vent Piping" for piping installation requirements. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Comply with requirements in Section 22 1319 "Sanitary Waste Piping Specialties" for backwater valves, air admittance devices and miscellaneous sanitary drainage piping specialties.
- C. Install piping adjacent to equipment to allow service and maintenance.

3.3 LABELING AND IDENTIFYING

- A. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit. Nameplates and signs are specified in Section 22 0553 "Identification for Plumbing Piping and Equipment."

3.4 PROTECTION

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Septic tanks.
2. Dosing tanks.
3. Distribution boxes.
4. Pipe and fittings.
5. Absorption systems.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

1. Include construction details, material descriptions, dimensions of individual components, and profiles.
2. Include manhole openings, covers, and pipe connections.

- B. Shop Drawings: For trench absorption systems.

1. Include manhole openings, covers, pipe connections, and accessories.
2. Include piping with sizes and invert elevations.
3. Include underground structures.
4. Include other utilities.

1.4 PROJECT CONDITIONS

PART 2 - PRODUCTS

2.1 CONCRETE SEPTIC TANKS

- A. Description: ASTM C1227, precast, reinforced-concrete tank and covers; single chamber.
- B. Manholes: 20-inch-diameter opening with reinforced-concrete risers to grade and access lid with steel lift rings. Include manhole in center of each septic tank compartment top.

- C. Filter Access: Reinforced-concrete access hole, large enough to remove filter, over filter position.
- D. Inlet and Outlet Access: 12-inch minimum diameter, reinforced-concrete access lids with steel lift rings. Include access centered over inlet and outlet.
- E. Resilient Connectors: ASTM C923, of size required for piping, fitted into inlet and outlet openings.
- F. Capacity and Characteristics:
 - 1. Capacity: 1,000 gal..
 - 2. Inlet and Outlet Size: 4 inch.

2.2 CONCRETE DISTRIBUTION BOXES

- A. Description: Precast concrete, single-chamber box and cover.
- B. Design: Made according to ASTM C913, and for traffic loading according to ASTM C890.
- C. Manholes: 20-inch- minimum diameter opening with reinforced-concrete risers to grade and cover with steel lift rings in center of distribution box cover.
- D. Resilient Connectors: **ASTM C923** of size required for piping, fitted into inlet and outlet openings. Include watertight plugs in outlets not required.
- E. Capacity and Characteristics
 - 1. Inlet Size: 4"
 - 2. Number of Outlets: **Two**.
 - 3. Outlet Size: 4"

2.3 PLASTIC DISTRIBUTION BOXES

- A. Description: Molded-HDPE or -PE, single-chamber box and cover.
- B. Manholes: Manufacturer's standard cover or other access opening of size that permits access to distribution-box inlet and outlets.
- C. Pipe Connections: With seal that prevents leakage. Include watertight plugs in outlets not required.
- D. Capacity and Characteristics:
 - 1. Inlet Size: 4".
 - 2. Number of Outlets: Two.
 - 3. Outlet Size: 4".

2.4 PE DISTRIBUTION PIPE AND FITTINGS

- A. Tube and Fittings: ASTM F405, perforated corrugated tube with solid-wall fittings.
- B. Couplings: PE band, matching tube and fitting dimensions.

2.5 PVC DISTRIBUTION PIPE AND FITTINGS

- A. Pipe and Fittings: ASTM D2729, perforated, for solvent-cemented joints.
- B. Solvent Cement: ASTM D2564. Include primer according to ASTM F656.

2.6 NONPRESSURE PIPE COUPLINGS

- A. Description: Comply with ASTM C1173, elastomeric, sleeve-type, reducing or transition coupling, for joining underground nonpressure piping. Include ends of same sizes as piping to be joined, with corrosion-resistant-metal tension band and tightening mechanism on each end.
 - 1. Sleeve Materials for Plastic Pipes: ASTM F477, elastomeric seal or ASTM D5926, PVC.
 - 2. Sleeve Materials for Dissimilar Pipes: ASTM D5926, PVC or other material compatible with pipe materials being joined.

2.7 TRENCH ABSORPTION-SYSTEM MATERIALS

- A. Filter Material: ASTM D448, Size No. 24, 3/4 to 2-1/2 inches washed, crushed stone or gravel; or broken, hard-burned clay brick.
- B. Filter Mat: Geotextile woven or spun filter fabric, in one or more layers, for minimum total unit weight of 3 oz./sq. yd.
- C. Cover for Distribution Pipe: Geotextile woven filter fabric, in one or more layers, for minimum total unit weight of 3 oz./sq. yd.
- D. Fill Material: Soil removed from trench.

PART 3 - EXECUTION

3.1 EARTHWORK

- A. Excavating, trenching, and backfilling for piping are specified in Section 312000 "Earth Moving."
 - 1. Stockpile topsoil for reuse in finish grading without intermixing with other excavated material. Stockpile materials away from edge of excavation and do not store within drip line of remaining trees.
 - 2. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.

- B. Excavating and Backfilling for Septic Tanks:
 - 1. Excavate sufficient width and length for tanks to depth determined by tank inlet elevation. Provide level bottom.
 - 2. Backfill with excavated soil, mounding soil above original grade without compacting.
- C. Excavating and Backfilling for Trench Absorption Systems:
 - 1. Excavate for trench absorption systems 30 inches wide and 24 inches deep, minimum.
 - 2. Backfill with excavated soil, mounding soil above original grade without compacting..
 - 3. Backfill with excavated soil, mounding soil above original grade without compacting.

3.2 SEPTIC TANK INSTALLATION

- A. Install precast concrete septic tanks according to ASTM C891.
- B. Install septic tanks level.
- C. Install filter in septic tank outlet. Secure filter to septic tank wall. Make direct connections to distribution piping.
- D. Install insulation on exterior sides and top of septic tank. Comply with requirements for insulation specified in Section 220716 "Plumbing Equipment Insulation."
- E. Fill septic tank with water.

3.3 DISTRIBUTION BOX INSTALLATION

- A. Install precast-concrete distribution boxes according to ASTM C891 and at invert elevations indicated. Set level and plumb.

3.4 PIPING INSTALLATION

- A. Comply with requirements for sewer pipe installation specified in Section 221313 "Facility Sanitary Sewers."
- B. Install distribution piping according to the following:
 - 1. Use perforated pipe and fittings for trench absorption systems with perforations at bottom.
 - 2. PE Tube and Fittings: ASTM F481.
 - 3. PVC Sewer Pipe and Fittings: ASTM F481.

3.5 PIPE JOINT CONSTRUCTION

- A. Join distribution piping with or according to the following:

1. Install pipe and fittings for trench absorption systems with closed joints unless otherwise indicated.
 2. PE Tube and Fittings: With PE band couplings.
 3. PVC Sewer Pipe and Fittings: With solvent-cemented joints according to ASTM F402 and ASTM D2321.
- B. Join dissimilar pipe materials according to ASTM D5926, with couplings and gaskets compatible with pipe materials being joined.

3.6 CLEANOUT INSTALLATION

- A. Install cleanouts according to the following:
1. Inlet and Outlet of Distribution Boxes: PVC cleanouts.
- B. Comply with requirements for cleanouts specified in Section 221313 "Facility Sanitary Sewers."
- C. PVC Cleanouts: Install with PVC riser from sewer and distribution piping to PVC cleanout at grade. Use NPS 4 PVC sewer pipe and fittings with solvent-cemented joints for risers and cleanout fitting.
- D. Set top of cleanout **1 inch** above surrounding rough grade, or set flush with grade if installed in pavement.

3.7 TRENCH ABSORPTION-SYSTEM INSTALLATION

- A. Filter Material: Place supporting layer of filter material over the compacted trench base to a compacted depth not less than 6 inches below bottom of pipe.
- B. Install sewer piping at minimum slope of 1 percent and maximum slope of 2 percent.
1. Install elbow fittings with tight joints.
 - a. Trench Size: **36 inches** wide by required length.
 - b. Intermediate Filter Material Layer: OD of distribution piping.
 - c. Filter Mat: Above final filter-material layer.
 - d. Fill: Above filter mat to final grade.
- C. Install filter mat over filter material before backfilling.

3.8 IDENTIFICATION

- A. Identification materials and their installation are specified in Section 312000 "Earth Moving." Arrange for installation of green, detectable warning tape directly over piping, at outside edges of underground structures, and at outside edges of absorption systems.

3.9 FIELD QUALITY CONTROL

- A. System Tests: Perform testing of completed septic tank system piping and structures according to authorities having jurisdiction.
- B. Additional Tests: Fill underground structures with water and let stand overnight. If water level recedes, locate and repair leaks and retest. Repeat tests and repairs until no leaks exist.

3.10 CLEANING

- A. Clear interior of piping and structures of dirt and other superfluous material as work progresses.
- B. Maintain swab or drag in piping, and pull past each joint as it is completed. Place plugs in ends of uncompleted pipe at end of workday or when work stops.

END OF SECTION 221353

SECTION 223300 - ELECTRIC, DOMESTIC-WATER HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Commercial, light-duty, storage, electric, domestic-water heaters.
 - 2. Flow-control, electric, tankless, domestic-water heaters.
 - 3. Thermostat-control, electric, tankless, domestic-water heaters.
 - 4. Domestic-water heater accessories.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Sustainable Design Submittals:
- C. Shop Drawings:
 - 1. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Equipment room drawing or BIM model, drawn to scale, on which the items described in this Section are shown and coordinated with all building trades.
- B. Seismic Qualification Data: Certificates, for commercial domestic-water heaters, accessories, and components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Product Certificates: For each type of commercial and tankless, electric, domestic-water heater.
- D. Domestic-Water Heater Labeling: Certified and labeled by testing agency acceptable to authorities having jurisdiction.

- E. Source quality-control reports.
- F. Field quality-control reports.
- G. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For electric, domestic-water heaters to include emergency, operation, and maintenance manuals.

1.6 COORDINATION

- A. Coordinate sizes and locations of concrete bases with actual equipment provided.

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of electric, domestic-water heaters that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Structural failures including storage tank and supports.
 - b. Faulty operation of controls.
 - c. Deterioration of metals, metal finishes, and other materials beyond normal use.
 - 2. Warranty Periods: From date of Final Acceptance.
 - a. Commercial, Light-Duty, Storage, Electric, Domestic-Water Heaters:
 - 1) Storage Tank: Five years.
 - 2) Controls and Other Components: Three years.
 - b. Electric, Tankless, Domestic-Water Heaters: Five year(s).
 - c. Expansion Tanks: Five years.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and use.
- B. ASHRAE/IES Compliance: Applicable requirements in ASHRAE/IES 90.1.
- C. ASME Compliance: Where ASME-code construction is indicated, fabricate and label commercial, domestic-water heater storage tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.
- D. NSF Compliance: Fabricate and label equipment components that will be in contact with potable water to comply with NSF 61 and NSF 372.

2.2 COMMERCIAL, ELECTRIC, DOMESTIC-WATER HEATERS

- A. Commercial, Light-Duty, Storage, Electric, Domestic-Water Heaters:
- 1.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. A. O. Smith Corporation.
 - b. American Water Heaters.
 - c. Bradford White Corporation.
 - d. Electric Heater Company (The).
 - e. Heat Transfer Products, Inc.
 - f. Lochinvar, LLC.
 - g. Rheem Manufacturing Company.
 - h. Ruud Water Heaters; a Rheem brand.
 - i. State Industries.
 - 2.Source Limitations: Obtain domestic-water heaters from single source from single manufacturer.
 - 3.Standard: UL 174.
 - 4.Storage-Tank Construction: Steel, vertical arrangement.
 - a. Tappings: ASME B1.20.1 pipe thread.
 - b. Pressure Rating: 150 psig.
 - c. Interior Finish: Comply with NSF 61 and NSF 372 barrier materials for potable-water tank linings, including extending lining material into tappings.
 - 5.Factory-Installed, Storage-Tank Appurtenances:
 - a. Anode Rod: Replaceable magnesium.
 - b. Dip Tube: Required unless cold-water inlet is near bottom of tank.
 - c. Drain Valve: Corrosion-resistant metal with hose-end connection.
 - d. Insulation: Comply with ASHRAE/IES 90.1.
 - e. Jacket: Steel with enameled finish or high-impact composite material.
 - f. Heat-Trap Fittings: Inlet type in cold-water inlet and outlet type in hot-water outlet.
 - g. Heating Elements: Electric, screw-in immersion type.
 - h. Temperature Control: Adjustable thermostat.
 - i. Safety Control: High-temperature-limit cutoff device or system.
 - j. Relief Valve: ASME rated and stamped for combination temperature-and-pressure relief valves. Include relieving capacity at least as great as heat input, and include pressure setting less than working-pressure rating of domestic-water heater. Select relief valve with sensing element that extends into storage tank.
 - 6.Special Requirements: NSF 5 construction with legs for off-floor installation.

2.3 ELECTRIC, TANKLESS, DOMESTIC-WATER HEATERS

- A. Flow-Control, Electric, Tankless, Domestic-Water Heaters:
- 1.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Bosch Thermotechnology Corp.
 - b. Bradley Corporation.
 - c. Chronomite Laboratories, Inc; a division of Morris Group International.
 - d. Eemax, Inc.; a Rheem brand.
 - e. Stiebel Eltron, Inc.

2. Source Limitations: Obtain domestic-water heaters from single source from single manufacturer.
3. Standard: UL 499 for electric, tankless, (domestic-water-heater) heating appliance.
4. Construction: Copper piping or tubing complying with NSF 61 and NSF 372 barrier materials for potable water, without storage capacity.
 - a. Connections: ASME B1.20.1 pipe thread.
 - b. Pressure Rating: 150 psig.
 - c. Heating Element: Resistance heating system.
 - d. Temperature Control: Flow-control fitting.
 - e. Safety Control: High-temperature-limit cutoff device or system.
 - f. Jacket: Aluminum or steel with enameled finish or plastic.
5. Support: Bracket for wall mounting.

2.4 DOMESTIC-WATER HEATER ACCESSORIES

- A. Domestic-Water Expansion Tanks:
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. A. O. Smith Corporation.
 - b. AMTROL, Inc.
 - c. Flexcon Industries.
 - d. Honeywell International Inc.
 - e. Pentair Aurora; Pentair Pump Group.
 - f. ProFlo; a Ferguson Enterprises, Inc. brand.
 - g. State Industries.
 - h. Taco Comfort Solutions.
 2. Source Limitations: Obtain domestic-water expansion tanks from single source from single manufacturer.
 3. Description: Steel pressure-rated tank constructed with welded joints and factory-installed, butyl-rubber diaphragm. Include air precharge to minimum system-operating pressure at tank.
 4. Construction:
 - a. Tappings: Factory-fabricated steel, welded to tank before testing and labeling. Include ASME B1.20.1 pipe thread.
 - b. Interior Finish: Comply with NSF 61 and NSF 372 barrier materials for potable-water tank linings, including extending finish into and through tank fittings and outlets.
 - c. Air-Charging Valve: Factory installed.
- B. Drain Pans: Corrosion-resistant metal with raised edge. Include dimensions not less than base of domestic-water heater, and include drain outlet not less than NPS 3/4 with ASME B1.20.1 pipe threads.
- C. Piping-Type Heat Traps: Field-fabricated piping arrangement in accordance with ASHRAE/IES 90.1.
- D. Heat-Trap Fittings: ASHRAE/IES 90.1.

- E. Manifold Kits: Domestic-water-heater manufacturer's factory-fabricated inlet and outlet piping for field installation, for multiple domestic-water heater installation. Include ball-, butterfly-, or gate-type shutoff valves to isolate each domestic-water heater and calibrated balancing valves to provide balanced flow through each domestic-water heater.
 - 1. Comply with requirements for ball-, butterfly-, or gate-type shutoff valves specified in Section 220523.12 "Ball Valves for Plumbing Piping," Section 220523.13 "Butterfly Valves for Plumbing Piping," and Section 220523.15 "Gate Valves for Plumbing Piping."
 - 2. Comply with requirements for balancing valves specified in Section 221119 "Domestic Water Piping Specialties."
- F. Pressure-Reducing Valves: ASSE 1003 for water. Set at 25-psig- maximum outlet pressure unless otherwise indicated.
- G. Combination Temperature-and-Pressure Relief Valves: ASME rated and stamped. Include relieving capacity at least as great as heat input, and include pressure setting less than working-pressure rating of domestic-water heater. Select relief valves with sensing element that extends into storage tank.
- H. Pressure Relief Valves: ASME rated and stamped. Include pressure setting less than working-pressure rating of domestic-water heater.
- I. Vacuum Relief Valves: ANSI Z21.22/CSA 4.4.
- J. Shock Absorbers: ASSE 1010 or PDI-WH 201, Size A water hammer arrester.
- K. Domestic-Water Heater Stands: Manufacturer's factory-fabricated steel stand for floor mounting, capable of supporting domestic-water heater and water. Include dimension that will support bottom of domestic-water heater a minimum of 18 inches above the floor.
- L. Domestic-Water Heater Mounting Brackets: Manufacturer's factory-fabricated steel bracket for wall mounting, capable of supporting domestic-water heater and water.

2.5 SOURCE QUALITY CONTROL

- A. Factory Tests: Test and inspect domestic-water heaters specified to be ASME-code construction, in accordance with ASME Boiler and Pressure Vessel Code.
- B. Hydrostatically test commercial domestic-water heaters to minimum of one and one-half times pressure rating before shipment.
- C. Electric, domestic-water heaters will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 DOMESTIC-WATER HEATER INSTALLATION

- A. Commercial, Electric, Domestic-Water Heater Mounting: Install commercial, electric, domestic-water heaters on concrete base. Comply with requirements for concrete bases specified in Section 033000 "Cast-in-Place Concrete."
1. Exception: Omit concrete bases for commercial, electric, domestic-water heaters if installation on stand, bracket, suspended platform, or directly on floor is indicated.
 2. Maintain manufacturer's recommended clearances.
 3. Arrange units so controls and devices that require servicing are accessible.
 4. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of concrete base.
 5. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
 6. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 7. Install anchor bolts to elevations required for proper attachment to supported equipment.
 8. Anchor domestic-water heaters to substrate.
- B. Electric, Tankless, Domestic-Water Heater Mounting: Install electric, tankless, domestic-water heaters at least 18 inches above floor on wall bracket.
1. Maintain manufacturer's recommended clearances.
 2. Arrange units so controls and devices that require servicing are accessible.
 3. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 4. Install anchor bolts to elevations required for proper attachment to supported equipment.
 5. Anchor domestic-water heaters to substrate.
- C. Install electric, domestic-water heaters level and plumb, in accordance with layout drawings, original design, and referenced standards. Maintain manufacturer's recommended clearances. Arrange units so controls and devices needing service are accessible.
1. Install shutoff valves on domestic-water-supply piping to domestic-water heaters and on domestic-hot-water outlet piping. Comply with requirements for shutoff valves specified in Section 220523.12 "Ball Valves for Plumbing Piping," Section 220523.13 "Butterfly Valves for Plumbing Piping," and Section 220523.15 "Gate Valves for Plumbing Piping."
- D. Install commercial, electric, domestic-water heaters with seismic-restraint devices. Comply with requirements for seismic-restraint devices specified in Section 220548.13 "Vibration Controls for Plumbing Piping and Equipment."
- E. Install combination temperature-and-pressure relief valves in top portion of storage tanks. Use relief valves with sensing elements that extend into tanks. Extend domestic-water heater relief-valve outlet, with drain piping same as domestic-water piping in continuous downward pitch, and discharge by positive air gap onto closest floor drain.
- F. Install combination temperature-and-pressure relief valves in water piping for electric, domestic-water heaters without storage. Extend domestic-water heater relief-valve outlet, with drain piping same as domestic-water piping in continuous downward pitch, and discharge by positive air gap onto closest floor drain.

- G. Install water-heater drain piping as indirect waste to spill by positive air gap into open drains or over floor drains. Install hose-end drain valves at low points in water piping for electric, domestic-water heaters that do not have tank drains. Comply with requirements for hose-end drain valves specified in Section 221119 "Domestic Water Piping Specialties."
- H. Install thermometers on outlet piping of electric, domestic-water heaters. Comply with requirements for thermometers specified in Section 220519 "Meters and Gages for Plumbing Piping."
- I. Install thermometers on inlet and outlet piping of residential, solar, electric, domestic-water heaters. Comply with requirements for thermometers specified in Section 220519 "Meters and Gages for Plumbing Piping."
- J. Assemble and install inlet and outlet piping manifold kits for multiple electric, domestic-water heaters. Fabricate, modify, or arrange manifolds for balanced water flow through each electric, domestic-water heater. Include shutoff valve and thermometer in each domestic-water heater inlet and outlet, and throttling valve in each electric, domestic-water heater outlet. Comply with requirements for valves specified in Section 220523.12 "Ball Valves for Plumbing Piping," Section 220523.13 "Butterfly Valves for Plumbing Piping," and Section 220523.15 "Gate Valves for Plumbing Piping," and comply with requirements for thermometers specified in Section 220519 "Meters and Gages for Plumbing Piping."
- K. Install pressure-reducing valve with integral bypass relief valve in electric, domestic-water booster-heater inlet piping and water hammer arrester in booster-heater outlet piping. Set pressure-reducing valve for outlet pressure of 25 psig. Comply with requirements for pressure-reducing valves and water hammer arresters specified in Section 221119 "Domestic Water Piping Specialties."
- L. Install piping-type heat traps on inlet and outlet piping of electric, domestic-water heater storage tanks without integral or fitting-type heat traps.
- M. Fill electric, domestic-water heaters with water.
- N. Charge domestic-water expansion tanks with air to required system pressure.
- O. Install dielectric fittings in all locations where piping of dissimilar metals is to be joined. The wetted surface of the dielectric fitting contacted by potable water shall contain less than 0.25 percent of lead by weight.

3.2 PIPING CONNECTIONS

- A. Comply with requirements for piping specified in Section 221116 "Domestic Water Piping." Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Where installing piping adjacent to electric, domestic-water heaters, allow space for service and maintenance of water heaters. Arrange piping for easy removal of domestic-water heaters.

3.3 IDENTIFICATION

- A. Identify system components. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections with the assistance of a factory-authorized service representative.
- E. Tests and Inspections:
 - 1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Operational Test: After electrical circuitry has been energized, start units to confirm proper operation.
 - 3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- F. Electric, domestic-water heaters will be considered defective if they do not pass tests and inspections.
- G. Prepare test and inspection reports.

3.5 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain commercial and tankless, electric, domestic-water heaters. Training shall be a minimum of one hour.

END OF SECTION

SECTION 224213.13 - COMMERCIAL WATER CLOSETS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Wall-mounted water closets.
 - 2. Flushometer valves.
 - 3. Toilet seats.
 - 4. Supports.

1.3 DEFINITIONS

- A. Effective Flush Volume: Average of two reduced flushes and one full flush per fixture.
- B. Remote Water Closet: Located more than 30 feet from other drain line connections or fixture and where less than 1.5 drainage fixture units are upstream of the drain line connection.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for water closets.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Sustainable Design Submittals:
- C. Shop Drawings: Include diagrams for power, signal, and control wiring.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For flushometer valves and electronic sensors to include in operation and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Flushometer-Valve Repair Kits: Provide two (2) of each type.

PART 2 - PRODUCTS

2.1 WALL-MOUNTED WATER CLOSETS

- A. Water Closets, Wall Mounted, Top Spud, Accessible (P-1):
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. American Standard.
 - b. Kohler Co.
 - c. Sloan Valve Company.
 - d. Zurn Industries, LLC.
 - 2. Bowl:
 - a. Standards: ASME A112.19.2/CSA B45.1 and ASME A112.19.5.
 - b. Material: Vitreous china.
 - c. Type: Siphon jet.
 - d. Style: Flushometer valve.
 - e. Height: Standard.
 - f. Rim Contour: Elongated.
 - g. Water Consumption: 1.28 gal. per flush.
 - h. Spud Size and Location: NPS 1-1/2; top.
 - 3. Flushometer Valve: (P-1).
 - 4. Toilet Seat: (P-1).
 - 5. Support: Water closet carrier.
 - 6. Water-Closet Mounting Height: Handicapped/elderly according to ICC/ANSI A117.1.

2.2 FLUSHOMETER VALVES

- A. Flushometer Valves - Diaphragm, Lever Handle (P-1):
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. American Standard.
 - b. Kohler Co.

- c. Sloan Valve Company.
 - d. Zurn Industries, LLC.
2. Source Limitations: Obtain flushometer valve from single source from single manufacturer.
 3. Minimum Pressure Rating: 125 psig.
 4. Features: Include integral check stop and backflow-prevention device.
 5. Material: Brass body with corrosion-resistant components.
 6. Style: Exposed.
 7. Flushometer-Valve Finish: Chrome-plated.
 8. Handle Finish: Chrome-plated.
 9. Consumption: 1.6 gal.per flush.
 10. Minimum Inlet: NPS 1.
 11. Minimum Outlet: NPS 1-1/4.

2.3 TOILET SEATS

A. Toilet Seats (P-1):

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. American Standard.
 - b. Bemis Manufacturing Company.
 - c. Church Seats; Bemis Manufacturing Company.
 - d. Kohler Co.
 - e. Zurn Industries, LLC.
2. Standard: IAPMO/ANSI Z124.5.
3. Material: Plastic.
4. Type: Commercial (Heavy duty).
5. Shape: Elongated rim, open front.
6. Hinge: Self-sustaining, check.
7. Hinge Material: Noncorroding metal.
8. Seat Cover: Not required.
9. Color: White.

2.4 SUPPORTS

A. Water Closet Carrier:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. Josam Company.
 - c. MIFAB, Inc.

- d. Wade Drains.
 - e. WATTS.
 - f. Zurn Industries, LLC.
2. Standard: ASME A112.6.1M.
 3. Description: Waste-fitting assembly, as required to match drainage piping material and arrangement with faceplates, couplings gaskets, and feet; bolts and hardware matching fixture. Include additional extension coupling, faceplate, and feet for installation in wide pipe space.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in of water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before water-closet installation.
- B. Examine walls and floors for suitable conditions where water closets will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Water-Closet Installation:

1. Install level and plumb according to roughing-in drawings.
2. Install accessible, wall-mounted water closets at mounting height for handi-capped/elderly, according to ICC/ANSI A117.1.

B. Support Installation:

1. Install supports, affixed to building substrate, for floor-mounted, back-outlet water closets.
2. Use carrier supports with waste-fitting assembly and seal.
3. Install wall-mounted, back-outlet water-closet supports with waste-fitting assembly and waste-fitting seals; and affix to building substrate.

C. Flushometer-Valve Installation:

1. Install flushometer-valve, water-supply fitting on each supply to each water closet.
2. Attach supply piping to supports or substrate within pipe spaces behind fixtures.
3. Install lever-handle flushometer valves for accessible water closets with handle mounted on open side of water closet.
4. Install actuators in locations that are easy for people with disabilities to reach.

D. Install toilet seats on water closets.

E. Wall Flange and Escutcheon Installation:

1. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations and within cabinets and millwork.
2. Install deep-pattern escutcheons if required to conceal protruding fittings.
3. Comply with escutcheon requirements specified in Section 22 0518 "Escutcheons for Plumbing Piping."

F. Joint Sealing:

1. Seal joints between water closets and walls using sanitary-type, one-part, mildew-resistant silicone sealant.
2. Match sealant color to water-closet color.
3. Comply with sealant requirements specified in Section 07 9200 "Joint Sealants."

3.3 CONNECTIONS

- A. Connect water closets with water supplies and soil, waste, and vent piping. Use size fittings required to match water closets.
- B. Comply with water piping requirements specified in Section 22 1116 "Domestic Water Piping."
- C. Comply with soil and waste piping requirements specified in Section 22 1316 "Sanitary Waste and Vent Piping."
- D. Where installing piping adjacent to water closets, allow space for service and maintenance.

3.4 ADJUSTING

- A. Operate and adjust water closets and controls. Replace damaged and malfunctioning water closets, fittings, and controls.
- B. Adjust water pressure at flushometer valves to produce proper flow.

3.5 CLEANING AND PROTECTION

- A. Clean water closets and fittings with manufacturers' recommended cleaning methods and materials.
- B. Install protective covering for installed water closets and fittings.
- C. Do not allow use of water closets for temporary facilities unless approved in writing by Owner.

END OF SECTION

SECTION 224213.16 - COMMERCIAL URINALS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Wall-hung urinals.
 - 2. Urinal flushometer valves.
 - 3. Supports.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for urinals.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Shop Drawings: Include diagrams for power, signal, and control wiring.

1.4 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For flushometer valves to include in operation and maintenance manuals.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Flushometer-Valve Repair Kits: Equal to 10 percent of amount of each type installed, but no fewer than one of each type.

PART 2 - PRODUCTS

2.1 WALL-HUNG URINALS

B. Urinals - Wall Hung, Back Outlet, Washdown: Accessible. (P-2)

1.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. American Standard.
- b. Kohler Co.
- c. Sloan Valve Company.
- d. Zurn Industries, LLC.

2.Fixture:

- a. Standards: ASME A112.19.2/CSA B45.1 and ASME A112.19.5/CSA B45.15.
- b. Material: Vitreous china.
- c. Type: Washdown with extended shields.
- d. Strainer or Trapway: Manufacturer's standard strainer with integral trap.
- e. Water Consumption: 0.125 gpf.
- f. Spud Size and Location: NPS 3/4, top.
- g. Outlet Size and Location: NPS 2, back.
- h. Color: White.

3.Flushometer Valve: (P-2)

4.Waste Fitting:

- a. Standard: ASME A112.18.2/CSA B125.2 for coupling.
- b. Size: NPS 2.

5.Support: Type I urinal carrier with fixture support plates and coupling with seal and fixture bolts and hardware matching fixture. Include rectangular, steel uprights. Urinal Mounting Height: Handicapped/elderly according to ICC A117.1.

6.Flushometer Valve:

- a. Standard: ASME A112.18.1/CSA B125.1.
- b. Flushing Device: Manufacturer's standard for NPS 1/2 supply; self-closing valve; and washdown pipe of length matching fixture.

7.Waste Fitting:

- a. Standard: ASME A112.18.2/CSA B125.2.
- b. Trap:
 - 1) Size: NPS 1-1/2.
 - 2) Material, Chrome Plated: Two-piece, cast-brass trap and swivel elbow with 0.032-inch- thick brass tube to wall; and chrome-plated brass or steel wall flange.

2.2 URINAL FLUSHOMETER VALVES

A. Lever-Handle, Diaphragm Flushometer Valves (P-1):

8.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. American Standard.
- b. Kohler Co.
- c. Sloan Valve Company.
- d. Zurn Industries, LLC.

9.Standard: ASSE 1037/ASME 112.1037/CSA B125.37.

10. Minimum Pressure Rating: 125 psig.
11. Features: Include integral check stop and backflow-prevention device.
12. Material: Brass body with corrosion-resistant components.
13. Exposed Flushometer-Valve Finish: Chrome plated.
14. Panel Finish: Chrome plated or stainless steel.
15. Style: Exposed.
16. Consumption: 0.125 gal. per flush.
17. Minimum Inlet: NPS 3/4.
18. Minimum Outlet: NPS 3/4.

2.2 SUPPORTS

A. Urinal Carrier:

1.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Jay R. Smith Mfg Co; a division of Morris Group International.
- b. Josam Company.
- c. MIFAB, Inc.
- d. Wade Drains.
- e. WATTS.
- f. Zurn Industries, LLC.

B. Standard

2.Standard: ASME A112.6.1M.

PART 3 - EXECUTION

3.1 EXAMINATION

- C. Examine roughing-in of water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before urinal installation.
- D. Examine walls and floors for suitable conditions where urinals will be installed.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Urinal Installation:

- 1. Install urinals level and plumb according to rough-in drawings.
- 2. Install wall-hung, back-outlet urinals onto waste fitting seals and attached to supports.
- 3. Install accessible, wall-mounted urinals at mounting height for the handicapped/elderly, according to ICC A117.1.

B. Support Installation:

- 4. Install supports, affixed to building substrate, for wall-hung urinals.
- 5. Use off-floor carriers with waste fitting and seal for back-outlet urinals.
- 6. Use carriers without waste fitting for urinals with tubular waste piping.
- 7. Use chair-type carrier supports with rectangular steel uprights for accessible urinals.

C. Flushometer-Valve Installation:

- 8. Install flushometer-valve water-supply fitting on each supply to each urinal.
- 9. Attach supply piping to supports or substrate within pipe spaces behind fixtures.
- 10. Install lever-handle flushometer valves for accessible urinals with handle mounted on open side of compartment.

D. Wall Flange and Escutcheon Installation:

- 11. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations.
- 12. Install deep-pattern escutcheons if required to conceal protruding fittings.
- 13. Comply with escutcheon requirements specified in Section 220518 "Escutcheons for Plumbing Piping."

E. Joint Sealing:

- 14. Seal joints between urinals and walls and floors using sanitary-type, one-part, mildew-resistant silicone sealant.
- 15. Match sealant color to urinal color.
- 16. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

3.3 PIPING CONNECTIONS

- A. Connect urinals with water supplies and soil, waste, and vent piping. Use size fittings required to match urinals.
- B. Comply with water piping requirements specified in Section 221116 "Domestic Water Piping."
- C. Comply with soil and waste piping requirements specified in Section 221316 "Sanitary Waste and Vent Piping."
- D. Where installing piping adjacent to urinals, allow space for service and maintenance.

3.4 ADJUSTING

- A. Operate and adjust urinals and controls. Replace damaged and malfunctioning urinals, fittings, and controls.
- B. Adjust water pressure at flushometer valves to produce proper flow.

3.5 CLEANING AND PROTECTION

- A. Clean urinals and fittings with manufacturers' recommended cleaning methods and materials.
- B. Install protective covering for installed urinals and fittings.
- C. Do not allow use of urinals for temporary facilities unless approved in writing by Owner.

END OF SECTION

SECTION 224216.13 - COMMERCIAL LAVATORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Vitreous-china, counter-mounted lavatories.
 - 2. Manually operated lavatory faucets.
 - 3. Supply fittings.
 - 4. Waste fittings.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for lavatories.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Shop Drawings: Include diagrams for power, signal, and control wiring of automatic faucets.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Counter cutout templates for mounting of counter-mounted lavatories.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For lavatories and faucets to include in operation and maintenance manuals.
 - 1. In addition to items specified in Section 01 7823 "Operation and Maintenance Data," include the following:
 - a. Servicing and adjustments of automatic faucets.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Faucet Washers and O-Rings: Equal to 2 of each type and size installed.
 - 2. Faucet Cartridges and O-Rings: Equal to 2 of each type and size installed.

PART 2 - PRODUCTS

2.1 VITREOUS-CHINA, COUNTER-MOUNTED LAVATORIES

- A. Lavatory - Vitreous China, Undercounter Mounted (P-3):
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. American Standard.
 - b. Kohler Co.
 - c. Zurn Industries, LLC.
 - 2. Fixture:
 - a. Standard: ASME A112.19.2/CSA B45.1.
 - b. Type: For undercounter mounting.
 - c. Nominal Size: Oval, 20 by 17.5 inches.
 - d. Faucet-Hole Punching: No holes.
 - e. Faucet-Hole Location: On countertop.
 - f. Color: White.
 - g. Mounting Material: Sealant and undercounter mounting kit.
 - 3. Faucet: Insert lavatory faucet designation from "Manually Operated Lavatory Faucets" or "Automatically Operated Lavatory Faucets" Article.

2.2 MANUALLY OPERATED LAVATORY FAUCETS

- A. Lavatory faucets intended to convey or dispense water for human consumption are to comply with the U.S. Safe Drinking Water Act (SDWA), with requirements of the Authority Having Jurisdiction (AHJ), and with NSF 61/NSF 372, or be certified in compliance with NSF 61/NSF 372 by an American National Standards Institute (ANSI) accredited third-party certification body, that the weighted average lead content at wetted surfaces is less than or equal to 0.25 percent.
- B. Lavatory Faucets - Manual Type: Single-Control Mixing:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. American Standard.
 - b. Chicago Faucets; Geberit Company.
 - c. Delta Faucet Company.
 - d. Elkay.
 - e. T&S Brass and Bronze Works, Inc.
 - f. Zurn Industries, LLC.
2. Standard: ASME A112.18.1/CSA B125.1.
3. General: Include hot- and cold-water indicators; coordinate faucet inlets with supplies and fixture hole punchings; coordinate outlet with spout and fixture receptor.
4. Body Type: Centerset single hole.
5. Body Material: Commercial, solid-brass, or die-cast housing with brazed copper and brass waterway.
6. Finish: Polished chrome plate.
7. Maximum Flow Rate: 0.5 gpm.
8. Mounting Type: Deck, exposed.
9. Valve Handle(s): Single lever.
10. Spout: Rigid type.
11. Spout Outlet: Aerator.
12. Operation: Compression, manual.
13. Drain: Not part of faucet.

2.3 SUPPLY FITTINGS

- A. NSF Standard: Comply with NSF 61 and NSF 372 for supply-fitting materials that will be in contact with potable water.
- B. Standard: ASME A112.18.1/CSA B125.1.
- C. Supply Piping: Chrome-plated-brass pipe or chrome-plated copper tube matching water-supply piping size. Include chrome-plated-brass or stainless steel wall flange.
- D. Supply Stops: Chrome-plated-brass, one-quarter-turn, ball-type or compression valve with inlet connection matching supply piping.
- E. Operation: Loose key.
- F. Risers:
 1. NPS 1/2.
 2. Chrome-plated, rigid-copper-pipe and brass straight or offset tailpieces riser.

2.4 WASTE FITTINGS

- A. Standard: ASME A112.18.2/CSA B125.2.
- B. Drain: Grid type with NPS 1-1/4 offset and straight tailpiece.
- C. Trap:
 - 1. Size: NPS 1-1/2 by NPS 1-1/4.
 - 2. Material:
 - a. Chrome-plated, two-piece, cast-brass trap and swivel elbow with 0.032-inch-thick brass tube to wall; and chrome-plated, brass or steel wall flange.
 - b. Stainless steel, two-piece trap and swivel elbow with 0.012-inch-thick stainless steel tube to wall, and stainless steel wall flange.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in of water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before lavatory installation.
- B. Examine counters and walls for suitable conditions where lavatories will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install lavatories level and plumb in accordance with roughing-in drawings.
- B. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 22 0518 "Escutcheons for Plumbing Piping."
- C. Seal joints between lavatories, counters, and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 07 9200 "Joint Sealants."
- D. Install protective shielding pipe covers and enclosures on exposed supplies and waste piping of accessible lavatories. Comply with requirements in Section 22 0719 "Plumbing Piping Insulation."

3.3 PIPING CONNECTIONS

- A. Connect fixtures with water supplies, stops, and risers, and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.

- B. Comply with water piping requirements specified in Section 22 1116 "Domestic Water Piping."
- C. Comply with soil and waste piping requirements specified in Section 22 1316 "Sanitary Waste and Vent Piping."

3.4 ADJUSTING

- A. Operate and adjust lavatories and controls. Replace damaged and malfunctioning lavatories, fittings, and controls.
- B. Install new batteries in battery-powered, electronic-sensor mechanisms.

3.5 CLEANING AND PROTECTION

- A. After completing installation of lavatories, inspect and repair damaged finishes.
- B. Clean lavatories, faucets, and other fittings with manufacturers' recommended cleaning methods and materials.
- C. Provide protective covering for installed lavatories and fittings.
- D. Do not allow use of lavatories for temporary facilities unless approved in writing by Owner.

END OF SECTION

SECTION 224716 - PRESSURE WATER COOLERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Pressure water coolers.
 - 2. Bottle filling stations.
 - 3. Supports.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of pressure water cooler and bottle filling station.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Sustainable Design Submittals:
- C. Shop Drawings:
 - 1. Include diagrams for power wiring.

1.4 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For pressure water coolers and bottle filling stations to include in maintenance manuals.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Filter Cartridges: Equal to 10 percent of quantity installed for each type and size indicated, but no fewer than 1 of each.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Standards:

1. Pressure water coolers and bottle filling stations intended to convey or dispense water for human consumption are to comply with the U.S. Safe Drinking Water Act (SDWA), requirements of the Authority Having Jurisdiction (AHJ), and with NSF 61 or NSF 372, or be certified in compliance with NSF 61 or NSF 372 by an ANSI-accredited third-party certification body, that the weighted average lead content at wetted surfaces is less than or equal to 0.25 percent.
2. Comply with ASHRAE 34 for water coolers. Provide HFC 134a (tetrafluoroethane) refrigerant unless otherwise indicated.
3. Comply with UL 399.
4. Comply with ASME A112.19.3/CSA B45.4.
5. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
6. Comply with NSF 42 and NSF 53 for water filters for water coolers and bottle filling stations.
7. Comply with ICC A117.1 for accessible water coolers and bottle filling stations.

2.2 PRESSURE WATER COOLERS

A. Pressure Water Coolers - Surface Wall-Mounted, Stainless Steel (P-5):

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Elkay.
 - b. Halsey Taylor.
 - c. Murdock Manufacturing; A Division of Morris Group International.
 - d. Oasis International.
2. Source Limitations: Obtain surface wall-mounted, stainless steel, pressure water coolers from single source from single manufacturer.
3. Type: Vandal resistant.
4. Bubbler: One, with adjustable stream regulator, located on each cabinet deck.
5. Control: Push bar.
6. Glass filler.
7. Bottle Filler: Sensor activation: Fill rate 1.5 gpm.
8. Drain: Grid with NPS 1-1/4 tailpiece.
9. Supply: NPS 3/8 with shutoff valve.
10. Waste Fitting: ASME A112.18.2/CSA B125.2, NPS 1-1/4 brass P-trap.
11. Filter: One or more water filters with capacity sized for unit peak flow rate.

12. Cooling System: Electric, with hermetically sealed compressor, cooling coil, air-cooled condensing unit, corrosion-resistant tubing, refrigerant, corrosion-resistant-metal storage tank, and adjustable thermostat.
13. Support: Water-cooler carrier.
14. Water-Cooler Mounting Height: High/low - standard/accessible in accordance with ICC A117.1.
15. Capacities and Characteristics:
 - a. Cooled Water: 8 gph.
 - b. Ambient-Air Temperature: 90 deg F.
 - c. Inlet-Water Temperature: 80 deg F.
 - d. Cooled-Water Temperature: 50 deg F.

2.3 SUPPORTS

A. Water-Cooler Carrier:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Jay R. Smith Mfg Co; a division of Morris Group International.
 - b. Josam Company.
 - c. MIFAB, Inc.
 - d. Wade; a subsidiary of McWane Inc.
 - e. Zurn Industries, LLC.
2. Standard: ASME A112.6.1M.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in for water-supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before fixture installation.
- B. Examine walls and floors for suitable conditions where fixtures will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install fixtures level and plumb according to roughing-in drawings. For fixtures indicated for children, install at height required by authorities having jurisdiction.
- B. Set freestanding, pressure water coolers on floor.
- C. Install off-the-floor carrier supports, affixed to building substrate, for wall-mounted fixtures.

- D. Install mounting frames, affixed to building construction, and attach recessed, pressure water coolers, and bottle filling stations to mounting frames.
- E. Install water-supply piping with shutoff valve on supply to each fixture to be connected to domestic-water distribution piping. Use ball valve. Install valves in locations where they can be easily reached for operation. Valves are specified in Section 220523.12 "Ball Valves for Plumbing Piping".
- F. Install trap and waste piping on drain outlet of each fixture to be connected to sanitary drainage system.
- G. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons where required to conceal protruding fittings. Comply with escutcheon requirements specified in Section 220518 "Escutcheons for Plumbing Piping."
- H. Seal joints between fixtures and walls using sanitary-type, one-part, mildew-resistant, silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

3.3 PIPING CONNECTIONS

- A. Connect fixtures with water supplies, stops, and risers, and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.
- B. Comply with water piping requirements specified in Section 221116 "Domestic Water Piping."
- C. Install ball shutoff valve on water supply to each fixture. Install valve upstream from filter for water cooler. Comply with valve requirements specified in Section 220523.12 "Ball Valves for Plumbing Piping".
- D. Comply with soil and waste piping requirements specified in Section 221316 "Sanitary Waste and Vent Piping."

3.4 ELECTRICAL CONNECTIONS

- A. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."
- B. Install electrical devices furnished by manufacturer, but not factory mounted, according to NFPA 70 and NECA 1.
- C. Install nameplate for each electrical connection, indicating electrical equipment designation and circuit number feeding connection.
 - 1. Nameplates to be laminated acrylic or melamine plastic signs, as specified in Section 260553 "Identification for Electrical Systems."
 - 2. Nameplates to be laminated acrylic or melamine plastic signs with a black background and engraved white letters at least 1/2 inch high.

3.5 ADJUSTING

- A. Adjust fixture flow regulators for proper flow and stream height.
- B. Adjust pressure water-cooler temperature settings.

3.6 CLEANING

- A. After installing fixture, inspect unit. Remove paint splatters and other spots, dirt, and debris. Repair damaged finish to match original finish.
- B. Clean fixtures, on completion of installation, according to manufacturer's written instructions.
- C. Provide protective covering for installed fixtures.
- D. Do not allow use of fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION

SECTION 230513 – COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on alternating-current power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

1.3 COORDINATION

- A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:
 - 1. Motor controllers.
 - 2. Torque, speed, and horsepower requirements of the load.
 - 3. Ratings and characteristics of supply circuit and required control sequence.
 - 4. Ambient and environmental conditions of installation location.

PART 2 - PRODUCTS

2.1 GENERAL MOTOR REQUIREMENTS

- A. Comply with NEMA MG 1 unless otherwise indicated.
- B. Comply with IEEE 841 for severe-duty motors.

2.2 MOTOR CHARACTERISTICS

- A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.
- B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.

2.3 POLYPHASE MOTORS

- A. Description: NEMA MG 1, Design B, medium induction motor.
- B. Efficiency: Premium efficient, as defined in NEMA MG 1.
- C. Service Factor: 1.15.
- D. Multispeed Motors: Variable torque.
 - 1. For motors with 2:1 speed ratio, consequent pole, single winding.
 - 2. For motors with other than 2:1 speed ratio, separate winding for each speed.
- E. Multispeed Motors: Separate winding for each speed.
- F. Rotor: Random-wound, squirrel cage.
- G. Bearings: Regreasable, shielded, antifriction ball bearings suitable for radial and thrust loading.
- H. Temperature Rise: Match insulation rating.
- I. Insulation: Class F.
- J. Code Letter Designation:
 - 1. Motors 15 HP and Larger: NEMA starting Code F or Code G.
 - 2. Motors Smaller Than 15 HP: Manufacturer's standard starting characteristic.
- K. Enclosure Material: Cast iron for motor frame sizes 324T and larger; rolled steel for motor frame sizes smaller than 324T.

2.4 ADDITIONAL REQUIREMENTS FOR POLYPHASE MOTORS

- A. Motors Used with Reduced-Voltage and Multispeed Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.
- B. Motors Used with Variable-Frequency Controllers:
 - 1. Windings: Copper magnet wire with moisture-resistant insulation varnish, designed and tested to resist transient spikes, high frequencies, and short time rise pulses produced by pulse-width-modulated inverters.
 - 2. Premium-Efficient Motors: Class B temperature rise; Class F insulation.
 - 3. Inverter-Duty Motors: Class F temperature rise; Class H insulation.
 - 4. Thermal Protection: Comply with NEMA MG 1 requirements for thermally protected motors.
- C. Severe-Duty Motors: Comply with IEEE 841, with 1.15 minimum service factor.

2.5 SINGLE-PHASE MOTORS

- A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:
 - 1. Permanent-split capacitor.
 - 2. Split phase.
 - 3. Capacitor start, inductor run.
 - 4. Capacitor start, capacitor run.
- B. Multispeed Motors: Variable-torque, permanent-split-capacitor type.
- C. Bearings: Prelubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.
- D. Motors 1/20 HP and Smaller: Shaded-pole type.
- E. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION

SECTION 230517 - SLEEVES AND SLEEVE SEALS FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Sleeves.
2. Stack-sleeve fittings.
3. Sleeve-seal systems.
4. Sleeve-seal fittings.
5. Grout.
6. Silicone sealants.

B. Related Requirements:

1. Section 07 8413 "Penetration Firestopping" for penetration firestopping installed in fire-resistance-rated walls, horizontal assemblies, and smoke barriers, with and without penetrating items.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Sustainable Design Submittals:

1.4 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

PART 2 - PRODUCTS

2.1 SLEEVES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 1. Advanced products & System, Inc.

2. CALPICO, Inc
 3. GPT; an EnPro Industries company
- B. Cast-Iron Pipe Sleeves: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop collar.
- C. Steel Pipe Sleeves: ASTM A53/A53M, Type E, Grade B, Schedule 40, zinc coated, with plain ends and integral welded waterstop collar.
- D. Galvanized-Steel Sheet Sleeves: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- E. PVC Pipe Sleeves: ASTM D1785, Schedule 40.
- F. Molded-PVC Sleeves: With nailing flange for attaching to wooden forms.
- G. Molded-PE or -PP Sleeves: Removable, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.

2.2 STACK-SLEEVE FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Jay R. Mfg Co; a dsivision of Morris Group International
 2. Zurn Industries, LLC
- B. Description: Manufactured, Galvanized cast-iron sleeve with integral cast flashing flange for use in waterproof floors and roofs. Include clamping ring, bolts, and nuts for membrane flashing.
1. Underdeck Clamp: Clamping ring with setscrews.

2.3 SLEEVE-SEAL SYSTEMS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Advance products & System, Inc.
 2. Airex Manufacturing
 3. CALPICO, Inc.
 4. GPT; an EnPro Industries company
 5. Metraflex Company (The)
 6. Proco Products, Inc.
- B. Description:
1. Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.

2. Designed to form a hydrostatic seal of 20-psig.
3. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size.
4. Pressure Plates: Carbon steel.
5. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, ASTM B633 of length required to secure pressure plates to sealing elements.

2.4 SLEEVE-SEAL FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Advance Products & Systems, Inc.
 2. CALPICO, Inc.
 3. GPT; an EnPro Industries company
 4. Metraflec Company (The)
 5. Proco Products, Inc.
- B. Description:
1. Manufactured plastic, sleeve-type, waterstop assembly, made for imbedding in concrete slab or wall.
 2. Plastic or rubber waterstop collar with center opening to match piping OD.

2.5 GROUT

- A. Description: Nonshrink, recommended for interior and exterior sealing openings in nonfire-rated walls or floors.
- B. Standard: ASTM C1107/C1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

2.6 SILICONE SEALANTS

- A. Silicone, S, NS, 25, NT: Single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant, ASTM C920, Type S, Grade NS, Class 25, use NT.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. GE Construction Sealants; Momentive Performance Materials Inc.
 - b. Pecora Corporation

- c. Permathane/ Acryl-R; ITW Polymers Sealants North America
 - d. Polymeric Systems, Inc.
 - e. Sherwin Williams Company (The)
 - f. The Dow Chemical Company
- B. Silicone, S, P, 25, T, NT: Single-component, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade P, Class 25, Uses T and NT. Grade P Pourable (self-leveling) formulation is for opening in floors and other horizontal surfaces that are not fire rated.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. May National Associates, Inc.; a subsidiary of Sika Corporation
- C. Silicone Foam: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Smooth-On

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION

- A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.
- B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.
 1. Sleeves are not required for core-drilled holes.
- C. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.
 1. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.
 2. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.
 3. Using grout, seal space outside of sleeves in slabs and walls without sleeve-seal system.
- D. Install sleeves for pipes passing through interior partitions.

1. Cut sleeves to length for mounting flush with both surfaces.
2. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
3. Seal annular space between sleeve and piping or piping insulation; use sealants appropriate for size, depth, and location of joint.

E. Fire-Resistance-Rated Penetrations, Horizontal Assembly Penetrations, and Smoke-Barrier Penetrations: Maintain indicated fire or smoke rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with fire- and smoke-stop materials. Comply with requirements for firestopping and fill materials specified in Section 07 8413 "Penetration Firestopping."

3.2 STACK-SLEEVE-FITTING INSTALLATION

- A. Install stack-sleeve fittings in new slabs as slabs are constructed.
1. Install fittings that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
 2. Secure flashing between clamping flanges for pipes penetrating floors with membrane waterproofing. Comply with requirements for flashing specified in Section 076200 "Sheet Metal Flashing and Trim."
 3. Install section of cast-iron soil pipe to extend sleeve to 3 inches above finished floor level.
 4. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
 5. Using waterproof silicone sealant, seal space between top hub of stack-sleeve fitting and pipe.
- B. Fire-Resistance-Rated, Horizontal Assembly, and Smoke Barrier Penetrations: Maintain indicated fire or smoke rating of floors at pipe penetrations. Seal pipe penetrations with fire- and smoke-stop materials. Comply with requirements for firestopping specified in Section 07 8413 "Penetration Firestopping."

3.3 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.
- B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal-system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

3.4 SLEEVE-SEAL-FITTING INSTALLATION

- A. Install sleeve-seal fittings as new walls and slabs are constructed.

- B. Assemble fitting components of length to be flush with both surfaces of concrete slabs and walls. Position waterstop flange to be centered in concrete slab or wall.
- C. Secure nailing flanges to concrete forms.
- D. Using grout, seal space around outside of sleeve-seal fittings.

3.5 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Leak Test: After allowing for a full cure, test sleeves and sleeve seals for leaks. Repair leaks and retest until no leaks exist.
- B. Sleeves and sleeve seals will be considered defective if they do not pass tests and inspections.

3.6 SLEEVE AND SLEEVE-SEAL SCHEDULE

- A. Use sleeves and sleeve seals for the following piping-penetration applications:
 - 1. Concrete Walls Below Grade:
 - a. Piping Smaller Than NPS 6: Cast-iron pipe sleeves with sleeve-seal system.
 - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
 - 2. Concrete Slabs-on-Grade:
 - a. Piping Smaller Than NPS 6: Cast-iron pipe sleeves with sleeve-seal system.
 - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
 - 3. Interior Partitions:
 - a. Piping Smaller Than NPS 6: Steel pipe sleeves.

END OF SECTION

SECTION 230518 - ESCUTCHEONS FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Escutcheons.
 - 2. Floor plates.

1.3 DEFINITIONS

- A. Existing Piping to Remain: Existing piping that is not to be removed and that is not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. BrassCraft Manufacturing Co.; a Masco company
 - 2. Keeney Manufacturing Company (The)
 - 3. ProFlo; a Ferguson Enterprises, Inc. brand

2.2 ESCUTCHEONS

- A. One-Piece, Steel Type: With polished, chrome-plated finish and setscrew fastener.
- B. One-Piece, Stainless-Steel Type: With polished stainless-steel finish.
- C. One-Piece, Cast-Brass Type: With polished, chrome-plated finish and setscrew fastener.

- D. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped steel with polished, chrome-plated finish and spring-clip fasteners.
- E. One-Piece, Stamped-Steel Type: With polished, chrome-plated finish and spring-clip fasteners.
- F. Split-Plate, Stamped-Steel Type: With polished, chrome-plated finish; concealed hinge; and spring-clip fasteners.

2.3 FLOOR PLATES

- A. Split Floor Plates: Steel with concealed hinge.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.
- B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.
 - 1. Escutcheons for New Piping and Relocated Existing Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep pattern.
 - b. Insulated Piping: One-piece steel with polished, chrome-plated finish.
 - c. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece steel with polished, chrome-plated finish.
 - d. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece steel with polished, chrome-plated finish.
 - e. Bare Piping in Unfinished Service Spaces: One-piece steel with polished, chrome-plated finish.
 - f. Bare Piping in Equipment Rooms: One-piece steel with polished, chrome-plated finish.
- C. Install floor plates for piping penetrations of equipment-room floors.
- D. Install floor plates with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.
 - 1. New Piping: Split floor plate.

3.2 FIELD QUALITY CONTROL

- A. Using new materials, replace broken and damaged escutcheons and floor plates.

END OF SECTION

SECTION 230529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Metal pipe hangers and supports.
2. Trapeze pipe hangers.
3. Metal framing systems.
4. Thermal-hanger shield inserts.
5. Fastener systems.
6. Pipe stands.
7. Equipment stands.
8. Equipment supports.

B. Related Requirements:

1. Section 23 0548.13 "Vibration Controls for HVAC" for vibration isolation devices.
2. Section 23 3113 "Metal Ducts" for duct hangers and supports.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Show fabrication and installation details and include calculations for the following; include Product Data for components:

1. Trapeze pipe hangers.
2. Metal framing systems.
3. Pipe stands.
4. Equipment supports.

C. Delegated-Design Submittal: For trapeze hangers indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Detail fabrication and assembly of trapeze hangers.
2. Include design calculations for designing trapeze hangers.

1.4 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Structural-Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code, Section IX.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design trapeze pipe hangers and equipment supports.
- B. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
 - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
 - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

2.2 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
 - 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
 - 2. Galvanized Metallic Coatings: Pregalvanized, hot-dip galvanized, or electro-galvanized.
 - 3. Nonmetallic Coatings: Plastic coated, or epoxy powder-coated.
 - 4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
 - 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
- B. Copper Pipe and Tube Hangers:
 - 1. Description: MSS SP-58, Types 1 through 58, copper-plated steel, factory-fabricated components.
 - 2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-plated steel.

2.3 TRAPEZE PIPE HANGERS

- A. Description: MSS SP-58, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.4 METAL FRAMING SYSTEMS

- A. MFMA Manufacturer Metal Framing Systems:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ABB, Electrification Products Division
 - b. B-line; Eaton, Electrical Sector
 - c. Flex-Strut Inc.
 - d. G-Strut
 - e. Haydon Corporation
 - f. MIRO Industries
 - g. Unistrut; Atkore International
 - h. Wesanco, Inc.
2. Description: Shop- or field-fabricated, pipe-support assembly made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
3. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
4. Channels: Continuous slotted carbon-steel channel with inturned lips.
5. Channel Width: Selected for applicable load criteria.
6. Channel Nuts: Formed or stamped nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
7. Hanger Rods: Continuous-thread rod, nuts, and washer made of galvanized steel.
8. Metallic Coating: Hot-dip galvanized.
9. Paint Coating: Green epoxy, acrylic, or urethane.

2.5 THERMAL-HANGER SHIELD INSERTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Buckaroos, Inc.
 2. CADDY; nVent
 3. Carpenter & Paterson, Inc.
 4. KB Enterprise
 5. National Pipe Hanger Corporation
 6. Pipe Shields Inc.
 7. Piping Technology & Products, Inc.
 8. Rilco Manufacturing Co., Inc.
 9. Value Engineered Products, Inc.

- B. Insulation-Insert Material for Cold Piping: ASTM C552, Type II cellular glass with 100-psi minimum compressive strength and vapor barrier.
- C. Insulation-Insert Material for Hot Piping: ASTM C552, Type II cellular glass with 100-psi minimum compressive strength.
- D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- F. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.6 FASTENER SYSTEMS

- A. Mechanical-Expansion Anchors: Insert-wedge-type anchors for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-line; Eaton, Electrical Sector
 - b. Empire Tool and Manufacturing Co., Inc.
 - c. Hilti, Inc.
 - d. ITW Ramset/Red Head; Illinois Tool Works, Inc.
 - e. MKT Fastening, LLC
 - 2. Indoor Applications: Zinc-coated or stainless steel.
 - 3. Outdoor Applications: Stainless steel.

2.7 EQUIPMENT SUPPORTS

- A. Description: Welded, shop- or field-fabricated equipment support made from structural carbon-steel shapes.

2.8 MATERIALS

- A. Aluminum: ASTM B221.
- B. Carbon Steel: ASTM A1011/A1011M.
- C. Structural Steel: ASTM A36/A36M, carbon-steel plates, shapes, and bars; galvanized.
- D. Stainless Steel: ASTM A240/A240M.
- E. Threaded Rods: Continuously threaded. Zinc-plated or galvanized steel for indoor applications and stainless steel for outdoor applications. Mating nuts and washers of similar materials as rods.

- F. Grout: ASTM C1107/C1107M, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with requirements in Section 07 8413 "Penetration Firestopping" for firestopping materials and installation for penetrations through fire-rated walls, ceilings, and assemblies.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-58. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-58. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
 - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.
 - 2. Field fabricate from ASTM A36/A36M, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled strut systems.
- D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- E. Fastener System Installation:
 - 1. Powder-actuated fasteners are not allowed.
 - 2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to the manufacturer's written instructions.
- F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.

- H. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- I. Install lateral bracing with pipe hangers and supports to prevent swaying.
- J. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- K. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- L. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- M. Insulated Piping:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
 - 2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
 - 3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
 - 4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
 - 5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
 - 6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make bearing surface smooth.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.4 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for [trapeze pipe hangers] [and] [equipment supports].
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.6 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Touchup: Comply with requirements in Section 09 9123 "Interior Painting" for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A780/A780M.

3.7 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-58 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports, metal trapeze pipe hangers and metal framing systems and attachments for general service applications.
- F. Use copper-plated pipe hangers and copper attachments for copper piping and tubing.
- G. Use padded hangers for piping that is subject to scratching.
- H. Use thermal-hanger shield inserts for insulated piping and tubing.
- I. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
 - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F, pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
 - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
 - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
 - 5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
 - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
 - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
 - 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
 - 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
 - 12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
 - 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.

14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
 16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
 17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction might occur.
 19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is unnecessary.
 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is unnecessary.
 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- J. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- K. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- L. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.

5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- M. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- N. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.

8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- O. Comply with MSS SP-58 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- P. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- Q. Use mechanical-expansion anchors instead of building attachments where required in concrete construction.

END OF SECTION

SECTION 230548.13 - VIBRATION CONTROLS FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Elastomeric isolation pads.
2. Elastomeric isolation mounts.
3. Restrained elastomeric isolation mounts.
4. Pipe-riser resilient support.
5. Resilient pipe guides.
6. Elastomeric hangers.
7. Spring hangers.
8. Snubbers.
9. Restraint accessories.
10. Post-installed concrete anchors.
11. Concrete inserts.
12. Vibration isolation equipment bases.

B. Related Requirements:

1. Section 22 0548.13 "Vibration Controls for Plumbing Piping and Equipment" for devices for plumbing equipment and systems.

1.3 DEFINITIONS

- A. IBC: International Building Code.
- B. OSHPD: Office of Statewide Health Planning and Development (for the State of California owned and regulated medical facilities).

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
2. Include load rating for each wind-force-restraint fitting and assembly.

3. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of vibration isolation device and wind-force-restraint component.
4. Annotate to indicate application of each product submitted and compliance with requirements.
5. Interlocking Snubbers: Include ratings for horizontal, vertical, and combined loads.

B. Shop Drawings:

1. Detail fabrication and assembly of equipment bases.
2. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.

C. Delegated-Design Submittal:

1. For each wind-load protection device that is required by this Section or is indicated on Drawings, submit the following:
 - a. Vibration Isolator and Wind-Load-Restraint Selection: Select vibration isolators, wind-load restraints, and vibration isolation bases complying with performance requirements, design criteria, and analysis data.
 - b. Riser Supports: Include riser diagrams and calculations showing anticipated expansion and contraction at each support point, initial and final loads on building structure, and spring deflection changes. Include certification by professional engineer that riser system was examined for excessive stress and that none exists.
 - c. Concrete Anchors and Inserts: Include calculations showing anticipated wind loads.
 - d. Wind-Load Design Calculations: Submit all static and dynamic loading calculations prepared under "Wind-Load Design Calculations" Paragraph in "Performance Requirements" Article.
 - e. Qualified Professional Engineer: All designated-design submittals for wind-restraint calculations are to be signed and sealed by qualified professional engineer responsible for their preparation.
2. All delegated-design submittals for wind-restraint detail Drawings are to be signed and sealed by qualified professional engineer responsible for their preparation.
3. Product Listing, Preapproval, and Evaluation Documentation: By an agency acceptable to authorities having jurisdiction, showing maximum ratings of restraint items and basis for approval (tests or calculations).
4. Design Calculations for Vibration Isolation Devices: Calculate static and dynamic loading due to equipment weight and operating forces required to select proper vibration isolators, and to design vibration isolation bases.
5. Riser Supports: Include riser diagrams and calculations showing anticipated expansion and contraction at each support point, initial and final loads on building structure, and spring deflection changes. Include certification that riser system was examined for excessive stress and that none exists.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show coordination of vibration isolation device installation for HVAC piping and equipment with other systems and equipment in the vicinity, including other supports and restraints.
- B. Qualification Data: For testing agency.
- C. Welding certificates.
- D. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data to include in operation and maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct testing indicated, be an NRTL as defined by OSHA in 29 CFR 1910.7 and be acceptable to authorities having jurisdiction.
- B. Welding Qualifications: Qualify procedures and personnel in accordance with AWS D1.1/D1.1M, "Structural Welding Code - Steel."

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design system.
 - 1. Wind-Load Performance: Equipment shall withstand the effects of high wind events determined in accordance with ASCE/SEI 7-16.
- B. Consequential Damage: Provide additional restraints for suspended HVAC components or anchorage of roof-mounted HVAC components as indicated in ASCE/SEI 7-16 so that failure of a non-essential or essential HVAC component will not cause the failure of any other essential architectural, mechanical, or electrical building component.
- C. Fire/Smoke Resistance: All components that are not constructed of ferrous metals must have a maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested by an NRTL in accordance with ASTM E84 or UL 723, and be so labeled.
- D. Component Supports:
 - 1. Load ratings, features, and applications of all reinforcement components must be based on testing standards of a nationally recognized testing agency.

2.2 ELASTOMERIC ISOLATION PADS

A. Elastomeric Isolation Pads:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent
 - c. California Dynamics Corporation
 - d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund
 - g. Mason Industries, Inc.
 - h. Novia; A Division of C&P.
 - i. Vibration Eliminator Co., Inc.
 - j. Vibration Isolation
 - k. Vibration Management Corp.
 - l. Vibration Mountings & Controls, Inc.
2. Fabrication: Single or multiple layers of sufficient durometer stiffness for uniform loading over pad area.
3. Size: Factory or field cut to match requirements of supported equipment.
4. Minimum deflection as indicated on Drawings.
5. Pad Material: Oil- and water-resistant rubber.
6. Infused nonwoven cotton or synthetic fibers.
7. Load-bearing metal plates adhered to pads.
8. Sandwich-Core Material: Resilient and elastomeric.
 - a. Infused nonwoven cotton or synthetic fibers.

2.3 ELASTOMERIC ISOLATION MOUNTS

A. Elastomeric Isolation Mounts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent
 - c. California Dynamics Corporation
 - d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund
 - g. Mason Industries, Inc.
 - h. Novia; A Division of C&P.
 - i. Vibration Eliminator Co., Inc.
 - j. Vibration Isolation
 - k. Vibration Management Corp.
 - l. Vibration Mountings & Controls, Inc.

2. Mounting Plates:
 - a. Top Plate: Encapsulated steel load transfer top plates, factory drilled and threaded with threaded studs or bolts.
 - b. Baseplate: Encapsulated steel bottom plates with holes provided for anchoring to support structure.
3. Minimum deflection as indicated on Drawings.
4. Elastomeric Material: Molded, oil-resistant rubber, neoprene, or other elastomeric material.

2.4 RESTRAINED ELASTOMERIC ISOLATION MOUNTS

A. Restrained Elastomeric Isolation Mounts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent
 - c. California Dynamics Corporation
 - d. Isolation Technology, Inc.
 - e. Kinetics Noise Control, Inc.
 - f. Korfund
 - g. Mason Industries, Inc.
 - h. Novia; A Division of C&P.
 - i. Vibration Eliminator Co., Inc.
 - j. Vibration Isolation
 - k. Vibration Management Corp.
 - l. Vibration Mountings & Controls, Inc.
2. Description: All-directional isolator with restraints containing two separate and opposing elastomeric elements that prevent central threaded element and attachment hardware from contacting the housing during normal operation.
 - a. Housing: Cast-ductile iron or welded steel.
 - b. Elastomeric Material: Molded, oil-resistant rubber, neoprene, or other elastomeric material.
3. Minimum deflection as indicated on Drawings.

2.5 PIPE-RISER RESILIENT SUPPORT

A. All-Directional, Acoustical Pipe Anchor Consisting of Two Steel Tubes Separated by a Minimum 1/2-inch- Thick Neoprene:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. California Dynamics Corporation
 - b. Kinetics Noise Control, Inc.
 - c. Mason Industries, Inc.
 - d. Vibration Eliminator Co., Inc.
 - e. Vibration Management Corp.
2. Vertical-Limit Stops: Steel and neoprene vertical-limit stops arranged to prevent vertical travel in both directions.
 3. Maximum Load Per Support: 500 psi on isolation material providing equal isolation in all directions.
 4. Minimum deflection as indicated on Drawings.

2.6 RESILIENT PIPE GUIDES

- A. Telescopic Arrangement of Two Steel Tubes or Post and Sleeve Arrangement Separated by a Minimum 1/2-inch- Thick Neoprene:
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. California Dynamics Corporation
 - b. Kinetics Noise Control, Inc.
 - c. Mason Industries, Inc.
 - d. Vibration Eliminator Co., Inc.
 - e. Vibration Management Corp.
 - f. Vibration Mountings & Controls, Inc.
 2. Factory-Set Height Guide with Shear Pin: Shear pin shall be removable and reinsertable to allow for selection of pipe movement. Guides shall be capable of motion to meet location requirements.

2.7 ELASTOMERIC HANGERS

- A. Elastomeric Mount in a Steel Frame with Upper and Lower Steel Hanger Rods:
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent.
 - c. California Dynamics Corporation
 - d. Kinetics Noise Control, Inc.
 - e. Mason Industries, Inc.
 - f. Novia; A Division of C&P.
 - g. Vibration Eliminator Co., Inc.
 - h. Vibration Isolation
 - i. Vibration Management Corp.
 - j. Vibration Mountings & Controls, Inc.

2. Frame: Steel, fabricated with a connection for an upper threaded hanger rod and an opening on the underside to allow for a maximum of 30 degrees of angular lower hanger-rod misalignment without binding or reducing isolation efficiency.
3. Damping Element: Molded, oil-resistant rubber, neoprene, or other elastomeric material with a projecting bushing for the underside opening preventing steel-to-steel contact.
4. Minimum deflection as indicated on Drawings.

2.8 SPRING HANGERS

A. Combination Coil-Spring and Elastomeric-Insert Hanger with Spring and Insert in Compression:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Ace Mountings Co., Inc.
 - b. CADDY; nVent
 - c. California Dynamics Corporation
 - d. Kinetics Noise Control, Inc.
 - e. Mason Industries, Inc.
 - f. Novia; A Division of C&P
 - g. Vibration Eliminator Co., Inc.
 - h. Vibration Isolation
 - i. Vibration Management Corp.
 - j. Vibration Mountings & Controls, Inc.
2. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
6. Minimum deflection as indicated on Drawings.
7. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
8. Elastomeric Element: Molded, oil-resistant rubber or neoprene. Steel-washer-reinforced cup to support spring and bushing projecting through bottom of frame.
9. Adjustable Vertical Stop: Steel washer with neoprene washer "up-stop" on lower threaded rod.
10. Self-centering hanger rod cap to ensure concentricity between hanger rod and support spring coil.

2.9 SNUBBERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. CADDY; nVent

2. Kinetics Noise Control, Inc.
3. Mason Industries, Inc.
4. Vibration Management Corp.
5. Vibration Mountings & Controls, Inc.

B. Description: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.

1. Post-Installed Concrete Anchor Bolts: Secure to concrete surface with post-installed concrete anchors. Anchors to be prequalified in accordance with ACI 355.2 testing and designated in accordance with ACI 318-14 Ch. 17 for 2015 or 2018 IBC.
2. Preset Concrete Inserts: Prequalified in accordance with ICC-ES AC446 testing.
3. Anchors in Masonry: Design in accordance with TMS 402.
4. Resilient Isolation Washers and Bushings: Oil- and water-resistant neoprene.
5. Resilient Cushion: Maximum 1/4-inch air gap, and minimum 1/4 inch thick.

2.10 RESTRAINTS - RIGID TYPE

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. B-line; Eaton, Electrical Sector
2. CADDY; nVent
3. California Dynamics Corporation
4. Hilti, Inc.
5. Isolation Technology, Inc.
6. TOLCO
7. Unistrut; Atkore International
8. Vibration Mountings & Controls, Inc.

B. Description: Shop- or field-fabricated bracing assembly made of AISI S110-07-S1 slotted steel channels, ANSI/ASTM A53/A53M steel pipe as per NFPA 13, or other rigid steel brace member. Includes accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; rated in tension, compression, and torsion forces.

2.11 RESTRAINT ACCESSORIES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. B-line; Eaton, Electrical Sector
2. CADDY; nVent
3. Hilti, Inc.
4. Loos & Co.
5. Mason Industries, Inc.
6. TOLCO
7. Unistrut; Atkore International

- B. Hanger-Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections to hanger rod.
- C. Hinged and Swivel Brace Attachments: Multifunctional steel connectors for attaching hangers to rigid channel bracings and restraint cables.
- D. Bushings for Floor-Mounted Equipment Anchor Bolts: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchor bolts and studs.
- E. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices used.
- F. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.

2.12 POST-INSTALLED CONCRETE ANCHORS

A. Mechanical Anchor Bolts:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-line; Eaton, Electrical Sector
 - b. Hilti, Inc.
 - c. Mason Industries, Inc.
 - d. Powers Fasteners
 - e. Simpson Strong-Tie Co., Inc.
 - f. Unistrut; Atkore International
- 2. Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength for anchor and as tested according to ASTM E488/E488M.

B. Adhesive Anchor Bolts:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-line; Eaton, Electrical Sector
 - b. Hilti, Inc.
 - c. Mason Industries, Inc.
 - d. Powers Fasteners
 - e. Simpson Strong-Tie Co., Inc.
 - f. Unistrut; Atkore International

2. Drilled-in and capsule anchor system containing PVC or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E488/E488M.
- C. Provide post-installed concrete anchors that have been prequalified for use in wind-load applications. Post-installed concrete anchors must comply with all requirements of [ASCE/SEI 7-05, Ch. 13] [ASCE/SEI 7-10, Ch. 13] [ASCE/SEI 7-16, Ch. 13].
1. Prequalify post-installed anchors in concrete in accordance with ACI 355.2 or other approved qualification testing procedures.
 2. Prequalify post-installed anchors in masonry in accordance with approved qualification procedures.
- D. Expansion-type anchor bolts are not permitted for equipment in excess of 10 hp that is not vibration isolated.
1. Undercut expansion anchors are permitted.

2.13 CONCRETE INSERTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. B-line; Eaton, Electrical Sector
 2. Hilti, Inc.
 3. Mason Industries, Inc.
 4. Powers Fasteners
 5. Simpson Strong-Tie Co., Inc.
 6. Unistrut; Atkore International
- B. Provide preset concrete inserts that are prequalified in accordance with ICC-ES AC466 testing.
- C. Comply with ANSI/MSS SP-58.

2.14 VIBRATION ISOLATION EQUIPMENT BASES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. CADDY; nVent
 2. California Dynamics Corporation
 3. Kinetics Noise Control, Inc.
 4. Mason Industries, Inc.
 5. Novia; A Division of C&P
 6. Vibration Eliminator Co., Inc.
 7. Vibration Isolation
 8. Vibration Management Corp.

9. Vibration Mountings & Controls, Inc.
- B. Steel Rails: Factory-fabricated, welded, structural-steel rails.
1. Design Requirements: Lowest possible mounting height with not less than 1-inch clearance above the floor. Include equipment anchor bolts and auxiliary motor slide rails.
 - a. Include supports for suction and discharge elbows for pumps.
 2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A36/A36M. Rails shall have shape to accommodate supported equipment.
 3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
- C. Steel Bases: Factory-fabricated, welded, structural-steel bases and rails.
1. Design Requirements: Lowest possible mounting height with not less than 1-inch clearance above the floor. Include equipment anchor bolts and auxiliary motor slide bases or rails.
 - a. Include supports for suction and discharge elbows for pumps.
 2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A36/A36M. Bases shall have shape to accommodate supported equipment.
 3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
- D. Concrete Inertia Base: Factory-fabricated, welded, structural-steel bases and rails ready for placement of cast-in-place concrete.
1. Design Requirements: Lowest possible mounting height with not less than 1-inch clearance above the floor. Include equipment anchor bolts and auxiliary motor slide bases or rails.
 - a. Include supports for suction and discharge elbows for pumps.
 2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A36/A36M. Bases shall have shape to accommodate supported equipment.
 3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
 4. Fabrication: Fabricate steel templates to hold equipment anchor-bolt sleeves and anchors in place during placement of concrete. Obtain anchor-bolt templates from supported equipment manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and equipment to receive vibration isolation and wind-load control devices for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Multiple Pipe Supports: Secure pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
- B. Hanger-Rod Stiffeners: Install hanger-rod stiffeners where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to wind-load forces.
- C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength is adequate to carry static and wind force loads within specified loading limits.

3.3 INSTALLATION OF VIBRATION AND WIND-LOAD CONTROL DEVICES

- A. Provide vibration and wind-load control devices for systems and equipment where indicated in Equipment Schedules or Vibration-Control Device Schedules on Drawings, where Specifications indicate they are to be installed on specific equipment and systems, and where required by applicable codes.
- B. Coordinate location of embedded connection hardware with supported equipment attachment and mounting points and with requirements for concrete reinforcement and formwork specified in Section 03 3000 "Cast-in-Place Concrete."
- C. Installation of vibration isolators and wind-load restraints must not cause any change of position of equipment, piping, or ductwork resulting in stresses or misalignment.
- D. Comply with requirements in Section 07 7200 "Roof Accessories" for installation of roof curbs, equipment supports, and roof penetrations.
- E. Equipment Restraints:
 - 1. Install snubbers on HVAC equipment mounted on vibration isolators. Locate snubbers as close as possible to vibration isolators and bolt to equipment base and supporting structure.
 - 2. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.

3. Install wind-load-restraint devices using methods approved by [an evaluation service member of ICC-ES] [OSHPD] [an agency acceptable to authorities having jurisdiction] that provides required submittals for component.

F. Piping Restraints:

1. Comply with requirements in MSS SP-127.
2. Space lateral supports a maximum of 40 feet o.c., and longitudinal supports a maximum of 80 feet o.c.
3. Brace a change of direction longer than 12 feet.

G. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.

H. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.

I. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.

J. Post-Installed Concrete Anchors:

1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
3. Wedge-Type Anchor Bolts: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
4. Adhesive-Type Anchor Bolts: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
5. Set anchors to manufacturer's recommended torque, using a torque wrench.
6. Install zinc-coated steel anchors for interior and stainless steel anchors for exterior applications.

3.4 ACCOMMODATION OF DIFFERENTIAL MOTION

- A. Provide flexible connections in piping systems where they cross structural joints and other point where differential movement may occur. Provide adequate flexibility to accommodate differential movement as determined in accordance with ASCE/SEI 7. Comply with requirements in Section 23 2113 "Hydronic Piping" and Section 23 2116 "Hydronic Piping Specialties" for piping flexible connections.

3.5 INSTALLATION OF VIBRATION ISOLATION EQUIPMENT BASES

- A. Coordinate location of embedded connection hardware with supported equipment attachment and mounting points and with requirements for concrete reinforcement and formwork specified in Section 03 3000 "Cast-in-Place Concrete."
- B. Coordinate dimensions of equipment bases with requirements of isolated equipment specified in this and other Sections. Where dimensions of base are indicated on Drawings, they may require adjustment to accommodate isolated equipment.

3.6 ADJUSTING

- A. Adjust isolators after system is at operating weight.
- B. Adjust limit stops on restrained-spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.

3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections.
- D. Tests and Inspections:
 - 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
 - 2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
 - 3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
 - 4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
 - 5. Test to 90 percent of rated proof load of device.
 - 6. Measure isolator restraint clearance.
 - 7. Measure isolator deflection.
 - 8. Verify snubber minimum clearances.
 - 9. Test and adjust restrained-air-spring isolator controls and safeties.
- E. Remove and replace malfunctioning units and retest as specified above.
- F. Prepare test and inspection reports.

END OF SECTION

SECTION 230553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Equipment labels.
 - 2. Warning signs and labels.
 - 3. Duct labels.
 - 4. Warning tags.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- D. Valve numbering scheme.
- E. Valve Schedules: For each piping system to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

- A. Metal Labels for Equipment:
 - 1. Material and Thickness: Brass, 0.032-inch, stainless steel, 0.025-inch, aluminum, 0.032-inch or anodized aluminum, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 - 2. Letter Color: White.
 - 3. Background Color: Black.
 - 4. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.

5. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
 6. Fasteners: Stainless-steel rivets or self-tapping screws.
 7. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- B. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), and the Specification Section number and title where equipment is specified.
- C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 WARNING SIGNS AND LABELS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Brady Corporation
 2. Brimar Industries, Inc.
 3. Carlton Industries, LP
 4. Champion America
 5. Craftmark Pipe Markers
 6. emedco
 7. LEM Products Inc.
 8. Marking Services Inc.
 9. National Marker Company
 10. Seton Identification Products; a Brady Corporation company
 11. Stranco, Inc.
- B. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
- C. Letter Color: White.
- D. Background Color: Red.
- E. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- F. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- G. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.

- H. Fasteners: Stainless-steel rivets or self-tapping screws.
- I. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- J. Label Content: Include caution and warning information plus emergency notification instructions.

2.3 DUCT LABELS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Brady Corporation
 - 2. Brimar Industries, Inc.
 - 3. Carlton Industries, LP
 - 4. Champion America
 - 5. Craftmark Pipe Markers
 - 6. emedco
 - 7. Kolbi Pipe Marker Co.
 - 8. LEM Products Inc.
 - 9. Marking Services Inc.
 - 10. Seton Identification Products; a Brady Corporation company
- B. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
- C. Letter Color: White.
- D. Background Color: Black.
- E. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- F. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- G. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Duct Label Contents: Include identification of duct service using same designations or abbreviations as used on Drawings; also include duct size and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with duct system service lettering to accommodate both directions or as separate unit on each duct label to indicate flow direction.

2.4 WARNING TAGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Brady Corporation
 2. Brimar Industries, Inc.
 3. Champion America
 4. Craftmark Pipe Markers
 5. emedco
 6. Kolbi Pipe Marker Co.
 7. LEM Products Inc.
 8. Marking Services Inc.
 9. Seton Identification Products; a Brady Corporation company
- B. Description: Preprinted or partially preprinted accident-prevention tags of plasticized card stock with matte finish suitable for writing.
1. Size: Approximately 4 by 7 inches.
 2. Fasteners: Brass grommet and wire.
 3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
 4. Color: Safety-yellow background with black lettering.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

3.4 DUCT LABEL INSTALLATION

- A. Install plastic-laminated duct labels with permanent adhesive on air ducts in the following color codes:
 - 1. Blue: For cold-air supply ducts.
 - 2. Green: For exhaust and outside-air ducts.
- B. Locate labels near points where ducts enter into and exit from concealed spaces and at maximum intervals of 50 feet in each space where ducts are exposed or concealed by removable ceiling system.

3.5 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION

SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Testing, Adjusting, and Balancing of Air Systems:
 - a. Variable-air-volume systems.
2. Testing, adjusting, and balancing of equipment.
3. Sound tests.
4. Vibration tests.
5. Duct leakage tests verification.
6. HVAC-control system verification.

1.3 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. NEBB: National Environmental Balancing Bureau.
- C. TAB: Testing, adjusting, and balancing.
- D. TABB: Testing, Adjusting, and Balancing Bureau.
- E. TAB Specialist: An independent entity meeting qualifications to perform TAB work.
- F. TDH: Total dynamic head.
- G. UFAD: Underfloor air distribution.

1.4 PREINSTALLATION MEETINGS

- A. TAB Conference: Conduct a TAB conference at the project site after approval of the TAB strategies and procedures plan, to develop a mutual understanding of the details. Provide a minimum of 14 days' advance notice of scheduled meeting time and location.
 1. Minimum Agenda Items:

- a. The Contract Documents examination report.
- b. The TAB plan.
- c. Needs for coordination and cooperation of trades and subcontractors.
- d. Proposed procedures for documentation and communication flow.

1.5 ACTION SUBMITTALS

- A. Sustainable Design Submittals:

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: Within 30 days of Contractor's Notice to Proceed, submit documentation that the TAB specialist and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.
- B. Contract Documents Examination Report: Within 60 days of Contractor's Notice to Proceed, submit the Contract Documents review report, as specified in Part 3.
- C. Strategies and Procedures Plan: Within 90 days of Contractor's Notice to Proceed, submit TAB strategies and step-by-step procedures, as specified in "Preparation" Article.
- D. System Readiness Checklists: Within 90 days of Contractor's Notice to Proceed, submit system readiness checklists, as specified in "Preparation" Article.
- E. Examination Report: Submit a summary report of the examination review required in "Examination" Article.
- F. Certified TAB reports.
- G. Sample report forms.
- H. Instrument calibration reports, to include the following:
 1. Instrument type and make.
 2. Serial number.
 3. Application.
 4. Dates of use.
 5. Dates of calibration.

1.7 QUALITY ASSURANCE

- A. TAB Specialists Qualifications, Certified by AABC:
 1. TAB Field Supervisor: Employee of the TAB specialist and certified by AABC.
 2. TAB Technician: Employee of the TAB specialist and certified by AABC.
- B. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."

- C. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6.7.2.3 - "System Balancing."
- D. Code and AHJ Compliance: TAB is required to comply with governing codes and requirements of authorities having jurisdiction.

1.8 FIELD CONDITIONS

- A. Full Owner Occupancy: Owner will occupy the site and existing building during entire TAB period. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.
- B. Partial Owner Occupancy: Owner may occupy completed areas of building before Final Acceptance. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.
- B. Examine installed systems for balancing devices, such as test ports, gauge cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.
- C. Examine the approved submittals for HVAC systems and equipment.
- D. Examine design data, including HVAC system descriptions, statements of design assumptions for environmental conditions and systems output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine ceiling plenums and underfloor air plenums used for HVAC to verify that they are properly separated from adjacent areas and sealed.
- F. Examine equipment performance data, including fan and pump curves.
 - 1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.

2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.
- G. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.
- H. Examine test reports specified in individual system and equipment Sections.
- I. Examine HVAC equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.
- J. Examine terminal units, such as variable-air-volume boxes, and verify that they are accessible and their controls are connected and functioning.
- K. Examine temporary and permanent strainers. Verify that temporary strainer screens used during system cleaning and flushing have been removed and permanent strainer baskets are installed and clean.
- L. Examine control valves for proper installation for their intended function of isolating, throttling, diverting, or mixing fluid flows.
- M. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- N. Examine system pumps to ensure absence of entrained air in the suction piping.
- O. Examine operating safety interlocks and controls on HVAC equipment.
- P. Examine control dampers for proper installation for their intended function of isolating, throttling, diverting, or mixing air flows.
- Q. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.2 PREPARATION

- A. Prepare a TAB plan that includes the following:
 1. Equipment and systems to be tested.
 2. Strategies and step-by-step procedures for balancing the systems.
 3. Instrumentation to be used.
 4. Sample forms with specific identification for all equipment.
- B. Perform system-readiness checks of HVAC systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:
 1. Airside:

- a. Verify that leakage and pressure tests on air distribution systems have been satisfactorily completed.
- b. Duct systems are complete with terminals installed.
- c. Volume, smoke, and fire dampers are open and functional.
- d. Clean filters are installed.
- e. Fans are operating, free of vibration, and rotating in correct direction.
- f. Variable-frequency controllers' startup is complete and safeties are verified.
- g. Automatic temperature-control systems are operational.
- h. Ceilings are installed.
- i. Windows and doors are installed.
- j. Suitable access to balancing devices and equipment is provided.

3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system in accordance with the procedures contained in AABC's "National Standards for Total System Balance", ASHRAE and in this Section.
- B. Cut insulation, ducts, pipes, and equipment casings for installation of test probes to the minimum extent necessary for TAB procedures.
 1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
 2. After testing and balancing, install test ports and duct access doors that comply with requirements in Section 23 3300 "Air Duct Accessories."
 3. Where holes for probes are required in piping or hydronic equipment, install pressure and temperature test plugs to seal systems.
 4. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish in accordance with Section 23 0713 "Duct Insulation," Section 23 0716 "HVAC Equipment Insulation," and Section 23 0719 "HVAC Piping Insulation."
- C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) units.

3.4 TESTING, ADJUSTING, AND BALANCING OF HVAC EQUIPMENT

- A. Test, adjust, and balance HVAC equipment indicated on Drawings, including, but not limited to, the following:
 1. Motors.
 2. Pumps.
 3. Fans and ventilators.
 4. Terminal units.
 5. Boilers.
 6. Heat exchangers.

7. Water chillers.
8. Air-handling units.
9. Coils.
10. Humidifiers.

3.5 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Crosscheck the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' Record drawings duct layouts.
- C. For variable-air-volume systems, develop a plan to simulate diversity.
- D. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.
- E. Check airflow patterns from the outdoor-air louvers and dampers and the exhaust-air dampers through the supply-fan discharge.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.
- K. Check for proper sealing of air-handling-unit components.

3.6 PROCEDURES FOR VARIABLE-AIR-VOLUME SYSTEMS

- A. Adjust the variable-air-volume systems as follows:
 1. Verify that the system static pressure sensor is located two-thirds of the distance down the duct from the fan discharge.
 2. Verify that the system is under static pressure control.
 3. Select the terminal unit that is most critical to the supply-fan airflow. Measure inlet static pressure and adjust system static pressure control set point so the entering static pressure for the critical terminal unit is not less than the sum of the terminal-unit manufacturer's recommended minimum inlet static pressure plus the static pressure needed to overcome terminal-unit discharge system losses.
 4. Calibrate and balance each terminal unit for maximum and minimum design airflow as follows:

- a. Adjust controls so that terminal is calling for maximum airflow. Some controllers require starting with minimum airflow. Verify calibration procedure for specific project.
 - b. Measure airflow and adjust calibration factor as required for design maximum airflow. Record calibration factor.
 - c. When maximum airflow is correct, balance the air outlets downstream from terminal units.
 - d. Adjust controls so that terminal is calling for minimum airflow.
 - e. Measure airflow and adjust calibration factor as required for design minimum airflow. Record calibration factor. If no minimum calibration is available, note any deviation from design airflow.
 - f. On constant volume terminals, in critical areas where room pressure is to be maintained, verify that the airflow remains constant over the full range of full cooling to full heating. Note any deviation from design airflow or room pressure.
5. After terminals have been calibrated and balanced, test and adjust system for total airflow. Adjust fans to deliver total design airflows within the maximum allowable fan speed listed by fan manufacturer.
- a. Set outside-air dampers for proper position that simulates minimum outdoor-air conditions.
 - b. Set terminals for maximum airflow. If system design includes diversity, adjust terminals for maximum and minimum airflow, so that connected total matches fan selection and simulates actual load in the building.
 - c. Where duct conditions allow, measure airflow by main Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses close to the fan and prior to any outlets, to obtain total airflow.
 - d. Where duct conditions are unsuitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
6. Measure fan static pressures as follows:
- a. Measure static pressure directly at the fan outlet or through the flexible connection.
 - b. Measure static pressure directly at the fan inlet or through the flexible connection.
 - c. Measure static pressure across each component that makes up the air-handling system.
 - d. Report any artificial loading of filters at the time static pressures are measured.
7. Set final outside airflow to the fan while operating at maximum outdoor airflow.
- a. Verify that terminal units are meeting design airflow under system maximum flow.
8. Re-measure the inlet static pressure at the most critical terminal unit, and adjust the system static pressure set point to the most energy-efficient set point to maintain the optimum system static pressure. Record set point and give to controls Contractor.
9. Verify final system conditions as follows:
- a. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to match design if necessary.
 - b. Re-measure and confirm that total airflow is within design.
 - c. Re-measure final fan operating data, speed, volts, amps, and static profile.

- d. Mark final settings.

3.7 PROCEDURES FOR MOTORS

- A. Motors 1/2> HP and Larger: Test at final balanced conditions and record the following data:
 1. Manufacturer's name, model number, and serial number.
 2. Motor horsepower rating.
 3. Motor rpm.
 4. Phase and hertz.
 5. Nameplate and measured voltage, each phase.
 6. Nameplate and measured amperage, each phase.
 7. Starter size and thermal-protection-element rating.
 8. Service factor and frame size.
- B. Motors Driven by Variable-Frequency Controllers: Test manual bypass of controller to prove proper operation.

3.8 PROCEDURES FOR HEAT-TRANSFER COILS

- A. Measure, adjust, and record the following data for each electric heating coil:
 1. Nameplate data.
 2. Airflow.
 3. Entering- and leaving-air temperature at full load.
 4. Air pressure drop.
 5. Voltage and amperage input of each phase at full load.
 6. Calculated kilowatt at full load.
 7. Fuse or circuit-breaker rating for overload protection.
- B. Measure, adjust, and record the following data for each refrigerant coil:
 1. Dry-bulb temperature of entering and leaving air.
 2. Wet-bulb temperature of entering and leaving air.
 3. Airflow.
 4. Air pressure drop.
 5. Entering and leaving refrigerant pressure and temperatures.

3.9 SOUND TESTS

- A. After systems are balanced and Final Acceptance, measure and record sound levels at five locations as designated by the Architect.
- B. Instrumentation:
 1. The sound-testing meter shall be a portable, general-purpose testing meter consisting of a microphone, processing unit, and readout.

2. The sound-testing meter shall be capable of showing fluctuations at minimum and maximum levels, and measuring the equivalent continuous sound pressure level (L_{eq}).
3. The sound-testing meter must be capable of using one-third octave band filters to measure mid-frequencies from 31.5 Hz to 8000 Hz.
4. The accuracy of the sound-testing meter shall be plus or minus one decibel.

C. Test Procedures:

1. Perform test at quietest background noise period. Note cause of unpreventable sound that affects test outcome.
2. Equipment should be operating at design values.
3. Calibrate the sound-testing meter prior to taking measurements.
4. Use a microphone suitable for the type of noise levels measured that is compatible with meter. Provide a windshield for outside or in-duct measurements.
5. Record a set of background measurements in dBA and sound pressure levels in the eight unweighted octave bands 63 Hz to 8000 Hz (NC) with the equipment off.
6. Take sound readings in dBA and sound pressure levels in the eight unweighted octave bands 63 Hz to 8000 Hz (NC) with the equipment operating.
7. Take readings no closer than 36 inches from a wall or from the operating equipment and approximately 60 inches from the floor, with the meter held or mounted on a tripod.
8. For outdoor measurements, move sound-testing meter slowly and scan area that has the most exposure to noise source being tested. Use A-weighted scale for this type of reading.

D. Reporting:

1. Report shall record the following:
 - a. Location.
 - b. System tested.
 - c. dBA reading.
 - d. Sound pressure level in each octave band with equipment on and off.
2. Plot sound pressure levels on Noise Criteria (NC) worksheet with equipment on and off.

3.10 VIBRATION TESTS

- A. After systems are balanced and Final Acceptance, measure and record vibration levels on equipment having motor horsepower equal to or greater than 10.
- B. Instrumentation:
 1. Use portable, battery-operated, and microprocessor-controlled vibration meter with or without a built-in printer.
 2. The meter shall automatically identify engineering units, filter bandwidth, amplitude, and frequency scale values.
 3. The meter shall be able to measure machine vibration displacement in mils of deflection, velocity in inches per second, and acceleration in inches per second squared.
 4. Verify calibration date is current for vibration meter before taking readings.

C. Test Procedures:

1. To ensure accurate readings, verify that accelerometer has a clean, flat surface and is mounted properly.
2. With the unit running, set up vibration meter in a safe, secure location. Connect transducer to meter with proper cables. Hold magnetic tip of transducer on top of the bearing, and measure unit in mils of deflection. Record measurement, then move transducer to the side of the bearing and record in mils of deflection. Record an axial reading in mils of deflection by holding nonmagnetic, pointed transducer tip on end of shaft.
3. Change vibration meter to velocity (inches per second) measurements. Repeat and record above measurements.
4. Record CPM or rpm.
5. Read each bearing on motor, fan, and pump as required. Track and record vibration levels from rotating component through casing to base.

D. Reporting:

1. Report shall record location and the system tested.
2. Include horizontal-vertical-axial measurements for tests.
3. Verify that vibration limits follow Specifications, or, if not specified, follow the General Machinery Vibration Severity Chart or Vibration Acceleration General Severity Chart from AABC's "National Standards for Total System Balance." Acceptable levels of vibration are normally "smooth" to "good."
4. Include in General Machinery Vibration Severity Chart, with conditions plotted.

3.11 DUCT LEAKAGE TESTS

- A. Witness the duct leakage testing performed by Installer.
- B. Verify that proper test methods are used and that leakage rates are within specified limits.
- C. Report deficiencies observed.

3.12 PIPE LEAKAGE TESTS

- A. Witness the pipe pressure testing performed by Installer.
- B. Verify that proper test methods are used and that leakage rates are within specified limits.
- C. Report deficiencies observed.

3.13 HVAC CONTROLS VERIFICATION

- A. In conjunction with system balancing, perform the following:
 1. Verify HVAC control system is operating within the design limitations.
 2. Confirm that the sequences of operation are in compliance with Contract Documents.
 3. Verify that controllers are calibrated and function as intended.

4. Verify that controller set points are as indicated.
5. Verify the operation of lockout or interlock systems.
6. Verify the operation of valve and damper actuators.
7. Verify that controlled devices are properly installed and connected to correct controller.
8. Verify that controlled devices travel freely and are in position indicated by controller: open, closed, or modulating.
9. Verify location and installation of sensors to ensure that they sense only intended temperature, humidity, or pressure.

- B. Reporting: Include a summary of verifications performed, remaining deficiencies, and variations from indicated conditions.

3.14 PROCEDURES FOR TESTING, ADJUSTING, AND BALANCING EXISTING SYSTEMS

- A. Perform a preconstruction inspection of existing equipment that is to remain and be reused.
1. Measure and record the operating speed, airflow, and static pressure of each fan and equipment with fan(s).
 2. Measure and record flows, temperatures, and pressures of each piece of equipment in each hydronic system. Compare the values to design or nameplate information, where information is available.
 3. Measure motor voltage and amperage. Compare the values to motor nameplate information.
 4. Check the condition of filters.
 5. Check the operation of the drain pan and condensate-drain trap.
 6. Check bearings and other lubricated parts for proper lubrication.
 7. Report on the operating condition of the equipment and the results of the measurements taken. Report deficiencies.
- B. TAB After Construction: Before performing testing and balancing of renovated existing systems, inspect existing equipment that is to remain and be reused to verify that existing equipment has been cleaned and refurbished in accordance with renovation scope indicated by Contract Documents. Verify the following:
1. New filters are installed.
 2. Coils are clean and fins combed.
 3. Drain pans are clean.
 4. Fans are clean.
 5. Bearings and other parts are properly lubricated.
 6. Deficiencies noted in the preconstruction report are corrected.
- C. Perform testing and balancing of existing systems to the extent that existing systems are affected by the renovation work.
1. Compare the indicated airflow of the renovated work to the measured fan airflows, and determine the new fan speed and the face velocity of filters and coils.
 2. Verify that the indicated airflows of the renovated work result in filter and coil face velocities and fan speeds that are within the acceptable limits defined by equipment manufacturer.

3. If calculations increase or decrease the airflow rates and water flow rates by more than 5 percent, make equipment adjustments to achieve the calculated rates. If increase or decrease is 5 percent or less, equipment adjustments are not required.
4. Balance each air outlet.

3.15 TOLERANCES

- A. Set HVAC system's airflow rates and water flow rates within the following tolerances:
 1. Supply and Exhaust Fans and Equipment with Fans: Plus or minus 10 percent. If design value is less than 100 cfm, within 10 cfm.
 2. Air Outlets and Inlets: Plus or minus 10 percent and supply/exhaust room differential plus or minus 10% with no change in pressure relationship. If design value is less than 100 cfm, within 10 cfm.
 3. Heating-Water Flow Rate: Plus or minus 5 percent. If design value is less than 10 gpm, within 10 percent.
 4. Chilled-Water Flow Rate: Plus or minus 5 percent. If design value is less than 10 gpm, within 10 percent.
- B. Maintaining pressure relationships as designed shall have priority over the tolerances specified above.

3.16 PROGRESS REPORTING

- A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for system-balancing devices. Recommend changes and additions to system-balancing devices, to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance-measuring and -balancing devices.
- B. Status Reports: Prepare biweekly progress reports to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors.

3.17 FINAL REPORT

- A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
 1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
 2. Include a list of instruments used for procedures, along with proof of calibration.
 3. Certify validity and accuracy of field data.
- B. Final Report Contents: In addition to certified field-report data, include the following:
 1. Pump curves.

2. Fan curves.
3. Manufacturers' test data.
4. Field test reports prepared by system and equipment installers.
5. Other information relative to equipment performance; do not include Shop Drawings and Product Data.

C. General Report Data: In addition to form titles and entries, include the following data:

1. Title page.
2. Name and address of the TAB specialist.
3. Project name.
4. Project location.
5. Architect's name and address.
6. Engineer's name and address.
7. Contractor's name and address.
8. Report date.
9. Signature of TAB supervisor who certifies the report.
10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
11. Summary of contents, including the following:
 - a. Indicated versus final performance.
 - b. Notable characteristics of systems.
 - c. Description of system operation sequence if it varies from the Contract Documents.
12. Nomenclature sheets for each item of equipment.
13. Data for terminal units, including manufacturer's name, type, size, and fittings.
14. Notes to explain why certain final data in the body of reports vary from indicated values.
15. Test conditions for fans performance forms, including the following:
 - a. Settings for outdoor and exhaust-air dampers.
 - b. Conditions of filters.
 - c. Cooling coil, wet- and dry-bulb conditions.
 - d. Heating coil, dry-bulb conditions.
 - e. Face and bypass damper settings at coils.
 - f. Fan drive settings, including settings and percentage of maximum pitch diameter.
 - g. Variable-frequency controller settings for variable-air-volume systems.
 - h. Settings for pressure controller(s).
 - i. Other system operating conditions that affect performance.
16. Test conditions for pump performance forms, including the following:
 - a. Variable-frequency controller settings for variable-flow hydronic systems.
 - b. Settings for pressure controller(s).
 - c. Other system operating conditions that affect performance.

D. System Diagrams: Include schematic layouts of air and hydronic distribution systems. Present each system with single-line diagram and include the following:

1. Quantities of outdoor, supply, and exhaust airflows.

2. Water and steam flow rates.
3. Duct, outlet, and inlet sizes.
4. Pipe and valve sizes and locations.
5. Terminal units.
6. Balancing stations.
7. Position of balancing devices.

E. Air-Handling-Unit Test Reports: For air-handling units, include the following:

1. Unit Data:
 - a. Unit identification.
 - b. Location.
 - c. Make and type.
 - d. Model number and unit size.
 - e. Manufacturer's serial number.
 - f. Unit arrangement and class.
 - g. Discharge arrangement.
 - h. Sheave make, size in inches, and bore.
 - i. Center-to-center dimensions of sheave and amount of adjustments in inches.
 - j. Number, make, and size of belts.
 - k. Number, type, and size of filters.
2. Motor Data:
 - a. Motor make, and frame type and size.
 - b. Horsepower and speed.
 - c. Volts, phase, and hertz.
 - d. Full-load amperage and service factor.
 - e. Sheave make, size in inches, and bore.
 - f. Center-to-center dimensions of sheave and amount of adjustments in inches.
3. Test Data (Indicated and Actual Values):
 - a. Total airflow rate in cfm.
 - b. Total system static pressure in inches wg.
 - c. Fan speed.
 - d. Inlet and discharge static pressure in inches wg.
 - e. For each filter bank, filter static-pressure differential in inches wg.
 - f. Preheat-coil static-pressure differential in inches wg.
 - g. Cooling-coil static-pressure differential in inches wg.
 - h. Heating-coil static-pressure differential in inches wg.
 - i. List for each internal component with pressure-drop, static-pressure differential in inches wg.
 - j. Outdoor airflow in cfm.
 - k. Outdoor-air damper position.

F. Apparatus-Coil Test Reports:

1. Coil Data:

- a. System identification.
 - b. Location.
 - c. Coil type.
 - d. Number of rows.
 - e. Fin spacing in fins per inch o.c.
 - f. Make and model number.
 - g. Face area in sq. ft..
 - h. Tube size in NPS.
 - i. Tube and fin materials.
 - j. Circuiting arrangement.
2. Test Data (Indicated and Actual Values):
- a. Airflow rate in cfm.
 - b. Average face velocity in fpm.
 - c. Air pressure drop in inches wg.
 - d. Outdoor-air, wet- and dry-bulb temperatures in deg F.
 - e. Entering-air, wet- and dry-bulb temperatures in deg F.
 - f. Leaving-air, wet- and dry-bulb temperatures in deg F.
 - g. Water flow rate in gpm.
 - h. Water pressure differential in feet of head or psig.
 - i. Entering-water temperature in deg F.
 - j. Leaving-water temperature in deg F.
 - k. Inlet steam pressure in psig.
- G. Fan Test Reports: For supply and exhaust fans, include the following:
1. Fan Data:
 - a. System identification.
 - b. Location.
 - c. Make and type.
 - d. Model number and size.
 - e. Manufacturer's serial number.
 - f. Arrangement and class.
 - g. Sheave make, size in inches, and bore.
 - h. Center-to-center dimensions of sheave and amount of adjustments in inches.
 2. Motor Data:
 - a. Motor make, and frame type and size.
 - b. Horsepower and speed.
 - c. Volts, phase, and hertz.
 - d. Full-load amperage and service factor.
 - e. Sheave make, size in inches, and bore.
 - f. Center-to-center dimensions of sheave and amount of adjustments in inches.
 - g. Number, make, and size of belts.
 3. Test Data (Indicated and Actual Values):
 - a. Total airflow rate in cfm.

- b. Total system static pressure in inches wg.
 - c. Fan speed.
 - d. Discharge static pressure in inches wg.
 - e. Suction static pressure in inches wg.
- H. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:
 1. Report Data:
 - a. System fan and air-handling-unit number.
 - b. Location and zone.
 - c. Traverse air temperature in deg F.
 - d. Duct static pressure in inches wg.
 - e. Duct size in inches.
 - f. Duct area in sq. ft..
 - g. Indicated airflow rate in cfm.
 - h. Indicated velocity in fpm.
 - i. Actual airflow rate in cfm.
 - j. Actual average velocity in fpm.
 - k. Barometric pressure in psig.
- I. Air-Terminal-Device Reports:
 1. Unit Data:
 - a. System and air-handling unit identification.
 - b. Location and zone.
 - c. Apparatus used for test.
 - d. Area served.
 - e. Make.
 - f. Number from system diagram.
 - g. Type and model number.
 - h. Size.
 - i. Effective area in sq. ft..
 2. Test Data (Indicated and Actual Values):
 - a. Airflow rate in cfm.
 - b. Air velocity in fpm.
 - c. Preliminary airflow rate as needed in cfm.
 - d. Preliminary velocity as needed in fpm.
 - e. Final airflow rate in cfm.
 - f. Final velocity in fpm.
 - g. Space temperature in deg F.
- J. System-Coil Reports: For reheat coils and water coils of terminal units, include the following:
 1. Unit Data:
 - a. System and air-handling-unit identification.

- b. Location and zone.
 - c. Room or riser served.
 - d. Coil make and size.
 - e. Flowmeter type.
2. Test Data (Indicated and Actual Values):
- a. Airflow rate in cfm.
 - b. Entering-water temperature in deg F.
 - c. Leaving-water temperature in deg F.
 - d. Water pressure drop in feet of head or psig.
 - e. Entering-air temperature in deg F.
 - f. Leaving-air temperature in deg F.
- K. Pump Test Reports: Calculate impeller size by plotting the shutoff head on pump curves, and include the following:
1. Unit Data:
- a. Unit identification.
 - b. Location.
 - c. Service.
 - d. Make and size.
 - e. Model number and serial number.
 - f. Water flow rate in gpm.
 - g. Water pressure differential in feet of head or psig.
 - h. Required net positive suction head in feet of head or psig.
 - i. Pump speed.
 - j. Impeller diameter in inches.
 - k. Motor make and frame size.
 - l. Motor horsepower and rpm.
 - m. Voltage at each connection.
 - n. Amperage for each phase.
 - o. Full-load amperage and service factor.
 - p. Seal type.
2. Test Data (Indicated and Actual Values):
- a. Static head in feet of head or psig.
 - b. Pump shutoff pressure in feet of head or psig.
 - c. Actual impeller size in inches.
 - d. Full-open flow rate in gpm.
 - e. Full-open pressure in feet of head or psig.
 - f. Final discharge pressure in feet of head or psig.
 - g. Final suction pressure in feet of head or psig.
 - h. Final total pressure in feet of head or psig.
 - i. Final water flow rate in gpm.
 - j. Voltage at each connection.
 - k. Amperage for each phase.
- L. Instrument Calibration Reports:

1. Report Data:
 - a. Instrument type and make.
 - b. Serial number.
 - c. Application.
 - d. Dates of use.
 - e. Dates of calibration.

3.18 VERIFICATION OF TAB REPORT

- A. The TAB specialist's test and balance engineer shall conduct the inspection in the presence of Commissioning Authority.
- B. Commissioning Authority shall randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to the lesser of either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day.
- C. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
- D. If the number of "FAILED" measurements is greater than [10] [20] <Insert number> percent of the total measurements checked during the final inspection, the TAB shall be considered incomplete and shall be rejected.
- E. If recheck measurements find the number of failed measurements noncompliant with requirements indicated, proceed as follows:
 1. TAB specialists shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection. All changes shall be tracked to show changes made to previous report.
 2. If the second final inspection also fails, Owner may pursue others Contract options to complete TAB work.
- F. Prepare test and inspection reports.

3.19 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.

END OF SECTION

SECTION 230713 - DUCT INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes insulating the following duct services:

1. Indoor, concealed supply, return, and exhaust air.
2. Indoor, exposed supply, return, and exhaust air.
3. Outdoor, exposed supply and return.

- B. Related Sections:

1. Section 23 0716 "HVAC Equipment Insulation."
2. Section 23 0719 "HVAC Piping Insulation."

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied if any).

- B. Sustainable Design Submittals:

- C. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
2. Detail insulation application at elbows, fittings, dampers, specialties and flanges for each type of insulation.
3. Detail application of field-applied jackets.
4. Detail application at linkages of control devices.

- D. Samples: For each type of insulation and jacket indicated. Identify each Sample, describing product and intended use. Sample sizes are as follows:

1. Sheet Form Insulation Materials: 12 inches square.
2. Sheet Jacket Materials: 12 inches square.
3. Manufacturer's Color Charts: For products where color is specified, show the full range of colors available for each type of finish material.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.
- C. Field quality-control reports.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
 - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
 - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 23 0529 "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with duct Installer for duct insulation application. Before preparing ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- C. Coordinate installation and testing of heat tracing.

1.8 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.

- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

- A. Comply with requirements in "Duct Insulation Schedule, General," "Indoor Duct and Plenum Insulation Schedule," and "Aboveground, Outdoor Duct and Plenum Insulation Schedule" articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- F. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C534, Type II for sheet materials.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Aeroflex USA
 - b. Armacell LLC
 - c. K-Flex USA
- G. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C553, Type II and ASTM C1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CertainTeed Corporation; Saint-Gobain North America
 - b. Johns Manville; a Berkshire Hathaway company
 - c. Knauf Insulation
 - d. Manson Insulation Inc.
 - e. Owens Corning
- H. Mineral-Fiber Board Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C612, Type IA or Type IB. For duct and plenum applications, provide insulation with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CertainTeed Corporation; Saint-Gobain North America
 - b. Johns Manville; a Berkshire Hathaway company
 - c. Knauf Insulation
 - d. Manson Insulation Inc.
 - e. Owens Corning

- I. Mineral-Fiber, Pipe and Tank Insulation: Mineral or glass fibers bonded with a thermosetting resin. Semirigid board material with factory-applied FSK jacket complying with ASTM C1393, Type II or Type IIIA Category 2, or with properties similar to ASTM C612, Type IB. Nominal density is 2.5 lb/cu. ft. or more. Thermal conductivity (k-value) at 100 deg F is 0.29 Btu x in./h x sq. ft. x deg F or less. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CertainTeed Corporation; Saint-Gobain North America
 - b. Johns Manville; a Berkshire Hathaway company
 - c. Knauf Insulation
 - d. Manson Insulation Inc.
 - e. Owens Corning

2.2 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.
- B. Flexible Elastomeric and Polyolefin Adhesive: Comply with MIL-A-24179A, Type II, Class I.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Aeroflex USA
 - b. Armacell LLC
 - c. Foster Brand; H. B. Fuller Construction Products
 - d. K-Flex USA
- C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Brand; H. B. Fuller Construction Products
 - b. Eagle Bridges - Marathon Industries
 - c. Foster Brand; H. B. Fuller Construction Products
 - d. Mon-Eco Industries, Inc.

- D. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Brand; H. B. Fuller Construction Products
 - b. Eagle Bridges - Marathon Industries
 - c. Foster Brand; H. B. Fuller Construction Products
 - d. Mon-Eco Industries, Inc.
- E. PVC Jacket Adhesive: Compatible with PVC jacket.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Johns Manville; a Berkshire Hathaway company
 - b. P.I.C. Plastics, Inc.
 - c. Speedline Corporation
 - d. The Dow Chemical Company

2.3 MASTICS AND COATINGS

- A. Materials shall be compatible with insulation materials, jackets, and substrates.
- B. Vapor-Retarder Mastic: Water based; suitable for indoor use on below ambient services.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Brand; H. B. Fuller Construction Products
 - b. Foster Brand; H. B. Fuller Construction Products
 - c. Knauf Insulation
 - d. Vimasco Corporation
 2. Water-Vapor Permeance: Comply with ASTM C755, Section 7.2.2, Table 2, for insulation type and service conditions.
 3. Service Temperature Range: Minus 20 to plus 180 deg F.
 4. Comply with MIL-PRF-19565C, Type II, for permeance requirements.
 5. Color: White.
- C. Breather Mastic: Water based; suitable for indoor and outdoor use on above ambient services.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Brand; H. B. Fuller Construction Products
 - b. Eagle Bridges - Marathon Industries
 - c. Foster Brand; H. B. Fuller Construction Products
 - d. Knauf Insulation

- e. Mon-Eco Industries, Inc.
 - f. Vimasco Corporation
2. Water-Vapor Permeance: ASTM E96, greater than 1.0 perm at manufacturer's recommended dry film thickness.
 3. Service Temperature Range: Minus 20 to plus 180 deg F.
 4. Color: White.

2.4 LAGGING ADHESIVES

- A. Description: Comply with MIL-A-3316C, Class I, Grade A and shall be compatible with insulation materials, jackets, and substrates.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Brand; H. B. Fuller Construction Products
 - b. Foster Brand; H. B. Fuller Construction Products
 - c. Vimasco Corporation
 2. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over duct insulation.
 3. Service Temperature Range: 0 to plus 180 deg F.
 4. Color: White.

2.5 SEALANTS

- A. FSK and Metal Jacket Flashing Sealants:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Brand; H. B. Fuller Construction Products
 - b. Eagle Bridges - Marathon Industries
 - c. Foster Brand; H. B. Fuller Construction Products
 - d. Mon-Eco Industries, Inc.
 2. Materials shall be compatible with insulation materials, jackets, and substrates.
 3. Fire- and water-resistant, flexible, elastomeric sealant.
 4. Service Temperature Range: Minus 40 to plus 250 deg F.
 5. Color: Aluminum.
- B. ASJ Flashing Sealants, and Vinyl and PVC Jacket Flashing Sealants:
1. Materials shall be compatible with insulation materials, jackets, and substrates.
 2. Fire- and water-resistant, flexible, elastomeric sealant.
 3. Service Temperature Range: Minus 40 to plus 250 deg F.
 4. Color: White.

2.6 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
 - 1. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C1136, Type II.

2.7 FIELD-APPLIED FABRIC-REINFORCING MESH

- A. Woven Glass-Fiber Fabric: Approximately 6 oz./sq. yd. with a thread count of 5 strands by 5 strands/sq. in. for covering ducts.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. Childers Brand; H. B. Fuller Construction Products
- B. Woven Polyester Fabric: Approximately 1 oz./sq. yd. with a thread count of 10 strands by 10 strands/sq. in., in a Leno weave, for ducts.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Foster Brand; H. B. Fuller Construction Products
 - b. Vimasco Corporation

2.8 FIELD-APPLIED CLOTHS

- A. Woven Glass-Fiber Fabric: Comply with MIL-C-20079H, Type I, plain weave, and presized a minimum of 8 oz./sq. yd..
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. Alpha Associates, Inc.

2.9 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C921, Type I, unless otherwise indicated.
- B. FSK Jacket: Aluminum-foil-face, fiberglass-reinforced scrim with kraft-paper backing.
- C. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Johns Manville; a Berkshire Hathaway company

- b. P.I.C. Plastics, Inc.
 - c. Proto Corporation
 - d. Speedline Corporation
 2. Adhesive: As recommended by jacket material manufacturer.
 3. Color: Color-code jackets based on system.
- D. Metal Jacket:
 1. Aluminum Jacket: Comply with ASTM B209, Alloy 3003, 3005, 3105, or 5005, Temper H-14.
 - a. Sheet and roll stock ready for shop or field sizing.
 - b. Finish and thickness are indicated in field-applied jacket schedules.
 - c. Moisture Barrier for Indoor Applications: 3-mil- thick, heat-bonded polyethylene and kraft paper.
 - d. Moisture Barrier for Outdoor Applications: 3-mil- thick, heat-bonded polyethylene and kraft paper.

2.10 TAPES

- A. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C1136.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Avery Dennison Corporation, Specialty Tapes Division
 - b. Compac Corporation
 - c. Ideal Tape Co., Inc., an American Biltrite Company
 - d. Knauf Insulation
 - e. Venture Tape
 2. Width: 3 inches.
 3. Thickness: 6.5 mils.
 4. Adhesion: 90 ounces force/inch in width.
 5. Elongation: 2 percent.
 6. Tensile Strength: 40 lbf/inch in width.
 7. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.
- B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Compac Corporation
 - b. Ideal Tape Co., Inc., an American Biltrite Company
 - c. Venture Tape
 2. Width: 2 inches.

3. Thickness: 6 mils.
4. Adhesion: 64 ounces force/inch in width.
5. Elongation: 500 percent.
6. Tensile Strength: 18 lbf/inch in width.

2.11 SECUREMENTS

A. Bands:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ITW Insulation Systems; Illinois Tool Works, Inc.
 - b. RPR Products, Inc.
2. Stainless Steel: ASTM A167 or ASTM A240/A240M, Type 304 or Type 316; 0.015 inch thick, 1/2 inch wide with closed seal.
3. Aluminum: ASTM B209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 1/2 inch wide with closed seal.
4. Springs: Twin spring set constructed of stainless steel with ends flat and slotted to accept metal bands. Spring size determined by manufacturer for application.

B. Insulation Pins and Hangers:

1. Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch-diameter shank, length to suit depth of insulation indicated.
 - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) AGM Industries, Inc.
 - 2) Gemco
 - 3) Hardcast; a Carlisle Company
 - 4) Midwest Fasteners, Inc.
 - 5) Nelson Stud Welding
2. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
 - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) AGM Industries, Inc.
 - 2) CL WARD & Family Inc.
 - 3) Gemco
 - 4) Hardcast; a Carlisle Company
 - 5) Midwest Fasteners, Inc.
 - 6) Nelson Stud Welding

3. Metal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
 - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) AGM Industries, Inc.
 - 2) Gemco
 - 3) Midwest Fasteners, Inc.
 - b. Baseplate: Perforated, galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
 - c. Spindle: Stainless steel, fully annealed, 0.106-inch- diameter shank, length to suit depth of insulation indicated.
 - d. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
4. Nonmetal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate fastened to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
 - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) Gemco
 - 2) Midwest Fasteners, Inc.
 - b. Baseplate: Perforated, nylon sheet, 0.030 inch thick by 1-1/2 inches in diameter.
 - c. Spindle: Nylon, 0.106-inch- diameter shank, length to suit depth of insulation indicated, up to 2-1/2 inches.
 - d. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
5. Self-Sticking-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
 - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) AGM Industries, Inc.
 - 2) Gemco
 - 3) Hardcast; a Carlisle Company
 - 4) Midwest Fasteners, Inc.
 - b. Baseplate: Galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.

- c. Spindle: [Copper- or zinc-coated, low-carbon steel] [Aluminum] [Stainless steel], fully annealed, 0.106-inch- diameter shank, length to suit depth of insulation indicated.
 - d. Adhesive-backed base with a peel-off protective cover.
6. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch- thick, stainless-steel sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) AGM Industries, Inc.
 - 2) Gemco
 - 3) Hardcast; a Carlisle Company
 - 4) Midwest Fasteners, Inc.
 - 5) Nelson Stud Welding
 - b. Protect ends with capped self-locking washers incorporating a spring steel insert to ensure permanent retention of cap in exposed locations.
7. Nonmetal Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick nylon sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) Gemco
 - 2) Midwest Fasteners, Inc.
- C. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.

2.12 CORNER ANGLES

- A. PVC Corner Angles: 30 mils thick, minimum 1 by 1 inch, PVC according to ASTM D1784, Class 16354-C. White or color-coded to match adjacent surface.
- B. Aluminum Corner Angles: 0.040 inch thick, minimum 1 by 1 inch, aluminum according to ASTM B209, Alloy 3003, 3005, 3105, or 5005; Temper H-14.
- C. Stainless-Steel Corner Angles: 0.024 inch thick, minimum 1 by 1 inch, stainless steel according to ASTM A167 or ASTM A240/A240M, Type 304 or Type 316.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
 - 1. Verify that systems to be insulated have been tested and are free of defects.
 - 2. Verify that surfaces to be insulated are clean and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.
- B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Keep insulation materials dry during application and finishing.
- G. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- H. Install insulation with least number of joints practical.
- I. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
 - 1. Install insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.

3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
- J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- K. Install insulation with factory-applied jackets as follows:
 1. Draw jacket tight and smooth.
 2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.
 - a. For below ambient services, apply vapor-barrier mastic over staples.
 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct flanges and fittings.
- L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
 1. Seal penetrations with flashing sealant.
 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.

1. Seal penetrations with flashing sealant.
 2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
 3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
 4. Seal jacket to wall flashing with flashing sealant.
- C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.
1. Comply with requirements in Section 07 8413 "Penetration Firestopping."
- E. Insulation Installation at Floor Penetrations:
1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
 2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 07 8413 "Penetration Firestopping."

3.5 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

- A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.6 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.

- c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
 - d. Do not overcompress insulation during installation.
 - e. Impale insulation over pins and attach speed washers.
 - f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
 - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
 - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
 5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
 6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
 7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.
- B. Board Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - b. On duct sides with dimensions larger than 18 inches, space pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
 - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
 - d. Do not overcompress insulation during installation.

- e. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
 - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
 - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
 5. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
 6. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

3.7 FIELD-APPLIED JACKET INSTALLATION

- A. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints; for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturer's recommended adhesive.
 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.
- B. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

3.8 FINISHES

- A. Do not field paint aluminum or stainless-steel jackets.

3.9 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

- B. Perform tests and inspections.
- C. Tests and Inspections:
 - 1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location for each duct system defined in the "Duct Insulation Schedule, General" Article.
- D. All insulation applications will be considered defective Work if sample inspection reveals non-compliance with requirements.

3.10 DUCT INSULATION SCHEDULE, GENERAL

- A. Plenums and Ducts Requiring Insulation:
 - 1. Indoor, concealed supply, return and exhaust air.
 - 2. Indoor, exposed supply, return and exhaust air.
 - 3. Outdoor, exposed supply and return.
- B. Items Not Insulated:
 - 1. Factory-insulated flexible ducts.
 - 2. Factory-insulated plenums and casings.
 - 3. Flexible connectors.
 - 4. Vibration-control devices.
 - 5. Factory-insulated access panels and doors.

3.11 INDOOR DUCT AND PLENUM INSULATION SCHEDULE

- A. Concealed, round and flat-oval, supply, return and exhaust-air duct insulation shall be the following:
 - 1. Mineral-Fiber Blanket: 2 inches thick and 1.5-lb/cu. ft. nominal density.
- B. Concealed, rectangular, supply, return and exhaust-air duct insulation shall be the following:
 - 1. Mineral-Fiber Blanket: 2 inches thick and 1.5-lb/cu. ft. nominal density.
- C. Exposed, round and flat-oval, supply and return-air duct insulation shall be the following:
 - 1. Mineral-Fiber Board: 2 inches thick and 3-lb/cu. ft. nominal density.
- D. Exposed, rectangular, supply and return-air duct insulation shall be the following:
 - 1. Mineral-Fiber Board: 2 inches thick and 3-lb/cu. ft. nominal density.

3.12 ABOVEGROUND, OUTDOOR DUCT AND PLENUM INSULATION SCHEDULE

- A. Insulation materials and thicknesses are identified below. If more than one material is listed for a duct system, selection from materials listed is Contractor's option.
- B. Exposed, rectangular, supply and return-air duct insulation shall be one of the following:
 - 1. Mineral-Fiber Blanket: 3 inches and 3-lb/cu. ft. nominal density.
 - 2. Mineral-Fiber Board: 3 inches thick and 3-lb/cu. ft. nominal density.

3.13 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Ducts and Plenums, Concealed:
 - 1. None.
- D. Ducts and Plenums, Exposed:
 - 1. None.

3.14 OUTDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Ducts and Plenums, Concealed:
 - 1. Aluminum, Smooth: 0.032 inch thick.
- D. Ducts and Plenums, Exposed, up to 48 Inches in Diameter or with Flat Surfaces up to 72 Inches:
 - 1. Aluminum, Smooth: 0.032 inch thick.

END OF SECTION

SECTION 230923 - DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes: Direct digital control (DDC) system for HVAC.

1.2 DEFINITIONS

- A. Algorithm: A logical procedure for solving a recurrent mathematical problem. A prescribed set of well-defined rules or processes for solving a problem in a finite number of steps.
- B. Analog: A continuously varying signal value, such as current, flow, pressure, or temperature.
- C. BACnet Specific Definitions:
 - 1. BACnet: Building Automation Control Network Protocol, ASHRAE 135. A communications protocol allowing devices to communicate data and services over a network.
 - 2. BACnet Interoperability Building Blocks (BIBBs): BIBB defines a small portion of BACnet functionality that is needed to perform a particular task. BIBBs are combined to build the BACnet functional requirements for a device.
 - 3. BACnet/IP: Defines and allows using a reserved UDP socket to transmit BACnet messages over IP networks. A BACnet/IP network is a collection of one or more IP subnetworks that share the same BACnet network number.
 - 4. BACnet Testing Laboratories (BTL): Organization responsible for testing products for compliance with ASHRAE 135, operated under direction of BACnet International.
- D. Binary: Two-state signal where a high signal level represents "ON" or "OPEN" condition and a low signal level represents "OFF" or "CLOSED" condition. "Digital" is sometimes used interchangeably with "Binary" to indicate a two-state signal.
- E. Controller: Generic term for any standalone, microprocessor-based, digital controller residing on a network, used for local or global control. Three types of controllers are indicated: network controllers, programmable application controllers, and application-specific controllers.
- F. Control System Integrator: An entity that assists in expansion of existing enterprise system and support of additional operator interfaces to I/O being added to existing enterprise system.
- G. COV: Changes of value.
- H. DDC System Provider: Authorized representative of, and trained by, DDC system manufacturer and responsible for execution of DDC system Work indicated.

- I. Distributed Control: Processing of system data is decentralized and control decisions are made at subsystem level. System operational programs and information are provided to remote subsystems and status is reported back. On loss of communication, subsystems to be capable of operating in a standalone mode using the last best available data.
- J. Gateway: Bidirectional protocol translator that connects control systems that use different communication protocols.
- K. HLC: Heavy load conditions.
- L. I/O: System through which information is received and transmitted. I/O refers to analog input (AI), binary input (BI), analog output (AO) and binary output (BO). Analog signals are continuous and represent control influences such as flow, level, moisture, pressure, and temperature. Binary signals convert electronic signals to digital pulses (values) and generally represent two-position operating and alarm status. "Digital," (DI) and (DO), is sometimes used interchangeably with "Binary," (BI) and (BO), respectively.
- M. LAN: Local area network.
- N. LNS: LonWorks Network Services.
- O. LON Specific Definitions:
 - 1.FTT-10: Echelon Transmitter-Free Topology Transceiver.
 - 2.LonMark International: Association comprising suppliers and installers of LonTalk products. Association provides guidelines for implementing LonTalk protocol to ensure interoperability through a standard or consistent implementation.
 - 3.LonTalk: An open standard protocol developed by Echelon Corporation that uses a "Neuron Chip" for communication. LonTalk is a register trademark of Echelon.
 - 4.LonWorks: Network technology developed by Echelon.
 - 5.Node: Device that communicates using CTA-709.1-D protocol and that is connected to a CTA-709.1-D network.
 - 6.Node Address: The logical address of a node on the network, consisting of a Domain number, Subnet number, and Node number. "Node number" portion of an address is a number assigned to device during installation, is unique within a subnet, and is not a factory-set unique Node ID.
 - 7.Node ID: A unique 48-bit identifier assigned at factory to each CTA-709.1-D device. Sometimes called a "Neuron ID."
 - 8.Program ID: An identifier (number) stored in a device (usually, EEPROM) that identifies node manufacturer, functionality of device (application and sequence), transceiver used, and intended device usage.
 - 9.Standard Configuration Property Type (SCPT): Pronounced "skip-it." A standard format type maintained by LonMark for configuration properties.
 - 10. Standard Network Variable Type (SNVT): Pronounced "snivet." A standard format type maintained by LonMark used to define data information transmitted and received by individual nodes. "SNVT" is used in two ways. It is an acronym for "Standard Network Variable Type" and is often used to indicate a network variable itself (i.e., it can mean "a network variable of a standard network variable type").
 - 11. Subnet: Consists of a logical grouping of up to 127 nodes, where logical grouping is defined by node addressing. Each subnet is assigned a number, which is unique within a Domain. See "Node Address."

12. TP/FT-10: Free Topology Twisted Pair network defined by CTA-709.3 and is most common media type for a CTA-709.1-D control network.
 13. TP/XF-1250: High-speed, 1.25 Mbps, twisted-pair, doubly terminated bus network defined by "LonMark Interoperability Guidelines" and typically used only to connect multiple TP/FT-10 networks.
 14. User-Defined Configuration Property Type (UCPT): Pronounced "u-keep-it." A Configuration Property format type that is defined by device manufacturer.
 15. User-Defined Network Variable Type (UNVT): Network variable format defined by device manufacturer. UNVTs create non-standard communications that other vendors' devices may not correctly interpret and may negatively impact system operation. UNVTs are not allowed.
- P. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control, signaling power-limited circuits.
- Q. Mobile Device: A data-enabled phone or tablet computer capable of connecting to a cellular data network and running a native control application or accessing a web interface.
- R. Modbus TCP/IP: An open protocol for exchange of process data.
- S. MS/TP: Master-slave/token-passing, ISO/IEC/IEEE 8802-3. Datalink protocol LAN option that uses twisted-pair wire for low-speed communication.
- T. MTBF: Mean time between failures.
- U. Network Controller: Digital controller, which supports a family of programmable application controllers and application-specific controllers, that communicates on peer-to-peer network for transmission of global data.
- V. Network Repeater: Device that receives data packet from one network and rebroadcasts it to another network. No routing information is added to protocol.
- W. Peer to Peer: Networking architecture that treats all network stations as equal partners.
- X. POT: Portable operator's terminal.
- Y. RAM: Random access memory.
- Z. RF: Radio frequency.
- AA. Router: Device connecting two or more networks at network layer.
- BB. Server: Computer used to maintain system configuration, historical and programming database.
- CC. TCP/IP: Transport control protocol/Internet protocol.
- DD. UPS: Uninterruptible power supply.
- EE. USB: Universal Serial Bus.

FF. User Datagram Protocol (UDP): This protocol assumes that the IP is used as the underlying protocol.

GG. VAV: Variable air volume.

HH. WLED: White light emitting diode.

1.3 ACTION SUBMITTALS

A. Multiple Submissions:

1. If multiple submissions are required to execute work within schedule, first submit a coordinated schedule clearly defining intent of multiple submissions. Include a proposed date of each submission with a detailed description of submittal content to be included in each submission.
2. Clearly identify each submittal requirement indicated and in which submission the information will be provided.
3. Include an updated schedule in each subsequent submission with changes highlighted to easily track the changes made to previous submitted schedule.

B. Product Data:

1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, control signal over range, default control signal with loss of power, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.
3. Product description with complete technical data, performance curves, and product specification sheets.
4. Installation, operation, and maintenance instructions including factors effecting performance.
5. Bill of materials of indicating quantity, manufacturer, and extended model number for each unique product.
 - a. Servers.
 - b. Gateways.
 - c. Routers.
 - d. Protocol analyzers.
 - e. DDC controllers.
 - f. Enclosures.
 - g. Electrical power devices.
 - h. UPS units.
 - i. Accessories.
 - j. Instruments.
 - k. Control dampers and actuators.
 - l. Control valves and actuators.

6. When manufacturer's product datasheets apply to a product series rather than a specific product model, clearly indicate and highlight only applicable information.

7. Each submitted piece of product literature to clearly cross reference specification and drawings that submittal is to cover.

C. Software Submittal:

1. Cross-referenced listing of software to be loaded on each operator workstation, server, gateway, and DDC controller.
2. Description and technical data of all software provided and cross-referenced to products in which software will be installed.
3. Operating system software, operator interface and programming software, color graphic software, DDC controller software, maintenance management software, and third-party software.
4. Include a flow diagram and an outline of each subroutine that indicates each program variable name and units of measure.
5. Listing and description of each engineering equation used with reference source.
6. Listing and description of each constant used in engineering equations and a reference source to prove origin of each constant.
7. Description of operator interface to alphanumeric and graphic programming.
8. Description of each network communication protocol.
9. Description of system database, including all data included in database, database capacity, and limitations to expand database.
10. Description of each application program and device drivers to be generated, including specific information on data acquisition and control strategies showing their relationship to system timing, speed, processing burden, and system throughout.
11. Controlled Systems: Instrumentation list with element name, type of device, manufacturer, model number, and product data. Include written description of sequence of operation including schematic diagram.

D. Shop Drawings:

1. General Requirements:

- a. Include cover drawing with Project name, location, Owner, Architect, Contractor, and issue date with each Shop Drawings submission.
 - b. Include a drawing index sheet listing each drawing number and title that matches information in each title block.
2. Include plans, elevations, sections, and mounting details where applicable.
 3. Include details of product assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 4. Detail means of vibration isolation and show attachments to rotating equipment.
 5. Plan Drawings indicating the following:
 - a. Screened backgrounds of walls, structural grid lines, HVAC equipment, ductwork, and piping.
 - b. Room names and numbers with coordinated placement to avoid interference with control products indicated.
 - c. Exact placement of products in rooms, ducts, and piping to reflect proposed installed condition.
 - d. Network communication cable and raceway routing.
 - e. Information, drawn to scale, of <Insert requirements>.

- f. Proposed routing of wiring, cabling, conduit, and tubing; coordinated with building services for review before installation.

6. Schematic drawings for each controlled HVAC system indicating the following:

- a. I/O points labeled with point names shown. Indicate instrument range, normal operating set points, and alarm set points. Indicate fail position of each damper and valve, if included in Project.
- b. I/O listed in table format showing point name, type of device, manufacturer, model number, and cross-reference to product data sheet number.
- c. A graphic showing location of control I/O in proper relationship to HVAC system.
- d. Wiring diagram with each I/O point having a unique identification and indicating labels for all wiring terminals.
- e. Unique identification of each I/O that to be consistently used between different drawings showing same point.
- f. Elementary wiring diagrams of controls for HVAC equipment motor circuits including interlocks, switches, relays, and interface to DDC controllers.
- g. Narrative sequence of operation.
- h. Graphic sequence of operation, showing all inputs and output logical blocks.

7. Control panel drawings indicating the following:

- a. Panel dimensions, materials, size, and location of field cable, raceways, and tubing connections.
- b. Interior subpanel layout, drawn to scale and showing all internal components, cabling and wiring raceways, nameplates, and allocated spare space.
- c. Front, rear, and side elevations and nameplate legend.
- d. Unique drawing for each panel.

8. DDC system network riser diagram indicating the following:

- a. Each device connected to network with unique identification for each.
- b. Interconnection of each different network in DDC system.
- c. For each network, indicate communication protocol, speed, and physical means of interconnecting network devices, such as copper cable type, or optical fiber cable type. Indicate raceway type and size for each.
- d. Each network port for connection of an operator workstation or other type of operator interface with unique identification for each.

9. DDC system electrical power riser diagram indicating the following:

- a. Each point of connection to field power with requirements (volts/phase/hertz/amperes/connection type) listed for each.
- b. Each control power supply including, as applicable, transformers, power-line conditioners, transient voltage suppression and high filter noise units, DC power supplies, and UPS units with unique identification for each.
- c. Each product requiring power with requirements (volts/phase/hertz/amperes/connection type) listed for each.
- d. Power wiring type and size, race type, and size for each.

10. Monitoring and control signal diagrams indicating the following:

- a. Control signal cable and wiring between controllers and I/O.
 - b. Point-to-point schematic wiring diagrams for each product.
 - c. Control signal tubing to sensors, switches, and transmitters.
 - d. Process signal tubing to sensors, switches, and transmitters.
11. Color graphics indicating the following:
- a. Itemized list of color graphic displays to be provided.
 - b. For each display screen to be provided, a true color copy showing layout of pictures, graphics, and data displayed.
 - c. Intended operator access between related hierarchical display screens.
- E. System Description:
1. Full description of DDC system architecture, network configuration, operator interfaces and peripherals, servers, controller types and applications, gateways, routers and other network devices, and power supplies.
 2. Complete listing and description of each report, log and trend for format and timing, and events that initiate generation.
 3. System and product operation under each potential failure condition including, but not limited to, the following:
 - a. Loss of power.
 - b. Loss of network communication signal.
 - c. Loss of controller signals to inputs and outpoints.
 - d. Operator workstation failure.
 - e. Server failure.
 - f. Gateway failure.
 - g. Network failure.
 - h. Controller failure.
 - i. Instrument failure.
 - j. Control damper and valve actuator failure.
 4. Complete bibliography of documentation and media to be delivered to Owner.
 5. Description of testing plans and procedures.
 6. Description of Owner training.
- F. Delegated Design Submittals: For DDC system products and installation indicated as being delegated.
1. Supporting documentation showing DDC system design complies with performance requirements indicated, including calculations and other documentation necessary to prove compliance.
 2. Schedule and design calculations for control dampers and actuators.
 - a. Flow at Project design and minimum flow conditions.
 - b. Face velocity at Project design and minimum airflow conditions.
 - c. Pressure drop across damper at Project design and minimum airflow conditions.
 - d. AMCA 500-D damper installation arrangement used to calculate and schedule pressure drop, as applicable to installation.
 - e. Maximum close-off pressure.

- f. Leakage airflow at maximum system pressure differential (fan close-off pressure).
- g. Torque required at worst case condition for sizing actuator.
- h. Actuator selection indicating torque provided.
- i. Actuator signal to control damper (on, close, or modulate).
- j. Actuator position on loss of power.
- k. Actuator position on loss of control signal.

3. Schedule and design calculations for control valves and actuators.

- a. Flow at Project design and minimum flow conditions.
- b. Pressure-differential drop across valve at Project design flow condition.
- c. Maximum system pressure-differential drop (pump close-off pressure) across valve at Project minimum flow condition.
- d. Design and minimum control valve coefficient with corresponding valve position.
- e. Maximum close-off pressure.
- f. Leakage flow at maximum system pressure differential.
- g. Torque required at worst case condition for sizing actuator.
- h. Actuator selection indicating torque provided.
- i. Actuator signal to control damper (on, close or modulate).
- j. Actuator position on loss of power.
- k. Actuator position on loss of control signal.

4. Schedule and design calculations for selecting flow instruments.

- a. Instrument flow range.
- b. Project design and minimum flow conditions with corresponding accuracy, control signal to transmitter, and output signal for remote control.
- c. Extreme points of extended flow range with corresponding accuracy, control signal to transmitter, and output signal for remote control.
- d. Pressure-differential loss across instrument at Project design flow conditions.
- e. Where flow sensors are mated with pressure transmitters, provide information for each instrument separately and as an operating pair.

G. Sustainable Design Submittals:

1.4 INFORMATIONAL SUBMITTALS

A. Coordination Drawings:

- 1. Plan drawings, reflected ceiling plans, or Building Information Model (BIM), and corresponding product installation details, drawn to scale, showing the items described in this Section and coordinated with all building trades.

B. Qualification Statements:

1. Systems Provider's Qualification Data:

- a. Resume of project manager assigned to Project.
- b. Resumes of application engineering staff assigned to Project.
- c. Resumes of installation and programming technicians assigned to Project.

- d. Resumes of service technicians assigned to Project.
- e. Brief description of past project including physical address, floor area, number of floors, building system cooling and heating capacity, and building's primary function.
- f. Description of past project DDC system, noting similarities to Project scope and complexity indicated.
- g. Names of staff assigned to past project that will also be assigned to execute work of this Project.
- h. Owner contact information for past project including name, phone number, and email address.
- i. Contractor contact information for past project including name, phone number, and email address.
- j. Architect and Engineer contact information for past project including name, phone number, and email address.

2. Manufacturer's qualification data.

3. Testing agency's qualification data.

C. Welding certificates.

D. Product Certificates:

1. Data Communications Protocol Certificates:

- a. Certifying that each proposed DDC system component complies with ASHRAE 135.

E. Test and Evaluation Reports:

1. Product Test Reports: For DDC system equipment and components, for tests performed by manufacturer and witnessed by a qualified testing agency.
2. Preconstruction Test Reports: For each separate test performed.

F. Source Quality-Control Reports: For DDC system equipment and components.

G. Field Quality-Control Reports: For DDC system equipment and components.

H. Sample warranty.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For DDC system.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
 - a. Project Record Drawings of as-built versions of submittal Shop Drawings provided in electronic PDF format.
 - b. Testing and commissioning reports and checklists of completed final versions of reports, checklists, and trend logs.
 - c. As-built versions of submittal Product Data.

- d. Names, addresses, email addresses, and 24-hour telephone numbers of Installer and service representatives for DDC system and products.
- e. Operator's manual with procedures for operating control systems including logging on and off, handling alarms, producing point reports, trending data, overriding computer control, and changing set points and variables.
- f. Programming manuals with description of programming language and syntax, of statements for algorithms and calculations used, of point database creation and modification, of program creation and modification, and of editor use.
- g. Engineering, installation, and maintenance manuals that explain how to do the following:
 - 1) Design and install new points, panels, and other hardware.
 - 2) Perform preventive maintenance and calibration.
 - 3) Debug hardware problems.
 - 4) Repair or replace hardware.
- h. Documentation of all programs created using custom programming language including set points, tuning parameters, and object database.
- i. Backup copy of graphic files, programs, and databases on electronic media.
- j. List of recommended spare parts with part numbers and suppliers.
- k. Complete original-issue documentation, installation, and maintenance information for furnished third-party hardware including computer equipment and sensors.
- l. Complete original-issue copies of furnished software, including operating systems, custom programming language, operator workstation software, and graphics software.
- m. Licenses, guarantees, and warranty documents.
- n. Recommended preventive maintenance procedures for system components, including schedule of tasks such as inspection, cleaning, and calibration; time between tasks; and task descriptions.
- o. Owner training materials.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Extra Stock Material: Furnish extra materials and parts to Owner that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
- B. Include product manufacturers' recommended parts lists for proper product operation over four-year period following warranty period. Parts list to be indicated for each year.
- C. Furnish parts, as indicated by manufacturer's recommended parts list, for product operation during one-year period following warranty period.
- D. Furnish quantity indicated of matching product(s) in Project inventory for each unique size and type of following:
 1. Network Controller: One.
 2. Programmable Application Controller: One.
 3. Application-Specific Controller: One.
 4. General-Purpose Relay: One.

5. Multifunction Time-Delay Relay: One.
6. Latching Relay: One.
7. Current-Sensing Relay: One.
8. Combination On-Off Status Sensor and On-Off Relay: One.
9. Transformer: One.
10. DC Power Supply: One.

1.7 QUALITY ASSURANCE

A. DDC System Manufacturer Qualifications:

1. Nationally recognized manufacturer of DDC systems and products.
2. DDC systems with similar requirements to those indicated for a continuous period of five years within time of bid.
3. DDC systems and products that have been successfully tested and in use on at least five past projects.
4. Having complete published catalog literature, installation, operation, and maintenance manuals for all products intended for use.
5. Having full-time in-house employees for the following:
 - a. Product research and development.
 - b. Product and application engineering.
 - c. Product manufacturing, testing, and quality control.
 - d. Technical support for DDC system installation training, commissioning, and troubleshooting of installations.
 - e. Owner operator training.

B. DDC System Provider Qualifications:

1. Authorized representative of, and trained by, DDC system manufacturer.
2. Demonstrate past experience with installation of DDC system products being installed for period within five consecutive years before time of bid.
3. Demonstrate past experience on five projects of similar complexity, scope, and value.
4. Demonstrate past experience of each person assigned to Project.
5. Staffing resources of competent and experienced full-time employees that are assigned to execute work according to schedule.
6. Service and maintenance staff assigned to support Project during warranty period.
7. Product parts inventory to support ongoing DDC system operation for a period of not less than five years after Final Acceptance.
8. DDC system manufacturer's backing to take over execution of the Work if necessary to comply with requirements indicated. Include Project-specific written letter, signed by manufacturer's corporate officer, if requested.

C. Testing Agency Qualifications: Member company of NETA.

1. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.

D. Welding Qualifications: Qualify procedures and personnel in accordance with the following welding codes:

- 1.AWS D1.1/D1.1M.
- 2.AWS D1.2/D1.2M.
- 3.AWS D1.3/D1.3M.
- 4.AWS D1.4/D1.4M.

1.8 MOCKUPS

- A. Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, to set quality standards for materials and execution, and to set quality standards for fabrication and installation.
- 1.Build mockups of completed installation where products are exposed to view and are located in areas with aesthetic requirements that warrant special attention, including the following spaces:
 - 2.Build mockups of completed installation for areas as indicated on Drawings.
 - 3.Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Owner specifically approves such deviations by Change Order.
 - 4.Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Final Acceptance.

1.9 PRECONSTRUCTION TESTING

- A. Preconstruction Testing Service: Engage a qualified testing agency to perform preconstruction testing on field mockups.
- 1.Provide test assemblies representative of proposed materials and construction.
 - 2.Build laboratory mockups at testing agency facility; use personnel, materials, and methods of construction that will be used at Project site.
 - 3.Notify Architect seven days in advance of dates and times when laboratory mockups will be tested.
- B. Preconstruction Testing: Performed by a qualified testing agency on manufacturer's standard assemblies.

1.10 WARRANTY

- A. Special Warranty: Manufacturer and Installer agree to repair or replace products that fail in materials or workmanship within specified warranty period.
- 1.Adjust, repair, or replace failures at no additional cost or reduction in service to Owner.
 - 2.Include updates or upgrades to software and firmware if necessary to resolve deficiencies.
 - a. Install updates only after receiving Owner's written authorization.
 - 3.Perform warranty service during normal business hours and commence within 16 hours of Owner's warranty service request.

4. Warranty Period: Two year(s) from date of Final Acceptance.

- a. For Gateway: Two-year parts and labor warranty for each.

PART 2 - PRODUCTS

2.1 DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Distech Controls.
2. Johnson Controls, Inc. (Preferred)
3. Schneider Electric USA, Inc. (Preferred)

2.2 DDC SYSTEM DESCRIPTION

- A. Microprocessor-based monitoring and control including analog/digital conversion and program logic. A control loop or subsystem in which digital and analog information is received and processed by a microprocessor, and digital control signals are generated based on control algorithms and transmitted to field devices to achieve a set of predefined conditions.

1. DDC system consisting of high-speed, peer-to-peer network of distributed DDC controllers, other network devices, operator interfaces, and software.

- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.3 WEB ACCESS

- A. DDC system to be web based or web compatible.

1. Web-Based Access to DDC System:

- a. DDC system software based on server thin-client architecture, designed around open standards of web technology. DDC system server accessed using a web browser over DDC system network, using Owner's LAN, and remotely over Internet.
- b. Intent of thin-client architecture is to provide operators complete access to DDC system via a web browser. No special software other than a web browser is required to access graphics, point displays, and trends; to configure trends, points, and controllers; and to edit programming.
- c. Password-protected web access.

2. Web-Compatible Access to DDC System:

- a. Workstation and or server to perform overall system supervision and configuration, graphical user interface, management report generation, and alarm annunciation.

- b. DDC system to support web browser access to building data. Operator using a standard web browser is able to access control graphics and change adjustable set points.
- c. Password-protected web access.

2.4 PERFORMANCE REQUIREMENTS

- A. Delivery of Selected Control Devices: Deliver to equipment and systems manufacturers for factory installation and to HVAC systems installers for field installation.
- B. Delegated Design, Qualified Professional Engineer: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design DDC system to satisfy requirements indicated.
- C. Delegated Design, Qualified Professional: Engage a qualified professional to design DDC system to satisfy requirements indicated.

1. System Performance Objectives:

- a. DDC system manages HVAC systems.
- b. DDC system operates HVAC systems to achieve optimum operating costs while using least possible energy and maintaining specified performance.
- c. DDC system responds to power failures, HVAC equipment failures, and adverse and emergency conditions encountered through connected I/O points.
- d. DDC system operates while unattended by an operator and through operator interaction.
- e. DDC system records trends and transactions of events and produces report information such as performance, energy, occupancies, and equipment operation.

- D. Surface-Burning Characteristics: Products installed in ducts, equipment, and return-air paths complying with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

- 1. Flame-Spread Index: 25 or less.
- 2. Smoke-Developed Index: 50 or less.

- E. DDC System Speed:

1. Response Time of Connected I/O:

- a. Update AI point values connected to DDC system at least every two seconds for use by DDC controllers. Points used globally to also comply with this requirement.
- b. Update BI point values connected to DDC system at least every two seconds for use by DDC controllers. Points used globally to also comply with this requirement.
- c. AO points connected to DDC system to begin to respond to controller output commands within two second(s). Global commands to also comply with this requirement.
- d. BO point values connected to DDC system to respond to controller output commands within two second(s). Global commands to also comply with this requirement.

2. Display of Connected I/O:

- a. Update and display analog point COV connected to DDC system at least every five seconds for use by operator.
 - b. Update and display binary point COV connected to DDC system at least every five seconds for use by operator.
 - c. Update and display alarms of analog and digital points connected to DDC system within 30 seconds of activation or change of state.
 - d. Update graphic display refresh within eight seconds.
 - e. Point change of values and alarms displayed from workstation to workstation when multiple operators are viewing from multiple workstations to not exceed graphic refresh rate indicated.
- F. Network Bandwidth: Design each network of DDC system to include spare bandwidth with DDC system operating under normal and heavy load conditions indicated. Calculate bandwidth usage, and apply a safety factor to ensure that requirement is satisfied when subjected to testing under worst case conditions. Minimum spare bandwidth as follows:
- 1.Level 1 Networks: 20.
 - 2.Level 2 Networks: 20.
 - 3.Level 3 Networks: 20.
- G. DDC System Data Storage:
- 1.Include capability to archive not less than 36 consecutive months of historical data for all I/O points connected to system, including alarms, event histories, transaction logs, trends, and other information indicated.
 - 2.Local Storage:
 - a. Provide server with data storage indicated. Server(s) to use IT industry standard database platforms and be capable of functions described in "DDC Data Access" Paragraph.
 - 3.Cloud Storage:
 - a. Provide web browser interfaces to configure, upload, download, and manage data and to service plan with storage adequate to store all data for term indicated. Cloud storage uses IT industry standard database platforms and is capable of functions described in "DDC Data Access" Paragraph.
- H. DDC Data Access:
- 1.When logged into the system, operator able to also interact with any DDC controllers connected to DDC system as required for functional operation of DDC system.
 - 2.Use for application configuration; for archiving, reporting, and trending of data; for operator transaction archiving and reporting; for network information management; for alarm annunciation; and for operator interface tasks and controls application management.
- I. Future Expandability:
- 1.DDC system size is expandable to an ultimate capacity of at least 1.5 times total I/O points indicated.

- 2.Design and install system networks to achieve ultimate capacity with only addition of DDC controllers, I/O, and associated wiring and cable. Design and install initial network infrastructure to support ultimate capacity without having to remove and replace portions of network installation.
 - 3.Operator interfaces installed initially do not require hardware and software additions and revisions for system when operating at ultimate capacity.
- J. Input Point Values Displayed Accuracy: Meet following end-to-end overall system accuracy, including errors associated with meter, sensor, transmitter, lead wire or cable, and analog to digital conversion.
- 1.Energy:
 - a. Thermal: Within 3 percent of reading.
 - b. Electric Power: Within 1percent of reading.
 - c. Requirements indicated on Drawings for meters not supplied by utility.
 - 2.Flow:
 - a. Air: Within 2 percent of design flow rate.
 - b. Air (Terminal Units): Within 10 percent of design flow rate.
 - 3.Gas:
 - a. Carbon Dioxide: Within 50 ppm.
 - b. Carbon Monoxide: Within 5 percent of reading.
 - c. Oxygen: Within 5 percent of reading.
 - d. Refrigerant: Within 5 percent of reading.
 - e. VOCs: Within 5 percent of reading.
 - 4.Moisture (Relative Humidity):
 - a. Air: Within 2 percent RH.
 - b. Space: Within 2 percent RH.
 - c. Outdoor: Within 2 percent RH.
 - 5.Level: Within 5 percent of reading.
 - 6.Pressure:
 - a. Air, Ducts and Equipment: 0.5 percent of instrument range.
 - 7.Speed: Within 5 percent of reading.
 - 8.Temperature, Dew Point:
 - a. Air: Within 0.5 deg F.
 - b. Space: Within 0.5 deg F.
 - c. Outdoor: Within 2 deg F.
 - 9.Temperature, Dry Bulb:
 - a. Air: Within 0.5 deg F.

- b. Space: Within 0.5 deg F.
 - c. Outdoor: Within 1 deg F.
 - d. Temperature Difference: Within 0.25 deg F.
 - e. Other Temperatures Not Indicated: Within 0.5 deg F.
10. Temperature, Wet Bulb:
- a. Air: Within 0.5 deg F.
 - b. Space: Within 0.5 deg F.
 - c. Outdoor: Within 1 deg F.
11. Vibration: Within 5 percent of reading.
- K. Precision of I/O Reported Values: Values reported in database and displayed to have following precision:
1. Current:
- a. Milliamperes: Nearest 1/100th of a milliampere.
 - b. Amperes: Nearest 1/10th of an ampere up to 100 A; nearest ampere for 100 A and more.
2. Energy:
- a. Electric Power:
 - 1) Rate (Watts): Nearest 1/10th of a watt through 1000 W.
 - 2) Rate (Kilowatts): Nearest 1/10th of a kilowatt through 1000 kW; nearest kilowatt above 1000 kW.
 - 3) Usage (Kilowatt-Hours): Nearest kilowatt through 10,000 kW; nearest 10 kW between 10,000 and 100,000 kW; nearest 100 kW for above 100,000 kW.
 - b. Thermal, Rate:
 - 1) Heating: For British thermal units per hour, nearest British thermal unit per hour up to 1000 Btu/h; nearest 10 Btu/h between 1000 and 10,000 Btu/h; nearest 100 Btu/h for above 10,000 Btu/h. For MBh, round to nearest MBh up to 1000 MBh; nearest 10 MBh between 1000 and 10,000 MBh; nearest 100 MBh above 10,000 MBh.
 - 2) Cooling: For tons, nearest ton up to 1000 tons; nearest 10 tons between 1000 and 10,000 tons; nearest 100 tons above 10,000 tons.
 - c. Thermal, Usage:
 - 1) Heating: For British thermal unit, nearest British thermal unit up to 1000 Btu; nearest 10 Btu between 1000 and 10,000 Btu; nearest 100 Btu for above 10,000 Btu. For MBtu, round to nearest MBtu up to 1000 MBtu; nearest 10 MBtu between 1000 and 10,000 MBtu; nearest 100 MBtu above 10,000 MBtu.

- 2) Cooling: For ton-hours, nearest ton-hours up to 1000 ton-hours; nearest 10 ton-hours between 1000 and 10,000 ton-hours; nearest 100 tons above 10,000 tons.

3.Flow:

- a. Air: Nearest 1/10th of a cubic feet per minute through 100 cfm; nearest cubic feet per minute between 100 and 1000 cfm; nearest 10 cfm between 1000 and 10,000 cfm; nearest 100 cfm above 10,000 cfm.
- b. Water: Nearest 1/10th of a gallon per minute through 100 gpm; nearest gallon per minute between 100 and 1000 gpm; nearest 10 gpm between 1000 and 10,000 gpm; nearest 100 gpm above 10,000 gpm.

4.Moisture (Relative Humidity):

- a. Relative Humidity (Percentage): Nearest 1 percent.

5.Level: Nearest 1/100th of an inch through 10 inches; nearest 1/10 of an inch between 10 and 100 inches; nearest inch above 100 inches.

6.Speed:

- a. Rotation (rpm): Nearest 1 rpm.
- b. Velocity: Nearest 1/10th of feet per minute through 100 fpm; nearest feet per minute between 100 and 1000 fpm; nearest 10 fpm above 1000 fpm.

7.Position, Dampers and Valves (Percentage Open): Nearest 1 percent.

8.Pressure:

- a. Air, Ducts and Equipment: Nearest 1/10th of an inch water closet.
- b. Space: Nearest 1/100th of an inch water closet.
- c. Water: Nearest 1/10 of a pound per square inch gauge through 100 psig; nearest pound per square inch gauge above 100 psig.

9.Temperature:

- a. Air, Ducts and Equipment: Nearest 1/10th of a degree.
- b. Outdoor: Nearest degree.
- c. Space: Nearest 1/10th of a degree.

10. Vibration: Nearest 1/10th of an inch per second.

11. Voltage: Nearest 1/10 V up to 100 V; nearest volt above 100 V.

L. Control Stability: Control variables indicated within the following limits:

1.Flow:

- a. Air, Ducts and Equipment, except Terminal Units: Within 5 percent of design flow rate.
- b. Air, Terminal Units: Within 10 percent of design flow rate.
- c. Water: Within 5 percent of design flow rate.

2. Gas:

- a. Carbon Monoxide: Within 5 percent of reading.

3. Moisture (Relative Humidity):

- a. Air: Within 2 percent RH.
- b. Space: Within 2 percent RH.
- c. Outdoor: Within 2 percent RH.

4. Level: Within 2 percent of reading.

5. Pressure:

- a. Air, Ducts and Equipment: 0.5 percent of instrument range.
- b. Space: Within 0.5 percent of instrument range.
- c. Water: Within 0.5 percent of instrument range.

6. Temperature, Dew Point:

- a. Air: Within 0.5 deg F.
- b. Space: Within 0.5 deg F.

7. Temperature, Dry Bulb:

- a. Air: Within 0.5 deg F.
- b. Space: Within 0.5 deg F.

8. Temperature, Wet Bulb:

- a. Air: Within 0.5 deg F.
- b. Space: Within 0.5 deg F.

M. Environmental Conditions for Controllers, Gateways, and Routers:

1. Products to operate without performance degradation under ambient environmental temperature, pressure, and humidity conditions encountered for installed location.

- a. If product alone cannot comply with requirement, install product in a protective enclosure that is isolated and protected from conditions impacting performance. Enclosure to be internally insulated, electrically heated, cooled, and ventilated as required by product and application.

N. Environmental Conditions for Instruments and Actuators:

1. Instruments and actuators to operate without performance degradation under the ambient environmental temperature, pressure, humidity, and vibration conditions specified and encountered for installed location.

- a. If instruments and actuators alone cannot comply with requirement, install instruments and actuators in protective enclosures that are isolated and protected from conditions impacting performance. Enclosure is internally insulated, electrically heated, cooled, and ventilated as required by instrument and application.

O. DDC System Reliability:

1. Design, install, and configure DDC controllers, gateways, routers, and to yield a MTBF of at least 40,000 hours, based on a confidence level of at least 90 percent. MTBF value includes any failure for any reason to any part of products indicated.
2. If required to comply with MTBF indicated, include DDC system and product redundancy to maintain DCC system, and associated systems and equipment being controlled, operational, and under automatic control.
3. See Drawings for critical systems and equipment that require a higher degree of DDC system redundancy than MTBF indicated.

P. Electric Power Quality:

1. Power-Line Surges:

- a. Protect susceptible DDC system products connected to ac power circuits from power-line surges to comply with requirements of IEEE C62.41.1 and IEEE C62.41.2.
- b. Do not use fuses for surge protection.
- c. Test protection in the normal mode and in the common mode, using the following two waveforms:
 - 1) 10-by-1000-microsecond waveform with a peak voltage of 1500 V and a peak current of 60 A.
 - 2) 8-by-20-microsecond waveform with a peak voltage of 1000 V and a peak current of 500 A.

2. Power Conditioning:

- a. Protect DDC system products connected to ac power circuits from irregularities and noise rejection. Characteristics of power-line conditioner are as follows:
 - 1) At 85 percent load, output voltage to not deviate by more than plus or minus 1 percent of nominal when input voltage fluctuates between minus 20 percent to plus 10 percent of nominal.
 - 2) During load changes from zero to full load, output voltage to not deviate by more than 2 percent of nominal.
 - 3) Accomplish full correction of load switching disturbances within five cycles, and 95 percent correction within two cycles of onset of disturbance.
 - 4) Total harmonic distortion to not exceed 2 percent at full load.

3. Ground Fault: Protect products from ground fault by providing suitable grounding. Products to not fail due to ground fault condition.

Q. Backup Power Source:

1. Serve DDC system products that control HVAC systems and equipment served by a backup power source also from a backup power source.

R. UPS:

1. DDC system products powered by UPS units are to include the following:

- a. Servers.
- b. Gateways.
- c. DDC controllers, except application-specific controllers.
- d. Desktop workstations.

2. DDC system instruments and actuators powered by UPS units are to include the following:

- a. Instruments: Where indicated on Drawings; where associated with the following systems controlled by DDC system:
- b. Damper Actuators: Where indicated on Drawings; where associated with the following systems controlled by DDC system:
- c. Valve Actuators: Where indicated on Drawings; where associated with the following systems controlled by DDC system:

S. Continuity of Operation after Electric Power Interruption:

1. Equipment and associated factory-installed controls, field-installed controls, electrical equipment, and power supply connected to building normal and backup power systems are to automatically return equipment and associated controls to operating state occurring immediately before loss of normal power, without need for manual intervention by operator when power is restored either through backup power source or through normal power if restored before backup power is brought online.

2.5 PANEL-MOUNTED, MANUAL OVERRIDE SWITCHES

A. Manual Override of Control Dampers:

1. Include panel-mounted, two-position, selector switch for each automatic control damper being controlled by DDC controller.
2. Label each switch with damper designation served by switch.
3. Label switch positions to indicate either "Manual" or "Auto" control signal to damper.
4. With switch in "Auto" position, control signal to damper actuator with control loop output signal from DDC controller.
5. With switch in "Manual" position, control signal to damper actuator at panel with either an integral or a separate switch to include local control.
 - a. For Binary Control Dampers: Manual two-position switch with "Close" and "Open" switch positions indicated. With switch in "Close" position, close damper. With switch in "Open" position, open damper.

- b. For Analog Control Dampers: A gradual switch with "Close" and "Open" switch limits indicated. Operator switches knob to adjust damper to any position from close to open.
- 6.DDC controller to monitor and report position of each manual override selector switch. With switch placed in "manual" position, DDC controller to signal an override condition to alert operator that damper is under manual, not automatic, control.
 - 7.Configure manual override switches to allow operator to manually operate damper while at panel without DDC controller installed and operational.
 - 8.Terminal equipment including VAV units, fan-coil units, and unit heaters do not require manual override unless otherwise indicated by sequence of operation.
- B. Manual Override of Control Valves:
- 1.Include panel-mounted, two-position, selector switch for each automatic control valve being controlled by DDC controller.
 - 2.Label each switch with valve designation served by switch.
 - 3.Label switch positions to indicate either "Manual" or "Auto" control signal to valve.
 - 4.With switch in "Auto" position, control signal to valve actuator with a control loop output signal from DDC controller.
 - 5.With switch in "Manual" position, control signal to valve actuator at panel with either an integral or a separate switch to include local control.
 - a. For Binary Control Valves: Manual two-position switch with "Close" and "Open" switch positions indicated. With switch in "Close" position, close valve. With switch in "Open" position, open valve.
 - b. For Analog Control Valves: A gradual switch with "Open" and "Close" switch limits indicated. Operator rotates switch knob to adjust valve to any position from close to open.
 - 6.DDC controller to monitor and report position of each manual override selector switch. With switch placed in "manual" position, DDC controller to signal an override condition to alert operator that valve is under manual, not automatic, control.
 - 7.Configure manual override switches to allow operator to manually operate valve while at panel without DDC controller installed and operational.
 - 8.Terminal equipment including VAV units, fan-coil units, and unit heaters do not require manual override unless otherwise indicated by sequence of operation.

2.6 SYSTEM ARCHITECTURE

- A. System architecture consisting of no more than two or three levels of LANs.
- 1.Level 2 LAN: Connect network controllers and operator workstations.
 - 2.Level 1 or Level 2 LAN: Connect Level 1 or Level 2 programmable application controllers to other programmable application controllers and to network controllers.
 - 3.Level 2 or Level 3 LAN: Connect Level 2 or Level 3 application-specific controllers to programmable application controllers and to network controllers.
- B. Minimum Data Transfer and Communication Speed:

- 1.LAN Connecting Operator Workstations and Network Controllers: 100 Mbps.
 - 2.LAN Connecting Programmable Application Controllers: 1000 kbps.
 - 3.LAN Connecting Application-Specific Controllers: 115,000 bps.
- C. Provide dedicated and separated DDC system LANs that are not shared with other building systems and tenant data and communication networks.
- D. Provide modular system architecture with inherent ability to expand to not less than 1.5 times system size indicated with no impact to performance indicated.
- E. Configure architecture to eliminate or minimize need to remove and replace existing network equipment for system expansion.
- F. Make number of LANs and associated communication transparent to operator. Configure all I/O points residing on any LAN to be capable of global sharing between all system LANs.
- G. Design system to eliminate dependence on any single device for system alarm reporting and control execution. Design each controller to operate independently by performing own control, alarm management, and historical data collection.
- H. Special Network Architecture Requirements:
- 1.Air-Handling Systems: For control applications of an air-handling system that consists of air-handling unit(s) and VAV terminal units, include a dedicated LAN of application-specific controllers serving VAV terminal units connected directly to controller that is controlling air-handling-system air-handling unit(s). Basically, create DDC system LAN that aligns with air-handling system being controlled.

2.7 DDC SYSTEM OPERATOR INTERFACES

- A. Operator Means of System Access: Operator able to access entire DDC system through any of multiple means including, but not limited to, the following:
- 1.Desktop and portable workstation with hardwired connection through LAN port.
 - 2.Portable operator terminal with hardwired connection through LAN port.
 - 3.Portable operator workstation with wireless connection through LAN router.
 - 4.Mobile device and application with secured wireless connection through LAN router or cellular data service.
 - 5.Remote connection through web access.
- B. Make access to system, regardless of operator means used, transparent to operator.
- C. Network Ports: For hardwired connection of desktop or portable workstation. Network port easily accessible, properly protected, clearly labeled, and installed at the following locations:
- 1.Each mechanical equipment room.
 - 2.Each outdoor on-grade yard and elevated platform with equipment connected to DDC system.
 - 3.Each different roof level with roof-mounted equipment connected to DDC system.
 - 4.Security system command center.
 - 5.Fire-alarm system command center.

D. Critical Alarm Reporting:

1. Send operator-selected critical alarms to notify operator of critical alarms that require immediate attention.
2. Send alarm notification to multiple recipients that are assigned for each alarm.
3. Notify recipients by any or all means, including email, text message, and prerecorded phone message to mobile and landline phone numbers.

E. Simultaneous Operator Use: Capable of accommodating up to 10 simultaneous operators that are accessing DDC system through any of operator interfaces indicated.

2.8 NETWORKS

A. Acceptable networks for connecting workstations, mobile devices, and network controllers include the following:

1. ATA 878.1, ARCNET.
2. CTA-709.1-D.
3. IP.
4. ISO/IEC/IEEE 8802-3, Ethernet.

B. Acceptable networks for connecting programmable application controllers include the following:

1. ATA 878.1, ARCNET.
2. CTA-709.1-D.
3. IP.
4. ISO/IEC/IEEE 8802-3, Ethernet.

C. Acceptable networks for connecting application-specific controllers include the following:

1. ATA 878.1, ARCNET.
2. CTA-709.1-D.
3. TIA 485-A.
4. IP.
5. ISO/IEC/IEEE 8802-3, Ethernet.

2.9 NETWORK COMMUNICATION PROTOCOL

A. Use network communication protocol(s) that are open to Owner and available to other companies for use in making future modifications to DDC system.

B. ASHRAE 135 Protocol:

1. Use ASHRAE 135 communication protocol as sole and native protocol used throughout entire DDC system.
2. DDC system to not require use of gateways except to integrate HVAC equipment and other building systems and equipment; not required to use ASHRAE 135 communication protocol.

- 3.If used, gateways to connect to DDC system using ASHRAE 135 communication protocol and Project object properties and read/write services indicated by interoperability schedule.
- 4.Use operator workstations, controllers, and other network devices that are tested and listed by BTL.

C. Industry Standard Protocols:

- 1.Use any one or a combination of the following industry standard protocols for network communication while complying with other DDC system requirements indicated:
 - a. ASHRAE 135.
 - b. Modbus Application Protocol Specification V1.1b3.
- 2.Operator workstations and network controllers are to communicate through ASHRAE 135 protocol.
- 3.Provide portions of DDC system networks using ASHRAE 135 communication protocol as an open implementation of network devices complying with ASHRAE 135. Use network devices that are tested and listed by BTL.
- 4.Provide portions of DDC system networks using CTA-709.1-D communication protocol as an open implementation of LonWorks technology using CTA-709.1-D communication protocol and using LonMark SNVTs as defined in LonMark SNVT list exclusively for DDC system.
- 5.Provide portions of DDC system networks using Modbus Application Protocol Specification V1.1b3 communication protocol as an open implementation of network devices and technology complying with Modbus Application Protocol Specification V1.1b3.
- 6.Use gateways to connect networks and network devices with different protocols.

2.10 DDC SYSTEM WIRELESS NETWORKS

- A. Use Zigbee or an open industry standard and technology used by multiple DDC system manufacturers technology to create a wireless mesh network to provide wireless connectivity for network devices at multiple system levels including communications from programmable application controllers and application-specific controllers to temperature sensors and from network controllers to programmable application controllers and application-specific controllers.
- B. Design and install wireless networks to comply with DDC system performance requirements indicated using wireless network devices that can co-exist on same network with hardwired devices.
- C. Provide hardwired controllers capable of retrofitting to wireless devices with no special software.
- D. Provide a wireless coordinator for wireless interface between programmable application controllers, application-specific controllers, and network controllers.
- E. Wireless Coordinators:
 - 1.Use for initiation and formation of each wireless mesh network.
 - 2.Use direct-sequence spread spectrum RF technology.
 - 3.Operate on 2.4 GHz ISM Band.

4. Comply with IEEE 802.15.4 for low-power, low duty-cycle RF transmitting systems.
5. FCC compliant to 47 CFR 15, Subpart B, Class A.
6. Operate as a bidirectional transceiver with sensors and routers to confirm and synchronize data transmission.
7. Capable of communication with sensors and routers up to a maximum distance of 250 ft. in line of sight.
8. Include visual indicators to provide diagnostic information required for operator verification of operation.

F. Wireless Routers:

1. Use wireless routers with any controller to provide a wireless interface to a network controller, through a wireless coordinator.
2. Use direct-sequence spread spectrum RF technology.
3. Operate on 2.4 GHz ISM Band.
4. Comply with IEEE 802.15.4 for low-power, low duty-cycle RF transmitting systems.
5. FCC compliant to 47 CFR 15, Subpart B, Class A.
6. Operate as a bidirectional transceiver with other mesh network devices to ensure network integrity.
7. Capable of communication with other mesh network devices at a maximum distance of 250 ft. in line of sight.
8. Include indication for use in commissioning and troubleshooting.

G. Wireless Temperature Sensors:

1. Wireless temperature sensors to sense and transmit room temperatures, temperature set point, room occupancy notification, and low battery condition to an associated router.
2. Use direct-sequence spread spectrum RF technology.
3. Operate on 2.4 GHz ISM Band.
4. Comply with IEEE 802.15.4 for low-power, low duty-cycle RF transmitting systems.
5. FCC compliant to 47 CFR 15, Subpart B, Class A.
6. Include set-point adjustment between 55 to 85 deg F.
7. Configure so multiple sensors can report to a router connected to DDC controller for averaging or high and low selection.

H. One-to-One Wireless Network Receivers:

1. One-to-one wireless receivers receive wireless RF signals containing temperature data from multiple wireless room temperature sensors and communicate information to programmable application controllers or application-specific controllers.
 - a. Use direct-sequence spread spectrum RF technology.
 - b. Operate on 2.4 GHz ISM Band.
 - c. Comply with IEEE 802.15.4 for low-power, low duty-cycle RF transmitting systems.
 - d. FCC compliant to 47 CFR 15, Subpart B, Class A.
 - e. Operate as a bidirectional transceiver with sensors to confirm and synchronize data transmission.
 - f. Capable of communication up to a distance of 200 ft..
 - g. Include visual indication of the following:
 - 1) Power.

- 2) Receiver activity.
- 3) Wireless RF transmission from wireless sensors.
- 4) No transmission, weak signal, adequate signal, or excellent signal.

I. One-to-One Wireless Network Sensors:

1. One-to-one wireless sensors sense and report room temperatures to one-to-one receiver.

- a. Use direct-sequence spread spectrum RF technology.
- b. Operate on 2.4 GHz ISM Band.
- c. Comply with IEEE 802.15.4 for low-power, low duty-cycle RF transmitting systems.
- d. FCC compliant to 47 CFR 15, Subpart B, Class A.
- e. Include set-point adjustment between 55 to 85 deg F.

2.11 SERVERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Dell Technologies Inc.
2. HP Inc.
3. Lenovo Holding Co., Inc.; Lenovo Group Ltd.

B. Description: x86-based permanently installed computer used for client-server computing.

C. Power: Single power supply, minimum 300 W.

D. Servers are to include the following:

1. Full-feature backup server (server and backup minimum requirement).
2. Software licenses.
3. Cable installation between server(s) and network.

E. Web Server:

1. If required to be separate, include web server hardware and software to match, except backup server is not required.
2. Firewalls between server web and networks.
3. Password protection for access to server from web server.
4. Cable installation between the server(s) and building Ethernet network.

F. Power each server through a UPS unit.

2.12 SYSTEM SOFTWARE

A. System Software Minimum Requirements:

1. Real-time multitasking and multiuser 32- or 64-bit operating system that allows concurrent multiple operator workstations operating and concurrent execution of multiple real-time programs and custom program development.
2. Operating system capable of operating DOS and Microsoft Windows applications.
3. Database management software to manage all data on an integrated and non-redundant basis. Additions and deletions to database are to be without detriment to existing data. Include cross linkages so no data required by a program can be deleted by an operator until that data have been deleted from respective programs.
4. Network communications software to manage and control multiple network communications to provide exchange of global information and execution of global programs.
5. Operator interface software to include day-to-day operator transaction processing, alarm and report handling, operator privilege level and data segregation control, custom programming, and online data modification capability.
6. Scheduling software to schedule centrally based time and event, temporary, and exception day programs.

B. Operator Interface Software:

1. Minimize operator training through use of English language pronouncing and English language point identification.
2. Minimize use of a typewriter-style keyboard through use of a pointing device similar to a mouse.
3. Make operator sign-off a manual operation or, if no keyboard or mouse activity takes place, an automatic sign-off.
4. Make automatic sign-off period programmable from one to 60 minutes in one-minute increments on a per operator basis.
5. Record operator sign-on and sign-off activity and send to printer.
6. Security Access:
 - a. Use password control for operator access to DDC system.
 - b. Assign an alphanumeric password (field assignable) to each operator.
 - c. Grant operators access to DDC system by entry of proper password.
 - d. Use same operator password regardless of which computer or other operator interface means are used.
 - e. Automatically update additions or changes made to passwords.
 - f. Assign each operator an access level to restrict access to data and functions the operator is capable of performing.
 - g. Provide software with at least five access levels.
 - h. Assign each menu item an access level so that a one-for-one correspondence between operator assigned access level(s) and menu item access level(s) is required to gain access to menu item.
 - i. Display menu items to operator with those capable of access highlighted. Make menu and operator access level assignments online programmable and under password control.
7. Data Segregation:
 - a. Include data segregation for control of specific data routed to a workstation, to an operator or to a specific output device, such as a printer.
 - b. Include at least 32 segregation groups.

- c. Make segregation groups selectable such as "fire points," "fire points on second floor," "space temperature points," "HVAC points," and so on.
- d. Make points assignable to multiple segregation groups. Display and output of data to printer or monitor is to occur where there is a match of operator or peripheral segregation group assignment and point segregations.
- e. Make alarms displayed and printed at each peripheral to which segregation allows, but only those operators assigned to peripheral and having proper authorization level will be allowed to acknowledge alarms.
- f. Assign operators and peripherals to multiple segregation groups and make all assignments online programmable and under password control.

8. Operators able to perform commands including, but not limited to, the following:

- a. Start or stop selected equipment.
- b. Adjust set points.
- c. Add, modify, and delete time programming.
- d. Enable and disable process execution.
- e. Lock and unlock alarm reporting for each point.
- f. Enable and disable totalization for each point.
- g. Enable and disable trending for each point.
- h. Override control loop set points.
- i. Enter temporary override schedules.
- j. Define holiday schedules.
- k. Change time and date.
- l. Enter and modify analog alarm limits.
- m. Enter and modify analog warning limits.
- n. View limits.
- o. Enable and disable demand limiting.
- p. Enable and disable duty cycle.
- q. Display logic programming for each control sequence.

9. Reporting:

- a. Generated automatically and manually.
- b. Sent to displays, printers and disc files.
- c. Types of Reporting:
 - 1) General listing of points.
 - 2) List points currently in alarm.
 - 3) List of off-line points.
 - 4) List points currently in override status.
 - 5) List of disabled points.
 - 6) List points currently locked out.
 - 7) List of items defined in a "Follow-Up" file.
 - 8) List weekly schedules.
 - 9) List holiday programming.
 - 10) List of limits and deadbands.

10. Summaries: For specific points, for a logical point group, for an operator selected group(s), or for entire system without restriction due to hardware configuration.

C. Graphic Interface Software:

1. Include a full interactive graphical selection means of accessing and displaying system data to operator. Include at least five levels with the penetration path operator assignable (for example, site, building, floor, air-handling unit, and supply temperature loop). Native language descriptors assigned to menu items are to be operator defined and modifiable under password control.
2. Include a hierarchical-linked dynamic graphic operator interface for accessing and displaying system data and commanding and modifying equipment operation. Interface is to use a pointing device with pull-down or penetrating menus, color, and animation to facilitate operator understanding of system.
3. Include at least 10 levels of graphic penetration with the hierarchy operator assignable.
4. Make descriptors for graphics, points, alarms, and such modifiable through operator's workstation under password control.
5. Make graphic displays online user definable and modifiable using the hardware and software provided.
6. Make data displayed within a graphic assignable regardless of physical hardware address, communication, or point type.
7. Make graphics online programmable and under password control.
8. Make points assignable to multiple graphics where necessary to facilitate operator understanding of system operation.
9. Graphics to also contain software points.
10. Penetration within a graphic hierarchy is to display each graphic name as graphics are selected to facilitate operator understanding.
11. Provide a back-trace feature to permit operator to move upward in the hierarchy using a pointing device. Back trace to show all previous penetration levels. Include operator with option of showing each graphic full-screen size with back trace as horizontal header or by showing a "stack" of graphics, each with a back trace.
12. Display operator accessed data on the monitor.
13. Provide operator with ability to select further penetration using pointing device to click on a site, building, floor, area, equipment, and so on. Display defined and linked graphic below that selection.
14. Include operator with means to directly access graphics without going through penetration path.
15. Make dynamic data assignable to graphics.
16. Display points (physical and software) with dynamic data provided by DDC system with appropriate text descriptors, status or value, and engineering unit.
17. Use color, rotation, or other highly visible means, to denote status and alarm states. Make colors variable for each class of points, as chosen by operator.
18. Provide dynamic points with operator adjustable update rates on a per point basis from one second to over a minute.
19. For operators with appropriate privilege, command points directly from display using pointing device.
 - a. For an analog command point such as set point, display current conditions and limits so operator can position new set point using pointing device.
 - b. For a digital command point such as valve position, show valve in current state such as open or closed so operator could select alternative position using pointing device.
 - c. Include a keyboard equivalent for those operators with that preference.

20. Give operator ability to split or resize viewing screen into quadrants to show one graphic on one quadrant of screen and other graphics or spreadsheet, bar chart, word processing, curve plot, and other information on other quadrants on screen. This feature allows real-time monitoring of one part of system while displaying other parts of system or data to better facilitate overall system operation.
 21. Help Features:
 - a. Online context-sensitive help utility to facilitate operator training and understanding.
 - b. Bridge to further explanation of selected keywords and contain text and graphics to clarify system operation.
 - 1) If help feature does not have ability to bridge on keywords for more information, provide a complete set of user manuals in an indexed word-processing program, which runs concurrently with operating system software.
 - c. Available for Every Menu Item:
 - 1) Index items for each system menu item.
 22. Provide graphic generation software to allow operator ability to add, modify, or delete system graphic displays.
 - a. Include libraries of symbols depicting HVAC symbols such as fans, coils, filters, dampers, valves pumps, and electrical symbols similar to those indicated.
 - b. Use a pointing device in conjunction with a drawing program to allow operator to perform the following:
 - 1) Define background screens.
 - 2) Define connecting lines and curves.
 - 3) Locate, orient, and size descriptive text.
 - 4) Define and display colors for all elements.
 - 5) Establish correlation between symbols or text and associated system points or other displays.
- D. Project-Specific Graphics: Graphics documentation including, but not limited to, the following:
1. Site plan showing each building, and additional site elements, which are being controlled or monitored by DDC system.
 2. Plan for each building floor, including interstitial floors, and each roof level of each building, showing the following:
 - a. Room layouts with room identification and name.
 - b. Locations and identification of all monitored and controlled HVAC equipment and other equipment being monitored and controlled by DDC system.
 - c. Location and identification of each hardware point being controlled or monitored by DDC system.
 3. Control schematic for each of following, including a graphic system schematic representation, similar to that indicated on Drawings, with point identification, set point and dynamic value indication, sequence of operation and control logic diagram.

4. Graphic display for each piece of equipment connected to DDC system through a data communications link. Include dynamic indication of all points associated with equipment.
5. DDC system network riser diagram that shows schematic layout for entire system including all networks and all controllers, gateways and other network devices.

E. Customizing Software:

1. Software to modify and tailor DDC system to specific and unique requirements of equipment installed, to programs implemented and to staffing and operational practices planned.
2. Online modification of DDC system configuration, program parameters, and database using menu selection and keyboard entry of data into preformatted display templates.
3. At a minimum, include the following modification capability:
 - a. Operator Assignment: Designation of operator passwords, access levels, point segregation, and auto sign-off.
 - b. Peripheral Assignment: Assignment of segregation groups and operators to consoles and printers, designation of backup workstations and printers, designation of workstation header points, and enabling and disabling of printout of operator changes.
 - c. System Configuration and Diagnostics: Communications and peripheral port assignments, DDC controller assignments to network, DDC controller enable and disable, assignment of command trace to points, and application programs and initiation of diagnostics.
 - d. System Text Addition and Change: English or native language descriptors for points, segregation groups and access levels and action messages for alarms, run time, and trouble condition.
 - e. Time and Schedule Change: Time and date set, time and occupancy schedules, exception and holiday schedules, and daylight-savings time schedules.
 - f. Point related change capability is to include the following:
 - 1) System and point enable and disable.
 - 2) Run-time enable and disable.
 - 3) Assignment of points to segregation groups, calibration tables, lockout, and run time and to a fixed I/O value.
 - 4) Assignment of alarm and warning limits.
 - g. Application program change capability is to include the following:
 - 1) Enable and disable of software programs.
 - 2) Programming changes.
 - 3) Assignment of comfort limits, global points, time and event initiators, time and event schedules and enable and disable time and event programs.
4. Provide software to allow operator ability to add points, or groups of points, to DDC system and to link them to energy optimization and management programs. Make additions and modifications online programmable using operator workstations, downloaded to other network devices and entered into their databases. After verification of point additions and associated program operation, upload and record database on hard drive and disc for archived record.
5. Include high-level language programming software capability for implementation of custom DDC programs. Include a compiler, linker, and up- and down-load capability.

6. Include a library of DDC algorithms, intrinsic control operators, arithmetic, logic, and relational operators for implementation of control sequences. Also include, at a minimum, the following:
 - a. Proportional control (P).
 - b. Proportional plus integral (PI).
 - c. Proportional plus integral plus derivative (PID).
 - d. Adaptive and intelligent self-learning control.
 - 1) Algorithm monitors loop response to output corrections and adjust loop response characteristics in accordance with time constant changes imposed.
 - 2) Algorithm operates in a continuous self-learning manner and retains in memory a stored record of system dynamics so that on system shut down and restart, learning process starts from where it left off.
7. Fully implemented intrinsic control operators including sequence, reversing, ratio, time delay, time of day, highest select AO, lowest select AO, analog controlled digital output, analog control AO, and digitally controlled AO.
8. Logic operators such as "And," "Or," "Not," and others that are part of a standard set available with a high-level language.
9. Arithmetic operators such as "Add," "Subtract," "Multiply," "Divide," and others that are part of a standard set available with a high-level language.
10. Relational operators such as "Equal to," "Not Equal to," "Less Than," "Greater Than," and others that are part of a standard set available with a high-level language.

F. Alarm Handling Software:

1. Include alarm handling software to report all alarm conditions monitored and transmitted through DDC controllers, gateways and other network devices.
2. Include first in, first out handling of alarms in accordance with alarm priority ranking, with most critical alarms first, and with buffer storage in case of simultaneous and multiple alarms.
3. Make alarm handling active at all times to ensure that alarms are processed even if an operator is not currently signed on to DDC system.
4. Alarms display is to include the following:
 - a. Indication of alarm condition such as "Abnormal Off," "Hi Alarm," and "Low Alarm."
 - b. "Analog Value" or "Status" group and point identification with native language point descriptor such as "Space Temperature, Building 110, 2nd Floor, Room 212."
 - c. Discrete per point alarm action message, such as "Call Maintenance Dept. Ext-5561."
 - d. Include extended message capability to allow assignment and printing of extended action messages. Capability is to be operator programmable and assignable on a per point basis.
5. Direct alarms to appropriate operator workstations, printers, and individual operators by privilege level and segregation assignments.
6. Send email alarm messages to designated operators.
7. Send email, page, text, and voice messages to designated operators for critical alarms.
8. Categorize and process alarms by class.

a. Class 1:

- 1) Associated with fire, security, and other extremely critical equipment monitoring functions; have alarm, trouble, return to normal, and acknowledge conditions printed and displayed.
- 2) Unacknowledged alarms to be placed in unacknowledged alarm buffer.
- 3) All conditions make an audible alarm sound and require individual acknowledgment to silence audible sound.

b. Class 2:

- 1) Critical, but not life-safety related, and processed same as Class 1 alarms, except do not require individual acknowledgment.
- 2) Acknowledgement may be through a multiple alarm acknowledgment.

c. Class 3:

- 1) General alarms; printed, displayed, and placed in unacknowledged alarm buffer queues.
- 2) Configure so each new alarm received makes an audible alarm sound that are silenced by "acknowledging" alarm or by pressing a "silence" key.
- 3) Make acknowledgement of queued alarms either on an individual basis or through a multiple alarm acknowledgement.
- 4) Print alarms returning to normal condition without an audible alarm sound or require acknowledgment.

d. Class 4:

- 1) Routine maintenance or other types of warning alarms.
- 2) Alarms to be printed only, with no display, no audible sound and no acknowledgment required.

9. Include an unacknowledged alarm indicator on display to alert operator that there are unacknowledged alarms in system. Operator able to acknowledge alarms on an individual basis or through a multiple alarm acknowledge key, depending on alarm class.

10. To ensure that no alarm records are lost, make it possible to assign a backup printer to accept alarms in case of failure of primary printer.

G. Reports and Logs:

1. Include reporting software package that allows operator to select, modify, or create reports using DDC system I/O point data available.
2. Setup each report so data content, format, interval, and date are operator definable.
3. Sample and store report data on DDC controller, within storage limits of DDC controller, and then uploaded to archive on workstation for historical reporting.
4. Make it possible for operators to obtain real-time logs of all I/O points by type or status, such as alarm, point lockout, or normal.
5. Store reports and logs on workstations and servers hard drives in a format that is readily accessible by other standard software applications, including spreadsheets and word processing.

6. Make reports and logs readily printable and set to be print either on operator command or at a specific time each day.
- H. Standard Reports: Provide standard DDC system reports with operator ability to customize reports later.
1. All I/O: With current status and values.
 2. Alarm: All current alarms, except those in alarm lockout.
 3. Disabled I/O: All I/O points that are disabled.
 4. Alarm Lockout I/O: All I/O points in alarm lockout, whether manual or automatic.
 5. Alarm Lockout I/O in Alarm: All I/O in alarm lockout that are currently in alarm.
 6. Logs:
 - a. Alarm history.
 - b. System messages.
 - c. System events.
 - d. Trends.
 - e. <Insert requirement>.
- I. Custom Reports: Operator able to easily define and prepare any system data into a daily, weekly, monthly, annual, or other historical report. Reports to include a title with time and date stamp.
- J. Tenant Override Reports: Prepare Project-specific reports.
1. Daily report showing total time in hours that each tenant has requested after-hours HVAC.
 2. Weekly report showing daily total time in hours that each tenant has requested after-hours HVAC.
 3. Monthly report showing daily total time in hours that each tenant has requested after-hours HVAC.
 4. Annual summary report that shows after-hours HVAC usage on a monthly basis.
- K. Utility Reports: Prepare Project-specific reports.
1. Electric Report:
 - a. Include weekly report showing daily electrical consumption and peak electrical demand with time and date stamp for each meter.
 - b. Include monthly report showing the daily electrical consumption and peak electrical demand with time and date stamp for each meter.
 - c. Include annual report showing monthly electrical consumption and peak electrical demand with time and date stamp for each meter.
 - d. For each weekly, monthly, and annual report, include sum total of submeters combined by load type, such as lighting, receptacles, and HVAC equipment showing daily electrical consumption and peak electrical demand.
 - e. For each weekly, monthly, and annual report, include sum total of all submeters in building showing electrical consumption and peak electrical demand.
 2. Service Water Report:
 - a. Include weekly, monthly, and annual report showing daily service water consumption and peak service water demand with time and date stamp for each meter.

- b. For each weekly, monthly, and annual report, include sum total of submeters combined by load type, such as cooling tower makeup and irrigation showing daily service water consumption and peak service water demand.
 - c. For each weekly, monthly, and annual report, include sum total of all submeters in building showing service water consumption and peak service water demand.
- L. Energy Reports: Prepare Project-specific daily, weekly, monthly, and annual , annual and since-installed energy reports.
- 1.Prepare report for each purchased energy utility, indicating the following:
 - a. Time being reported with beginning and end date, and time indicated.
 - b. Consumption in units of measure commonly used to report specific utility consumption over time.
 - c. Gross area served by utility.
 - d. Consumption per unit area served using utility-specific unit of measure.
 - e. Cost per utility unit.
 - f. Utility cost per unit area.
 - g. Convert all utilities to a common energy consumption unit of measure and report for each utility.
 - h. Consumption per unit area using common unit of measure.
 - 2.Prepare report for each renewable energy source, indicating the following:
 - a. Time being reported with beginning and end date, and time indicated.
 - b. Harvested energy in units of measure commonly used to report specific harvested energy consumption over time.
 - c. Gross area served by renewable energy source.
 - d. Harvested energy per unit area served using specific unit of measure.
 - e. Cost per purchased utility unit displaced by renewable energy.
 - f. Cost savings attributed to harvested energy source.
 - g. Cost savings per unit area attributed to harvested energy.
 - h. Convert all renewable energy sources to a common energy consumption unit of measure and report for each.
 - i. Harvested energy per unit area using common unit of measure.
 - 3.Prepare purchased energy utility report for each submetered area that indicates the following:
 - a. Time being reported with beginning and end date, and time indicated.
 - b. Gross area served.
 - c. Energy consumption by energy utility type.
 - d. Energy consumption per unit area by energy utility type.
 - e. Total energy consumption of all utilities in common units of measure.
 - f. Total energy consumption of all utilities in common units of measure per unit area.
 - g. Unit energy cost by energy utility type.
 - h. Energy cost by energy utility type.
 - i. Energy cost per unit area by energy utility type.
 - j. Total cost of all energy utilities.
 - k. Total cost of all energy utilities per unit area.

4. Prepare Project total purchased energy utility report that combines all purchased energy utilities and all areas served. Project total energy report is to indicate the following:
- a. Time being reported with beginning and end date, and time indicated.
 - b. Gross area served.
 - c. Energy consumption by energy utility type.
 - d. Energy consumption per unit area by energy utility type.
 - e. Total energy consumption of all utilities in common units of measure.
 - f. Total energy consumption of all utilities in common units of measure per unit area.
 - g. Unit energy cost by energy utility type.
 - h. Energy cost by energy utility type.
 - i. Energy cost per unit area by energy utility type.
 - j. Total cost of all energy utilities.
 - k. Total cost of all energy utilities per unit area.

M. Weather Reports:

1. Include daily report showing the following:

- a. Daily minimum, maximum, and average outdoor dry-bulb temperature.
- b. Daily minimum, maximum, and average outdoor wet-bulb temperature.
- c. Daily minimum, maximum, and average outdoor dew point temperature.
- d. Number of heating degree-days for each day calculated from a base temperature of 55 deg F.
- e. Number of cooling degree-days for each day calculated from a base temperature of 65 deg F.
- f. Daily minimum, maximum, and average outdoor carbon dioxide level.
- g. Daily minimum, maximum, and average relative humidity.
- h. Daily minimum, maximum, and average barometric pressure.
- i. Daily minimum, maximum, and average wind speed and direction.

2. Include weekly report showing the following:

- a. Daily minimum, maximum, and average outdoor dry-bulb temperature.
- b. Daily minimum, maximum, and average outdoor wet-bulb temperature.
- c. Daily minimum, maximum, and average outdoor dew point temperature.
- d. Number of heating degree-days for each day calculated from a base temperature of 55 deg F.
- e. Number of cooling degree-days for each day calculated from a base temperature of 65 deg F.
- f. Weekly minimum, maximum, and average outdoor carbon dioxide level.
- g. Daily minimum, maximum, and average relative humidity.
- h. Daily minimum, maximum, and average barometric pressure.
- i. Daily minimum, maximum, and average wind speed and direction.

3. Include monthly report showing the following:

- a. Daily minimum, maximum, and average outdoor dry-bulb temperature.
- b. Daily minimum, maximum, and average outdoor wet-bulb temperature.
- c. Daily minimum, maximum, and average outdoor dew point temperature.

- d. Number of heating degree-days for each day calculated from a base temperature of 55 deg F.
- e. Number of cooling degree-days for each day calculated from a base temperature of 65 deg F.
- f. Monthly minimum, maximum, and average outdoor carbon dioxide level.
- g. Daily minimum, maximum, and average relative humidity.
- h. Daily minimum, maximum, and average barometric pressure.
- i. Daily minimum, maximum, and average wind speed and direction.

4. Include annual (12-month) report showing the following:

- a. Monthly minimum, maximum, and average outdoor dry-bulb temperature.
- b. Monthly minimum, maximum, and average outdoor wet-bulb temperature.
- c. Monthly minimum, maximum, and average outdoor dew point temperature.
- d. Number of heating degree-days for each month calculated from a base temperature of 55 deg F.
- e. Number of cooling degree-days for each month calculated from a base temperature of 65 deg F.
- f. Annual minimum, maximum, and average outdoor carbon dioxide level.
- g. Monthly minimum, maximum, and average relative humidity.
- h. Daily minimum, maximum, and average barometric pressure.
- i. Daily minimum, maximum, and average wind speed and direction.

N. Standard Trends:

1. Trend all I/O point present values, set points, and other parameters indicated for trending.
2. Associate trends into groups, and setup a trend report for each group.
3. Store trends within DDC controller and uploaded to hard drives automatically on reaching 75 percent of DDC controller buffer limit, or by operator request, or by archiving time schedule.
4. Preset trend intervals for each I/O point after review with Owner.
5. Make trend intervals operator selectable from 10 seconds up to 60 minutes. Make minimum number of consecutive trend values stored at one time 100 per variable.
6. When drive storage memory is full, overwrite oldest data with most recent data.
7. Make archived and real-time trend data available for viewing numerically and graphically by operators.

O. Custom Trends: Operator-definable custom trend log for any I/O point in DDC system.

1. Include each trend with interval, start time, and stop time.
2. Sample and store data on DDC controller, within reaching 75 percent storage limits of DDC controller, and then uploaded to archive on server hard drives.
3. Make data retrievable for use in spreadsheets and standard database programs.

P. Programming Software:

1. Include programming software to execute sequences of operation indicated.
2. Include programming routines in simple and easy to follow logic with detailed text comments describing what the logic does and how it corresponds to sequence of operation.
3. Programming Software: As follows:

- a. Graphic Based: Use a library of function blocks made from preprogrammed code designed for DDC control systems.
 - 1) Assemble function blocks with interconnection lines that represent to control sequence in a flowchart.
 - 2) Make programming tools viewable in real time to show present values and logical results of each function block.
 - b. Menu Based: Done by entering parameters, definitions, conditions, requirements, and constraints.
 - c. Line by Line and Text Based: Programming is to declare variable types such as local, global, real, integer, and so on, at the beginning of the program. Use descriptive comments frequently to describe programming code.
4. Include means for detecting programming errors and testing software control strategies with a simulation tool before implementing in actual control. Simulation tool may be inherent with programming software or as a separate product.

Q. Database Management Software:

1. Where a separate SQL database is used for information storage, include database management software that separates database monitoring and managing functions by supporting multiple separate windows.
2. Secure database access using standard SQL authentication including ability to access data for use outside of DDC system applications.
3. Include database management function summarizing information on trend, alarm, event, and audit for the following database management actions:
 - a. Backup.
 - b. Purge.
 - c. Restore.
4. Database management software supporting the following:
 - a. Statistics: Display database server information and trend, alarm, event, and audit information on database.
 - b. Maintenance: Include method of purging records from trend, alarm, event, and audit databases by supporting separate screens for creating a backup before purging, selecting database, and allowing for retention of a selected number of day's data.
 - c. Backup: Include means to create a database backup file and select a storage location.
 - d. Restore: Include a restricted means of restoring a database by requiring operator to have proper security level.
5. Information of current database activity, including the following:
 - a. Ready.
 - b. Purging record from a database.
 - c. Action failed.
 - d. Refreshing statistics.
 - e. Restoring database.
 - f. Shrinking a database.

- g. Backing up a database.
- h. Resetting Internet information services.
- i. Starting network device manager.
- j. Shutting down the network device manager.
- k. Action successful.

6. Database management software monitoring functions is to continuously read database information once operator has logged on.

7. Include operator notification through on-screen pop-up display and email message when database value has exceeded a warning or alarm limit.

8. Monitoring settings window with the following Sections:

- a. Allow operator to set and review scan intervals and start times.
- b. Email: Allow operator to create and review email and phone text messages to be delivered when a warning or an alarm is generated.
- c. Warning: Allow operator to define warning limit parameters, set reminder frequency, and link email message.
- d. Alarm: Allow operator to define alarm limit parameters, set reminder frequency, and link email message.
- e. Database Login: Protect system from unauthorized database manipulation by creating a read access and a write access for each of trend, alarm, event, and audit databases as well as operator proper security access to restore a database.

9. Monitoring settings taskbar with following informational icons:

- a. Normal: Indicates by color and size, or other easily identifiable means, that all databases are within their limits.
- b. Warning: Indicates by color and size, or other easily identifiable means, that one or more databases have exceeded their warning limit.
- c. Alarm: Indicates by color and size, or other easily identifiable means, that one or more databases have exceeded their alarm limit.

2.13 ANALYTICS SOFTWARE

A. Scope: Incorporate analytics software into DDC System:

1. Licensing, without Recurring Cost: No re-occurring cost for licensing and subscriptions.

2. Licensing: With or without re-occurring cost for licensing and subscriptions.

- a. For products with re-occurring costs, provide incremental costs broken down over a 10-year operating period that begins at Final Acceptance.
- b. Setup service agreements direct to Owner.

3. Purpose: Analyze energy and operational data to identify faults and opportunities for improved performance and reduced energy use.

4. Verification: Verify that HVAC systems and associated sequence of operations are executing as specified or as described on Drawings, through the analysis of energy and operational data, identification of faults showing where control sequences are not functioning as prescribed, and identification of opportunities for improved performance in the operation of systems.

B. Use during Project Life:

1. During Construction: Use for verification of performance during startup, commissioning, and final acceptance of DDC system.
2. During Warranty Period: Use for continuous operational tuning of DDC system and verification of operation and designed to identify warranty issues preemptively, thus reducing failures and potential down time.
3. After Warranty Period: Use to diagnose ongoing operational degradation and for Owner to perform continuous monitoring-based commissioning.

C. Minimum Features and Capabilities:

1. Operating Systems: Current version of Windows-based operating systems.
2. Time Series Database: Database technology, designed for efficient storage and analysis of large volumes of time series data, using tagging to model and describe data; supports an open-source tagging standard.
3. Data Import: Ability to accept and normalize data from a variety of sources including SQL compatible databases, CSV format files, XML format files or web services, and other EDI techniques. Once imported, software is to provide a unified data format to enable analytics algorithms to identify patterns across different data sets.
4. Open Interfaces: Open, REST-based APIs to enable integration with third-party software applications. Open APIs are to enable data to be entered/imported into database, exported from database, posting of analytic queries, and output of analytic results. APIs are to be fully documented and available as part of standard product.
5. Host: Local deployed on DDC system network.
6. Weather Data Service: Built-in worldwide weather service providing weather data including, but not limited to, the following:
 - a. Current temperature.
 - b. High temperature for the day.
 - c. Low temperature for the day.
 - d. Sunrise and sunset times.
 - e. Relative humidity.
 - f. Degree days (heating and cooling with adjustable balance point value).
 - g. Seven-day forecast.
 - h. Historical weather data extending back at least one year.
7. Email Notification: Automatic notification of detected issues via email including, but not limited to, the following:
 - a. Immediate notification of detected issues.
 - b. Daily digest or summary of detected issues.
 - c. Ability to delineate which notifications are sent to which recipients down to the level of specifying individual issues sent to individual recipients.

D. Hardware Requirements:

1. Host on a server in a virtual environment complying with Owner's security requirements.
2. Comply with standard software and hardware profiles required by Owner.

E. Analytic Rules:

1. Custom Rule Development: Develop customized rules and algorithms tailored to operational needs and characteristics of individual facilities and needs of monitoring and verification project and fault-detection requirements of Project without depending on manufacturer for rule development. Provide tools for user development and full documentation.
2. Standard Analytic Functions: Library of standard analytic functions is to use these standard analytic functions as elements to build custom analytic rules for specific needs of individual facilities.
3. Existing library of not less than 200 standard analytic rules written for applications similar to those required for this Project.

F. Reporting:

1. Standard Views of Analytic Results: Standard views to present analytic results, automatically generated when issues are found by analytic rules including, but not limited to, the following:
 - a. Rules violations across a portfolio of sites, rules violations per site, including time, date, and duration of all violations.
 - b. Ability to assign cost relationships to rule logic to provide cost per violation.
 - c. Standard filters to enable operator to easily look at rule violations by site, data, and violation type for any selected date or date range.
 - d. Automatic calculation and presentation of Key Performance Indicators (KPIs) and to define custom KPIs as needed.
2. Custom Views of Analytic Results:
 - a. Any standard system view is to be able to be saved as a custom report including its configuration criteria, e.g., time range, sites, rule violations, or other configuration options as applicable to standard system view.
 - b. Created by making queries against the database and saving the query as a saved report executed by single mouse click.
 - c. Export: Support report views export into CSV, Excel, XML, and HTML format, accomplished in a couple of mouse clicks.

G. Energy-Specific Reporting and Information Presentation Tools:

1. Greenhouse Gas Analysis: Energy/carbon dioxide relationships; easily changed and added without involvement of software manufacturer.
2. Energy Baseline: Quantify and define energy consumption and demand baselines (including weather normalization metrics) and compare actual and forecasted energy demand and consumption against those baselines.
3. Benchmarking: Multisite benchmarking to compare energy consumption and demand profiles and baselines across all buildings within Owner's portfolio.
4. Forecasting: Forecast near-future loads by using historic trends and forecasted weather data.
5. Financial Analysis: Calculate costs based on energy consumption and demand and energy costs and associate costs with any faults discovered by any analytic function and perform model- or tariff-based calculations to determine costs.
6. Tracking of Key Performance Indicators: Definition and tracking of user-defined key performance indicators/operational metrics. Examples include energy demand and consumption normalized for area and weather, peak demand, and consumption shown with minimum and maximum ranges across any user-selectable period.

7. Correlation of Energy Use with Equipment Operation: Automatically present views showing correlation between energy demand and consumption and operation of loads associated with that usage. Include the following:

- a. All submeters and virtual meters.
- b. Weather data as a selectable item.

H. Implementation:

1. Apply analytic rules to all HVAC systems and equipment monitored and controlled by DDC system. To extent available, use a subset of rules in existing rules library.
2. Implement rules to aid in determining proper operation of any HVAC system with a programmed sequence of operation.
3. Generate reports to aid in verification of proper operation during initial system startup and commissioning to supplement (not replace) commissioning agent reports.
4. Prepare quarterly reports summarizing faults detected and KPIs, including recommended corrective action.

I. Training:

1. Train Owner sufficiently to use software without need for external support.

2.14 MAINTENANCE MANAGEMENT SOFTWARE

A. Scope:

1. Include complete and functional software-driven maintenance management system to perform scheduling of preventive maintenance and generation of work orders, for mechanical and electrical equipment and systems, and other equipment and systems indicated.
2. Automatically generate work orders from alarm conditions, run time, and calendar time. For each work order generated, list parts, tools, and craftspeople and define task to be performed.
3. Use work orders generated to schedule a repair or preventive maintenance routine.
4. Use work orders to track completion of work, parts used, and total cost of repair.
5. Include a database inventory tracking system to automatically update inventory database to show quantity of tools, repair parts, and expendables used for a work order.
6. Print work orders and preventive maintenance schedules on a printer assigned solely to maintenance management function.

B. Additional Hardware Requirements:

1. Maintenance management software is to not require additional hardware, except for an additional printer that is dedicated to maintenance management.

C. Integration: Integrate maintenance management software into DDC system.

D. Software Requirements:

1. From main menu of maintenance management system, use selection of icons to penetrate to individual functions described below.

2. Work Orders:

- a. Automatically generate work orders initiated from alarm conditions, accumulated run time, or calendar time. Work orders generated are to specify a particular task to be accomplished including labor, material, and tools needed to accomplish work.
- b. Include at least two of the following types of work orders:
 - 1) Corrective and Emergency Maintenance: Generate for a specific job or repair for emergency, breakdown, or scheduled work.
 - 2) Preventive Maintenance: Use on a periodic basis to generate preventive maintenance work orders.
- c. Include the following functions:
 - 1) Work Order Tracking: Perform every function related to processing work orders including creating, approving and initiating work orders, checking their status history, and closing or reworking them when appropriate.
 - 2) Work Requests: Report any problems that require corrective maintenance activity generated by dispatchers and those people designated to request work orders.
 - 3) Quick Reporting: Report work done on an open work order or a small job.
 - 4) Work Manager: Specify type of labor to be applied to a specific work order at specific times. Include capability to dispatch one or more laborers to top-priority jobs on as-needed basis and to interrupt work in progress to reassign labor to higher priority tasks.
- d. Reports:
 - 1) Daily Maintenance Schedule by Supervisor: List a schedule of open work orders for a specified date by supervisor.
 - 2) Equipment Cost Roll-up Report: Include a roll-up of equipment costs incurred since the date the report was last run.
 - 3) Delinquent Work Order Report: List open work orders whose target completion date is earlier than the date the report is run.
 - 4) Employee Job Assignments: List labor codes that have job assignments for specified date.
 - 5) Daily Work Order Assignment: List work orders that have labor assignments for specified date.
 - 6) Estimated versus Actual Work Order Costs: List a cost summary of outstanding work orders.
 - 7) Open Work Orders Report: List open work orders for locations and equipment.

3. Inventory:

- a. Include an inventory tracking system to keep track of stocked, non-stocked, and special-order items.
- b. Link inventory tracking to database and when items are consumed, as noted on a work order issued by system, and automatically update inventory of stocked items.
- c. Include the following functions:

- 1) Inventory Control: Enter, display, and update information on each inventory item. Allow viewing of master inventory records that are independent of storeroom locations or item/location records. Include a screen that lists inventory transactions that move items in or out of inventory or from one storeroom location to another. Minimum information tracked is to include the following:
 - a) Vendors supply items.
 - b) Item balances, including the bin and lot level for each storeroom location.
 - c) Alternative items.
- 2) Issues and Transfers: Issue stock directly from inventory, with or without a work order. When transfer of stock from one location to another location occurs, provide appropriate adjustments in stock balance record. Include a trace record of stock transfers from one storeroom to another.
- 3) Item Assembly Structures: Include modeling of equipment with inventory items and building of equipment and location hierarchies.
- 4) Metered Material Usage:
 - a) Track usage by a piece of equipment.
 - b) Record against a standing work order for a selected piece of equipment.
 - c) Include a material usage transaction for each item of material used and provide as an input to calculation for per unit material consumption report for a piece of equipment.

d. Reports:

- 1) Inventory Analysis Report: List for a given storeroom location, inventory items analysis information that allows quick identification of which inventory items represent greatest monetary investment for dollar value and rate of turnover.
- 2) Inventory Cycle Count Report: List for a specified storeroom, inventory items that are due to be cycle-counted, based on cycle-count frequency and last count date.
- 3) Economic Order Quantity Report: For a given storeroom location, display optimum economic ordering quantity for items in selected results set.
- 4) Inventory Pick Report: A pick list, by work order for items needed to be pulled from a designated storeroom's inventory for work orders having a target start date of specified date.
- 5) Suggested Order Report: List inventory items in selected results set that are due to be recorded, for a specified storeroom location, based on the following calculation: Suggest a reorder if current balance minus reserve quantity plus on-order quantity is less than reorder point.
- 6) Reorder Point Report: List selected set of items and optimum minimum level to have in stock based on demand, lead delivery time, and a reserve safety stock.
- 7) Inventory Valuation Report: Gives an accounting of cost of current inventory, for inventory records in a designated storeroom location.
- 8) Item Order Status: Lists items on order.

- 9) List of Expired Items: Lists expired lot items in a storeroom. Report is to include item number, description, expiration date, bin number, lot number, manufacturer lot number, and quantity of expired items in that lot and bin.
- 10) Item Availability at All Locations: Lists alternative storeroom locations for selected items.
- 11) Where Used Report: List equipment on which item is recorded as being used.

4. Equipment:

- a. Include equipment and location records; establish relationships between equipment, between locations, and between equipment and locations; track maintenance costs; and enter and review meter readings.
- b. Include the following functions:
 - 1) Equipment: Store equipment numbers and corresponding information including equipment class, location, vendor, up/down status, and maintenance costs for each piece of equipment. Include building of equipment assemblies. Provide equipment assemblies hierarchical ordering for arrangement of buildings, departments, equipment, and sub-assemblies.
 - 2) Operating Locations: Facilitate creation of records for operating locations of equipment, and track equipment that is used in multiple locations. In addition, allow hierarchical organization of equipment operating in facility by means of grouping equipment locations into areas of responsibility.
 - 3) Failure Codes: Develop and display failure hierarchies to acquire an accurate history of types of failures that affect equipment and operating locations.
 - 4) Condition Monitoring: Display time-related or limit measurements recorded for a piece of equipment. Generate work orders from this screen and to take immediate action on problem conditions.
- c. Reports:
 - 1) Availability Statistic by Location: List equipment availability by location over a user-specified period.
 - 2) Equipment Failure Summary: List total number of failures by problem code for a piece of equipment for specified period.
 - 3) Detailed Equipment Failure Report by Equipment: List of failure reports for the current piece of equipment for specified period.
 - 4) Equipment Hierarchy Report: List of equipment.
 - 5) Equipment History Graphs: Include a graphical report in histogram format that displays equipment breakdown history over a specified period.
 - 6) Equipment Measurement Report: Tabular listing and description of each measurement point for a piece of equipment and history of measurements taken for that point.
 - 7) Maintenance Cost by Equipment: List of transactions costs for elected equipment in the specified date range.
 - 8) Failure Count by Equipment: Graphically report number of failures for each piece of equipment showing number of failures for each piece of equipment over a specified period, occurrence of each problem code within set of failures, and failures by problem code.

- 9) Failure Analysis Graphs: Graphically report number of failures for each piece of equipment over a specified period, number of occurrences of each problem code within set of failures, and failures by problem code.
- 10) Failure Code Hierarchy Report: List of failure codes in each level of failure hierarchy.
- 11) Location Failure Summary: A summary for each selected location of failures reported and any hierarchy level locations for specified period.
- 12) Failure Summary by Location: A summary of failures for selected location and their subordinate locations that are part of hierarchical system.
- 13) Detailed Failure Report by Location: List all failures for selected location and its subordinate locations that are part of hierarchical system.
- 14) Maintenance Cost by System: List of total costs reported in a given date range for locations in selected hierarchical system.
- 15) Location Hierarchy Report: Lists member locations of hierarchical system displayed in hierarchical fashion.

5. Purchasing:

- a. Include preparation and generation of purchase requisitions and purchase orders; to report receipt of both items and services, match invoices with purchase orders and receipts and define and convert foreign currencies.
- b. Include the following functions:
 - 1) Purchase Requisition: Create and process purchase requisitions for items and services.
 - 2) Purchase Orders: Create and process purchase orders for items and services from scratch or from purchase requisitions. Record receipts of items and services.
 - 3) Invoices: Include functionality to match purchase orders with invoices and receipts. It is also possible to match a service receipt to an invoice. Project for entering of an invoice for bills that do not require purchase orders or receipts.
 - 4) Currency Management: Define currencies and specify exchange rates. Include preparation of purchase requisitions and purchase orders in currency of vendor while tracking costs in systems base currency.
- c. Reports:
 - 1) Invoice Approval Report: Include an approval form for entered invoices.
 - 2) Inventory Receipts Register: List purchase orders and inventory received for user-specified time frame.
 - 3) Direct Purchase Back-Order Report: List of items ordered as a direct purchase not received by required delivery date.
 - 4) Standard Purchase Order: A printing of primary purchase order with vendors shipping information, and items purchased.
 - 5) Purchase Order Status Report: List of purchase orders whose status has changed during a certain period.
 - 6) Standard Purchase Requisition: A printing of primary purchase requisition, including vendor name and shipping information.

6. Job Plans:

- a. Include creation of a detailed description of work to be performed by work order. Job plan is to contain operations, procedures and list of estimated material, labor, and tools required for work.

7.Labor:

- a. Store information on employees, contractors, and crafts and include the following functions:
 - 1) Labor: Create, modify, and view employee records. Employee records are to contain pay rate, overtime worked, overtime refused, specials skills, and certifications.
 - 2) Crafts: Create, modify, and view craftspeople records.
 - 3) Labor Reporting: Report labor usage by employee or craft externally from work orders module.
- b. Reports:
 - 1) Employee Attendance Analysis: List of planned attendance, actual attendance, and vacation and sick time in hours as a percentage of planned attendance for selected employees for specified period.
 - 2) Labor Productivity Analysis: List of actual labor hours by labor report category showing each by percentage.
 - 3) Labor Availability versus Commitments by Crafts: A graphical report that details available labor hours versus committed work order hours by craft and day.

8.Calendars:

- a. Establish calendar records indicating working time for equipment, location, craft, and labor records.

9.Resources:

- a. Include entry and retrieval of data associated with resources required to maintain facility and to include the following functions:
 - 1) Companies: Establish and update data on vendors and other companies.
 - 2) Tools: Create and maintain information on the tools used on jobs. Make information contained within this module available to job plans and work orders.
 - 3) Service Contracts: Specify information on service contracts with vendors or manufacturers.

10. Custom Applications:

- a. Include creation of customized database tables and application screens that supplement functions specified.

11. Setup:

- a. Include configuration of database, security, and setup applications.
- b. Perform the following functions:
 - 1) Reports and Other Applications: Register reports and other applications for use within system.
 - 2) Documents: Enter, track, and link information from Drawings to equipment and inventory items.
 - 3) Chart of Accounts: Add or modify accounts; set up financial periods; enter inventory accounts, company accounts, and resource recovery accounts; and define tax codes and rates.
 - 4) Signature Security: Establish each user's access rights to modules, applications, screens, and options.
 - 5) Database Configuration: Customize database, including adjusting field lengths and modifying data types.
 - 6) Application Setup: Change position of icons and menu items on the main menu screen.
 - 7) Application Launching: Allow for connecting of third-party applications to data fields and push buttons.

12. Utilities:

- a. Include utilities module that allows system administrator to customize system and to maintain database.
- b. Include the following functions:
 - 1) Interactive SQL: Include access to database for database management functions of import/export and backup.
 - 2) Edit Windows: Display a dialog box to customize an application.
 - 3) Archive Data: Remove records from database and store them for future reference.

E. Documentation:

1. Include complete documentation for system consisting of a User Manual and Systems Administrator Guide.
2. Describe how to use each application module and screen with step-by-step instructions detailing entry and retrieval of data for functions specified.
3. Include a step-by-step description of how each report is defined and retrieved.
4. Bind documentation and clearly title it indicating volume number and use.

2.15 OFFICE APPLICATION SOFTWARE

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Microsoft Corporation.

- B. Include current version of office application software at time of Final Acceptance.

- C. Office application software package to include multiple separate applications and use a common platform for all applications.
 - 1.Database.
 - 2.Email.
 - 3.Presentation.
 - 4.Publishing.
 - 5.Spreadsheets.
 - 6.Word processing.

2.16 ASHRAE 135 GATEWAYS

- A. Include BACnet communication ports, whenever available as an equipment OEM standard option, for integration via a single communication cable.
- B. Include gateways to connect BACnet to legacy systems where indicated, existing non-BACnet devices, and existing non-BACnet DDC-controlled equipment.
- C. Include with each gateway an interoperability schedule showing each point or event on legacy side that BACnet "client" will read, and each parameter that BACnet network will write to. Describe this interoperability of BACnet services, or BIBBs, defined in ASHRAE 135, Annex K.
- D. Gateway Minimum Requirements:
 - 1.Read and view all readable object properties on non-BACnet network to BACnet network, and vice versa, where applicable.
 - 2.Write to all writable object properties on non-BACnet network from BACnet network, and vice versa, where applicable.
 - 3.Include single-pass (only one protocol to BACnet without intermediary protocols) translation from non-BACnet protocol to BACnet, and vice versa.
 - 4.Comply with requirements of Data Sharing Read Property, Data Sharing Write Property, Device Management Dynamic Device Binding-B, and Device Management Communication Control BIBBs in accordance with ASHRAE 135.
 - 5.Hardware, software, software licenses, and configuration tools for operator-to-gateway communications.
 - 6.Backup programming and parameters on CD media with ability to modify, download, backup, and restore gateway configuration.

2.17 ASHRAE 135 PROTOCOL ANALYZER

- A. Analyzer and required cables and fittings for connection to ASHRAE 135 network.
- B. Include the following minimum capabilities:
 - 1.Capture and store to a file data traffic on all network levels.
 - 2.Measure bandwidth usage.
 - 3.Filtering options with ability to ignore select traffic.

2.18 CTA-709.1-D NETWORK HARDWARE

A. Routers:

1. Network routers, including routers configured as repeaters, are to comply with requirements of CTA-709.1-D and include connection between two or more CTA-709.3 TP/FT-10 channels or between two or more CTA-709.3 TP/FT-10 channels and a TP/XF-1250 channel.

2. IP Routers:

- a. Perform layer three routing of CTA-709.1-D packets over an IP network in accordance with CTA-852-C.
- b. Include appropriate connection to IP network and connections to CTA-709.3 TP/FT-10 or TP/XF-1250 network.
- c. Support the Dynamic Host Configuration Protocol for IP configuration and use of an CTA-852-C Configuration Server (for CTA-852-C configuration), but do not rely on these services for configuration.
- d. Capable of manual configuration via a console RS-232 port.

B. Gateways:

1. Perform bidirectional protocol translation from one non-CTA-709.1-D protocol to CTA-709.1-D.
2. Incorporate a network connection to TP/FT-10 network in accordance with CTA-709.3 and a connection for non-CTA-709.1-D network.

2.19 WIRELESS ROUTERS FOR OPERATOR INTERFACE

A. Dual-Band Wireless Routers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. ASUSTek Computer Inc.
- b. Cisco Linksys.
- c. D-Link Corporation/D-Link Systems, Inc.
- d. NETGEAR Inc.

2. Description: High-speed, dual-band router with integral Ethernet ports and USB port.

3. Technology: IEEE 802.11; 2.4 and 5 GHz speed bands.

4. Wireless Speed: Up to 300 Mbps on 2.4 GHz band and up to 2400 Mbps on 5 GHz band.

5. Compatibility: IEEE 802.11 ac wireless devices.

6. Ethernet Ports: Four, gigabit (1000 Mbps).

7. USB Port: One, USB 2.0 or 3.0.

8. Wireless Security: Wi-Fi Protected Access (WPA) and WPA2 in accordance with IEEE 802.11.

B. Tri-Band Wireless Routers:

- 1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ASUSTek Computer Inc.
 - b. Cisco Linksys.
 - c. NETGEAR Inc.
- 2.Description: High-speed, tri-band router with integral Ethernet ports and USB port.
- 3.Technology: IEEE 802.11; 2.4 and 5 GHz speed bands.
- 4.Wireless Speed: Up to 600 Mbps on 2.4 GHz band and up to 4800 Mbps on two 5 GHz bands.
- 5.Compatibility: IEEE 802.11 ac or ax wireless devices.
- 6.Ethernet Ports: Four, gigabit 1000 Mbps.
- 7.USB Port: One, USB 2.0 or 3.0.
- 8.Wireless Security: Wi-Fi Protected Access (WPA) and WPA2 in accordance with IEEE 802.11.

2.20 DDC CONTROLLERS

- A. DDC system consisting of a combination of network controllers, programmable application controllers, and application-specific controllers to satisfy performance requirements indicated.
- B. DDC controllers to perform monitoring, control, energy optimization, and other requirements indicated.
- C. DDC controllers are to use a multitasking, multiuser, real-time digital control microprocessor with a distributed network database and intelligence.
- D. Each DDC controller is capable of full and complete operation as a completely independent unit and as a part of DDC system wide distributed network.
- E. Environment Requirements:
 - 1.Controller hardware suitable for anticipated ambient conditions.
 - 2.Controllers located in conditioned space rated for operation at 32 to 120 deg F.
 - 3.Controllers located outdoors rated for operation at 40 to 150 deg F.
- F. Power and Noise Immunity:
 - 1.Operate controller at 90 to 110 percent of nominal voltage rating and perform an orderly shutdown below 80 percent of nominal voltage.
 - 2.Protect against electrical noise of 5 to 120 Hz and from keyed radios with up to 5 W of power located within 36 inches of enclosure.
- G. DDC Controller Spare Processing Capacity:
 - 1.Include spare processing memory for each controller. RAM, PROM, or EEPROM will implement requirements indicated with the following spare memory:
 - a. Network Controllers: 60 percent.

- b. Programmable Application Controllers: Not less than 70 percent.
- c. Application-Specific Controllers: Not less than 80 percent.

2.Memory for DDC controller's operating system and database are to include the following:

- a. Monitoring and control.
- b. Energy management, operation, and optimization applications.
- c. Alarm management.
- d. Historical trend data of all connected I/O points.
- e. Maintenance applications.
- f. Operator interfaces.
- g. Monitoring of manual overrides.

H. DDC Controller Spare I/O Point Capacity: Include spare I/O point capacity for each controller as follows:

1.Network Controllers:

- a. 10 percent of each AI, AO, BI, and BO point connected to controller.
- b. Minimum Spare I/O Points per Controller:
 - 1) AIs: Two.
 - 2) AOs: Two.
 - 3) BIs: Three.
 - 4) BOs: Three.
 - 5) Option to provide universal I/O to meet spare requirements.

2.Programmable Application Controllers:

- a. 10 percent of each AI, AO, BI, and BO point connected to controller.
- b. Minimum Spare I/O Points per Controller:
 - 1) AIs: Two.
 - 2) AOs: Two.
 - 3) BIs: Three.
 - 4) BOs: Three.
 - 5) Option to provide universal I/O to meet spare requirements.

3.Application-Specific Controllers:

- a. 10 percent of each AI, AO, BI, and BO point connected to controller.
- b. Minimum Spare I/O Points per Controller:
 - 1) AIs: One.
 - 2) AOs: One.
 - 3) BIs: One.
 - 4) BOs: One.
 - 5) Option to provide universal I/O to meet spare requirements.

I. Maintenance and Support: Include the following features to facilitate maintenance and support:

1. Mount microprocessor components on circuit cards for ease of removal and replacement.
2. Means to quickly and easily disconnect controller from network.
3. Means to quickly and easily access connect to field test equipment.
4. Visual indication that controller electric power is on, of communication fault or trouble, and that controller is receiving and sending signals to network.

J. General Requirements for CTA-709.1-D DDC Controllers:

1. LonMark certified.
2. Distinguishable and accessible switch, button, or pin, when pressed is to broadcast its 48-bit Node ID and Program ID over network.
3. TP/FT-10 transceiver in accordance with CTA-709.3 and connections for TP/FT-10 control network wiring.
4. TP/XF-1250 transceiver in accordance with CTA-709.3 and connections for TP/XF-1250 control network wiring.
5. Communicate using CTA-709.1-D protocol.
6. Controllers configured into subnets, as required, to comply with performance requirements indicated.
7. Network communication through LNS network management and database standard for CTA-709.1-D network devices.
8. Locally powered, not powered through network connection.
9. Functionality required to support applications indicated including, but not limited to, the following:
 - a. I/Os indicated and as required to support sequence of operation and application in which it is used. SNVTs to have meaningful names identifying the value represented by SNVT. Unless SNVT of an appropriate engineering type is unavailable, all network variables to be of SNVT with engineering units appropriate to value the variable represents.
 - b. Configurable through SCPTs defined in LonMark SCPT List, operator-defined UCPTs, network configuration inputs (NCIs) of SNVT type defined in LonMark SNVT List, NCIs of an operator-defined network variable type, or hardware settings on controller itself for all settings and parameters used by application in which it is used.
10. Programmable controllers comply with "LonMark Interoperability Guidelines" and have LonMark certification.

K. I/O Point Interface:

1. Connect hardwired I/O points to network, programmable application, and application-specific controllers.
2. Protect I/O points so shorting of point to itself, to another point, or to ground will not damage controller.
3. Protect I/O points from voltage up to 24 V of any duration so that contact will not damage controller.
4. AIs:
 - a. Include monitoring of low-voltage (0 to 10 V dc), current (4 to 20 mA) and resistance signals from thermistor and RTD sensors.
 - b. Compatible with, and field configurable to, sensor and transmitters installed.

- c. Perform analog-to-digital (A-to-D) conversion with a minimum resolution of 12 bits or better to comply with accuracy requirements indicated.
- d. Signal conditioning including transient rejection for each AI.
- e. Capable of being individually calibrated for zero and span.
- f. Incorporate common-mode noise rejection of at least 50 dB from 0 to 100 Hz for differential inputs, and normal-mode noise rejection of at least 20 dB at 60 Hz from a source impedance of 10000 ohms.
- g. External conversion resistors are not permitted.

5.AOs:

- a. Perform analog-to-digital (A-to-D) conversion with a minimum resolution of 12 bits or better to comply with accuracy requirements indicated.
- b. Output signals range of 4 to 20 mA dc or 0 to 10 V dc as required to include proper control of output device.
- c. Capable of being individually calibrated for zero and span.
- d. Drift is to be not greater than 0.4 percent of range per year.
- e. External conversion resistors are not permitted.

6.BIs:

- a. Accept contact closures and ignore transients of less than 5 ms duration.
- b. Isolate and protect against an applied steady-state voltage of up to 180 V ac peak.
- c. Include a wetting current of at least 12 mA to be compatible with commonly available control devices and protected against effects of contact bounce and noise.
- d. Sense "dry contact" closure without external power (other than that provided by controller) being applied.
- e. Pulse accumulation input points complying with all requirements of BIs and accept up to 10 pulses per second for pulse accumulation. Include buffer to totalize pulses. Pulse accumulator is to accept rates of at least 20 pulses per second. Reset the totalized value to zero on operator's command.

7.BOs:

- a. Include relay contact closures or triac outputs for momentary and maintained operation of output devices.
 - 1) Relay contact closures to have a minimum duration of 0.1 second and at least 180 V of isolation.
 - 2) Include electromagnetic interference suppression on all output lines to limit transients to non-damaging levels.
 - 3) Minimum contact rating to be 1 A at 24 V ac.
 - 4) Triac outputs to have at least 180 V of isolation and minimum contact rating of 1 A at 24 V ac.
- b. Include BOs with two-state operation or a pulsed low-voltage signal for pulse-width modulation control.
- c. BOs to be selectable for either normally open or normally closed operation.
- d. Include tristate outputs (two coordinated BOs) for control of three-point, floating-type electronic actuators without feedback.

- e. Limit use of three-point floating devices to VAV terminal unit control applications, and other applications indicated on Drawings. Control algorithms to operate actuator to one end of its stroke once every 24 hours for verification of operator tracking.

2.21 NETWORK CONTROLLERS

A. General:

1. Include adequate number of controllers to achieve performance indicated.
2. Provide one or more independent, standalone, microprocessor-based network controllers to manage global strategies indicated.
3. Include enough memory to support its operating system, database, and programming requirements with spare memory indicated.
4. Share data between networked controllers and other network devices.
5. Operating system of controller to manage I/O communication signals to allow distributed controllers to share real and virtual object information and allow for central monitoring and alarms.
6. Include network controllers with a real-time clock.
7. Controller to continually check status of its processor and memory circuits. If an abnormal operation is detected, controller is to assume a predetermined failure mode and generate an alarm notification.
8. Make controllers fully programmable.

B. Communication:

1. Network controllers communicate with other devices on DDC system Level 1 network.
2. Network controller to also perform routing if connected to network of programmable application controllers and application-specific controllers.

C. Operator Interface:

1. Local Keypad and Display:

- a. Equip controller with local keypad and digital display for interrogating and editing data.
- b. Use of keypad and display requires a security password.

D. Serviceability:

1. Equip controller with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
2. Connect wiring and cable connections to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
3. Maintain Basic Input Output System (BIOS) and programming information in event of power loss for at least 72 hours.

2.22 PROGRAMMABLE APPLICATION CONTROLLERS

A. General:

1. Include adequate number of controllers to achieve performance indicated.
2. Provide enough memory to support its operating system, database, and programming requirements with spare memory indicated.
3. Share data between networked controllers and other network devices.
4. Include controller with operating system to manage I/O communication signals to allow distributed controllers to share real and virtual object information and allow for central monitoring and alarms.
5. Include controllers that perform scheduling with a real-time clock.
6. Controller is to continually check status of its processor and memory circuits. If an abnormal operation is detected, controller assumes a predetermined failure mode and generates an alarm notification.
7. Fully programmable.

B. Communication:

1. Programmable application controllers are to communicate with other devices on network.

C. Operator Interface:

1. Local Keypad and Display:
 - a. Equip controller with local keypad and digital display for interrogating and editing data.
 - b. Protect use of keypad and display by security password.

D. Serviceability:

1. Equip controller with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
2. Connect wiring and cable connections to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
3. Maintain BIOS and programming information in event of power loss for at least 72 hours.

2.23 APPLICATION-SPECIFIC CONTROLLERS

A. Description: Microprocessor-based controllers, which through hardware or firmware design are dedicated to control a specific piece of equipment or system. Controllers are not fully user-programmable but are configurable and customizable for operation of equipment they are designed to control.

1. Capable of standalone operation and continued control functions without being connected to network.
2. Share data between networked controllers and other network devices.

B. Communication: Application-specific controllers are to communicate with other application-specific controllers and devices on network, and to programmable application controllers and network controllers.

C. Serviceability:

1. Equip controller with diagnostic LEDs or other form of local visual indication of power, communication, and processor.
2. Connect wiring and cable connections to field-removable, modular terminal strips or to a termination card connected by a ribbon cable.
3. Use nonvolatile memory and maintain all BIOS and programming information in event of power loss.

2.24 CONTROLLER SOFTWARE

A. General:

1. Software applications are to reside and operate in controllers. Edit applications through operator workstations.
2. Identify I/O points by up to 30-character point name and up to 16-character point descriptor. Use same names throughout, including at operator workstations.
3. Execute control functions within controllers using DDC algorithms.
4. Configure controllers to use stored default values to ensure fail-safe operation. Use default values when there is a failure of a connected input instrument or loss of communication of a global point value.

B. Security:

1. Secure operator access using individual security passwords and user names.
2. Passwords restrict operator to points, applications, and system functions as assigned by system manager.
3. Record operator log-on and log-off attempts.
4. Protect from unauthorized use by automatically logging off after last keystroke. Make the delay time operator-definable.

C. Scheduling: Include capability to schedule each point or group of points in system. Each schedule is to consist of the following:

1. Weekly Schedules:

- a. Include separate schedules for each day of week.
- b. Each schedule should include capability for start, stop, optimal start, optimal stop, and night economizer.
- c. Each schedule may consist of up to 10 events.
- d. When a group of objects are scheduled together, include capability to adjust start and stop times for each member.

2. Exception Schedules:

- a. Include ability for operator to designate any day of the year as an exception schedule.
- b. Exception schedules may be defined up to a year in advance. Once an exception schedule is executed, it will be discarded and replaced by regular schedule for that day of week.

3. Holiday Schedules:

- a. Include capability for operator to define up to 99 special or holiday schedules.
- b. Place schedules on scheduling calendar with ability to repeated each year.
- c. Operator able to define length of each holiday period.

D. System Coordination:

1. Include standard application for proper coordination of equipment.
2. Include operator with a method of grouping together equipment based on function and location.
3. Include groups that may be for use in scheduling and other applications.

E. Binary Alarms:

1. Set each binary point to alarm based on operator-specified state.
2. Include capability to automatically and manually disable alarming.

F. Analog Alarms:

1. Provide each analog object with both high and low alarm limits.
2. Include capability to automatically and manually disable alarming.

G. Alarm Reporting:

1. Include ability for operators to determine action to be taken in event of an alarm.
2. Route alarms to appropriate operator workstations based on time and other conditions.
3. Include ability for alarms to start programs, print, be logged in event logs, generate custom messages, and display graphics.

H. Remote Communication:

1. Include ability for system to notify operators by phone message, text message, and email in event of an alarm.

I. Electric Power Demand Limiting:

1. Monitor building or other operator-defined electric power consumption from signals connected to electric power meter or from a watt transducer or current transformer.
2. Predict probable power demand such that action can be taken to prevent exceeding demand limit. When demand prediction exceeds demand limit, action will be taken to reduce loads in a predetermined manner. When demand prediction indicates demand limit will not be exceeded, action will be taken to restore loads in a predetermined manner.
3. Accomplish demand reduction by the following means:
 - a. Reset air-handling-unit supply temperature set points.
 - b. Reset space temperature set points.
 - c. De-energize equipment based on priority.

4. Base demand-limiting parameters, frequency of calculations, time intervals, and other relevant variables on the means by which electric power service provider computes demand charges.
5. Include demand-limiting prediction and control for any individual meter monitored by system or for total of any combination of meters.
6. Include means operator to make the following changes online:
 - a. Addition and deletion of loads controlled.
 - b. Changes in demand intervals.
 - c. Changes in demand limit for meter(s).
 - d. Maximum shutoff time for equipment.
 - e. Minimum shutoff time for equipment.
 - f. Select rotational or sequential shedding and restoring.
 - g. Shed and restore priority.
7. Include the following information and reports, to be available on an hourly, daily, weekly, monthly, and annual basis:
 - a. Total electric consumption.
 - b. Peak demand.
 - c. Date and time of peak demand.
 - d. Daily peak demand.
- J. Maintenance Management: Monitor equipment status and generate maintenance messages based on operator-designated run-time, starts, and calendar date limits.
- K. Sequencing: Include application software based on sequences of operation indicated to properly sequence and other applicable HVAC equipment.
- L. Control Loops:
 1. Support any of the following control loops, as applicable to control required:
 - a. Two-position (on/off, open/close, slow/fast) control.
 - b. Proportional control.
 - c. Proportional plus integral (PI) control.
 - d. Proportional plus integral plus derivative (PID) control.
 - 1) Include PID algorithms with direct or reverse action and anti-windup.
 - 2) Algorithm to calculate a time-varying analog value used to position an output or stage a series of outputs.
 - 3) Make controlled variable, set point, and PID gains operator-selectable.
 - e. Adaptive (automatic tuning).
- M. Staggered Start: Prevent all controlled equipment from simultaneously restarting after a power outage. Make the order which equipment (or groups of equipment) is started, along with the time delay between starts, operator-selectable.
- N. Energy Calculations:

1. Include software to allow instantaneous power or flow rates to be accumulated and converted to energy usage data.
2. Include algorithm that calculates a sliding-window average (rolling average). Make algorithm flexible to allow window intervals to be operator specified (such as 15, 30, or 60 minutes).
3. Include algorithm that calculates a fixed-window average. Use a digital input signal to define start of window period (such as signal from utility meter) to synchronize fixed-window average with that used by utility.

O. Anti-Short Cycling:

1. Protect BO points from short cycling.
2. Feature to allow minimum on-time and off-time to be selected.

P. On and Off Control with Differential:

1. Include algorithm that allows BO to be cycled based on a controlled variable and set point.
2. Use direct- or reverse-acting algorithm and incorporate an adjustable differential.

Q. Run-Time Totalization:

1. Include software to totalize run-times for all BI and BO points.
2. Assign a high run-time alarm, if required, by operator.

2.25 ENCLOSURES

A. General:

1. House each controller and associated control accessories in single enclosure. Enclosure is to serve as central tie-in point for control devices such as switches, transmitters, transducers, power supplies, and transformers.
2. Do not house more than one controller in single enclosure.
3. Include enclosure door with key locking mechanism. Key locks alike for all enclosures and include one pair of keys per enclosure.
4. Equip doors of enclosures housing controllers and components with analog or digital displays with windows to allow visual observation of displays without opening enclosure door.
5. Individual, wall-mounted, single-door enclosures maximum of 36 inches wide and 48 inches high.
6. Individual, wall-mounted, double-door enclosures maximum of 60 inches wide and 36 inches high.
7. Freestanding enclosures maximum of 48 inches wide and 72 inches high.
8. Include wall-mounted enclosures with brackets suitable for mounting enclosures to wall or freestanding support stand as indicated.
9. Supply each enclosure with complete set of as-built schematics, tubing, and wiring diagrams and product literature located in pocket on inside of door. For enclosures with windows, include pocket on bottom of enclosure.

B. Internal Arrangement:

1. Arrange internal layout of enclosure to group and protect electric, and electronic components associated with controller, but not an integral part of controller.
2. Arrange layout to group similar products together.
3. Include a barrier between line-voltage and low-voltage electrical and electronic products.
4. Factory or shop install products, tubing, cabling, and wiring complying with requirements and standards indicated.
5. Terminate field cable and wire using heavy-duty terminal blocks.
6. Include spare terminals, equal to not less than 10 percent of used terminals.
7. Include spade lugs for stranded cable and wire.
8. Install maximum of two wires on each side of terminal.
9. Include enclosure field electric power supply with toggle-type switch located at entrance inside enclosure to disconnect power.
10. Include enclosure with line-voltage nominal 20 A GFCI duplex receptacle for service and testing tools. Wire receptacle on hot side of enclosure disconnect switch and include with 5 A circuit breaker.
11. Mount products within enclosure on removable internal panel(s).
12. Include products mounted in enclosures with engraved, laminated phenolic nameplates (black letters on a white background). Nameplates are to have at least 1/4-inch- high lettering.
13. Route tubing cable and wire located inside enclosure within a raceway with continuous removable cover.
14. Label each end of cable, wire, and tubing in enclosure following an approved identification system that extends from field I/O connection and all intermediate connections throughout length to controller connection.
15. Size enclosure internal panel to include at least 15 percent spare area on face of panel.

C. Environmental Requirements:

1. Evaluate temperature and humidity requirements of each product to be installed within each enclosure.
2. Calculate enclosure internal operating temperature considering heat dissipation of all products installed within enclosure and ambient effects (solar, conduction, and wind) on enclosure.
3. Where required by application, include temperature-controlled electrical heat to maintain inside of enclosure above minimum operating temperature of product with most stringent requirement.
4. Where required by application, include temperature-controlled ventilation fans with filtered louver(s) to maintain inside of enclosure below maximum operating temperature of product with most stringent requirement.
5. Include temperature-controlled cooling within the enclosure for applications where ventilation fans cannot maintain inside temperature of enclosure below maximum operating temperature of product with most stringent requirement.
6. Where required by application, include humidity-controlled electric dehumidifier or cooling to maintain inside of enclosure below maximum relative humidity of product with most stringent requirement and to prevent surface condensation within enclosure.

D. Wall-Mounted, NEMA 250, Type 1:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. B-Line; a division of Eaton, Electrical Sector.
 - b. Hammond Mfg. Co. Inc.
 - c. Hoffman; brand of nVent Electrical plc.
 - d. Saginaw Control and Engineering.
- 2.NRTL listed in accordance with UL 50 or UL 50E.
- 3.Construct enclosure of steel, not less than the following:
- a. Enclosure Size Less Than 24 Inches (600 mm): 0.053 inch or 0.067 inch thick.
 - b. Enclosure Size 24 Inches (600 mm) and Larger: 0.067 inch or 0.093 inch thick.
- 4.Finish enclosure inside and out with polyester powder coating that is electrostatically applied and then baked to bond to substrate.
- a. Exterior Color: Manufacturer's standard.
 - b. Interior Color: Manufacturer's standard.
- 5.Hinged door full size of front face of enclosure and supported using the following:
- a. Enclosures Sizes Less Than 36 Inches (900 mm) Tall: Multiple butt hinges.
 - b. Enclosures Sizes 36 Inches (900 mm) Tall and Larger: Continuous piano hinges.
- 6.Removable internal panel with white or gray polyester powder coating that is electrostatically applied and then baked to bond to substrate.
- a. Size Less Than 24 Inches (600 mm): Solid or perforated] steel, 0.053 inch thick.
 - b. Size 24 Inches (600 mm) and Larger: Solid aluminum, 0.10 inch or steel, 0.093 inch thick.
- 7.Internal panel mounting hardware, grounding hardware, and sealing washers.
- 8.Grounding stud on enclosure body.
- 9.Thermoplastic pocket on inside of door for record Drawings and Product Data.
- E. Wall-Mounted, NEMA 250, Types 4 and 12:
- 1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-Line; a division of Eaton, Electrical Sector.
 - b. Hammond Mfg. Co. Inc.
 - c. Hoffman; brand of nVent Electrical plc.
 - d. Saginaw Control and Engineering.
 - 2.NRTL listed in accordance with UL 508A.
 - 3.Seam and joints are continuously welded and ground smooth.
 - 4.Where recessed enclosures are indicated, include enclosures with face flange for flush mounting.
 - 5.Externally formed body flange around perimeter of enclosure face for continuous perimeter seamless gasket door seal.
 - 6.Single-door enclosure sizes up to 60 inches tall by 36 inches wide.
 - 7.Double-door enclosure sizes up to 36 inches tall by 60 inches wide.

8. Construct enclosure of steel, not less than the following:
 - a. Size Less Than 24 Inches (600 mm): 0.053 inch or 0.067 inch thick.
 - b. Size 24 Inches (600 mm) and Larger: 0.067 inch thick.
 9. Finish enclosure with polyester powder coating that is electrostatically applied and then baked to bond to substrate.
 - a. Exterior Color: Manufacturer's standard.
 - b. Interior Color: Manufacturer's standard.
 10. Corner-formed door, full size of enclosure face, supported using multiple concealed hinges with easily removable hinge pins.
 - a. Sizes through 24 Inches (600 mm) Tall: Two hinges.
 - b. Sizes between 24 Inches (600 mm) through 48 Inches (1200 mm) Tall: Three hinges.
 - c. Sizes Larger Than 48 Inches (1200 mm) Tall: Four hinges.
 11. Double-door enclosures with overlapping door design to include unobstructed full-width access.
 - a. Single-door enclosures 48 inches and taller, and all double-door enclosures, with three-point (top, middle and bottom) latch system.
 12. Removable internal panel with white or gray polyester powder coating that is electrostatically applied and then baked to bond to substrate.
 - a. Size Less Than 24 Inches (600 mm): Solid or perforated steel, 0.053 inch thick.
 - b. Size 24 Inches (600 mm) and Larger: Solid aluminum, 0.10 inch or steel, 0.093 inch thick.
 13. Internal panel mounting studs with hardware, grounding hardware, and sealing washers.
 14. Grounding stud on enclosure body.
 15. Thermoplastic pocket on inside of door for record Drawings and Product Data.
- F. Wall-Mounted, NEMA 250, Type 4X-SS:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Crouse-Hinds; brand of Eaton, Electrical Sector.
 - b. Hammond Mfg. Co. Inc.
 - c. Hoffman; brand of nVent Electrical plc.
 - d. Saginaw Control and Engineering.
 2. NRTL listed in accordance with UL 508A.
 3. Seams and joints are continuously welded and ground smooth.
 4. Externally formed body flange around perimeter of enclosure face for continuous perimeter seamless gasket door seal.
 5. Construct enclosure of Type 304 or Type 316L stainless steel, not less than the following:

- a. Size Less Than 24 Inches (600 mm): 0.053 inch thick.
 - b. Size 24 Inches (600 mm) and Larger: 0.067 inch thick.
6. Outside body and door of enclosure with brushed No. 4 finish.
 7. Corner-formed door, full size of enclosure face, supported using multiple concealed hinges with easily removable hinge pins.
 - a. Sizes through 24 Inches (600 mm) Tall: Two hinges.
 - b. Sizes between 24 Inches (600 mm) through 48 Inches (1200 mm) Tall: Three hinges.
 - c. Sizes Larger Than 48 Inches (1200 mm) Tall: Four hinges.
 8. Corner-formed door, full size of enclosure face, supported using continuous piano hinge full length of door.
 9. Doors fitted with three-point (top, middle, and bottom) latch system with single, heavy-duty, liquidtight, Type 304 or Type 316L stainless steel handle with integral locking mechanism.
 10. Removable internal panel of 0.093-inch stainless steel.
 11. Internal panel mounting studs and hardware, grounding hardware, and sealing washers.
 12. Install corrosion-resistant polyester vent drain in a stainless steel sleeve at bottom of enclosure.
 13. Include enclosure with stainless steel mounting brackets.
- G. Freestanding, NEMA 250, Type 1:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. B-Line; a division of Eaton, Electrical Sector.
 - b. Hammond Mfg. Co. Inc.
 - c. Hoffman; brand of nVent Electrical plc.
 - d. Saginaw Control and Engineering.
 2. NRTL listed in accordance with UL 508A.
 3. Seams and joints are continuously welded and ground smooth.
 4. Externally formed body flange around perimeter of enclosure face.
 5. Single-door enclosure sizes up to 84 inches tall by 36 inches wide.
 6. Double-door enclosure sizes up to 84 inches tall by 72 inches wide.
 7. Construct enclosure of steel, not less than 0.067 inch thick.
 8. Finish enclosure with polyester powder coating that is electrostatically applied and then baked to bond to substrate.
 - a. Exterior Color: Manufacturer's standard.
 - b. Interior Color: Manufacturer's standard.
 9. Corner-formed flush door, full size of enclosure face, supported using four concealed hinges with easily removable hinge pins.
 10. Double-door enclosures with overlapping door design to include unobstructed full-width access.
 11. Doors with three-point (top, middle, and bottom) latch system with single heavy-duty handle and integral locking mechanism.
 12. Removable back covers.

13. Removable solid steel internal panel, 0.093 inch thick, with white or gray polyester powder coating that is electrostatically applied and then baked to bond to substrate.
14. Internal panel mounting studs with hardware, grounding hardware, and sealing washers.
15. Grounding stud on enclosure body.
16. Thermoplastic pocket on inside of door for record Drawings and Product Data.
17. Nominal 4-inch- tall integral lifting base, not less than 0.123 inch thick, with predrilled holes for attachment to mounting surface.
18. Equip each top end of enclosure with lifting tabs, not less than 0.172 inch thick, or not less than two lifting eyes.
19. Internal rack-mount shelves and angles, as required by application.

H. Freestanding, NEMA 250, Types 4 and 12:

1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. B-Line; a division of Eaton, Electrical Sector.
- b. Hammond Mfg. Co. Inc.
- c. Hoffman; brand of nVent Electrical plc.
- d. Saginaw Control and Engineering.

2.NRTL listed in accordance with UL 508A.

3.Seams and joints are continuously welded and ground smooth.

4.Externally formed body flange around perimeter of enclosure face.

5.Type 12 Enclosure Sizes:

- a. Single-door enclosure sizes up to 90 inches tall by 36 inches wide.
- b. Double-door enclosure sizes up to 90 inches tall by 72 inches wide.

6.Type 4 Enclosure Sizes:

- a. Single-door enclosure sizes up to 72 inches tall by 36 inches wide.
- b. Double-door enclosure sizes larger than 36 inches wide.

7.Construct enclosure of steel, not less than 0.093 inch thick.

8.Finish enclosure with polyester powder coating that is electrostatically applied and then baked to bond to substrate.

- a. Exterior Color: Manufacturer's standard.
- b. Interior Color: Manufacturer's standard.

9.Corner-formed door with continuous perimeter oil-resistant gasket supported using continuous piano hinge full length of door.

10. Doors fitted with three-point (top, middle, and bottom) latch system with latching rod rollers and single, heavy-duty, oiltight handle with integral locking mechanism.

11. Removable solid steel internal panel, 0.093 inch thick, with white or gray polyester powder coating that is electrostatically applied and then baked to bond to substrate.

12. Internal panel mounting studs with hardware, grounding hardware, and sealing washers.

13. Grounding stud on enclosure body.

14. Thermoplastic pocket on inside of door for record Drawings and Product Data.

15. Equip top of enclosure with no fewer than two lifting eyes.

16. Internal rack-mount shelves and angles, as required by application.

I. Freestanding, NEMA 250, Type 4X-SS:

1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Crouse-Hinds; brand of Eaton, Electrical Sector.
- b. Hammond Mfg. Co. Inc.
- c. Hoffman; brand of nVent Electrical plc.
- d. Saginaw Control and Engineering.

2.NRTL listed in accordance with UL 508A.

3.Seams and joints are continuously welded and ground smooth.

4.Externally formed body flange around perimeter of enclosure face for continuous perimeter seamless gasket door seal.

5.Construct enclosure of Type 304 or Type 316L stainless steel, not less than the following:

- a. Size Less Than 24 Inches (600 mm): 0.053 inch thick.
- b. Size 24 Inches (600 mm) and Larger: 0.067 inch thick.

6.Outside enclosure and door of enclosure with brushed No. 4 finish.

7.Doors:

- a. Single-door enclosure sizes up to 36 inches wide.
- b. Double-door enclosure sizes larger than 36 inches wide.
- c. Corner-formed door(s) with continuous perimeter oil-resistant gasket, full size of enclosure face, supported using continuous piano hinge full length of door.
- d. Doors fitted with three-point (top, middle, and bottom) latch system with single, heavy-duty, liquidtight, Type 304 or Type 316L stainless steel handle with integral locking mechanism.

8.Removable internal panel of 0.093-inch stainless steel.

9.Internal panel mounting studs and hardware, grounding hardware, and sealing washers.

10. Install corrosion-resistant polyester vent drain in a stainless steel sleeve at bottom of enclosure.

11. Include enclosure with stainless steel mounting brackets.

12. Thermoplastic pocket on inside of door for record Drawings and Product Data.

13. Equip top of enclosure with no fewer than two lifting eyes.

14. Internal rack-mount shelves and angles, as required by application.

J. Accessories:

1.Electric Heater:

- a. Aluminum housing with brushed finish.
- b. Thermostatic control with adjustable set point from 0 to 100 deg F.
- c. Capacity: 100, 200, 400, and 800 W, as required by application.
- d. Fan draws cool air from bottom of enclosure and passes air across thermostat and heating elements before being released into enclosure cavity. Heated air is discharged through the top of heater.

2. Ventilation Fans, Filtered Intake, and Exhaust Grilles:

- a. Number and size of fans, filters, and grilles, as required by application.
- b. Compact cooling fans engineered for 50,000 hours of continuous operation without lubrication or service.
- c. Fans capable of being installed on any surface and in any position within enclosure for spot cooling or air circulation.
- d. Thermostatic control with adjustable set point from 32 to 140 deg F.
- e. Airflow Capacity at Zero Pressure:
 - 1) 4-Inch (100-mm) Fan: 100 cfm.
 - 2) 6-Inch (150-mm) Fan: 240 cfm.
 - 3) 10-Inch (250-mm) Fan: 560 cfm.
- f. Maximum operating temperature of 158 deg F.
- g. 4-inch fan thermally protected and provided with permanently lubricated ball-bearings.
- h. 6- and 10-inch fans with ball-bearing construction and split capacitor motors thermally protected to avoid premature failure.
- i. Dynamically balanced impellers molded from polycarbonate material.
- j. Fan furnished with power cord and polarized plug for power connection.
- k. Fan brackets, finger guards, and mounting hardware provided with fans to complete installation.
- l. Removable Intake and Exhaust Grilles: ABS plastic or stainless steel, of size to match fan size and suitable for NEMA 250, Types 1 and 12 enclosures.
- m. Filters for NEMA 250, Type 1 Enclosures: Washable foam or aluminum, of size to match intake grille.
- n. Filters for NEMA 250, Type 12 Enclosures: Disposable, of size to match intake grille.

3. Air Conditioner:

- a. Electric-powered, self-contained, air-conditioning unit specially designed for electrical enclosures to maintain temperature inside enclosure below ambient temperature outside enclosure.
- b. Thermostatic control with adjustable set point from 60 to 120 deg F.
- c. Enclosure side or top mounting with unit capacity, as required by application.
- d. Designed for closed-loop cooling with continuous operation in ambient environments up to 125 deg F.
- e. HFC refrigerant.
- f. Reusable and washable air filter.
- g. High-performance, industrial-grade, and high-efficiency fans.
- h. Furnished with power cord and polarized plug for power connection.
- i. Condensate management system with base pan side drain.
- j. Mounting hardware, gaskets, mounting template, and instruction manual furnished with unit.
- k. Outdoor units equipped with head pressure control for low ambient operation, compressor heater, coated condenser coil, and thermostat.

4. Thermoelectric Humidifier:

- a. ABS plastic enclosure.
- b. Capacity of 8 oz. of water per 24 hours.
- c. Built-in drain captures moisture and plastic hose directs moisture to outside enclosure through a drain.
- d. Controlled to maintain enclosure relative humidity at adjustable set point.
- e. Unit power supply is internally wired to enclosure electrical power source.

5. Framed Fixed Window Kit for NEMA 250, Types 4, 4X, and 12 Enclosures:

- a. 0.25-inch- thick, scratch-resistant acrylic or polycarbonate window mounted in a metal frame matching adjacent door material.
- b. Enclosure types, except NEMA 250 Type 1, to have continuous gasket material around perimeter of window and frame to provide watertight seal.
- c. Window kit to be factory or shop installed before shipment to Project.

6. Frameless Fixed Window Kit for NEMA 250, Type 1 Enclosures:

- a. 0.125-inch- thick, polycarbonate window mounted in enclosure door material.
- b. Window attached to door with screw fasteners and continuous strip of high-strength, double-sided tape around window perimeter.
- c. Window kit is factory or shop installed before shipment to Project.

7. Frame Fixed or Hinged Window Kit for NEMA 250, Types 1 and 12 Enclosures:

- a. 0.25-inch- thick, scratch-resistant acrylic or polycarbonate window mounted in a metal frame matching adjacent door material.
- b. Enclosure types, except NEMA 250 Type 1, to have continuous gasket material around perimeter of window and frame to provide watertight seal.
- c. Window kit to be factory or shop installed before shipment to Project.

8. Bar handle with keyed cylinder lock set.

2.26 RELAYS

A. General-Purpose Relays:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allen Bradley; by Rockwell Automation.
 - b. Eaton.
 - c. IDEC Corporation.
 - d. Omron Americas.
 - e. Siemens Industry, Inc., Building Technologies Division.
 - f. Square D; Schneider Electric USA.
2. NRTL listed.
3. Heavy-duty, electromechanical type; rated for at least 10 A at 250 V ac and 60 Hz.
4. SPDT, DPDT, or three-pole double-throw, as required by control application.

5. Plug-in-style relay with 8-pin octal or multiblade plug for DPDT relays and 11-pin octal or multiblade plug for three-pole double-throw relays.
6. Construct contacts of silver, silver alloy, or gold.
7. Enclose relay in a clear transparent polycarbonate dust-tight cover.
8. Include LED indication and push-to-test button to test manual operation of relay without power on coil.
9. Performance:
 - a. Mechanical Life: At least 10 million cycles.
 - b. Electrical Life: At least 100,000 cycles at rated load.
 - c. Pickup Time: 15 ms or less.
 - d. Dropout Time: 10 ms or less.
 - e. Pull-in Voltage: 85 percent of rated voltage.
 - f. Dropout Voltage: 50 percent of nominal rated voltage.
 - g. Power Consumption: 5 VA or less.
 - h. Ambient Operating Temperatures: Minus 40 to 115 deg F.
10. Equip relays with coil transient suppression to limit transients to non-damaging levels.
11. Plug each relay into industry-standard, 35 mm DIN rail socket. Plug all relays located in control panels into sockets that are mounted on a DIN rail.
12. Include relay socket with screw terminals. Mold into socket the coincident screw terminal numbers.

B. Multifunction Time-Delay Relays:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allen Bradley; by Rockwell Automation.
 - b. Eaton.
 - c. IDEC Corporation.
 - d. Omron Americas.
 - e. Siemens Industry, Inc., Building Technologies Division.
 - f. Square D; Schneider Electric USA.
2. NRTL listed.
3. Continuous-duty type, rated for at least 10 A at 240 V ac and 60 Hz.
4. Relay with up to 4 programmable functions to provide on/off delay, interval, and recycle timing functions.
5. Plug-in-style relay with either multi-pin or blade plug.
6. Construct contacts of silver, silver alloy, or gold.
7. Enclose relay in a dust-tight cover.
8. Include knob and dial scale for alternative digital interface for setting delay time.
9. Visual Status Indication: Power "On" and Output "On" status.
10. Performance:
 - a. Mechanical Life: At least 10 million cycles.
 - b. Electrical Life: At least 100,000 cycles at rated load.
 - c. Timing Ranges: Multiple ranges from 0.1 seconds to 100 minutes.
 - d. Repeatability: Within 2 percent.
 - e. Recycle Time: 45 ms.

- f. Minimum Pulse-Width Control: 50 ms.
 - g. Power Consumption: 5 VA or less.
 - h. Ambient Operating Temperatures: Minus 40 to 115 deg F.
- 11. Equip relays with transient suppression to limit transients to non-damaging levels.
 - 12. Plug each relay into industry-standard, 35 mm DIN rail socket. Plug all relays located in control panels into sockets that are mounted on a DIN rail.
 - 13. Include relay socket with screw terminals. Mold into socket the coincident screw terminal numbers.

C. Latching Relays:

- 1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allen Bradley; by Rockwell Automation.
 - b. Eaton.
 - c. IDEC Corporation.
 - d. Omron Americas.
 - e. Siemens Industry, Inc., Building Technologies Division.
 - f. Square D; Schneider Electric USA.
- 2.NRTL listed.
- 3.Continuous-duty type, rated for at least 10 A at 250 V ac and 60 Hz.
- 4.SPDT, DPDT, or three-pole double-throw, as required by control application.
- 5.Plug-in-style relay with either multi-pin or blade plug.
- 6.Construct contacts of silver, silver alloy, or gold.
- 7.Enclose relay in a clear transparent polycarbonate dust-tight cover.
- 8.Performance:
 - a. Mechanical Life: At least 10 million cycles.
 - b. Electrical Life: At least 100,000 cycles at rated load.
 - c. Pickup Time: 15 ms or less.
 - d. Dropout Time: 10 ms or less.
 - e. Pull-in Voltage: 85 percent of rated voltage.
 - f. Dropout Voltage: 50 percent of nominal rated voltage.
 - g. Power Consumption: 2 VA or less.
 - h. Ambient Operating Temperatures: Minus 40 to 115 deg F.
- 9.Equip relays with coil transient suppression to limit transients to non-damaging levels.
- 10. Plug each relay into industry-standard, 35 mm DIN rail socket. Plug all relays located in control panels into sockets that are mounted on a DIN rail.
- 11. Relay socket with screw terminals. Mold into socket the coincident screw terminal numbers.

D. Current Sensing Relays:

- 1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Eaton.

- b. Functional Devices Inc.
- c. NK Technologies.
- d. Square D; Schneider Electric USA.

- 2.NRTL listed.
- 3.Monitors ac current.
- 4.Independent adjustable controls for pickup and dropout current.
- 5.Energized when supply voltage is present and current is above pickup setting.
- 6.De-energizes when monitored current is below dropout current.
- 7.Dropout current is adjustable from 50 to 95 percent of pickup current.
- 8.Visual indication of contact status.
- 9.Include current transformer, if required for application.
- 10. House current sensing relay and current transformer if required in its own enclosure. Use NEMA 250, Type 1 or Type 12 enclosure for indoors applications and NEMA 250, Type 4 or Type 4X for outdoor applications.

E. Combination On-Off Status Sensor and On-Off Control Relays:

- 1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Functional Devices Inc.
 - b. Veris Industries.
- 2.Description:
 - a. On-off control and on-off status indication in a single device.
 - b. LED status indication of activated relay and current trigger.
 - c. Closed-Open-Auto override switch located on the load side of relay.
- 3.Performance:
 - a. Ambient Temperature: Minus 30 to 140 deg F.
 - b. Voltage Rating: Single-phase loads rated for 300 V ac. Three-phase loads rated for 600 V ac.
- 4.Status Indication:
 - a. Current Sensor: Integral sensing for single-phase loads up to 20 A and external solid or split sensing ring for three-phase loads up to 150 A.
 - b. Current Sensor Range: As required by application.
 - c. Current Set Point: Fixed or adjustable, as required by application.
 - d. Current Sensor Output:
 - 1) Solid-state, SPDT contact rated for 30 V ac and dc and for 0.4 A.
 - 2) Solid-state, SPDT contact rated for 120 V ac and 1.0 A.
 - 3) Analog, 0 to 5 or 10 V dc.
 - 4) Analog, 4 to 20 mA, loop powered.
- 5.Relay: SPDT, continuous-duty coil; rated for 10-million mechanical cycles.

6. Enclosure: NEMA 250, Type 12 enclosure for indoor applications; NEMA 250, Type 4X enclosure for outdoor applications.

2.27 ELECTRICAL POWER DEVICES

A. Control Transformers:

1. Sizing Criteria: Size control transformers for total connected load, plus additional 25 percent of connected load for future spare capacity.
2. Transformer Minimum Capacity: 40 VA.
3. Protection: Provide transformers with both primary and secondary fuses. Integral circuit breaker is acceptable in lieu of fuses.
4. Enclosure: House control transformers in NEMA 250 enclosures, type as indicated in "Performance Requirements" Article for application.

B. Power-Line Conditioners:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Eaton.
 - b. Emerson Electric Co., Automation Solutions.
 - c. SolaHD; Emerson Electric Co., Automation Solutions.
2. General Power-Line Conditioner Requirements:
 - a. Design to ensure maximum reliability, serviceability, and performance.
 - b. Overall function of power-line conditioner is to receive raw, polluted electrical power and purify it for use by electronic equipment. Power-line conditioner is to provide isolated, regulated, transient, and noise-free sinusoidal power to loads served.
3. Standards: NRTL listed per UL 1012.
4. Performance:
 - a. Single phase, continuous, 100 percent duty rated kVA/kW capacity. Design to supply power for linear or nonlinear, high crest factor, resistive and reactive loads.
 - b. Automatically regulate output voltage to within 2 percent or better with input voltage fluctuations of plus 10 to minus 20 percent of nominal when system is loaded 100 percent. Use Variable Range Regulation to obtain improved line voltage regulation when operating under less than full load conditions.
 - 1) At 75 Percent Load: Output voltage automatically regulated to within 3 percent with input voltage fluctuations of plus 10 to minus 35 percent of nominal.
 - 2) At 50 Percent Load: Output voltage automatically regulated to within 3 percent with input voltage fluctuations of plus 10 to minus 40 percent of nominal.
 - 3) At 25 Percent Load: Output voltage automatically regulated to within 3 percent with input voltage fluctuations of plus 10 to minus 45 percent of nominal.

- c. With input voltage distortion of up to 40 percent, limit the output voltage sine wave to maximum harmonic content of 5 percent.
- d. Automatically regulate output voltage to within 2.5 percent when load (resistive) changes from zero to 100 to zero percent.
- e. Output voltage returns to 95 percent of nominal level within two cycles and to 100 percent within three cycles when output is taken from no load to full-resistive load, or vice versa. Recovery from partial resistive load changes is corrected in a shorter period.
- f. K Factor: 30, designed to operate with nonlinear, non-sinusoidal, high crest factor loads without overheating.
- g. Input power factor within 0.95 approaching unity with load power factor as poor as 0.6.
- h. Attenuate load-generated odd current harmonics 23 dB at the input.
- i. Electrically isolate the primary from the secondary. Meet isolation criteria as defined in NFPA 70, Article 250-5D.
- j. Lighting and Surge Protection: Compares to UL 1449 rating of 330 V when subjected to Category B3 (6000 V/3000 A) combination waveform as established by IEEE C62.41.1 and IEEE C62.41.2.
- k. Common-mode noise attenuation of 140 dB.
- l. Transverse-mode noise attenuation of 120 dB.
- m. With loss of input power for up to 16.6 ms, output sine wave remains at usable ac voltage levels.
- n. Reliability of 200,000 hours' MTBF.
- o. At full load, when measured at 1 m distance, audible noise is not to exceed 54 dB.
- p. Approximately 92 percent efficient at full load.

5. Transformer Construction:

- a. Ferroresonant, dry type, convection cooled, 600 V class. Transformer windings of Class H (220 deg C) insulated copper.
- b. Use Class H installation system throughout with operating temperatures not to exceed 150 deg C over a 40 deg C ambient temperature.
- c. Configure transformer primary for multi-input voltage. Include input terminals for source conductors and ground.
- d. Manufacture transformer core using M-6 grade, grain-oriented, stress-relieved transformer steel.
- e. Configure transformer secondary in 240/120 V split with 208 V tap or straight 120 V, depending on power output size.
- f. Electrically isolate the transformer secondary windings from primary windings. Bond neutral conductor to cabinet enclosure and output neutral terminal.
- g. Include interface terminals for output power hot, neutral, and ground conductors.
- h. Label leads, wires, and terminals to correspond with circuit wiring diagram.
- i. Vacuum impregnate transformer with epoxy resin.

6. Cabinet Construction:

- a. Design for panel or floor mounting.
- b. NEMA 250, Type 1 or Type 2 enclosure for indoor applications. NEMA 250, Type 3R for outdoor applications.
- c. Manufacture the cabinet from heavy gauge steel complying with UL 50 or UL 508A.
- d. Include textured baked-on paint finish.

C. DC Power Supplies:

1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Acopian Technical Company.
- b. Emerson Electric Co., Automation Solutions.
- c. IDEC Corporation.
- d. Omron Americas.

2.Description: Linear or switched, regulated power supplies with ac input to one or multiple dc output(s).

- a. Include both line and load regulation to ensure stable output.
- b. To protect both power supply and load, include power supply with an automatic current limiting circuit.

3.Features:

- a. Connection: Plug-in style suitable for mating with standard 8-pin octal socket. Include power supply with mating mounting socket.
- b. Housing: Enclose circuitry in a housing.
- c. Local Adjustment: Include screw adjustment on exterior of housing for dc voltage output.
- d. Mounting: DIN rail.
- e. Visual status indicator.

4.Performance:

- a. Input Voltage: Nominally 120 V ac, 60 Hz.
- b. Output Voltage: Nominally 24 V dc with plus or minus 1 V dc adjustment.
- c. Output Current: Minimum 100 mA.
- d. Load Regulation: Within 0.1 percent.
- e. Line Regulation: Within 0.05 percent.
- f. Stability: Within 0.1 percent of rated volts after warmup period.
- g. Ripple: 1 mV rms.

2.28 UNINTERRUPTABLE POWER SUPPLY (UPS) UNITS

A. Furnish local UPS units, of type indicated, installed with DDC system.

B. DIN Rail Mounted UPS:

1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. APC by Schneider Electric.
- b. Emerson Electric Co., Automation Solutions.
- c. Phoenix Contact.

2. Provide continuous, regulated output power without using batteries during brown-out, surge, and spike conditions.

3. Performance:

- a. Capacity: Load not to exceed 75 percent of rated capacity.
- b. Efficiency: Minimum 94 percent.
- c. Input Voltage: Single phase, 120 V ac, compatible with field power source.
- d. Load Power Factor Range (Crest Factor): 0.65 to 1.0.
- e. Output Voltage: 101 to 132 V ac, while input voltage varies between 89 and 152 V ac.
- f. On Battery Output Voltage: Sine wave.
- g. Inverter Overload Capacity: Minimum 150 percent for 30 seconds.
- h. Battery Backup: 10 minutes of operation at full load with battery power.
- i. Battery Recharge Time: Maximum of six hours to 90 percent capacity after full discharge.
- j. Transfer Time: 6 ms.
- k. Surge Voltage Withstand Capacity: IEEE C62.41.1 and IEEE C62.41.2, Categories A and B.

4. Automatic bypass operation during fault or overload conditions.

5. Integral line-interactive, power condition topology to eliminate all power contaminants.

6. Include power switch and visual indication of power, battery, fault, and temperature.

7. Include audible alarm of faults with silence feature.

8. Include dry contacts (digital output points) for low battery condition and battery-on (primary utility power failure) and connect points to DDC system.

9. Batteries: Sealed; maintenance free; replacement without dropping load.

C. Tower UPS Models through 1000 VA:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. APC by Schneider Electric.
- b. Eaton.
- c. Toshiba International Corporation.

2. Provide continuous, regulated output power without using batteries during brown-out, surge, and spike conditions.

3. Performance:

- a. Capacity: Load not to exceed 75 percent of rated capacity.
- b. Efficiency: Complying with ENERGY STAR requirements; minimum 91 percent.
- c. Input Voltage: Single phase, 120 V ac, compatible with field power source.
- d. Load Power Factor Range (Crest Factor): 0.65 to 1.0.
- e. Output Voltage: 101 to 132 V ac, while input voltage varies between 89 and 152 V ac.
- f. On Battery Output Voltage: Sine wave.
- g. Inverter Overload Capacity: Minimum 150 percent for 30 seconds.
- h. Battery Backup: 10 minutes of operation at full load with battery power.
- i. Battery Recharge Time: Maximum of four hours to 90 percent capacity after full discharge to cutoff.

- j. Transfer Time: 0 ms.
- k. Surge Voltage Withstand Capacity: IEEE C62.41.1 and IEEE C62.41.2, Categories A and B; 6 kV/200 and 500 A; 100 kHz ring wave.

- 4. Automatic bypass operation during fault or overload conditions.
- 5. Integral line-interactive, power condition topology to eliminate all power contaminants.
- 6. Include power switch and visual indication of power, battery, fault, and temperature.
- 7. Include audible alarm of faults and front panel silence feature.
- 8. Receptacles: Minimum four, NEMA WD 1, NEMA WD 6 Configuration 5-15R receptacles.
- 9. Remote Alarms: Include dry contacts (digital output points) or serial communication interface for low battery condition and battery-on (primary utility power failure) and connect points to DDC system.
- 10. Batteries: Sealed type; maintenance free. Battery replacement is to be front accessible by user without dropping load.
- 11. Install tower models in enclosures rated for location.

D. UPS Models through 3000 VA: Tower and Rack.

- 1. Manufacturers: Subject to compliance with requirements, provide products by the following:

- a. APC by Schneider Electric.
- b. Eaton.
- c. Toshiba International Corporation.

- 2. NRTL Listing: UL 1778.

- 3. Provide continuous, regulated output power without using batteries during brown-out, surge, and spike conditions.

- 4. Performance:

- a. Capacity: Load not to exceed 75 percent of UPS rated capacity.
- b. Efficiency: Complying with ENERGY STAR requirements; minimum 91 percent.
- c. Input Voltage: Single phase, 120 V ac, plus 20 to minus 30 percent.
- d. Power Factor: Minimum 0.95 at full load.
- e. Output Voltage: Single phase, 120 V ac, within 2 percent.
- f. Inverter overload capacity to be minimum 150 percent for 30 seconds.
- g. Battery Backup: 10 minutes of operation at full load with battery power.
- h. Battery Recharge Time: Maximum of 6 hours to 90 percent capacity.
- i. Transfer Time: 0 ms.

- 5. LCD display with operator interface.

- 6. Receptacles: Minimum 6, NEMA WD 1, NEMA WD 6 Configuration 5-15R or 5-20R receptacles.

- 7. Automatic bypass operation during fault or overload conditions.

- 8. Remote Alarms: Include dry contacts (digital output points) or serial communication interface for low battery condition and battery-on (primary utility power failure) and connect points to DDC system.

- 9. Batteries: Sealed; maintenance free.

- 10. Enclosures: Install tower models in enclosures rated for location. Install rack models installed on matching racks, as applicable to particular installation location and space availability/configuration.

2.29 CONTROL WIRE AND CABLE

A. Wire: Single conductor control wiring above 24 V.

1. Wire Size: Minimum 16 AWG.
2. Conductors: 7/24 soft annealed copper strand with 2- to 2.5-inch lay.
3. Conductor Insulation: 600 V, Type THWN or Type THHN, and 90 deg C in accordance with UL 83.
4. Conductor Insulation Colors: Black (hot), white (neutral), and green (ground).
5. Furnish on spools.

B. Single, Twisted-Shielded, Instrumentation Cable above 24 V:

1. Wire Size: Minimum 20 AWG.
2. Conductors: Twisted, 7/24 soft annealed copper strand with a 2- to 2.5-inch lay.
3. Conductor Insulation: Type THHN/THWN or Type TFN rating.
4. Conductor Insulation Colors:
 - a. Twisted Pair: Black and white.
 - b. Twisted Triad: Black, red, and white.
5. Shielding: 100 percent type, 0.35/0.5-mil aluminum/Mylar tape, helically applied with 25 percent overlap, and aluminum side in with tinned copper drain wire.
6. Outer Jacket Insulation: 600 V, 90 deg C rating, and Type TC cable.
7. Furnish on spools.

C. Single, Twisted-Shielded, Instrumentation Cable 24 V and Less:

1. Wire Size: Minimum 20 AWG.
2. Conductors: Twisted, 7/24 soft annealed copper stranding with a 2- to 2.5-inch lay.
3. Conductor Insulation: Nominal 15-mil thickness, constructed from flame-retardant PVC.
4. Conductor Insulation Colors:
 - a. Twisted Pair: Black and white.
 - b. Twisted Triad: Black, red, and white.
5. Shielding: 100 percent type, 1.35-mil aluminum/polymer tape, helically applied with 25 percent overlap, and aluminum side in with tinned copper drain wire.
6. Outer Jacket Insulation: 300 V, 105 deg C rating, and Type PLTC cable.
7. Furnish on spools.

D. LAN and Communication Cable: Comply with DDC system manufacturer requirements for network being installed.

1. Comply with following requirements for balanced twisted pair cable described in Section 260523 "Control-Voltage Electrical Power Cables."
2.
 - a. Plenum rated.
 - b. Unique color that is different from other cables used on Project.

2.30 RACEWAYS

- A. Comply with requirements in Section 260533.13 "Conduits for Electrical Systems" and Section 260533.16 "Boxes and Covers for Electrical Systems" for electrical power raceways and boxes.
- B. Comply with requirements in Section 270528 "Pathways for Communications Systems" for raceways for balanced twisted pair cables and optical fiber cables.

2.31 OPTICAL FIBER CABLE AND CONNECTORS

- A. Comply with requirements in Section 271323 "Communications Optical Fiber Backbone Cabling" for optical fiber backbone cabling and connectors.
- B. Comply with requirements in Section 271523 "Communications Optical Fiber Horizontal Cabling" for optical fiber horizontal cabling and connectors.

2.32 ACCESSORIES

- A. Control Damper Blade Limit Switches:

- 1. Application: Sense positive open and/or closed position of damper blades.
- 2. NEMA 250, Type 13, oiltight construction. Install in instrument enclosure where required for additional environmental protection.
- 3. Arrange for mounting application, and to prevent "over-center" operation.

4. Industrial Grade:

- a. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - 1) ControlAir, Inc.
 - 2) Fischer; Emerson Electric Co., Automation Solutions.
 - 3) Marsh Bellofram.
- b. Description: Transducer converting an electronic current (I) or voltage (E) AO signal.
- c. Features:
 - 1) Adjustments: Separate zero and span calibration adjustments.
 - 2) Conduit Connections: Nominal 1/2 inch.
 - 3) Enclosure: NEMA 250, Type 4X.
 - 4) Pressure Gauge: Integral output pressure gauge.
- d. Performance:
 - 1) Accuracy: Within 0.5 percent of output span.
 - 2) Hysteresis: Within 0.5 percent of output span.
 - 3) Linearity: Within 0.5 percent of output span.
 - 4) Repeatability: Within 0.5 percent of output span.

- 5) Output Capacity: Not less than 5 scfm at 15 psig.
- 6) Air Consumption: Maximum of 5 scfh at 15 psig.
- 7) Ambient Temperature: Suitable for operation in ambient temperature range of minus 20 to 150 deg F.
- 8) Pressure: Up to 50 psig without damage.
- 9) Vibration: Construct entire assembly so shock and vibration will not harm transducer or affect accuracy.

e. Applications:

- 1) All applications, except for terminal units and other applications with commercial-grade transducers.

B. E/P Switch:

- 1.Body: Cast aluminum or brass; three pipe body (common, normally open, and normally closed).
- 2.Internal Components: Brass, copper, steel, or stainless steel.
- 3.Connections: Barb, or threaded for mating to compression fittings.
- 4.Rating: 30 psig when installed in systems below 25 psig; 150 psig when installed in systems above 25 psig.
- 5.Features: Include coil transient suppression.

C. Instrument Enclosures:

- 1.Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Hammond Mfg. Co. Inc.
 - b. Hoffman; brand of nVent Electrical plc.
 - c. Saginaw Control and Engineering.
- 2.Application: Include instrument enclosure for secondary protection to comply with requirements indicated in "Performance Requirements" Article.
- 3.Certification: NRTL listed and labeled to UL 50 or UL 508A as applicable.
- 4.Subpanel:
 - a. Size enclosure with least 25 percent spare area on subpanel.
 - b. Mount instrument(s) within enclosure on internal subpanel(s).
- 5.Identification: Include on face of enclosure an engraved, laminated phenolic nameplate for each instrument installed within enclosure.
- 6.Raceways: For enclosures housing multiple instruments, route tubing, cable, and wiring within enclosure in a raceway having continuous removable cover.
- 7.Access: Provide enclosures larger than 12 inches with hinged full-size face cover.
- 8.Security: Equip enclosures with lock and common key.

2.33 IDENTIFICATION

A. Instrument Air Pipe and Tubing:

1. Engraved tag bearing the following information:

- a. Service (Example): "Instrument Air."
- b. Pressure Range (Example): 0 to 30 psig.

2. Letter size minimum of 0.25 inch high.

3. Engraved phenolic consisting of three layers of rigid laminate. Top and bottom layers color-coded blue with contrasting white center exposed by engraving through outer layer.

4. Include tag with brass grommet, chain, and S-hook.

B. Control Equipment, Instruments, and Control Devices:

1. Self-adhesive label bearing unique identification.

- a. Include instruments with unique identification identified by equipment being controlled or monitored, followed by point identification.

2. Letter size as follows:

- a. Servers: Minimum of 0.5 inch high.
- b. DDC Controllers: Minimum of 0.5 inch high.
- c. Gateways: Minimum of 0.5 inch high.
- d. Repeaters: Minimum of 0.5 inch high.
- e. Enclosures: Minimum of 0.5 inch high.
- f. Electrical Power Devices: Minimum of 0.25 inch high.
- g. UPS units: Minimum of 0.5 inch high.
- h. Accessories: Minimum of 0.25 inch high.
- i. Instruments: Minimum of 0.25 inch high.
- j. Control Damper and Valve Actuators: Minimum of 0.25 inch high.

3. Engraved phenolic consisting of three layers of rigid laminate. Top and bottom layers color-coded black with contrasting white center exposed by engraving through outer layer.

4. Fastened with drive pins.

5. Instruments, control devices, and actuators with Project-specific identification tags having unique identification numbers following requirements indicated and provided by original manufacturer do not require additional identification.

C. Valve Tags:

1. Brass tags and brass chains attached to valve.

2. Tag Size: Minimum 1.5 inches in diameter.

3. Include tag with unique valve identification indicating control influence such as flow, level, pressure, or temperature; followed by location of valve, and followed by three-digit sequential number. For example: TV-1.001.

4. Valves with Project-specific identification tags having unique identification numbers following requirements indicated and provided by original manufacturer do not require an additional tag.

D. Raceway and Boxes:

1. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
2. Paint cover plates on junction boxes and conduit same color as tape banding for conduits. After painting, label cover plate "HVAC Controls" using engraved phenolic tag.

E. Equipment Warning Labels:

1. Self-adhesive label with pressure-sensitive adhesive back and peel-off protective jacket.
2. Lettering size at least 14-point type with white lettering on red background.
3. Warning label to read "CAUTION-Equipment operated under remote automatic control and may start or stop at any time without warning. Switch electric power disconnecting means to OFF position before servicing."
4. Lettering to be enclosed in a white line border. Edge of label is to extend at least 0.25 inch beyond white border.

2.34 SOURCE QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to evaluate the following in accordance with industry standards for each product, and to verify DDC system reliability specified in performance requirements:
1. DDC controllers.
 2. Gateways.
 3. Routers.
- B. Product(s) and material(s) will be considered defective if it does not pass tests and inspections.
- C. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
1. Verify compatibility with and suitability of substrates.
- B. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.
- C. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.
- D. Examine walls, floors, roofs, and ceilings for suitable conditions where product will be installed.
- E. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

- F. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 DDC SYSTEM INTERFACE WITH OTHER SYSTEMS AND EQUIPMENT

A. Communication Interface to Equipment with Integral Controls:

1.DDC system has communication interface with equipment having integral controls and having communication interface for remote monitoring or control.

2.Equipment to Be Connected:

- a. Domestic water heaters specified in Section 223300 "Electric, Domestic-Water Heaters" and Section 223400 "Fuel-Fired, Domestic-Water Heaters."
- b. Air-terminal units specified in Section 233600 "Air Terminal Units."
- c. Roof-top units specified in Section 237416.11 "Packaged, Small-Capacity, Rooftop Air-Conditioning Units."
- d. Variable refrigerant flow units specified in Section 238129 "Variable-Refrigerant-Flow HVAC Systems."
- e. Fan-coil units specified in Section 238219 "Fan Coil Units."
- f. Unit ventilators specified in Section 238223 "Unit Ventilators."
- g. Switchboards specified in Section 262300 "Low-Voltage Switchgear."
- h. Motor-control centers specified in Section 262419 "Motor-Control Centers."
- i. Variable-frequency controllers specified in Section 262923 "Variable-Frequency Motor Controllers."
- j. Diesel emergency engine generators specified in Section 263213.13 "Diesel-Engine-Driven Generator Sets."
- k. Bi-fuel emergency engine generators specified in Section 263213.19 "Bi-Fuel-Engine-Driven Generator Sets."
- l. UPS specified in Section 263353 "Static Uninterruptible Power Supply."

B. Communication Interface to Other Building Systems:

1.DDC system communicates with systems having communication interface.

2.Systems to Be Connected:

- a. Elevators specified in Section 142100 "Electric Traction Elevators."
- b. Elevators specified in Section 142113 "Electric Traction Freight Elevators."
- c. Elevators specified in Section 142400 "Hydraulic Elevators."
- d. Elevators specified in Section 142413 "Hydraulic Freight Elevators."
- e. Escalators specified in Section 143100 "Escalators."
- f. Automated water treatment systems specified in Section 232500 "HVAC Water Treatment."
- g. Automated water treatment systems specified in Section 232516 "Water Treatment for Open-Loop Hydronic Systems."
- h. Power monitoring specified in Section 260913 "Electrical Power Monitoring."
- i. Lighting controls specified in Section 260936 "Modular Dimming Controls."
- j. Lighting controls specified in Section 260943.16 "Addressable Luminaire Lighting Controls."
- k. Lighting controls specified in Section 260943.23 "Relay-Based Lighting Controls."
- l. Fire-alarm system specified in Section 284621.11 "Addressable Fire-Alarm Systems."

- m. Fire-alarm system specified in Section 284621.13 "Conventional Fire-Alarm Systems."
- n. Access controls specified in Section 281300 "Access Control System Software and Database Management."
- o. Intrusion detection specified in Section 283100 "Intrusion Detection."
- p. Perimeter security specified in Section 283121 "Area and Perimeter Intrusion Detection."

3.3 PREINSTALLATION INTEGRATION TESTING

- A. Perform the following pretesting of other systems and equipment integration with DDC system before field installation:
 - 1. Test all communications in a controlled environment to ensure connectivity.
 - 2. Load software and demonstrate functional compliance with each control sequence of operation indicated.
 - 3. Using simulation, demonstrate compliance with sequences of operation and other requirements indicated including, but not limited to, the following:
 - a. HVAC equipment controlled through DDC system, such as air-handling units.
 - b. Equipment faults and system recovery with fault annunciation.
 - c. Analog and Boolean value alarming and annunciation.
 - 4. Develop a method for testing interfaces before deployment.
 - 5. Submit documentation supporting compliance upon request.

3.4 DDC SYSTEM INTERFACE WITH EXISTING SYSTEMS

- A. Integration with Existing Enterprise System:
 - 1. Interface DDC system with an existing enterprise system to adhere to Owner standards already in-place and to achieve integration.
 - 2. Owner's control system integrator to provide the following services:
 - a. Enterprise system expansion and development of graphics, logs, reports, trends, and other operational capabilities of enterprise system for I/O being added to DDC control system for use by enterprise system operators.
 - b. Limited assistance during commissioning to extent of DDC system integration with existing enterprise system.
 - c. Prepare on-site demonstration mockup of integration of DDC system to be installed with existing system before installing DDC system.
 - 3. Engage Owner's control system integrator to provide the following services:
 - a. Enterprise system expansion and development of graphics, logs, reports, trends, and other operational capabilities of enterprise system for I/O being added to DDC control system for use by enterprise system operators.
 - b. Limited assistance during commissioning to extent of DDC system integration with existing enterprise system.

- c. Prepare on-site demonstration mockup of integration of DDC system to be installed with existing system before installing DDC system.

4. Attend meetings with control system integrator to integrate DDC system.

3.5 CONTROL DEVICES FOR INSTALLATION BY INSTALLERS

- A. Deliver selected control devices, specified in indicated HVAC instrumentation and control device Sections, to identified equipment and systems manufacturers for factory installation and to identified installers for field installation.
- B. Deliver the following to duct fabricator and Installer for installation in ductwork. Include installation instructions to Installer and supervise installation for compliance with requirements.
 1. Control dampers, which are specified in Section 230923.12 "Control Dampers."
 2. Airflow sensors and switches, which are specified in Section 230923.14 "Flow Instruments."
 3. Pressure sensors, which are specified in Section 230923.23 "Pressure Instruments."
- C. Deliver the following to plumbing and HVAC piping installers for installation in piping. Include installation instructions to Installer and supervise installation for compliance with requirements.
 1. Control valves, which are specified in Section 230923.11 "Control Valves."
 2. Pipe-mounted flow meters, which are specified in Section 230923.14 "Flow Instruments."
 3. Pipe-mounted sensors, switches, and transmitters. Flow meters are specified in Section 230923.14 "Flow Instruments."
 4. Tank-mounted sensors, switches, and transmitters. Pressure sensors, switches, and transmitters are specified in Section 230923.23 "Pressure Instruments."

3.6 CONTROL DEVICES FOR EQUIPMENT MANUFACTURER FACTORY INSTALLATION

- A. Deliver the following to air-handling unit manufacturer for factory installation. Include installation instructions to air-handling unit manufacturer and supervise installation for compliance with requirements.
 1. Programmable application controller.
 2. Unit-mounted DDC control dampers and actuators, which are specified in Section 230923.12 "Control Dampers."
 3. Unit-mounted airflow sensors, switches, and transmitters, which are specified in Section 230923.14 "Flow Instruments."
 4. Unit-mounted leak-detection switches, which are specified in Section 230923.18 "Leak Detection Instruments."
 5. Unit-mounted pressure sensors, switches, and transmitters, which are specified in Section 230923.23 "Pressure Instruments."
 6. Unit-mounted speed sensors, switches, and transmitters, which are specified in Section 230923.24 "Speed Instruments."
 7. Unit-mounted temperature sensors, switches, and transmitters. Air-temperature sensors, switches, and transmitters are specified in Section 230923.27 "Temperature Instruments."
 8. Relays.

- B. Deliver the following to terminal unit manufacturer for factory installation. Include installation instructions to terminal unit manufacturer.
1. Programmable application controller.
 2. Electric damper actuator. Damper actuators are specified in Section 230923.12 "Control Dampers."
 3. Unit-mounted flow and pressure sensors, transmitters, and transducers. Flow sensors, transmitters, and transducers are specified in Section 230923.14 "Flow Instruments." Pressure sensors, switches, and transmitters are specified in Section 230923.23 "Pressure Instruments."
 4. Unit-mounted temperature sensors. Air-temperature sensors, switches, and transmitters are specified in Section 230923.27 "Temperature Instruments."
 5. Relays.
- C. Deliver the following to fan-coil unit manufacturer for factory installation. Include installation instructions to fan-coil unit manufacturer.
1. Programmable application controller.
 2. Unit-mounted temperature sensors. Air-temperature sensors, switches, and transmitters are specified in Section 230923.27 "Temperature Instruments."
 3. Flow and pressure switches. Air and liquid flow sensors, transmitters, and transducers are specified in Section 230923.14 "Flow Instruments." Pressure sensors, switches, and transmitters are specified in Section 230923.23 "Pressure Instruments."
 4. Relays.

3.7 GENERAL INSTALLATION REQUIREMENTS

- A. Install products to satisfy more stringent of all requirements indicated.
- B. Install products level, plumb, parallel, and perpendicular with building construction.
- C. Support products, tubing, piping wiring, and raceways. Brace products to prevent lateral movement and sway or a break in attachment when subjected to <Insert value> force.
- D. If codes and referenced standards are more stringent than requirements indicated, comply with requirements in codes and referenced standards.
- E. Fabricate openings and install sleeves in ceilings, floors, roof, and walls required by installation of products. Before proceeding with drilling, punching, and cutting, check for concealed work to avoid damage. Patch, flash, grout, seal, and refinish openings to match adjacent condition.
- F. Firestop Penetrations Made in Fire-Rated Assemblies: Comply with requirements in Section 078413 "Penetration Firestopping."
- G. Seal penetrations made in acoustically rated assemblies. Comply with requirements in Section 079200 "Joint Sealants."
- H. Welding Requirements:
1. Restrict welding and burning to supports and bracing.

- 2.No equipment is cut or welded without approval. Welding or cutting will not be approved if there is risk of damage to adjacent Work.
- 3.Welding, where approved, is to be by inert-gas electric arc process and is to be performed by qualified welders in accordance with applicable welding codes.
- 4.If requested on-site, show satisfactory evidence of welder certificates indicating ability to perform welding work intended.

I. Fastening Hardware:

- 1.Wrenches, pliers, and other tools that damage surfaces of rods, nuts, and other parts are prohibited for work of assembling and tightening fasteners.
- 2.Tighten bolts and nuts firmly and uniformly. Do not overstress threads by excessive force or by oversized wrenches.
- 3.Lubricate threads of bolts, nuts, and screws with graphite and oil before assembly.

- J. If product locations are not indicated, install products in locations that are accessible and that will permit service and maintenance from floor, equipment platforms, or catwalks without removal of permanently installed furniture and equipment.

3.8 INSTALLATION OF SERVERS

- A. Install server(s) at location(s) indicated on Drawings.
- B. Install number of servers required to suit requirements indicated. Review Project requirements and indicate layout of proposed server location in Shop Drawings.
- C. Install software indicated on server(s) and verify that software functions properly.
- D. Develop Project-specific graphics, trends, reports, logs, and historical database.
- E. Power servers through dedicated UPS unit. Locate UPS adjacent to server. Install rack-mounted UPS units for powering rack-mounted servers and tower UPS units for tower servers.

3.9 INSTALLATION OF PRINTERS

- A. Install Owner-furnished printers at location(s) indicated on Drawings.

3.10 INSTALLATION OF GATEWAYS

- A. Install gateways if required for DDC system communication interface requirements indicated.
 - 1.Install gateway(s) required to suit indicated requirements.
- B. Test gateways to verify that communication interface functions properly.

3.11 INSTALLATION OF ROUTERS

- A. Install routers if required for DDC system communication interface requirements indicated.

1. Install router(s) required to suit indicated requirements.

- B. Test routers to verify that communication interface functions properly.

3.12 INSTALLATION OF CONTROLLERS

- A. Install controllers in enclosures to comply with indicated requirements.

- B. Connect controllers to field power supply and to UPS units where indicated.

- C. Install controllers with latest version of applicable software and configure to execute requirements indicated.

- D. Test and adjust controllers to verify operation of connected I/O to achieve performance indicated requirements while executing sequences of operation.

- E. Installation of Network Controllers:

1. DDC system provider and DDC system manufacturer to determine quantity and location of network controllers to satisfy requirements indicated. Provide minimum quantity indicated.

2. Install controllers in a protected location that is easily accessible by operators.

3. Locate top of controller within 72 inches of finished floor.

- F. Installation of Programmable Application Controllers:

1. DDC system provider and DDC system manufacturer to determine quantity and location of programmable application controllers to satisfy requirements indicated. Provide minimum quantity indicated.

2. Install controllers in a protected location that is easily accessible by operators.

3. Locate top of controller within 72 inches of finished floor, except where dedicated controllers are installed at terminal units.

- G. Application-Specific Controllers:

1. DDC system provider and DDC system manufacturer to determine quantity and location of application-specific controllers to satisfy requirements indicated. Provide minimum quantity indicated.

2. For controllers not mounted directly on equipment being controlled, install controllers in a protected location that is easily accessible by operators.

3.13 INSTALLATION OF WIRELESS ROUTERS FOR OPERATOR INTERFACE

- A. Install wireless routers to achieve optimum performance and best possible coverage.

- B. Mount wireless routers in a protected location that is within 60 inches of floor and easily accessible by operators.

- C. Connect wireless routers to field power supply and to UPS units if network controllers are powered through UPS units.
- D. Install wireless router with latest version of applicable software and configure wireless router with security and password protection. Create access password with not less than 12 characters consisting of letters and numbers and at least one special character. Document password in operations and maintenance manuals for reference by operators.
- E. Test and adjust wireless routers for proper operation with all types (such as, laptops, smartphones, and tablets) of wireless devices intended for use by operators.

3.14 INSTALLATION OF ENCLOSURES

- A. Install the following items in enclosures, to comply with indicated requirements:
 - 1. Gateways.
 - 2. Routers.
 - 3. Controllers.
 - 4. Electrical power devices.
 - 5. UPS units.
 - 6. Relays.
 - 7. Accessories.
 - 8. Instruments.
 - 9. Actuators.
- B. Attach wall-mounted enclosures to wall using the following types of steel struts:
 - 1. For NEMA 250, Type 1 Enclosures: Use painted steel strut and hardware.
 - 2. For NEMA 250, Type 4 Enclosures and Enclosures Located Outdoors: Use stainless steel strut and hardware.
 - 3. Install plastic caps on exposed cut edges of strut.
- C. Align top or bottom of adjacent enclosures of like size.
- D. Install floor-mounted enclosures located in mechanical equipment rooms on concrete housekeeping pads. Attach enclosure legs using galvanized-steel or stainless steel anchors.
- E. Install continuous and fully accessible wireways to connect conduit, wire, and cable to multiple adjacent enclosures. Wireways used for application are to have protection equal to NEMA 250 rating of connected enclosures.

3.15 ELECTRIC POWER CONNECTIONS

- A. Connect electrical power to DDC system products requiring electrical power connections.
- B. Design of electrical power to products not indicated with electric power is delegated to DDC system provider and installing trade to provide a fully functioning DDC system. Work is to comply with NFPA 70 and other requirements indicated.

- C. Comply with requirements in Section 262816 "Enclosed Switches and Circuit Breakers" for electrical power circuit breakers.
- D. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for electrical power conductors and cables.
- E. Comply with requirements in Section 260533.13 "Conduits for Electrical Systems," Section 260533.16 "Boxes and Covers for Electrical Systems," and Section 260533.23 "Surface Raceways for Electrical Systems" for electrical power raceways and boxes.

3.16 INSTALLATION OF IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements in Section 260553 "Identification for Electrical Systems" for identification products and installation.
- B. Install self-adhesive labels with unique identification on face for each of the following:
 - 1. Server.
 - 2. Gateway.
 - 3. Router.
 - 4. Protocol analyzer.
 - 5. DDC controller.
 - 6. Enclosure.
 - 7. Electrical power device.
 - 8. UPS unit.
 - 9. Accessory.
- C. Install unique instrument identification for each instrument connected to DDC controller.
- D. Install unique identification for each control damper actuator connected to DDC controller.
- E. Where product is installed above accessible tile ceiling, also install matching identification on face of ceiling grid located directly below.
- F. Where product is installed above an inaccessible ceiling, also install identification on face of access door directly below.
- G. Warning Labels and Signs:
 - 1. Permanently attach to equipment that can be automatically started by DDC control system.
 - 2. Locate where highly visible near power service entry points.

3.17 INSTALLATION OF NETWORKS

- A. Install optical fiber cable when connecting between the following network devices and when located in different buildings on campus:
 - 1. Operator workstations.
 - 2. Operator workstations and network controllers.

3. Network controllers.
- B. Install balanced twisted pair or optical fiber cable when connecting between the following network devices:
 1. Operator workstations.
 2. Operator workstations and network controllers.
 3. Network controllers.
 - C. Install balanced twisted pair or copper cable (as required by equipment) when connecting between the following:
 1. Gateways.
 2. Gateways and network controllers or programmable application controllers.
 3. Routers.
 4. Routers and network controllers or programmable application controllers.
 5. Network controllers and programmable application controllers.
 6. Programmable application controllers.
 7. Programmable application controllers and application-specific controllers.
 8. Application-specific controllers.
 - D. Install cable in continuous raceway.
 1. Where indicated on Drawings, cable trays may be used for copper cable in lieu of conduit.

3.18 NETWORK NAMING AND NUMBERING

- A. Coordinate with Owner and provide unique naming and addressing for networks and devices.
- B. ASHRAE 135 Networks:
 1. MAC Address:
 - a. Assign and document a MAC address unique to its network for every network device.
 - b. Ethernet Networks: Document MAC address assigned at its creation.
 - c. MS/TP Networks: Assign from 00 to 64.
 2. Network Numbering:
 - a. Assign unique numbers to each new network.
 - b. Provide ability for changing network number through device switches or operator interface.
 - c. DDC system, with all possible connected LANs, can contain up to 65,534 unique networks.
 3. Device Object Identifier Property Number:
 - a. Assign unique device object identifier property numbers or device instances for each device network.

- b. Provide for future modification of device instance number by device switches or operator interface.
- c. LAN is to support up to 4,194,302 unique devices.

4. Device Object Name Property Text:

- a. Device object name property field to support 32 minimum printable characters.
- b. Assign unique device "Object Name" property names with plain-English descriptive names for each device.
 - 1) Example 1: Device object name for device controlling heating water boiler plant at Building 1000 would be "Heating Water System Bldg. 1000."
 - 2) Example 2: Device object name for VAV terminal unit controller could be "VAV Unit 102."

5. Object Name Property Text for Other Than Device Objects:

- a. Object name property field is to support 32 minimum printable characters.
- b. Assign object name properties with plain-English names descriptive of application.
 - 1) Example 1: "Zone 1 Temperature."
 - 2) Example 2 "Fan Start and Stop."

6. Object Identifier Property Number for Other Than Device Objects:

- a. Assign object identifier property numbers according to Drawings or tables indicated.
- b. If not indicated, object identifier property numbers may be assigned at Installer's discretion but must be approved by Owner in advance, be documented, and be unique for like object types within device.

3.19 INSTALLATION OF CONTROL WIRE, CABLE, AND RACEWAY

A. Comply with NECA 1.

B. Wire and Cable Installation:

1. Comply with installation requirements in Section 260523 "Control-Voltage Electrical Power Cables."
2. Comply with installation requirements in Section 271313 "Communications Copper Backbone Cabling."
3. Comply with installation requirements in Section 271513 "Communications Copper Horizontal Cabling."
4. Install cables with protective sheathing that is waterproof and capable of withstanding continuous temperatures of 90 deg C with no measurable effect on physical and electrical properties of cable.
 - a. Provide shielding to prevent interference and distortion from adjacent cables and equipment.
5. Terminate wiring in a junction box.

- a. Clamp cable over jacket in a junction box.
 - b. Individual conductors in the stripped section of cable is to be slack between the clamping point and terminal block.
6. Terminate field wiring and cable not directly connected to instruments and control devices having integral wiring terminals using terminal blocks.
 7. Install signal transmission components in accordance with IEEE C2, REA Form 511a, NFPA 70, and as indicated.
 8. Use shielded cable to transmitters.
 9. Use shielded cable to temperature sensors.
 10. Perform continuity and meager testing on wire and cable after installation.
- C. Conduit Installation:
1. Comply with Section 260533.13 "Conduits for Electrical Systems," Section 260533.16 "Boxes and Covers for Electrical Systems," and Section 260533.23 "Surface Raceways for Electrical Systems" for control-voltage conductors.
 2. Comply with Section 270528 "Pathways for Communications Systems" for balanced twisted pair cabling and optical fiber installation.

3.20 INSTALLATION OF OPTICAL FIBER CABLE SYSTEMS

- A. Comply with installation requirements in Section 271323 "Communications Optical Fiber Backbone Cabling."
- B. Comply with installation requirements in Section 271523 "Communications Optical Fiber Horizontal Cabling."

3.21 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and installations, including connections.
- C. Tests and Inspections: Perform the following tests and inspections with the assistance of a factory-authorized service representative:
 1. Perform each visual and mechanical inspection and electrical test stated in NETA ATS. Certify compliance with test parameters.
 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Optical Fiber Cable Testing:
 1. Perform preinstallation, in-progress, and final tests, supplemented by additional tests, as necessary.

2. Preinstallation Cable Verification: Verify integrity and serviceability for new cable lengths before installation. This assurance may be provided by using vendor verification documents, testing, or other methods. At a minimum, furnish evidence of verification for cable attenuation and bandwidth parameters.
3. In-Progress Testing: Perform standard tests for correct pair identification and termination during installation to ensure proper installation and cable placement. Perform tests in addition to those specified if there is any reason to question condition of material furnished and installed. Testing accomplished is to be documented by agency conducting tests. Submit test results for Project record.
4. Final Testing: Perform final test of installed system to demonstrate acceptability as installed. Perform testing according to test plan supplied by DDC system manufacturer. Correct defective Work or material and retest. At a minimum, final testing for cable system, including spare cable, to verify compliance of attenuation, length, and bandwidth parameters with performance indicated.
5. Test Equipment: Use optical fiber time-domain reflectometer for testing of length and optical connectivity.
6. Test Results: Record test results and submit copy of test results for Project record.

3.22 DDC SYSTEM I/O CHECKOUT PROCEDURES

- A. Check installed products before continuity tests, leak tests, and calibration.
- B. Check instruments for proper location and accessibility.
- C. Check instruments for proper installation on direction of flow, elevation, orientation, insertion depth, or other applicable considerations that will impact performance.
- D. Check instrument tubing for proper isolation, fittings, slope, dirt legs, drains, material, and support.
- E. Control Damper Checkout:
 1. Verify that control dampers are installed correctly for flow direction.
 2. Verify that proper blade alignment, either parallel or opposed, has been provided.
 3. Verify that damper frame attachment is properly secured and sealed.
 4. Verify that damper actuator and linkage attachment are secure.
 5. Verify that actuator wiring is complete, enclosed, and connected to correct power source.
 6. Verify that damper blade travel is unobstructed.
- F. Control Valve Checkout:
 1. Verify that control valves are installed correctly for flow direction.
 2. Verify that valve body attachment is properly secured and sealed.
 3. Verify that valve actuator and linkage attachment are secure.
 4. Verify that actuator wiring is complete, enclosed, and connected to correct power source.
 5. Verify that valve ball, disc, or plug travel is unobstructed.
 6. After piping systems have been tested and put into service, but before insulating and balancing, inspect each valve for leaks. Adjust or replace packing to stop leaks. Replace valve if leaks persist.

G. Instrument Checkout:

1. Verify that instrument is correctly installed for location, orientation, direction, and operating clearances.
2. Verify that attachment is properly secured and sealed.
3. Verify that conduit connections are properly secured and sealed.
4. Verify that wiring is properly labeled with unique identification, correct type, and size and is securely attached to proper terminals.
5. Inspect instrument tag against approved submittal.
6. For instruments with tubing connections, verify that tubing attachment is secure and isolation valves have been provided.
7. For flow instruments, verify that recommended upstream and downstream distances have been maintained.
8. For temperature instruments, verify the following:
 - a. Sensing element type and proper material.
 - b. Length and insertion.

3.23 DDC SYSTEM I/O ADJUSTMENT, CALIBRATION, AND TESTING

- A. Calibrate each instrument installed that is not factory calibrated and provided with calibration documentation.
- B. Provide written description of proposed field procedures and equipment for calibrating each type of instrument. Submit procedures before calibration and adjustment.
- C. For each analog instrument, make three-point test of calibration for both linearity and accuracy.
- D. Equipment and procedures used for calibration to comply with instrument manufacturer's written instructions.
- E. Provide diagnostic and test equipment for calibration and adjustment.
 1. Use field testing and diagnostic instruments and equipment with an accuracy at least twice the instrument accuracy of instrument to be calibrated. For example, test and calibrate an installed instrument with accuracy of 1 percent using field testing and diagnostic instrument with accuracy of 0.5 percent or better.
- F. Calibrate each instrument in accordance with instruction manual supplied by instrument manufacturer.
- G. If after calibration the indicated performance cannot be achieved, replace out-of-tolerance instruments.
- H. Comply with field testing requirements and procedures indicated by ASHRAE's Guideline 11, "Field Testing of HVAC Controls Components," in the absence of specific requirements, and to supplement requirements indicated.
- I. Analog Signals:

1. Check analog voltage signals using a precision voltage meter at zero, 50, and 100 percent.
2. Check analog current signals using a precision current meter at zero, 50, and 100 percent.
3. Check resistance signals for temperature sensors at zero, 50, and 100 percent of operating span using a precision-resistant source.

J. Digital Signals:

1. Check digital signals using a jumper wire.
2. Check digital signals using an ohmmeter to test for contact making or breaking.

K. Control Dampers:

1. Stroke and adjust control dampers following manufacturer's recommended procedure, from 100 percent open to 100 percent closed and back to 100 percent open.
2. Check and document open and close cycle times for applications with cycle time less than 30 seconds.
3. For control dampers equipped with positive position indication, check feedback signal at multiple positions to confirm proper position indication.

L. Control Valves:

1. Stroke and adjust control valves following manufacturer's recommended procedure, from 100 percent open to 100 percent closed and back to 100 percent open.
2. Check and document open and close cycle times for applications with cycle time less than 30 seconds.
3. For control valves equipped with positive position indication, check feedback signal at multiple positions to confirm proper position indication.

M. Meters: Check meters at zero, 50, and 100 percent of Project design values.

N. Sensors: Check sensors at zero, 50, and 100 percent of Project design values.

O. Switches: Calibrate switches to make or break contact at set points indicated.

P. Transmitters:

1. Check and calibrate transmitters at zero, 50, and 100 percent of Project design values.
2. Calibrate resistance temperature transmitters at zero, 50, and 100 percent of span using a precision-resistant source.

3.24 DDC SYSTEM CONTROLLER CHECKOUT

A. Verify power supply.

1. Verify voltage, phase, and hertz.
2. Verify that protection from power surges is installed and functioning.
3. Verify that ground fault protection is installed.
4. If applicable, verify if connected to UPS unit.
5. If applicable, verify if connected to backup power source.
6. If applicable, verify that power conditioning units are installed.

- B. Verify that wire and cabling are properly secured to terminals and labeled with unique identification.
- C. Verify that spare I/O capacity is provided.

3.25 DDC CONTROLLER I/O CONTROL LOOP TESTS

A. Testing:

1. Test every I/O point connected to DDC controller to verify that safety and operating control set points are as indicated and as required to operate controlled system safely and at optimum performance.
2. Test every I/O point throughout its full operating range.
3. Test every control loop to verify that operation is stable and accurate.
4. Adjust control loop proportional, integral, and derivative settings to achieve optimum performance while complying with performance requirements indicated. Document testing of each control loop's precision and stability via trend logs.
5. Test and adjust every control loop for proper operation according to sequence of operation.
6. Test software and hardware interlocks for proper operation. Correct deficiencies.
7. Operate each analog point at the following:
 - a. Upper quarter of range.
 - b. Lower quarter of range.
 - c. At midpoint of range.
8. Exercise each binary point.
9. For every I/O point in DDC system, read and record each value at operator workstation, at DDC controller, and at field instrument simultaneously. Value displayed at operator workstation, at DDC controller, and at field instrument must match.
10. Prepare and submit report documenting results for each I/O point in DDC system and include in each I/O point a description of corrective measures and adjustments made to achieve desired results.

3.26 DDC SYSTEM VALIDATION TESTS

- A. Perform validation tests before requesting final review of system. Before beginning testing, first submit Pretest Checklist and Test Plan.
- B. After review of Pretest Checklist and Test Plan, execute all tests and procedures indicated in plan.
- C. After testing is complete, submit completed Pretest Checklist.
- D. Pretest Checklist: Submit the following list with items checked off once verified:
 1. Detailed explanation for any items that are not completed or verified.
 2. Required mechanical installation work is successfully completed and HVAC equipment is working correctly.
 3. HVAC equipment motors operate below full-load amperage ratings.
 4. Required DDC system components, wiring, and accessories are installed.

5. Installed DDC system architecture matches approved Drawings.
6. Control electric power circuits operate at proper voltage and are free from faults.
7. Required surge protection is installed.
8. DDC system network communications function properly, including uploading and downloading programming changes.
9. Using BACnet protocol analyzer, verify that communications are error free.
10. Each controller's programming is backed up.
11. Equipment, products, tubing, wiring cable, and conduits are properly labeled.
12. All I/O points are programmed into controllers.
13. Testing, adjusting, and balancing work affecting controls is complete.
14. Dampers and actuators zero and span adjustments are set properly.
15. Each control damper and actuator goes to failed position on loss of power and loss of signal.
16. Valves and actuators zero and span adjustments are set properly.
17. Each control valve and actuator goes to failed position on loss of power and loss of signal.
18. Meter, sensor, and transmitter readings are accurate and calibrated.
19. Control loops are tuned for smooth and stable operation.
20. View trend data where applicable.
21. Each controller works properly in standalone mode.
22. Safety controls and devices function properly.
23. Interfaces with fire-alarm system function properly.
24. Electrical interlocks function properly.
25. Operator workstations and other interfaces are delivered, all system and database software is installed, and graphics are created.
26. Record Drawings are completed.

E. Test Plan:

1. Prepare and submit validation Test Plan including test procedures for performance validation tests.
2. Address all specified functions of DDC system and sequences of operation in Test Plan.
3. Explain detailed actions and expected results to demonstrate compliance with requirements indicated.
4. Explain method for simulating necessary conditions of operation used to demonstrate performance.
5. Include Test Checklist to be used to check and initial that each test has been successfully completed.
6. Submit Test Plan documentation 10 business days before start of tests.

F. Validation Test:

1. Verify operating performance of each I/O point in DDC system.
 - a. Verify analog I/O points at operating value.
 - b. Make adjustments to out-of-tolerance I/O points.
 - 1) Identify I/O points for future reference.
 - 2) Simulate abnormal conditions to demonstrate proper function of safety devices.

- 3) Replace instruments and controllers that cannot maintain performance indicated after adjustments.
2. Simulate conditions to demonstrate proper sequence of control.
3. Readjust settings to design values and observe ability of DDC system to establish desired conditions.
4. 24 hours after initial validation test, do as follows:
 - a. Re-check I/O points that required corrections during initial test.
 - b. Identify I/O points that still require additional correction and make corrections necessary to achieve desired results.
5. 24 Hours after second validation test, do as follows:
 - a. Re-check I/O points that required corrections during second test.
 - b. Continue validation testing until I/O point is normal on two consecutive tests.
6. Completely check out, calibrate, and test all connected hardware and software to ensure that DDC system performs according to requirements indicated.
7. After validation testing is complete, prepare and submit report indicating results of testing. For all I/O points that required correction, indicate how many validation re-tests it took to pass. Identify adjustments made for each test and indicate instruments that were replaced.

G. DDC System Response Time Test:

1. Simulate HLC.
 - a. Heavy load to be occurrence of 50 percent of total connected binary COV, one-half of which represents "alarm" condition, and 50 percent of total connected analog COV, one-half of which represents "alarm" condition, that are initiated simultaneously on a one-time basis.
2. Initiate 10 successive occurrences of HLC and measure response time to typical alarms and status changes.
3. Measure with timer having at least 0.1-second resolution and 0.01 percent accuracy.
4. Purpose of test is to demonstrate DDC system, as follows:
 - a. Reaction to COV and alarm conditions during HLC.
 - b. Ability to update DDC system database during HLC.
5. Passing test is contingent on the following:
 - a. Alarm reporting at printer beginning no more than two seconds after initiation (time zero) of HLC.
 - b. All alarms, both binary and analog, are reported and printed; none are lost.
 - c. Compliance with response times specified.
6. Prepare and submit report documenting HLC tested and results of test including time stamp and print out of all alarms.

H. DDC System Network Bandwidth Test:

1. Test network bandwidth usage on all DDC system networks to demonstrate bandwidth usage under DDC system normal operating conditions and under simulated HLC.
2. To pass, none of DDC system networks are to use more than 70 percent of available bandwidth under normal and HLC operation.

3.27 VERIFICATION OF DDC SYSTEM WIRELESS NETWORK

- A. DDC system Installer is to design wireless DDC system networks to comply with performance requirements indicated.
- B. Verify wireless network performance through field testing and document results in a field test report.
- C. Testing and verification of all wireless devices to include, but not be limited to, the following:
 1. Speed.
 2. Online status.
 3. Signal strength.

3.28 FINAL REVIEW

- A. Submit written request to Architect when DDC system is ready for final review. State the following:
 1. DDC system has been thoroughly inspected for compliance with Contract Documents and found to be in full compliance.
 2. DDC system has been calibrated, adjusted, and tested and found to comply with requirements of operational stability, accuracy, speed, and other performance requirements indicated.
 3. DDC system monitoring and control of HVAC systems results in operation according to sequences of operation indicated.
 4. DDC system is complete and ready for final review.
- B. Upon receipt of written request for final review, Architect to start review within reasonable period and upon completion issue field report(s) documenting observations and deficiencies.
- C. Take prompt action to remedy deficiencies indicated in reviewer's field report(s) and submit second written request after all deficiencies have been corrected. Repeat process until no deficiencies are reported.
- D. Compensation for Subsequent Reviews: Should more than two reviews be required, DDC system manufacturer and Installer to compensate entity/entities performing reviews for total costs (labor and expenses) associated with subsequent reviews. Estimated cost of each subsequent review to be submitted and approved by DDC system manufacturer and Installer before review.
- E. Prepare and submit closeout submittals and begin procedures indicated in "Extended Operation Test" Article when no deficiencies are reported.
- F. Part of DDC system final review to include demonstration to parties participating in final review.

1. Provide staff familiar with DDC system installed to demonstrate operation of DDC system during final review.
2. Provide testing equipment to demonstrate accuracy and other performance requirements of DDC system that is requested by reviewers during final review.
3. Demonstration to include, but not be limited to, the following:
 - a. Accuracy and calibration of 10 I/O points randomly selected by reviewers. If review finds that some I/O points are not properly calibrated and not satisfying performance requirements indicated, additional I/O points may be selected by reviewers until total I/O points being reviewed that satisfy requirements equals quantity indicated.
 - b. HVAC equipment and system hardwired and software safeties and life-safety functions are operating according to sequence of operation. Up to 10 I/O points to be randomly selected by reviewers. Additional I/O points may be selected by reviewers to discover problems with operation.
 - c. Correct sequence of operation after electrical power interruption and resumption after electrical power is restored for randomly selected HVAC systems.
 - d. Operation of randomly selected dampers and valves in normal-on, normal-off, and failed positions.
 - e. Reporting of alarm conditions for randomly selected alarms, including different classes of alarms, to ensure that alarms are properly received by operators and operator workstations.
 - f. Trends, summaries, logs, and reports set up for Project.
 - g. For up to three HVAC systems randomly selected by reviewers, use graph trends to show that sequence of operation is executed in correct manner and that HVAC systems operate properly through complete sequence of operation including different modes of operations indicated. Show that control loops are stable and operating at set points and respond to changes in set point of 20 percent or more.
 - h. Software's ability to communicate with controllers, operator workstations, and uploading and downloading of control programs.
 - i. Software's ability to edit control programs offline.
 - j. Data entry to show Project-specific customizing capability including parameter changes.
 - k. Step through penetration tree, display all graphics, demonstrate dynamic update, and direct access to graphics.
 - l. Execution of digital and analog commands in graphic mode.
 - m. Spreadsheet and curve plot software and its integration with database.
 - n. Online user guide and help functions.
 - o. Multitasking by showing different operations occurring simultaneously on four quadrants of split screen.
 - p. System speed of response compared to requirements indicated.
 - q. For Each Controller: Applies to network and programmable application controllers.
 - 1) Memory: Programmed data, parameters, trend, and alarm history collected during normal operation are not to be lost during power failure.
 - 2) Operator Interface: Ability to connect directly to each type of digital controller with portable workstation and mobile device. Show that maintenance personnel interface tools perform as indicated in manufacturer's technical literature.

- 3) Standalone Ability: Demonstrate that controllers provide stable and reliable standalone operation using default values or other method for values normally read over network.
 - 4) Electric Power: Ability to disconnect any controller safely from its power source.
 - 5) Wiring Labels: Match control drawings.
 - 6) Network Communication: Ability to locate controller's location on network and communication architecture matches Shop Drawings.
 - 7) Nameplates and Tags: Accurate and permanently attached to control panel doors, instrument, actuators, and devices.
- r. For Each Operator Workstation:
- 1) I/O points lists agree with naming conventions.
 - 2) Graphics are complete.
 - 3) UPS unit, if applicable, operates.
- s. Communications and Interoperability: Demonstrate proper interoperability of data sharing, alarm and event management, trending, scheduling, and device and network management. Use ASHRAE 135 protocol analyzer to help identify devices, view network traffic, and verify interoperability. Requirements must be met even if only one manufacturer's equipment is installed.
- 1) Data Presentation: On each operator workstation, demonstrate graphic display capabilities.
 - 2) Reading of Any Property: Demonstrate ability to read and display any used readable object property of any device on network.
 - 3) Set-Point and Parameter Modifications: Show ability to modify set points and tuning parameters indicated. Modifications are made with messages and write services initiated by operator using workstation graphics, or by completing a field in menu with instructional text.
 - 4) Peer-to-Peer Data Exchange: Network devices are installed and configured to perform without need for operator intervention to implement Project sequence of operation and to share global data.
 - 5) Alarm and Event Management: Alarms and events are installed and prioritized according to Owner. Demonstrate that time delays and other logic are set up to avoid nuisance tripping. Show that operators with sufficient privileges are permitted.
 - 6) Schedule Lists: Schedules are configured for start and stop, mode change, occupant overrides, and night setback as defined in sequence of operations.
 - 7) Schedule Display and Modification: Ability to display any schedule with start and stop times for calendar year. Show that all calendar entries and schedules are modifiable from any connected operator workstation by an operator with sufficient privilege.
 - 8) Archival Storage of Data: Data archiving is handled by operator workstation and server and local trend archiving and display is accomplished.
 - 9) Modification of Trend Log Object Parameters: Operator with sufficient privilege can change logged data points, sampling rate, and trend duration.
 - 10) Device and Network Management:
 - a) Display of network device status.

- b) Display of BACnet object information.
- c) Silencing devices transmitting erroneous data.
- d) Time synchronization.
- e) Remote device re-initialization.
- f) Backup and restore network device programming and master database(s).
- g) Configuration management of routers.

3.29 EXTENDED OPERATION TEST

- A. Operate DDC system for operating period of 21 consecutive calendar days following Final Acceptance. Coordinate exact start date of testing with Owner.
- B. Provide operator familiar with DDC system installed to man an operator workstation while on-site during eight hours of each normal business day occurring during operating period.
- C. During operating period, DDC system to demonstrate correct operation and accuracy of monitored and controlled points as well as operation capabilities of sequences, logs, trends, reports, specialized control algorithms, diagnostics, and other software indicated.
 - 1. Correct defects of hardware and software when they occur.
- D. Definition of Failures and Downtime during Operating Period:
 - 1. Failed I/O point constituting downtime is I/O point failing to perform its intended function consistently and a point physically failed due to hardware and software.
 - 2. Downtime is when any I/O point in DDC system is unable to fulfill its required function.
 - 3. Calculate downtime as elapsed time between detected point failure as confirmed by operator, and time point is restored to service.
 - 4. Maximum time interval allowed between DDC system detection of failure occurrence and operator confirmation is to be 0.5 hours.
 - 5. Log downtime in hours to nearest 0.1 hour.
 - 6. Power outages do not count as downtime, but do suspend test hours unless systems are provided with UPS and served through a backup power source.
 - 7. Hardware or software failures caused by power outages do count as downtime.
- E. During operating period, log downtime and operational problems are encountered.
 - 1. Identify source of problem.
 - 2. Provide written description of corrective action taken.
 - 3. Record duration of downtime.
 - 4. Maintain log showing the following:
 - a. Time of occurrence.
 - b. Description of each occurrence and pertinent written comments for reviewer to understand scope and extent of occurrence.
 - c. Downtime for each failed I/O point.
 - d. Running total of downtime and total time of I/O point after each problem has been restored.
 - 5. Make log available to Owner for review at any time.

- F. For DDC system to pass extended operation test, total downtime is limited to 2 percent of total point-hours during operating period.
- 1.If DDC system testing results fail to comply with minimum requirements of passing at end of operating period indicated, extend operating period one consecutive day at a time until DDC system passes requirement.
- G. Base evaluation of DDC system passing test on the following calculation:
- 1.Count downtime on point-hour basis where total number of DDC system point-hours is equal to total number of I/O points in DDC system multiplied by total number of hours during operating period.
 - 2.One point-hour of downtime is one I/O point down for one hour. For example, three I/O points down for five hours is total of 15 point-hours of downtime. Four points down for one-half hour is two point-hours of downtime.
 - 3.Example Calculation: Maximum allowable downtime for 30-day test for DDC system with 1000 total I/O points (combined analog and binary) and passing score of 1 percent downtime is computed by 30 days x 24 h/day x 1000 points x 1 percent equals 7200 point-hours of maximum allowable downtime.
- H. Prepare test and inspection reports.

3.30 ADJUSTING

- A. Occupancy Adjustments: When requested within 12 months from date of Final Acceptance, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.31 MAINTENANCE SERVICE

- A. Beginning at Final Acceptance, verify that maintenance service includes six months' full maintenance by DDC system manufacturer's authorized service representative. Include quarterly preventive maintenance, repair or replacement of worn or defective components, cleaning, calibration, and adjusting as required for proper operation. Use only manufacturer's authorized replacement parts and supplies.

3.32 SOFTWARE SERVICE AGREEMENT

- A. Technical Support: Beginning at Final Acceptance, verify that service agreement includes software support for two year(s).
- B. Upgrade Service: At Final Acceptance, update software to latest version. Install and program software upgrades that become available within two year(s) from date of Final Acceptance. Verify that upgrading software includes operating system and new or revised licenses for using software.
- 1.Upgrade Notice: No fewer than 30 days to allow Owner to schedule and access system and to upgrade computer equipment if necessary.

3.33 DEMONSTRATION

- A. Engage a factory-authorized service representative with complete knowledge of Project-specific system installed to train Owner's maintenance personnel to adjust, operate, and maintain DDC system.
- B. Extent of Training:
1. Base extent of training on scope and complexity of DDC system indicated and training requirements indicated. Provide extent of training required to satisfy requirements indicated even if more than minimum training requirements are indicated.
 2. Inform Owner of anticipated training requirements if more than minimum training requirements are indicated.
 3. Minimum Training Requirements:
 - a. Provide not less than 10 days of training total.
 - b. Stagger training over multiple training classes to accommodate Owner's requirements. All training to occur before end of warranty period.
 - c. Break down total days of training into not more than three separate training classes.
 - d. Schedule training so each training class is not less than two consecutive day(s).
- C. Training Schedule:
1. Schedule training with Owner 20 business days before expected Final Acceptance.
 2. Schedule training to provide Owner with at least 15 business days of notice in advance of training.
 3. Training to occur within normal business hours at mutually agreed on time. Unless otherwise agreed to, training to occur Monday through Friday, except on U.S. Federal holidays, with two morning sessions and two afternoon sessions. Each morning session and afternoon session to be split in half with 30-minute break between sessions. Morning and afternoon sessions to be separated by 30-minute lunch period. Training, including breaks and excluding lunch period, are not to exceed eight hours per day.
 4. Provide staggered training schedule as requested by Owner.
- D. Training Attendee List and Sign-in Sheet:
1. Request from Owner in advance of training a proposed attendee list with name, phone number, and email address.
 2. Provide preprinted sign-in sheet for each training session with proposed attendees listed and no fewer than six blank spaces to add additional attendees.
 3. Include preprinted sign-in sheet with training session number, date and time, instructor name, phone number, email address, and brief description of content to be covered during session. List attendees with columns for name, phone number, and email address and a column for attendee signature or initials.
 4. Circulate sign-in sheet at beginning of each session and solicit attendees to sign or initial in applicable location.
 5. At end of each training day, send Owner an email with attachment of scanned copy (PDF) of circulated sign-in sheet for each session. Indicate which attendees, if any, joined for only part of training sessions.
- E. Training Attendee Headcount:

1. Plan in advance of training for three attendees.
 2. Make allowance for Owner to add up to two attendee(s) at time of training.
 3. Headcount may vary depending on training content covered in session. Attendee access may be restricted to some training content for purposes of maintaining system security.
- F. Training Attendee Prior Knowledge: For guidance in planning required training and instruction, assume attendees have the following:
1. Intermediate user knowledge of computers and office applications.
 2. Intermediate knowledge of HVAC systems.
 3. Intermediate knowledge of DDC systems.
 4. Intermediate knowledge of DDC system and products installed.
- G. Attendee Training Manuals:
1. Provide each attendee with color hard copy of all training materials and visual presentations.
 2. Organize hard-copy materials in three-ring binder with table of contents and individual divider tabs marked for each logical grouping of subject matter. Organize material to provide space for attendees to take handwritten notes within training manuals.
 3. In addition to hard-copy materials included in training manual, provide each binder with a sleeve or pocket that includes DVD or flash drive with PDF copy of all hard-copy materials.
- H. Instructor Requirements:
1. One or multiple qualified instructors, as required, to provide training.
 2. Use instructors who have provided not less than five years of instructional training on not less than five past projects with similar DDC system scope and complexity to DDC system installed.
- I. Organization of Training Sessions:
1. Organize training sessions into logical groupings of technical content and to reflect different levels of operators having access to system. Plan training sessions to accommodate the following three levels of operators:
 - a. Daily operators.
 - b. Advanced operators.
 - c. System managers and administrators.
 2. Plan and organize training sessions to group training content to protect DDC system security. Some attendees may be restricted to some training sessions to ensure DDC system security.
- J. Training Outline:
1. Submit training outline for Owner review at least 10 business day before scheduling training.
 2. Include in outline a detailed agenda for each training day that is broken down into each of four training sessions that day, training objectives for each training session, and synopses for each lesson planned.
- K. On-Site Training:

1. Owner will provide conditioned classroom or workspace with ample desks or tables, chairs, power, and data connectivity for instructor and each attendee.
2. Provide training materials, projector, and other audiovisual equipment used in training.
3. Provide as much of training located on-site as deemed feasible and practical by Owner.
4. Include on-site training with regular walk-through tours, as required, to observe each unique product type installed with hands-on review of operation, calibration, and service requirements.
5. Use operator workstation that is to be used with DDC system in the training. If operator workstations are unavailable, provide temporary workstation to convey training content.

L. Off-Site Training:

1. Provide conditioned training rooms and workspace with ample tables desks or tables, chairs, power, and data connectivity for each attendee.
2. Provide capability to remotely access to Project DDC system for use in training.
3. Provide operator workstation for use by each attendee.

M. Training Content for Daily Operators:

1. Basic operation of system.
2. Understanding DDC system architecture and configuration.
3. Understanding each unique product type installed including performance and service requirements for each.
4. Understanding operation of each system and equipment controlled by DDC system including sequences of operation, each unique control algorithm, and each unique optimization routine.
5. Operating operator workstations, printers, and other peripherals.
6. Logging on and off system.
7. Accessing graphics, reports, and alarms.
8. Adjusting and changing set points and time schedules.
9. Recognizing DDC system malfunctions.
10. Understanding content of operation and maintenance manuals including control drawings.
11. Understanding physical location and placement of DDC controllers and I/O hardware.
12. Accessing data from DDC controllers.
13. Operating portable operator workstations.
14. Review of DDC testing results to establish basic understanding of DDC system operating performance and HVAC system limitations as of Final Acceptance.
15. Running each specified report and log.
16. Displaying and demonstrating each data entry to show Project-specific customizing capability. Demonstrating parameter changes.
17. Stepping through graphics penetration tree, displaying all graphics, demonstrating dynamic updating, and direct access to graphics.
18. Executing digital and analog commands in graphic mode.
19. Demonstrating control loop precision and stability via trend logs of I/O for not less than 10 percent of I/O installed.
20. Demonstrating DDC system performance through trend logs and command tracing.
21. Demonstrating scan, update, and alarm responsiveness.
22. Demonstrating spreadsheet and curve plot software, and its integration with database.
23. Demonstrating on-line user guide, and help function and mail facility.

24. Demonstrating multitasking by showing dynamic curve plot, and graphic construction operating simultaneously via split screen.
25. Demonstrating the following for HVAC systems and equipment controlled by DDC system:
 - a. Operation of HVAC equipment in normal-off, normal-on, and failed conditions while observing individual equipment, dampers, and valves for correct position under each condition.
 - b. For HVAC equipment with factory-installed software, show that integration into DDC system is able to communicate with DDC controllers or gateways, as applicable.
 - c. Using graphed trends, show that sequence of operation is executed in correct manner, and HVAC systems operate properly through complete sequence of operation including seasonal change, occupied and unoccupied modes, warm-up and cool-down cycles, and other modes of operation indicated.
 - d. Hardware interlocks and safeties function properly and DDC system performs correct sequence of operation after electrical power interruption and resumption after power is restored.
 - e. Reporting of alarm conditions for each alarm, and confirm that alarms are received at assigned locations, including operator workstations.
 - f. Each control loop responds to set-point adjustment and stabilizes within time period indicated.
 - g. Sharing of previously graphed trends of all control loops to demonstrate that each control loop is stable and set points are being maintained.

N. Training Content for Advanced Operators:

1. Making and changing workstation graphics.
2. Creating, deleting, and modifying alarms including annunciation and routing.
3. Creating, deleting, and modifying point trend logs including graphing and printing on an ad-hoc basis and operator-defined time intervals.
4. Creating, deleting, and modifying reports.
5. Creating, deleting, and modifying points.
6. Creating, deleting, and modifying programming including ability to edit control programs off-line.
7. Creating, deleting, and modifying system graphics and other types of displays.
8. Adding DDC controllers and other network communication devices such as gateways and routers.
9. Adding operator workstations.
10. Performing DDC system checkout and diagnostic procedures.
11. Performing DDC controllers operation and maintenance procedures.
12. Performing operator workstation operation and maintenance procedures.
13. Configuring DDC system hardware including controllers, workstations, communication devices, and I/O points.
14. Maintaining, calibrating, troubleshooting, diagnosing, and repairing hardware.
15. Adjusting, calibrating, and replacing DDC system components.

O. Training Content for System Managers and Administrators:

1. DDC system software maintenance and backups.
2. Uploading, downloading, and offline archiving of all DDC system software and databases.

3. Interface with Project-specific, third-party operator software.
4. Understanding password and security procedures.
5. Adding new operators and making modifications to existing operators.
6. Operator password assignments and modification.
7. Operator authority assignment and modification.
8. Workstation data segregation and modification.

P. Video of Training Sessions:

1. Provide digital video and audio recording of each training session. Create separate recording file for each session.
2. Stamp each recording file with training session number, session name, and date.
3. Provide Owner with two copies of digital files on cloud and flash drives for later reference and for use in future training.
4. Owner retains right to make additional copies for intended training purposes without having to pay royalties.

END OF SECTION

SECTION 232113 - HYDRONIC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Copper tube and fittings.
 - 2. Joining materials.
 - 3. Transition fittings.
 - 4. Bypass chemical feeder.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of the following:
 - 1. Pipe and tube.
 - 2. Fittings.
 - 3. Joining materials.
 - 4. Transition fittings.
 - 5. Bypass chemical feeder.
- B. Sustainable Design Submittals:
- C. Delegated-Design Submittal:
 - 1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
 - 2. Locations of pipe anchors and alignment guides and expansion joints and loops.
 - 3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.
 - 4. Locations of and details for penetration and firestopping for fire- and smoke-rated wall and floor and ceiling assemblies.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Piping layout, or BIM model, drawn to scale, showing the items described in this Section, and coordinated with all building trades.

- B. Qualification Data: For Installer.
- C. Welding certificates.
- D. Field quality-control reports.
- E. Preconstruction Test Reports:
 - 1. Water Analysis: Submit a copy of the water analysis to illustrate water quality available at Project site.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Hydronic piping components and installation shall be capable of withstanding the following minimum working pressure and temperature unless otherwise indicated:
 - 1. Condensate-Drain Piping: 73 deg F.

2.2 COPPER TUBE AND FITTINGS

- A. Drawn-Temper Copper Tube: ASTM B88, Type L.
- B. DWV Copper Tube: ASTM B306, Type DWV.
- C. Cast-Copper, Solder-Joint Fittings: ASME B16.18, pressure fittings.
- D. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, pressure fittings.
- E. Cast Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body, with ball-and-socket, metal-to-metal seating surfaces and solder-joint or threaded ends.
- F. Wrought Copper Unions: ASME B16.22.

2.3 JOINING MATERIALS

- A. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos free, 1/8-inch maximum thickness unless otherwise indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
- B. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.

- C. Solder Filler Metals: ASTM B32, lead-free alloys. Include water-flushable flux according to ASTM B813.
- D. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for joining copper with copper; or BAg-1, silver alloy for joining copper with bronze or steel.

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS

- A. Condensate-Drain Piping, Copper: Type DWV, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.

3.2 INSTALLATION OF PIPING

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Select system components with pressure rating equal to or greater than system operating pressure.
- K. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- L. Install drains, consisting of a tee fitting, NPS 3/4 ball valve, and short NPS 3/4 threaded nipple with cap, at low points in piping system mains and elsewhere as required for system drainage.
- M. Install piping at a uniform grade of 0.2 percent upward in direction of flow.

- N. Reduce pipe sizes using eccentric reducer fitting installed with level side up.
- O. Install branch connections to mains using mechanically formed tee fittings in main pipe, with the branch connected to the bottom of the main pipe. For up-feed risers, connect the branch to the top of the main pipe.
- P. Install unions in piping, NPS 2 and smaller, adjacent to valves, at final connections of equipment, and elsewhere as indicated.
- Q. Install flanges in piping, NPS 2-1/2 and larger, at final connections of equipment and elsewhere as indicated.
- R. Install shutoff valve immediately upstream of each dielectric fitting.
- S. Comply with requirements in Section 23 0553 "Identification for HVAC Piping and Equipment" for identifying piping.
- T. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 23 0517 "Sleeves and Sleeve Seals for HVAC Piping."

3.3 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- C. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8/A5.8M.
- D. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- E. Welded Joints: Construct joints according to AWS D10.12M/D10.12, using qualified processes and welding operators according to "Quality Assurance" Article.
- F. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.
- G. Mechanically Formed, Copper-Tube-Outlet Joints: Use manufacturer-recommended tools and procedure, and brazed joints.
- H. Pressure-Sealed Joints: Use manufacturer-recommended tools and procedure. Leave insertion marks on pipe after assembly.

3.4 INSTALLATION OF HANGERS AND SUPPORTS

- A. Comply with requirements for seismic-restraint devices specified in Section 23 0548 "Vibration and Seismic Controls for HVAC."
- B. Comply with requirements in Section 23 0529 "Hangers and Supports for HVAC Piping and Equipment" for hangers, supports, and anchor devices.
- C. Install hangers for copper tubing and steel piping, with maximum horizontal spacing and minimum rod diameters, to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- D. Install hangers for plastic piping, with maximum horizontal spacing and minimum rod diameters, to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- E. Install hangers for fiberglass piping, with maximum horizontal spacing and minimum rod diameters, to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- F. Support horizontal piping within 12 inches of each fitting and coupling.
- G. Support vertical runs of copper tubing and steel piping to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- H. Support vertical runs of fiberglass piping to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.5 TERMINAL EQUIPMENT CONNECTIONS

- A. Sizes for supply and return piping connections shall be the same as or larger than equipment connections.
- B. Install ports for pressure gauges and thermometers at coil inlet and outlet connections. Comply with requirements in Section 23 0519 "Meters and Gages for HVAC Piping."

3.6 IDENTIFICATION

- A. Identify system components. Comply with requirements for identification materials and installation in Section 23 0553 "Identification for HVAC Piping and Equipment."

3.7 FIELD QUALITY CONTROL

- A. Prepare hydronic piping according to ASME B31.9 and as follows:
 - 1. Leave joints, including welds, uninsulated and exposed for examination during test.
 - 2. Provide temporary restraints for expansion joints that cannot sustain reactions due to test pressure. If temporary restraints are impractical, isolate expansion joints from testing.

3. Flush hydronic piping systems with clean water; then remove and clean or replace strain-er screens.
4. Isolate equipment from piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Install blinds in flanged joints to isolate equipment.
5. Install safety valve, set at a pressure no more than one-third higher than test pressure, to protect against damage by expanding liquid or other source of overpressure during test.

B. Perform the following before operating the system:

1. Open manual valves fully.
2. Inspect pumps for proper rotation.
3. Set makeup pressure-reducing valves for required system pressure.
4. Inspect air vents at high points of system and determine if all are installed and operating freely (automatic type), or bleed air completely (manual type).
5. Set temperature controls so all coils are calling for full flow.
6. Inspect and set operating temperatures of hydronic equipment, such as boilers, chillers, cooling towers, to specified values.
7. Verify lubrication of motors and bearings.

END OF SECTION

SECTION 233113 - METAL DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Single-wall rectangular ducts and fittings.
 - 2. Single-wall round and flat-oval ducts and fittings.
 - 3. Sheet metal materials.
 - 4. Sealants and gaskets.
 - 5. Hangers and supports.
 - 6. Seismic-restraint devices.
- B. Related Sections:
 - 1. Section 23 0593 "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing requirements for metal ducts.
 - 2. Section 23 3300 "Air Duct Accessories" for dampers, sound-control devices, duct-mounting access doors and panels, turning vanes, and flexible ducts.

1.3 DEFINITIONS

- A. OSHPD: Office of Statewide Health Planning and Development (State of California).

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of the following products:
 - 1. Liners and adhesives.
 - 2. Sealants and gaskets.
 - 3. Seismic-restraint devices.
- B. Shop Drawings:
 - 1. Fabrication, assembly, and installation, including plans, elevations, sections, components, and attachments to other work.
 - 2. Factory- and shop-fabricated ducts and fittings.
 - 3. Duct layout indicating sizes, configuration, liner material, and static-pressure classes.
 - 4. Elevation of top and bottom of ducts.
 - 5. Dimensions of all duct runs from building grid lines.
 - 6. Fittings.
 - 7. Reinforcement and spacing.

8. Seam and joint construction.
9. Penetrations through fire-rated and other partitions.
10. Equipment installation based on equipment being used on Project.
11. Locations for duct accessories, including dampers, turning vanes, and access doors and panels.
12. Hangers and supports, including methods for duct and building attachment and vibration isolation.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: A single set of plans, drawn to scale, showing the items described in this Section, and coordinated with all building trades.
- B. Welding certificates.
- C. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel in accordance with the following:
 1. AWS D1.1/D1.1M, "Structural Welding Code - Steel," for hangers and supports.
 2. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum," for aluminum supports.
 3. AWS D9.1/D9.1M, "Sheet Metal Welding Code," for duct joint and seam welding.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Duct hangers and supports shall withstand the effects of gravity loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible".
- B. Airstream Surfaces: Surfaces in contact with airstream shall comply with requirements in ASHRAE 62.1.
- C. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment," and Section 7 - "Construction and System Startup."
- D. ASHRAE/IES Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6.4.4 - "HVAC System Construction and Insulation."
- E. Duct Dimensions: Unless otherwise indicated, all duct dimensions indicated on Drawings are inside clear dimensions and do not include insulation or duct wall thickness.

2.2 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.
1. Construct ducts of galvanized sheet steel unless otherwise indicated.
 2. For ducts exposed to weather or corrosive environments, construct of Type 304 stainless steel indicated by manufacturer to be suitable for outdoor installation.
- B. Transverse Joints: Fabricate joints in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
1. For ducts with longest side less than 36 inches, select joint types in accordance with Figure 2-1.
 2. For ducts with longest side 36 inches or greater, use flange joint connector Type T-22, T-24, T-24A, T-25a, or T-25b. Factory-fabricated flanged duct connection system may be used if submitted and approved by engineer of record.
 3. Where specified for specific applications, all joints shall be welded.
- C. Longitudinal Seams: Select seam types and fabricate in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"
- D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Ch. 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.3 SINGLE-WALL ROUND AND FLAT-OVAL DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Ch. 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.
1. Construct ducts of galvanized sheet steel unless otherwise indicated.
 2. For ducts exposed to weather and corrosive environments, construct of Type 304 stainless steel indicated by manufacturer to be suitable for outdoor installation.
 3. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Ductmate Industries, Inc.
 - b. Elgen Manufacturing
 - c. Linx Industries (formerly Lindab)
 - d. McGill AirFlow LLC
 - e. MKT Metal Manufacturing
 - f. Nordfab Ducting
 - g. SEMCO, LLC; part of FlaktGroup
 - h. Set Duct Manufacturing

- i. Sheet Metal Connectors, Inc.
 - j. Spiral Manufacturing Co., Inc.
 - k. Stamped Fittings Inc.
- B. Flat-Oval Ducts: Indicated dimensions are the duct width (major dimension) and diameter of the round sides connecting the flat portions of the duct (minor dimension).
- C. Transverse Joints: Select joint types and fabricate in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.
- D. Longitudinal Seams: Select seam types and fabricate in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-2, "Round Duct Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
1. Fabricate round ducts larger than 90 inches in diameter with butt-welded longitudinal seams.
 2. Fabricate flat-oval ducts larger than 72 inches in width (major dimension) with butt-welded longitudinal seams.
- E. Tees and Laterals: Select types and fabricate in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.4 SHEET METAL MATERIALS

- A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A653/A653M.
1. Galvanized Coating Designation: G90.
 2. Finishes for Surfaces Exposed to View: Mill phosphatized.
- C. Stainless-Steel Sheets: Comply with ASTM A480/A480M, Type 304 or 316, as indicated in "Duct Schedule" Article; cold rolled, annealed, sheet. Exposed surface finish shall be No. 2B, No. 2D, No. 3, or No. 4 as indicated in "Duct Schedule" Article.
- D. Reinforcement Shapes and Plates: ASTM A36/A36M, steel plates, shapes, and bars; black and galvanized.
1. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.

- E. Tie Rods: Galvanized steel, 1/4-inch- minimum diameter for lengths 36 inches or less; 3/8-inch- minimum diameter for lengths longer than 36 inches.

2.5 SEALANT AND GASKETS

- A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested in accordance with UL 723; certified by an NRTL.
- B. Two-Part Tape Sealing System:
 - 1. Tape: Woven cotton fiber impregnated with mineral gypsum and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
 - 2. Tape Width: 3 inches.
 - 3. Sealant: Modified styrene acrylic.
 - 4. Water resistant.
 - 5. Mold and mildew resistant.
 - 6. Maximum Static-Pressure Class: 10 inch wg, positive and negative.
 - 7. Service: Indoor and outdoor.
 - 8. Service Temperature: Minus 40 to plus 200 deg F.
 - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum.
 - 10. Sealant shall have a VOC content of 420 g/L or less.
 - 11. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- C. Water-Based Joint and Seam Sealant:
 - 1. Application Method: Brush on.
 - 2. Solids Content: Minimum 65 percent.
 - 3. Shore A Hardness: Minimum 20.
 - 4. Water resistant.
 - 5. Mold and mildew resistant.
 - 6. VOC: Maximum 75 g/L (less water).
 - 7. Maximum Static-Pressure Class: 10 inch wg, positive and negative.
 - 8. Service: Indoor or outdoor.
 - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.
- D. Flanged Joint Sealant: Comply with ASTM C920.
 - 1. General: Single-component, acid-curing, silicone, elastomeric.
 - 2. Type: S.
 - 3. Grade: NS.
 - 4. Class: 25.
 - 5. Use: O.
 - 6. Sealant shall have a VOC content of 420 g/L or less.
 - 7. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- E. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

F. Round Duct Joint O-Ring Seals:

1. Seal shall provide maximum leakage class of 3 cfm/100 sq. ft. at 1-inch wg and shall be rated for 10-inch wg static-pressure class, positive or negative.
2. EPDM O-ring to seal in concave bead in coupling or fitting spigot.
3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

2.6 HANGERS AND SUPPORTS

- A. Hanger Rods for Noncorrosive Environments: Galvanized-steel rods and nuts.
- B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.
- C. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."
- D. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A603.
- E. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A492.
- F. Steel Cable End Connections: Galvanized-steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.
- G. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.
- H. Trapeze and Riser Supports:
 1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
 2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.

PART 3 - EXECUTION

3.1 DUCT INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and coordination drawings.
- B. Install ducts in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" unless otherwise indicated.
- C. Install ducts in maximum practical lengths with fewest possible joints.

- D. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.
- E. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.
- F. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- G. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.
- H. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.
- I. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- J. Install fire, combination fire/smoke, and smoke dampers where indicated on Drawings and as required by code, and by local authorities having jurisdiction. Comply with requirements in Section 23 3300 "Air Duct Accessories" for fire and smoke dampers and specific installation requirements of the damper UL listing.
- K. Install heating coils, cooling coils, air filters, dampers, and all other duct-mounted accessories in air ducts where indicated on Drawings.
- L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials both before and after installation.
- M. Elbows: Use long-radius elbows wherever they fit.
 - 1. Fabricate 90-degree rectangular mitered elbows to include turning vanes.
 - 2. Fabricate 90-degree round elbows with a minimum of three segments for 12 inches and smaller and a minimum of five segments for 14 inches and larger.
- N. Branch Connections: Use lateral or conical branch connections.

3.2 INSTALLATION OF EXPOSED DUCTWORK

- A. Protect ducts exposed in finished spaces from being dented, scratched, or damaged.
- B. Trim duct sealants flush with metal. Create a smooth and uniform exposed bead. Do not use two-part tape sealing system.
- C. Grind welds to provide smooth surface free of burrs, sharp edges, and weld splatter. When welding stainless steel with a No. 3 or 4 finish, grind the welds flush, polish the exposed welds, and treat the welds to remove discoloration caused by welding.
- D. Maintain consistency, symmetry, and uniformity in arrangement and fabrication of fittings, hangers and supports, duct accessories, and air outlets.

- E. Repair or replace damaged sections and finished work that does not comply with these requirements.

3.3 ADDITIONAL INSTALLATION REQUIREMENTS FOR EXHAUST DUCTS SERVING CAGEWASH AND OTHER HIGH-HUMIDITY LOCATIONS

- A. Install exhaust ducts and other exhaust ducts from wet, high-humidity locations without dips and traps that may hold water. Slope ducts a minimum of 2 percent back to dishwasher or toward drain.
- B. Provide a drain pocket at each low point and at the base of each riser with a 1-inch trapped copper drain from each drain pocket to open site floor drain.
- C. Minimize number of transverse seams.
- D. Do not locate longitudinal seams on bottom of duct.

3.4 ADDITIONAL INSTALLATION REQUIREMENTS FOR LABORATORY EXHAUST AND FUME HOOD EXHAUST DUCTS

- A. Install ducts in accordance with NFPA 45, "Fire Protection for Laboratories Using Chemicals."
- B. Install exhaust ducts without dips and traps that may hold water. Slope ducts a minimum of 2 percent back to hood or inlet. Where indicated on Drawings, install trapped drain piping.
- C. Connect duct to fan, fume hood, and other equipment indicated on Drawings.

3.5 DUCTWORK EXPOSED TO WEATHER

- A. All external joints are to be welded or have secure watertight mechanical connections. Seal all openings to provide weatherproof construction.
- B. Construct ductwork to resist external loads of wind, snow, ice, and other effects of weather. Provide necessary supporting structures.
- C. Single Wall:
 - 1. Ductwork shall be Type 304 stainless steel.
 - 2. Ductwork shall be galvanized steel.
 - a. If duct outer surface is uninsulated, protect outer surface with suitable paint. Paint materials and application requirements are specified in Section 09 9113 "Exterior Painting."
 - 3. Where ducts have external insulation, provide weatherproof aluminum jacket. See Section 23 073 "Duct Insulation."

3.6 DUCT SEALING

- A. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- B. Seal ducts at a minimum to the following seal classes in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible":
 - 1. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
 - 2. Outdoor, Supply-Air Ducts: Seal Class A.
 - 3. Outdoor, Exhaust Ducts: Seal Class C.
 - 4. Outdoor, Return-Air Ducts: Seal Class C.
 - 5. Unconditioned Space, Supply-Air Ducts in Pressure Classes 2-Inch wg and Lower: Seal Class B.
 - 6. Unconditioned Space, Supply-Air Ducts in Pressure Classes Higher Than 2-Inch wg: Seal Class A.
 - 7. Unconditioned Space, Exhaust Ducts: Seal Class C.
 - 8. Unconditioned Space, Return-Air Ducts: Seal Class B.
 - 9. Conditioned Space, Supply-Air Ducts in Pressure Classes 2-Inch wg and Lower: Seal Class C.
 - 10. Conditioned Space, Supply-Air Ducts in Pressure Classes Higher Than 2-Inch wg: Seal Class B.
 - 11. Conditioned Space, Exhaust Ducts: Seal Class B.
 - 12. Conditioned Space, Return-Air Ducts: Seal Class C.

3.7 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 5, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
 - 1. Where practical, install concrete inserts before placing concrete.
 - 2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
 - 3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
 - 4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.
 - 5. Do not use powder-actuated concrete fasteners for seismic restraints.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.
- D. Hangers Exposed to View: Threaded rod and angle or channel supports.
- E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.

- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.8 CONNECTIONS

- A. Make connections to equipment with flexible connectors complying with Section 23 3300 "Air Duct Accessories."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

3.9 PAINTING

- A. Paint interior of metal ducts that are visible through registers and grilles and that do not have duct liner. Apply one coat of flat, black, latex paint over a compatible galvanized-steel primer. Paint materials and application requirements are specified in Section 09 9113 "Exterior Painting" and Section 09 9123 "Interior Painting."

3.10 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Leakage Tests:
 - 1. Comply with SMACNA's "HVAC Air Duct Leakage Test Manual." Submit a test report for each test.
 - 2. Test the following systems:
 - a. Supply Ducts with a Pressure Class of 2-Inch wg or Higher: Test representative duct sections totaling no less than 100 percent of total installed duct area for each designated pressure class.
 - b. Exhaust Ducts with a Pressure Class of 2-inch wg or Higher: Test representative duct sections totaling no less than 100 percent of total installed duct area for each designated pressure class.
 - c. Outdoor-Air Ducts with a Pressure Class of 2-Inch wg or Higher: Test representative duct sections totaling no less than 100 percent of total installed duct area for each designated pressure class.
 - 3. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
 - 4. Testing of each duct section is to be performed with access doors, coils, filters, dampers, and other duct-mounted devices in place as designed. No devices are to be removed or blanked off so as to reduce or prevent additional leakage.
 - 5. Test for leaks before applying external insulation.
 - 6. Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure.
 - 7. Give seven days' advance notice for testing.
- C. Duct System Cleanliness Tests:
 - 1. Visually inspect duct system to ensure that no visible contaminants are present.

2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness in accordance with "Description of Method 3 - NADCA Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."
 - a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.

- D. Duct system will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

3.11 DUCT CLEANING

- A. Clean new duct system(s) before testing, adjusting, and balancing.
- B. Use duct cleaning methodology as indicated in NADCA ACR.
- C. Use service openings for entry and inspection.
 1. Provide openings with access panels appropriate for duct static-pressure and leakage class at dampers, coils, and any other locations where required for inspection and cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer. Comply with Section 23 3300 "Air Duct Accessories" for access panels and doors.
 2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
 3. Remove and reinstall ceiling to gain access during the cleaning process.
- D. Particulate Collection and Odor Control:
 1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
 2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.
- E. Clean the following components by removing surface contaminants and deposits:
 1. Air outlets and inlets (registers, grilles, and diffusers).
 2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
 3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
 4. Coils and related components.
 5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
 6. Supply-air ducts, dampers, actuators, and turning vanes.
 7. Dedicated exhaust and ventilation components and makeup air systems.
- F. Mechanical Cleaning Methodology:
 1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.

2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
5. Clean coils and coil drain pans in accordance with NADCA ACR. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
6. Provide drainage and cleanup for wash-down procedures.
7. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents in accordance with manufacturer's written instructions after removal of surface deposits and debris.

3.12 STARTUP

- A. Air Balance: Comply with requirements in Section 23 0593 "Testing, Adjusting, and Balancing for HVAC."

3.13 DUCT SCHEDULE

- A. Fabricate ducts with galvanized sheet steel except as otherwise indicated and as follows:
 1. Fabricate all ducts to achieve SMACNA pressure class, seal class, and leakage class as indicated below.
- B. Supply Ducts:
 1. Ducts Connected to the downstream side of Terminal Units:
 - a. Pressure Class: Positive 1-inch wg.
 - b. Minimum SMACNA Seal Class: A.
 - c. SMACNA Leakage Class for Rectangular: 4.
 - d. SMACNA Leakage Class for Round and Flat Oval: 4.
 2. Ducts Connected to Variable-Air-Volume Air-Handling Units:
 - a. Pressure Class: Positive 3-inch wg.
 - b. Minimum SMACNA Seal Class: A.
 - c. SMACNA Leakage Class for Rectangular: 4.
 - d. SMACNA Leakage Class for Round and Flat Oval: 4.
- C. Return Ducts:
 1. Ducts Connected to Air-Handling Units:
 - a. Pressure Class: Negative 2-inch wg.

- b. Minimum SMACNA Seal Class: A.
- c. SMACNA Leakage Class for Rectangular: 4.
- d. SMACNA Leakage Class for Round and Flat Oval: 4.

D. Exhaust Ducts:

1. Ducts Connected to Fans Exhausting (ASHRAE 62.1, Class 1 and 2) Air:

- a. Pressure Class: Negative 2-inch wg.
- b. Minimum SMACNA Seal Class: A.
- c. SMACNA Leakage Class for Rectangular: 4.
- d. SMACNA Leakage Class for Round and Flat Oval: 4.

E. Intermediate Reinforcement:

1. Galvanized-Steel Ducts: Galvanized steel

F. Double-Wall Duct Interstitial Insulation:

1. Supply-Air Ducts: 2 inch thick.

G. Elbow Configuration:

1. Rectangular Duct - Requirements for Different Velocities: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-2, "Rectangular Elbows."

a. Velocity 1000 fpm or Lower:

- 1) Radius Type RE 1 with minimum 0.5 radius-to-diameter ratio.
- 2) Mitered Type RE 4 without vanes.

b. Velocity 1000 to 1500 fpm:

- 1) Radius Type RE 1 with minimum 1.0 radius-to-diameter ratio.
- 2) Radius Type RE 3 with minimum 0.5 radius-to-diameter ratio and two vanes.
- 3) Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."

c. Velocity 1500 fpm or Higher:

- 1) Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio.
- 2) Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes.
- 3) Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."

2. Rectangular Duct - Requirements for All Velocities: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-2, "Rectangular Elbows."

- a. Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio.

- b. Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes.
- c. Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."

3.Round Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-4, "Round Duct Elbows."

- a. Minimum Radius-to-Diameter Ratio and Elbow Segments: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 3-1, "Mitered Elbows." Elbows with less than 90-degree change of direction have proportionately fewer segments.
 - 1) Velocity 1000 fpm or Lower: 0.5 radius-to-diameter ratio and three segments for 90-degree elbow.
 - 2) Velocity 1000 to 1500 fpm: 1.0 radius-to-diameter ratio and four segments for 90-degree elbow.
 - 3) Velocity 1500 fpm or Higher: 1.5 radius-to-diameter ratio and five segments for 90-degree elbow.
 - 4) Radius-to Diameter Ratio: 1.5.
- b. Round Elbows, 12 Inches and Smaller in Diameter: Stamped or pleated.
- c. Round Elbows, 14 Inches and Larger in Diameter: Standing seam.

H. Branch Configuration:

1.Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-6, "Branch Connection."

- a. Rectangular Main to Rectangular Branch: 45-degree entry.
- b. Rectangular Main to Round Branch: Conical spin in.

2.Round and Flat Oval: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees." Saddle taps are permitted in existing duct.

- a. Velocity 1000 fpm or Lower: 90-degree tap.
- b. Velocity 1000 to 1500 fpm: Conical tap.
- c. Velocity 1500 fpm or Higher: 45-degree lateral.

END OF SECTION

SECTION 233300 - AIR DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Manual volume dampers.
2. Flange connectors.
3. Turning vanes.
4. Duct-mounted access doors.
5. Duct access panel assemblies.
6. Flexible connectors.
7. Duct accessory hardware.

B. Related Requirements:

1. Section 23 3346 "Flexible Ducts" for insulated and non-insulated flexible ducts.
2. Section 28 4621.11 "Addressable Fire-Alarm Systems" for duct-mounted fire and smoke detectors.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. For duct silencers, include pressure drop, dynamic insertion loss, and self-generated noise data. Include breakout noise calculations for high-transmission-loss casings.

B. Sustainable Design Submittals:

C. Shop Drawings: For duct accessories. Include plans, elevations, sections, details, and attachments to other work.

1. Detail duct accessories' fabrication and installation in ducts and other construction. Include dimensions, weights, loads, and required clearances; and method of field assembly into duct systems and other construction. Include the following:
 - a. Special fittings.
 - b. Manual volume damper installations.
 - c. Control-damper installations.

- d. Fire-damper, smoke-damper, combination fire- and smoke-damper, ceiling, and corridor-damper installations, including sleeves; and duct-mounted access doors and remote damper operators.
- e. Duct security bars.
- f. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, or BIM model, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from installers of the items involved.
- B. Source quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Fusible Links: Furnish quantity equal to 10 percent of amount installed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Comply with NFPA 90A and NFPA 90B.
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

2.2 MANUAL VOLUME DAMPERS

- A. Low-Leakage, Steel, Manual Volume Dampers:
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Air Balance; a division of MESTEK, Inc.

- b. American Warming and Ventilating; a Mestek Architectural Group company
 - c. Arrow United Industries
 - d. Cesco Products; a division of MESTEK, Inc.
 - e. Greenheck Fan Corporation
 - f. Lloyd Industries, Inc.
 - g. McGill AirFlow LLC
 - h. Nailor Industries Inc.
 - i. Pottorff
 - j. Ruskin Company
 - k. Safe Air - Dowco Products
 - l. United Enertech
 - m. Vent Products Co., Inc.
2. Performance:
- a. AMCA Certification: Test and rate in accordance with AMCA 511.
 - b. Leakage:
 - 1) Class IA: Leakage shall not exceed 3 cfm/sq. ft. against 1-inch wg differential static pressure.
 - 2) Class I: Leakage shall not exceed 4 cfm/sq. ft. against 1-inch wg differential static pressure.
 - 3) Class II: Leakage shall not exceed 10 cfm/sq. ft. against 1-inch wg differential static pressure.
3. Construction:
- a. Linkage: Out of airstream.
 - b. Suitable for horizontal or vertical airflow applications.
4. Frames:
- a. Hat, U, or angle shaped.
 - b. Thickness: 18-gauge stainless steel.
 - c. Mitered and welded corners.
 - d. Flanges for attaching to walls and flangeless frames for installing in ducts.
5. Blades:
- a. Multiple or single blade.
 - b. Parallel- or opposed-blade design.
 - c. Stiffen damper blades for stability.
 - d. Stainless, roll-formed steel; 16 gauge thick.
6. Blade Edging Seals:
- a. Closed-cell neoprene.
 - b. Inflatable seal blade edging or replaceable rubber seals.
7. Blade Jamb Seals: Flexible metal compression type.
8. Blade Axles: Stainless steel.

9. Bearings:
 - a. Stainless steel sleeve.
 - b. Dampers mounted with vertical blades to have thrust bearing at each end of every blade.
10. Tie Bars and Brackets: Aluminum.
11. Locking device to hold damper blades in a fixed position without vibration.

B. Jackshaft:

1. Size: 0.5-inch diameter.
2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.

C. Damper Hardware:

1. Zinc-plated, die-cast core with dial and handle, made of 3/32-inch- thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
2. Include center hole to suit damper operating-rod size.
3. Include elevated platform for insulated duct mounting.

2.3 FLANGE CONNECTORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. CL WARD & Family Inc.
 2. Ductmate Industries, Inc.
 3. DynAir; a Carlisle Company
 4. Elgen Manufacturing
 5. Ward Industries; a brand of Hart & Cooley, Inc.
- B. Description: Add-on or roll-formed, factory fabricated, slide-on transverse flange connectors, gaskets, and components.
- C. Material: Galvanized steel.
- D. Gauge and Shape: Match connecting ductwork.

2.4 TURNING VANES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. Aero-Dyne Sound Control Co.
 2. CL WARD & Family Inc.

3. Ductmate Industries, Inc.
 4. Duro Dyne Inc.
 5. DynAir; a Carlisle Company
 6. Elgen Manufacturing
 7. Ward Industries; a brand of Hart & Cooley, Inc.
- B. Manufactured Turning Vanes for Metal Ducts: Fabricate curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.
- C. Manufactured Turning Vanes for Nonmetal Ducts: Fabricate curved blades of resin-bonded fiberglass with acrylic polymer coating; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
- D. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."
- E. Vane Construction:
1. Single wall for ducts up to 48 inches wide and double wall for larger dimensions.

2.5 DUCT-MOUNTED ACCESS DOORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. Aire Technologies
 2. Arrow United Industries
 3. Cesco Products; a division of MESTEK, Inc.
 4. CL WARD & Family Inc.
 5. Ductmate Industries, Inc.
 6. Duro Dyne Inc.
 7. Elgen Manufacturing
 8. Flexmaster U.S.A., Inc.
 9. McGill AirFlow LLC
 10. Ruskin Company
 11. United Enertech
 12. Ventfabrics, Inc.
 13. Ward Industries; a brand of Hart & Cooley, Inc.
- B. Duct-Mounted Access Doors: Fabricate access panels in accordance with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figure 7-2 (7-2M), "Duct Access Doors and Panels," and Figure 7-3, "Access Doors - Round Duct."
1. Door:

- a. Double wall, rectangular.
 - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
 - c. 24-gauge- thick galvanized steel 24-gauge- thick stainless steel door panel.
 - d. Vision panel.
 - e. Hinges and Latches: 1-by-1-inch butt or piano hinge and cam latches.
 - f. Fabricate doors airtight and suitable for duct pressure class.
2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
 - a. 24-gauge- thick galvanized steel or 0.032-inch- thick aluminum frame.
 3. Number of Hinges and Locks:
 - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
 - b. Access Doors up to 18 Inches Square: Continuous and two sash locks.
 - c. Access Doors up to 24 by 48 Inches: Continuous and two compression latches with outside and inside handles.
 - d. Access Doors Larger Than 24 by 48 Inches: Continuous and two compression latches with outside and inside handles.

2.6 DUCT ACCESS PANEL ASSEMBLIES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. CL WARD & Family Inc.
 2. Ductmate Industries, Inc.
 3. Flame Gard, Inc.
- B. Access panels used in cooking applications:
 1. Labeled compliant to NFPA 96 for grease duct access doors.
 2. Labeled in accordance with UL 1978 by an NRTL.
- C. Panel and Frame: Minimum thickness 16-gauge stainless steel.
- D. Fasteners: Stainless steel. Panel fasteners shall not penetrate duct wall.
- E. Gasket: Comply with NFPA 96, grease-tight, high-temperature ceramic fiber, rated for minimum 2000 deg F.
- F. Minimum Pressure Rating: 10 inches wg positive or negative.

2.7 FLEXIBLE CONNECTORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. CL WARD & Family Inc.
 2. Ductmate Industries, Inc.
 3. Duro Dyne Inc.
 4. DynAir; a Carlisle Company
 5. Elgen Manufacturing
 6. Ventfabrics, Inc.
 7. Ward Industries; a brand of Hart & Cooley, Inc.
- B. Fire-Performance Characteristics: Adhesives, sealants, fabric materials, and accessory materials shall have flame-spread index not exceeding 25 and smoke-developed index not exceeding 50 when tested in accordance with ASTM E84.
- C. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
- D. Materials: Flame-retardant or noncombustible fabrics.
- E. Coatings and Adhesives: Comply with UL 181, Class 1.
- F. Metal-Edged Connectors: Factory fabricated with a fabric strip 5-3/4 inches wide attached to two strips of 2-3/4-inch- wide, 0.028-inch- thick, galvanized sheet steel or 0.032-inch- thick aluminum sheets. Provide metal compatible with connected ducts.
- G. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
1. Minimum Weight: 26 oz./sq. yd.
 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
 3. Service Temperature: Minus 40 to plus 200 deg F.
- H. High-Temperature System, Flexible Connectors: Glass fabric coated with silicone rubber.
1. Minimum Weight: 16 oz./sq. yd.
 2. Tensile Strength: 285 lbf/inch in the warp and 185 lbf/inch in the filling.
 3. Service Temperature: Minus 67 to plus 500 deg F.
- I. High-Corrosive-Environment System, Flexible Connectors: Glass fabric with chemical-resistant coating.
1. Minimum Weight: 14 oz./sq. yd.
 2. Tensile Strength: 450 lbf/inch in the warp and 340 lbf/inch in the filling.
 3. Service Temperature: Minus 67 to plus 500 deg F.
- J. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression, and with a load stop. Include rod and angle-iron brackets for attaching to fan discharge and duct.
1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
 2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.

4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

2.8 DUCT ACCESSORY HARDWARE

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. CL WARD & Family Inc.
 2. Ductmate Industries, Inc.
 3. Duro Dyne Inc.
 4. DynAir; a Carlisle Company
 5. Elgen Manufacturing
 6. Hardcast; a Carlisle Company
 7. United Enertech
 8. Ventfabrics, Inc.
 9. Ward Industries; a brand of Hart & Cooley, Inc.
- B. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.
- C. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

2.9 MATERIALS

- A. Galvanized Sheet Steel: Comply with ASTM A653/A653M.
1. Galvanized Coating Designation: G90.
 2. Exposed-Surface Finish: Mill phosphatized.
- B. Stainless Steel Sheets: Comply with ASTM A480/A480M, Type 304, and having a No. 2 finish for concealed ducts and <Insert finish designation> finish for exposed ducts.
- C. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless steel ducts.
- D. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch <Insert dimension> minimum diameter for lengths longer than 36 inches.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install duct accessories in accordance with applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116 for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless steel accessories in stainless steel ducts, and aluminum accessories in aluminum ducts.
- C. Where multiple damper sections are necessary to achieve required dimensions, provide reinforcement to fully support damper assembly when fully closed at full system design static pressure.
- D. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
 - 1. Install steel volume dampers in steel ducts.
 - 2. Install aluminum volume dampers in aluminum ducts.
- E. Set dampers to fully open position before testing, adjusting, and balancing.
- F. Install test holes at fan inlets and outlets and elsewhere as indicated and as needed for testing and balancing.
- G. Install fire and smoke dampers in accordance with UL listing.
- H. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
 - 1. On both sides of duct coils.
 - 2. At outdoor-air intakes and mixed-air plenums.
 - 3. At drain pans and seals.
 - 4. Downstream from manual volume dampers, control dampers, backdraft dampers, and equipment.
 - 5. Adjacent to and close enough to fire or smoke dampers, to reset or reinstall fusible links. Access doors for access to fire or smoke dampers having fusible links shall be pressure relief access doors and shall be outward operation for access doors installed upstream from dampers and inward operation for access doors installed downstream from dampers.
 - 6. At each change in direction and at maximum 50-ft. spacing.
 - 7. Upstream from turning vanes.
 - 8. Upstream or downstream from duct silencers.
 - 9. For grease ducts, install at locations and spacing as required by NFPA 96.
 - 10. Control devices requiring inspection.
 - 11. Elsewhere as indicated.
- I. Install access doors with swing against duct static pressure.

- J. Access Door Sizes:
 - 1. One-Hand or Inspection Access: 8 by 5 inches.
 - 2. Two-Hand Access: 12 by 6 inches.
 - 3. Head and Hand Access: 18 by 10 inches.
 - 4. Head and Shoulders Access: 21 by 14 inches.
 - 5. Body Access: 25 by 14 inches.
 - 6. Body plus Ladder Access: 25 by 17 inches.
- K. Label access doors according to Section 23 0553 "Identification for HVAC Piping and Equipment" to indicate the purpose of access door.
- L. Install flexible connectors to connect ducts to equipment.
- M. For fans developing static pressures of 5 inches wg and more, cover flexible connectors with loaded vinyl sheet held in place with metal straps.
- N. Install duct test holes where required for testing and balancing purposes.
- O. Install thrust limits at centerline of thrust, symmetrical on both sides of equipment. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop of fans.

3.2 FIELD QUALITY CONTROL

- A. Tests and Inspections:
 - 1. Operate dampers to verify full range of movement.
 - 2. Inspect locations of access doors, and verify that size and location of access doors are adequate to perform required operation.
 - 3. Inspect turning vanes for proper and secure installation, and verify that vanes do not move or rattle.

END OF SECTION

SECTION 233346 - FLEXIBLE DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Insulated flexible ducts.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For flexible ducts.
 - 1. Include plans showing locations and mounting and attachment details.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from installers of the items involved.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTION

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- C. Comply with the Air Diffusion Council's "ADC Flexible Air Duct Test Code FD 72-R1."
- D. Comply with ASTM E96/E96M, "Test Methods for Water Vapor Transmission of Materials."

2.2 INSULATED FLEXIBLE DUCTS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. Flexmaster U.S.A., Inc.
 2. JP Lamborn Co.
 3. McGill AirFlow LLC
 4. Thermaflex; a Flex-Tek Group company
 5. Ward Industries; a brand of Hart & Cooley, Inc.
- B. Insulated, Flexible Duct: UL 181, Class 1, multiple layers of aluminum laminate supported by helically wound, spring-steel wire; fibrous-glass insulation; aluminized vapor-barrier film.
1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
 2. Maximum Air Velocity: 4000 fpm.
 3. Temperature Range: Minus 20 to plus 210 deg F.
 4. Insulation R-Value: Comply with ASHRAE/IES 90.1.

2.3 FLEXIBLE DUCT CONNECTORS

- A. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action in sizes 3 through 18 inches, to suit duct size.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install flexible ducts according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install in indoor applications only. Flexible ductwork should not be exposed to UV lighting.
- C. Connect diffusers to ducts directly or with maximum 60-inch lengths of flexible duct clamped or strapped in place.
- D. Install duct test holes where required for testing and balancing purposes.
- E. Installation:
1. Install ducts fully extended.
 2. Do not bend ducts across sharp corners.
 3. Bends of flexible ducting shall not exceed a minimum of one duct diameter.
 4. Avoid contact with metal fixtures, water lines, pipes, or conduits.
 5. Install flexible ducts in a direct line, without sags, twists, or turns.
- F. Supporting Flexible Ducts:

1. Suspend flexible ducts with bands 1-1/2 inches wide or wider and spaced a maximum of 48 inches apart. Maximum centerline sag between supports shall not exceed 1/2 inch per 12 inches.
2. Install extra supports at bends placed approximately one duct diameter from center line of the bend.
3. Ducts may rest on ceiling joists or truss supports. Spacing between supports shall not exceed the maximum spacing per manufacturer's written installation instructions.
4. Vertically installed ducts shall be stabilized by support straps at a maximum of 72 inches o.c.

END OF SECTION

SECTION 233416 - CENTRIFUGAL HVAC FANS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Square in-line centrifugal fans.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

- 1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes for fans.
 - 2. Rated capacities, operating characteristics, and furnished specialties and accessories.
 - 3. Certified fan performance curves with system operating conditions indicated.
 - 4. Certified fan sound-power ratings.
 - 5. Motor ratings and electrical characteristics, plus motor and electrical accessories.
 - 6. Material thickness and finishes, including color charts.
 - 7. Dampers, including housings, linkages, and operators.
 - 8. Fan speed controllers.

- B. Shop Drawings:

- 1. Include plans, elevations, sections, and attachment details.
 - 2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 3. Include diagrams for power, signal, and control wiring.
 - 4. Design Calculations: Calculate requirements for selecting vibration isolators and for designing vibration isolation bases.
 - 5. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Fan room layout and relationships between components and adjacent structural and mechanical elements, drawn to scale, and coordinated with each other, using input from installers of the items involved.
- B. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For centrifugal fans to include in normal operation, emergency operation, and maintenance manuals with replacement parts listing.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NFPA Compliance: Comply with NFPA 90A for design, fabrication, and installation of unit components.
- C. ASHRAE 62.1 Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and System Startup."
- D. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

2.2 SQUARE IN-LINE CENTRIFUGAL FANS

- A. Description: Square in-line centrifugal fans.
- B. Housing:
 - 1.Housing Material: Reinforced steel.
 - 2.Housing Coating: None.
 - 3.Housing Construction: Side panels shall be easily removable for service. Include inlet and outlet flanges, and support bracket adaptable to floor, side wall, or ceiling mounting.
- C. Direct-Drive Units: Motor mounted in airstream, factory wired to disconnect switch located on outside of fan housing; with wheel, inlet cone, and motor on swing-out service door.

- D. Belt-Driven Units: Motor mounted on adjustable base, with adjustable sheaves, enclosures around belts within fan housing, and lubricating tubes from fan bearings extended to outside of fan housing.
- E. Fan Wheels: Aluminum airfoil blades welded to aluminum hub.
- F. Motor Enclosure: Totally enclosed, fan cooled.
- G. Accessories:
 - 1. Access for Inspection, Cleaning, and Maintenance: Comply with requirements in ASHRAE 62.1.
 - 2. Variable-Speed Controller: Solid-state control to reduce speed from 100 to less than 50 percent.
 - 3. Volume-Control Damper: Manually operated with quadrant lock, located in fan outlet.
 - 4. Companion Flanges: For inlet and outlet duct connections.
 - 5. Fan Guards: 1/2- by 1-inch mesh of galvanized steel in removable frame. Provide guard for inlet or outlet for units not connected to ductwork.
 - 6. Motor and Drive Cover (Belt Guard): Epoxy-coated steel.
 - 7. Side Discharge: Flange connector and attachment hardware to provide right-angle discharge on side of unit.

2.3 MOTORS

- A. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
- B. Where variable-frequency drives are indicated or scheduled, provide fan motor compatible with variable-frequency drive.

2.4 SOURCE QUALITY CONTROL

- A. AMCA Certification for Fan Sound Performance Rating: Test, rate, and label in accordance with AMCA 311.
- B. AMCA Certification for Fan Aerodynamic Performance Ratings: Test, rate, and label in accordance with AMCA 211.
- C. AMCA Certification for Fan Energy Index (FEI): Test, rate, and label in accordance with AMCA 211.
- D. Operating Limits: Classify fans in accordance with AMCA 99, Section 14.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Install centrifugal fans level and plumb.

- B. Disassemble and reassemble units, as required for moving to the final location, according to manufacturer's written instructions.
- C. Lift and support units with manufacturer's designated lifting or supporting points.
- D. Equipment Mounting:
 - 1. Support duct-mounted and other hanging centrifugal fans directly from the building structure, using suitable hanging systems as specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."
 - 2. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."
- E. Install units with clearances for service and maintenance.
- F. Label fans according to requirements specified in Section 230553 "Identification for HVAC Piping and Equipment."

3.2 DUCTWORK AND PIPING CONNECTIONS

- A. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors. Flexible connectors are specified in Section 233300 "Air Duct Accessories."
- B. Install ducts adjacent to fans to allow service and maintenance.
- C. Install piping from scroll drain connection, with trap with seal equal to 1.5 times specified static pressure, to nearest floor drain with pipe sizes matching the drain connection.

3.3 ELECTRICAL CONNECTIONS

- A. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- B. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."
- C. Install electrical devices furnished by manufacturer, but not factory mounted, according to NFPA 70 and NECA 1.
- D. Install nameplate for each electrical connection, indicating electrical equipment designation and circuit number feeding connection.
 - 1. Nameplate shall be laminated acrylic or melamine plastic signs, as specified in Section 260553 "Identification for Electrical Systems."
 - 2. Nameplate shall be laminated acrylic or melamine plastic signs with a black background and engraved white letters at least 1/2 inch high.

3.4 CONTROL CONNECTIONS

- A. Install control and electrical power wiring to field-mounted control devices.
- B. Connect control wiring according to Section 260523 "Control-Voltage Electrical Power Cables."

3.5 STARTUP SERVICE:

- A. Engage a factory-authorized service representative to perform startup service.
 - 1. Complete installation and startup checks in accordance with manufacturer's written instructions.
 - 2. Verify that shipping, blocking, and bracing are removed.
 - 3. Verify that unit is secure on mountings and supporting devices and that connections to ducts and electrical components are complete. Verify that proper thermal-overload protection is installed in motors, starters, and disconnect switches.
 - 4. Verify that cleaning and adjusting are complete.
 - 5. For direct-drive fans, verify proper motor rotation direction and verify fan wheel free rotation and smooth bearing operation.
 - 6. For belt-drive fans, disconnect fan drive from motor, verify proper motor rotation direction, and verify fan wheel free rotation and smooth bearing operation. Reconnect fan drive system, align and adjust belts, and install belt guards.
 - 7. Adjust belt tension.
 - 8. Adjust damper linkages for proper damper operation.
 - 9. Verify lubrication for bearings and other moving parts.
 - 10. Verify that manual and automatic volume control and fire and smoke dampers in connected ductwork systems are in fully open position.
 - 11. Disable automatic temperature-control operators, energize motor and confirm proper motor rotation and unit operation, adjust fan to indicated rpm, and measure and record motor voltage and amperage.
 - 12. Shut unit down and reconnect automatic temperature-control operators.
 - 13. Remove and replace malfunctioning units and retest as specified above.

3.6 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Adjust belt tension.
- C. Lubricate bearings.
- D. Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC."

3.7 CLEANING

- A. After completing system installation and testing, adjusting, and balancing and after completing startup service, clean fans internally to remove foreign material and construction dirt and dust

3.8 FIELD QUALITY CONTROL

- A. Testing Agency: Contractor will engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections with the assistance of a factory-authorized service representative.
 - 1. Fan Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 3. Fans and components will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

3.9 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain centrifugal fans.

END OF SECTION

SECTION 233600 - AIR TERMINAL UNITS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Shutoff, single-duct air terminal units.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of air terminal unit.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for air terminal units.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

B. Shop Drawings: For air terminal units.

1. Include plans, elevations, sections, and mounting details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.
4. Hangers and supports, including methods for duct and building attachment and vibration isolation.

C. Delegated Design Submittal:

1. Materials, fabrication, assembly, and spacing of hangers and supports.
2. Design Calculations: Calculate requirements for selecting vibration isolators and supports.

1.3 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Floor plans and other details, or BIM model, drawn to scale, indicating the items described in this Section, and coordinated with all building trades.

B. Seismic Qualification Data: For air terminal units, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.

3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Field quality-control reports.

1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For air terminal units to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

- a. Instructions for resetting minimum and maximum air volumes.
- b. Instructions for adjusting software set points.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a Qualified Electrical Testing Laboratory, and marked for intended location and application.
- B. ASHRAE 62.1 Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment," and Section 7 - "Construction and System Start-up."
- C. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, "Section 6 - Heating, Ventilating, and Air Conditioning."

2.2 SHUTOFF, SINGLE-DUCT AIR TERMINAL UNITS

- A. Description: Pressure-dependent, diverting-damper assembly inside unit casing with control components inside a protective metal shroud. Configuration enables variable volume airflow to individual zones while bypassing the unneeded air to the ceiling plenum for recirculation.
- B. Casing: Minimum 22-gauge-thick galvanized steel.
 1. Casing Lining: Adhesive attached, 1-inch-thick, coated, fibrous-glass duct liner complying with ASTM C 1071, and having a maximum flame-spread index of 25 and a maximum smoke-developed index of 50, for both insulation and adhesive, when tested according to ASTM E 84.

C. Diverter Assembly:

1. Damper, shaft, and heavy-duty self-lubricating bearings.

D. Electric-Resistance Heating Coils: Nickel-chromium heating wire, free of expansion noise and hum, mounted in ceramic inserts in a galvanized-steel housing; with primary automatic, and secondary manual, reset thermal cutouts. Terminate elements in stainless steel, machine-staked terminals secured with stainless steel hardware. Provide electric-resistance heating coils for air terminal units scheduled on Drawings.

1. SCR controlled.

2. Access door interlocked disconnect switch.

3. Downstream air temperature sensor with local connection to override discharge-air temperature to not exceed a maximum temperature set point (adjustable).

4. Nickel chrome 80/20 heating elements.

5. Airflow switch for proof of airflow.

6. Fuses in terminal box for overcurrent protection (for coils of more than 48 A).

7. Pneumatic-electric switches and relays.

8. Magnetic contactor for each step of control (for three-phase coils).

E. Direct Digital Controls:

1. Terminal Unit Controller: Pressure-independent, VAV controller and integrated actuator, and electronic airflow transducer with multipoint velocity sensor at air inlet, factory calibrated to minimum and maximum air volumes.

- a. Occupied and unoccupied operating mode.

- b. Remote reset of airflow or temperature set points.

- c. Adjusting and monitoring with portable terminal.

- d. Communication with temperature-control system specified in Section 230923 "Direct Digital Control (DDC) System for HVAC."

2. Room Sensor: Wall mounted with temperature set-point adjustment and access for connection of portable operator terminal.

3. Terminal Unit Controller, Section 230923: Controller is to be factory mounted and wired by air terminal manufacturer; unit controller, actuators, and room sensors are to be furnished under Section 230923 "Direct Digital Control (DDC) System for HVAC."

2.3 SOURCE QUALITY CONTROL

- A. AHRI 880 Certification: Test, rate, and label assembled air terminal units in accordance with AHRI 880.

- B. AHRI 880: Test and rate assembled air terminal units in accordance with AHRI 880.

- C. Water Coils: Factory pressure test to 300 psig in accordance with AHRI 410 and ASHRAE 33.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Comply with Section 230529 "Hangers and Supports for HVAC Piping and Equipment" and Section 233113 "Metal Ducts" for hangers and supports.
- B. Install air terminal units according to NFPA 90A.
- C. Install air terminal units level and plumb. Maintain sufficient clearance for normal service and maintenance.
- D. Install wall-mounted thermostats.

3.2 DUCTWORK CONNECTIONS

- A. Comply with requirements in Section 233113 "Metal Ducts for connecting ducts to air terminal units.
- B. Make connections to air terminal units with flexible connectors complying with requirements in Section 233300 "Air Duct Accessories."

3.3 ELECTRICAL CONNECTIONS

- A. Install field power to each air terminal unit electrical power connection. Coordinate with air terminal unit manufacturer and installers.
- B. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- C. Ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."
- D. Install electrical devices furnished by manufacturer, but not factory mounted, in accordance with NFPA 70 and NECA 1.
- E. Install nameplate for each electrical connection, indicating electrical equipment designation and circuit number feeding connection.
 - 1. Nameplate shall be laminated acrylic or melamine plastic signs, as specified in Section 260553 "Identification for Electrical Systems."
 - 2. Nameplate shall be laminated acrylic or melamine plastic signs with a black background and engraved white letters at least 1/2 inch high.

3.4 CONTROL CONNECTIONS

- A. Install control and electrical power wiring to field-mounted control devices.

- B. Connect control wiring in accordance with Section 260523 "Control-Voltage Electrical Power Cables."

3.5 IDENTIFICATION

- A. Label each air terminal unit with drawing designation, nominal airflow, maximum and minimum factory-set airflows, and coil type. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for equipment labels and warning signs and labels.

3.6 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
 1. Complete installation and startup checks in accordance with manufacturer's written instructions.
 2. Verify that inlet duct connections are as recommended by air terminal unit manufacturer to achieve proper performance.
 3. Verify that controls and control enclosure are accessible.
 4. Verify that control connections are complete.
 5. Verify that nameplate and identification tag are visible.
 6. Verify that controls respond to inputs as specified.

3.7 ADJUSTING

- A. Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC" for air terminal unit testing, adjusting, and balancing.

3.8 FIELD QUALITY CONTROL

- A. Testing Agency: Contractor will engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform the following tests and inspections with the assistance of a factory-authorized service representative:
 1. After installing air terminal units and after electrical circuitry has been energized, test for compliance with requirements.
 2. Leak Test: After installation, fill water coils and test for leaks. Repair leaks and retest until no leaks exist.
 3. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

- D. Air terminal unit will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

3.9 DEMONSTRATION

- A. Train Owner's maintenance personnel to adjust, operate, and maintain air terminal units.

END OF SECTION

SECTION 233713.13 - AIR DIFFUSERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Rectangular and square ceiling diffusers.
- 2. Perforated diffusers.

B. Related Requirements:

- 1. Section 233300 "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers.
- 2. Section 233713.23 "Air Registers and Grilles" for adjustable-bar register and grilles, fixed-face registers and grilles, and linear bar grilles.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

- 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
- 2. Diffuser Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

B. Samples: For each exposed product and for each color and texture specified. Actual size of smallest diffuser indicated.

C. Samples for Initial Selection: For diffusers with factory-applied color finishes. Actual size of smallest diffuser indicated.

D. Samples for Verification: For diffusers, in manufacturer's standard sizes to verify color selected. Actual size of smallest diffuser indicated.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

- 1.Ceiling suspension assembly members.
- 2.Method of attaching hangers to building structure.
- 3.Size and location of initial access modules for acoustical tile.
- 4.Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
- 5.Duct access panels.

- B. Source quality-control reports.

PART 2 - PRODUCTS

2.1 RECTANGULAR AND SQUARE CEILING DIFFUSERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- 1.Krueger-HVAC, a division of Air System Components; Johnson Controls, Inc.
- 2.METALAIRE, Inc.
- 3.Nailor Industries Inc.
- 4.Price Industries
- 5.Shoemaker Mfg. Co.
- 6.Titus, a division of Air System Components; Johnson Controls, Inc.
- 7.Tuttle & Bailey, a division of Air System Components; Johnson Controls, Inc.

- B. Devices shall be specifically designed for variable-air-volume flows.

- C. Material: Steel.

- D. Finish: Baked enamel, white.

- E. Face Size: 24 by 24 inches.

- F. Face Style: Plaque.

- G. Mounting: T-bar.

- H. Pattern: Fixed.

2.2 PERFORATED DIFFUSERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- 1.Krueger-HVAC, a division of Air System Components; Johnson Controls, Inc.
- 2.METALAIRE, Inc.
- 3.Nailor Industries Inc.
- 4.Price Industries
- 5.Shoemaker Mfg. Co.

- 6. Titus, a division of Air System Components; Johnson Controls, Inc.
- 7. Tuttle & Bailey, a division of Air System Components; Johnson Controls, Inc.

- B. Devices shall be specifically designed for variable-air-volume flows.
- C. Material: Steel backpan and pattern controllers, with steel face.
- D. Finish: Baked enamel, white.
- E. Face Size: 24 by 24 inches.
- F. Duct Inlet: Round.
- G. Face Style: Flush.
- H. Mounting: T-bar.
- I. Pattern Controller: None.

2.3 SOURCE QUALITY CONTROL

- A. Verification of Performance: Rate diffusers according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas where diffusers are installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install diffusers level and plumb.
- B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
- C. Install diffusers with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

- A. After installation, adjust diffusers to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION

SECTION 233713.23 - REGISTERS AND GRILLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1.Fixed face registers.

B. Related Requirements:

- 1.Section 233300 "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to registers and grilles.
- 2.Section 233713.13 "Air Diffusers" for various types of air diffusers.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

- 1.Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
- 2.Register and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

B. Samples: For each exposed product and for each color and texture specified. Smallest size register and grille indicated.

C. Samples for Initial Selection: For registers and grilles with factory-applied color finishes. Smallest size register and grille indicated.

D. Samples for Verification: For registers and grilles, in manufacturer's standard sizes to verify color selected. Smallest size register and grille indicated.

1.4 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

- 1.Ceiling suspension assembly members.
- 2.Method of attaching hangers to building structure.

3. Size and location of initial access modules for acoustical tile.
4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
5. Duct access panels.

- B. Source quality-control reports.

PART 2 - PRODUCTS

2.1 REGISTERS

- A. Fixed Face Register:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Krueger-HVAC, a division of Air System Components; Johnson Controls, Inc.
 - b. Nailor Industries Inc.
 - c. Price Industries
 - d. Titus, a division of Air System Components; Johnson Controls, Inc.
 - e. Tuttle & Bailey, a division of Air System Components; Johnson Controls, Inc.
2. Material: Steel.
3. Finish: Baked enamel, white.
4. Face Blade Arrangement: Horizontal spaced 3/4 inch apart.
5. Face Arrangement: Perforated core.
6. Core Construction: Integral.
7. Frame: 1-1/4 inch wide.
8. Mounting: Lay in.
9. Accessory: Filter.

2.2 SOURCE QUALITY CONTROL

- A. Verification of Performance: Rate registers and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas where registers and grilles are installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install registers and grilles level and plumb.
- B. Outlets and Inlets Locations: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
- C. Install registers and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

- A. After installation, adjust registers and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION

SECTION 237416.11 - PACKAGED, SMALL-CAPACITY, ROOFTOP AIR-CONDITIONING UNITS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes: Packaged, small-capacity, rooftop air-conditioning units (RTUs) with the following components:
1. Unit casings.
 2. Fans, drives, and motors.
 3. Coils.
 4. Refrigerant circuit components.
 5. Air filtration.
 6. Dampers.
 7. Electrical power connections.
 8. Controls.
 9. Accessories.

1.2 DEFINITIONS

- A. RTU: Rooftop unit. As used in this Section, this abbreviation means packaged, small-capacity, rooftop air-conditioning units. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground.

1.3 ACTION SUBMITTALS

- A. Product Data: For each RTU.
1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
 2. Include rated capacities, dimensions, required clearances, characteristics, and furnished specialties and accessories.
 3. Include unit dimensions and weight.
 4. Include cabinet material, metal thickness, finishes, insulation, and accessories.
 5. Fans:
 - a. Include certified fan-performance curves with system operating conditions indicated.
 - b. Include certified fan-sound power ratings.
 - c. Include fan construction and accessories.
 - d. Include motor ratings, electrical characteristics, and motor accessories.
 6. Include certified coil-performance ratings with system operating conditions indicated.
 7. Include filters with performance characteristics.
 8. Include dampers, including housings, linkages, and operators.

- B. Shop Drawings: For each packaged, small-capacity, rooftop air-conditioning unit.
 - 1. Include plans, elevations, sections, and mounting details.
 - 2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 3. Include diagrams for power, signal, and control wiring.
- C. Delegated Design Submittals: For RTU supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
 - 1. Include design calculations for selecting vibration isolators and for designing vibration isolation bases.
 - 2. Detail mounting, securing, and flashing of roof curb to roof structure. Indicate coordinating requirements with roof membrane system.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Floor plans and other details, or BIM model, drawn to scale, showing the items described in this Section, and coordinated with all building trades.
- B. Sample Warranty: For manufacturer's warranty.
- C. Product Certificates: Submit certification that specified equipment will withstand wind forces identified in "Performance Requirements" Article and in Section 230548 "Vibration and Seismic Controls for HVAC."
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculations.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of wind force and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- D. Source quality-control reports.
- E. System startup reports.
- F. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For RTUs to include in emergency, operation, and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Filters: One set(s) of filters for each unit.
2. Gaskets: One set(s) for each access door.
3. Fan Belts: One set(s) for each belt-driven fan.

1.7 WARRANTY

- A. Warranty: Manufacturer agrees to repair or replace components of packaged, small-capacity, rooftop air-conditioning unit that fail in materials or workmanship within specified warranty period.

1. Warranty Period: 5 year(s) from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and application.
- B. NFPA Compliance: Comply with NFPA 90A for design, fabrication, and installation of RTUs and components.
- C. ASHRAE 62.1 Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."
- D. ASHRAE 15 Compliance: For refrigeration system safety.
- E. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."
- F. UL Compliance: Comply with UL 1995.

2.2 PACKAGED, SMALL-CAPACITY, ROOFTOP AIR-CONDITIONING UNITS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. AAON.
 2. Addison.
 3. Allied Commercial.
 4. Carrier Global Corporation.
 5. Daikin Applied.
 6. Engineered Air.

7. Lennox Industries, Inc.; Lennox International.
8. Rheem Manufacturing Company; Heating and Cooling Products.
9. Trane.
10. Valent.
11. WaterFurnace International, Inc.
12. YORK; brand of Johnson Controls International plc, Building Solutions North America.

2.3 UNIT CASINGS

- A. General Fabrication Requirements for Casings: Formed and reinforced double-wall insulated panels, fabricated to allow removal for access to internal parts and components, with joints between sections sealed.
- B. Double-Wall Construction:
 1. Outside Casing Wall: Galvanized steel, minimum 18 gauge thick with manufacturer's standard finish, with pitched roof panels and knockouts with grommet seals for electrical and piping connections and lifting lugs.
 2. Inside Casing Wall: G90-coated galvanized steel, 0.034 inch thick.
 3. Floor Plate: G90 galvanized steel, treadplate, minimum 18 gauge thick.
 4. Casing Insulation:
 - a. Materials: Injected polyurethane foam insulation.
 - b. Insulation Thickness: 2 inches.
 - c. Thermal Break: Provide continuity of insulation with no through-casing metal in casing walls, floors, or roof of unit.
- C. Airstream Surfaces: Surfaces in contact with airstream to comply with requirements in ASHRAE 62.1.
- D. Static-Pressure Classifications:
 1. For Unit Sections Upstream of Fans: Minus 3-inch wg.
 2. For Unit Sections Downstream and Including Fans: 3-inch wg.
- E. Panels and Doors:
 1. Panels:
 - a. Fabrication: Formed and reinforced with same materials and insulation thickness as casing.
 - b. Fasteners: Two or more camlock type for panel lift-out operation. Arrangement to allow panels to be opened against air-pressure differential.
 - c. Gasket: Neoprene, applied around entire perimeters of panel frames.
 - d. Size: Large enough to allow inspection and maintenance of air-handling unit's internal components.
 2. Access Doors:

- a. Hinges: A minimum of two ball-bearing hinges or stainless steel piano hinge and two wedge-lever-type latches, operable from inside and outside. Arrange doors to be opened against air-pressure differential.
- b. Gasket: Neoprene, applied around entire perimeters of panel frames.
- c. Size: Large enough to allow inspection and maintenance of air-handling unit's internal components.

3. Locations and Applications:

- a. Fan Section: Doors.
- b. Access Section: Doors.
- c. Coil Section: Inspection and access panels.
- d. Damper Section: Inspection and access panels.
- e. Filter Section: Inspection and access panels.
- f. Mixing Section: Doors.

F. Condensate Drain Pans:

1. Location: Each type of cooling coil.

2. Construction:

- a. Single-wall, stainless steel sheet.

3. Drain Connection:

- a. Located at lowest point of pan and sized to prevent overflow. Terminate with threaded nipple on one end of pan.
- b. Minimum Connection Size: NPS 2.

4. Slope: Minimum 0.125-in./ft. slope, to comply with ASHRAE 62.1, in at least two planes to collect condensate from cooling coils (including coil piping connections, coil headers, and return bends) and from humidifiers and to direct water toward drain connection.

5. Length: Extend drain pan downstream from leaving face for distance to comply with ASHRAE 62.1.

6. Width: Entire width of water producing device.

7. Depth: A minimum of 2 inches deep.

8. Pan-Top Surface Coating for Galvanized-Steel Drain Pans: Asphaltic waterproofing compound.

9. Units with stacked coils must have an intermediate drain pan to collect condensate from top coil.

2.4 FANS, DRIVES, AND MOTORS

- A. Fan and Drive Assemblies: Statically and dynamically balanced and designed for continuous operation at maximum-rated fan speed and motor horsepower.
- B. Supply-Air Fans: Centrifugal, rated according to AMCA 210; galvanized or painted steel; mounted on solid-steel shaft.

1. Shafts: With field-adjustable alignment.

- a. Turned, ground, and polished hot-rolled steel with keyway.
2. Shaft Bearings:
- a. Heavy-duty, self-aligning, pillow-block type with an L-50 rated life of minimum 100,000 hours according to ABMA 9.
3. Housings: Formed- and reinforced-steel panels to form curved scroll housings with shaped cutoff and spun-metal inlet bell.
- a. Bracing: Steel angle or channel supports for mounting and supporting fan scroll, wheel, motor, and accessories.
4. Centrifugal Fan Wheels: Inlet flange, backplate, and shallow blades with inlet and tip curved forward in direction of airflow and mechanically fastened to flange and backplate; steel or aluminum hub swaged to backplate and fastened to shaft with setscrews.
5. Mounting: For internal vibration isolation. Factory-mount fans with manufacturer's standard vibration isolation mounting devices having a minimum static deflection of 1 inch.
6. Shaft Lubrication Lines: Extended to a location outside the casing.
7. Flexible Connector: Factory fabricated with a fabric strip minimum 3-1/2 inches wide, attached to two strips of minimum 2-3/4-inch-wide by 0.028-inch-thick, galvanized-steel sheet.
- a. Flexible Connector Fabric: Glass fabric, double coated with neoprene. Fabrics, coatings, and adhesives to comply with UL 181, Class 1.
- C. Drives, Direct: Factory-mounted, direct drive.
- D. Condenser-Coil Fan: Variable-speed propeller, mounted on shaft of permanently lubricated ECM motors.
- E. Motors:
1. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
 2. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.
 3. Enclosure Type: Open, dripproof.
 4. Enclosure Materials: Cast iron.
 5. Efficiency: Premium efficient as defined in NEMA MG 1.
 6. Motor Pulleys: Adjustable pitch for use with 5-hp motors and smaller; fixed pitch for use with motors larger than 5 hp. Select pulley size so pitch adjustment is at the middle of adjustment range at fan design conditions.
 7. Controllers, Electrical Devices, and Wiring: Comply with requirements for electrical devices and connections specified in electrical Sections.

2.5 COILS

A. General Requirements for Coils:

1. Comply with AHRI 410.
2. Fabricate coils section to allow for removal and replacement of coil for maintenance and to allow in-place access for service and maintenance of coil(s).
3. Coils to not act as structural component of unit.

B. Supply-Air Refrigerant Coil:

1. Tubes: Copper.
2. Fins:
 - a. Material: Aluminum.
3. Fin and Tube Joints: Mechanical bond.
4. Headers: Seamless-copper headers with brazed connections.
5. Frames: Galvanized steel.
6. Coatings: None.
7. Ratings: Designed, tested, and rated according to ASHRAE 33 and AHRI 410.
 - a. Working Pressure: Minimum 300 psig.

C. Hot-Gas Reheat Refrigerant Coil:

1. Tubes: Copper.
2. Fins:
 - a. Material: Aluminum.
3. Fin and Tube Joints: Mechanical bond.
4. Headers: Seamless-copper headers with brazed connections.
5. Frames: Galvanized steel.
6. Coatings: None.
7. Ratings: Designed, tested, and rated according to ASHRAE 33 and AHRI 410.
 - a. Working Pressure: Minimum 300 psig.
8. Suction-discharge bypass valve.

2.6 REFRIGERANT CIRCUIT COMPONENTS

A. Compressor: Hermetic, variable-speed scroll, mounted on vibration isolators; with internal over-current and high-temperature protection, internal pressure relief, and crankcase heater.

B. Refrigeration Specialties:

1. Refrigerant: R-454B.
2. Expansion valve with replaceable thermostatic element.

- 3.Refrigerant filter/dryer.
- 4.Manual-reset high-pressure safety switch.
- 5.Automatic-reset low-pressure safety switch.
- 6.Minimum off-time relay.
- 7.Automatic-reset compressor motor thermal overload.
- 8.Brass service valves installed in compressor suction and liquid lines.
- 9.Low-ambient kit high-pressure sensor.
10. Hot-gas reheat solenoid valve modulating with a replaceable magnetic coil.
11. Hot-gas bypass solenoid valve with a replaceable magnetic coil.
12. Four-way reversing valve with a replaceable magnetic coil, thermostatic expansion valves with bypass check valves, and a suction line accumulator.

2.7 AIR FILTRATION

- A. Particulate air filtration is specified in Section 234100 "Particulate Air Filtration."
- B. Panel Filters:
 - 1.Description: Pleated factory-fabricated, self-supported, disposable air filters with holding frames.
 - 2.Filter Unit Class: UL 900.
 - 3.Media: Interlaced glass, synthetic or cotton fibers coated with nonflammable adhesive and antimicrobial coating.
 - 4.Filter-Media Frame: Beverage board with perforated metal retainer, or metal grid, on outlet side.
- C. Adhesive, Sustainability Projects: As recommended by air-filter manufacturer and with a VOC content of 80 g/L or less.

2.8 DAMPERS

- A. Comply with requirements in Section 230923.12 "Control Dampers."
- B. Outdoor- and Return-Air Dampers: Low-leakage, double-skin, airfoil-blade, galvanized-steel dampers with compressible jamb seals and extruded-vinyl blade edge seals in opposed-blade arrangement with zinc-plated steel operating rods rotating in sintered bronze or nylon bearings mounted in a single galvanized-steel frame, and with operating rods connected with a common linkage. Leakage rate must not exceed 4 cfm/sq. ft. at 1-inch wg and 8 cfm/sq. ft. at 4-inch wg rated in accordance with AMCA 500D.
- C. Barometric relief dampers.
- D. Damper Operators: Comply with requirements in Section 230923.12 "Control Dampers."
- E. Electronic Damper Operators:
 - 1.Direct-coupled type designed for minimum 60,000 full-stroke cycles at rated torque.
 - 2.Electronic damper position indicator to have visual scale indicating percent of travel and 2- to 10-V dc, feedback signal.

3. Operator Motors:

- a. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
- b. Size to operate with sufficient reserve power to provide smooth modulating action or two-position action.
- c. Permanent Split-Capacitor or Shaded-Pole Type: Gear trains completely oil immersed and sealed. Equip spring-return motors with integral spiral-spring mechanism in housings designed for easy removal for service or adjustment of limit switches, auxiliary switches, or feedback potentiometer.

4. Nonspring-Return Motors for Dampers Larger Than 25 Sq. Ft.: Size for running torque of 150 in. x lbf and breakaway torque of 300 in. x lbf.

5. Spring-Return Motors for Dampers Larger Than 25 Sq. Ft.: Size for running and breakaway torque of 150 in. x lbf.

6. Size dampers for running torque calculated as follows:

- a. Parallel-Blade Damper with Edge Seals: 7 inch-lb/sq. ft. of damper.
- b. Opposed-Blade Damper with Edge Seals: 5 inch-lb/sq. ft. of damper.
- c. Parallel-Blade Damper without Edge Seals: 4 inch-lb/sq. ft. of damper.
- d. Opposed-Blade Damper without Edge Seals: 3 inch-lb/sq. ft. of damper.
- e. Dampers with 2- to 3-Inch wg of Pressure Drop or Face Velocities of 1000 to 2500 fpm: Increase running torque by 1.5.
- f. Dampers with 3- to 4-Inch wg of Pressure Drop or Face Velocities of 2500 to 3000 fpm: Increase running torque by 2.0.

7. Coupling: V-bolt and V-shaped, toothed cradle.

8. Overload Protection: Electronic overload or digital rotation-sensing circuitry.

9. Fail-Safe Operation: Mechanical, spring-return mechanism with external, manual gear release on nonspring-return actuators.

10. Power Requirements (Two-Position Spring Return): 120 V ac.

11. Power Requirements (Modulating): Maximum 10 VA at 24 V ac or 8 W at 24 V dc.

12. Proportional Signal: 2 to 10 V dc or 4 to 20 mA, and 2- to 10-V dc position feedback signal.

13. Temperature Rating: Minus 22 to plus 122 deg F.

14. Run Time: 12 seconds open, 5 seconds closed.

2.9 ELECTRICAL POWER CONNECTIONS

- A. RTU to have a single connection of power to unit with unit-mounted disconnect switch accessible from outside unit and control-circuit transformer with built-in overcurrent protection.

2.10 CONTROLS

- A. Control equipment and sequence of operation are specified in Section 230923 "Direct Digital Control (DDC) System for HVAC."
- B. Basic Unit Controls:

1. Control-voltage transformer.
2. Wall-mounted thermostat or sensor with the following features:
 - a. Heat-cool-off switch.
 - b. Fan on-auto switch.
 - c. Fan-speed switch.
 - d. Automatic changeover.
 - e. Adjustable deadband.
 - f. Concealed set point.
 - g. Concealed indication.
 - h. Degree F indication.
 - i. Unoccupied-period-override push button.
 - j. Data entry and access port to input temperature and humidity set points, occupied and unoccupied periods, and output room temperature and humidity, supply-air temperature, operating mode, and status.

3. Wall-mounted humidistat or sensor with the following features:

- a. Concealed set point.
- b. Concealed indication.

4. Annunciator Panel for Each Unit:

- a. Configuration: Remote wall-mounted.
- b. Lights to indicate power on, cooling, heating, fan running, filter dirty, and unit alarm or failure.
- c. DDC controller or programmable timer and interface with HVAC instrumentation and control system.
- d. Digital display of outdoor-air temperature, supply-air temperature, return-air temperature, economizer damper position, indoor-air quality, and control parameters.

C. Controller:

1. Type: DDC.
2. Controller to have volatile-memory backup.
3. Safety Control Operation:
 - a. Smoke Detectors: Stop fan and close outdoor-air damper if smoke is detected. Provide additional contacts for alarm interface to fire-alarm control panel.
 - b. Firestats: Stop fan and close outdoor-air damper if air greater than 130 deg F enters unit. Provide additional contacts for alarm interface to fire-alarm control panel.
 - c. Fire-Alarm Control Panel Interface: Provide control interface to coordinate with operating sequence described in Section 284621.11 "Addressable Fire-Alarm Systems."
 - d. Low-Discharge Temperature: Stop fan and close outdoor-air damper if supply-air temperature is less than 40 deg F.
 - e. Defrost Control for Condenser Coil: Pressure differential switch to initiate defrost sequence.
4. Scheduled Operation: Occupied and unoccupied periods on 365-day clock with a minimum of four programmable periods per day.

5. Unoccupied Period:

- a. Heating Setback: 10 deg F.
- b. Cooling Setback: System off.
- c. Override Operation: Two hours.

6. Supply Fan Operation:

- a. Occupied Periods: Run fan continuously.
- b. Unoccupied Periods: Cycle fan to maintain setback temperature.

7. Refrigerant Circuit Operation:

- a. Occupied Periods: Cycle or stage compressors[, and operate hot-gas bypass] to match compressor output to cooling load to maintain discharge temperature and humidity. Cycle condenser fans to maintain maximum hot-gas pressure. Operate low-ambient control kit to maintain minimum hot-gas pressure.
- b. Unoccupied Periods: Cycle compressors and condenser fans for heating to maintain setback temperature.
- c. Switch reversing valve for heating or cooling mode on air-to-air heat pump.

8. Hot-Gas Reheat-Coil Operation:

- a. Occupied Periods: Humidistat opens hot-gas valve to provide hot-gas reheat, and cycles the compressor.
- b. Unoccupied Periods: Reheat not required.

9. Fixed Minimum Outdoor-Air Damper Operation:

- a. Occupied Periods: Open to 25 percent.
- b. Unoccupied Periods: Close the outdoor-air damper.

10. Economizer Outdoor-Air Damper Operation:

- a. Morning warm-up & cool-down cycles.
- b. Occupied Periods: Open to 10 percent fixed minimum intake, and maximum 100 percent of the fan capacity. Controller is to permit air-side economizer operation when outdoor air is less than 60 deg F. Use outdoor-air enthalpy to adjust mixing dampers. Start relief-air fan with end switch on outdoor-air damper. During economizer cycle operation, lock out cooling.
- c. Unoccupied Periods: Close outdoor-air damper and open return-air damper.
- d. Outdoor-Airflow Monitor: Accuracy maximum plus or minus 5 percent within 15 and 100 percent of total outdoor air. Monitor microprocessor to adjust for temperature, and output to range from 4 to 20 mA.

11. Carbon Dioxide Sensor Operation:

- a. Occupied Periods: Reset minimum outdoor-air ratio down to minimum 10 percent to maintain maximum 1000-ppm concentration.
- b. Unoccupied Periods: Close outdoor-air damper and open return-air damper.

12. Terminal-Unit Relays:

- a. Provide heating- and cooling-mode changeover relays compatible with terminal control system required in Section 233600 "Air Terminal Units" and Section 230923 "Direct Digital Control (DDC) System for HVAC."

D. Interface Requirements for HVAC Instrumentation and Control System:

1. Interface relay for scheduled operation.
2. Interface relay to provide indication of fault at the central workstation and diagnostic code storage.
3. Provide BACnet compatible interface for central HVAC control workstation for the following:
 - a. Adjusting set points.
 - b. Monitoring supply fan start, stop, and operation.
 - c. Inquiring data to include [outdoor-air damper position, supply- and room-air temperature [and humidity].
 - d. Monitoring occupied and unoccupied operations.
 - e. Monitoring constant and variable motor loads.
 - f. Monitoring variable-frequency drive operation.
 - g. Monitoring cooling load.
 - h. Monitoring economizer cycles.
 - i. Monitoring air-distribution static pressure and ventilation air volume.

2.11 ACCESSORIES

- A. Duplex, 115-V, ground-fault-interrupter outlet with 15-A overcurrent protection. Include transformer if required. Outlet is to be energized even if the unit main disconnect is open.
- B. Low-ambient kit using variable-speed condenser fans for operation down to 35 deg F.
- C. Filter differential pressure switch with sensor tubing on either side of filter. Set for final filter pressure loss.
- D. Remote potentiometer to adjust minimum economizer damper position.
- E. Return-air bypass damper.
- F. Factory- or field-installed, demand-controlled ventilation.
- G. Safeties:
 1. Smoke detector.
 2. Condensate overflow switch.
 3. Phase-loss reversal protection.
 4. High and low pressure control.
- H. Coil guards of painted, galvanized-steel wire.

- I. Hail guards of galvanized steel, painted to match casing.
- J. Concentric diffuser with white louvers and polished aluminum return grilles, insulated diffuser box with mounting flanges, and interior transition.
- K. Door switches to disable heating or reset set point when open.
- L. Outdoor-air intake weather hood.
- M. Service Lights and Switch: Factory installed in each accessible section with weatherproof cover. Factory wire lights to a single-point field connection.

2.12 MATERIALS

- A. Steel:
 - 1. ASTM A36/A36M for carbon structural steel.
 - 2. ASTM A568/A568M for steel sheet.
- B. Stainless Steel:
 - 1. Manufacturer's standard grade for casing.
 - 2. Manufacturer's standard type, ASTM A240/A240M for bare steel exposed to airstream or moisture.
- C. Galvanized Steel: ASTM A653/A653M.
- D. Aluminum: ASTM B209.
- E. Comply with Section 230546 "Coatings for HVAC" for corrosion-resistant coating.

2.13 SOURCE QUALITY CONTROL

- A. AHRI Compliance:
 - 1. Comply with AHRI 210/240 for testing and rating energy efficiencies for RTUs.
 - 2. Comply with AHRI 340/360 for testing and rating energy efficiencies for RTUs.
 - 3. Comply with AHRI 270 for testing and rating sound performance for RTUs.
 - 4. Comply with AHRI 1060 for testing and rating performance for air-to-air exchanger.
- B. AMCA Compliance:
 - 1. Comply with AMCA 11 and bear the AMCA-Certified Ratings Seal for air and sound performance according to AMCA 211 and AMCA 311.
 - 2. Damper leakage tested according to AMCA 500-D.
 - 3. Operating Limits: Classify according to AMCA 99.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of RTUs.
- B. Examine roughing-in for RTUs to verify actual locations of piping and duct connections before equipment installation.
- C. Examine roofs for suitable conditions where RTUs will be installed.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Unit Support: Install unit level on concrete pad. Coordinate wall penetrations and flashing with wall construction. Secure RTUs to structural support with anchor bolts.
- B. Equipment Mounting:
 - 1. Install RTUs on cast-in-place concrete equipment bases. Comply with requirements for equipment bases and foundations specified in Section 033000 "Cast-in-Place Concrete."
 - 2. Comply with requirements for vibration isolation and seismic-control devices specified in Section 230548 "Vibration and Seismic Controls for HVAC."
 - 3. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."

3.3 PIPING CONNECTIONS

- A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Where installing piping adjacent to RTU, allow space for service and maintenance.
- C. Connect piping to unit mounted on vibration isolators with flexible connectors.
- D. Connect condensate drain pans using NPS 1-1/4, ASTM B88, Type M copper tubing. Extend to nearest equipment or roof drain. Construct deep trap at connection to drain pan and install cleanouts at changes in direction.
- E. Refrigerant Piping: Comply with applicable requirements in Section 232300 "Refrigerant Piping." Install shutoff valve and union or flange at each supply and return connection.

3.4 DUCT CONNECTIONS

- A. Comply with duct installation requirements specified in other HVAC Sections. Drawings indicate general arrangement of ducts. The following are specific connection requirements:

1. Install ducts to termination at top of roof curb.
2. Remove roof decking only as required for passage of ducts. Do not cut out decking under entire roof curb.
3. Connect supply ducts to RTUs with flexible duct connectors specified in Section 233300 "Air Duct Accessories."
4. Install return-air duct continuously through roof structure.

3.5 ELECTRICAL CONNECTIONS

- A. Connect electrical wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- B. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."
- C. Install electrical devices furnished by manufacturer, but not factory mounted, according to NFPA 70 and NECA 1.
- D. Install nameplate for each electrical connection, indicating electrical equipment designation and circuit number feeding connection.
 1. Nameplate is to be laminated acrylic or melamine plastic signs as specified in Section 260553 "Identification for Electrical Systems."
 2. Nameplate is to be laminated acrylic or melamine plastic signs as layers of black with engraved white letters at least 1/2 inch high.
 3. Locate nameplate where easily visible.

3.6 CONTROL CONNECTIONS

- A. Install control and electrical power wiring to field-mounted control devices.
- B. Connect control wiring according to Section 260523 "Control-Voltage Electrical Power Cables."

3.7 STARTUP SERVICE

- A. [Engage a factory-authorized service representative to perform] [Perform] startup service.
 1. Complete installation and startup checks according to manufacturer's written instructions.
 2. Inspect for visible damage to unit casing.
 3. Inspect for visible damage to furnace combustion chamber.
 4. Inspect for visible damage to compressor, coils, and fans.
 5. Inspect internal insulation.
 6. Verify that labels are clearly visible.
 7. Verify that clearances have been provided for servicing.
 8. Verify that controls are connected and operable.
 9. Verify that filters are installed.
 10. Clean condenser coil and inspect for construction debris.
 11. Clean furnace flue and inspect for construction debris.

12. Connect and purge gas line.
13. Remove packing from vibration isolators.
14. Inspect operation of barometric relief dampers.
15. Verify lubrication on fan and motor bearings.
16. Inspect fan-wheel rotation for movement in correct direction without vibration and binding.
17. Adjust fan belts to proper alignment and tension.
18. Start unit according to manufacturer's written instructions.
 - a. Start refrigeration system.
 - b. Do not operate below recommended low-ambient temperature.
 - c. Complete startup sheets and attach copy with Contractor's startup report.
19. Inspect and record performance of interlocks and protective devices; verify sequences.
20. Operate unit for an initial period as recommended or required by manufacturer.
21. Perform the following operations for both minimum and maximum firing. Adjust burner for peak efficiency:
 - a. Measure gas pressure on manifold.
 - b. Inspect operation of power vents.
 - c. Measure combustion-air temperature at inlet to combustion chamber.
 - d. Measure supply-air temperature and volume when burner is at maximum firing rate and when burner is off. Calculate useful heat to supply air.
22. Calibrate thermostats.
23. Adjust and inspect high-temperature limits.
24. Inspect outdoor-air dampers for proper stroke and interlock with return-air dampers.
25. Start refrigeration system and measure and record the following when ambient is a minimum of 15 deg F above return-air temperature:
 - a. Coil leaving-air, dry- and wet-bulb temperatures.
 - b. Coil entering-air, dry- and wet-bulb temperatures.
 - c. Outdoor-air, dry-bulb temperature.
 - d. Outdoor-air-coil, discharge-air, dry-bulb temperature.
26. Inspect controls for correct sequencing of heating, mixing dampers, refrigeration, and normal and emergency shutdown.
27. Measure and record the following minimum and maximum airflows. Plot fan volumes on fan curve.
 - a. Supply-air volume.
 - b. Return-air volume.
 - c. Relief-air volume.
 - d. Outdoor-air intake volume.
28. Simulate maximum cooling demand and inspect the following:
 - a. Compressor refrigerant suction and hot-gas pressures.
 - b. Short circuiting of air through condenser coil or from condenser fans to outdoor-air intake.

29. Verify operation of remote panel including pilot-light operation and failure modes. Inspect the following:
 - a. Low-temperature safety operation.
 - b. Filter high-pressure differential alarm.
 - c. Economizer to minimum outdoor-air changeover.
 - d. Relief-air fan operation.
 - e. Smoke and firestat alarms.
30. After startup and performance testing and prior to Final Acceptance, replace existing filters with new filters.

3.8 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC" for air-handling system testing, adjusting, and balancing.
- C. Occupancy Adjustments: When requested within 12 months from date of Final Acceptance, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.9 CLEANING

- A. After completing system installation and testing, adjusting, and balancing RTUs and air-distribution systems, clean RTUs internally to remove foreign material and construction dirt and dust. Clean fan wheels, cabinets, dampers, coils, and filter housings, and install new, clean filters.

3.10 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections with the assistance of a factory-authorized service representative.
- D. Tests and Inspections:
 1. After installing RTUs and after electrical circuitry has been energized, test units for compliance with requirements.
 2. Inspect for and remove shipping bolts, blocks, and tie-down straps.
 3. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

- E. RTU will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.

3.11 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain RTUs.

END OF SECTION

SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Copper building wire.
 - 2. Fire-alarm wire and cable.
 - 3. Connectors and splices.

1.3 DEFINITIONS

- A. RoHS: Restriction of Hazardous Substances.
- B. VFC: Variable-frequency controller.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Product Schedule: Indicate type, use, location, and termination locations.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Member company of NETA.
 - 1. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.
 - 2. Power conductors and cables shall be listed by an approved third-party testing agency accredited by the North Carolina Building Code Council (<https://www.ncosfm.gov/third-party-testing-agencies/open>)

PART 2 - PRODUCTS

2.1 COPPER BUILDING WIRE

- A. Description: Flexible, insulated and uninsulated, drawn copper current-carrying conductor with an overall insulation layer or jacket, or both, rated 600 V or less.
- B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Alpha Wire; brand of Belden, Inc.
 - 2. Belden Inc.
 - 3. Cerro Wire LLC.
 - 4. Encore Wire Corporation.
 - 5. General Cable; Prysmian Group North America.
 - 6. Okonite Company (The).
 - 7. Service Wire Co.
 - 8. Southwire Company, LLC.
 - 9. WESCO.
- C. Standards:
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
 - 2. RoHS compliant.
 - 3. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."
- D. Conductors: Copper, complying with ASTM B3 for bare annealed copper and with ASTM B8 for stranded conductors.
- E. Conductor Insulation:
 - 1. Type THHN and Type THWN-2: Comply with UL 83.
 - 2. Type XHHW-2: Comply with UL 44.

2.2 FIRE-ALARM WIRE AND CABLE

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Allied Wire & Cable Inc.
 - 2. CommScope, Inc.
 - 3. Comtran Corporation.
 - 4. Genesis; Resideo Technologies, Inc.
 - 5. PYROTENAX; brand of nVent Electrical plc.
 - 6. Prysmian Cables and Systems; Prysmian Group North America.
 - 7. Radix Wire.
 - 8. Rockbestos-Suprenant Cable Corp.
 - 9. Superior Essex Inc.; subsidiary of LS Corp.

10. West Penn Wire; brand of Belden, Inc.
 11. Cerro Wire LLC.
- B. General Wire and Cable Requirements: NRTL listed and labeled as complying with NFPA 70, Article 760.
- C. Signaling Line Circuits: Twisted, shielded pair, not less than No. 18 AWG.
1. Circuit Integrity Cable: Twisted shielded pair, NFPA 70, Article 760, Classification CI, for power-limited fire-alarm signal service Type FPL. NRTL listed and labeled as complying with UL 1424 and UL 2196 for a two-hour rating.
- D. Non-Power-Limited Circuits: Solid-copper conductors with 600-V rated, 75 deg C, color-coded insulation, and complying with requirements in UL 2196 for a two-hour rating.
1. Low-Voltage Circuits: No. 16 AWG, minimum, in pathway.
 2. Line-Voltage Circuits: No. 12 AWG, minimum, in pathway.
 3. Multiconductor Armored Cable: NFPA 70, Type MC, copper conductors, Type TFN/THHN conductor insulation, copper drain wire, copper armor with outer jacket with red identifier stripe, NRTL listed for fire-alarm and cable tray installation, plenum rated.

2.3 CONNECTORS AND SPLICES

- A. Description: Factory-fabricated connectors, splices, and lugs of size, ampacity rating, material, type, and class for application and service indicated; listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
- B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. 3M Electrical Products.
 2. ABB, Electrification Business.
 3. AFC Cable Systems; Atkore International.
 4. Gardner Bender.
 5. Hubbell Utility Solutions; Hubbell Incorporated.
 6. ILSCO.
 7. Ideal Industries, Inc.
 8. NSi Industries LLC.
 9. O-Z/Gedney; brand of Emerson Electric Co., Automation Solutions, Appleton Group.
 10. Service Wire Co.
 11. TE Connectivity Ltd.
 12. Burndy; brand of Hubbell Electrical Solutions; Hubbell Incorporated.
- C. Jacketed Cable Connectors: For steel and aluminum jacketed cables, zinc die-cast with set screws, designed to connect conductors specified in this Section.
- D. Lugs: One piece, seamless, designed to terminate conductors specified in this Section.
1. Material: Copper.
 2. Type: One hole with standard barrels.

3.Termination: Compression.

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL APPLICATIONS

A. Feeders:

- 1.Copper; solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- 2.Copper for feeders smaller than No. 4 AWG; copper or aluminum for feeders No. 4 AWG and larger. Conductors shall be solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.

B. Branch Circuits:

- 1.Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- 2.Copper. Solid for No. 12 AWG and smaller; stranded for No. 10 AWG and larger.

C. VFC Output Circuits Cable: Extra-flexible stranded for all sizes.

D. Power-Limited Fire Alarm and Control: Solid for No. 12 AWG and smaller.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Service Entrance: Type THHN/THWN-2, single conductors in raceway or Type XHHW-2, single conductors in raceway.
- B. Exposed Feeders: Type THHN/THWN-2, single conductors in raceway, or Type XHHW-2, single conductors in raceway.
- C. Feeders Concealed in Ceilings, Walls, Partitions, and Crawlspace: Type THHN/THWN-2, single conductors in raceway or Metal-clad cable, Type MC.
- D. Feeders Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN/THWN-2, single conductors in raceway or Type XHHW-2, single conductors in raceway.
- E. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN/THWN-2, single conductors in raceway or Metal-clad cable, Type MC.
- F. Branch Circuits Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN/THWN-2, single conductors in raceway or Type XHHW-2, single conductors in raceway.

3.3 INSTALLATION, GENERAL

- A. Conceal cables in finished walls, ceilings, and floors unless otherwise indicated.

- B. Complete raceway installation between conductor and cable termination points according to Section 260533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.
- C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."
- G. Complete cable tray systems installation according to Section 260536 "Cable Trays for Electrical Systems" prior to installing conductors and cables.

3.4 INSTALLATION OF FIRE-ALARM WIRE AND CABLE

- A. Comply with NECA 1 and NFPA 72.
- B. Wiring Method: Install wiring in metal pathway according to Section 270528.29 "Hangers and Supports for Communications Systems."
 - 1. Install plenum cable in environmental airspaces, including plenum ceilings.
 - 2. Fire-alarm circuits and equipment control wiring associated with fire-alarm system shall be installed in a dedicated pathway system.
 - a. Cables and pathways used for fire-alarm circuits, and equipment control wiring associated with fire-alarm system, may not contain any other wire or cable.
 - 3. Fire-Rated Cables: Use of two-hour, fire-rated fire-alarm cables, NFPA 70, Types MI and CI, is not permitted.
 - 4. Signaling Line Circuits: Power-limited fire-alarm cables shall not be installed in the same cable or pathway as signaling line circuits.
- C. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with fire-alarm system to terminal blocks. Mark each terminal according to system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.
- D. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes; cabinets; or equipment enclosures where circuit connections are made.

- E. Color-Coding: Color-code fire-alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and another for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire-alarm system junction boxes and covers red.
- F. Risers: Install at least two vertical cable risers to serve the fire-alarm system. Separate risers in close proximity to each other with a minimum one-hour-rated wall, so the loss of one riser does not prevent receipt or transmission of signals from other floors or zones.
- G. Wiring to Remote Alarm Transmitting Device: 1-inch conduit between the fire-alarm control panel and the transmitter. Install number of conductors and electrical supervision for connecting wiring as needed to suit monitoring function.

3.5 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- B. Make splices, terminations, and taps that are compatible with conductor material.
 - 1. Use oxide inhibitor in each splice, termination, and tap for aluminum conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least [6 inches] [12 inches] of slack.
- D. Comply with requirements in Section 284621.11 "Addressable Fire-Alarm Systems" for connecting, terminating, and identifying wires and cables.

3.6 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

3.7 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

3.8 FIRESTOPPING

- A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Section 078413 "Penetration Firestopping."

3.9 FIELD QUALITY CONTROL

A. Administrant for Tests and Inspections:

1. Owner will engage qualified testing agency to administer and perform tests and inspections.
2. Engage qualified testing agency to administer and perform tests and inspections.
3. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.
4. Administer and perform tests and inspections with assistance of factory-authorized service representative.

B. Tests and Inspections:

1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors for compliance with requirements.
2. Perform each of the following visual and electrical tests:
 - a. Inspect exposed sections of conductor and cable for physical damage and correct connection according to the single-line diagram.
 - b. Test bolted connections for high resistance using one of the following:
 - 1) A low-resistance ohmmeter.
 - 2) Calibrated torque wrench.
 - 3) Thermographic survey.
 - c. Inspect compression-applied connectors for correct cable match and indentation.
 - d. Inspect for correct identification.
 - e. Inspect cable jacket and condition.
 - f. Insulation-resistance test on each conductor for ground and adjacent conductors. Apply a potential of 500-V dc for 300-V rated cable and 1000-V dc for 600-V rated cable for a one-minute duration.
 - g. Continuity test on each conductor and cable.
 - h. Uniform resistance of parallel conductors.
3. Initial Infrared Scanning: After Final Acceptance, but before Final Acceptance, perform an infrared scan of each splice in conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner. Correct deficiencies determined during the scan.
 - a. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - b. Record of Infrared Scanning: Prepare a certified report that identifies switches checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
4. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each switch 11 months after date of Final Acceptance.

C. Cables will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports to record the following:

- 1.Procedures used.
- 2.Results that comply with requirements.
- 3.Results that do not comply with requirements, and corrective action taken to achieve compliance with requirements.

END OF SECTION

SECTION 260526 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes grounding and bonding systems and equipment.
- B. Section includes grounding and bonding systems and equipment, plus the following special applications:
 - 1. Underground distribution grounding.
 - 2. Foundation steel electrodes.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Plans showing dimensioned locations of grounding features specified in "Field Quality Control" Article, including the following:
 - 1. Test wells.
 - 2. Ground rods.
 - 3. Ground rings.
 - 4. Grounding arrangements and connections for separately derived systems.
- B. Qualification Data: For testing agency and testing agency's field supervisor.
- C. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For grounding to include in emergency, operation, and maintenance manuals.
 - 1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

- a. Plans showing as-built, dimensioned locations of system described in "Field Quality Control" Article, including the following:
 - 1) Test wells.
 - 2) Ground rods.
 - 3) Ground rings.
 - 4) Grounding arrangements and connections for separately derived systems.
- b. Instructions for periodic testing and inspection of grounding features at test wells based on NFPA 70B.
 - 1) Tests shall determine if ground-resistance or impedance values remain within specified maximums, and instructions shall recommend corrective action if values do not.
 - 2) Include recommended testing intervals.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Certified by NETA.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with UL 467 for grounding and bonding materials and equipment.

2.2 CONDUCTORS

- A. Insulated Conductors: Copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.
- B. Bare Copper Conductors:
 1. Solid Conductors: ASTM B3.
 2. Stranded Conductors: ASTM B8.
 3. Tinned Conductors: ASTM B33.
 4. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG conductor, 1/4 inch in diameter.
 5. Bonding Conductor: No. 4 or No. 6 AWG, stranded conductor.
 6. Bonding Jumper: Copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.
 7. Tinned Bonding Jumper: Tinned-copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.

- C. Grounding Bus: Predrilled rectangular bars of annealed copper, **1/4 by 4 inches** in cross section, with 9/32-inch holes spaced 1-1/8 inches apart. Stand-off insulators for mounting shall comply with UL 891 for use in switchboards, 600 V and shall be Lexan or PVC, impulse tested at 5000 V.

2.3 CONNECTORS

- A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction for applications in which used and for specific types, sizes, and combinations of conductors and other items connected.
- B. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.
- C. Bus-Bar Connectors: Mechanical type, cast silicon bronze, solderless compression-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.
- D. Bus-Bar Connectors: Compression type, copper or copper alloy, with two wire terminals.
- E. Beam Clamps: Mechanical type, terminal, ground wire access from four directions, with dual, tin-plated or silicon bronze bolts.
- F. Cable-to-Cable Connectors: Compression type, copper or copper alloy.
- G. Conduit Hubs: Mechanical type, terminal with threaded hub.
- H. Ground Rod Clamps: Mechanical type, copper or copper alloy, terminal with hex head bolt.
- I. Lay-in Lug Connector: Mechanical type, copper rated for direct burial terminal with set screw.
- J. Signal Reference Grid Clamp: Mechanical type, stamped-steel terminal with hex head screw.
- K. Straps: Solid copper, copper lugs. Rated for 600 A.
- L. Tower Ground Clamps: Mechanical type, copper or copper alloy, terminal one-piece clamp.
- M. U-Bolt Clamps: Mechanical type, copper or copper alloy, terminal listed for direct burial.
- N. Water Pipe Clamps:
 - 1. Mechanical type, two pieces with stainless-steel bolts.
 - a. Material: Tin-plated aluminum.
 - b. Listed for direct burial.
 - 2. U-bolt type with malleable-iron clamp and copper ground connector.

2.4 GROUNDING ELECTRODES

- A. Ground Rods: Copper-clad; 3/4 inch by 10 feet.

- B. Chemical-Enhanced Grounding Electrodes: Copper tube, straight or L-shaped, charged with non-hazardous electrolytic chemical salts.
 - 1. Termination: Factory-attached No. 4/0 AWG bare conductor at least 48 inches long.
 - 2. Backfill Material: Electrode manufacturer's recommended material.
- C. Ground Plates: 1/4 inch thick, hot-dip galvanized.

PART 3 - EXECUTION

3.1 APPLICATIONS

- A. Conductors: Install solid conductor for No. 10 AWG and smaller, and stranded conductors for No. 8 AWG and larger unless otherwise indicated.
- B. Underground Grounding Conductors: Install bare copper conductor, No. 2/0 AWG minimum.
 - 1. Bury at least 30 inches below grade.
 - 2. Duct-Bank Grounding Conductor: Bury 12 inches above duct bank when indicated as part of duct-bank installation.
- C. Grounding Conductors: Green-colored insulation with continuous yellow stripe.
- D. Isolated Grounding Conductors: Green-colored insulation with more than one continuous yellow stripe. On feeders with isolated ground, identify grounding conductor where visible to normal inspection, with alternating bands of green and yellow tape, with at least three bands of green and two bands of yellow.
- E. Grounding Bus: Install in electrical equipment rooms, in rooms housing service equipment, and elsewhere as indicated.
 - 1. Install bus horizontally, on insulated spacers 2 inches minimum from wall, 6 inches above finished floor unless otherwise indicated.
 - 2. Where indicated on both sides of doorways, route bus up to top of door frame, across top of doorway, and down; connect to horizontal bus.
- F. Conductor Terminations and Connections:
 - 1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
 - 2. Underground Connections: Welded connectors except at test wells and as otherwise indicated.
 - 3. Connections to Ground Rods at Test Wells: Bolted connectors.
 - 4. Connections to Structural Steel: Welded connectors.

3.2 GROUNDING AT THE SERVICE

- A. Equipment grounding conductors and grounding electrode conductors shall be connected to the ground bus. Install a main bonding jumper between the neutral and ground buses.

3.3 GROUNDING SEPARATELY DERIVED SYSTEMS

- A. Generator: Install grounding electrode(s) at the generator location. The electrode shall be connected to the equipment grounding conductor and to the frame of the generator.

3.4 GROUNDING UNDERGROUND DISTRIBUTION SYSTEM COMPONENTS

- A. Comply with IEEE C2 grounding requirements.

3.5 EQUIPMENT GROUNDING

- A. Install insulated equipment grounding conductors with all feeders and branch circuits.
- B. Install insulated equipment grounding conductors with the following items, in addition to those required by NFPA 70:
 - 1. Feeders and branch circuits.
 - 2. Lighting circuits.
 - 3. Receptacle circuits.
 - 4. Single-phase motor and appliance branch circuits.
 - 5. Three-phase motor and appliance branch circuits.
 - 6. Flexible raceway runs.
 - 7. Armored and metal-clad cable runs.
- C. Air-Duct Equipment Circuits: Install insulated equipment grounding conductor to duct-mounted electrical devices operating at 120 V and more, including air cleaners, heaters, dampers, humidifiers, and other duct electrical equipment. Bond conductor to each unit and to air duct and connected metallic piping.
- D. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install a separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.
- E. Poles Supporting Outdoor Lighting Fixtures: Install grounding electrode and a separate insulated equipment grounding conductor in addition to grounding conductor installed with branch-circuit conductors.
- F. Metallic Fences: Comply with requirements of IEEE C2.
 - 1. Grounding Conductor: Bare, copper, not less than No. 8 AWG.
 - 2. Gates: Shall be bonded to the grounding conductor with a flexible bonding jumper.
 - 3. Barbed Wire: Strands shall be bonded to the grounding conductor.

3.6 INSTALLATION

- A. Grounding Conductors: Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.

- B. Ground Bonding Common with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest point to electrical service grounding electrode. Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.
- C. Ground Rods: Drive rods until tops are 2 inches below finished floor or final grade unless otherwise indicated.
1. Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating if any.
 2. Use exothermic welds for all below-grade connections.
 3. For grounding electrode system, install at least three rods spaced at least one-rod length from each other and located at least the same distance from other grounding electrodes, and connect to the service grounding electrode conductor.
- D. Test Wells: Ground rod driven through drilled hole in bottom of handhole. Handholes are specified in Section 260543 "Underground Ducts and Raceways for Electrical Systems," and shall be at least 12 inches deep, with cover.
1. Install at least one test well for each service unless otherwise indicated. Install at the ground rod electrically closest to service entrance. Set top of test well flush with finished grade or floor.
- E. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance except where routed through short lengths of conduit.
1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
 2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.
 3. Use exothermic-welded connectors for outdoor locations; if a disconnect-type connection is required, use a bolted clamp.
- F. Grounding and Bonding for Piping:
1. Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes; use a bolted clamp connector or bolt a lug-type connector to a pipe flange by using one of the lug bolts of the flange. Where a dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
 2. Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with a bolted connector.
 3. Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.
- G. Bonding Interior Metal Ducts: Bond metal air ducts to equipment grounding conductors of associated fans, blowers, electric heaters, and air cleaners. Install [**tinned**] bonding jumper to bond across flexible duct connections to achieve continuity.

- H. Grounding for Steel Building Structure: Install a driven ground rod at base of each corner column and at intermediate exterior columns at distances not more than 60 feet apart.
- I. Connections: Make connections so possibility of galvanic action or electrolysis is minimized. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact are galvanically compatible.
 - 1. Use electroplated or hot-tin-coated materials to ensure high conductivity and to make contact points closer in order of galvanic series.
 - 2. Make connections with clean, bare metal at points of contact.
 - 3. Make aluminum-to-steel connections with stainless-steel separators and mechanical clamps.
 - 4. Make aluminum-to-galvanized-steel connections with tin-plated copper jumpers and mechanical clamps.
 - 5. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.

3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections with the assistance of a factory-authorized service representative.
- E. Tests and Inspections:
 - 1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
 - 2. Inspect physical and mechanical condition. Verify tightness of accessible, bolted, electrical connections with a calibrated torque wrench according to manufacturer's written instructions.
 - 3. Test completed grounding system at each location where a maximum ground-resistance level is specified, at service disconnect enclosure grounding terminal, at ground test wells. Make tests at ground rods before any conductors are connected.
 - a. Measure ground resistance no fewer than two full days after last trace of precipitation and without soil being moistened by any means other than natural drainage or seepage and without chemical treatment or other artificial means of reducing natural ground resistance.
 - b. Perform tests by fall-of-potential method according to IEEE 81.
 - 4. Prepare dimensioned Drawings locating each test well, ground rod and ground-rod assembly, and other grounding electrodes. Identify each by letter in alphabetical order, and key to the record of tests and observations. Include the number of rods driven and their depth at each location, and include observations of weather and other phenomena that may affect test results. Describe measures taken to improve test results.

- F. Grounding system will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.
- H. Report measured ground resistances that exceed the following values:
 - 1. Power and Lighting Equipment or System with Capacity of 500 kVA and Less: 10 ohms.
 - 2. Power and Lighting Equipment or System with Capacity of 500 to 1000 kVA: 5 ohms.
- I. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Architect promptly and include recommendations to reduce ground resistance.

END OF SECTION

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Steel slotted support systems.
2. Conduit and cable support devices.
3. Support for conductors in vertical conduit.
4. Structural steel for fabricated supports and restraints.
5. Mounting, anchoring, and attachment components, including mechanical expansion anchors, concrete inserts, clamps, through bolts, toggle bolts, and hanger rods.
6. Fabricated metal equipment support assemblies.

B. Related Requirements:

1. Section 260548.16 "Seismic Controls for Electrical Systems" for products and installation requirements necessary for compliance with seismic criteria.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:

- a. Slotted support systems, hardware, and accessories.
- b. Clamps.
- c. Hangers.
- d. Sockets.
- e. Eye nuts.
- f. Fasteners.
- g. Anchors.
- h. Saddles.
- i. Brackets.

2. Include rated capacities and furnished specialties and accessories.

- B. Shop Drawings: Signed and sealed by a qualified professional engineer. For fabrication and installation details for electrical hangers and support systems.

1. Hangers. Include product data for components.
2. Slotted support systems.
3. Equipment supports.
4. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.

C. Delegated-Design Submittal: For hangers and supports for electrical systems.

1. Include design calculations and details of hangers.
2. Include design calculations for seismic restraints.

1.4 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Suspended ceiling components.
2. Ductwork, piping, fittings, and supports.
3. Structural members to which hangers and supports will be attached.
4. Size and location of initial access modules for acoustical tile.
5. Items penetrating finished ceiling, including the following:

- a. Luminaires.
- b. Air outlets and inlets.
- c. Speakers.
- d. Sprinklers.
- e. Access panels.
- f. Projectors.

B. Seismic Qualification Data: Certificates, for hangers and supports for electrical equipment and systems, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Welding certificates.

1.5 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M.

B. Welding Qualifications: Qualify procedures and personnel according to the following:

- 1.AWS D1.1/D1.1M.
- 2.AWS D1.2/D1.2M.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design hanger and support system.
 - 1.Engineer of delegated designed shall be licensed in North Carolina and shall seal the design.
- B. Seismic Performance: Hangers and supports shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 - 1.The term "withstand" means "the supported equipment and systems will remain in place without separation of any parts when subjected to the seismic forces specified and the supported equipment and systems will be fully operational after the seismic event."
 - 2.Component Importance Factor: 1.5.
- C. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1.Flame Rating: Class 1.
 - 2.Self-extinguishing according to ASTM D635.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Preformed steel channels and angles with minimum 13/32-inch-diameter holes at a maximum of 8 inches o.c. in at least one surface.
 - 1.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. ABB, Electrification Business.
 - b. Allied Tube & Conduit; Atkore International.
 - c. Atkore Unistrut.
 - d. B-Line; a division of Eaton, Electrical Sector.
 - e. CADDY; brand of nVent Electrical plc.
 - f. Flex-Strut Inc.
 - g. G-Strut.
 - h. Gripple Inc.
 - i. Haydon Corporation.
 - j. MIRO Industries Inc.
 - k. Metal Ties Innovation.
 - l. Rocket Rack; Robroy Industries.
 - m. Wesanco/ZSi-Foster; an Ideal Tridon Group Company.

2. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
 3. Material for Channel, Fittings, and Accessories: Stainless steel, Type 304.
 4. Channel Width: **1-5/8 inches**.
 5. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
 6. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.
 7. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
 8. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Conduit and Cable Support Devices: Stainless-steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- C. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for nonarmored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be made of malleable iron.
- D. Structural Steel for Fabricated Supports and Restraints: ASTM A36/A36M steel plates, shapes, and bars; black and galvanized.
- E. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
1. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1) B-Line; a division of Eaton, Electrical Sector.
 - 2) Empire Industries, Inc.
 - 3) Hilti, Inc.
 - 4) ITW Ramset/Red Head; Illinois Tool Works, Inc.
 - 5) MKT Fastening, LLC.
 2. Concrete Inserts: Steel or malleable-iron, slotted support system units are similar to MSS Type 18 units and comply with MFMA-4 or MSS SP-58.
 3. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
 4. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM F3125/F3125M, Grade A325.
 5. Toggle Bolts: Stainless-steel springhead type.
 6. Hanger Rods: Threaded steel.

2.3 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.
- B. Materials: Comply with requirements in Section 055000 "Metal Fabrications" for steel shapes and plates.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with the following standards for application and installation requirements of hangers and supports, except where requirements on Drawings or in this Section are stricter:
 - 1.NECA 1.
 - 2.NECA 101
 - 3.NECA 102.
 - 4.NECA 105.
 - 5.NECA 111.
- B. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping materials and installation for penetrations through fire-rated walls, ceilings, and assemblies.
- C. Comply with requirements for raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
- D. Maximum Support Spacing and Minimum Hanger Rod Size for Raceways: Space supports for EMT, IMC, and RMC as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- E. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
 - 1.Secure raceways and cables to these supports with two-bolt conduit clamps.
- F. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch and smaller raceways serving branch circuits and communication systems above suspended ceilings, and for fastening raceways to trapeze supports.

3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this article.
- B. Raceway Support Methods: In addition to methods described in NECA 1, EMT may be supported by openings through structure members, according to NFPA 70.

- C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
 - 1.To Wood: Fasten with lag screws or through bolts.
 - 2.To New Concrete: Bolt to concrete inserts.
 - 3.To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 4.To Existing Concrete: Expansion anchor fasteners.
 - 5.To Steel: Welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts.
 - 6.To Light Steel: Sheet metal screws.
 - 7.Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that comply with seismic-restraint strength and anchorage requirements.
- E. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Comply with installation requirements in Section 055000 "Metal Fabrications" for site-fabricated metal supports.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- C. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 CONCRETE BASES

- A. Construct concrete bases of dimensions indicated, but not less than 4 inches larger in both directions than supported unit, and so anchors will be a minimum of 10 bolt diameters from edge of the base.
- B. Use **3000-psi**, 28-day compressive-strength concrete. Concrete materials, reinforcement, and placement requirements are specified in Section 033000 "Cast-in-Place Concrete."
- C. Anchor equipment to concrete base as follows:
 - 1.Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.

2. Install anchor bolts to elevations required for proper attachment to supported equipment.
3. Install anchor bolts according to anchor-bolt manufacturer's written instructions.

3.5 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.
- B. Touchup: Comply with requirements in Section 099113 "Exterior Painting", Section 099123 "Interior Painting" for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A780.

END OF SECTION

SECTION 260533 - RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Metal conduits and fittings.
2. Nonmetallic conduits and fittings.
3. Metal wireways and auxiliary gutters.
4. Surface raceways.
5. Boxes, enclosures, and cabinets.
6. Handholes and boxes for exterior underground cabling.

B. Related Requirements:

1. Section 078413 "Penetration Firestopping" for firestopping at conduit and box entrances.
2. Section 260543 "Underground Ducts and Raceways for Electrical Systems" for exterior ductbanks, manholes, and underground utility construction.

1.3 DEFINITIONS

- A. ARC: Aluminum rigid conduit.
- B. GRC: Galvanized rigid steel conduit.
- C. IMC: Intermediate metal conduit.

1.4 ACTION SUBMITTALS

- A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.
- B. Shop Drawings: For custom enclosures and cabinets. Include plans, elevations, sections, and attachment details.
- C. Samples: For wireways and surface raceways and for each color and texture specified, **12 inches** long.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Conduit routing plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of items involved:
1. Structural members in paths of conduit groups with common supports.
 2. HVAC and plumbing items and architectural features in paths of conduit groups with common supports.
- B. Qualification Data: For professional engineer.
- C. Seismic Qualification Data: Certificates, for enclosures, cabinets, and conduit racks and their mounting provisions, including those for internal components, from manufacturer.
1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
 4. Detailed description of conduit support devices and interconnections on which the certification is based and their installation requirements.
- D. Source quality-control reports.

PART 2 - PRODUCTS

2.1 METAL CONDUITS AND FITTINGS

- A. Metal Conduit:
1. Listing and Labeling: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 2. GRC: Comply with ANSI C80.1 and UL 6.
 3. ARC: Comply with ANSI C80.5 and UL 6A.
 4. IMC: Comply with ANSI C80.6 and UL 1242.
 5. PVC-Coated Steel Conduit: PVC-coated IMC.
 - a. Comply with NEMA RN 1.
 - b. Coating Thickness: 0.040 inch, minimum.
 6. EMT: Comply with ANSI C80.3 and UL 797.
 7. FMC: Comply with UL 1; zinc-coated steel or aluminum.
 8. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- B. Metal Fittings:
1. Comply with NEMA FB 1 and UL 514B.

2. Listing and Labeling: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 3. Fittings, General: Listed and labeled for type of conduit, location, and use.
 4. Conduit Fittings for Hazardous (Classified) Locations: Comply with UL 1203 and NFPA 70.
 5. Fittings for EMT:
 - a. Material: Steel or die cast.
 - b. Type: Compression.
 6. Expansion Fittings: PVC or steel to match conduit type, complying with UL 651, rated for environmental conditions where installed, and including flexible external bonding jumper.
 7. Coating for Fittings for PVC-Coated Conduit: Minimum thickness of 0.040 inch, with overlapping sleeves protecting threaded joints.
- C. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

2.2 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Description: Sheet metal, complying with UL 870 and NEMA 250, Type 1 or Type 3R unless otherwise indicated, and sized according to NFPA 70.
1. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- C. Wireway Covers: Hinged type unless otherwise indicated.
- D. Finish: Manufacturer's standard enamel finish.

2.3 SURFACE RACEWAYS

- A. Listing and Labeling: Surface raceways and tele-power poles shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Surface Metal Raceways: Galvanized steel with snap-on covers complying with UL 5. Manufacturer's standard enamel finish in color selected by Architect.

2.4 BOXES, ENCLOSURES, AND CABINETS

- A. General Requirements for Boxes, Enclosures, and Cabinets: Boxes, enclosures, and cabinets installed in wet locations shall be listed for use in wet locations.

- B. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- C. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, [**ferrous alloy**] [**aluminum**], Type FD, with gasketed cover.
- D. Nonmetallic Outlet and Device Boxes: Comply with NEMA OS 2 and UL 514C.
- E. Metal Floor Boxes:
 - 1. Material: Sheet metal.
 - 2. Type: Fully adjustable.
 - 3. Shape: Rectangular.
 - 4. Listing and Labeling: Metal floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- F. Luminaire Outlet Boxes: Nonadjustable, designed for attachment of luminaire weighing 50 lb. Outlet boxes designed for attachment of luminaires weighing more than 50 lb shall be listed and marked for the maximum allowable weight.
- G. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- H. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, cast aluminum with gasketed cover.
- I. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- J. Device Box Dimensions: **4 inches square by 2-1/8 inches deep.**
- K. Gangable boxes are allowed.
- L. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1 or Type 3R with continuous-hinge cover with flush latch unless otherwise indicated.
 - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
 - 2. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.
- M. Cabinets:
 - 1. NEMA 250, Type 1 or Type 3R galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.
 - 2. Hinged door in front cover with flush latch and concealed hinge.
 - 3. Key latch to match panelboards.
 - 4. Metal barriers to separate wiring of different systems and voltage.
 - 5. Accessory feet where required for freestanding equipment.
 - 6. Nonmetallic cabinets shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.5 HANDHOLES AND BOXES FOR EXTERIOR UNDERGROUND WIRING

A. General Requirements for Handholes and Boxes:

- 1.Boxes and handholes for use in underground systems shall be designed and identified as defined in NFPA 70, for intended location and application.
- 2.Boxes installed in wet areas shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Polymer-Concrete Handholes and Boxes with Polymer-Concrete Cover: Molded of sand and aggregate, bound together with polymer resin, and reinforced with steel, fiberglass, or a combination of the two.

- 1.Standard: Comply with SCTE 77.
- 2.Configuration: Designed for flush burial with closed bottom unless otherwise indicated.
- 3.Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure and handhole location.
- 4.Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
- 5.Cover Legend: Molded lettering, "ELECTRIC."
- 6.Conduit Entrance Provisions: Conduit-terminating fittings shall mate with entering ducts for secure, fixed installation in enclosure wall.
- 7.Handholes **12 Inches Wide by 24 Inches Long** and Larger: Have inserts for cable racks and pulling-in irons installed before concrete is poured.

2.6 SOURCE QUALITY CONTROL FOR UNDERGROUND ENCLOSURES

A. Handhole and Pull-Box Prototype Test: Test prototypes of handholes and boxes for compliance with SCTE 77. Strength tests shall be for specified tier ratings of products supplied.

- 1.Tests of materials shall be performed by an independent testing agency.
- 2.Strength tests of complete boxes and covers shall be by either an independent testing agency or manufacturer. A qualified registered professional engineer shall certify tests by manufacturer.
- 3.Testing machine pressure gages shall have current calibration certification complying with ISO 9000 and ISO 10012 and traceable to NIST standards.

PART 3 - EXECUTION

3.1 RACEWAY APPLICATION

A. Outdoors: Apply raceway products as specified below unless otherwise indicated:

- 1.Exposed Conduit: IMC.
- 2.Concealed Conduit, Aboveground: IMC.
- 3.Underground Conduit: RNC, Type EPC-40-PVC, concrete encased.
- 4.Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
- 5.Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.

- B. Indoors: Apply raceway products as specified below unless otherwise indicated:
- 1.Exposed, Not Subject to Physical Damage: EMT.
 - 2.Exposed, Not Subject to Severe Physical Damage: EMT.
 - 3.Exposed and Subject to Severe Physical Damage: IMC. Raceway locations include the following:
 - a. Loading dock.
 - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
 - c. Mechanical rooms.
 - 4.Concealed in Ceilings and Interior Walls and Partitions: EMT.
 - 5.Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations.
 - 6.Damp or Wet Locations: IMC.
 - 7.Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel in institutional and commercial kitchens and damp or wet locations.
 - 8.Raceway Color Coding: Apply color coding to both concealed raceway in all locations and exposed raceway in non-finished areas:
 - a. 120/208V Raceway: EMT raceway containing 120/208V wiring shall have a factory applied black color finish.
 - 1) Labels shall be located 15' apart. Label text "120/208V" white text on black label.
 - b. Fire Alarm Raceway: EMT raceway containing fire alarm wiring shall have a factory applied color finish.
 - 1) Labels shall be located 15' apart. Label text "FA" black text on red label.
- C. Minimum Raceway Size: **1/2-inch** trade size.
- D. Raceway Fittings: Compatible with raceways and suitable for use and location.
- 1.Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
 - 2.PVC Externally Coated, Rigid Steel Conduits: Use only fittings listed for use with this type of conduit. Patch and seal all joints, nicks, and scrapes in PVC coating after installing conduits and fittings. Use sealant recommended by fitting manufacturer and apply in thickness and number of coats recommended by manufacturer.
 - 3.EMT: Use compression, steel fittings. Comply with NEMA FB 2.10.
 - 4.Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.
- E. Install nonferrous conduit or tubing for circuits operating above 60 Hz. Where aluminum raceways are installed for such circuits and pass through concrete, install in nonmetallic sleeve.
- F. Do not install aluminum conduits, boxes, or fittings in contact with concrete or earth.
- G. Install surface raceways only where indicated on Drawings.
- H. Do not install nonmetallic conduit where ambient temperature exceeds **120 deg F**.

3.2 INSTALLATION

- A. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- B. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum conduits. Comply with NFPA 70 limitations for types of raceways allowed in specific occupancies and number of floors.
- C. Do not install raceways or electrical items on any "explosion-relief" walls or rotating equipment.
- D. Do not fasten conduits onto the bottom side of a metal deck roof.
- E. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- F. Complete raceway installation before starting conductor installation.
- G. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- H. Install no more than the equivalent of three 90-degree bends in any conduit run except for control wiring conduits, for which fewer bends are allowed. Support within 12 inches of changes in direction.
- I. Make bends in raceway using large-radius preformed ells. Field bending shall be according to NFPA 70 minimum radii requirements. Use only equipment specifically designed for material and size involved.
- J. Conceal conduit within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- K. Support conduit within 12 inches of enclosures to which attached.
- L. Raceways Embedded in Slabs:
 - 1. Run conduit larger than 1-inch trade size, parallel or at right angles to main reinforcement. Where at right angles to reinforcement, place conduit close to slab support. Secure raceways to reinforcement at maximum 10-foot intervals.
 - 2. Arrange raceways to cross building expansion joints at right angles with expansion fittings.
 - 3. Arrange raceways to keep a minimum of **1 inch** of concrete cover in all directions.
 - 4. Do not embed threadless fittings in concrete unless specifically approved by Architect for each specific location.
 - 5. Change from ENT to GRC or IMC before rising above floor.
- M. Stub-Ups to Above Recessed Ceilings:
 - 1. Use EMT, IMC, or RMC for raceways.
 - 2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.

- N. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- O. Coat field-cut threads on PVC-coated raceway with a corrosion-preventing conductive compound prior to assembly.
- P. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors including conductors smaller than No. 4 AWG.
- Q. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to 1-1/4-inch trade size and insulated throat metal bushings on 1-1/2-inch trade size and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.
- R. Install raceways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.
- S. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.
- T. Cut conduit perpendicular to the length. For conduits 2-inch trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.
- U. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.
- V. Surface Raceways:
 - 1. Install surface raceway with a minimum 2-inch radius control at bend points.
 - 2. Secure surface raceway with screws or other anchor-type devices at intervals not exceeding 48 inches and with no less than two supports per straight raceway section. Support surface raceway according to manufacturer's written instructions. Tape and glue are not acceptable support methods.
- W. Install raceway sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed raceways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install raceway sealing fittings according to NFPA 70.
- X. Install devices to seal raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all raceways at the following points:
 - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
 - 2. Where an underground service raceway enters a building or structure.
 - 3. Conduit extending from interior to exterior of building.
 - 4. Conduit extending into pressurized duct and equipment.
 - 5. Conduit extending into pressurized zones that are automatically controlled to maintain different pressure set points.

6. Where otherwise required by NFPA 70.

Y. Comply with manufacturer's written instructions for solvent welding RNC and fittings.

Z. Expansion-Joint Fittings:

1. Install in each run of aboveground RNC that is located where environmental temperature change may exceed 30 deg F and that has straight-run length that exceeds 25 feet. Install in each run of aboveground RMC conduit that is located where environmental temperature change may exceed 100 deg F and that has straight-run length that exceeds 100 feet.

2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:

- a. Outdoor Locations Not Exposed to Direct Sunlight: **125 deg F** temperature change.
- b. Outdoor Locations Exposed to Direct Sunlight: **155 deg F** temperature change.
- c. Indoor Spaces Connected with Outdoors without Physical Separation: **125 deg F** temperature change.

3. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F of temperature change for PVC conduits. Install fitting(s) that provide expansion and contraction for at least 0.000078 inch per foot of length of straight run per deg F of temperature change for metal conduits.

4. Install expansion fittings at all locations where conduits cross building or structure expansion joints.

5. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.

AA. Flexible Conduit Connections: Comply with NEMA RV 3. Use a maximum **72 inches** of flexible conduit for recessed and semirecessed luminaires, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.

1. Use LFMC in damp or wet locations subject to severe physical damage.
2. Use LFMC or LFNC in damp or wet locations not subject to severe physical damage.

BB. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.

CC. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box.

DD. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.

EE. Locate boxes so that cover or plate will not span different building finishes.

FF. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.

GG. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.

HH. Set metal floor boxes level and flush with finished floor surface.

II. Set nonmetallic floor boxes level. Trim after installation to fit flush with finished floor surface.

3.3 INSTALLATION OF UNDERGROUND CONDUIT

A. Direct-Buried Conduit:

1. Excavate trench bottom to provide firm and uniform support for conduit. Prepare trench bottom as specified in Section 312000 "Earth Moving" for pipe less than 6 inches in nominal diameter.
2. Install backfill as specified in Section 312000 "Earth Moving."
3. After installing conduit, backfill and compact. Start at tie-in point, and work toward end of conduit run, leaving conduit at end of run free to move with expansion and contraction as temperature changes during this process. Firmly hand tamp backfill around conduit to provide maximum supporting strength. After placing controlled backfill to within 12 inches of finished grade, make final conduit connection at end of run and complete backfilling with normal compaction as specified in Section 312000 "Earth Moving."
4. Install manufactured duct elbows for stub-ups at poles and equipment and at building entrances through floor unless otherwise indicated. Encase elbows for stub-up ducts throughout length of elbow.
5. Install manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through floor.
 - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches of concrete for a minimum of 12 inches on each side of the coupling.
 - b. For stub-ups at equipment mounted on outdoor concrete bases and where conduits penetrate building foundations, extend steel conduit horizontally a minimum of 60 inches from edge of foundation or equipment base. Install insulated grounding bushings on terminations at equipment.
6. Warning Planks: Bury warning planks approximately 12 inches above direct-buried conduits but a minimum of 6 inches below grade. Align planks along centerline of conduit.
7. Underground Warning Tape: Comply with requirements in Section 260553 "Identification for Electrical Systems."

3.4 INSTALLATION OF UNDERGROUND HANDHOLES AND BOXES

- A. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting conduits to minimize bends and deflections required for proper entrances.
- B. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1/2-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.

- C. Elevation: In paved areas, set so cover surface will be flush with finished grade. Set covers of other enclosures 1 inch above finished grade.
- D. Install handholes with bottom below frost line, below grade.
- E. Install removable hardware, including pulling eyes, cable stanchions, cable arms, and insulators, as required for installation and support of cables and conductors and as indicated. Select arm lengths to be long enough to provide spare space for future cables but short enough to preserve adequate working clearances in enclosure.
- F. Field-cut openings for conduits according to enclosure manufacturer's written instructions. Cut wall of enclosure with a tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.

3.5 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

3.6 FIRESTOPPING

- A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

3.7 PROTECTION

- A. Protect coatings, finishes, and cabinets from damage and deterioration.
 - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
 - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION

SECTION 260543 - UNDERGROUND DUCTS AND RACEWAYS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Metal conduits and fittings, including GRC and PVC-coated steel conduit.
2. Rigid nonmetallic duct.
3. Flexible nonmetallic duct.
4. Duct accessories.
5. Precast concrete handholes.
6. Polymer concrete handholes and boxes with polymer concrete cover.
7. Precast manholes.
8. Cast-in-place manholes.
9. Utility structure accessories.

1.3 DEFINITIONS

- A. Direct Buried: Duct or a duct bank that is buried in the ground, without any additional casing materials such as concrete.
- B. Duct: A single duct or multiple ducts. Duct may be either installed singly or as component of a duct bank.
- C. Duct Bank:
 1. Two or more ducts installed in parallel, with or without additional casing materials.
 2. Multiple duct banks.
- D. GRC: Galvanized rigid (steel) conduit.
- E. Trafficways: Locations where vehicular or pedestrian traffic is a normal course of events.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 1. Include duct-bank materials, including spacers and miscellaneous components.

2. Include duct, conduits, and their accessories, including elbows, end bells, bends, fittings, and solvent cement.
3. Include accessories for manholes, handholes, boxes.
4. Include underground-line warning tape.
5. Include warning planks.

B. Shop Drawings:

1. Precast or Factory-Fabricated Underground Utility Structures:

- a. Include plans, elevations, sections, details, attachments to other work, and accessories.
- b. Include duct entry provisions, including locations and duct sizes.
- c. Include reinforcement details.
- d. Include frame and cover design and manhole chimneys.
- e. Include ladder details.
- f. Include grounding details.
- g. Include dimensioned locations of cable rack inserts, pulling-in and lifting irons, and sumps.
- h. Include joint details.

2. Factory-Fabricated Handholes and Boxes Other Than Precast Concrete:

- a. Include dimensioned plans, sections, and elevations, and fabrication and installation details.
- b. Include duct entry provisions, including locations and duct sizes.
- c. Include cover design.
- d. Include grounding details.
- e. Include dimensioned locations of cable rack inserts, and pulling-in and lifting irons.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: For duct and duct bank. Show duct profiles and coordination with other utilities and underground structures.
 1. Include plans and sections, drawn to scale, and show bends and locations of expansion fittings.
 2. Drawings shall be signed and sealed by a qualified professional engineer.
- B. Qualification Data: For professional engineer and testing agency responsible for testing nonconcrete handholes and boxes.
- C. Product Certificates: For concrete and steel used in precast concrete manholes and handholes, as required by ASTM C858.
- D. Source quality-control reports.
- E. Field quality-control reports.

1.6 MAINTENANCE MATERIALS SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
- B. Furnish cable-support stanchions, arms, insulators, and associated fasteners in quantities equal to 5 percent of quantity of each item installed.

1.7 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM E329 for testing indicated.

1.8 FIELD CONDITIONS

- A. Ground Water: Assume ground-water level is at grade level unless a lower water table is noted on Drawings.
- B. Ground Water: Assume ground-water level is 36 inches below ground surface unless a higher water table is noted on Drawings.

PART 2 - PRODUCTS

2.1 METAL CONDUIT AND FITTINGS

- A. GRC: Comply with ANSI C80.1 and UL 6.
- B. Coated Steel Conduit: PVC-coated GRC or IMC.
 - 1. Comply with NEMA RN 1.
 - 2. Coating Thickness: 0.040 inch, minimum.
- C. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Excellerate.
- D. Listed and labeled as defined in NFPA 70, by a nationally recognized testing laboratory, and marked for intended location and application.

2.2 RIGID NONMETALLIC DUCT

- A. Underground Plastic Utilities Duct: Type EPC-40-PVC RNC, complying with NEMA TC 2 and UL 651, with matching fittings complying with NEMA TC 3 by same manufacturer as duct.
- B. Listed and labeled as defined in NFPA 70, by a nationally recognized testing laboratory, and marked for intended location and application.

- C. Solvents and Adhesives: As recommended by conduit manufacturer.

2.3 FLEXIBLE NONMETALLIC DUCTS

- A. HDPE Duct: Type EPEC-40 HDPE, complying with NEMA TC 7 and UL 651A.

1. Listed and labeled as defined in NFPA 70, by a nationally recognized testing laboratory, and marked for intended location and application.

2.4 DUCT ACCESSORIES

- A. Duct Spacers: Factory-fabricated, rigid, PVC interlocking spacers; sized for type and size of duct with which used, and selected to provide minimum duct spacing indicated while supporting duct during concreting or backfilling.

1. <Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. ABB, Electrification Business.
- b. Allied Tube & Conduit; Atkore International.
- c. Cantex Inc.
- d. IPEX USA LLC.
- e. PenCell Plastics; brand of Hubbell Utility Solutions; Hubbell Incorporated.
- f. Underground Devices, Inc.

- B. Underground-Line Warning Tape: Comply with requirements for underground-line warning tape specified in Section 260553 "Identification for Electrical Systems."

- C. Concrete Warning Planks: Nominal 12 by 24 by 3 inches in size, manufactured from 6000-psi concrete.

1. Color: Red dye added to concrete during batching.
2. Mark each plank with "ELECTRIC" in 2-inch- high, 3/8-inch- deep letters.

2.5 POLYMER CONCRETE HANDHOLES AND BOXES WITH POLYMER CONCRETE COVER

- A. Description: Molded of sand and aggregate, bound together with a polymer resin, and reinforced with steel or fiberglass or a combination of the two.

- B. <Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Armorcast Products Company; brand of Hubbell Utility Solutions; Hubbell Incorporated.
2. MacLean Highline.
3. NewBasis.
4. Oldcastle Infrastructure Inc.; CRH Americas.
5. Quazite; brand of Hubbell Utility Solutions; Hubbell Incorporated.

- C. Standard: Comply with SCTE 77. Comply with tier requirements in "Underground Enclosure Application" Article.
- D. Color: Gray.
- E. Configuration: Units shall be designed for flush burial and have closed bottom unless otherwise indicated.
- F. Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure.
- G. Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
- H. Cover Legend: Molded lettering, "ELECTRIC." as indicated for each service.
- I. Direct-Buried Wiring Entrance Provisions: Knockouts equipped with insulated bushings or end-bell fittings, selected to suit box material, sized for wiring indicated, and arranged for secure, fixed installation in enclosure wall.
- J. Duct Entrance Provisions: Duct-terminating fittings shall mate with entering duct for secure, fixed installation in enclosure wall.
- K. Handholes 12 inches wide by 24 inches long and larger shall have factory-installed inserts for cable racks and pulling-in irons.

2.6 SOURCE QUALITY CONTROL

- A. Test and inspect precast concrete utility structures according to ASTM C1037.
- B. Nonconcrete Handhole and Pull-Box Prototype Test: Test prototypes of manholes and boxes for compliance with SCTE 77. Strength tests shall be for specified tier ratings of products supplied.
 - 1. Tests of materials shall be performed by an independent testing agency.
 - 2. Strength tests of complete boxes and covers shall be by an independent testing agency or manufacturer. A qualified registered professional engineer shall certify tests by manufacturer.
 - 3. Testing machine pressure gages shall have current calibration certification, complying with ISO 9000 and ISO 10012, and traceable to NIST standards.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Coordinate layout and installation of duct, duct bank, manholes, handholes, and boxes with final arrangement of other utilities, site grading, and surface features as determined in the field. Notify Architect if there is a conflict between areas of excavation and existing structures or archaeological sites to remain.

- B. Coordinate elevations of duct and duct-bank entrances into manholes, handholes, and boxes with final locations and profiles of duct and duct banks, as determined by coordination with other utilities, underground obstructions, and surface features. Revise locations and elevations as required to suit field conditions and to ensure that duct and duct bank will drain to manholes and handholes, and as approved by Architect.
- C. Clear and grub vegetation to be removed, and protect vegetation to remain according to Section 311000 "Site Clearing." Remove and stockpile topsoil for reapplication according to Section 311000 "Site Clearing."

3.2 UNDERGROUND DUCT APPLICATION

- A. Duct for Electrical Cables More Than 600 V: Type EPC-40-PVC RNC, concrete-encased unless otherwise indicated.
- B. Duct for Electrical Feeders 600 V and Less: Type EPC-40-PVC RNC, concrete-encased unless otherwise indicated.
- C. Duct for Electrical Feeders 600 V and Less: Type EPC-40-PVC RNC, direct-buried unless otherwise indicated.
- D. Duct for Electrical Branch Circuits: Type EPC-40-PVC RNC, direct-buried unless otherwise indicated.
- E. Bored Underground Duct: Type EPEC-40-HDPE unless otherwise indicated.
- F. Underground Ducts Crossing Paved Paths, Walks and Driveways, Roadways: Type EPC-40 PVC RNC, encased in reinforced concrete.
- G. Stub-ups: Concrete-encased GRC.

3.3 UNDERGROUND ENCLOSURE APPLICATION

- A. Handholes and Boxes for 600 V and Less:
 - 1. Units in Roadways and Other Deliberate Traffic Paths: Precast concrete. AASHTO HB 17, H-10 structural load rating.
 - 2. Units in Driveway, Parking Lot, and Off-Roadway Locations, Subject to Occasional, Non-deliberate Loading by Heavy Vehicles: Precast concrete, AASHTO HB 17, H-20 structural load rating.
 - 3. Units in Sidewalk and Similar Applications with a Safety Factor for Nondeliberate Loading by Vehicles: Precast concrete, AASHTO HB 17, H-10 structural load rating.
 - 4. Units Subject to Light-Duty Pedestrian Traffic Only: Fiberglass-reinforced polyester resin, structurally tested according to SCTE 77 with 3000-lbf vertical loading.
 - 5. Cover design load shall not exceed the design load of the handhole or box.
- B. Manholes: Precast concrete.

1. Units Located in Roadways and Other Deliberate Traffic Paths by Heavy or Medium Vehicles: H-20 structural load rating according to AASHTO HB 17.
2. Units Not Located in Deliberate Traffic Paths by Heavy or Medium Vehicles: H-10 load rating according to AASHTO HB 17.

3.4 EARTHWORK

- A. Excavation and Backfill: Comply with Section 312000 "Earth Moving," but do not use heavy-duty, hydraulic-operated, compaction equipment.
- B. Restoration: Replace area immediately after backfilling is completed or after construction vehicle traffic in immediate area is complete.
- C. Restore surface features at areas disturbed by excavation, and re-establish original grades unless otherwise indicated. Replace removed sod immediately after backfilling is completed.
- D. Restore areas disturbed by trenching, storing of dirt, cable laying, and other work. Restore vegetation and include necessary topsoiling, fertilizing, liming, seeding, sodding, sprigging, and mulching. Comply with Section 329200 "Turf and Grasses" and Section 329300 "Plants."
- E. Cut and patch existing pavement in the path of underground duct, duct bank, and underground structures according to "Cutting and Patching" Article in Section 017300 "Execution."

3.5 DUCT AND DUCT-BANK INSTALLATION

- A. Where indicated on Drawings, install duct, spacers, and accessories into the duct-bank configuration shown. Duct installation requirements in this Section also apply to duct bank.
- B. Install duct according to NEMA TCB 2.
- C. Slope: Pitch duct a minimum slope of 1:300 down toward manholes and handholes and away from buildings and equipment. Slope duct from a high point between two manholes, to drain in both directions.
- D. Curves and Bends: Use 5-degree angle couplings for small changes in direction. Use manufactured long sweep bends with a minimum radius of [48 inches] [12.5 feet] [25 feet], both horizontally and vertically, at other locations unless otherwise indicated.
 1. Duct shall have maximum of two 90 degree bends or the total of all bends shall be no more 180 degrees between pull points.
- E. Joints: Use solvent-cemented joints in duct and fittings and make watertight according to manufacturer's written instructions. Stagger couplings so those of adjacent duct do not lie in same plane.

- F. Installation Adjacent to High-Temperature Steam Lines: Where duct is installed parallel to underground steam lines, perform calculations showing the duct will not be subject to environmental temperatures above 40 deg C. Where environmental temperatures are calculated to rise above 40 deg C, and anywhere the duct crosses above an underground steam line, install insulation blankets listed for direct burial to isolate the duct bank from the steam line.
- G. End Bell Entrances to Manholes and Concrete and Polymer Concrete Handholes: Use end bells, spaced approximately 10 inches o.c. for 5-inch duct, and vary proportionately for other duct sizes.
- 1.Begin change from regular spacing to end-bell spacing 10 feet from the end bell, without reducing duct slope and without forming a trap in the line.
 - 2.Expansion and Deflection Fittings: Install an expansion and deflection fitting in each duct in the area of disturbed earth adjacent to manhole or handhole. Install an expansion fitting near the center of all straight line direct-buried duct with calculated expansion of more than 3/4 inch.
 - 3.Grout end bells into structure walls from both sides to provide watertight entrances.
- H. Terminator Entrances to Manholes and Concrete and Polymer Concrete Handholes: Use manufactured, cast-in-place duct terminators, with entrances into structure spaced approximately 6 inches o.c. for 4-inch duct, and vary proportionately for other duct sizes.
- 1.Begin change from regular spacing to terminator spacing 10 feet from the terminator, without reducing duct line slope and without forming a trap in the line.
 - 2.Expansion and Deflection Fittings: Install an expansion and deflection fitting in each duct in the area of disturbed earth adjacent to manhole or handhole. Install an expansion fitting near the center of all straight line duct with calculated expansion of more than 3/4 inch.
- I. Building Wall Penetrations: Make a transition from underground duct to GRC at least 10 feet outside the building wall, without reducing duct line slope away from the building and without forming a trap in the line. Use fittings manufactured for RNC-to-GRC transition. Install GRC penetrations of building walls as specified in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."
- J. Sealing: Provide temporary closure at terminations of duct with pulled cables. Seal spare duct at terminations. Use sealing compound and plugs to withstand at least 15-psig hydrostatic pressure.
- K. Pulling Cord: Install 200-lbf- test nylon cord in empty ducts.
- L. Concrete-Encased Ducts and Duct Bank:
- 1.Excavate trench bottom to provide firm and uniform support for duct. Prepare trench bottoms as specified in Section 312000 "Earth Moving" for pipes less than 6 inches in nominal diameter.
 - 2.Width: Excavate trench 12 inches wider than duct on each side.
 - 3.Width: Excavate trench 3 inches wider than duct on each side.
 - 4.Depth: Install so top of duct envelope is at least 24 inches below finished grade in areas not subject to deliberate traffic, and at least 30 inches below finished grade in deliberate traffic paths for vehicles unless otherwise indicated.

5. Support duct on duct spacers coordinated with duct size, duct spacing, and outdoor temperature.
6. Spacer Installation: Place spacers close enough to prevent sagging and deforming of duct, with not less than four spacers per 20 feet of duct. Place spacers within 24 inches of duct ends. Stagger spacers approximately 6 inches between tiers. Secure spacers to earth and to duct to prevent floating during concreting. Tie entire assembly together using fabric straps; do not use tie wires or reinforcing steel that may form conductive or magnetic loops around ducts or duct groups.
7. Minimum Space between Duct: 3 inches between edge of duct and exterior envelope wall, 2 inches between ducts for like services, and 4 inches between power and communications ducts.
8. Elbows: Use manufactured duct elbows for stub-ups, at building entrances, and at changes of direction in duct unless otherwise indicated. Extend encasement throughout length of elbow.
9. Elbows: Use manufactured GRC elbows for stub-ups, at building entrances, and at changes of direction in duct run.
 - a. Couple RNC duct to GRC with adapters designed for this purpose, and encase coupling with 3 inches of concrete.
 - b. Stub-ups to Outdoor Equipment: Extend concrete-encased GRC horizontally a minimum of 60 inches from edge of base. Install insulated grounding bushings on terminations at equipment.
 - 1) Stub-ups shall be minimum 4 inches above finished floor and minimum 3 inches from conduit side to edge of slab
 - c. Stub-ups to Indoor Equipment: Extend concrete-encased GRC horizontally a minimum of 60 inches from edge of wall. Install insulated grounding bushings on terminations at equipment.
 - 1) Stub-ups shall be minimum 4 inches above finished floor and no less than 3 inches from conduit side to edge of slab
10. Reinforcement: Reinforce concrete-encased duct where crossing disturbed earth and where indicated. Arrange reinforcing rods and ties without forming conductive or magnetic loops around ducts or duct groups.
11. Forms: Use walls of trench to form side walls of duct bank where soil is self-supporting and concrete envelope can be poured without soil inclusions; otherwise, use forms.
12. Concrete Cover: Install a minimum of 3 inches of concrete cover between edge of duct to exterior envelope wall, 2 inches between duct of like services, and 4 inches between power and communications ducts.
13. Concreting Sequence: Pour each run of envelope between manholes or other terminations in one continuous operation.
 - a. Start at one end and finish at the other, allowing for expansion and contraction of duct as its temperature changes during and after the pour. Use expansion fittings installed according to manufacturer's written instructions, or use other specific measures to prevent expansion-contraction damage.
 - b. If more than one pour is necessary, terminate each pour in a vertical plane and install 3/4-inch reinforcing-rod dowels extending a minimum of 18 inches into concrete on both sides of joint near corners of envelope.

14. Pouring Concrete: Comply with requirements in "Concrete Placement" Article in Section 033000 "Cast-in-Place Concrete." Place concrete carefully during pours to prevent voids under and between duct and at exterior surface of envelope. Do not allow a heavy mass of concrete to fall directly onto ducts. Allow concrete to flow around duct and rise up in middle, uniformly filling all open spaces. Do not use power-driven agitating equipment unless specifically designed for duct-installation application.

M. Direct-Buried Duct and Duct Bank:

1. Excavate trench bottom to provide firm and uniform support for duct. Comply with requirements in Section 312000 "Earth Moving" for preparation of trench bottoms for pipes less than 6 inches in nominal diameter.
2. Width: Excavate trench 12 inches wider than duct on each side.
3. Width: Excavate trench 3 inches wider than duct on each side.
4. Depth: Install top of duct at least 36 inches below finished grade unless otherwise indicated.
5. Set elevation of bottom of duct bank below frost line.
6. Support ducts on duct spacers coordinated with duct size, duct spacing, and outdoor temperature.
7. Spacer Installation: Place spacers close enough to prevent sagging and deforming of duct, with not less than four spacers per 20 feet of duct. Place spacers within 24 inches of duct ends. Stagger spacers approximately 6 inches between tiers. Secure spacers to earth and to ducts to prevent floating during concreting. Tie entire assembly together using fabric straps; do not use tie wires or reinforcing steel that may form conductive or magnetic loops around ducts or duct groups.
8. Install duct with a minimum of 3 inches between ducts for like services and 6 inches between power and communications duct.
9. Elbows: Install manufactured duct elbows for stub-ups, at building entrances, and at changes of direction in duct direction unless otherwise indicated. Encase elbows for stub-up ducts throughout length of elbow.
10. Install manufactured GRC elbows for stub-ups, at building entrances, and at changes of direction in duct.
 - a. Couple RNC duct to GRC with adapters designed for this purpose, and encase coupling with 3 inches of concrete.
 - b. Stub-ups to Outdoor Equipment: Extend concrete-encased GRC horizontally a minimum of 60 inches from edge of base. Install insulated grounding bushings on terminations at equipment.
 - 1) Stub-ups shall be minimum 4 inches above finished floor and minimum 3 inches from conduit side to edge of slab
 - c. Stub-ups to Indoor Equipment: Extend concrete-encased GRC horizontally a minimum of 60 inches from edge of wall. Install insulated grounding bushings on terminations at equipment.
 - 1) Stub-ups shall be minimum 4 inches above finished floor and no less than 3 inches from conduit side to edge of slab

11. After installing first tier of duct, backfill and compact. Start at tie-in point and work toward end of duct run, leaving ducts at end of run free to move with expansion and contraction as temperature changes during this process. Repeat procedure after placing each tier. After placing last tier, hand place backfill to 4 inches over duct and hand tamp. Firmly tamp backfill around ducts to provide maximum supporting strength. Use hand tamper only. After placing controlled backfill over final tier, make final duct connections at end of run and complete backfilling with normal compaction. Comply with requirements in Section 312000 "Earth Moving" for installation of backfill materials.
 - a. Place minimum 3 inches of sand as a bed for duct. Place sand to a minimum of 6 inches above top level of duct.
 - b. Place minimum 6 inches of engineered fill above concrete encasement of duct.
- N. Warning Planks: Bury warning planks approximately 12 inches above direct-buried duct, placing them 24 inches o.c. Align planks along the width and along the centerline of duct or duct bank. Provide an additional plank for each 12-inch increment of duct-bank width over a nominal 18 inches. Space additional planks 12 inches apart, horizontally.
- O. Underground-Line Warning Tape: Bury conducting underground line specified in Section 260553 "Identification for Electrical Systems" no less than 12 inches above all concrete-encased duct and approximately 6-8 inches below grade. Align tape parallel to and within 3 inches of centerline of duct bank. Provide an additional warning tape for each 12-inch increment of duct-bank width over a nominal 18 inches. Space additional tapes 12 inches apart, horizontally.

3.6 INSTALLATION OF CONCRETE MANHOLES, HANDHOLES, AND BOXES

A. Cast-in-Place Manhole Installation:

1. Finish interior surfaces with a smooth-troweled finish.
2. Knockouts for Future Duct Connections: Form and pour concrete knockout panels 1-1/2 to 2 inches thick, arranged as indicated.
3. Comply with requirements in Section 033000 "Cast-in-Place Concrete" for cast-in-place concrete, formwork, and reinforcement.

B. Precast Concrete Handhole and Manhole Installation:

1. Comply with ASTM C891 unless otherwise indicated.
2. Install units level and plumb and with orientation and depth coordinated with connecting duct, to minimize bends and deflections required for proper entrances.
3. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.

C. Elevations:

1. Manhole Roof: Install with rooftop at least 15 inches below finished grade.
2. Manhole Frame: In paved areas and trafficways, set frames flush with finished grade. Set other manhole frames 1 inch above finished grade.
3. Install handholes with bottom below frost line, below grade.

4. Handhole Covers: In paved areas and trafficways, set surface flush with finished grade. Set covers of other handholes 1 inch above finished grade.
 5. Where indicated, cast handhole cover frame integrally with handhole structure.
- D. Drainage: Install drains in bottom of manholes where indicated. Coordinate with drainage provisions indicated.
- E. Manhole Access: Circular opening in manhole roof; sized to match cover size.
1. Manholes with Fixed Ladders: Offset access opening from manhole centerlines to align with ladder.
 2. Install chimney, constructed of precast concrete collars and rings, to support cast-iron frame to connect cover with manhole roof opening. Provide moisture-tight masonry joints and waterproof grouting for frame to chimney.
- F. Waterproofing: Apply waterproofing to exterior surfaces of manholes and handholes after concrete has cured at least three days. Waterproofing materials and installation are specified in Section 071353 "Elastomeric Sheet Waterproofing." or Section 071354 "Thermoplastic Sheet Waterproofing." After duct has been connected and grouted, and before backfilling, waterproof joints and connections, and touch up abrasions and scars. Waterproof exterior of manhole chimneys after mortar has cured at least three days.
- G. Dampproofing: Apply dampproofing to exterior surfaces of manholes and handholes after concrete has cured at least three days. Dampproofing materials and installation are specified in Section 071113 "Bituminous Dampproofing." After ducts are connected and grouted, and before backfilling, dampproof joints and connections, and touch up abrasions and scars. Damp-proof exterior of manhole chimneys after mortar has cured at least three days.
- H. Hardware: Install removable hardware, including pulling eyes, cable stanchions and insulators, as required for installation and support of cables and conductors and as indicated.
- I. Fixed Manhole Ladders: Arrange to provide for safe entry with maximum clearance from cables and other items in manholes.
- J. Field-Installed Bolting Anchors in Manholes and Concrete Handholes: Do not drill deeper than 3-7/8 inches for manholes and 2 inches for handholes, for anchor bolts installed in the field. Use a minimum of two anchors for each cable stanchion.

3.7 INSTALLATION OF HANDHOLES AND BOXES OTHER THAN PRECAST CONCRETE

- A. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting duct, to minimize bends and deflections required for proper entrances. Use box extension if required to match depths of duct, and seal joint between box and extension as recommended by manufacturer.
- B. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1/2-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.
- C. Elevation: In paved areas and trafficways, set cover flush with finished grade. Set covers of other handholes 1 inch above finished grade.

- D. Install handholes and boxes with bottom below frost line, below grade.
- E. Install removable hardware, including pulling eyes, cable stanchions, cable arms, and insulators, as required for installation and support of cables and conductors and as indicated. Select arm lengths to be long enough to provide spare space for future cables, but short enough to preserve adequate working clearances in enclosure.
- F. Field cut openings for duct according to enclosure manufacturer's written instructions. Cut wall of enclosure with a tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.
- G. For enclosures installed in asphalt paving and subject to occasional, nondeliberate, heavy-vehicle loading, form and pour a concrete ring encircling, and in contact with, enclosure and with top surface screeded to top of box cover frame. Bottom of ring shall rest on compacted earth.
 - 1. Concrete: 3000 psi, 28-day strength, complying with Section 033000 "Cast-in-Place Concrete," with a troweled finish.
 - 2. Dimensions: 10 inches wide by 12 inches deep

3.8 GROUNDING

- A. Ground underground ducts and utility structures according to Section 260526 "Grounding and Bonding for Electrical Systems."

3.9 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Demonstrate capability and compliance with requirements on completion of installation of underground duct, duct bank, and utility structures.
 - 2. Pull solid aluminum or wood test mandrel through duct to prove joint integrity and adequate bend radii, and test for out-of-round duct. Provide a minimum 12-inch-long mandrel equal to duct size minus 1/4 inch. If obstructions are indicated, remove obstructions and retest.
 - 3. Test manhole and handhole grounding to ensure electrical continuity of grounding and bonding connections. Measure and report ground resistance as specified in Section 260526 "Grounding and Bonding for Electrical Systems."
- B. Correct deficiencies and retest as specified above to demonstrate compliance.
- C. Prepare test and inspection reports.

3.10 CLEANING

- A. Pull leather-washer-type duct cleaner, with graduated washer sizes, through full length of duct until duct cleaner indicates that duct is clear of dirt and debris. Follow with rubber duct swab for final cleaning and to assist in spreading lubricant throughout ducts.

B. Clean internal surfaces of manholes, including sump.

- 1.Sweep floor, removing dirt and debris.
- 2.Remove foreign material.

END OF SECTION

SECTION 260548.16 - SEISMIC CONTROLS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Restraints - rigid type.
2. Restraints - cable type.
3. Restraint accessories.
4. Post-installed concrete anchors.
5. Concrete inserts.

B. Related Requirements:

1. Section 260529 "Hangers and Supports for Electrical Systems" for commonly used electrical supports and installation requirements.

1.3 DEFINITIONS

- A. Designated Seismic System: An electrical system component that requires design in accordance with ASCE/SEI 7, Ch. 13 and for which the Component Importance Factor is greater than 1.0.
- B. OSHPD: Office of Statewide Health Planning and Development (for the State of California owned and regulated medical facilities).

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include rated load capacity for each seismic-restraint device.
2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of seismic-restraint component used.
3. Annotate types and sizes of seismic restraints and accessories, complete with listing markings or report numbers and load rating in tension and compression as evaluated by UL product listing.
4. Annotate to indicate application of each product submitted and compliance with requirements.

B. Delegated Design Submittal for Each Seismic-Restraint Device:

1. For each seismic-restraint device, including restraint - rigid and cable type, restraint accessory, and concrete anchor and insert that is required by this Section or is indicated on Drawings, submit the following:
 - a. Seismic Restraints: Select seismic restraints complying with performance requirements, design criteria, and analysis data.
 - b. Post-Installed Concrete Anchors and Inserts: Include calculations showing anticipated seismic loads. Include certification that device is approved by an NRTL for seismic reinforcement use.
 - c. Seismic Design Calculations: Submit all input data and loading calculations prepared under "Seismic Design Calculations" Paragraph in "Performance Requirements" Article.
 - d. Qualified Professional Engineer: All designated design submittals for seismic calculations are to be signed and sealed by the qualified professional engineer responsible for their preparation.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show coordination of seismic bracing for electrical components with other systems and equipment in the vicinity, including other supports and seismic restraints.
- B. Qualification Data: For professional engineer.
- C. Welding certificates.
- D. Field quality-control reports.
- E. Seismic Qualification Data: Provide special certification for designated seismic systems as indicated in ASCE/SEI 7-05 Paragraph 13.2.2, "Special Certification Requirements for Designated Seismic Systems" for all Designated Seismic Systems identified as such on Drawings or in the Specifications.
 1. Provide equipment manufacturer's written certification for each designated active electrical seismic device and system, stating that it will remain operable following the design earthquake. Certification must be based on requirements of ASCE/SEI 7, including shake table testing per ICC-ES AC156 or a similar nationally recognized testing standard procedure acceptable to authorities having jurisdiction.
 2. Provide equipment manufacturer's written certification that components with hazardous contents maintain containment following the design earthquake by methods required in ASCE/SEI 7-05.
 3. Submit evidence demonstrating compliance with these requirements for approval to authorities having jurisdiction after review and acceptance by a licensed professional engineer.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct testing indicated, be and NRTL as defined by OSHA in 29 CFR 1910.7, and be acceptable to authorities having jurisdiction.

- B. Welding Qualifications: Qualify procedures and personnel in accordance with AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- C. Seismic-Restraint Device Load Ratings: Devices to be tested and rated in accordance with applicable code requirements and authorities having jurisdiction. Devices to be listed by a nationally recognized third party that requires periodic follow-up inspections and has a listing directory available to the public. Provide third-party listing by one or more of the following: UL product listing.
- D. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design seismic control system.
 - 1. Seismic Performance: Equipment shall withstand the effects of earthquake motions determined in accordance with ASCE/SEI 7-05.
- B. Seismic Design Calculations:
 - 1. Perform calculations to obtain force information necessary to properly select seismic-restraint devices, fasteners, and anchorage. Perform calculations using methods acceptable to applicable code authorities and as presented in ASCE/SEI 7-05 or other seismic calculation method required by authorities having jurisdiction. Where "ASCE/SEI 7" is used throughout this Section, it is to be understood that the edition referred to in this subparagraph is the edition intended as reference throughout the Section Text.
 - a. Data indicated below to be determined by Delegated Design Contractor must be obtained by Contractor and must be included in individual component submittal packages.
 - b. Coordinate seismic design calculations with wind-load calculations for equipment mounted outdoors.
 - c. Building Occupancy Category: II.
 - d. Building Risk Category: II.
 - e. Building Site Classification: D.
 - 2. Calculation Factors, ASCE/SEI 7-16, Ch. 13 - Seismic Design Requirements for Nonstructural Components: All section, paragraph, equation, and table numbers refer to ASCE/SEI 7-16 unless otherwise noted.
 - a. Horizontal Seismic Design Force F_p : Value is to be calculated by Delegated Design Contractor using Equation 13.3-1. Factors below must be obtained for this calculation.
 - 1) S_{DS} = Spectral Acceleration: 16.9. Value applies to all components on Project.

- 2) a_p = Component Amplification Factor: See Drawing Schedule for each component.
 - 3) I_p = Component Importance Factor: See Drawing Schedule for each component.
 - 4) W_p = Component Operating Weight: For each component. Obtain by Delegated Design Contractor from each component submittal.
 - 5) R_p = Component Response Modification Factor: See Drawing Schedule for each component.
 - 6) z = Height in Structure of Point of Attachment of Component for Base: Determine from Project Drawings for each component by the Delegated Design Contractor. For items at or below the base, "z" shall be taken as zero.
 - 7) h = Average Roof Height of Structure with Respect to Base: Determine from Project Drawings by Delegated Design Contractor.
- b. Vertical Seismic Design Force: Calculated by Delegated Design Contractor using method explained in ASCE/SEI 7-16, Paragraph 13.3.1.2.
- c. Seismic Relative Displacement D_p : Calculated by Delegated Design Contractor using methods explained in ASCE/SEI 7-16, Paragraph 13.3.2. Factors below must be obtained for this calculation:
- 1) D_p = Relative Seismic Displacement that Each Component Must Be Designed to Accommodate: Calculated by Delegated Design Contractor in accordance with ASCE/SEI 7-16, Paragraph 13.3.2.
 - 2) I_c = Structure Importance Factor: 1.00. Value applies to all components on Project.
 - 3) δ_{xA} = Deflection at Building Level x of Structure A: See Drawing Schedule for each component.
 - 4) δ_{yA} = Deflection at Building Level y of Structure A: See Drawing Schedule for each component.
 - 5) δ_{yB} = Deflection at Building Level y of Structure B: See Drawing Schedule for each component.
 - 6) h_x = Height of Level x to Which Upper Connection Point Is Attached: Determine for each component by Delegated Design Contractor from Project Drawings and manufacturer's data.
 - 7) h_y = Height of Level y to Which Upper Connection Point Is Attached: Determine for each component by Delegated Design Contractor from Project Drawings and manufacturer's data.
 - 8) A_{aA} = Allowable Story Drift for Structure A: See Drawing Schedules for each component.
 - 9) A_{aB} = Allowable Story Drift for Structure B: See Drawing Schedules for each component.
 - 10) h_{sx} = Story Height Used in the Definition of Allowable Drift A_a : See Drawings Schedules for each component.
- d. Component Fundamental Period T_p : Calculated by Delegated Design Contractor using methods explained in ASCE/SEI 7-16, Paragraph 13.3.3. Factors below must be obtained for this calculation:
- 1) W_p = Component Operating Weight: Determined by Contractor from Project Drawings and manufacturer's data.
 - 2) g = Gravitational Acceleration: 32.17 fps².

- 3) K_p = Combined Stiffness of the Component, Supports, and Attachments: Determined by delegated design seismic engineer.

3. Calculation Factors, ASCE/SEI 7-10, Ch. 13 - Seismic Design Requirements for Nonstructural Components: All section, paragraph, equation, and table numbers refer to ASCE/SEI 7-10 unless otherwise noted.

- a. Horizontal Seismic Design Force F_p : Calculated by Delegated Design Contractor by ASCE/SEI 7-10, Equation 13.3-1. Factors below must be obtained for this calculation.
 - 1) S_{DS} = Spectral Acceleration: 16.9. Value applies to all components on Project.
 - 2) a_p = Component Amplification Factor: See Drawing Schedule for each component.
 - 3) I_p = Component Importance Factor: See Drawing Schedule for each component.
 - 4) W_p = Component Operating Weight: For each component. Obtain by Delegated Design Contractor from equipment submittal.
 - 5) R_p = Component Response Modification Factor: See Drawing Schedule for each component.
 - 6) z = Height in Structure of Point of Attachment of Component with Respect to Base: Determined from Project Drawings for each component by contractor. For items at or below the base, "z" shall be taken as zero.
 - 7) h = Average Roof Height of Structure with Respect to Base: Determine from Project Drawings by Delegated Design Contractor.
- b. Vertical Seismic Design Force: Calculate by Delegated Design Contractor using method explained in ASCE/SEI 7-10, Paragraph 13.3.1.
- c. Seismic Relative Displacement D_p : Calculate by Delegated Design Contractor using methods explained in ASCE/SEI 7-10, Paragraph 13.3.2. Factors below must be obtained for this calculation:
 - 1) D_p = Relative Seismic Displacement that Each Component Must Be Designed to Accommodate: Calculate by Delegated Design Contractor in accordance with ASCE/SEI 7-10, Paragraph 13.3.2.
 - 2) I_e = Structure Importance Factor: 1.00. Value applies to all components on Project.
 - 3) δ_{xA} = Deflection at Building Level x of Structure A: See Drawing Schedule for each component.
 - 4) δ_{yA} = Deflection at Building Level y of Structure A: See Drawing Schedule for each component.
 - 5) δ_{yB} = Deflection at Building Level y of Structure B: See Drawing Schedule for each component.
 - 6) h_x = Height of Level x to Which Upper Connection Point Is Attached: Determine for each component by Delegated Design Contractor from Project Drawings and manufacturer's data.
 - 7) h_y = Height of Level y to Which Upper Connection Point Is Attached: Determine for each component by Delegated Design Contractor from Project Drawings and manufacturer's data.

- 8) A_{aA} = Allowable Story Drift for Structure A: See Drawing Schedule for each component.
- 9) A_{aB} = Allowable Story Drift for Structure B: See Drawing Schedule for each component.
- 10) h_{sx} = Story Height Used in the Definition of Allowable Drift A_a : See Drawing Schedule for each component.

4. Calculation Factors, ASCE/SEI 7-05, Ch. 13 - Seismic Design Requirements for Nonstructural Components: All section, paragraph, equation, and table numbers refer to ASCE/SEI 7-05 unless otherwise noted.

- a. Horizontal Seismic Design Force F_p : Calculated by Delegated Design Contractor by ASCE/SEI 7-05, Equation 13.3-1. Factors below must be obtained for this calculation:
 - 1) S_{DS} = Spectral Acceleration: 16.9. Value applies to all components on Project.
 - 2) a_p = Component Amplification Factor: See Drawing Schedule for each component.
 - 3) I_p = Component Importance Factor: See Drawing Schedule for each component.
 - 4) W_p = Component Operating Weight: Obtain by Delegated Design Contractor for each component from component submittal.
 - 5) R_p = Component Response Modification Factor: See Drawing Schedule for each component.
 - 6) z = Height in Structure of Point of Attachment of Component with Respect to Base: Determine by Delegated Design Contractor for each component from Project Drawings. For items at or below the base, "z" shall be taken as zero.
 - 7) h = Average Roof Height of Structure With Respect to Base: Determine by Delegated Design Contractor from Project Drawings.
- b. Vertical Seismic Design Force: Calculated by Delegated Design Contractor using method explained in ASCE/SEI 7-05, Paragraph 13.3.1.
- c. Seismic Relative Displacement D_p : Calculated by Delegated Design Contractor using methods explained in ASCE/SEI 7-05, Paragraph 13.3.2. Factors below must be obtained for this calculation:
 - 1) δ_{xA} = Deflection at Building Level x of Structure A: See Drawing Schedule for each component.
 - 2) δ_{yA} = Deflection at Building Level y of Structure A: See Drawing Schedule for each component.
 - 3) δ_{yB} = Deflection at Building Level y of Structure B: See Drawing Schedule for each component.
 - 4) h_x = Height of Level x to Which Upper Connection Point Is Attached: Determine for each component by Delegated Design Contractor from Project Drawings and manufacturer's data.
 - 5) h_y = Height of Level y to Which Upper Connection Point Is Attached: Determine for each component by Delegated Design Contractor from Project Drawings and manufacturer's data.
 - 6) A_{aA} = Allowable Story Drift for Structure A: See Drawing Schedule for each component.

- 7) A_{aB} = Allowable Story Drift for Structure B: See Drawing Schedule for each component.
- 8) h_{sx} = Story Height Used in the Definition of Allowable Drift A_a : See Drawing Schedule for each component.

C. Wind-Load Design Calculations:

1. Perform calculations to obtain force information necessary to properly select wind-load-restraint devices, fasteners, and anchorage. Perform calculations using methods acceptable to applicable code authorities and as presented in ASCE/SEI 7-05. Where "ASCE/SEI 7" is used throughout this Section, it is to be understood that the edition referred to in this subparagraph is intended as referenced throughout the Section Text unless otherwise noted.
 - a. Data indicated below that are specific to individual pieces of equipment must be obtained by Contractor and must be included in individual component submittal packages.
 - b. Coordinate design wind-load calculations with seismic load calculations for equipment requiring both seismic and wind-load reinforcement. Comply with requirements in other Sections in addition to those in this Section.
2. Design wind pressure "p" for external sidewall-mounted equipment is to be calculated by Delegated Design Contractor using methods in ASCE/SEI 7-16, Ch. 30. Perform calculations according to one of the following, as appropriate:
 - a. PART 1: Low-Rise Buildings.
 - b. PART 2: Low-Rise Buildings (Simplified).
 - c. PART 3: Buildings with "h" less than 60 ft..
 - d. PART 4: Buildings with "h" greater than 60 ft. and less than 160 ft..
 - e. PART 5: Open Buildings.
3. Design wind pressure "p" for rooftop equipment is to be calculated by Delegated Design Contractor using methods in ASCE/SEI 7-16, Ch. 30, PART 6: Building Appurtenances and Rooftop Structures and Equipment.
 - a. Risk Category: II.
 - b. h = Mean Roof Height: <Insert value>.
 - c. V = Basic Wind Speed: 89 MPH.
 - d. K_d = Wind Directionality Factor: <Insert factor>.
 - e. Exposure Category: C.
 - f. K_{zt} = Topographic Factor: <Insert factor>.
 - g. K_e = Ground Elevation Factor: <Insert factor>.
 - h. K_z = Velocity Pressure Exposure Coefficient (Evaluated at Height z): <Insert coefficient>.
 - i. K_h = Velocity Pressure Exposure Coefficient (Evaluated at Height h): <Insert coefficient>.
 - j. q_z = Velocity Pressure: Value calculated by delegated wind-load design Contractor using methods detailed in ASCE/SEI 7-16 Section 26.10.1 or other source approved by authorities having jurisdiction.

- k. q_h = Velocity Pressure: Value calculated by delegated wind-load design contractor using methods detailed in ASCE/SEI 7-16 Section 26.10.1 or other source approved by authorities having jurisdiction.
- 1) G = Gust-Effect Factor: [0.85] <Insert factor>.
 - 2) Enclosure Classification: <Insert classification>.
 - 3) GC_{pi} = Internal Pressure Coefficient: <Insert coefficient>.

4. Design wind pressure "p" for external sidewall-mounted equipment is to be calculated by Delegated Design Contractor using methods in ASCE/SEI 7-10, Ch. 30. Perform calculations according with one of the following, as appropriate:

- a. PART 1: Low-Rise Buildings.
- b. PART 2: Low-Rise Buildings (Simplified).
- c. PART 3: Buildings with "h" greater than 60 ft..
- d. PART 4: Buildings with h less than 160 ft..
- e. PART 5: Open Buildings.

5. Design wind pressure "p" for rooftop equipment is to be calculated by Delegated Design Contractor using methods in ASCE/SEI 7-10, Ch. 30, PART 6: Building Appurtenances and Rooftop Structures and Equipment.

- a. Risk Category: [I] [II] [III] [IV] [V].
- b. h = Mean Roof Height: <Insert value>.
- c. V = Basic Wind Speed: <Insert value>.
- d. K_d = Wind Directionality Factor: <Insert factor>.
- e. Exposure Category: [B] [C] [D].
- f. K_{zt} = Topographic Factor: <Insert factor>.
- g. K_z = Velocity Pressure Exposure Coefficient (Evaluated at Height z): <Insert coefficient>.
- h. K_h = Velocity Pressure Exposure Coefficient (Evaluated at Height h): <Insert coefficient>.
- i. q_z = Velocity Pressure at Height z: Value calculated by delegated wind-load design Contractor using methods detailed in ASCE/SEI 7-10 Section 26.10.1 or other source approved by authorities having jurisdiction.
- j. q_h = Velocity Pressure at Height h: Value calculated by delegated wind-load design Contractor using methods detailed in ASCE/SEI 7-10 Section 26.10.1 or other source approved by authorities having jurisdiction.
- k. G = Gust-Effect Factor: [0.85] <Insert factor>.
- l. Enclosure Classification: <Insert classification>.
- m. GC_{pi} = Internal Pressure Coefficient: <Insert coefficient>.

D. Consequential Damage: Provide additional seismic [and wind-load] restraints for suspended electrical components or anchorage of floor-, roof-, or wall-mounted electrical components as indicated in [ASCE/SEI 7-05] [ASCE/SEI 7-10] [ASCE/SEI 7-16] so that failure of a non-essential or essential electrical component will not cause failure of any other essential architectural, mechanical, or electrical building component.

E. Fire/Smoke Resistance: Seismic-restraint devices that are not constructed of ferrous metals must have a maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested by an NRTL in accordance with ASTM E84 or UL 723, and be so labeled.

F. Component Supports:

1. Load ratings, features, and applications of all reinforcement components must be based on testing standards of a nationally recognized testing agency.
2. All component support attachments must comply with force and displacement resistance requirements of ASCE/SEI 7-05 Section 13.6.

2.2 RESTRAINTS - RIGID TYPE

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Atkore Unistrut.
2. B-Line; a division of Eaton, Electrical Sector.
3. CADDY; brand of nVent Electrical plc.
4. California Dynamics Corporation.
5. Hilti, Inc.
6. Isolation Technology, Inc.
7. TOLCO Incorporated.
8. VMC GROUP.

B. Description: Shop- or field-fabricated bracing assembly made of ANSI/AISI S110-07-S1 slotted steel channels, ANSI/ASTM A53/A53M steel pipe, or other rigid steel brace member. Includes accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; rated in tension, compression, and torsion forces.

2.3 RESTRAINTS - CABLE TYPE

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. B-Line; a division of Eaton, Electrical Sector.
2. CADDY; brand of nVent Electrical plc.
3. Gripple Inc.
4. Loos & Co. Inc.
5. VMC GROUP.

B. Seismic-Restraint Cables: ASTM A492 stainless steel cables. End connections made of steel assemblies with thimbles, brackets, swivel, and bolts designed for seismic-restraining cable service; with fittings attached by means of poured socket, swaged socket or mechanical (Flemish eye) loop.

C. Restraint cable assembly and cable fittings must comply with ASCE/SEI 19. All cable fittings and complete cable assembly must maintain the minimum cable breaking force. U-shaped cable clips and wedge-type end fittings do not comply and are unacceptable.

2.4 RESTRAINT ACCESSORIES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. Atkore Unistrut.
 2. B-Line; a division of Eaton, Electrical Sector.
 3. CADDY; brand of nVent Electrical plc.
 4. Hilti, Inc.
 5. Loos & Co. Inc.
 6. Mason Industries, Inc.
 7. TOLCO Incorporated.
- B. Hanger-Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections to hanger rod. Non-metallic stiffeners are unacceptable.
- C. Hinged and Swivel Brace Attachments: Multifunctional steel connectors for attaching hangers to rigid channel bracings and restraint cables.
- D. Bushings for Floor-Mounted Equipment Anchor Bolts: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchor bolts and studs.
- E. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices used.
- F. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.

2.5 POST-INSTALLED CONCRETE ANCHORS

- A. Mechanical Anchor Bolts:
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Atkore Unistrut.
 - b. B-Line; a division of Eaton, Electrical Sector.
 - c. Hilti, Inc.
 - d. Mason Industries, Inc.
 - e. Powers Fasteners.
 2. Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength for anchor and as tested according to ASTM E488/E488M.
- B. Adhesive Anchor Bolts:

- 1.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Atkore Unistrut.
 - b. B-Line; a division of Eaton, Electrical Sector.
 - c. Hilti, Inc.
 - d. Mason Industries, Inc.
 - e. Powers Fasteners.
 - 2.Drilled-in and capsule anchor system containing PVC or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E488/E488M.
- C. Provide post-installed concrete anchors that have been prequalified for use in seismic and wind-load applications. Post-installed concrete anchors must comply with all requirements of ASCE/SEI 7-05, Ch. 13.
- 1.Prequalify post-installed anchors in concrete in accordance with ACI 355.2 or other approved qualification testing procedures.
 - 2.Prequalify post-installed anchors in masonry in accordance with approved qualification procedures.
- D. Expansion-type anchor bolts are not permitted for equipment in excess of 10 hp that is not vibration isolated.
- 1.Undercut expansion anchors are permitted.

2.6 CONCRETE INSERTS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
- 1.Atkore Unistrut.
 - 2.B-Line; a division of Eaton, Electrical Sector.
 - 3.Hilti, Inc.
 - 4.Mason Industries, Inc.
 - 5.Powers Fasteners.
- B. Provide preset concrete inserts that are seismically prequalified in accordance with ICC-ES AC446 testing.
- C. Comply with MSS SP-58.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and equipment to receive seismic control devices for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Multiple Raceways or Cables: Secure raceways and cables to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
- B. Hanger-Rod Stiffeners: Install where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods caused by seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry static and seismic loads within specified loading limits.

3.3 INSTALLATION OF SEISMIC-RESTRAINT DEVICES

- A. Provide seismic-restraint devices for systems and equipment where indicated in Equipment Schedules or Electrical Seismic and Wind-Load Controls Schedule, where indicated on Drawings, where the Specifications indicate they are to be installed on specific equipment and systems, and where required by applicable codes.
 - 1. Install all equipment and devices to withstand the effects of earthquake motions determined in accordance with ASCE/SEI 7-05.
- B. Coordinate location of embedded connection hardware with supported equipment attachment and mounting points and with requirements for concrete reinforcement and formwork specified in Section 033000 "Cast-in-Place Concrete."
- C. Installation of seismic restraints must not cause any stresses, misalignment, or change of position of equipment or conduits.
- D. Equipment Restraints:
 - 1. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
 - 2. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction that provides required submittals for component.
- E. Raceway, Cable, Wireway, Cable Tray, and Busway Support and Hanger Restraints:

1. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
2. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction that provides required submittals for component.
3. Comply with requirements in NFPA 70 and ASCE/SEI 7.

F. Equipment and Hanger Restraints:

1. Install resilient, bolt-isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
2. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction providing required submittals for component.

G. Install cables so they do not bend across edges of adjacent equipment or building structure.

H. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.

I. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.

J. Post-Installed Concrete Anchors:

1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
3. Mechanical-Type Anchor Bolts: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
4. Adhesive-Type Anchor Bolts: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
5. Set anchors to manufacturer's recommended torque using a torque wrench.
6. Install zinc-coated steel anchors for interior and stainless steel anchors for exterior applications.

3.4 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Install flexible connections in runs of raceways, cables, wireways, cable trays, and busways where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where connection is terminated to equipment that is anchored to a different structural element from the one supporting them as they approach equipment.

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Tests and Inspections:
 - 1. Perform tests and inspections with the assistance of a factory-authorized service representative.
 - 2. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
 - 3. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
 - 4. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
 - 5. Test no fewer than four of each type and size of installed anchors and fasteners selected by Architect.
 - 6. Test to 90 percent of rated proof load of device.
- C. Seismic controls will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

END OF SECTION

SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Bands and tubes.
 - 2. Tapes and stencils.
 - 3. Tags.
 - 4. Signs.
 - 5. Cable ties.
 - 6. Miscellaneous identification products.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for electrical identification products.
- B. Samples: For each type of label and sign to illustrate composition, size, colors, lettering style, mounting provisions, and graphic features of identification products.
- C. Identification Schedule: For each piece of electrical equipment and electrical system components to be an index of nomenclature for electrical equipment and system components used in identification signs and labels. Use same designations indicated on Drawings.
- D. Delegated-Design Submittal: For arc-flash hazard study.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Comply with ASME A13.1 and IEEE C2.
- B. Comply with NFPA 70.
- C. Comply with 29 CFR 1910.144 and 29 CFR 1910.145.

- D. Comply with ANSI Z535.4 for safety signs and labels.
- E. Comply with NFPA 70E requirements for arc-flash warning labels.
- F. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.
- G. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.
 - 1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 COLOR AND LEGEND REQUIREMENTS

- A. Raceways and Cables Carrying Circuits at 600 V or Less:
 - 1. Legend: Indicate voltage.
- B. Color-Coding for Phase- and Voltage-Level Identification, 600 V or Less: Use colors listed below for ungrounded service, feeder and branch-circuit conductors.
 - 1. Color shall be factory applied or field applied for sizes larger than No. 8 AWG if authorities having jurisdiction permit.
 - 2. Colors for 208/120-V Circuits:
 - a. Phase A: Black.
 - b. Phase B: Red.
 - c. Phase C: Blue.
 - 3. Colors for 480/277-V Circuits:
 - a. Phase A: Brown.
 - b. Phase B: Orange.
 - c. Phase C: Yellow.
 - 4. Color for Neutral: White for 208/120V or natural gray for 480/277V.
 - 5. Color for Equipment Grounds: Green.
 - 6. Colors for Isolated Grounds: Green with two or more yellow stripes.
- C. Raceways and Cables Carrying Circuits at More Than 600 V:
 - 1. Black letters on an orange field.
 - 2. Legend: "DANGER - CONCEALED HIGH VOLTAGE WIRING."
- D. Warning Label Colors:
 - 1. Identify system voltage with black letters on an orange background.
- E. Warning labels and signs shall include, but are not limited to, the following legends:

1. Multiple Power Source Warning: "DANGER - ELECTRICAL SHOCK HAZARD - EQUIPMENT HAS MULTIPLE POWER SOURCES."
2. Workspace Clearance Warning: "WARNING - OSHA REGULATION - AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 36 INCHES."

F. Equipment Identification Labels:

1. Black letters on a white field.

2.3 BANDS AND TUBES

A. Snap-around, Color-Coding Bands: Slit, pretensioned, flexible, solid-colored acrylic sleeves, 2 inches long, with diameters sized to suit diameters and that stay in place by gripping action.

1.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Brady Corporation.
- b. HellermannTyton.
- c. Marking Services Inc.
- d. Panduit Corp.

B. Heat-Shrink Preprinted Tubes: Flame-retardant polyolefin tubes with machine-printed identification labels, sized to suit diameter and shrunk to fit firmly. Full shrink recovery occurs at a maximum of 200 deg F. Comply with UL 224.

2.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Brady Corporation.
- b. Panduit Corp.
- c. Marking Services Inc.

2.4 TAPES AND STENCILS

A. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.

3.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Brady Corporation.
- b. Carlton Industries, LP.
- c. Champion America.
- d. HellermannTyton.
- e. Ideal Industries, Inc.
- f. Marking Services Inc.

- g. Panduit Corp.
- B. Self-Adhesive Vinyl Tape: Colored, heavy duty, waterproof, fade resistant; not less than 3 mils thick by 1 to 2 inches wide; compounded for outdoor use.
- 4.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
- a. Brady Corporation.
 - b. Carlton Industries, LP.
 - c. Marking Services Inc.
 - d. emedco.
- C. Tape and Stencil: 4-inch- wide black stripes on 10-inch centers placed diagonally over orange background and are 12 inches wide. Stop stripes at legends.
- 5.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
- a. HellermannTyton.
 - b. LEM Products Inc.
 - c. Marking Services Inc.
 - d. Pipemarket.com; Brimar Industries, Inc.
 - e. Seton Identification Products; a Brady Corporation company.
- D. Floor Marking Tape: 2-inch- wide, 5-mil pressure-sensitive vinyl tape, with black and white stripes and clear vinyl overlay.
- 6.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
- a. Brady Corporation.
 - b. Carlton Industries, LP.
 - c. Seton Identification Products; a Brady Corporation company.
- E. Underground-Line Warning Tape:
- 7.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
- a. Brady Corporation.
 - b. Ideal Industries, Inc.
 - c. LEM Products Inc.
 - d. Marking Services Inc.
 - e. Pipemarket.com; Brimar Industries, Inc.
 - f. Reef Industries, Inc.
 - g. Seton Identification Products; a Brady Corporation company.

1. Tape:
 - a. Recommended by manufacturer for the method of installation and suitable to identify and locate underground electrical utility lines.
 - b. Printing on tape shall be permanent and shall not be damaged by burial operations.
 - c. Tape material and ink shall be chemically inert and not subject to degradation when exposed to acids, alkalis, and other destructive substances commonly found in soils.
2. Color and Printing:
 - a. Comply with ANSI Z535.1, ANSI Z535.2, ANSI Z535.3, ANSI Z535.4, and ANSI Z535.5.
 - b. Inscriptions for Red-Colored Tapes: "ELECTRIC LINE, HIGH VOLTAGE" .
 - c. Inscriptions for Orange-Colored Tapes: "TELEPHONE CABLE, CATV CABLE, COMMUNICATIONS CABLE, OPTICAL FIBER CABLE".
3. Tape Type I:
 - a. Pigmented polyolefin, bright colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
 - b. Width: 3 inches.
 - c. Thickness: 4 mils.
 - d. Weight: 18.5 lb/1000 sq. ft..
 - e. Tensile according to ASTM D882: 30 lbf and 2500 psi.
4. Tape Type II:
 - a. Multilayer laminate, consisting of high-density polyethylene scrim coated with pigmented polyolefin; bright colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
 - b. Width: 3 inches.
 - c. Thickness: 12 mils.
 - d. Weight: 36.1 lb/1000 sq. ft..
 - e. Tensile according to ASTM D882: 400 lbf and 11,500 psi.
5. Tape Type ID:
 - a. Detectable three-layer laminate, consisting of a printed pigmented polyolefin film, a solid aluminum-foil core, and a clear protective film that allows inspection of the continuity of the conductive core; bright colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
 - b. Width: 3 inches.
 - c. Overall Thickness: 5 mils.
 - d. Foil Core Thickness: 0.35 mil.
 - e. Weight: 28 lb/1000 sq. ft..
 - f. Tensile according to ASTM D882: 70 lbf and 4600 psi.
6. Tape Type IID:

- a. Reinforced, detectable three-layer laminate, consisting of a printed pigmented woven scrim, a solid aluminum-foil core, and a clear protective film that allows inspection of the continuity of the conductive core; bright-colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
 - b. Width: 3 inches.
 - c. Overall Thickness: 8 mils.
 - d. Foil Core Thickness: 0.35 mil.
 - e. Weight: 34 lb/1000 sq. ft..
 - f. Tensile according to ASTM D882: 300 lbf and 12,500 psi.
- F. Stenciled Legend: In nonfading, waterproof, black ink or paint. Minimum letter height shall be [1 inch].

2.5 TAGS

- A. Metal Tags: Brass or aluminum, 2 by 2 by 0.05 inch, with stamped legend, punched for use with self-locking cable tie fastener.
- 8.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
- a. Brady Corporation.
 - b. Carlton Industries, LP.
 - c. Marking Services Inc.
 - d. Seton Identification Products; a Brady Corporation company.
 - e. emedco.

2.6 SIGNS

- A. Baked-Enamel Signs:
- 9.Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
- a. Brady Corporation.
 - b. Carlton Industries, LP.
 - c. Champion America.
 - d. Marking Services Inc.
 - e. emedco.
1. Preprinted aluminum signs, high-intensity reflective, punched or drilled for fasteners, with colors, legend, and size required for application.
 2. 1/4-inch grommets in corners for mounting.
 3. Nominal Size: 7 by 10 inches.
- B. Metal-Backed Butyrate Signs:

10. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Brady Corporation.
 - b. Champion America.
 - c. Marking Services Inc.
 - d. emedco.
 1. Weather-resistant, nonfading, preprinted, cellulose-acetate butyrate signs, with 0.0396-inch galvanized-steel backing, punched and drilled for fasteners, and with colors, legend, and size required for application.
 2. 1/4-inch grommets in corners for mounting.
 3. Nominal Size: 10 by 14 inches.
- C. Laminated Acrylic or Melamine Plastic Signs:
11. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. Brady Corporation.
 - b. Carlton Industries, LP.
 - c. Marking Services Inc.
 - d. Seton Identification Products; a Brady Corporation company.
 - e. emedco.
 1. Engraved legend.
 2. Thickness:
 - a. For signs up to 20 sq. in., minimum 1/16 inch thick.
 - b. For signs larger than 20 sq. in., 1/8 inch thick.
 - c. Engraved legend with black letters on white face.
 - d. Self-adhesive.
 - e. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.
- D. Nameplate Material Colors:
12. Blue surface with white core for 120/208-volts equipment.
 - a. Bright red surface with white core for all equipment related to fire alarm system.
 - b. Dark red (burgundy) surface with white core for all equipment related to security.
 - c. Green surface with white core for all equipment related to emergency systems.
 - d. Orange surface with white core for all equipment related to telephone systems.
 - e. Brown surface with white core for all equipment related to data systems.
 - f. Purple surface with white core for all equipment related to TV systems.

2.7 CABLE TIES

- B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. HellermannTyton.
2. Ideal Industries, Inc.
3. Marking Services Inc.
4. Panduit Corp.

- A. General-Purpose Cable Ties: Fungus inert, self-extinguishing, one piece, self-locking, and Type 6/6 nylon.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 Deg F according to ASTM D638: 12,000 psi.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black, except where used for color-coding.

- B. UV-Stabilized Cable Ties: Fungus inert, designed for continuous exposure to exterior sunlight, self-extinguishing, one piece, self-locking, and Type 6/6 nylon.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 Deg F according to ASTM D638: 12,000 psi.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black.

- C. Plenum-Rated Cable Ties: Self-extinguishing, UV stabilized, one piece, and self-locking.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 Deg F according to ASTM D638: 7000 psi.
3. UL 94 Flame Rating: 94V-0.
4. Temperature Range: Minus 50 to plus 284 deg F.
5. Color: Black.

2.8 MISCELLANEOUS IDENTIFICATION PRODUCTS

- A. Paint: Comply with requirements in painting Sections for paint materials and application requirements. Retain paint system applicable for surface material and location (exterior or interior).

- B. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Self-Adhesive Identification Products: Before applying electrical identification products, clean substrates of substances that could impair bond, using materials and methods recommended by manufacturer of identification product.

3.2 INSTALLATION

- A. Verify and coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and operation and maintenance manual. Use consistent designations throughout Project.
- B. Install identifying devices before installing acoustical ceilings and similar concealment.
- C. Verify identity of each item before installing identification products.
- D. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and operation and maintenance manual.
- E. Apply identification devices to surfaces that require finish after completing finish work.
- F. Install signs with approved legend to facilitate proper identification, operation, and maintenance of electrical systems and connected items.
- G. System Identification for Raceways and Cables under 600 V: Identification shall completely encircle cable or conduit. Place identification of two-color markings in contact, side by side.
 - 1. Secure tight to surface of conductor, cable, or raceway.
- H. System Identification for Raceways and Cables over 600 V: Identification shall completely encircle cable or conduit. Place adjacent identification of two-color markings in contact, side by side.
 - 1. Secure tight to surface of conductor, cable, or raceway.
- I. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.
- J. Emergency Operating Instruction Signs: Install instruction signs with white legend on a red background with minimum 3/8-inch- high letters for emergency instructions at equipment used for power transfer.
- K. Elevated Components: Increase sizes of labels, signs, and letters to those appropriate for viewing from the floor.

- L. Accessible Fittings for Raceways: Identify the covers of each junction and pull box of the following systems with the wiring system legend and system voltage. Cover color shall follow same scheme as Section 2.6.D. System legends shall be as follows:
1. "EMERGENCY STANDBY POWER."
 2. "EMERGENCY LIFE SAFETY POWER"
 3. "POWER."
 4. "UPS."
- M. Vinyl Wraparound Labels:
1. Secure tight to surface of raceway or cable at a location with high visibility and accessibility.
 2. Attach labels that are not self-adhesive type with clear vinyl tape, with adhesive appropriate to the location and substrate.
- N. Snap-around Labels: Secure tight to surface at a location with high visibility and accessibility.
- O. Self-Adhesive Wraparound Labels: Secure tight to surface at a location with high visibility and accessibility.
- P. Self-Adhesive Labels:
1. On each item, install unique designation label that is consistent with wiring diagrams, schedules, and operation and maintenance manual.
 2. Unless otherwise indicated, provide a single line of text with 1/2-inch- high letters on 1-1/2-inch- high label; where two lines of text are required, use labels 2 inches high.
- Q. Snap-around Color-Coding Bands: Secure tight to surface at a location with high visibility and accessibility.
- R. Heat-Shrink, Preprinted Tubes: Secure tight to surface at a location with high visibility and accessibility.
- S. Marker Tapes: Secure tight to surface at a location with high visibility and accessibility.
- T. Self-Adhesive Vinyl Tape: Secure tight to surface at a location with high visibility and accessibility.
1. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding.
- U. Tape and Stencil: Comply with requirements in painting Sections for surface preparation and paint application.
- V. Floor Marking Tape: Apply stripes to finished surfaces following manufacturer's written instructions.
- W. Underground Line Warning Tape:

1. During backfilling of trenches, install continuous underground-line warning tape directly above cable or raceway at 6 to 8 inches below finished grade. Use multiple tapes where width of multiple lines installed in a common trench [or concrete envelope]exceeds 16 inches overall.
2. Limit use of underground-line warning tape to direct-buried cables.
3. Install underground-line warning tape for direct-buried cables and cables in raceways.

X. Metal Tags:

1. Place in a location with high visibility and accessibility.
2. Secure using plenum-rated cable ties.

Y. Nonmetallic Preprinted Tags:

1. Place in a location with high visibility and accessibility.
2. Secure using plenum-rated cable ties.

Z. Write-on Tags:

1. Place in a location with high visibility and accessibility.
2. Secure using plenum-rated cable ties.

AA. Baked-Enamel Signs:

1. Attach signs that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
2. Unless otherwise indicated, provide a single line of text with 1/2-inch- high letters on minimum 1-1/2-inch- high sign; where two lines of text are required, use signs minimum 2 inches high.

BB. Metal-Backed Butyrate Signs:

1. Attach signs that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
2. Unless otherwise indicated, provide a single line of text with 1/2-inch- high letters on 1-1/2-inch- high sign; where two lines of text are required, use labels 2 inches high.

CC. Laminated Acrylic or Melamine Plastic Signs:

1. Attach signs that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
2. Unless otherwise indicated, provide a single line of text with 1/2-inch- high letters on 1-1/2-inch- high sign; where two lines of text are required, use labels 2 inches high.

DD. Cable Ties: General purpose, for attaching tags, except as listed below:

1. Outdoors: UV-stabilized nylon.
2. In Spaces Handling Environmental Air: Plenum rated.

3.3 IDENTIFICATION SCHEDULE

- A. Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment. Install access doors or panels to provide view of identifying devices.
- B. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, pull points, and locations of high visibility. Identify by system and circuit designation.
- C. Concealed Raceways, Duct Banks, More Than 600 V, within Buildings: Tape and stencil. Stencil legend "DANGER - CONCEALED HIGH-VOLTAGE WIRING" with 3-inch- high, black letters on 20-inch centers.
 - 1. Locate identification at changes in direction, at penetrations of walls and floors, and at [10-foot] [30-foot] maximum intervals.
- D. Accessible Raceways and Metal-Clad Cables, 600 V or Less, for Service, Feeder, and Branch Circuits, More Than 30 A and 120 V to Ground: Identify with self-adhesive vinyl tape applied in bands.
 - 1. Locate identification at changes in direction, at penetrations of walls and floors, at 50-foot maximum intervals in straight runs, and at 25-foot maximum intervals in congested areas.
- E. Accessible Fittings for Raceways and Cables within Buildings: Identify the covers of each junction and pull box of the following systems with self-adhesive labels containing the wiring system legend and system voltage. System legends shall be as follows:
 - 1. "EMERGENCY POWER."
 - 2. "EMERGENCY LIFE SAFETY POWER"
 - 3. "POWER."
 - 4. "UPS."
- F. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use self-adhesive vinyl tape to identify the phase.
 - 1. Locate identification at changes in direction, at penetrations of walls and floors, at 50-foot maximum intervals in straight runs, and at 25-foot maximum intervals in congested areas.
- G. Control-Circuit Conductor Identification: For conductors and cables in pull and junction boxes, manholes, and handholes, use write-on tags with the conductor or cable designation, origin, and destination.
- H. Control-Circuit Conductor Termination Identification: For identification at terminations, provide heat-shrink preprinted tubes with the conductor designation.
- I. Conductors to Be Extended in the Future: Attach marker tape to conductors and list source.
- J. Auxiliary Electrical Systems Conductor Identification: Marker tape that is uniform and consistent with system used by manufacturer for factory-installed connections.

1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
- K. Locations of Underground Lines: Underground-line warning tape for power, lighting, communication, and control wiring and optical-fiber cable.
- L. Concealed Raceways and Duct Banks, More Than 600 V, within Buildings: Apply floor marking tape to the following finished surfaces:
1. Floor surface directly above conduits running beneath and within 12 inches of a floor that is in contact with earth or is framed above unexcavated space.
 2. Wall surfaces directly external to raceways concealed within wall.
 3. Accessible surfaces of concrete envelope around raceways in vertical shafts, exposed in the building, or concealed above suspended ceilings.
- M. Workspace Indication: Apply floor marking tape to finished surfaces. Show working clearances in the direction of access to live parts. Workspace shall comply with NFPA 70 and 29 CFR 1926.403 unless otherwise indicated. Do not install at flush-mounted panelboards and similar equipment in finished spaces.
- N. Instructional Signs: Self-adhesive labels, including the color code for grounded and ungrounded conductors.
- O. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Baked-enamel warning signs.
1. Apply to exterior of door, cover, or other access.
 2. For equipment with multiple power or control sources, apply to door or cover of equipment, including, but not limited to, the following:
 - a. Power-transfer switches.
 - b. Controls with external control power connections.
- P. Arc Flash Warning Labeling: Self-adhesive labels.
- Q. Operating Instruction Signs: Baked-enamel warning signs.
- R. Emergency Operating Instruction Signs: Baked-enamel warning signs with white legend on a red background with minimum 3/8-inch- high letters for emergency instructions at equipment used for power transfer.
- S. Equipment Identification Labels:
1. Indoor Equipment: Baked-enamel signs.
 2. Outdoor Equipment: Laminated acrylic or melamine sign, Stenciled legend 4 inches high.
 3. Equipment to Be Labeled:
 - a. Panelboards: Typewritten directory of circuits in the location provided by panelboard manufacturer. Panelboard identification shall be in the form of a self-adhesive, engraved, laminated acrylic or melamine label.
 - b. Enclosures and electrical cabinets.

- c. Access doors and panels for concealed electrical items.
- d. Emergency system boxes and enclosures.
- e. Enclosed switches.
- f. Enclosed circuit breakers.
- g. Enclosed controllers.
- h. Variable-speed controllers.
- i. Push-button stations.
- j. Power-transfer equipment.
- k. Contactors.
- l. Remote-controlled switches, dimmer modules, and control devices.
- m. Battery racks.
- n. Power-generating units.
- o. Monitoring and control equipment.

END OF SECTION

SECTION 260573 - COORDINATION STUDIES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes computer-based, overcurrent protective device coordination studies to determine overcurrent protective devices and to determine overcurrent protective device settings for selective tripping.
 - 1. Study results shall be used to determine coordination of series-rated devices.

1.2 DEFINITIONS

- A. Field Adjusting Agency: An independent electrical testing agency with full-time employees and the capability to adjust devices and conduct testing indicated and that is a member company of NETA.
- B. One-Line Diagram: A diagram that shows, by means of single lines and graphic symbols, the course of an electric circuit or system of circuits and the component devices or parts used therein.
- C. Power System Analysis Software Developer: An entity that commercially develops, maintains, and distributes computer software used for power system studies.
- D. Power System Analysis Specialist: Professional engineer in charge of performing the study and documenting recommendations, licensed in the state where Project is located.
- E. Protective Device: A device that senses when an abnormal current flow exists and then removes the affected portion of the circuit from the system.
- F. SCCR: Short-circuit current rating.
- G. Service: The conductors and equipment for delivering electric energy from the serving utility to the wiring system of the premises served.
- H. Single-Line Diagram: See "One-Line Diagram."

1.3 ACTION SUBMITTALS

- A. Product Data:
 - 1. For computer software program to be used for studies.
 - 2. Submit the following after the approval of system protective devices submittals. Submittals shall be in digital form.
 - a. Coordination-study input data, including completed computer program input data sheets.
 - b. Study and equipment evaluation reports.

3. Overcurrent protective device coordination study report; signed, dated, and sealed by a qualified professional engineer.
 - a. Submit study report for action prior to receiving final approval of distribution equipment submittals. If formal completion of studies will cause delay in equipment manufacturing, obtain approval from Engineer for preliminary submittal of sufficient study data to ensure that selection of devices and associated characteristics is satisfactory.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data:
 1. For Power System Analysis Software Developer.
 2. For Power Systems Analysis Specialist.
 3. For Field Adjusting Agency.
- B. Product Certificates: For overcurrent protective device coordination study software, certifying compliance with IEEE 399.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For overcurrent protective devices to include in emergency, operation, and maintenance manuals.
 1. The following are from the Coordination Study Report:
 - a. Final one-line diagram.
 - b. Final protective device coordination study.
 - c. Coordination study data files.
 - d. List of all protective device settings.
 - e. Time-current coordination curves.
 - f. Power system data.

1.6 QUALITY ASSURANCE

- A. Studies shall be performed using commercially developed and distributed software designed specifically for power system analysis.
- B. Software algorithms shall comply with requirements of standards and guides specified in this Section.
- C. Manual calculations are unacceptable.
- D. Power System Analysis Software Qualifications:
 1. Computer program shall be designed to perform coordination studies or have a function, component, or add-on module designed to perform coordination studies.
 2. Computer program shall be developed under the charge of a licensed professional engineer who holds IEEE Computer Society's Certified Software Development Professional certification.

- E. Power Systems Analysis Specialist Qualifications: Professional engineer licensed in the state where Project is located. All elements of the study shall be performed under the direct supervision and control of this professional engineer.
- F. Field Adjusting Agency Qualifications:
 - 1. Employer of a NETA ETT-Certified Technician Level III responsible for all field adjusting of the Work.
 - 2. A member company of NETA.
 - 3. Acceptable to authorities having jurisdiction.

PART 2 - PRODUCTS

2.1 POWER SYSTEM ANALYSIS SOFTWARE DEVELOPERS

- A. Software: SKM Systems Analysis, Inc.
- B. Comply with IEEE 242 and IEEE 399.
- C. Analytical features of device coordination study computer software program shall have the capability to calculate "mandatory," "very desirable," and "desirable" features as listed in IEEE 399.
- D. Computer software program shall be capable of plotting and diagramming time-current-characteristic curves as part of its output. Computer software program shall report device settings and ratings of all overcurrent protective devices and shall demonstrate selective coordination by computer-generated, time-current coordination plots.
 - 1. Optional Features:
 - a. Arcing faults.
 - b. Simultaneous faults.
 - c. Explicit negative sequence.
 - d. Mutual coupling in zero sequence.

2.2 COORDINATION STUDY REPORT CONTENTS

- A. Executive summary of study findings.
- B. Study descriptions, purpose, basis, and scope. Include case descriptions, definition of terms, and guide for interpretation of results.
- C. One-line diagram of modeled power system, showing the following:
 - 1. Protective device designations and ampere ratings.
 - 2. Conductor types, sizes, and lengths.
 - 3. Transformer kilovolt ampere (kVA) and voltage ratings.
 - 4. Motor and generator designations and kVA ratings.
 - 5. Switchgear, switchboard, motor-control center, and panelboard designations.
 - 6. Any revisions to electrical equipment required by the study.
- D. Protective Device Coordination Study:

1. Report recommended settings of protective devices, ready to be applied in the field. Use manufacturer's data sheets for recording the recommended setting of overcurrent protective devices when available.
 - a. Phase and Ground Relays:
 - 1) Device tag.
 - 2) Relay current transformer ratio and tap, time dial, and instantaneous pickup value.
 - 3) Recommendations on improved relaying systems, if applicable.
 - b. Circuit Breakers:
 - 1) Adjustable pickups and time delays (long time, short time, and ground).
 - 2) Adjustable time-current characteristic.
 - 3) Adjustable instantaneous pickup.
 - 4) Recommendations on improved trip systems, if applicable.
 - c. Fuses: Show current rating, voltage, and class.

- E. Time-Current Coordination Curves: Determine settings of overcurrent protective devices to achieve selective coordination. Graphically illustrate that adequate time separation exists between devices installed in series, including power utility company's upstream devices. Prepare separate sets of curves for the switching schemes and for emergency periods where the power source is local generation. Show the following information:
 1. Device tag and title, one-line diagram with legend identifying the portion of the system covered.
 2. Terminate device characteristic curves at a point reflecting maximum symmetrical or asymmetrical fault current to which the device is exposed.
 3. Identify the device associated with each curve by manufacturer type, function, and, if applicable, tap, time delay, and instantaneous settings recommended.
 4. Plot the following listed characteristic curves, as applicable:
 - a. Power utility's overcurrent protective device.
 - b. Medium-voltage equipment overcurrent relays.
 - c. Medium- and low-voltage fuses including manufacturer's minimum melt, total clearing, tolerance, and damage bands.
 - d. Low-voltage equipment circuit-breaker trip devices, including manufacturer's tolerance bands.
 - e. Transformer full-load current, magnetizing inrush current, and ANSI through-fault protection curves.
 - f. Cables and conductors damage curves.
 - g. Ground-fault protective devices.
 - h. Motor-starting characteristics and motor damage points.
 - i. Generator short-circuit decrement curve and generator damage point.
 - j. The largest feeder circuit breaker in each motor-control center and panelboard.
 5. Maintain selectivity for tripping currents caused by overloads.
 6. Maintain maximum achievable selectivity for tripping currents caused by overloads on series-rated devices.
 7. Provide adequate time margins between device characteristics such that selective operation is achieved.
 8. Comments and recommendations for system improvements.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine Project overcurrent protective device submittals for compliance with electrical distribution system coordination requirements and other conditions affecting performance of the Work. Devices to be coordinated are indicated on Drawings.
1. Proceed with coordination study only after relevant equipment submittals have been assembled. Overcurrent protective devices that have not been submitted and approved prior to coordination study may not be used in study.

3.2 POWER SYSTEM DATA

- A. Obtain all data necessary for conduct of the overcurrent protective device study.
1. Verify completeness of data supplied in one-line diagram on Drawings. Call any discrepancies to Engineer's attention.
 2. For equipment included as Work of this Project, use characteristics submitted under provisions of action submittals and information submittals for this Project.
- B. Gather and tabulate all required input data to support the coordination study. List below is a guide. Comply with recommendations in IEEE 551 for the amount of detail required to be acquired in the field. Field data gathering shall be under direct supervision and control of the engineer in charge of performing the study, and shall be by the engineer or its representative who holds NETA ETT-Certified Technician Level III or NICET Electrical Power Testing Level III certification. Data include, but are not limited to, the following:
1. Product Data for overcurrent protective devices specified in other Sections and involved in overcurrent protective device coordination studies. Use equipment designation tags that are consistent with electrical distribution system diagrams, overcurrent protective device submittals, input and output data, and recommended device settings.
 2. Electrical power utility impedance at the service.
 3. Power sources and ties.
 4. Short-circuit current at each system bus (three phase and line to ground).
 5. Full-load current of all loads.
 6. Voltage level at each bus.
 7. For transformers, include kVA, primary and secondary voltages, connection type, impedance, X/R ratio, taps measured in percent, and phase shift.
 8. For reactors, provide manufacturer and model designation, voltage rating, and impedance.
 9. For circuit breakers and fuses, provide manufacturer and model designation. List type of breaker, type of trip and available range of settings, SCCR, current rating, and breaker settings.
 10. Generator short-circuit current contribution data, including short-circuit reactance, rated kVA, rated voltage, and X/R ratio.
 11. For relays, provide manufacturer and model designation, current transformer ratios, potential transformer ratios, and relay settings.
 12. Maximum demands from service meters.
 13. Busway manufacturer and model designation, current rating, impedance, lengths, size, and conductor material.
 14. Motor horsepower and NEMA MG 1 code letter designation.

15. Low-voltage cable sizes, lengths, number, conductor material, and conduit material (magnetic or nonmagnetic).
16. Medium-voltage cable sizes, lengths, conductor material, cable construction, metallic shield performance parameters, and conduit material (magnetic or nonmagnetic).
17. Data sheets to supplement electrical distribution system one-line diagram, cross-referenced with tag numbers on diagram, showing the following:
 - a. Special load considerations, including starting inrush currents and frequent starting and stopping.
 - b. Transformer characteristics, including primary protective device, magnetic inrush current, and overload capability.
 - c. Motor full-load current, locked rotor current, service factor, starting time, type of start, and thermal-damage curve.
 - d. Generator thermal-damage curve.
 - e. Ratings, types, and settings of utility company's overcurrent protective devices.
 - f. Special overcurrent protective device settings or types stipulated by utility company.
 - g. Time-current-characteristic curves of devices indicated to be coordinated.
 - h. Manufacturer, frame size, interrupting rating in amperes root mean square (rms) symmetrical, ampere or current sensor rating, long-time adjustment range, short-time adjustment range, and instantaneous adjustment range for circuit breakers.
 - i. Manufacturer and type, ampere-tap adjustment range, time-delay adjustment range, instantaneous attachment adjustment range, and current transformer ratio for over-current relays.
 - j. Switchgear, switchboards, motor-control centers, and panelboards ampacity, and SCCR in amperes rms symmetrical.
 - k. Identify series-rated interrupting devices for a condition where the available fault current is greater than the interrupting rating of downstream equipment. Obtain device data details to allow verification that series application of these devices complies with NFPA 70 and UL 489 requirements.

3.3 COORDINATION STUDY

- A. Comply with IEEE 242 for calculating short-circuit currents and determining coordination time intervals.
- B. Comply with IEEE 399 for general study procedures.
- C. Base study on device characteristics supplied by device manufacturer.
- D. Extent of electrical power system to be studied is indicated on Drawings.
- E. Begin analysis at the service, extending down to system overcurrent protective devices as follows:
 1. To normal system low-voltage load buses where fault current is 10 kA or less.
 2. Retain first subparagraph below when authorities having jurisdiction do not require
 3. Exclude equipment rated 240 V ac or less when supplied by a single transformer rated less than 125 kVA.
- F. Study electrical distribution system from normal and alternate power sources throughout electrical distribution system for Project. Study all cases of system-switching configurations and alternate operations that could result in maximum fault conditions.

- G. Transformer Primary Overcurrent Protective Devices:
 - 1. Device shall not operate in response to the following:
 - a. Inrush current when first energized.
 - b. Self-cooled, full-load current or forced-air-cooled, full-load current, whichever is specified for that transformer.
 - c. Permissible transformer overloads according to IEEE C57.96 if required by unusual loading or emergency conditions.
 - 2. Device settings shall protect transformers according to IEEE C57.12.00, for fault currents.
- H. Motor Protection:
 - 1. Select protection for low-voltage motors according to IEEE 242 and NFPA 70.
 - 2. Select protection for motors served at voltages more than 600 V according to IEEE 620.
- I. Conductor Protection: Protect cables against damage from fault currents according to ICEA P-32-382, ICEA P-45-482, and protection recommendations in IEEE 242. Demonstrate that equipment withstands the maximum short-circuit current for a time equivalent to the tripping time of the primary relay protection or total clearing time of the fuse. To determine temperatures that damage insulation, use curves from cable manufacturers or from listed standards indicating conductor size and short-circuit current.
- J. Generator Protection: Select protection according to manufacturer's written instructions and to IEEE 242.
- K. Include the arc fault-current decay from induction motors, synchronous motors, and asynchronous generators and apply to low- and medium-voltage, three-phase ac systems. Also account for fault-current dc decrement, to address asymmetrical requirements of interrupting equipment.
- L. Calculate short-circuit momentary and interrupting duties for a three-phase bolted fault and a single line-to-ground fault at each equipment indicated on one-line diagram.
 - 1. For grounded systems, provide a bolted line-to-ground fault-current study for areas as defined for the three-phase bolted fault short-circuit study.
- M. Protective Device Evaluation:
 - 1. Evaluate equipment and protective devices and compare to short-circuit ratings.
 - 2. Adequacy of switchgear, motor-control centers, and panelboard bus bars to withstand short-circuit stresses.
 - 3. Any application of series-rated devices shall be recertified, complying with requirements in NFPA 70.
 - 4. Include in the report identification of any protective device applied outside its capacity.

3.4 LOAD-FLOW AND VOLTAGE-DROP STUDY

- A. Perform a load-flow and voltage-drop study to determine the steady-state loading profile of the system. Analyze power system performance two times as follows:
 - 1. Determine load flow and voltage drop based on full-load currents obtained in "Power System Data" Article.
 - 2. Determine load flow and voltage drop based on 80 percent of the design capacity of load buses.

3. Prepare load-flow and voltage-drop analysis and report to show power system components that are overloaded, or might become overloaded; show bus voltages that are less than as prescribed by NFPA 70.

3.5 MOTOR-STARTING STUDY

- A. Perform a motor-starting study to analyze the transient effect of system's voltage profile during motor starting. Calculate significant motor-starting voltage profiles and analyze the effects of motor starting on the power system stability.
- B. Prepare the motor-starting study report, noting light flicker for limits proposed by IEEE 141, and voltage sags so as not to affect operation of other utilization equipment on system supplying the motor.

3.6 FIELD ADJUSTING

- A. Adjust relay and protective device settings according to recommended settings provided by the coordination study. Field adjustments shall be completed by the engineering service division of equipment manufacturer under the "Startup and Acceptance Testing" contract portion.
- B. Make minor modifications to equipment as required to accomplish compliance with short-circuit and protective device coordination studies.
- C. Testing and adjusting shall be by a full-time employee of the Field Adjusting Agency, who holds NETA ETT-Certified Technician Level III or NICET Electrical Power Testing Level III certification.
 1. Perform each visual and mechanical inspection and electrical test stated in NETA ATS. Certify compliance with test parameters. Perform NETA tests and inspections for all adjustable overcurrent protective devices.

3.7 DEMONSTRATION

- A. Engage Power Systems Analysis Specialist to train Owner's maintenance personnel in the following:
 1. Acquaint personnel in fundamentals of operating the power system in normal and emergency modes.
 2. Hand-out and explain the coordination study objectives, study descriptions, purpose, basis, and scope. Include case descriptions, definition of terms, and guide for interpreting time-current coordination curves.
 3. For Owner's maintenance staff certified as NETA ETT-Certified Technicians Level III or NICET Electrical Power Testing Level III Technicians, teach how to adjust, operate, and maintain overcurrent protective device settings.

3.8 ARC FLASH ANALYSIS

- A. The Engineer of Record will perform an Arc Flash Analysis of the installed system after the completion of the coordination study. The Arc Flash Labels for each panel will be provided by the Engineer and will be installed on the panels by the contractor.

END OF SECTION

SECTION 260800 - COMMISSIONING OF ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Electrical equipment connected to Essential electrical systems that provide an alternative source of power in the absence of power from the Normal electrical system, including the following:
 - a. Generators.

1.2 DEFINITIONS

- A. Cx: Commissioning.
- B. CxA: Commissioning Authority.

1.3 INFORMATIONAL SUBMITTALS

- A. Construction Checklists by Contractor: Include the following and comply with requirements in Section 019113 "General Commissioning Requirements" for construction checklists:
 1. Engine generators.

1.4 QUALITY ASSURANCE

- A. Testing Equipment and Instrumentation Quality and Calibration: For test equipment and instrumentation required to perform electrical Cx work, perform the following:
 1. Submit test equipment and instrumentation list. For each equipment or instrument, identify the following:
 - a. Equipment/instrument identification number.
 - b. Planned Cx application or use.
 - c. Manufacturer, make, model, and serial number.
 - d. Calibration history, including certificates from agencies that calibrate the equipment and instrumentation.
 2. Test equipment and instrumentation must meet the following criteria:
 - a. Capable of testing and measuring performance within the specified acceptance criteria.
 - b. Be calibrated at manufacturer's recommended intervals with current calibration tags permanently affixed to the instrument being used.

- c. Be maintained in good repair and operating condition throughout duration of use on Project.
- d. Be recalibrated/repaired if dropped or damaged in any way since last calibrated.

B. Proprietary Test Instrumentation and Tools:

1. Equipment Manufacturer's Proprietary Instrumentation and Tools: For installed equipment included in the Cx process, test instrumentation and tools manufactured or prescribed by equipment manufacturer to service, calibrate, adjust, repair, or otherwise work on its equipment or required as a condition of equipment warranty, perform the following:
 - a. Submit proprietary instrumentation and tools list. For each instrument or tool, identify the following:
 - 1) Instrument or tool identification number.
 - 2) Equipment schedule designation of equipment for which the instrument or tool is required.
 - 3) Manufacturer, make, model, and serial number.
 - 4) Calibration history, including certificates from agencies that calibrate the instrument or tool, where appropriate.
 - b. Include a separate list of proprietary test instrumentation and tools in operation and maintenance manuals.
 - c. Electrical proprietary test instrumentation and tools become property of Owner at the time of Substantial Completion.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 CONSTRUCTION CHECKLISTS

- A. Prepare detailed construction checklists for electrical systems, subsystems, equipment, and components. Complete and submit construction checklists.

3.2 CONSTRUCTION CHECKLIST REVIEW

- A. Review and provide written comments on draft construction checklists. CxA will create required draft construction checklists and provide them to Contractor.
- B. Return draft Construction Checklist review comments within 10 days of receipt.
- C. When review comments have been resolved, CxA will provide final construction checklists, marked "Approved for Use, (date)."
- D. Use only construction checklists, marked "Approved for Use, (date)."

3.3 GENERAL TESTING REQUIREMENTS

- A. Certify that electrical systems, subsystems, and equipment have been installed, calibrated, and started and that they are operating according to the Contract Documents and approved Shop Drawings and submittals.
- B. Certify that electrical instrumentation and control systems have been completed and calibrated, that they are operating according to the Contract Documents and approved Shop Drawings and submittals, and that pretest set points have been recorded.
- C. Set systems, subsystems, and equipment into operating mode to be tested according to approved test procedures (for example, normal shutdown, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).
- D. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment, and components, including operational and control functions to verify compliance with acceptance criteria.
- E. Test systems, assemblies, subsystems, equipment, and components operating modes, interlocks, control responses, and responses to abnormal or emergency conditions, and response according to acceptance criteria.
- F. Construction Checklists: Prepare and submit detailed construction checklists for electrical systems, subsystems, equipment, and components.
 - 1. Contributors to development of construction checklists must include, but are not limited to, the following:
 - a. Electrical systems and equipment installers.
 - b. Electrical instrumentation and controls installers.
- G. Perform tests using design conditions, whenever possible.
 - 1. Simulated conditions may, with approval of Architect, be imposed using an artificial load when it is impractical to test under design conditions. Before simulating conditions, calibrate testing instruments. Provide equipment to simulate loads. Set simulated conditions as directed by CxA, and document simulated conditions and methods of simulation. After tests, return configurations and settings to normal operating conditions.
 - 2. Cx test procedures may direct that set points be altered when simulating conditions is impractical.
 - 3. Cx test procedures may direct that sensor values be altered with a signal generator when design or simulating conditions and altering set points are impractical.
- H. If tests cannot be completed because of a deficiency outside the scope of the electrical system, document the deficiency and report it to Owner. After deficiencies are resolved, reschedule tests.
- I. If seasonal testing is specified, complete appropriate initial performance tests and documentation and schedule seasonal tests.
- J. Coordinate schedule with, and perform Cx activities at the direction of the CxA.

- K. Comply with Construction Checklist requirements, including material verification, installation checks, startup, and performance tests requirements specified in Sections specifying electrical systems and equipment.
- L. Provide qualified testing and inspecting agency personnel including instrumentation, tools, and equipment to complete and document the following:
 - 1. Performance tests.
 - 2. Demonstration of a sample of performance tests.
 - 3. Cx tests.
 - 4. Cx test demonstrations.

3.4 TESTS FOR ELECTRICAL SYSTEMS

- A. Verification of Normal Electrical System Operation:
 - 1. Prerequisites: Acceptance of results for construction checklists for Division 26 electrical components associated with Normal electrical system.
 - 2. Equipment and Systems to Be Tested: Division 26 electrical equipment.
 - 3. Test Purpose: Verify operation of Normal electrical system.
 - 4. Test Conditions: Energize components of Normal electrical system, one at a time.
- B. Verification of Essential Electrical System Operation:
 - 1. Prerequisites:
 - a. Acceptance of results for construction checklists for Division 26 electrical components associated with Essential electrical system.
 - 2. Equipment and Systems to Be Tested: Division 26 electrical equipment.
 - 3. Test Purpose: Verify operation of Essential electrical system.
 - 4. Test Conditions:
 - a. Simulate a failure of Normal electrical system.
 - 5. Acceptance Criteria: Transfer of power from Essential electrical system within OPR.
- C. Test Purpose: Verify operation of control and monitoring systems for Essential electrical systems.
- D. Test Conditions:
 - 1. Energize components of Normal electrical system.
 - 2. Test operation of equipment.
- E. Acceptance Criteria: Operation of equipment according to OPR.

END OF SECTION 260800

SECTION 260923 - LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Electronic time switches.
2. Outdoor photoelectric switches, solid state, flexible mounting.
3. Outdoor photoelectric switches, solid state, luminaire-mounted.
4. Outdoor photoelectric switches, low voltage.
5. Indoor occupancy and vacancy sensors.
6. Switchbox-mounted occupancy sensors.
7. Outdoor motion sensors.
8. Lighting contactors.
9. Emergency shunt relay.
10. Conductors and cables.

B. Related Requirements:

1. Section 262726 "Wiring Devices" for wall-box dimmers, non-networkable wall-switch occupancy sensors, and manual light switches.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings:

1. Show installation details for the following:
 - a. Occupancy sensors.
 - b. Vacancy sensors.
2. Interconnection diagrams showing field-installed wiring.
3. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plan(s) and elevations, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
- 1.Suspended ceiling components.
 - 2.Structural members to which equipment will be attached.
 - 3.Items penetrating finished ceiling, including the following:
 - a. Luminaires.
 - b. Air outlets and inlets.
 - c. Speakers.
 - d. Sprinklers.
 - e. Access panels.
 - f. Control modules.
 - g. <Insert item>.
- B. Field quality-control reports.
- C. Sample Warranty: For manufacturer's warranties.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For each type of lighting control device to include in operation and maintenance manuals.
- B. Software and Firmware Operational Documentation:
- 1.Software operating and upgrade manuals.
 - 2.Program Software Backup: On USB media. Provide names, versions, and website addresses for locations of installed software.
 - 3.Device address list.
 - 4.Printout of software application and graphic screens.

1.6 WARRANTY

- A. Manufacturer's Warranty: Manufacturer and Installer agree to repair or replace lighting control devices that fail(s) in materials or workmanship within specified warranty period.
- 1.Failures include, but are not limited to, the following:
 - a. Faulty operation of lighting control software.
 - b. Faulty operation of lighting control devices.
 - 2.Warranty Period: Two year(s) from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 ELECTRONIC TIME SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Eaton.
2. Intermatic, Inc.
3. Leviton Manufacturing Co., Inc.
4. NSi Industries LLC.
5. Schneider Electric USA, Inc.
6. TE Connectivity Ltd.
7. Touché Lighting Control.
8. nLight; Acuity Brands Lighting, Inc.

- B. Electronic Time Switches: Solid state, programmable, with alphanumeric display; complying with UL 917.

1. Listed and labeled as defined in NFPA 70 and marked for intended location and application.
2. Contact Configuration: SPST.
3. Contact Rating: 30-A inductive or resistive, 240-V ac.
4. Programs:

- a. Eight on-off set points on a 24-hour schedule and an annual holiday schedule that overrides the weekly operation on holidays.
- b. Two on-off set points on a 24-hour schedule, allowing different set points for each day of the week and an annual holiday schedule that overrides the weekly operation on holidays.

5. Circuitry: Allow connection of a photoelectric relay as substitute for on-off function of a program.
6. Astronomic Time: All channels.
7. Automatic daylight savings time changeover.
8. Battery Backup: Not less than seven days reserve, to maintain schedules and time clock.

2.2 INDOOR OCCUPANCY

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. nLight; Acuity Brands Lighting, Inc.

- B. General Requirements for Sensors:

1. Wall or Ceiling-mounted, solid-state indoor occupancy sensors.
2. Dual technology.
3. Integrated power pack.
4. Hardwired connection to switch.

5. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

6. Operation:

- a. Occupancy Sensor: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
- b. Vacancy Sensor: Unless otherwise indicated, lights are manually turned on and sensor turns lights off when the room is unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
- c. Combination Sensor: Unless otherwise indicated, sensor shall be programmed to turn lights on when coverage area is occupied and turn them off when unoccupied, or to turn off lights that have been manually turned on; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.

7. Sensor Output: Sensor is powered from the power pack.

8. Power: Line voltage.

9. Power Pack: Dry contacts rated for 20-A LED load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Sensor has 24-V dc, 150-mA, Class 2 power source, as defined by NFPA 70.

10. Mounting:

- a. Sensor: Suitable for mounting in any position on a standard outlet box.
- b. Relay: Externally mounted through a 1/2-inch knockout in a standard electrical enclosure.
- c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.

11. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.

12. Bypass Switch: Override the "on" function in case of sensor failure.

13. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc; turn lights off when selected lighting level is present.

C. PIR Type: Wall or Ceiling mounted; detect occupants in coverage area by their heat and movement.

1. Detector Sensitivity: Detect occurrences of 6-inch- minimum movement of any portion of a human body that presents a target of not less than 36 sq. in..
2. Detection Coverage (Room, Ceiling Mounted): Detect occupancy anywhere in a circular area of 1000 sq. ft. when mounted on a 96-inch- high ceiling.
3. Detection Coverage (Corridor, Ceiling Mounted): Detect occupancy within 90 feet when mounted on a 10-foot- high ceiling.
4. Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 2000 square feet when mounted 48 inches above finished floor.

D. Ultrasonic Type: Wall or Ceiling mounted; detect occupants in coverage area through pattern changes of reflected ultrasonic energy.

1. Detector Sensitivity: Detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
 2. Detection Coverage (Small Room): Detect occupancy anywhere within a circular area of 600 sq. ft. when mounted on a 96-inch- high ceiling.
 3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. when mounted on a 96-inch- high ceiling.
 4. Detection Coverage (Large Room): Detect occupancy anywhere within a circular area of 2000 sq. ft. when mounted on a 96-inch- high ceiling.
 5. Detection Coverage (Corridor): Detect occupancy anywhere within 90 feet when mounted on a 10-foot- high ceiling in a corridor not wider than 14 feet.
 6. Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 2000 square feet when mounted 84 inches above finished floor.
- E. Dual-Technology Type: Wall or Ceiling mounted; detect occupants in coverage area using PIR and ultrasonic detection methods. The particular technology or combination of technologies that control on-off functions is selectable in the field by operating controls on unit.
1. Sensitivity Adjustment: Separate for each sensing technology.
 2. Detector Sensitivity: Detect occurrences of 6-inch- minimum movement of any portion of a human body that presents a target of not less than 36 sq. in., and detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
 3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. when mounted on a 96-inch- high ceiling.
 4. Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 2000 square feet when mounted 48 inches above finished floor.

2.3 LIGHTING CONTACTORS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. ABB, Electrification Business.
 2. ASCO Power Technologies.
 3. Allen-Bradley/Rockwell Automation.
 4. Eaton.
 5. Leviton Manufacturing Co., Inc.
 6. Square D; Schneider Electric USA.
- B. Description: Electrically operated and mechanically held, combination-type lighting contactors with nonfused disconnect, complying with NEMA ICS 2 and UL 508.
1. Current Rating for Switching: Listing or rating consistent with type of load served, including tungsten filament, inductive, and high-inrush ballast (ballast with 15 percent or less THD of normal load current).
 2. Fault Current Withstand Rating: Equal to or exceeding the available fault current at the point of installation.
 3. Enclosure: Comply with NEMA 250.

4. Provide with control and pilot devices as indicated on Drawings, matching the NEMA type specified for the enclosure.

C. Interface with DDC System for HVAC: Provide hardware interface to enable the DDC system for HVAC to monitor and control lighting contactors.

1. Monitoring: On-off status.

2. Control: On-off operation.

2.4 EMERGENCY SHUNT RELAY

A. Description: NC, electrically held relay, arranged for wiring in parallel with manual [or automatic] switching contacts; complying with UL 924.

1. Coil Rating: 120 V.

2.5 CONDUCTORS AND CABLES

A. Power Wiring to Supply Side of Remote-Control Power Sources: Not smaller than No. 12 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

B. Classes 2 and 3 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

C. Class 1 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine lighting control devices before installation. Reject lighting control devices that are wet, moisture damaged, or mold damaged.

B. Examine walls and ceilings for suitable conditions where lighting control devices will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF SENSORS

A. Comply with NECA 1.

- B. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression systems, and partition assemblies.
- C. Install and aim sensors in locations to achieve not less than 90 percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's written instructions.

3.3 INSTALLATION OF CONTACTORS

- A. Comply with NECA 1.
- B. Mount electrically held lighting contactors with elastomeric isolator pads to eliminate structure-borne vibration unless contactors are installed in an enclosure with factory-installed vibration isolators.

3.4 INSTALLATION OF WIRING

- A. Comply with NECA 1.
- B. Wiring Method: Comply with Section 260519 "Low-Voltage Electrical Power Conductors and Cables." Minimum conduit size is 1/2 inch.
- C. Wiring within Enclosures: Comply with NECA 1. Separate power-limited and nonpower-limited conductors in accordance with conductor manufacturer's written instructions.
- D. Size conductors in accordance with lighting control device manufacturer's written instructions unless otherwise indicated.
- E. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.

3.5 IDENTIFICATION

- A. Identify components and power and control wiring in accordance with Section 260553 "Identification for Electrical Systems."
 - 1. Identify controlled circuits in lighting contactors.
 - 2. Identify circuits or luminaires controlled by photoelectric and occupancy sensors at each sensor.
- B. Label time switches and contactors with a unique designation.

3.6 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to evaluate lighting control devices and perform tests and inspections.

- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform the following tests and inspections with the assistance of a factory-authorized service representative:
 - 1. Operational Test: After installing time switches and sensors, and after electrical circuitry has been energized, start units to confirm proper unit operation.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Lighting control devices will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports.

3.7 ADJUSTING

- A. Occupancy Adjustments: When requested within 12 months from date of Final Acceptance, provide on-site assistance in adjusting lighting control devices to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.
 - 1. For occupancy and motion sensors, verify operation at outer limits of detector range. Set time delay to suit Owner's operations.
 - 2. For daylighting controls, adjust set points and deadband controls to suit Owner's operations.
 - 3. Align high-bay occupancy sensors using manufacturer's laser aiming tool.

3.8 SOFTWARE SERVICE AGREEMENT

- A. Technical Support: Beginning at Final Acceptance, service agreement shall include software support for two years.
- B. Upgrade Service: At Final Acceptance, update software to latest version. Install and program software upgrades that become available within [two] <Insert number> years from date of Final Acceptance. Upgrading software shall include operating system and new or revised licenses for using software.
 - 1. Upgrade Notice: At least 30 days to allow Owner to schedule and access the system and to upgrade computer equipment if necessary.

3.9 DEMONSTRATION

- A. Coordinate demonstration of products specified in this Section with demonstration requirements for low-voltage, programmable lighting control systems specified in Section 260943.16 "Addressable-Luminaire Lighting Controls" and Section 260943.23 "Relay-Based Lighting Controls."
- B. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain lighting control devices.

END OF SECTION

SECTION 262416 - PANELBOARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Distribution panelboards.
 - 2. Lighting and appliance branch-circuit panelboards.

1.3 DEFINITIONS

- A. ATS: Acceptance testing specification.
- B. GFCI: Ground-fault circuit interrupter.
- C. GFEP: Ground-fault equipment protection.
- D. HID: High-intensity discharge.
- E. MCCB: Molded-case circuit breaker.
- F. SPD: Surge protective device.
- G. VPR: Voltage protection rating.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of panelboard.
 - 1. Include materials, switching and overcurrent protective devices, SPDs, accessories, and components indicated.
 - 2. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, and finishes.
- B. Shop Drawings: For each panelboard and related equipment.
 - 1. Include dimensioned plans, elevations, sections, and details.
 - 2. Show tabulations of installed devices with nameplates, conductor termination sizes, equipment features, and ratings.

3. Detail enclosure types including mounting and anchorage, environmental protection, knock-outs, corner treatments, covers and doors, gaskets, hinges, and locks.
4. Detail bus configuration, current, and voltage ratings.
5. Short-circuit current rating of panelboards and overcurrent protective devices.
6. Include evidence of NRTL listing for series rating of installed devices.
7. Include evidence of NRTL listing for SPD as installed in panelboard.
8. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
9. Include wiring diagrams for power, signal, and control wiring.
10. Key interlock scheme drawing and sequence of operations.
11. Include time-current coordination curves for each type and rating of overcurrent protective device included in panelboards. Submit on translucent log-log graph paper; include selectable ranges for each type of overcurrent protective device. Include an Internet link for electronic access to downloadable PDF of the coordination curves.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Panelboard Schedules: For installation in panelboards. Submit final versions after load balancing.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For panelboards and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
 1. Manufacturer's written instructions for testing and adjusting overcurrent protective devices.
 2. Time-current curves, including selectable ranges for each type of overcurrent protective device that allows adjustments.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 1. Keys: Two spares for each type of panelboard cabinet lock.
 2. Circuit Breakers Including GFCI and GFEP Types: Two spares for each panelboard.
 3. Fuses for Fused Switches: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.
 4. Fuses for Fused Power-Circuit Devices: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.

1.8 QUALITY ASSURANCE

- A. Manufacturer Qualifications: ISO 9001 or ISO 9002 certified.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Remove loose packing and flammable materials from inside panelboards; install temporary electric heating (250 W per panelboard) to prevent condensation.
- B. Handle and prepare panelboards for installation according to NEMA PB 1.

1.10 FIELD CONDITIONS

A. Environmental Limitations:

- 1. Do not deliver or install panelboards until spaces are enclosed and weathertight, wet work in spaces is complete and dry, work above panelboards is complete, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.
- 2. Rate equipment for continuous operation under the following conditions unless otherwise indicated:
 - a. Ambient Temperature: Not exceeding minus 22 deg F to plus 104 deg F.
 - b. Altitude: Not exceeding 6600 feet.

B. Service Conditions: NEMA PB 1, usual service conditions, as follows:

- 1. Ambient temperatures within limits specified.
- 2. Altitude not exceeding 6600 feet.

C. Interruption of Existing Electric Service: Do not interrupt electric service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electric service according to requirements indicated:

- 1. Notify Owner no fewer than two days in advance of proposed interruption of electric service.
- 2. Do not proceed with interruption of electric service without Owner's written permission.
- 3. Comply with NFPA 70E.

1.11 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace panelboards that fail in materials or workmanship within specified warranty period.

- 1. Panelboard Warranty Period: 18 months from date of Final Acceptance.

B. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace SPD that fails in materials or workmanship within specified warranty period.

- 1. SPD Warranty Period: Five years from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 PANELBOARDS AND LOAD CENTERS COMMON REQUIREMENTS

- A. Fabricate and test panelboards according to IEEE 344 to withstand seismic forces defined in Section 260548.16 "Seismic Controls for Electrical Systems."
- B. Product Selection for Restricted Space: Drawings indicate maximum dimensions for panelboards including clearances between panelboards and adjacent surfaces and other items. Comply with indicated maximum dimensions.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. Comply with NEMA PB 1.
- E. Comply with NFPA 70.
- F. Enclosures: Surface-mounted, dead-front cabinets.
 - 1. Rated for environmental conditions at installed location.
 - a. Indoor Dry and Clean Locations: NEMA 250, Type 1.
 - b. Other Wet or Damp Indoor Locations: NEMA 250, Type 4.
 - c. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 12.
 - 2. Height: 84 inches maximum.
 - 3. Front: Secured to box with concealed trim clamps. For surface-mounted fronts, match box dimensions; for flush-mounted fronts, overlap box. Trims shall cover all live parts and shall have no exposed hardware.
 - 4. Hinged Front Cover: Entire front trim hinged to box and with standard door within hinged trim cover. Trims shall cover all live parts and shall have no exposed hardware.
 - 5. Skirt for Surface-Mounted Panelboards: Same gage and finish as panelboard front with flanges for attachment to panelboard, wall, and ceiling or floor.
 - 6. Gutter Extension and Barrier: Same gage and finish as panelboard enclosure; integral with enclosure body. Arrange to isolate individual panel sections.
 - 7. Finishes:
 - a. Panels and Trim: Steel and galvanized steel, factory finished immediately after cleaning and pretreating with manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.
 - b. Back Boxes: Same finish as panels and trim.
 - c. Fungus Proofing: Permanent fungicidal treatment for overcurrent protective devices and other components.
- G. Incoming Mains:
 - 1. Location: Convertible between top and bottom.

2. Main Breaker: Main lug interiors up to 400 amperes shall be field convertible to main breaker.

H. Phase, Neutral, and Ground Buses:

1. Material: Hard-drawn copper, 98 percent conductivity.

- a. Plating shall run entire length of bus.
- b. Bus shall be fully rated the entire length.

2. Interiors shall be factory assembled into a unit. Replacing switching and protective devices shall not disturb adjacent units or require removing the main bus connectors.

3. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment grounding conductors; bonded to box.

4. Isolated Ground Bus: Adequate for branch-circuit isolated ground conductors; insulated from box.

5. Full-Sized Neutral: Equipped with full-capacity bonding strap for service entrance applications. Mount electrically isolated from enclosure. Do not mount neutral bus in gutter.

6. Extra-Capacity Neutral Bus: Neutral bus rated 200 percent of phase bus and listed and labeled by an NRTL acceptable to authority having jurisdiction, as suitable for nonlinear loads in electronic-grade panelboards and others designated on Drawings. Connectors shall be sized for double-sized or parallel conductors as indicated on Drawings. Do not mount neutral bus in gutter.

7. Split Bus: Vertical buses divided into individual vertical sections.

I. Conductor Connectors: Suitable for use with conductor material and sizes.

1. Material: Hard-drawn copper, 98 percent conductivity.

2. Terminations shall allow use of 75 deg C rated conductors without derating.

3. Size: Lugs suitable for indicated conductor sizes, with additional gutter space, if required, for larger conductors.

4. Main and Neutral Lugs: Compression type, with a lug on the neutral bar for each pole in the panelboard.

5. Ground Lugs and Bus-Configured Terminators: Compression type, with a lug on the bar for each pole in the panelboard.

6. Feed-Through Lugs: Compression type, suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.

7. Subfeed (Double) Lugs: Compression type suitable for use with conductor material. Locate at same end of bus as incoming lugs or main device.

8. Gutter-Tap Lugs: Compression type suitable for use with conductor material and with matching insulating covers. Locate at same end of bus as incoming lugs or main device.

9. Extra-Capacity Neutral Lugs: Rated 200 percent of phase lugs mounted on extra-capacity neutral bus.

J. NRTL Label: Panelboards or load centers shall be labeled by an NRTL acceptable to authority having jurisdiction for use as service equipment with one or more main service disconnecting and overcurrent protective devices. Panelboards or load centers shall have meter enclosures, wiring, connections, and other provisions for utility metering. Coordinate with utility company for exact requirements.

- K. Future Devices: Panelboards or load centers shall have mounting brackets, bus connections, filler plates, and necessary appurtenances required for future installation of devices.
1. Percentage of Future Space Capacity: 25 percent.
- L. Panelboard Short-Circuit Current Rating: Rated for series-connected system with integral or remote upstream overcurrent protective devices and labeled by an NRTL. Include label or manual with size and type of allowable upstream and branch devices listed and labeled by an NRTL for series-connected short-circuit rating.
1. Panelboards rated 240 V or less shall have short-circuit ratings as shown on Drawings, but not less than 10,000 A rms symmetrical.
 2. Panelboards rated above 240 V and less than 600 V shall have short-circuit ratings as shown on Drawings, but not less than 14,000 A rms symmetrical.
- M. Panelboard Short-Circuit Current Rating: Fully rated to interrupt symmetrical short-circuit current available at terminals. Assembly listed by an NRTL for 100 percent interrupting capacity.
1. Panelboards and overcurrent protective devices rated 240 V or less shall have short-circuit ratings as shown on Drawings, but not less than 10,000 A rms symmetrical.
 2. Panelboards and overcurrent protective devices rated above 240 V and less than 600 V shall have short-circuit ratings as shown on Drawings, but not less than 14,000 A rms symmetrical.

2.2 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Panelboards shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."
- B. Surge Suppression: Factory installed as an integral part of indicated panelboards, complying with UL 1449 SPD Type 1.

2.3 POWER PANELBOARDS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. ABB, Electrification Business.
 2. ESL Power Systems, Inc.
 3. Eaton.
 4. Mersen USA.
 5. Siemens Industry, Inc., Energy Management Division.
 6. Square D; Schneider Electric USA.
- B. Panelboards: NEMA PB 1, distribution type.

- C. Doors: Secured with vault-type latch with tumbler lock; keyed alike.
 - 1. For doors more than 36 inches high, provide two latches, keyed alike.
- D. Mains: Circuit breaker.
- E. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes 125 A and Smaller: Plug-in circuit breakers with 2 fastening screws.
- F. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes Larger Than 125 A: Bolt-on circuit breakers with 2 fastening screws.
- G. Branch Overcurrent Protective Devices: Fused switches.
- H. Contactors in Main Bus: NEMA ICS 2, Class A, mechanically held, general-purpose controller, with same short-circuit interrupting rating as panelboard.
 - 1. Internal Control-Power Source: Control-power transformer, with fused primary and secondary terminals, connected to main bus ahead of contactor connection.
 - 2. External Control-Power Source: 120-V branch circuit.

2.4 LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. ABB, Electrification Business.
 - 2. Eaton.
 - 3. Siemens Industry, Inc., Energy Management Division.
 - 4. Square D; Schneider Electric USA.
- B. Panelboards: NEMA PB 1, lighting and appliance branch-circuit type.
- C. Mains: Circuit breaker or lugs only.
- D. Branch Overcurrent Protective Devices: Plug-in and Bolt-on circuit breakers, replaceable without disturbing adjacent units.
- E. Contactors in Main Bus: NEMA ICS 2, Class A, mechanically held, general-purpose controller, with same short-circuit interrupting rating as panelboard.
 - 1. Internal Control-Power Source: Control-power transformer, with fused primary and secondary terminals, connected to main bus ahead of contactor connection.
 - 2. External Control-Power Source: 120-V branch circuit.
- F. Doors: Concealed hinges; secured with flush latch with tumbler lock; keyed alike.

- G. Doors: Door-in-door construction with concealed hinges; secured with multipoint latch with tumbler lock; keyed alike. Outer door shall permit full access to the panel interior. Inner door shall permit access to breaker operating handles and labeling, but current carrying terminals and bus shall remain concealed.
- H. Column-Type Panelboards: Single row of overcurrent devices with narrow gutter extension.
 - 1. Doors: Concealed hinges secured with multipoint latch with tumbler lock; keyed alike.

2.5 DISCONNECTING AND OVERCURRENT PROTECTIVE DEVICES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. ABB, Electrification Business.
 - 2. Eaton.
 - 3. Siemens Industry, Inc., Energy Management Division.
 - 4. Square D; Schneider Electric USA.
- B. MCCB: Comply with UL 489, with interrupting capacity to meet available fault currents.
 - 1. Thermal-Magnetic Circuit Breakers:
 - a. Inverse time-current element for low-level overloads.
 - b. Instantaneous magnetic trip element for short circuits.
 - c. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
 - 2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
 - 3. Electronic Trip Circuit Breakers:
 - a. RMS sensing.
 - b. Field-replaceable rating plug or electronic trip.
 - c. Digital display of settings, trip targets, and indicated metering displays.
 - d. Multi-button keypad to access programmable functions and monitored data.
 - e. Ten-event, trip-history log. Each trip event shall be recorded with type, phase, and magnitude of fault that caused the trip.
 - f. Integral test jack for connection to portable test set or laptop computer.
 - g. Field-Adjustable Settings:
 - 1) Instantaneous trip.
 - 2) Long- and short-time pickup levels.
 - 3) Long and short time adjustments.
 - 4) Ground-fault pickup level, time delay, and I squared T response.
 - 4. Current-Limiting Circuit Breakers: Frame sizes 400 A and smaller; let-through ratings less than NEMA FU 1, RK-5.
 - 5. GFCI Circuit Breakers: Single- and double-pole configurations with Class A ground-fault protection (6-mA trip).
 - 6. GFEP Circuit Breakers: Class B ground-fault protection (30-mA trip).

7. Arc-Fault Circuit Interrupter Circuit Breakers: Comply with UL 1699; 120/240-V, single-pole configuration.

8. Subfeed Circuit Breakers: Vertically mounted.

9. MCCB Features and Accessories:

- a. Standard frame sizes, trip ratings, and number of poles.
- b. Breaker handle indicates tripped status.
- c. UL listed for reverse connection without restrictive line or load ratings.
- d. Lugs: Compression style, suitable for number, size, trip ratings, and conductor materials.
- e. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and HID lighting circuits.
- f. Ground-Fault Protection: Integrally mounted relay and trip unit with adjustable pickup and time-delay settings, push-to-test feature, and ground-fault indicator.
- g. Communication Capability: Circuit-breaker-mounted communication module with functions and features compatible with power monitoring and control system specified in Section 260913 "Electrical Power Monitoring and Control."
- h. Shunt Trip: 120-V trip coil energized from separate circuit, set to trip at [55] [75] percent of rated voltage.
- i. Undervoltage Trip: Set to operate at 35 to 75 percent of rated voltage with field-adjustable 0.1- to 0.6-second time delay.
- j. Rating Plugs: Three-pole breakers with ampere ratings greater than 150 amperes shall have interchangeable rating plugs or electronic adjustable trip units.
- k. Auxiliary Contacts: One, SPDT switch with "a" and "b" contacts; "a" contacts mimic circuit-breaker contacts and "b" contacts operate in reverse of circuit-breaker contacts.
- l. Alarm Switch: Single-pole, normally open contact that actuates only when circuit breaker trips.
- m. Key Interlock Kit: Externally mounted to prohibit circuit-breaker operation; key shall be removable only when circuit breaker is in off position.
- n. Zone-Selective Interlocking: Integral with electronic trip unit; for interlocking ground-fault protection function with other upstream or downstream devices.
- o. Multipole units enclosed in a single housing with a single handle or factory assembled to operate as a single unit.
- p. Handle Padlocking Device: Fixed attachment, for locking circuit-breaker handle in on or off position.
- q. Handle Clamp: Loose attachment, for holding circuit-breaker handle in on position.

C. Fused Switch: NEMA KS 1, Type HD; clips to accommodate specified fuses; lockable handle.

1. Fuses and Spare-Fuse Cabinet: Comply with requirements specified in Section 262813 "Fuses."

2. Fused Switch Features and Accessories:

- a. Standard ampere ratings and number of poles.
- b. Mechanical cover interlock with a manual interlock override, to prevent the opening of the cover when the switch is in the on position. The interlock shall prevent the switch from being turned on with the cover open. The operating handle shall have lock-off means with provisions for three padlocks.
- c. Auxiliary Contacts: One normally open and normally closed contact(s) that operate with switch handle operation.

2.6 IDENTIFICATION

- A. Panelboard Label: Manufacturer's name and trademark, voltage, amperage, number of phases, and number of poles shall be located on the interior of the panelboard door.
- B. Breaker Labels: Faceplate shall list current rating, UL and IEC certification standards, and AIC rating.
- C. Circuit Directory: Directory card inside panelboard door, mounted in transparent card holder.
 - 1. Circuit directory shall identify specific purpose with detail sufficient to distinguish it from all other circuits.
- D. Circuit Directory: Computer-generated circuit directory mounted inside panelboard door with transparent plastic protective cover.
 - 1. Circuit directory shall identify specific purpose with detail sufficient to distinguish it from all other circuits.

2.7 ACCESSORY COMPONENTS AND FEATURES

- A. Accessory Set: Include tools and miscellaneous items required for overcurrent protective device test, inspection, maintenance, and operation.
- B. Portable Test Set: For testing functions of solid-state trip devices without removing from panelboard. Include relay and meter test plugs suitable for testing panelboard meters and switchboard class relays.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify actual conditions with field measurements prior to ordering panelboards to verify that equipment fits in allocated space in, and comply with, minimum required clearances specified in NFPA 70.
- B. Receive, inspect, handle, and store panelboards according to NEMA PB 1.1.
- C. Examine panelboards before installation. Reject panelboards that are damaged, rusted, or have been subjected to water saturation.
- D. Examine elements and surfaces to receive panelboards for compliance with installation tolerances and other conditions affecting performance of the Work.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, encumbrances to workspace clearance requirements, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.
- B. Comply with NECA 1.
- C. Install panelboards and accessories according to NEMA PB 1.1.
- D. Equipment Mounting:
 - 1. Install panelboards on cast-in-place concrete equipment base(s). Comply with requirements for equipment bases and foundations specified in Section 033000 "Cast-in-Place Concrete."
 - 2. Attach panelboard to the vertical finished or structural surface behind the panelboard.
 - 3. Comply with requirements for seismic control devices specified in Section 260548.16 "Seismic Controls for Electrical Systems."
- E. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from panelboards.
- F. Comply with mounting and anchoring requirements specified in Section 260548.16 "Seismic Controls for Electrical Systems."
- G. Mount top of trim 90 inches above finished floor unless otherwise indicated.
- H. Mount panelboard cabinet plumb and rigid without distortion of box.
- I. Mount recessed panelboards with fronts uniformly flush with wall finish and mating with back box.
- J. Mount surface-mounted panelboards to steel slotted supports 5/8 inch in depth. Orient steel slotted supports vertically.
- K. Install overcurrent protective devices and controllers not already factory installed.
 - 1. Set field-adjustable, circuit-breaker trip ranges.
 - 2. Tighten bolted connections and circuit breaker connections using calibrated torque wrench or torque screwdriver per manufacturer's written instructions.
- L. Make grounding connections and bond neutral for services and separately derived systems to ground. Make connections to grounding electrodes, separate grounds for isolated ground bars, and connections to separate ground bars.
- M. Install filler plates in unused spaces.

- N. Stub four 1-inch empty conduits from panelboard into accessible ceiling space or space designated to be ceiling space in the future. Stub four 1-inch empty conduits into raised floor space or below slab not on grade.
- O. Arrange conductors in gutters into groups and bundle and wrap with wire ties after completing load balancing.
- P. Mount spare fuse cabinet in accessible location.

3.3 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; install warning signs complying with requirements in Section 260553 "Identification for Electrical Systems."
- B. Create a directory to indicate installed circuit loads after balancing panelboard loads; incorporate Owner's final room designations. Obtain approval before installing. Handwritten directories are not acceptable. Install directory inside panelboard door.
- C. Panelboard Nameplates: Label each panelboard with a nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
- D. Device Nameplates: Label each branch circuit device in power panelboards with a nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
- E. Install warning signs complying with requirements in Section 260553 "Identification for Electrical Systems" identifying source of remote circuit.

3.4 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.
- B. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- C. Acceptance Testing Preparation:
 - 1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
 - 2. Test continuity of each circuit.
- D. Tests and Inspections:

1. Perform each visual and mechanical inspection and electrical test for low-voltage air circuit breakers and low-voltage surge arrestors stated in NETA ATS, Paragraph 7.6 Circuit Breakers and Paragraph 7.19.1 Surge Arrestors, Low-Voltage. Do not perform optional tests. Certify compliance with test parameters.
 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
 3. Perform the following infrared scan tests and inspections and prepare reports:
 - a. Initial Infrared Scanning: After Final Acceptance, but not more than 60 days after Final Acceptance, perform an infrared scan of each panelboard. Remove front panels so joints and connections are accessible to portable scanner.
 - b. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each panelboard 11 months after date of Final Acceptance.
 - c. Instruments and Equipment:
 - 1) Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
- E. Panelboards will be considered defective if they do not pass tests and inspections.
- F. Prepare test and inspection reports, including a certified report that identifies panelboards included and that describes scanning results, with comparisons of the two scans. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5 ADJUSTING

- A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.
- B. Set field-adjustable circuit-breaker trip ranges as indicated.
- C. Load Balancing: After Final Acceptance, but not more than 60 days after Final Acceptance, measure load balancing and make circuit changes. Prior to making circuit changes to achieve load balancing, inform Architect of effect on phase color coding.
1. Measure loads during period of normal facility operations.
 2. Perform circuit changes to achieve load balancing outside normal facility operation schedule or at times directed by the Architect. Avoid disrupting services such as fax machines and on-line data processing, computing, transmitting, and receiving equipment.
 3. After changing circuits to achieve load balancing, recheck loads during normal facility operations. Record load readings before and after changing circuits to achieve load balancing.
 4. Tolerance: Maximum difference between phase loads, within a panelboard, shall not exceed 20 percent.

3.6 PROTECTION

- A. Temporary Heating: Prior to energizing panelboards, apply temporary heat to maintain temperature according to manufacturer's written instructions.

END OF SECTION

SECTION 262726 - WIRING DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Standard-grade receptacles, 125 V, 20 A.
 - 2. GFCI receptacles, 125 V, 20 A.
 - 3. Cord and plug sets.
 - 4. Toggle switches, 120/277 V, 20 A.
 - 5. Occupancy sensors.
 - 6. Wall plates.
 - 7. Floor service fittings.

1.3 DEFINITIONS

- A. AFCI: Arc-fault circuit interrupter.
- B. BAS: Building automation system.
- C. EMI: Electromagnetic interference.
- D. GFCI: Ground-fault circuit interrupter.
- E. Pigtail: Short lead used to connect a device to a branch-circuit conductor.
- F. RFI: Radio-frequency interference.
- G. SPD: Surge protective device.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: List of legends and description of materials and process used for premarking wall plates.
- C. Samples: One for each type of device and wall plate specified, in each color specified.

1.5 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For wiring devices to include in all manufacturers' packing-label warnings and instruction manuals that include labeling conditions.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Floor Service-Outlet Assemblies: One for every 10, but no fewer than one.

PART 2 - PRODUCTS

2.1 GENERAL WIRING-DEVICE REQUIREMENTS

- A. Wiring Devices, Components, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
- B. Comply with NFPA 70.
- C. RoHS compliant.
- D. Comply with NEMA WD 1.
- E. Devices that are manufactured for use with modular plug-in connectors may be substituted under the following conditions:
 - 1. Connectors shall comply with UL 2459 and shall be made with stranding building wire.
 - 2. Devices shall comply with requirements in this Section.
- F. Devices for Owner-Furnished Equipment:
 - 1. Receptacles: Match plug configurations.
 - 2. Cord and Plug Sets: Match equipment requirements.
- G. Device Color:
 - 1. Wiring Devices Connected to Normal Power System: As selected by Architect unless otherwise indicated or required by NFPA 70 or device listing.
 - 2. Wiring Devices Connected to Essential Electrical System: Red.
- H. Wall Plate Color: For plastic covers, match device color.

- I. Source Limitations: Obtain each type of wiring device and associated wall plate from single source from single manufacturer.

2.2 STANDARD-GRADE RECEPTACLES, 125 V, 20 A

A. Duplex Receptacles, 125 V, 20 A:

1. Description: Two pole, three wire, and self-grounding.
2. Configuration: NEMA WD 6, Configuration 5-20R.
3. Standards: Comply with UL 498 and FS W-C-596.
4. Federal Grade.

B. Tamper-Resistant Duplex Receptacles, 125 V, 20 A:

1. Description: Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle.
2. Configuration: NEMA WD 6, Configuration 5-20R.
3. Standards: Comply with UL 498 and FS W-C-596.
4. Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" Article.
5. Federal Grade.

C. Weather-Resistant Duplex Receptacle, 125 V, 20 A:

1. Description: Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle. Square face.
2. Configuration: NEMA WD 6, Configuration 5-20R.
3. Standards: Comply with UL 498.
4. Marking: Listed and labeled as complying with NFPA 70, "Receptacles in Damp or Wet Locations" Article.
5. Federal Grade.

D. Tamper- and Weather-Resistant Duplex Receptacles, 125 V, 20 A:

1. Description: Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle. Square face.
2. Configuration: NEMA WD 6, Configuration 5-20R.
3. Standards: Comply with UL 498.
4. Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" and "Receptacles in Damp or Wet Locations" articles.
5. Federal Grade.

2.3 GFCI RECEPTACLES, 125 V, 20 A

A. Duplex GFCI Receptacles, 125 V, 20 A:

1. Description: Integral GFCI with "Test" and "Reset" buttons and LED indicator light. Two pole, three wire, and self-grounding.
2. Configuration: NEMA WD 6, Configuration 5-20R.

- 3.Type: Feed through.
- 4.Standards: Comply with UL 498, UL 943 Class A, and FS W-C-596.
- 5.Federal Grade.

B. Tamper-Resistant Duplex GFCI Receptacles, 125 V, 20 A:

- 1.Description: Integral GFCI with "Test" and "Reset" buttons and LED indicator light. Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle.
- 2.Configuration: NEMA WD 6, Configuration 5-20R.
- 3.Type: Feed through.
- 4.Standards: Comply with UL 498, UL 943 Class A, and FS W-C-596.
- 5.Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" Article.
- 6.Federal Grade.

C. Tamper- and Weather-Resistant, GFCI Duplex Receptacles, 125 V, 20 A:

- 1.Description: Integral GFCI with "Test" and "Reset" buttons and LED indicator light. Two pole, three wire, and self-grounding. Integral shutters that operate only when a plug is inserted in the receptacle. Square face.
- 2.Configuration: NEMA WD 6, Configuration 5-15R.
- 3.Type: Feed through.
- 4.Standards: Comply with UL 498 and UL 943 Class A.
- 5.Marking: Listed and labeled as complying with NFPA 70, "Tamper-Resistant Receptacles" and "Receptacles in Damp or Wet Locations" articles.
- 6.Federal Grade.

2.4 CORD AND PLUG SETS

- A. Match voltage and current ratings and number of conductors to requirements of equipment being connected.
- B. Cord: Rubber-insulated, stranded-copper conductors, with Type SOW-A jacket; with green-insulated grounding conductor and ampacity of at least 130 percent of the equipment rating.
- C. Plug: Nylon body and integral cable-clamping jaws. Match cord and receptacle type for connection.

2.5 TOGGLE SWITCHES, 120/277 V, 20 A

A. Single-Pole Switches, 120/277 V, 20 A:

- 1.Standards: Comply with UL 20 and FS W-S-896.

B. Three-Way Switches, 120/277 V, 20 A:

- 1.Comply with UL 20 and FS W-S-896.

2.6 DIMMERS

A. Wall-Box Dimmers:

1. Description: Modular, full-wave, solid-state dimmer switch with integral, quiet on-off switches, with audible frequency and EMI/RFI suppression filters.
2. Control: Continuously adjustable slider; with single-pole or three-way switching.
3. Standards: Comply with UL 1472.
4. LED Lamp Dimmer Switches: Modular; compatible with LED lamps; trim potentiometer to adjust low-end dimming; capable of consistent dimming with low end not greater than 20 percent of full brightness.

2.7 WALL PLATES

A. Single Source: Obtain wall plates from same manufacturer of wiring devices.

B. Single and combination types shall match corresponding wiring devices.

1. Plate-Securing Screws: Metal with head color to match plate finish.
2. Material for Finished Spaces: Smooth, high-impact thermoplastic 0.035-inch-thick, satin-finished, Type 302 stainless.
3. Material for Unfinished Spaces: Galvanized steel.
4. Material for Damp Locations: Thermoplastic with spring-loaded lift cover, and listed and labeled for use in wet and damp locations.

C. Wet-Location, Weatherproof Cover Plates: NEMA 250, complying with Type 3R, weather-resistant, die-cast aluminum with lockable cover.

2.8 FLOOR BOXES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Legrand/Wiremold RPSFB & RPSFB-OG series.
2. Equal products by Hubbel, Leviton may be substituted for approval.

B. Floor boxes for slab on grade:

1. Rectangular dual service metal concrete floor box with a non-metallic top that permits for thick concrete pours between 4" and 6" thick.
2. 6 1/16" high, 5 5/16" diameter top.
3. Graduated markings on the inside and outside of the box indicating volume capacity and depth of concrete pour.
4. Box shall accept 2HUB to allow 2" conduit feeds while maintaining 4" deep concrete pour.
5. Provide reusable concrete cap.
6. Conduit entry for:
 - a. 2 sides with 3/4" and 1-1/4" knockouts each side.
 - b. 2 sides with 1" knockouts each side.
 - c. Bottom: two 1-1/2" knockouts.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with NECA 1, including mounting heights listed in that standard, unless otherwise indicated.
- B. Coordination with Other Trades:
1. Protect installed devices and their boxes. Do not place wall finish materials over device boxes, and do not cut holes for boxes with routers that are guided by riding against outside of boxes.
 2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
 3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
 4. Install wiring devices after all wall preparation, including painting, is complete.
- C. Conductors:
1. Do not strip insulation from conductors until right before they are spliced or terminated on devices.
 2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
 3. The length of free conductors at outlets for devices shall comply with NFPA 70, Article 300, without pigtails.
 4. Existing Conductors:
 - a. Cut back and pigtail, or replace all damaged conductors.
 - b. Straighten conductors that remain and remove corrosion and foreign matter.
 - c. Pigtailing existing conductors is permitted, provided the outlet box is large enough.
- D. Device Installation:
1. Replace devices that have been in temporary use during construction and that were installed before building finishing operations were complete.
 2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
 3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
 4. Connect devices to branch circuits using pigtails that are not less than 6 inches in length.
 5. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, two-thirds to three-fourths of the way around terminal screw.
 6. Use a torque screwdriver when a torque is recommended or required by manufacturer.
 7. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
 8. Tighten unused terminal screws on the device.
 9. When mounting into metal boxes, remove the fiber or plastic washers used to hold device-mounting screws in yokes, allowing metal-to-metal contact.

E. Receptacle Orientation:

1. Install ground pin of vertically mounted receptacles down, and on horizontally mounted receptacles to the right.
2. Install hospital-grade receptacles in patient-care areas with the ground pin or neutral blade at the top.

F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.

G. Dimmers:

1. Install dimmers within terms of their listing.
2. Verify that dimmers used for fan-speed control are listed for that application.
3. Install unshared neutral conductors on line and load side of dimmers according to manufacturers' device, listing conditions in the written instructions.

H. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multi-gang wall plates.

I. Adjust locations of floor service outlets and service poles to suit arrangement of partitions and furnishings.

3.2 GFCI RECEPTACLES

- A. Install non-feed-through GFCI receptacles where protection of downstream receptacles is not required.

3.3 IDENTIFICATION

- A. Comply with Section 260553 "Identification for Electrical Systems."
- B. Identify each receptacle with panelboard identification and circuit number. Use hot, stamped, or engraved machine printing with white-filled lettering on face of plate, and durable wire markers or tags inside outlet boxes.
- C. Essential Electrical System: Mark receptacles supplied from the essential electrical system to allow easy identification using a self-adhesive label.

3.4 FIELD QUALITY CONTROL

- A. Test Instruments: Use instruments that comply with UL 1436.
- B. Test Instrument for Receptacles: Digital wiring analyzer with digital readout or illuminated digital-display indicators of measurement.
- C. Perform the following tests and inspections with the assistance of a factory-authorized service representative:

1. In healthcare facilities, prepare reports that comply with NFPA 99.
2. Test Instruments: Use instruments that comply with UL 1436.
3. Test Instrument for Receptacles: Digital wiring analyzer with digital readout or illuminated digital-display indicators of measurement.

D. Tests for Receptacles:

1. Line Voltage: Acceptable range is 105 to 132 V.
2. Percent Voltage Drop under 15-A Load: A value of 6 percent or higher is unacceptable.
3. Ground Impedance: Values of up to 2 ohms are acceptable.
4. GFCI Trip: Test for tripping values specified in UL 1436 and UL 943.
5. Using the test plug, verify that the device and its outlet box are securely mounted.
6. Tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault-current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.

- E. Test straight-blade for the retention force of the grounding blade according to NFPA 99. Retention force shall be not less than 4 oz.
- F. Wiring device will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.

END OF SECTION

SECTION 262813 - FUSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Cartridge fuses rated 600 V ac and less for use in the following:
 - a. Control circuits.
 - b. Enclosed controllers.
 - c. Enclosed switches.
2. Spare-fuse cabinets.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for spare-fuse cabinets. Include the following for each fuse type indicated:
 1. Ambient Temperature Adjustment Information: If ratings of fuses have been adjusted to accommodate ambient temperatures, provide list of fuses with adjusted ratings.
 - a. For each fuse having adjusted ratings, include location of fuse, original fuse rating, local ambient temperature, and adjusted fuse rating.
 - b. Provide manufacturer's technical data on which ambient temperature adjustment calculations are based.
 2. Dimensions and manufacturer's technical data on features, performance, electrical characteristics, and ratings.
 3. Current-limitation curves for fuses with current-limiting characteristics.
 4. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse. Submit in PDF format.
 5. Coordination charts and tables and related data.
 6. Fuse sizes for elevator feeders and elevator disconnect switches.

1.4 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For fuses to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017700 "Closeout Procedures" include the following:
1. Ambient temperature adjustment information.
 2. Current-limitation curves for fuses with current-limiting characteristics.
 3. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse used on the Project. Submit in PDF format.
 4. Coordination charts and tables and related data.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
1. Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.

1.6 FIELD CONDITIONS

- A. Where ambient temperature to which fuses are directly exposed is less than **40 deg F** or more than **100 deg F**, apply manufacturer's ambient temperature adjustment factors to fuse ratings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations: Obtain fuses, for use within a specific product or circuit, from single source from single manufacturer.

2.2 CARTRIDGE FUSES

- A. Characteristics: NEMA FU 1, current-limiting, nonrenewable cartridge fuses with voltage ratings consistent with circuit voltages.
1. Type RK-1: 250-V, zero- to 600-A rating, 200 kAIC, time delay.
 2. Type RK-5: 250-V, zero- to 600-A rating, 200 kAIC, time delay.
 3. Type T: 250-V, zero- to 1200-A rating, 200 kAIC, very fast acting , time delay.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. Comply with NEMA FU 1 for cartridge fuses.

- D. Comply with NFPA 70.
- E. Coordinate fuse ratings with utilization equipment nameplate limitations of maximum fuse size and with system short-circuit current levels.

2.3 SPARE-FUSE CABINET

- A. Characteristics: Wall-mounted steel unit with full-length, recessed piano-hinged door and key-coded cam lock and pull.
 - 1. Size: Adequate for storage of spare fuses specified with 15 percent spare capacity minimum.
 - 2. Finish: Gray, baked enamel.
 - 3. Identification: "SPARE FUSES" in 1-1/2-inch- high letters on exterior of door.
 - 4. Fuse Pullers: For each size of fuse, where applicable and available, from fuse manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine fuses before installation. Reject fuses that are moisture damaged or physically damaged.
- B. Examine holders to receive fuses for compliance with installation tolerances and other conditions affecting performance, such as rejection features.
- C. Examine utilization equipment nameplates and installation instructions. Install fuses of sizes and with characteristics appropriate for each piece of equipment.
- D. Evaluate ambient temperatures to determine if fuse rating adjustment factors must be applied to fuse ratings.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 FUSE APPLICATIONS

- A. Cartridge Fuses:
 - 1. Service Entrance and Feeders over 600A: Class L, current-limiting with 200 kA interrupting rating.
 - 2. Service Entrance and Feeders under 600A: Class RK1, current-limiting with 200 kA interrupting rating or Class J, current-limiting with 200 kA interrupting rating.
 - 3. Motor Branch Circuits: Class RK5, time delay, current-limiting with 200 kA interrupting rating.
 - 4. Large Motor Branch (601-4000 A): Class RK5, time delay, current-limiting with 200 kA interrupting rating.
 - 5. Power Electronics Circuits: Class J, high speed.
 - 6. Other Branch Circuits: Class K5, time delay.
 - 7. Control Transformer Circuits: Class CC, time delay, control transformer duty.

8. Provide open-fuse indicator fuses or fuse covers with open fuse indication.

3.3 INSTALLATION

- A. Install fuses in fusible devices. Arrange fuses so rating information is readable without removing fuse.
- B. Install spare-fuse cabinet(s) in location shown on the Drawings or as indicated in the field by Owner.

3.4 IDENTIFICATION

- A. Install labels complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems" and indicating fuse replacement information inside of door of each fused switch and adjacent to each fuse block, socket, and holder.

END OF SECTION

SECTION 262816 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Fusible switches.
2. Nonfusible switches.
3. Molded-case circuit breakers (MCCBs).
4. Molded-case switches.
5. Enclosures.

1.3 DEFINITIONS

- A. NC: Normally closed.
- B. NO: Normally open.
- C. SPDT: Single pole, double throw.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of enclosed switch, circuit breaker, accessory, and component indicated. Include nameplate ratings, dimensioned elevations, sections, weights, and manufacturers' technical data on features, performance, electrical characteristics, ratings, accessories, and finishes.
 1. Enclosure types and details for types other than NEMA 250, Type 1.
 2. Current and voltage ratings.
 3. Short-circuit current ratings (interrupting and withstand, as appropriate).
 4. Include evidence of a nationally recognized testing laboratory (NRTL) listing for series rating of installed devices.
 5. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices, accessories, and auxiliary components.
 6. Include time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device. Provide in PDF.
- B. Shop Drawings: For enclosed switches and circuit breakers.

1. Include plans, elevations, sections, details, and attachments to other work.
2. Include wiring diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified testing agency.
- B. Seismic Qualification Data: Certificates, for enclosed switches and circuit breakers, accessories, and components, from manufacturer.
 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For enclosed switches and circuit breakers to include in emergency, operation, and maintenance manuals.
 1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
 - a. Manufacturer's written instructions for testing and adjusting enclosed switches and circuit breakers.
 - b. Time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device. Provide in PDF electronic format.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 1. Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.
 2. Fuse Pullers: Two for each size and type.

1.8 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Accredited by NETA.
 1. Testing Agency's Field Supervisor: Currently certified by NETA to supervise on-site testing.

1.9 FIELD CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
 - 1. Ambient Temperature: Not less than minus 22 deg F and not exceeding 104 deg F.
 - 2. Altitude: Not exceeding 6600 feet.

1.10 WARRANTY

- A. Manufacturer's Warranty: Manufacturer and Installer agree to repair or replace components that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period: One year(s) from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Enclosed switches and circuit breakers shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."

2.2 GENERAL REQUIREMENTS

- A. Source Limitations: Obtain enclosed switches and circuit breakers, overcurrent protective devices, components, and accessories, within same product category, from single manufacturer.
- B. Product Selection for Restricted Space: Drawings indicate maximum dimensions for enclosed switches and circuit breakers, including clearances between enclosures, and adjacent surfaces and other items. Comply with indicated maximum dimensions.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and application.
- D. Comply with NFPA 70.

2.3 FUSIBLE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. ABB, Electrification Business.
 - 2. Eaton.

- 3.Siemens Industry, Inc., Energy Management Division.
- 4.Square D; Schneider Electric USA.

B. Type HD, Heavy Duty:

- 1.Single throw.
- 2.Three pole.
- 3.240-V ac.
- 4.1200 A and smaller.
- 5.UL 98 and NEMA KS 1, horsepower rated, with clips or bolt pads to accommodate indicated fuses.
- 6.Lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.

C. Accessories:

- 1.Equipment Ground Kit: Internally mounted and labeled for copper and aluminum ground conductors.
- 2.Neutral Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
- 3.Isolated Ground Kit: Internally mounted; insulated, labeled for copper and aluminum neutral conductors.
- 4.Class R Fuse Kit: Provides rejection of other fuse types when Class R fuses are specified.
- 5.Auxiliary Contact Kit: One NO/NC (Form "C") auxiliary contact(s), arranged to activate before switch blades open. Contact rating - 120-V ac.
- 6.Hookstick Handle: Allows use of a hookstick to operate the handle.
- 7.Lugs: Compression type, suitable for number, size, and conductor material.
- 8.Service-Rated Switches: Labeled for use as service equipment.

2.4 NONFUSIBLE SWITCHES

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- 1.ABB, Electrification Business.
- 2.Eaton.
- 3.Siemens Industry, Inc., Energy Management Division.
- 4.Square D; Schneider Electric USA.

B. Type HD, Heavy Duty, Three Pole, Single Throw, 240-V ac, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.

C. Type HD, Heavy Duty, Six Pole, Single Throw, 240-V ac, 200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.

D. Type HD, Heavy Duty, Three Pole, Double Throw, 240-V ac, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.

E. Accessories:

1. Equipment Ground Kit: Internally mounted and labeled for copper and aluminum ground conductors.
2. Neutral Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
3. Isolated Ground Kit: Internally mounted; insulated, labeled for copper and aluminum neutral conductors.
4. Class R Fuse Kit: Provides rejection of other fuse types when Class R fuses are specified.
5. Auxiliary Contact Kit: One NO/NC (Form "C") auxiliary contact(s), arranged to activate before switch blades open. Contact rating - 120-V ac.
6. Hookstick Handle: Allows use of a hookstick to operate the handle.
7. Lugs: Compression type, suitable for number, size, and conductor material.
8. Service-Rated Switches: Labeled for use as service equipment.

2.5 MOLDED-CASE CIRCUIT BREAKERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. ABB, Electrification Business.
 2. Eaton.
 3. NOARK Electric North America.
 4. Siemens Industry, Inc., Energy Management Division.
 5. Square D; Schneider Electric USA.
- B. Circuit breakers shall be constructed using glass-reinforced insulating material. Current carrying components shall be completely isolated from the handle and the accessory mounting area.
- C. Circuit breakers shall have a toggle operating mechanism with common tripping of all poles, which provides quick-make, quick-break contact action. The circuit-breaker handle shall be over center, be trip free, and reside in a tripped position between on and off to provide local trip indication. Circuit-breaker escutcheon shall be clearly marked on and off in addition to providing international I/O markings. Equip circuit breaker with a push-to-trip button, located on the face of the circuit breaker to mechanically operate the circuit-breaker tripping mechanism for maintenance and testing purposes.
- D. The maximum ampere rating and UL, IEC, or other certification standards with applicable voltage systems and corresponding interrupting ratings shall be clearly marked on face of circuit breaker. Circuit breakers shall be 100 percent rated. Circuit breaker/circuit breaker combinations for series connected interrupting ratings shall be listed by UL as recognized component combinations. Any series rated combination used shall be marked on the end-use equipment along with the statement "Caution - Series Rated System. _____ Amps Available. Identical Replacement Component Required."
- E. MCCBs shall be equipped with a device for locking in the isolated position.
- F. Lugs shall be suitable for 140 deg F rated wire on 125-A circuit breakers and below rated wire, sized according to the 167 deg F temperature rating in NFPA 70.

- G. Standard: Comply with UL 489 with interrupting capacity to comply with available fault currents.
- H. Thermal-Magnetic Circuit Breakers: Inverse time-current thermal element for low-level overloads and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
- I. Adjustable, Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
- J. Electronic Trip Circuit Breakers: Field-replaceable rating plug, rms sensing, with the following field-adjustable settings:
1. Instantaneous trip.
 2. Long- and short-time pickup levels.
 3. Long- and short-time time adjustments.
 4. Ground-fault pickup level, time delay, and I-squared t response.
- K. Current-Limiting Circuit Breakers: Frame sizes 400 A and smaller, and let-through ratings less than NEMA FU 1, RK-5.
- L. Integrally Fused Circuit Breakers: Thermal-magnetic trip element with integral limiter-style fuse listed for use with circuit breaker and trip activation on fuse opening or on opening of fuse compartment door.
- M. Ground-Fault Circuit-Interrupter (GFCI) Circuit Breakers: Single- and two-pole configurations with Class A ground-fault protection (6-mA trip).
- N. Ground-Fault Equipment-Protection (GFEP) Circuit Breakers: With Class B ground-fault protection (30-mA trip).
- O. Features and Accessories:
1. Standard frame sizes, trip ratings, and number of poles.
 2. Lugs: Compression type, suitable for number, size, trip ratings, and conductor material.
 3. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and high-intensity discharge lighting circuits.
 4. Ground-Fault Protection: Comply with UL 1053; integrally mounted, self-powered type with mechanical ground-fault indicator; relay with adjustable pickup and time-delay settings, push-to-test feature, internal memory, and shunt trip unit; and three-phase, zero-sequence current transformer/sensor.
 5. Communication Capability: Circuit-breaker-mounted communication module with functions and features compatible with power monitoring and control system, specified in Section 260913 "Electrical Power Monitoring and Control."
 6. Shunt Trip: Trip coil energized from separate circuit, with coil-clearing contact.
 7. Undervoltage Trip: Set to operate at 35 to 75 percent of rated voltage without intentional time delay.
 8. Auxiliary Contacts: One SPDT switch with "a" and "b" contacts; "a" contacts mimic circuit-breaker contacts, "b" contacts operate in reverse of circuit-breaker contacts.
 9. Alarm Switch: One NO contact that operates only when circuit breaker has tripped.
 10. Key Interlock Kit: Externally mounted to prohibit circuit-breaker operation; key shall be removable only when circuit breaker is in off position.

11. Zone-Selective Interlocking: Integral with electronic trip unit; for interlocking ground-fault protection function.
12. Electrical Operator: Provide remote control for on, off, and reset operations.
13. Accessory Control Power Voltage: Integrally mounted, self-powered; 120-V ac.

2.6 MOLDED-CASE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1.ABB, Electrification Business.
 - 2.Eaton.
 - 3.NOARK Electric North America.
 - 4.Siemens Industry, Inc., Energy Management Division.
 - 5.Square D; Schneider Electric USA.
- B. Description: MCCB with fixed, high-set instantaneous trip only, and short-circuit withstand rating equal to equivalent breaker frame size interrupting rating.
- C. Standard: Comply with UL 489 with interrupting capacity to comply with available fault currents.
- D. Features and Accessories:
 - 1.Standard frame sizes and number of poles.
 - 2.Lugs:
 - a. Compression type, suitable for number, size, trip ratings, and conductor material.
 - b. Lugs shall be suitable for 140 deg F rated wire on 125-A circuit breakers and below, sized according to the 167 deg F temperature rating in NFPA 70.
 - 3.Ground-Fault Protection: Comply with UL 1053; remote-mounted and powered type with mechanical ground-fault indicator; relay with adjustable pickup and time-delay settings, push-to-test feature, internal memory, and shunt trip unit; and three-phase, zero-sequence current transformer/sensor.
 - 4.Shunt Trip: Trip coil energized from separate circuit, with coil-clearing contact.
 - 5.Undervoltage Trip: Set to operate at 35 to 75 percent of rated voltage without intentional time delay.
 - 6.Auxiliary Contacts: One SPDT switch with "a" and "b" contacts; "a" contacts mimic switch contacts, "b" contacts operate in reverse of switch contacts.
 - 7.Alarm Switch: One NO contact that operates only when switch has tripped.
 - 8.Key Interlock Kit: Externally mounted to prohibit switch operation; key shall be removable only when switch is in off position.
 - 9.Zone-Selective Interlocking: Integral with ground-fault shunt trip unit; for interlocking ground-fault protection function.
 10. Electrical Operator: Provide remote control for on, off, and reset operations.
 11. Accessory Control Power Voltage: Integrally mounted, self-powered; 120-V ac.

2.7 ENCLOSURES

- A. Enclosed Switches and Circuit Breakers: UL 489, NEMA KS 1, NEMA 250, and UL 50, to comply with environmental conditions at installed location.
- B. Enclosure Finish: The enclosure shall be gray baked enamel paint, electrodeposited on cleaned, phosphatized steel (NEMA 250 Type 1).
- C. Conduit Entry: NEMA 250 Types 4, 4X, and 12 enclosures shall contain no knockouts. NEMA 250 Types 7 and 9 enclosures shall be provided with threaded conduit openings in both endwalls.
- D. Operating Mechanism: The circuit-breaker operating handle shall be externally operable with the operating mechanism being an integral part of the box, not the cover. The cover interlock mechanism shall have an externally operated override. The override shall not permanently disable the interlock mechanism, which shall return to the locked position once the override is released. The tool used to override the cover interlock mechanism shall not be required to enter the enclosure in order to override the interlock.
- E. Enclosures designated as NEMA 250 Type 4, 4X stainless steel, 12, or 12K shall have a dual cover interlock mechanism to prevent unintentional opening of the enclosure cover when the circuit breaker is ON and to prevent turning the circuit breaker ON when the enclosure cover is open.
- F. NEMA 250 Type 7/9 enclosures shall be furnished with a breather and drain kit to allow their use in outdoor and wet location applications.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine elements and surfaces to receive enclosed switches and circuit breakers for compliance with installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
 - 1. Commencement of work shall indicate Installer's acceptance of the areas and conditions as satisfactory.

3.2 PREPARATION

- A. Interruption of Existing Electric Service: Do not interrupt electric service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electric service according to requirements indicated:
 - 1. Notify Owner no fewer than seven days in advance of proposed interruption of electric service.
 - 2. Indicate method of providing temporary electric service.

3. Do not proceed with interruption of electric service without Owner's written permission.
4. Comply with NFPA 70E.

3.3 ENCLOSURE ENVIRONMENTAL RATING APPLICATIONS

- A. Enclosed Switches and Circuit Breakers: Provide enclosures at installed locations with the following environmental ratings.
 1. Indoor, Dry and Clean Locations: NEMA 250, Type 1.
 2. Outdoor Locations: NEMA 250, Type 3R.
 3. Wash-Down Areas: NEMA 250, Type 4X, stainless steel.
 4. Other Wet or Damp, Indoor Locations: NEMA 250, Type 4.
 5. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 12.

3.4 INSTALLATION

- A. Coordinate layout and installation of switches, circuit breakers, and components with equipment served and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.
- B. Install individual wall-mounted switches and circuit breakers with tops at uniform height unless otherwise indicated.
- C. Comply with mounting and anchoring requirements specified in Section 260548.16 "Seismic Controls for Electrical Systems."
- D. Temporary Lifting Provisions: Remove temporary lifting of eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.
- E. Install fuses in fusible devices.
- F. Comply with NFPA 70 and NECA 1.

3.5 IDENTIFICATION

- A. Comply with requirements in Section 260553 "Identification for Electrical Systems."
 1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
 2. Label each enclosure with engraved metal or laminated-plastic nameplate.

3.6 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections with the assistance of a factory-authorized service representative.
- E. Tests and Inspections for Switches:

1. Visual and Mechanical Inspection:

- a. Inspect physical and mechanical condition.
- b. Inspect anchorage, alignment, grounding, and clearances.
- c. Verify that the unit is clean.
- d. Verify blade alignment, blade penetration, travel stops, and mechanical operation.
- e. Verify that fuse sizes and types match the Specifications and Drawings.
- f. Verify that each fuse has adequate mechanical support and contact integrity.
- g. Inspect bolted electrical connections for high resistance using one of the two following methods:
 - 1) Use a low-resistance ohmmeter.
 - a) Compare bolted connection resistance values to values of similar connections. Investigate values that deviate from those of similar bolted connections by more than 50 percent of the lowest value.
 - 2) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method in accordance with manufacturer's published data or NETA ATS Table 100.12.
 - a) Bolt-torque levels shall be in accordance with manufacturer's published data. In the absence of manufacturer's published data, use NETA ATS Table 100.12.
- h. Verify that operation and sequencing of interlocking systems is as described in the Specifications and shown on the Drawings.
- i. Verify correct phase barrier installation.
- j. Verify lubrication of moving current-carrying parts and moving and sliding surfaces.

2. Electrical Tests:

- a. Perform resistance measurements through bolted connections with a low-resistance ohmmeter. Compare bolted connection resistance values to values of similar connections. Investigate values that deviate from adjacent poles or similar switches by more than 50 percent of the lowest value.
- b. Measure contact resistance across each switchblade fuseholder. Drop values shall not exceed the high level of the manufacturer's published data. If manufacturer's published data are not available, investigate values that deviate from adjacent poles or similar switches by more than 50 percent of the lowest value.

- c. Perform insulation-resistance tests for one minute on each pole, phase-to-phase and phase-to-ground with switch closed, and across each open pole. Apply voltage in accordance with manufacturer's published data. In the absence of manufacturer's published data, use Table 100.1 from the NETA ATS. Investigate values of insulation resistance less than those published in Table 100.1 or as recommended in manufacturer's published data.
- d. Measure fuse resistance. Investigate fuse-resistance values that deviate from each other by more than 15 percent.
- e. Perform ground fault test according to NETA ATS 7.14 "Ground Fault Protection Systems, Low-Voltage."

F. Tests and Inspections for Molded Case Circuit Breakers:

1. Visual and Mechanical Inspection:

- a. Verify that equipment nameplate data are as described in the Specifications and shown on the Drawings.
- b. Inspect physical and mechanical condition.
- c. Inspect anchorage, alignment, grounding, and clearances.
- d. Verify that the unit is clean.
- e. Operate the circuit breaker to ensure smooth operation.
- f. Inspect bolted electrical connections for high resistance using one of the two following methods:
 - 1) Use a low-resistance ohmmeter.
 - a) Compare bolted connection resistance values to values of similar connections. Investigate values that deviate from those of similar bolted connections by more than 50 percent of the lowest value.
 - 2) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method in accordance with manufacturer's published data or NETA ATS Table 100.12.
 - a) Bolt-torque levels shall be in accordance with manufacturer's published data. In the absence of manufacturer's published data, use NETA ATS Table 100.12.
- g. Inspect operating mechanism, contacts, and chutes in unsealed units.
- h. Perform adjustments for final protective device settings in accordance with the coordination study.

2. Electrical Tests:

- a. Perform resistance measurements through bolted connections with a low-resistance ohmmeter. Compare bolted connection resistance values to values of similar connections. Investigate values that deviate from adjacent poles or similar switches by more than 50 percent of the lowest value.

- b. Perform insulation-resistance tests for one minute on each pole, phase-to-phase and phase-to-ground with circuit breaker closed, and across each open pole. Apply voltage in accordance with manufacturer's published data. In the absence of manufacturer's published data, use Table 100.1 from the NETA ATS. Investigate values of insulation resistance less than those published in Table 100.1 or as recommended in manufacturer's published data.
 - c. Perform a contact/pole resistance test. Drop values shall not exceed the high level of the manufacturer's published data. If manufacturer's published data are not available, investigate values that deviate from adjacent poles or similar switches by more than 50 percent of the lowest value.
 - d. Perform insulation resistance tests on all control wiring with respect to ground. Applied potential shall be 500-V dc for 300-V rated cable and 1000-V dc for 600-V rated cable. Test duration shall be one minute. For units with solid state components, follow manufacturer's recommendation. Insulation resistance values shall be no less than two megohms.
 - e. Determine the following by primary current injection:
 - 1) Long-time pickup and delay. Pickup values shall be as specified. Trip characteristics shall not exceed manufacturer's published time-current characteristic tolerance band, including adjustment factors.
 - 2) Short-time pickup and delay. Short-time pickup values shall be as specified. Trip characteristics shall not exceed manufacturer's published time-current characteristic tolerance band, including adjustment factors.
 - 3) Ground-fault pickup and time delay. Ground-fault pickup values shall be as specified. Trip characteristics shall not exceed manufacturer's published time-current characteristic tolerance band, including adjustment factors.
 - 4) Instantaneous pickup. Instantaneous pickup values shall be as specified and within manufacturer's published tolerances.
 - f. Test functionality of the trip unit by means of primary current injection. Pickup values and trip characteristics shall be as specified and within manufacturer's published tolerances.
 - g. Perform minimum pickup voltage tests on shunt trip and close coils in accordance with manufacturer's published data. Minimum pickup voltage of the shunt trip and close coils shall be as indicated by manufacturer.
 - h. Verify correct operation of auxiliary features such as trip and pickup indicators; zone interlocking; electrical close and trip operation; trip-free, anti-pump function; and trip unit battery condition. Reset all trip logs and indicators. Investigate units that do not function as designed.
 - i. Verify operation of charging mechanism. Investigate units that do not function as designed.
3. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
4. Perform the following infrared scan tests and inspections and prepare reports:
- a. Initial Infrared Scanning: After Final Acceptance, but not more than 60 days after Final Acceptance, perform an infrared scan of each enclosed switch and circuit breaker. Remove front panels so joints and connections are accessible to portable scanner.

- b. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each enclosed switch and circuit breaker 11 months after date of Final Acceptance.
- c. Instruments and Equipment: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.

5. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.

G. Enclosed switches and circuit breakers will be considered defective if they do not pass tests and inspections.

H. Prepare test and inspection reports.

- 1. Test procedures used.
- 2. Include identification of each enclosed switch and circuit breaker tested and describe test results.
- 3. List deficiencies detected, remedial action taken, and observations after remedial action.

3.7 ADJUSTING

- A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.
- B. Set field-adjustable circuit-breaker trip ranges to values indicated on the Drawings.

END OF SECTION

SECTION 262923 - VARIABLE-FREQUENCY MOTOR CONTROLLERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes separately enclosed, preassembled, combination VFCs, rated 600 V and less, for speed control of three-phase, squirrel-cage induction motors.

1.3 DEFINITIONS

- A. CE: Conformities European (European Compliance).
- B. CPT: Control power transformer.
- C. DDC: Direct digital control.
- D. EMI: Electromagnetic interference.
- E. LED: Light-emitting diode.
- F. NC: Normally closed.
- G. NO: Normally open.
- H. OCPD: Overcurrent protective device.
- I. PID: Control action, proportional plus integral plus derivative.
- J. RFI: Radio-frequency interference.
- K. VFC: Variable-frequency motor controller.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type and rating of VFC indicated.
 - 1. Include dimensions and finishes for VFCs.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

- B. Shop Drawings: For each VFC indicated.
1. Include mounting and attachment details.
 2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 3. Include diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Floor plans, drawn to scale, showing dimensioned layout on which the following items are shown and coordinated with each other, using input from installers of the items involved:
1. Required working clearances and required area above and around VFCs.
 2. Show VFC layout and relationships between electrical components and adjacent structural and mechanical elements.
 3. Show support locations, type of support, and weight on each support.
 4. Indicate field measurements.
- B. Qualification Data: For testing agency.
- C. Seismic Qualification Data: Certificates, for each VFC, accessories, and components, from manufacturer.
1. Certificate of compliance.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based, and their installation requirements.
- D. Product Certificates: For each VFC from manufacturer.
- E. Harmonic Analysis Report: Provide Project-specific calculations and manufacturer's statement of compliance with IEEE 519.
- F. Source quality-control reports.
- G. Field quality-control reports.
- H. Sample Warranty: For special warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For VFCs to include in emergency, operation, and maintenance manuals.
1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

- a. Manufacturer's written instructions for testing and adjusting thermal-magnetic circuit breaker and motor-circuit protector trip settings.
- b. Manufacturer's written instructions for setting field-adjustable overload relays.
- c. Manufacturer's written instructions for testing, adjusting, and reprogramming micro-processor control modules.
- d. Manufacturer's written instructions for setting field-adjustable timers, controls, and status and alarm points.
- e. Load-Current and Overload-Relay Heater List: Compile after motors have been installed, and arrange to demonstrate that selection of heaters suits actual motor nameplate, full-load currents.
- f. Load-Current and List of Settings of Adjustable Overload Relays: Compile after motors have been installed, and arrange to demonstrate that switch settings for motor-running overload protection suit actual motors to be protected.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 1. Power Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.
 2. Control Power Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than two of each size and type.
 3. Indicating Lights: Two of each type and color installed.
 4. Auxiliary Contacts: Furnish one spare(s) for each size and type of magnetic controller installed.
 5. Power Contacts: Furnish three spares for each size and type of magnetic contactor installed.

1.8 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Accredited by NETA.
 1. Testing Agency's Field Supervisor: Currently certified by NETA to supervise on-site testing.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. If stored in space that is not permanently enclosed and air conditioned, remove loose packing and flammable materials from inside controllers and install temporary electric heating, with at least 250 W per controller.
- B. Product Selection for Restricted Space: Drawings indicate maximum dimensions for VFCs, including clearances between VFCs, and adjacent surfaces and other items.

1.10 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace VFCs that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. ABB, Electrification Business.
 2. ABB, Motion Business.
 3. Cerus Industrial, Inc.
 4. Danfoss, Inc.
 5. Eaton.
 6. Nidec Motor Corporation; Nidec Corporation.
 7. Rockwell Automation, Inc.
 8. Schneider Electric USA, Inc.
 9. Siemens Industry, Inc., Building Technologies Division.
 10. Yaskawa Electric America, Inc.
 11. Service Wire Co.

2.2 SYSTEM DESCRIPTION

- A. General Requirements for VFCs:
 1. VFCs and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 2. Comply with NEMA ICS 7, NEMA ICS 61800-2, and UL 508A.
- B. Application: Variable torque.
- C. VFC Description: Variable-frequency motor controller, consisting of power converter that employs pulse-width-modulated inverter, factory built and tested in an enclosure, with integral disconnecting means and overcurrent and overload protection; listed and labeled by an NRTL as a complete unit; arranged to provide self-protection, protection, and variable-speed control of one or more three-phase induction motors by adjusting output voltage and frequency.
 1. Units suitable for operation of NEMA MG 1, Design A and Design B motors, as defined by NEMA MG 1, Section IV, Part 30, "Application Considerations for Constant Speed Motors Used on a Sinusoidal Bus with Harmonic Content and General Purpose Motors Used with Adjustable-Voltage or Adjustable-Frequency Controls or Both."
 2. Units suitable for operation of inverter-duty motors as defined by NEMA MG 1, Section IV, Part 31, "Definite-Purpose Inverter-Fed Polyphase Motors."
 3. Listed and labeled for integrated short-circuit current (withstand) rating by an NRTL acceptable to authorities having jurisdiction.
- D. Design and Rating: Match load type, such as fans, blowers, and pumps; and type of connection used between motor and load such as direct or through a power-transmission connection.

- E. Output Rating: Three phase; 10 to 60 Hz, with voltage proportional to frequency throughout voltage range; maximum voltage equals input voltage.
- F. Unit Operating Requirements:
1. Input AC Voltage Tolerance: Plus 10 and minus 10 percent of VFC input voltage rating.
 2. Input AC Voltage Unbalance: Not exceeding 3 percent.
 3. Input Frequency Tolerance: Plus or minus 3 percent of VFC frequency rating.
 4. Minimum Efficiency: 96 percent at 60 Hz, full load.
 5. Minimum Displacement Primary-Side Power Factor: 96 percent under any load or speed condition.
 6. Minimum Short-Circuit Current (Withstand) Rating: 65 kA.
 7. Ambient Temperature Rating: Not less than 32 deg F and not exceeding 104 deg F.
 8. Humidity Rating: Less than 95 percent (noncondensing).
 9. Altitude Rating: Not exceeding 3300 feet.
 10. Vibration Withstand: Comply with NEMA ICS 61800-2.
 11. Overload Capability: 1.1 times the base load current for 60 seconds; minimum of 1.8 times the base load current for three seconds.
 12. Starting Torque: Minimum 100 percent of rated torque from 3 to 60 Hz.
 13. Speed Regulation: Plus or minus 5 percent.
 14. Output Carrier Frequency: Selectable; 0.5 to 15 kHz.
 15. Stop Modes: Programmable; includes fast, free-wheel, and dc injection braking.
- G. Inverter Logic: Microprocessor based, 32 bit, isolated from all power circuits.
- H. Isolated Control Interface: Allows VFCs to follow remote-control signal over a minimum 40:1 speed range.
1. Signal: Electrical.
- I. Internal Adjustability Capabilities:
1. Minimum Speed: 5 to 25 percent of maximum rpm.
 2. Maximum Speed: 80 to 100 percent of maximum rpm.
 3. Acceleration: 0.1 to 999.9 seconds.
 4. Deceleration: 0.1 to 999.9 seconds.
 5. Current Limit: 30 to minimum of 150 percent of maximum rating.
- J. Self-Protection and Reliability Features:
1. Surge Suppression: Factory installed as an integral part of the VFC, complying with UL 1449 SPD, Type 1 or Type 2.
 2. Surge Suppression: Field-mounted surge suppressors complying with Section 264313 "Surge Protection for Low-Voltage Electrical Power Circuits," UL 1449 SPD, Type 2.
 3. Loss of Input Signal Protection: Selectable response strategy, including speed default to a percent of the most recent speed, a preset speed, or stop; with alarm.
 4. Under- and overvoltage trips.
 5. Inverter overcurrent trips.

6. VFC and Motor-Overload/Overtemperature Protection: Microprocessor-based thermal protection system for monitoring VFCs and motor thermal characteristics, and for providing VFC overtemperature and motor-overload alarm and trip; settings selectable via the keypad.
 7. Critical frequency rejection, with three selectable, adjustable deadbands.
 8. Instantaneous line-to-line and line-to-ground overcurrent trips.
 9. Loss-of-phase protection.
 10. Reverse-phase protection.
 11. Short-circuit protection.
 12. Motor-overtemperature fault.
- K. Automatic Reset/Restart: Attempt three restarts after drive fault or on return of power after an interruption and before shutting down for manual reset or fault correction; adjustable delay time between restart attempts.
- L. Power-Interruption Protection: To prevent motor from re-energizing after a power interruption until motor has stopped, unless "Bidirectional Autospeed Search" feature is available and engaged.
- M. Bidirectional Autospeed Search: Capable of starting VFC into rotating loads spinning in either direction and returning motor to set speed in proper direction, without causing damage to drive, motor, or load.
- N. Torque Boost: Automatically varies starting and continuous torque to at least 1.5 times the minimum torque to ensure high-starting torque and increased torque at slow speeds.
- O. Motor Temperature Compensation at Slow Speeds: Adjustable current fall-back based on output frequency for temperature protection of self-cooled, fan-ventilated motors at slow speeds.
- P. Integral Input Disconnecting Means and OCPD: UL 489, instantaneous-trip circuit breaker with pad-lockable, door-mounted handle mechanism.
1. Disconnect Rating: Not less than 115 percent of VFC input current rating.
 2. Disconnect Rating: Not less than 115 percent of NFPA 70 motor full-load current rating or VFC input current rating, whichever is larger.
 3. Auxiliary Contacts: NO or NC, arranged to activate before switch blades open.
 4. Auxiliary contacts "a" and "b" arranged to activate with circuit-breaker handle.
 5. NC alarm contact that operates only when circuit breaker has tripped.

2.3 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: VFCs shall withstand the effects of earthquake motions determined according to ASCE/SEI 7. The designated VFCs shall be tested and certified by an NRTL as meeting the ICC-ES AC 156 test procedure requirements.
1. The term "withstand" means "the unit will remain in place without separation of any parts when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."

2.4 CONTROLS AND INDICATION

- A. Status Lights: Door-mounted LED indicators displaying the following conditions:
- 1.Power on.
 - 2.Run.
 - 3.Overtoltage.
 - 4.Line fault.
 - 5.Overcurrent.
 - 6.External fault.
- B. Panel-Mounted Operator Station: Manufacturer's standard front-accessible, sealed keypad and plain-English-language digital display; allows complete programming, program copying, operating, monitoring, and diagnostic capability.
- 1.Keypad: In addition to required programming and control keys, include keys for HAND, OFF, and AUTO modes.
 - 2.Security Access: Provide electronic security access to controls through identification and password with at least three levels of access: View only; view and operate; and view, operate, and service.
 - a. Control Authority: Supports at least four conditions: Off, local manual control at VFC, local automatic control at VFC, and automatic control through a remote source.
- C. Historical Logging Information and Displays:
- 1.Real-time clock with current time and date.
 - 2.Running log of total power versus time.
 - 3.Total run time.
 - 4.Fault log, maintaining last four faults with time and date stamp for each.
- D. Indicating Devices: Digital display mounted flush in VFC door and connected to display VFC parameters including, but not limited to:
- 1.Output frequency (Hz).
 - 2.Motor speed (rpm).
 - 3.Motor status (running, stop, fault).
 - 4.Motor current (amperes).
 - 5.Motor torque (percent).
 - 6.Fault or alarming status (code).
 - 7.PID feedback signal (percent).
 - 8.DC-link voltage (V dc).
 - 9.Set point frequency (Hz).
 10. Motor output voltage (V ac).
- E. Control Signal Interfaces:
- 1.Electric Input Signal Interface:
 - a. A minimum of two programmable analog inputs: 0- to 10-V dc.

- b. A minimum of six multifunction programmable digital inputs.
2. Pneumatic Input Signal Interface: 3 to 15 psig.
 3. Remote Signal Inputs: Capability to accept any of the following speed-setting input signals from the DDC system for HVAC or other control systems:
 - a. 0- to 10-V dc.
 - b. 4- to 20-mA dc.
 - c. Potentiometer using up/down digital inputs.
 - d. Fixed frequencies using digital inputs.
 4. Output Signal Interface: A minimum of one programmable analog output signal(s) (0- to 10-V dc), which can be configured for any of the following:
 - a. Output frequency (Hz).
 - b. Output current (load).
 - c. DC-link voltage (V dc).
 - d. Motor torque (percent).
 - e. Motor speed (rpm).
 - f. Set point frequency (Hz).
 5. Remote Indication Interface: A minimum of two programmable dry-circuit relay outputs (120-V ac, 1 A) for remote indication of the following:
 - a. Motor running.
 - b. Set point speed reached.
 - c. Fault and warning indication (overtemperature or overcurrent).
 - d. PID high- or low-speed limits reached.
- F. PID Control Interface: Provides closed-loop set point, differential feedback control in response to dual feedback signals. Allows for closed-loop control of fans and pumps for pressure, flow, or temperature regulation.
1. Number of Loops: One.
- G. Interface with DDC System for HVAC: Factory-installed hardware and software shall interface with DDC system for HVAC to monitor, control, display, and record data for use in processing reports. VFC settings shall be retained within VFC's nonvolatile memory.
1. Hardwired Points:
 - a. Monitoring: On-off status.
 - b. Control: On-off operation.
 2. Communication Interface: Comply with ASHRAE 135. Communication shall interface with DDC system for HVAC to remotely control and monitor lighting from a DDC system for HVAC operator workstation. Control features and monitoring points displayed locally at lighting panel shall be available through the DDC system for HVAC.

2.5 LINE CONDITIONING AND FILTERING

- A. Input Line Conditioning: Based on the manufacturer's harmonic analysis study and report, provide input filtering, as required, to limit total demand (harmonic current) distortion and total harmonic voltage demand at the defined point of common coupling to meet IEEE 519 recommendations.
- B. Output Filtering: <Insert requirements>.
- C. EMI/RFI Filtering: CE marked; certify compliance with IEC 61800-3 for [Category C2] <Insert category>.
- D. EMI/RFI Filtering: <Insert requirements>.

2.6 BYPASS SYSTEMS

- A. Bypass Operation: Safely transfers motor between power converter output and bypass circuit, manually, automatically, or both. Selector switches set modes and indicator lights indicate mode selected. Unit is capable of stable operation (starting, stopping, and running) with motor completely disconnected from power converter.
- B. Bypass Mode: Manual operation only; requires local operator selection at VFC. Transfer between power converter and bypass contactor, and retransfer shall only be allowed with the motor at zero speed.
- C. Bypass Mode: Field-selectable automatic or manual, allows local and remote transfer between power converter and bypass contactor and retransfer, either via manual operator interface or automatic-control system feedback.
- D. Bypass Controller: Two-contactor-style bypass allows motor operation via the power converter or the bypass controller.
 - 1. Bypass Contactor: Load-break, NEMA-rated contactor.
 - 2. Output Isolating Contactor: Non-load-break, NEMA-rated contactor.
 - 3. Isolating Switch: Non-load-break switch arranged to isolate power converter and permit safe troubleshooting and testing of the power converter, both energized and de-energized, while motor is operating in bypass mode; pad-lockable, door-mounted handle mechanism.
- E. Bypass Controller: Three-contactor-style bypass allows motor operation via the power converter or the bypass controller arranged to isolate the power converter input and output and permit safe testing of the power converter, both energized and de-energized, while motor is operating in bypass mode.
 - 1. Bypass Contactor: Load-break, NEMA-rated contactor.
 - 2. Input and Output Isolating Contactors: Non-load-break, NEMA-rated contactors.
 - 3. Isolating Switch: Non-load-break switch arranged to isolate power converter and permit safe troubleshooting and testing of the power converter, both energized and de-energized, while motor is operating in bypass mode; pad-lockable, door-mounted handle mechanism.

F. Bypass Contactor Configuration: Full-voltage (across-the-line) type.

1. NORMAL/BYPASS selector switch.
2. HAND/OFF/AUTO selector switch.
3. NORMAL/TEST Selector Switch: Allows testing and adjusting of VFC while the motor is running in the bypass mode.
4. Contactor Coils: Pressure-encapsulated type.
 - a. Operating Voltage: Depending on contactor NEMA size and line-voltage rating, manufacturer's standard matching control power or line voltage.
 - b. Power Contacts: Totally enclosed, double break, and silver-cadmium oxide; assembled to allow inspection and replacement without disturbing line or load wiring.
5. Control Circuits: 120-V ac; obtained from integral CPT, with primary and secondary fuses, with CPT of sufficient capacity to operate all integral devices and remotely located pilot, indicating, and control devices.
 - a. CPT Spare Capacity: 50 VA.
6. Overload Relays: NEMA ICS 2.
 - a. Melting-Alloy Overload Relays:
 - 1) Inverse-time-current characteristic.
 - 2) Class 10 tripping characteristic.
 - 3) Heaters in each phase matched to nameplate full-load current of actual protected motor and with appropriate adjustment for duty cycle.
 - b. Bimetallic Overload Relays:
 - 1) Inverse-time-current characteristic.
 - 2) Class 10 tripping characteristic.
 - 3) Heaters in each phase matched to nameplate full-load current of actual protected motor and with appropriate adjustment for duty cycle.
 - 4) Ambient compensated.
 - 5) Automatic resetting.
 - c. Solid-State Overload Relays:
 - 1) Switch or dial selectable for motor-running overload protection.
 - 2) Sensors in each phase.
 - 3) Class 10 tripping characteristic selected to protect motor against voltage and current unbalance and single phasing.
 - 4) Class II ground-fault protection, with start and run delays to prevent nuisance trip on starting.
 - 5) Analog communication module.
 - d. NC isolated overload alarm contact.
 - e. External overload, reset push button.

2.7 OPTIONAL FEATURES

- A. Multiple-Motor Capability: VFC suitable for variable-speed service to multiple motors. Overload protection shuts down VFC and motors served by it, and generates fault indications when overload protection activates.
 - 1. Configure to allow two or more motors to operate simultaneously at the same speed; separate overload relay for each controlled motor.
 - 2. Configure to allow two motors to operate separately; operator selectable via local or remote switch or contact closures; single overload relay for both motors; separate output magnetic contactors for each motor.
 - 3. Configure to allow two motors to operate simultaneously and in a lead/lag mode, with one motor operated at variable speed via the power converter and the other at constant speed via the bypass controller; separate overload relay for each controlled motor.
- B. Damper control circuit with end-of-travel feedback capability.
- C. Sleep Function: Senses a minimal deviation of a feedback signal and stops the motor. On an increase in speed-command signal deviation, VFC resumes normal operation.
- D. Motor Preheat Function: Preheats motor when idle to prevent moisture accumulation in the motor.
- E. Remote Indicating Circuit Terminals: Mode selection, controller status, and controller fault.
- F. Remote digital operator kit.
- G. Communication Port: RS-232 port, USB 2.0 port, or equivalent connection capable of connecting a printer.

2.8 ENCLOSURES

- A. VFC Enclosures: NEMA 250, to comply with environmental conditions at installed location.
 - 1. Dry and Clean Indoor Locations: Type 1.
 - 2. Outdoor Locations: Type 3R.
 - 3. Wash-Down Areas: Type 4X, stainless steel.
 - 4. Other Wet or Damp Indoor Locations: Type 4.
 - 5. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: Type 12.
- B. Plenum Rating: UL 1995; NRTL certification label on enclosure, clearly identifying VFC as "Plenum Rated."

2.9 ACCESSORIES

- A. General Requirements for Control-Circuit and Pilot Devices: NEMA ICS 5; factory installed in VFC enclosure cover unless otherwise indicated.
 - 1. Push Buttons: Covered.

2. Pilot Lights: Push to test.
3. Selector Switches: Rotary type.
4. Stop and Lockout Push-Button Station: Momentary-break, push-button station with a factory-applied hasp arranged so padlock can be used to lock push button in depressed position with control circuit open.

- B. NC bypass contactor auxiliary contact(s).
- C. Control Relays: Auxiliary and adjustable solid-state time-delay relays.
- D. Phase-Failure, Phase-Reversal, and Undervoltage and Overvoltage Relays: Solid-state sensing circuit with isolated output contacts for hard-wired connections. Provide adjustable undervoltage, overvoltage, and time-delay settings.
1. Current Transformers: Continuous current rating, basic impulse insulating level (BIL) rating, burden, and accuracy class suitable for connected circuitry. Comply with IEEE C57.13.
- E. Supplemental Digital Meters:
1. Elapsed-time meter.
 2. Kilowatt meter.
 3. Kilowatt-hour meter.
- F. Breather and drain assemblies, to maintain interior pressure and release condensation in NEMA 250, Type 4 enclosures installed outdoors or in unconditioned interior spaces subject to humidity and temperature swings.
- G. Space heaters, with NC auxiliary contacts, to mitigate condensation in NEMA 250, Type 3R enclosures installed outdoors or in unconditioned interior spaces subject to humidity and temperature swings.
- H. Cooling Fan and Exhaust System: For NEMA 250, Type 1; UL 508 component recognized: Supply fan, with stainless-steel intake and exhaust grills and filters; 120-V ac; obtained from integral CPT.
- I. Sun shields installed on fronts, sides, and tops of enclosures installed outdoors and subject to direct and extended sun exposure.
- J. Spare control-wiring terminal blocks; unwired.

2.10 SOURCE QUALITY CONTROL

- A. Testing: Test and inspect VFCs according to requirements in NEMA ICS 61800-2.
1. Test each VFC while connected to its specified motor.
 2. Verification of Performance: Rate VFCs according to operation of functions and features specified.
- B. VFCs will be considered defective if they do not pass tests and inspections.

- C. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas, surfaces, and substrates to receive VFCs, with Installer present, for compliance with requirements for installation tolerances, and other conditions affecting performance of the Work.
- B. Examine VFC before installation. Reject VFCs that are wet, moisture damaged, or mold damaged.
- C. Examine roughing-in for conduit systems to verify actual locations of conduit connections before VFC installation.
- D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Wall-Mounting Controllers: Install with tops at uniform height and with disconnect operating handles not higher than 79 inches above finished floor, unless otherwise indicated, and by bolting units to wall or mounting on lightweight structural-steel channels bolted to wall. For controllers not on walls, provide freestanding racks complying with Section 260529 "Hangers and Supports for Electrical Systems."
- B. Floor-Mounting Controllers: Install VFCs on 4-inch nominal thickness concrete base. Comply with requirements for concrete base specified in Section 033000 "Cast-in-Place Concrete."
 - 1. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of concrete base.
 - 2. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
 - 3. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 4. Install anchor bolts to elevations required for proper attachment to supported equipment.
- C. Roof-Mounting Controllers: Install VFC on roofs with tops at uniform height and with disconnect operating handles not higher than 79 inches above finished roof surface unless otherwise indicated, and by bolting units to curbs or mounting on freestanding, lightweight, structural-steel channels bolted to curbs. Seal roof penetrations after raceways are installed.
 - 1. Curbs and roof penetrations are specified in Section 077200 "Roof Accessories."
 - 2. Structural-steel channels are specified in Section 260529 "Hangers and Supports for Electrical Systems."

- D. Seismic Bracing: Comply with requirements specified in Section 260548.16 "Seismic Controls for Electrical Systems."
- E. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.
- F. Install fuses in each fusible-switch VFC.
- G. Install fuses in control circuits if not factory installed. Comply with requirements in Section 262813 "Fuses."
- H. Install heaters in thermal-overload relays. Select heaters based on actual nameplate full-load amperes after motors are installed.
- I. Install, connect, and fuse thermal-protector monitoring relays furnished with motor-driven equipment.
- J. Comply with NECA 1.

3.3 CONTROL WIRING INSTALLATION

- A. Install wiring between VFCs and remote devices. Comply with requirements in Section 260523 "Control-Voltage Electrical Power Cables."
- B. Bundle, train, and support wiring in enclosures.
- C. Connect selector switches and other automatic-control devices where applicable.
 - 1. Connect selector switches to bypass only those manual- and automatic-control devices that have no safety functions when switches are in manual-control position.
 - 2. Connect selector switches with control circuit in both manual and automatic positions for safety-type control devices such as low- and high-pressure cutouts, high-temperature cutouts, and motor-overload protectors.

3.4 IDENTIFICATION

- A. Identify VFCs, components, and control wiring. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
 - 1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
 - 2. Label each VFC with engraved nameplate.
 - 3. Label each enclosure-mounted control and pilot device.
- B. Operating Instructions: Frame printed operating instructions for VFCs, including control sequences and emergency procedures. Fabricate frame of finished metal, and cover instructions with clear acrylic plastic. Mount on front of VFC units.

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections with the assistance of a factory-authorized service representative.
- D. Acceptance Testing Preparation:
 - 1. Test insulation resistance for each VFC element, bus, component, connecting supply, feeder, and control circuit.
 - 2. Test continuity of each circuit.
- E. Tests and Inspections:
 - 1. Inspect VFC, wiring, components, connections, and equipment installation. Test and adjust controllers, components, and equipment.
 - 2. Test insulation resistance for each VFC element, component, connecting motor supply, feeder, and control circuits.
 - 3. Test continuity of each circuit.
 - 4. Verify that voltages at VFC locations are within 10 percent of motor nameplate rated voltages. If outside this range for any motor, notify Owner before starting the motor(s).
 - 5. Test each motor for proper phase rotation.
 - 6. Perform tests according to the Inspection and Test Procedures for Adjustable Speed Drives stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
 - 7. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
 - 8. Perform the following infrared (thermographic) scan tests and inspections, and prepare reports:
 - a. Initial Infrared Scanning: After Final Acceptance, but not more than 60 days after Final Acceptance, perform an infrared scan of each VFC. Remove front panels so joints and connections are accessible to portable scanner.
 - b. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each VFC 11 months after date of Final Acceptance.
 - c. Instruments and Equipment: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - 9. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.
- F. VFCs will be considered defective if they do not pass tests and inspections.
- G. Prepare test and inspection reports, including a certified report that identifies the VFC and describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations made after remedial action.

3.6 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
 - 1. Complete installation and startup checks according to manufacturer's written instructions.

3.7 ADJUSTING

- A. Program microprocessors for required operational sequences, status indications, alarms, event recording, and display features. Clear events memory after final acceptance testing and prior to Final Acceptance.
- B. Set field-adjustable switches, auxiliary relays, time-delay relays, timers, and overload-relay pickup and trip ranges.
- C. Adjust the trip settings of instantaneous-only circuit breakers and thermal-magnetic circuit breakers with adjustable, instantaneous trip elements. Initially adjust to 6 times the motor nameplate full-load amperes and attempt to start motors several times, allowing for motor cool-down between starts. If tripping occurs on motor inrush, adjust settings in increments until motors start without tripping. Do not exceed 8 times the motor full-load amperes (or 11 times for NEMA Premium Efficient motors if required). Where these maximum settings do not allow starting of a motor, notify Owner before increasing settings.
- D. Set the taps on reduced-voltage autotransformer controllers.
- E. Set field-adjustable circuit-breaker trip ranges.
- F. Set field-adjustable pressure switches.

3.8 PROTECTION

- A. Temporary Heating: Apply temporary heat to maintain temperature according to manufacturer's written instructions until controllers are ready to be energized and placed into service.
- B. Replace VFCs whose interiors have been exposed to water or other liquids prior to Final Acceptance.

3.9 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, reprogram, and maintain VFCs.

END OF SECTION

SECTION 26 32 14 - ENGINE GENERATORS - DIESEL

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes packaged engine-generator sets for emergency power supply with the following features:
 - 1. Diesel-engine-driven generator sets.
 - 2. Diesel engine.
 - 3. Diesel fuel-oil system.
 - 4. Control and monitoring.
 - 5. Generator overcurrent and fault protection.
 - 6. Generator, exciter, and voltage regulator.
 - 7. Outdoor engine generator enclosure.
 - 8. Remote radiator motors.
 - 9. Vibration isolation devices.

- B. Related Sections include the following:
 - 1. Division 26 Section "Transfer Switches" for transfer switches including sensors and relays to initiate automatic-starting and -stopping signals for engine-generator sets.

1.2 DEFINITIONS

- A. EPS: Emergency power supply.

- B. EPSS: Emergency power supply system.

- C. Operational Bandwidth: The total variation from the lowest to highest value of a parameter over the range of conditions indicated, expressed as a percentage of the nominal value of the parameter.

1.3 SUBMITTALS

- A. Product Data: For each type of packaged engine generator indicated. Include rated capacities, operating characteristics, and furnished specialties and accessories. In addition, include the following:
 - 1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
 - 2. Include thermal damage curve for generator.
 - 3. Include time-current characteristic curves for generator protective device.
 - 4. Include fuel consumption in gallons per hour at 0.8 power factor at 0.5, 0.75, and 1.0 times generator capacity.
 - 5. Include generator efficiency at 0.8 power factor at 0.5, 0.75, and 1.0 times generator capacity.

6. Include airflow requirements for cooling and combustion air in cubic feet per minute at 0.8 power factor, with air-supply temperature of 95, 80, 70, and 50 deg F. Provide Drawings indicating requirements and limitations for location of air intake and exhausts.
 7. Include generator characteristics, including, but not limited to, kilowatt rating, efficiency, reactances, and short-circuit current capability.
- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
1. Include plans and elevations for engine generator and other components specified. Indicate access requirements affected by height of subbase fuel tank.
 2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 3. Identify fluid drain ports and clearance requirements for proper fluid drain.
 4. Design calculations for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
 5. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include base weights.
 6. Include diagrams for power, signal, and control wiring. Complete schematic, wiring, and interconnection diagrams showing terminal markings for engine generators and functional relationship between all electrical components.
- C. Qualification Data: For installer, manufacturer, and testing agency.
- D. Source quality-control test reports.
1. Certified summary of prototype-unit test report.
 2. Certified Test Reports: For components and accessories that are equivalent, but not identical, to those tested on prototype unit.
 3. Report of factory test on units to be shipped for this Project, showing evidence of compliance with specified requirements.
 4. Report of sound generation.
 5. Report of exhaust emissions showing compliance with applicable regulations, including EPA requirements.
 6. Certified Torsional Vibration Compatibility: Comply with NFPA 110.
- E. Field quality-control test reports.
- F. Operation and Maintenance Data: For packaged engine generators include the following:
1. List of tools and replacement items recommended to be stored at Project for ready access. Include part and drawing numbers, current unit prices, and source of supply.
- G. Warranty: Special warranty specified in this Section.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.

1. Maintenance Proximity: Not more than four hours' normal travel time from Installer's place of business to Project site.
- B. Manufacturer Qualifications: The engine generator supplier shall maintain 24 hour parts and service capability within 100 miles of the project site. The distributor shall stock parts as needed to support the generator set package for this specific project. The distributor shall carry sufficient inventory to cover no less than 80% of the parts service within 24 hours and 95% within 48 hours.
- C. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a member company of the InterNational Electrical Testing Association or is a nationally recognized testing laboratory (NRTL), and that is acceptable to authorities having jurisdiction.
 1. Testing Agency's Field Supervisor: Person currently certified by the InterNational Electrical Testing Association or the National Institute for Certification in Engineering Technologies to supervise on-site testing specified in Part 3.
- D. Source Limitations: Obtain packaged generator sets and auxiliary components through one source from a single manufacturer.
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- F. Comply with ASME B15.1.
- G. Comply with NFPA 37.
- H. Comply with NFPA 70.
- I. Comply with NFPA 110 requirements for Level 1 emergency power supply system.
- J. Comply with NFPA 111.
- K. Comply with UL 2200.
- L. Engine Exhaust Emissions: Comply with applicable state and local government requirements.
- M. Noise Emission: Comply with applicable state and local government requirements for maximum noise level at adjacent property boundaries due to sound emitted by generator set including engine, engine exhaust, engine cooling-air intake and discharge, and other components of installation.
- N. The emergency generator must be in compliance with all applicable requirements of 40 CFR Part 60 Subpart III.
 1. The engine will be provided along with manufacturer certification of compliance with pertinent emission limits.

1.5 PROJECT CONDITIONS.

- A. Environmental Conditions: Engine-generator system shall withstand the following environmental conditions without mechanical or electrical damage or degradation of performance capability:
 - 1. Ambient Temperature: 5 to 40 deg C.
 - 2. Altitude: Sea level to 1000 feet.

1.6 COORDINATION

- A. Coordinate size and location of concrete bases for package engine generators. Cast anchor-bolt inserts into bases.

1.7 WARRANTY

- A. Special Warranty: Five Year Standby Generator Set Warranty
 - 1. The manufacturer's standard warranty shall in no event be for a period of less than Five (5) years from date of initial start-up of the system and shall include repair parts, labor, reasonable travel expense necessary for repairs at the job site, and expendables (lubricating oil, filters, antifreeze, and other service items made unusable by the defect) used during the course of repair. Running hours shall be limited to 500 hours annually for the system warranty by both the manufacturer and servicing distributor. Submittals received without written warranties as specified will be rejected in their entirety.
 - 2. Warranty shall include a temporary generator set in the event a warrantable repair will take more than 48 hours. Selling dealer must have a minimum of 100 units in its rental fleet to assure a temporary unit is available if needed. Provide documentation as such.

1.8 Documentation and training

- A. Documentation: Prior to Final Acceptance, the manufacturer shall supply three (3) copies of the complete instruction manuals to Owner. The manuals shall include operation and maintenance procedures, complete parts lists, dimensional drawings, and unit wiring diagrams and schematics, and interconnection wiring diagrams.
- B. Training: Prior to Final Acceptance, the manufacturer shall provide comprehensive training to the Owner's designated personnel. Training shall cover, but not be limited to, operation, maintenance and troubleshooting of the equipment.

1.9 MAINTENANCE SERVICE

- A. Initial Maintenance Service: Beginning at Final Acceptance, provide 12 months' full maintenance by skilled employees of manufacturer's designated service organization. Include quarterly exercising to check for proper starting, load transfer, and running under load. Include routine preventive maintenance as recommended by manufacturer and adjusting as required for proper operation. Provide parts and supplies same as those used in the manufacture and installation of original equipment.

1.10 Maintenance MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
1. Fuses: One for every 10 of each type and rating, but no fewer than one of each.
 2. Indicator Lamps: Two for every six of each type used, but no fewer than two of each.
 3. Filters: One set each of lubricating oil, fuel, and combustion-air filters.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Caterpillar; Engine Div.
 2. Generac Power Systems, Inc.
 3. Onan/Cummins Power Generation; Industrial Business Group.

2.2 DIESEL-ENGINE-DRIVEN GENERATOR SETS

- a. Source Limitations: Obtain packaged engine generators and auxiliary components from single source from single manufacturer.

2.3 PERFORMANCE REQUIREMENTS

1. Seismic Performance: Engine generator housing, subbase fuel tank engine generator, batteries, battery racks, silencers, sound attenuating equipment, accessories, and components shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 - 1) Component Importance Factor: 1.5.
- b. B11 Compliance: Comply with B11.19.
- c. NFPA Compliance:
 - 1) Comply with NFPA 37.
 - 2) Comply with NFPA 70.
 - 3) Comply with NFPA 110 requirements for Level 2 EPSS.
- d. UL Compliance: Comply with UL 2200.
- e. Engine Exhaust Emissions: Comply with EPA Tier 2 requirements and applicable state and local government requirements.
- f. Noise Emission: Comply with applicable state and local government requirements for maximum noise level at adjacent property boundaries due to sound emitted by engine generator including engine, engine exhaust, engine cooling-air intake and discharge, and other components of installation.
- g. Environmental Conditions: Engine generator system shall withstand the following environmental conditions without mechanical or electrical damage or degradation of performance capability:
 - 1) Ambient Temperature: 5 to 104 deg F
 - 2) Relative Humidity: Zero to 95 percent.
 - 3) Altitude: Sea level to 1000 feet.

2.4 ENGINE GENERATOR ASSEMBLY DESCRIPTION

- a. Factory-assembled and -tested, water-cooled engine, with brushless generator and accessories.
- b. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
- c. Power Rating: Standby.
- d. EPSS Class: Engine generator shall be classified as a Class 2 according to NFPA 110.
- e. Service Load: 218 kVA.
- f. Power Factor: 0.8, lagging.
- g. Frequency: 60 Hz.
- h. Voltage: 208-V ac.
- i. Phase: Three-phase, four wire, wye.
- j. Induction Method: Naturally aspirated.
- k. Governor: Adjustable isochronous, with speed sensing.
- l. Mounting Frame: Structural steel framework to maintain alignment of mounted components without depending on concrete foundation. Provide lifting attachments sized and spaced to prevent deflection of base during lifting and moving.
 - 1) Rigging Diagram: Inscribed on metal plate permanently attached to mounting frame to indicate location and lifting capacity of each lifting attachment and engine generator center of gravity.
- m. Capacities and Characteristics:
 - 1) Power Output Ratings: Nominal ratings as indicated at 0.8 power factor excluding power required for the continued and repeated operation of the unit and auxiliaries.
 - 2) Nameplates: For each major system component to identify manufacturer's name and address, and model and serial number of component.
- n. Engine Generator Performance:
 - 1) Steady-State Voltage Operational Bandwidth: 3 percent of rated output voltage from no load to full load.
 - 2) Transient Voltage Performance: Not more than 20 percent variation for 50 percent step-load increase or decrease. Voltage shall recover and remain within the steady-state operating band within three seconds.
 - 3) Steady-State Frequency Operational Bandwidth: 0.5 percent of rated frequency from no load to full load.
 - 4) Steady-State Frequency Stability: When system is operating at any constant load within the rated load, there shall be no random speed variations outside the steady-state operational band and no hunting or surging of speed.
 - 5) Transient Frequency Performance: Less than 5 percent variation for 50 percent step-load increase or decrease. Frequency shall recover and remain within the steady-state operating band within five seconds.
 - 6) Output Waveform: At no load, harmonic content measured line to line or line to neutral shall not exceed 5 percent total and 3 percent for single harmonics. Telephone influence factor, determined according to NEMA MG 1, shall not exceed 50 percent.
 - 7) Sustained Short-Circuit Current: For a three-phase, bolted short circuit at system output terminals, system shall supply a minimum of 250 percent of rated full-load current for not less than 10 seconds and then clear the fault automatically, without damage to generator system components.
 - 8) Start Time:

- a) Comply with NFPA 110, Type 10 system requirements.

2.5 DIESEL ENGINE

- a. Fuel: ASTM D975, diesel fuel oil, Grade 2-D S15.
- b. Rated Engine Speed: 1800 rpm.
- c. Lubrication System: Engine or skid-mounted.
 - 1) Filter and Strainer: Rated to remove 90 percent of particles 5 micrometers and smaller while passing full flow.
 - 2) Thermostatic Control Valve: Control flow in system to maintain optimum oil temperature. Unit shall be capable of full flow and is designed to be fail-safe.
 - 3) Crankcase Drain: Arranged for complete gravity drainage to an easily removable container with no disassembly and without use of pumps, siphons, special tools, or appliances.
- d. Jacket Coolant Heater: Electric-immersion type, factory installed in coolant jacket system. Comply with UL 499 and with NFPA 110 requirements for Level 1 equipment for heater capacity.
- e. Integral Cooling System: Closed loop, liquid cooled, with radiator factory mounted on engine generator set mounting frame and integral engine-driven coolant pump.
 - 1) Coolant: Solution of 50 percent ethylene-glycol-based antifreeze and 50 percent water, with anticorrosion additives as recommended by engine manufacturer.
 - 2) Size of Radiator: Adequate to contain expansion of total system coolant from cold start to 110 percent load condition.
 - 3) Expansion Tank: Constructed of welded steel plate and rated to withstand maximum closed-loop coolant system pressure for engine used. Equip with gage glass and petcock.
 - 4) Temperature Control: Self-contained, thermostatic-control valve modulates coolant flow automatically to maintain optimum constant coolant temperature as recommended by engine manufacturer.
 - 5) Coolant Hose: Flexible assembly with inside surface of nonporous rubber and outer covering of aging-, UV-, and abrasion-resistant fabric.
 - a) Rating: 50-psig maximum working pressure with coolant at 180 deg F, and noncollapsible under vacuum.
 - b) End Fittings: Flanges or steel pipe nipples with clamps to suit piping and equipment connections.
- f. Muffler/Silencer:
 - 1) Commercial type, sized as recommended by engine manufacturer and selected with exhaust piping system to not exceed engine manufacturer's engine backpressure requirements.
 - a) Minimum sound attenuation of 12 dB at 500 Hz.
 - b) Sound level measured at a distance of 25 feet from exhaust discharge after installation is complete shall be 90 dBA or less.
- g. Air-Intake Filter: Standard-duty, engine-mounted air cleaner with replaceable dry-filter element and "blocked filter" indicator.
- h. Starting System: 12-V electric, with negative ground.
 - 1) Components: Sized so they are not damaged during a full engine-cranking cycle with ambient temperature at maximum specified in "Performance Requirements" Article.

- 2) Cranking Motor: Heavy-duty unit that automatically engages and releases from engine flywheel without binding.
- 3) Cranking Cycle: As required by NFPA 110 for system level specified.
- 4) Battery: Lead acid, with capacity within ambient temperature range specified in "Performance Requirements" Article to provide specified cranking cycle at least twice without recharging.
- 5) Battery Cable: Size as recommended by engine manufacturer for cable length indicated. Include required interconnecting conductors and connection accessories.
- 6) Battery Compartment: Factory fabricated of metal with acid-resistant finish and thermal insulation. Thermostatically controlled heater shall be arranged to maintain battery above 50 deg F regardless of external ambient temperature within range specified in "Performance Requirements" Article. Include accessories required to support and fasten batteries in place. Provide ventilation to exhaust battery gases.
- 7) Battery Stand: Factory-fabricated, two-tier metal with acid-resistant finish designed to hold the quantity of battery cells required and to maintain the arrangement to minimize lengths of battery interconnections.
- 8) Battery-Charging Alternator: Factory mounted on engine with solid-state voltage regulation and 35-A minimum continuous rating.
- 9) Battery Charger: Current-limiting, automatic-equalizing, and float-charging type designed for lead-acid batteries. Unit shall comply with UL 1236 and include the following features:
 - a) Operation: Equalizing-charging rate of 10 A shall be initiated automatically after battery has lost charge until an adjustable equalizing voltage is achieved at battery terminals. Unit shall then be automatically switched to a lower float-charging mode and shall continue to operate in that mode until battery is discharged again.
 - b) Automatic Temperature Compensation: Adjust float and equalize voltages for variations in ambient temperature from minus 40 to 140 deg F to prevent overcharging at high temperatures and undercharging at low temperatures.
 - c) Automatic Voltage Regulation: Maintain constant output voltage regardless of input voltage variations up to plus or minus 10 percent.
 - d) Ammeter and Voltmeter: Flush mounted in door. Meters shall indicate charging rates.
 - e) Safety Functions: Sense abnormally low battery voltage and close contacts providing low battery voltage indication on control and monitoring panel. Sense high battery voltage and loss of ac input or dc output of battery charger. Either condition shall close contacts that provide a battery-charger malfunction indication at system control and monitoring panel.
 - f) Enclosure and Mounting: NEMA 250, Type 1, wall-mounted cabinet.

2.6 DIESEL FUEL-OIL SYSTEM

- a. Comply with NFPA 37.
- b. Piping: Fuel-oil piping shall be Schedule 40 black steel, complying with requirements in Section 231113 "Facility Fuel-Oil Piping." Cast iron, aluminum, copper, and galvanized steel shall not be used in the fuel-oil system.

- c. Main Fuel Pump: Mounted on engine to provide primary fuel flow under starting and load conditions.
- d. Fuel Filtering: Remove water and contaminants larger than 1 micron.
- e. Relief-Bypass Valve: Automatically regulates pressure in fuel line and returns excess fuel to source.
- f. Subbase-Mounted, Double-Wall, Fuel-Oil Tank: Factory installed and piped, complying with UL 142 fuel-oil tank. Features include the following:
 - 1) Tank level indicator.
 - 2) Fuel-Tank Capacity: Minimum 133 percent of total fuel required for planned operation plus fuel for periodic maintenance operations between fuel refills.
 - 3) Leak detection in interstitial space.
 - 4) Vandal-resistant fill cap.
 - 5) Containment Provisions: Comply with requirements of authorities having jurisdiction.

2.7 CONTROL AND MONITORING

- a. Automatic Starting System Sequence of Operation: When mode-selector switch on the control and monitoring panel is in the automatic position, remote-control contacts in one or more separate automatic transfer switches initiate starting and stopping of engine generator. When mode-selector switch is switched to the on position, engine generator starts. The off position of same switch initiates engine generator shutdown. When engine generator is running, specified system or equipment failures or derangements automatically shut down engine generator and initiate alarms.
- b. Provide minimum run time control set for 30 minutes with override only by operation of a remote emergency-stop switch.
- c. Comply with UL 508A.
- d. Configuration:
 - 1) Operating and safety indications, protective devices, basic system controls, and engine gages shall be grouped in a common control and monitoring panel mounted on the engine generator. Mounting method shall isolate the control panel from engine generator vibration. Panel shall be powered from the engine generator battery.
 - a) Wall-Mounting Cabinet Construction: Rigid, self-supporting steel unit complying with NEMA ICS 6.
- e. Control and Monitoring Panel:
 - 1) Digital engine generator controller with integrated LCD display, controls, and microprocessor, capable of local and remote control, monitoring, and programming, with battery backup.
 - 2) Instruments: Located on the control and monitoring panel and viewable during operation.
 - a) Engine lubricating-oil pressure gage.
 - b) Engine-coolant temperature gage.
 - c) DC voltmeter (alternator battery charging).
 - d) Running-time meter.
 - e) AC voltmeter, [for each phase] [connected to a phase selector switch].
 - f) AC ammeter, [for each phase] [connected to a phase selector switch].
 - g) AC frequency meter.
 - h) Generator-voltage adjusting rheostat.

- 3) Controls and Protective Devices: Controls, shutdown devices, and common alarm indication, including the following:
 - a) Cranking control equipment.
 - b) Run-Off-Auto switch.
 - c) Control switch not in automatic position alarm.
 - d) Overcrank alarm.
 - e) Overcrank shutdown device.
 - f) Low-water temperature alarm.
 - g) High engine temperature prealarm.
 - h) High engine temperature.
 - i) High engine temperature shutdown device.
 - j) Overspeed alarm.
 - k) Overspeed shutdown device.
 - l) Low fuel main tank.
 - i. Low-fuel-level alarm shall be initiated when the level falls below that required for operation for duration required for the indicated EPSS class.
 - m) Coolant low-level alarm.
 - n) EPS load indicator.
 - o) Battery high-voltage alarm.
 - p) Low cranking voltage alarm.
 - q) Battery-charger malfunction alarm.
 - r) Battery low-voltage alarm.
 - s) Lamp test.
 - t) Contacts for local and remote common alarm.
 - u) Low-starting air pressure alarm.
 - v) Low-starting hydraulic pressure alarm.
 - w) Remote manual stop shutdown device.
 - x) Air shutdown damper alarm when used.
 - y) Air shutdown damper shutdown device when used.
 - z) Generator overcurrent-protective-device not-closed alarm.
 - aa) Hours of operation.
 - bb) Engine generator metering, including voltage, current, hertz, kilowatt, kilovolt ampere, and power factor.
- f. Engine Generator Metering: Comply with [Section 260913 "Electrical Power Monitoring and Control."] [Section 262713 "Electricity Metering."] [Section 260913 "Electrical Power Monitoring and Control" and Section 262713 "Electricity Metering."]
- g. Remote Alarm Annunciator: An LED indicator light labeled with proper alarm conditions shall identify each alarm event, and a common audible signal shall sound for each alarm condition. Silencing switch in face of panel shall silence signal without altering visual indication. Connect so that after an alarm is silenced, clearing of initiating condition will reactivate alarm until silencing switch is reset. Cabinet and faceplate are surface- or flush-mounting type to suit mounting conditions indicated.
 - 1) Overcrank alarm.
 - 2) Low water-temperature alarm.
 - 3) High engine temperature prealarm.
 - 4) High engine temperature alarm.
 - 5) Low lube oil pressure alarm.
 - 6) Overspeed alarm.

- 7) Low fuel main tank alarm.
 - 8) Low coolant level alarm.
 - 9) Low cranking voltage alarm.
 - 10) Contacts for local and remote common alarm.
 - 11) Audible-alarm silencing switch.
 - 12) Air shutdown damper when used.
 - 13) Run-Off-Auto switch.
 - 14) Control switch not in automatic position alarm.
 - 15) Low-cranking voltage alarm.
- h. Supporting Items: Include sensors, transducers, terminals, relays, and other devices and include wiring required to support specified items. Locate sensors and other supporting items on engine or generator unless otherwise indicated.
- i. Remote Emergency-Stop Switch: Flush; wall mounted unless otherwise indicated; and labeled. Push button shall be protected from accidental operation.

2.8 GENERATOR OVERCURRENT AND FAULT PROTECTION

- a. Overcurrent protective devices shall be coordinated to optimize selective tripping when a short circuit occurs.
- 1) Overcurrent protective devices for the entire EPSS shall be coordinated to optimize selective tripping when a short circuit occurs. Coordination of protective devices shall consider both utility and EPSS as the voltage source.
 - 2) Overcurrent protective devices for the EPSS shall be accessible only to authorized personnel.
- b. Generator Overcurrent Protective Device:
- 1) Insulated-case circuit breaker, electronic-trip type; 100 percent rated; complying with UL 489:
 - a) Tripping Characteristics: Adjustable long-time and short-time delay and instantaneous.
 - b) Trip Settings: Selected to coordinate with generator thermal damage curve.
 - c) Shunt Trip: Connected to trip breaker when engine generator is shut down by other protective devices.
 - d) Mounting: Adjacent to, or integrated with, control and monitoring panel.
- c. Generator Protector: Microprocessor-based unit shall continuously monitor current level in each phase of generator output, integrate generator heating effect over time, and predict when thermal damage of alternator will occur. When signaled by generator protector or other engine generator protective devices, a shunt-trip device in the generator disconnect switch shall open the switch to disconnect the generator from load circuits. Protector performs the following functions:
- 1) Initiates a generator overload alarm when generator has operated at an overload equivalent to 110 percent of full-rated load for 60 seconds. Indication for this alarm is integrated with other engine generator malfunction alarms. Contacts shall be available for load shed functions.
 - 2) Under single- or three-phase fault conditions, regulates generator to 300 percent of rated full-load current for up to 10 seconds.
 - 3) As overcurrent heating effect on the generator approaches the thermal damage point of the unit, protector switches the excitation system off, opens the generator disconnect device, and shuts down the engine generator.
 - 4) Senses clearing of a fault by other overcurrent devices and controls recovery of rated voltage to avoid overshoot.

2.9 GENERATOR, EXCITER, AND VOLTAGE REGULATOR

- a. Comply with NEMA MG 1.
- b. Drive: Generator shaft shall be directly connected to engine shaft. Exciter shall be rotated integrally with generator rotor.
- c. Electrical Insulation: Class H.
- d. Stator-Winding Leads: Brought out to terminal box to permit future reconnection for other voltages if required. Provide 12-lead alternator.
- e. Range: Provide **extended** range of output voltage by adjusting the excitation level.
- f. Construction shall prevent mechanical, electrical, and thermal damage due to vibration, overspeed up to 125 percent of rating, and heat during operation at 110 percent of rated capacity.
- g. Enclosure: Dripproof.
- h. Instrument Transformers: Mounted within generator enclosure.
- i. Voltage Regulator: Solid-state type, separate from exciter, providing performance as specified and as required by NFPA 11.
 - 1) Adjusting Rheostat on Control and Monitoring Panel: Provide plus or minus 5 percent adjustment of output-voltage operating band.
 - 2) Maintain voltage within 15 percent on one step, full load.
 - 3) Provide anti-hunt provision to stabilize voltage.
 - 4) Maintain frequency within 5 percent and stabilize at rated frequency within 5 seconds.
- j. Strip Heater: Thermostatically controlled unit arranged to maintain stator windings above dew point.
- k. Windings: Two-thirds pitch stator winding and fully linked amortisseur winding.
- l. Subtransient Reactance: 12 percent, maximum.

2.10 OUTDOOR ENGINE GENERATOR ENCLOSURE

- a. Description:
 - 1) Vandal-resistant, sound-attenuating, weatherproof steel housing; wind resistant up to 100 mph. Multiple panels shall be lockable and provide adequate access to components requiring maintenance. Panels shall be removable by one person without tools. Instruments and control shall be mounted within enclosure.
 - a) Sound Attenuation Level: 1
- b. Structural Design and Anchorage: Comply with ASCE/SEI 7 for wind loads up to 100 mph.
- c. Space Heater: Thermostatically controlled and sized to prevent condensation.
- d. Lighting: Provide weather-resistant LED lighting with 30 fc average maintained.
- e. Thermal Insulation: Manufacturer's standard materials and thickness selected in coordination with space heater to maintain winter interior temperature within operating limits required by engine generator components.
- f. Muffler Location: Within enclosure.
- g. Engine-Cooling Airflow through Enclosure: Maintain temperature rise of system components within required limits when unit operates at 110 percent of rated load for two hours with ambient temperature at top of range specified in system service conditions.

2.11 VIBRATION ISOLATION DEVICES

- a. Elastomeric Isolator Pads: Oil- and water-resistant elastomer or natural rubber, arranged in single or multiple layers, molded with a nonslip pattern and galvanized-steel baseplates of sufficient stiffness for uniform loading over pad area, and factory cut to sizes that match requirements of supported equipment.
- b. Restrained Spring Isolators: Freestanding, steel, open-spring isolators with seismic restraint.
 - 1) Housing: Steel with resilient vertical-limit stops to prevent spring extension due to wind loads or if weight is removed; factory-drilled baseplate bonded to 1/4-inch-thick, elastomeric isolator pad attached to baseplate underside; and adjustable equipment-mounting and -leveling bolt that acts as blocking during installation.
 - 2) Outside Spring Diameter: Not less than 80 percent of compressed height of the spring at rated load.
 - 3) Minimum Additional Travel: 50 percent of required deflection at rated load.
 - 4) Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 - 5) Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 - 6) Minimum Deflection: 1 inch.

2.12 FINISHES

- a. Indoor and Outdoor Enclosures and Components: Manufacturer's standard finish over corrosion-resistant pretreatment and compatible primer.

2.13 SOURCE QUALITY CONTROL

- a. Prototype Testing: Factory test engine generator using same engine model, constructed of identical or equivalent components and equipped with identical or equivalent accessories.
 - 1) Tests: Comply with IEEE 115[and with NFPA 110, Level 1 Energy Converters].
- b. Project-Specific Equipment Tests: Before shipment, factory test engine generator and other system components and accessories manufactured specifically for this Project. Perform tests at rated load and power factor. Include the following tests:
 - 1) Test components and accessories furnished with installed unit that are not identical to those on tested prototype to demonstrate compatibility and reliability.
 - 2) Test generator, exciter, and voltage regulator as a unit.
 - 3) Full load run.
 - 4) Maximum power.
 - 5) Voltage regulation.
 - 6) Transient and steady-state governing.
 - 7) Single-step load pickup.
 - 8) Safety shutdown.
 - 9) Report factory test results within 10 days of completion of test.

PART 3 - EXECUTION

3.1 EXAMINATION

- a. Examine areas, equipment bases, and conditions, with Installer present, for compliance with requirements for installation and other conditions affecting packaged engine generator performance.
- b. Examine roughing-in for piping systems and electrical connections. Verify actual locations of connections before packaged engine generator installation.
- c. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- a. Comply with NECA 1 and NECA 404.
- b. Comply with packaged engine generator manufacturers' written installation and alignment instructions and with NFPA 110.
- c. Equipment Mounting:
 - 1) Install packaged engine generators on cast-in-place concrete equipment bases. Comply with requirements for equipment bases and foundations specified in Section 033000 "Cast-in-Place Concrete."
 - 2) Coordinate size and location of concrete bases for packaged engine generators. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified with concrete.
 - 3) Install packaged engine generator with elastomeric isolator pads having a minimum deflection of 1 inch on 4-inch- high concrete base. Secure enclosure to anchor bolts installed in concrete bases.
- d. Install packaged engine generator to provide access, without removing connections or accessories, for periodic maintenance.
- e. Install electrical devices furnished by equipment manufacturers but not specified to be factory mounted.

3.3 IDENTIFICATION

- a. Identify system components according to Section 230553 "Identification for HVAC Piping and Equipment" and Section 260553 "Identification for Electrical Systems."

3.4 FIELD QUALITY CONTROL

- a. Testing Agency:
 - 1) Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- b. Tests and Inspections:
 - 1) Perform tests recommended by manufacturer and each visual and mechanical inspection and electrical and mechanical test listed in first two subparagraphs below, as specified in NETA ATS. Certify compliance with test parameters.
 - a) Visual and Mechanical Inspection:
 - ii. Compare equipment nameplate data with Drawings and the Specifications.
 - iii. Inspect physical and mechanical condition.

- iv. Inspect anchorage, alignment, and grounding.
- v. Verify that the unit is clean.
- b) Electrical and Mechanical Tests:
 - vi. Perform insulation-resistance tests according to IEEE 43. Machines 200 hp or Less: Test duration shall be one minute. Calculate the dielectric-absorption ratio.
 - vii. Test protective relay devices.
 - viii. Verify phase rotation, phasing, and synchronized operation as required by the application.
 - ix. Functionally test engine shutdown for low oil pressure, overtemperature, overspeed, and other protection features as applicable.
 - x. Verify correct functioning of the governor and regulator.
- 2) NFPA 110 Acceptance Tests: Perform tests required by NFPA 110 that are additional to those specified here, including, but not limited to, single-step full-load pickup test.
- 3) Battery Tests: Equalize charging of battery cells according to manufacturer's written instructions. Record individual cell voltages.
 - a) Measure charging voltage and voltages between available battery terminals for full-charging and float-charging conditions. Check electrolyte level and specific gravity under both conditions.
 - b) Test for contact integrity of all connectors. Perform an integrity load test and a capacity load test for the battery.
 - c) Verify acceptance of charge for each element of the battery after discharge.
 - d) Verify that measurements are within manufacturer's specifications.
- 4) Battery-Charger Tests: Verify specified rates of charge for both equalizing and float-charging conditions.
- 5) System Integrity Tests: Methodically verify proper installation, connection, and integrity of each element of engine generator system before and during system operation. Check for air, exhaust, and fluid leaks.
- 6) Voltage and Frequency Transient Stability Tests: Use recording oscilloscope to measure voltage and frequency transients for 50 and 100 percent step-load increases and decreases, and verify that performance is as specified.
- 7) Harmonic-Content Tests: Measure harmonic content of output voltage at 25 and 100 percent of rated linear load. Verify that harmonic content is within specified limits.
- 8) Noise Level Tests: Measure A-weighted level of noise emanating from engine generator installation, including engine exhaust and cooling-air intake and discharge, at four locations 25 feet from edge of the generator enclosure and compare measured levels with required values.
- c. Coordinate tests with tests for transfer switches and run them concurrently.
- d. Test instruments shall have been calibrated within the past 12 months, traceable to NIST Calibration Services, and adequate for making positive observation of test results. Make calibration records available for examination on request.
- e. Leak Test: After installation, charge exhaust, coolant, and fuel systems and test for leaks. Repair leaks and retest until no leaks exist.
- f. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation for generator and associated equipment.
- g. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- h. Remove and replace malfunctioning units and retest as specified above.

- i. Retest: Correct deficiencies identified by tests and observations, and retest until specified requirements are met.
- j. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation resistances, time delays, and other values and observations. Attach a label or tag to each tested component indicating satisfactory completion of tests.
- k. Infrared Scanning: After Substantial Completion, but not more than 60 days after final acceptance, perform an infrared scan of each power wiring termination and each bus connection while running with maximum load. Remove all access panels so terminations and connections are accessible to portable scanner.
 - 1) Follow-up Infrared Scanning: Perform an additional follow-up infrared scan 11 months after date of Substantial Completion.
 - 2) Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - 3) Record of Infrared Scanning: Prepare a certified report that identifies terminations and connections checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5 MAINTENANCE SERVICE

- a. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by skilled employees of manufacturer's authorized service representative. Include quarterly preventive maintenance and exercising to check for proper starting, load transfer, and running under load. Include routine preventive maintenance as recommended by manufacturer and adjusting as required for proper operation. Parts shall be manufacturer's authorized replacement parts and supplies.

3.6 DEMONSTRATION

- a. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain packaged engine generators.

END OF SECTION 26 32 14

SECTION 263600 - TRANSFER SWITCHES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Contactor-type automatic transfer switches.
 - 2. Molded-case-type automatic transfer switches.
 - 3. Transfer switch accessories.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for transfer switches.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and accessories.
- B. Shop Drawings:
 - 1. Include plans, elevations, sections, details showing minimum clearances, conductor entry provisions, gutter space, and installed features and devices.
 - 2. Include material lists for each switch specified.
 - 3. Single-Line Diagram: Show connections between transfer switch, [bypass/isolation switch,]power sources, and load; and show interlocking provisions for each combined transfer switch and bypass/isolation switch.
 - 4. Riser Diagram: Show interconnection wiring between transfer switches, bypass/isolation switches, annunciators, and control panels.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Seismic Qualification Data: Certificates, for transfer switches, accessories, and components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.

2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For each type of product to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

- a. Features and operating sequences, both automatic and manual.
- b. List of all factory settings of relays; provide relay-setting and calibration instructions, including software, where applicable.

1.6 QUALITY ASSURANCE

A. Testing Agency Qualifications:

1. Member company of NETA.

- a. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.

1.7 FIELD CONDITIONS

A. Interruption of Existing Electrical Service: Do not interrupt electrical service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electrical service:

1. Notify Owner no fewer than two days in advance of proposed interruption of electrical service.
2. Do not proceed with interruption of electrical service without Owner's written permission.

1.8 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace components of transfer switch or transfer switch components that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NEMA ICS 1.
- C. Comply with NFPA 99.
- D. Comply with NFPA 110.
- E. Comply with UL 1008 unless requirements of these Specifications are stricter.
- F. Indicated Current Ratings: Apply as defined in UL 1008 for continuous loading and total system transfer, including tungsten filament lamp loads not exceeding 30 percent of switch ampere rating, unless otherwise indicated.
- G. Tested Fault-Current Closing and Short-Circuit Ratings: Adequate for duty imposed by protective devices at installation locations in Project under the fault conditions indicated, based on testing according to UL 1008.
 - 1. Where transfer switch includes internal fault-current protection, rating of switch and trip unit combination shall exceed indicated fault-current value at installation location.
 - 2. Short-time withstand capability for three cycles.
- H. Repetitive Accuracy of Solid-State Controls: All settings shall be plus or minus 2 percent or better over an operating temperature range of minus 20 to plus 70 deg C.
- I. Resistance to Damage by Voltage Transients: Components shall meet or exceed voltage-surge withstand capability requirements when tested according to IEEE C62.62. Components shall meet or exceed voltage-impulse withstand test of NEMA ICS 1.
- J. Electrical Operation: Accomplish by a nonfused, momentarily energized solenoid or electric-motor-operated mechanism. Switches for emergency or standby purposes shall be mechanically and electrically interlocked in both directions to prevent simultaneous connection to both power sources unless closed transition.
- K. Service-Rated Transfer Switch:
 - 1. Comply with UL 869A and UL 489.
 - 2. Provide terminals for bonding the grounding electrode conductor to the grounded service conductor.
 - 3. In systems with a neutral, the bonding connection shall be on the neutral bus.
 - 4. Provide removable link for temporary separation of the service and load grounded conductors.
 - 5. Surge Protective Device: Service rated.
 - 6. Ground-Fault Protection: Comply with UL 1008 for normal bus.
 - 7. Service Disconnecting Means: Externally operated, manual mechanically actuated.

- L. Neutral Switching: Where four-pole switches are indicated, provide neutral pole switched simultaneously with phase poles.
- M. Neutral Terminal: Solid and fully rated unless otherwise indicated.
- N. Oversize Neutral: Ampacity and switch rating of neutral path through units indicated for oversize neutral shall be double the nominal rating of circuit in which switch is installed.
- O. Heater: Equip switches exposed to outdoor temperatures and humidity, and other units indicated, with an internal heater. Provide thermostat within enclosure to control heater.
- P. Battery Charger: For generator starting batteries.
 - 1. Float type, rated 2 A.
 - 2. Ammeter to display charging current.
 - 3. Fused ac inputs and dc outputs.
- Q. Annunciation, Control, and Programming Interface Components: Devices at transfer switches for communicating with remote programming devices, annunciators, or annunciator and control panels shall have communication capability matched with remote device.
- R. Factory Wiring: Train and bundle factory wiring and label, consistent with Shop Drawings, by color-code or by numbered or lettered wire and cable with printed markers at terminations. Color-coding and wire and cable markers are specified in Section 260553 "Identification for Electrical Systems."
 - 1. Designated Terminals: Pressure type, suitable for types and sizes of field wiring indicated.
 - 2. Power-Terminal Arrangement and Field-Wiring Space: Suitable for top, side, or bottom entrance of feeder conductors as indicated.
 - 3. Control Wiring: Equipped with lugs suitable for connection to terminal strips.
 - 4. Accessible via front access.
- S. Enclosures: General-purpose NEMA 250, Type 1, complying with NEMA ICS 6 and UL 508, unless otherwise indicated.

2.2 CONTACTOR-TYPE AUTOMATIC TRANSFER SWITCHES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. ABB, Electrification Business.
 - 2. ASCO Power Technologies.
 - 3. Caterpillar, Inc.; Electric Power Division.
 - 4. Cummins Power Generation.
 - 5. Eaton.
 - 6. Generac.
 - 7. Hubbell Utility Solutions; Hubbell Incorporated.
 - 8. Kohler Power Systems.
 - 9. Rolls-Royce Solutions America Inc.
 - 10. Russelectric, Inc.

11. Vertiv; Vertiv Holdings Co.
- B. Comply with Level 1 equipment according to NFPA 110.
 - C. Switch Characteristics: Designed for continuous-duty repetitive transfer of full-rated current between active power sources.
 - 1.Limitation: Switches using molded-case switches or circuit breakers or insulated-case circuit-breaker components are unacceptable.
 - 2.Switch Action: Double throw; mechanically held in both directions.
 - 3.Contacts: Silver composition or silver alloy for load-current switching. Contactor-style automatic transfer-switch units, rated 600 A and higher, shall have separate arcing contacts.
 - 4.Conductor Connectors: Suitable for use with conductor material and sizes.
 - 5.Material: Hard-drawn copper, 98 percent conductivity.
 - 6.Main and Neutral Lugs: Compression type.
 - 7.Ground Lugs and Bus-Configured Terminators: Compression type.
 - 8.Ground bar.
 - 9.Connectors shall be marked for conductor size and type according to UL 1008.
 - D. Automatic Open-Transition Transfer Switches: Interlocked to prevent the load from being closed on both sources at the same time.
 - 1.Sources shall be mechanically and electrically interlocked to prevent closing both sources on the load at the same time.
 - E. Digital Communication Interface: Matched to capability of remote annunciator or annunciator and control panel.
 - F. Automatic Transfer-Switch Controller Features:
 - 1.Controller operates through a period of loss of control power.
 - 2.Undervoltage Sensing for Each Phase of Normal and Alternate Source: Sense low phase-to-ground voltage on each phase. Pickup voltage shall be adjustable from 85 to 100 percent of nominal, and dropout voltage shall be adjustable from 75 to 98 percent of pickup value. Factory set for pickup at 90 percent and dropout at 85 percent.
 - 3.Voltage/Frequency Lockout Relay: Prevent premature transfer to generator. Pickup voltage shall be adjustable from 85 to 100 percent of nominal. Factory set for pickup at 90 percent. Pickup frequency shall be adjustable from 90 to 100 percent of nominal. Factory set for pickup at 95 percent.
 - 4.Time Delay for Retransfer to Normal Source: Adjustable from zero to 30 minutes, and factory set for 10 minutes. Override shall automatically defeat delay on loss of voltage or sustained undervoltage of emergency source, provided normal supply has been restored.
 - 5.Test Switch: Simulate normal-source failure.
 - 6.Switch-Position Pilot Lights: Indicate source to which load is connected.
 - 7.Source-Available Indicating Lights: Supervise sources via transfer-switch normal- and emergency-source sensing circuits.
 - a. Normal Power Supervision: Green light with nameplate engraved "Normal Source Available."
 - b. Emergency Power Supervision: Red light with nameplate engraved "Emergency Source Available."

8. Unassigned Auxiliary Contacts: Two normally open, single-pole, double-throw contacts for each switch position, rated 10 A at 240-V ac.
 9. Transfer Override Switch: Overrides automatic retransfer control so transfer switch will remain connected to emergency power source regardless of condition of normal source. Pilot light indicates override status.
 10. Engine Starting Contacts: One isolated and normally closed, and one isolated and normally open; rated 10 A at 32-V dc minimum.
 11. Engine Shutdown Contacts:
 - a. Instantaneous; shall initiate shutdown sequence at remote engine-generator controls after retransfer of load to normal source.
 - b. Time delay adjustable from zero to five minutes, and factory set for five minutes. Contacts shall initiate shutdown at remote engine-generator controls after retransfer of load to normal source.
 12. Engine-Generator Exerciser: Solid-state, programmable-time switch starts engine generator and transfers load to it from normal source for a preset time, then retransfers and shuts down engine after a preset cool-down period. Initiates exercise cycle at preset intervals adjustable from 7 to 30 days. Running periods shall be adjustable from 10 to 30 minutes. Factory settings shall be for 7-day exercise cycle, 20-minute running period, and 5-minute cool-down period. Exerciser features include the following:
 - a. Exerciser Transfer Selector Switch: Permits selection of exercise with and without load transfer.
 - b. Push-button programming control with digital display of settings.
 - c. Integral battery operation of time switch when normal control power is unavailable.
- G. Large-Motor-Load Power Transfer:
1. In-Phase Monitor: Factory-wired, internal relay controls transfer so contacts close only when the two sources are synchronized in phase and frequency. Relay shall compare phase relationship and frequency difference between normal and emergency sources and initiate transfer when both sources are within 15 electrical degrees, and only if transfer can be completed within 60 electrical degrees. Transfer shall be initiated only if both sources are within 2 Hz of nominal frequency and 70 percent or more of nominal voltage.
 2. Motor Disconnect and Timing Relay Controls: Designated starters in loss of power scenario shall disconnect motors before transfer and reconnect them selectively at an adjustable time interval after transfer. Control connection to motor starters shall be through wiring external to automatic transfer switch. Provide adjustable time delay between 1 and 60 seconds for reconnecting individual motor loads. Provide relay contacts rated for motor-control circuit inrush and for actual seal currents to be encountered.
 3. Programmed Neutral Switch Position: Switch operator with programmed neutral position arranged to provide a midpoint between the two working switch positions, with an intentional, time-controlled pause at midpoint during transfer. Adjustable pause from 0.5 to 30 seconds minimum, and factory set for 0.5 second unless otherwise indicated. Time delay occurs for both transfer directions. Disable pause unless both sources are live.

2.3 TRANSFER SWITCH ACCESSORIES

- A. Remote Annunciator System:

1. Source Limitations: Same manufacturer as transfer switch in which installed.
2. Functional Description: Remote annunciator panel shall annunciate conditions for indicated transfer switches.
3. Annunciation panel display shall include the following indicators:
 - a. Sources available, as defined by actual pickup and dropout settings of transfer-switch controls.
 - b. Switch position.
 - c. Switch in test mode.
 - d. Failure of communication link.
4. Annunciator Panel: LED-lamp type with audible signal and silencing switch.
 - a. Indicating Lights: Grouped for each transfer switch monitored.
 - b. Label each group, indicating transfer switch it monitors, location of switch, and identity of load it serves.
 - c. Mounting: Flush, modular, steel cabinet unless otherwise indicated.
 - d. Lamp Test: Push-to-test or lamp-test switch on front panel.

B. Remote Annunciator and Control System:

1. Source Limitations: Same manufacturer as transfer switch in which installed.
2. Include the following functions for indicated transfer switches:
 - a. Indication of sources available, as defined by actual pickup and dropout settings of transfer-switch controls.
 - b. Indication of switch position.
 - c. Indication of switch in test mode.
 - d. Indication of failure of digital communication link.
 - e. Key-switch or user-code access to control functions of panel.
 - f. Control of switch-test initiation.
 - g. Control of switch operation in either direction.
 - h. Control of time-delay bypass for transfer to normal source.
3. Malfunction of annunciator, annunciation and control panel, or communication link shall not affect functions of automatic transfer switch. In the event of failure of communication link, automatic transfer switch automatically shall revert to standalone, self-contained operation. Automatic transfer-switch sensing, controlling, or operating function shall not depend on remote panel for proper operation.
4. Remote Annunciation and Control Panel: Solid-state components. Include the following features:
 - a. Controls and indicating lights grouped together for each transfer switch.
 - b. Label each indicating light control group. Indicate transfer switch it controls, location of switch, and load it serves.
 - c. Digital Communication Capability: Matched to that of transfer switches supervised.
 - d. Mounting: Flush, modular, steel cabinet unless otherwise indicated.

2.4 SOURCE QUALITY CONTROL

- A. Factory Tests: Test and inspect components, assembled switches, and associated equipment according to UL 1008. Ensure proper operation. Check transfer time and voltage, frequency, and time-delay settings for compliance with specified requirements. Perform dielectric strength test complying with NEMA ICS 1.
- B. Prepare test and inspection reports.
 - 1. For each of the tests required by UL 1008, performed on representative devices, for emergency systems. Include results of test for the following conditions:
 - a. Overvoltage.
 - b. Undervoltage.
 - c. Loss of supply voltage.
 - d. Reduction of supply voltage.
 - e. Alternative supply voltage or frequency is at minimum acceptable values.
 - f. Temperature rise.
 - g. Dielectric voltage-withstand; before and after short-circuit test.
 - h. Overload.
 - i. Contact opening.
 - j. Endurance.
 - k. Short circuit.
 - l. Short-time current capability.
 - m. Receptacle withstand capability.
 - n. Insulating base and supports damage.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Floor-Mounting Switch: Anchor to floor by bolting.
 - 1. Install transfer switches on cast-in-place concrete equipment base(s). Comply with requirements for equipment bases and foundations specified in Section 033000 "Cast-in-Place Concrete."
 - 2. Comply with requirements for seismic control devices specified in Section 260548.16 "Seismic Controls for Electrical Systems."
 - 3. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases.
 - 4. Provide workspace and clearances required by NFPA 70.
- B. Annunciator and Control Panel Mounting: Flush in wall unless otherwise indicated.
- C. Identify components according to Section 260553 "Identification for Electrical Systems."
- D. Set field-adjustable intervals and delays, relays, and engine exerciser clock.
- E. Comply with NECA 1.

3.2 CONNECTIONS

- A. Wiring to Remote Components: Match type and number of cables and conductors to generator sets, motor controls, control, and communication requirements of transfer switches as recommended by manufacturer. Increase raceway sizes at no additional cost to Owner if necessary to accommodate required wiring.
- B. Wiring Method: Install cables in raceways and cable trays except within electrical enclosures. Conceal raceway and cables except in unfinished spaces.
 - 1. Comply with requirements for raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
- C. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii.
- D. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."
- E. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- F. Connect twisted pair cable according to Section 260523 "Control-Voltage Electrical Power Cables."
- G. Route and brace conductors according to manufacturer's written instructions. and Section 260529 "Hangers and Supports for Electrical Systems." Do not obscure manufacturer's markings and labels.
- H. Brace and support equipment according to Section 260548.16 "Seismic Controls for Electrical Systems."
- I. Final connections to equipment shall be made with liquidtight, flexible metallic conduit no more than 18 inches in length.

3.3 FIELD QUALITY CONTROL

- A. Adminstrant for Tests and Inspections:
 - 1. Owner will engage qualified testing agency to administer and perform tests and inspections.
 - 2. Engage qualified testing agency to administer and perform tests and inspections.
 - 3. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.
 - 4. Administer and perform tests and inspections with assistance of factory-authorized service representative.
- B. Tests and Inspections:
 - 1. After installing equipment, test for compliance with requirements according to NETA ATS.
 - 2. Visual and Mechanical Inspection:

- a. Compare equipment nameplate data with Drawings and Specifications.
- b. Inspect physical and mechanical condition.
- c. Inspect anchorage, alignment, grounding, and required clearances.
- d. Verify that the unit is clean.
- e. Verify appropriate lubrication on moving current-carrying parts and on moving and sliding surfaces.
- f. Verify that manual transfer warnings are attached and visible.
- g. Verify tightness of all control connections.
- h. Inspect bolted electrical connections for high resistance using one of the following methods, or both:
 - 1) Use of low-resistance ohmmeter.
 - 2) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method according to manufacturer's published data.
- i. Perform manual transfer operation.
- j. Verify positive mechanical interlocking between normal and alternate sources.
- k. Perform visual and mechanical inspection of surge arresters.
- l. Inspect control power transformers.
 - 1) Inspect for physical damage, cracked insulation, broken leads, tightness of connections, defective wiring, and overall general condition.
 - 2) Verify that primary and secondary fuse or circuit-breaker ratings match Drawings.
 - 3) Verify correct functioning of drawout disconnecting contacts, grounding contacts, and interlocks.

3. Electrical Tests:

- a. Perform insulation-resistance tests on all control wiring with respect to ground.
- b. Perform a contact/pole-resistance test. Compare measured values with manufacturer's acceptable values.
- c. Verify settings and operation of control devices.
- d. Calibrate and set all relays and timers.
- e. Verify phase rotation, phasing, and synchronized operation.
- f. Perform automatic transfer tests.
- g. Verify correct operation and timing of the following functions:
 - 1) Normal source voltage-sensing and frequency-sensing relays.
 - 2) Engine start sequence.
 - 3) Time delay on transfer.
 - 4) Alternative source voltage-sensing and frequency-sensing relays.
 - 5) Automatic transfer operation.
 - 6) Interlocks and limit switch function.
 - 7) Time delay and retransfer on normal power restoration.
 - 8) Engine cool-down and shutdown feature.

4. Measure insulation resistance phase-to-phase and phase-to-ground with insulation-resistance tester. Include external annunciation and control circuits. Use test voltages and procedure recommended by manufacturer. Comply with manufacturer's specified minimum resistance.

- a. Check for electrical continuity of circuits and for short circuits.
 - b. Inspect for physical damage, proper installation and connection, and integrity of barriers, covers, and safety features.
 - c. Verify that manual transfer warnings are properly placed.
 - d. Perform manual transfer operation.
5. After energizing circuits, perform each electrical test for transfer switches stated in NETA ATS and demonstrate interlocking sequence and operational function for each switch at least three times.
- a. Simulate power failures of normal source to automatic transfer switches and retransfer from emergency source with normal source available.
 - b. Simulate loss of phase-to-ground voltage for each phase of normal source.
 - c. Verify time-delay settings.
 - d. Verify pickup and dropout voltages by data readout or inspection of control settings.
 - e. Test bypass/isolation unit functional modes and related automatic transfer-switch operations.
 - f. Perform contact-resistance test across main contacts and correct values exceeding 500 microhms and values for one pole deviating by more than 50 percent from other poles.
 - g. Verify proper sequence and correct timing of automatic engine starting, transfer time delay, retransfer time delay on restoration of normal power, and engine cool-down and shutdown.
6. Ground-Fault Tests: Coordinate with testing of ground-fault protective devices for power delivery from both sources.
- a. Verify grounding connections and locations and ratings of sensors.
- C. Coordinate tests with tests of generator and run them concurrently.
- D. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation and contact resistances and time delays. Attach a label or tag to each tested component indicating satisfactory completion of tests.
- E. Transfer switches will be considered defective if they do not pass tests and inspections.
- F. Remove and replace malfunctioning units and retest as specified above.
- G. Prepare test and inspection reports.
- H. Infrared Scanning: After Final Acceptance, but not more than 60 days after Final Acceptance, perform an infrared scan of each switch. Remove all access panels so joints and connections are accessible to portable scanner.
1. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 2. Record of Infrared Scanning: Prepare a certified report that identifies switches checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each switch 11 months after date of Final Acceptance.

3.4 DEMONSTRATION

- A. Train Owner's maintenance personnel to adjust, operate, and maintain transfer switches and related equipment.
- B. Training shall include testing ground-fault protective devices and instructions to determine when the ground-fault system shall be retested. Include instructions on where ground-fault sensors are located and how to avoid negating the ground-fault protection scheme during testing and circuit modifications.
- C. Coordinate this training with that for generator equipment.

END OF SECTION

SECTION 263610 – GENERATOR DOCKING STATION

PART 1 - GENERAL

1.1 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ETL/UL LISTED to 1008 Standards
- C. UL 50 LISTED

1.2 COORDINATION

- A. Coordinate layout and installation of Generator Docking Station, and components with equipment served and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

1.3 GUARANTEE/WARRANTY

- A. Manufacturer Warranty shall be provided for a minimum of 1 Year, after Final Acceptance.
- B. The equipment installed under this contract shall be left in proper working order.
- C. New materials and equipment shall be guaranteed against defects in composition, design or workmanship. Guarantee certificates shall be furnished.

PART 2 - PRODUCTS

2.1 DOCKING STATION

- A. Manufacturers: Subject to compliance with requirements, provide products by on of the following:
 - 1. Bases of Design: TRYSTAR Model No.: DBDS-1
 - 2. PSI Power & Controls.
 - 3. Powertron.

2.2 GENERAL REQUIREMENTS

- A. Enclosure
 - 1. NEMA 3R Rain-Tight Aluminum Enclosure
 - a. Pad-lockable front door shall include a hinged access plate at the bottom for entry of temporary cabling that prevents unauthorized tampering while in use.

- b. NEMA 3R Integrity shall be maintained while temporary cabling is connected during use.
 - c. Front and Side shall be accessible for maintenance.
 - d. Top, Side, and Bottom shall be accessible for permanent cabling.
 2. Powder coat
 - a. Paint after fabrication shall be Hammer tone Gray.
- B. Phase, Neutral, and Ground Busbar
 1. Material: Silver-plated Copper
 2. Equipment Ground Bus: bonded to box.
 3. Isolated Ground Bus: insulated from box.
 4. Ground Bus: 100% of phase size.
 5. Neutral Bus: Neutral bus rated 100 percent of phase bus.
- C. Temporary generator connectors shall be Camlok style mounted on gland plate.
 1. Camlok shall be 16 Series model and color coded according to system voltage requirements.
 2. Camlok connections shall be Bus Bar Style, Cabling or Double Set Screw is not acceptable.
 3. Camlok connection shall be protected against accidental contact while not in use.
- D. Permanent Connection shall be factory installed broad range set-screw mechanical type, located behind a physical barrier.
- E. Short Circuit & Withstand Rating
 1. Shall be minimum 22 KAIC unless otherwise indicated on drawings.
- F. Voltage & Amperage
 1. 208/120V, 3 Phase. Refer to drawings for amperage.
- G. Factory Installed Phase Rotation Monitor Device:
 1. Phase monitoring relay to be factory installed.
- H. Additional accessories shall be included in submittal drawing as follows:
 1. A: Two Wire Auto Start
 2. B: Battery Charger Receptacle 20A duplex, GFCI, 125V
 3. D: Block Heater Receptacle 30A, L5-30, 125V
 4. M: Listed Monitoring Device

PART 3 - PART 3 EXECUTION

3.1 EXAMINATION

- A. Examine elements and surfaces to receive Generator Docking Station for compliance with installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Surface, Flush or Base Mounted: Determined by Application
 - 1. Install anchor bolts to elevations required for proper attachment to Generator Docking Station.

3.3 IDENTIFICATION

- A. Comply with requirements in Division 26 Section "Identification for Electrical Systems."
- B. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
- C. Label each enclosure with engraved metal or laminated-plastic nameplate.

3.4 FIELD QUALITY CONTROL

- A. Third Party Tests and Inspections to include the following:
 - 1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
- B. Prepare test and inspection reports, including a certified report that identifies Generator Docking Station and that describes scanning results. Include notation.

END OF SECTION

SECTION 264313 - SURGE PROTECTION FOR LOW-VOLTAGE ELECTRICAL POWER
CIRCUITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes:

- 1.Type 1 surge protective devices.
- 2.Type 2 surge protective devices.
- 3.Enclosures.
- 4.Conductors and cables.

- B. Related Requirements:

- 1.Section 262416 "Panelboards" for integral SPDs installed by panelboard manufacturer.
- 2.Section 262726 "Wiring Devices" for integral SPDs installed by receptacle manufacturer.

1.3 DEFINITIONS

- A. Inominal: Nominal discharge current.
- B. MCOV: Maximum continuous operating voltage.
- C. Mode(s), also Modes of Protection: air of electrical connections where the VPR applies.
- D. MOV: Metal-oxide varistor; an electronic component with a significant non-ohmic current-voltage characteristic.
- E. NRTL: Nationally recognized testing laboratory.
- F. OCPD: Overcurrent protective device.
- G. SCCR: Short-circuit current rating.
- H. SPD: Surge protective device.
- I. Type 1 SPDs: Permanently connected SPDs intended for installation between the secondary of the service transformer and the line side of the service disconnect overcurrent device.

- J. Type 2 SPDs: Permanently connected SPDs intended for installation on the load side of the service disconnect overcurrent device, including SPDs located at the branch panel.
- K. Type 3 SPDs: Point of utilization SPDs.
- L. Type 4 SPDs: Component SPDs, including discrete components, as well as assemblies.
- M. Type 5 SPDs: Discrete component surge suppressors, such as MOVs that may be mounted on a printed wiring board, connected by its leads or provided within an enclosure with mounting means and wiring terminations.
- N. VPR: Voltage protection rating.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include electrical characteristics, specialties, and accessories for SPDs.
 - 2. NRTL certification of compliance with UL 1449.
 - a. Tested values for VPRs.
 - b. Inominal ratings.
 - c. MCOV, type designations.
 - d. OCPD requirements.
 - e. Manufacturer's model number.
 - f. System voltage.
 - g. Modes of protection.

1.5 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.
- B. Sample Warranty: For manufacturer's special warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For SPDs to include in maintenance manuals.

1.7 WARRANTY

- A. Manufacturer's Warranty: Manufacturer agrees to repair or replace SPDs that fail in materials or workmanship within five years from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 TYPE 1 SURGE PROTECTIVE DEVICES (SPDs)

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- 1.ABB, Electrification Business.
- 2.ALLTEC LLC.
- 3.Advanced Protection Technologies Inc. (APT).
- 4.Citel, Inc.
- 5.DITEK Surge Protection.
- 6.Eaton.
- 7.Intermatic, Inc.
- 8.Leviton Manufacturing Co., Inc.
- 9.Liebert; Vertiv Holdings Co.
10. Mersen USA.
11. SSI, an ILSCO Company.
12. Schneider Electric USA, Inc.
13. Siemens Industry, Inc., Energy Management Division.

B. Source Limitations: Obtain devices from single source from single manufacturer.

C. Standards:

- 1.Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 1449, Type 1.

D. Product Options:

- 1.Include integral disconnect switch.
- 2.Include internal thermal protection that disconnects the SPD before damaging internal suppressor components.
- 3.Include indicator light display for protection status.
- 4.Include audible alarm.
- 5.Include NEMA ICS 5, dry Form C contacts rated at 2 A and 24 V ac for remote monitoring of protection status.
- 6.Include surge counter.

E. Performance Criteria:

- 1.MCOV: Not less than 125 percent of nominal system voltage for 208Y/120 V and 120/240 V power systems, and not less than 115 percent of nominal system voltage for 480Y/277 V power systems.
- 2.Peak Surge Current Rating: Minimum single-pulse surge current withstand rating per phase must not be less than 200 kA. Peak surge current rating must be arithmetic sum of the ratings of individual MOVs in a given mode.
- 3.Protection modes and UL 1449 VPR for grounded wye circuits with 208Y/120 V, three-phase, four-wire circuits must not exceed the following:

- a. Line to Neutral: 700 V for 208Y/120 V.
 - b. Line to Line: 1200 V for 208Y/120 V.
4. Protection modes and UL 1449 VPR for 240/120 V, single-phase, three-wire circuits must not exceed the following:
- a. Line to Neutral: 700 V.
 - b. Line to Line: 1200 V.
5. SCCR: Not less than 200 kA.
6. Inominal Rating: 20 kA.

2.2 TYPE 2 SURGE PROTECTIVE DEVICES (SPDs)

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. ABB, Electrification Business.
 2. ALLTEC LLC.
 3. Advanced Protection Technologies Inc. (APT).
 4. Citel, Inc.
 5. Eaton.
 6. Intermatic, Inc.
 7. Leviton Manufacturing Co., Inc.
 8. Liebert; Vertiv Holdings Co.
 9. Mersen USA.
 10. SSI, an ILSCO Company.
 11. Schneider Electric USA, Inc.
 12. Siemens Industry, Inc., Energy Management Division.
- B. Source Limitations: Obtain devices from single source from single manufacturer.
- C. Standards:
1. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 1449, Type 2.
 2. Comply with UL 1283.
- D. Product Options:
1. Include LED indicator lights for power and protection status.
 2. Include internal thermal protection that disconnects the SPD before damaging internal suppressor components.
 3. Include NEMA ICS 5, dry Form C contacts rated at 2 A and 24 V ac for remote monitoring of protection status.
 4. Include surge counter.
- E. Performance Criteria:

- 1.MCOV: Not less than 125 percent of nominal system voltage for 208Y/120 V and 120/240 V power systems, and not less than 115 percent of nominal system voltage for 480Y/277 V power systems.
- 2.Peak Surge Current Rating: Minimum single-pulse surge current withstand rating per phase must not be less than 100 kA. Peak surge current rating must be arithmetic sum of the ratings of individual MOVs in a given mode.
- 3.Protection modes and UL 1449 VPR for grounded wye circuits with 208Y/120 V, three-phase, four-wire circuits must not exceed the following:
 - a. Line to Neutral: 700 V for 208Y/120 V.
 - b. Line to Ground: 700 V for 208Y/120 V.
 - c. Neutral to Ground: 700 V for 208Y/120 V.
 - d. Line to Line: 1200 V for 208Y/120 V.
- 4.Protection modes and UL 1449 VPR for 240/120 V, single-phase, three-wire circuits must not exceed the following:
 - a. Line to Neutral: 700 V.
 - b. Line to Ground: 700 V.
 - c. Neutral to Ground: 700 V.
 - d. Line to Line: 1200 V.
- 5.SCCR: Equal or exceed 100 kA.
- 6.Inominal Rating: 20 kA.

2.3 TYPE 3, TYPE 4, AND TYPE 5 SURGE PROTECTIVE DEVICES (SPDs)

- A. Type 3, Type 4, and Type 5 SPDs are not approved for field installation.

2.4 ENCLOSURES

- A. Indoor Enclosures: NEMA 250, Type 1.
- B. Outdoor Enclosures: NEMA 250, Type 3R.

2.5 CONDUCTORS AND CABLES

- A. Power Wiring: Same size as SPD leads, complying with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with NECA 1.

- B. Provide OCPD and disconnect for installation of SPD in accordance with UL 1449 and manufacturer's written instructions.
- C. Install leads between disconnects and SPDs short, straight, twisted, and in accordance with manufacturer's written instructions. Comply with wiring methods in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
 - 1. Do not splice and extend SPD leads unless specifically permitted by manufacturer.
 - 2. Do not exceed manufacturer's recommended lead length.
 - 3. Do not bond neutral and ground.
- D. Use crimped connectors and splices only. Wire nuts are unacceptable.

3.2 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections with the assistance of a factory-authorized service representative:
 - 1. Compare equipment nameplate data for compliance with Drawings and the Specifications.
 - 2. Inspect anchorage, alignment, grounding, and clearances.
 - 3. Verify that electrical wiring installation complies with manufacturer's written installation requirements.
- B. SPDs that do not pass tests and inspections will be considered defective.
- C. Prepare test and inspection reports.

3.3 STARTUP SERVICE

- A. Complete startup checks in accordance with manufacturer's written instructions.
- B. Do not perform insulation-resistance tests of the distribution wiring equipment with SPDs installed. Disconnect SPDs before conducting insulation-resistance tests; reconnect them immediately after the testing is over.
- C. Energize SPDs after power system has been energized, stabilized, and tested.

3.4 DEMONSTRATION

- A. Train Owner's maintenance personnel to operate and maintain SPDs.

END OF SECTION

SECTION 265119 - LED INTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Cylinder.
2. Downlight.
3. Linear industrial.
4. Strip light.
5. Suspended, linear.
6. Materials.
7. Luminaire support.

- B. Related Requirements:

1. Section 260923 "Lighting Control Devices" for automatic control of lighting, including time switches, photoelectric relays, occupancy sensors, and multipole lighting relays and contactors.

1.3 DEFINITIONS

- A. CCT: Correlated color temperature.
- B. CRI: Color Rendering Index.
- C. Fixture: See "Luminaire."
- D. IP: International Protection or Ingress Protection Rating.
- E. LED: Light-emitting diode.
- F. Lumen: Measured output of lamp and luminaire, or both.
- G. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1. Arrange in order of luminaire designation.
 2. Include data on features, accessories, and finishes.
 3. Include physical description and dimensions of luminaires.
 4. Include emergency lighting units, including batteries and chargers.
 5. Include life, output (lumens, CCT, and CRI), and energy-efficiency data.
 6. Photometric data and adjustment factors based on laboratory tests, complying with IES "Lighting Measurements Testing and Calculation Guides" for each luminaire type. The adjustment factors shall be for lamps and accessories identical to those indicated for the luminaire as applied in this Project.
 - a. Manufacturers' Certified Data: Photometric data certified by manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program for Energy Efficient Lighting Products.
 - b. Testing Agency Certified Data: For indicated luminaires, photometric data certified by a qualified independent testing agency. Photometric data for remaining luminaires shall be certified by manufacturer.
- B. Shop Drawings: For nonstandard or custom luminaires.
1. Include plans, elevations, sections, and mounting and attachment details.
 2. Include details of luminaire assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 3. Include diagrams for power, signal, and control wiring.
- C. Samples: For each luminaire and for each color and texture with standard factory-applied finish.
- D. Samples for Initial Selection: For each type of luminaire with custom factory-applied finishes.
1. Include Samples of luminaires and accessories involving color and finish selection.
- E. Samples for Verification: For each type of luminaire.
1. Include Samples of luminaires and accessories to verify finish selection.
- F. Product Schedule: For luminaires and lamps. [Use same designations indicated on Drawings.]

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
1. Luminaires.
 2. Suspended ceiling components.
 3. Partitions and millwork that penetrate the ceiling or extend to within 12 inches of the plane of the luminaires.
 4. Structural members to which equipment and luminaires will be attached.
 5. Initial access modules for acoustical tile, including size and locations.
 6. Items penetrating finished ceiling, including the following:

- a. Other luminaires.
- b. Air outlets and inlets.
- c. Speakers.
- d. Sprinklers.
- e. Access panels.
- f. Ceiling-mounted projectors.

7. Moldings.

- B. Qualification Data: For testing laboratory providing photometric data for luminaires.
- C. Seismic Qualification Data: For luminaires, accessories, and components, from manufacturer.
 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- D. Product Certificates: For each type of luminaire.
- E. Product Test Reports: For each type of luminaire, for tests performed by a qualified testing agency.
- F. Sample warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For luminaires and lighting systems to include in operation and maintenance manuals.
 1. Provide a list of all lamp types used on Project; use ANSI and manufacturers' codes.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 1. Lamps: Ten for every 100 of each type and rating installed. Furnish at least one of each type.
 2. Diffusers and Lenses: One for every 100 of each type and rating installed. Furnish at least one of each type.
 3. Globes and Guards: One for every 20 of each type and rating installed. Furnish at least one of each type.

1.8 QUALITY ASSURANCE

- A. Luminaire Photometric Data Testing Laboratory Qualifications:

1. Luminaire manufacturer's laboratory that is accredited under the NVLAP for Energy Efficient Lighting Products.
 2. Provided by an independent agency, with the experience and capability to conduct the testing indicated, that is an NRTL as defined by OSHA in 29 CFR 1910.7, accredited under the NVLAP for Energy Efficient Lighting Products, and complying with the applicable IES testing standards.
- B. Provide luminaires from a single manufacturer for each luminaire type.
- C. Each luminaire type shall be binned within a three-step MacAdam Ellipse to ensure color consistency among luminaires.
- D. Mockups: For interior luminaires in room or module mockups, complete with power and control connections.
1. Obtain Architect's approval of luminaires in mockups before starting installations.
 2. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Final Acceptance.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Protect finishes of exposed surfaces by applying a strippable, temporary protective covering before shipping.

1.10 WARRANTY

- A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within specified warranty period.
- B. Warranty Period: Five year(s) from date of Final Acceptance.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Seismic Performance:
1. Luminaires shall withstand the effects of earthquake motions determined in accordance with ASCE/SEI 7.
 2. Luminaires and lamps shall be labeled vibration and shock resistant.

3.The term "withstand" means "the luminaire will remain in place without separation of any parts when subjected to the seismic forces specified and the luminaire will be fully operational during and after the seismic event."

B. Ambient Temperature: 41 to 104 deg F.

1.Relative Humidity: Zero to 95 percent.

C. Altitude: Sea level to 1000 feet.

2.2 LUMINAIRE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Factory-Applied Labels: Comply with UL 1598. Include recommended lamps. Locate labels where they will be readily visible to service personnel, but not seen from normal viewing angles when lamps are in place.

1.Label shall include the following lamp characteristics:

- a. "USE ONLY" and include specific lamp type.
- b. Lamp diameter, shape, size, wattage, and coating.
- c. CCT and CRI.

C. Recessed luminaires shall comply with NEMA LE 4.

D. NRTL Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by an NRTL.

E. FM Global Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by FM Global.

F. California Title 24 compliant.

2.3 CYLINDER

A. Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.

B. Nominal Operating Voltage: 120 V ac.

C. Lamp:

- 1.Minimum 250 lm.
- 2.Minimum allowable efficacy of 80 lm/W.
- 3.CRI of minimum 80. CCT of 2700 K.
- 4.Rated lamp life of 35,000 hours to L70.
- 5.Dimmable from 100 percent to zero percent of maximum light output.
- 6.Internal driver.
- 7.User-Replaceable Lamps:

- a. Bulb shape complying with ANSI C78.79.
- b. Lamp base complying with ANSI C81.61.

8. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

D. Housings:

1. Extruded-aluminum housing and heat sink.
2. Powder-coated finish.

E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Components are designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

F. Diffusers and Globes:

1. Prismatic acrylic.
2. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
3. Glass: Annealed crystal glass unless otherwise indicated.
4. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

G. With integral mounting provisions.

H. Standards:

1. ENERGY STAR certified.
2. RoHS compliant.
3. UL Listing: Listed for damp location.

2.4 DOWNLIGHT

A. Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.

B. Nominal Operating Voltage: 120 V ac.

C. Lamp:

1. Minimum 250 lm.
2. Minimum allowable efficacy of 80 lm/W.
3. CRI of minimum 80. CCT of 2700 K.
4. Rated lamp life of 35,000 hours to L70.
5. Dimmable from 100 percent to zero percent of maximum light output.
6. Internal driver.
7. User-Replaceable Lamps:

- a. Bulb shape complying with ANSI C78.79.
- b. Lamp base complying with ANSI C81.61.

8. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

D. Housings:

1. Extruded-aluminum housing and heat sink.
2. Powder-coat finish.
3. Universal mounting bracket.
4. Integral junction box with conduit fittings.

E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

F. Diffusers and Globes:

1. Fixed lens.
2. Wide light distribution.
3. Prismatic acrylic.
4. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
5. Glass: Annealed crystal glass unless otherwise indicated.
6. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

G. Standards:

1. ENERGY STAR certified.
2. RoHS compliant.
3. UL Listing: Listed for damp location.
4. Recessed luminaires shall comply with NEMA LE 4.

2.5 STRIP LIGHT

A. Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.

B. Nominal Operating Voltage: 120 V ac.

C. Lamp:

1. Minimum 750 lm.
2. Minimum allowable efficacy of 80 lm/W.
3. CRI of minimum 80. CCT of 2700 K.
4. Rated lamp life of 35,000 hours to L70.
5. Dimmable from 100 percent to zero percent of maximum light output.
6. Internal driver.
7. User-Replaceable Lamps:
 - a. Bulb shape complying with ANSI C78.79.
 - b. Lamp base complying with ANSI C81.61.

8.Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

D. Housings:

- 1.Extruded-aluminum housing and heat sink.
- 2.Powder-coat finish.
- 3.With integral mounting provisions.

E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping of luminaire without use of tools. Components are designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

F. Diffusers and Globes:

- 1.Prismatic acrylic.
- 2.Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
- 3.Glass: Annealed crystal glass unless otherwise indicated.
- 4.Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

G. Standards:

- 1.ENERGY STAR certified.
- 2.RoHS compliant.
- 3.UL Listing: Listed for damp location.

2.6 SUSPENDED, LINEAR

A. Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.

B. Nominal Operating Voltage: 120 V ac.

C. Lamp:

- 1.Minimum 1,500 lm.
- 2.Minimum allowable efficacy of 85 lm/W.
- 3.CRI of minimum 80. CCT of 2700 K.
- 4.Rated lamp life of 35,000 hours to L70.
- 5.Dimmable from 100 percent to zero percent of maximum light output.
- 6.Internal driver.
- 7.User-Replaceable Lamps:
 - a. Bulb shape complying with ANSI C78.79.
 - b. Lamp base complying with.

8.Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

D. Housings:

- 1.Extruded-aluminum housing and heat sink.
 - 2.Powder-coat finish.
 - 3.With integral mounting provisions.
- E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Components are designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.
- F. Diffusers and Globes:
- 1.Prismatic acrylic.
 - 2.Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
 - 3.Glass: Annealed crystal glass unless otherwise indicated.
 - 4.Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.
- G. Standards:
- 1.ENERGY STAR certified.
 - 2.RoHS compliant.
 - 3.UL Listing: Listed for damp location.

2.7 MATERIALS

- A. Metal Parts:
- 1.Free of burrs and sharp corners and edges.
 - 2.Sheet metal components shall be steel unless otherwise indicated.
 - 3.Form and support to prevent warping and sagging.
- B. Steel:
- 1.ASTM A36/A36M for carbon structural steel.
 - 2.ASTM A568/A568M for sheet steel.
- C. Stainless Steel:
- 1.Manufacturer's standard grade.
 - 2.Manufacturer's standard type, ASTM A240/240M.
- D. Galvanized Steel: ASTM A653/A653M.
- E. Aluminum: ASTM B209.

2.8 METAL FINISHES

- A. Variations in finishes are unacceptable in the same piece. Variations in finishes of adjoining components are acceptable if they are within the range of approved Samples and if they can be and are assembled or installed to minimize contrast.

2.9 LUMINAIRE SUPPORT

- A. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for channel and angle iron supports and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch steel tubing with swivel ball fittings and ceiling canopy. Finish same as luminaire.
- C. Wires: ASTM A641/A641M, Class 3, soft temper, zinc-coated steel, 12 gage.
- D. Rod Hangers: 3/16-inch minimum diameter, cadmium-plated, threaded steel rod.
- E. Hook Hangers: Integrated assembly matched to luminaire, line voltage, and equipment with threaded attachment, cord, and locking-type plug.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for luminaire to verify actual locations of luminaire and electrical connections before luminaire installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 TEMPORARY LIGHTING

- A. If approved by the Architect, use selected permanent luminaires for temporary lighting. When construction is sufficiently complete, clean luminaires used for temporary lighting and install new lamps.

3.3 INSTALLATION

- A. Comply with NECA 1.
- B. Install luminaires level, plumb, and square with ceilings and walls unless otherwise indicated.
- C. Install lamps in each luminaire.

D. Supports:

1. Sized and rated for luminaire weight.
2. Able to maintain luminaire position after cleaning and relamping.
3. Provide support for luminaire without causing deflection of ceiling or wall.
4. Luminaire-mounting devices shall be capable of supporting a horizontal force of 100 percent of luminaire weight and a vertical force of 400 percent of luminaire weight.

E. Flush-Mounted Luminaires:

1. Secured to outlet box.
2. Attached to ceiling structural members at four points equally spaced around circumference of luminaire.
3. Trim ring flush with finished surface.

F. Wall-Mounted Luminaires:

1. Attached to structural members in walls.
2. Do not attach luminaires directly to gypsum board.

G. Suspended Luminaires:

1. Ceiling Mount:

- a. Two 5/32-inch- diameter aircraft cable supports adjustable to 10 feet in length.
- b. Pendant mount with 5/32-inch- diameter aircraft cable supports adjustable to 10 feet in length.
- c. Hook mount.

2. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
3. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.
4. Continuous Rows of Luminaires: Use tubing or stem for wiring at one point and tubing or rod for suspension for each unit length of luminaire chassis, including one at each end.
5. Do not use ceiling grid as support for pendant luminaires. Connect support wires or rods to building structure.

H. Ceiling-Grid-Mounted Luminaires:

1. Secure to any required outlet box.
2. Secure luminaire to the luminaire opening using approved fasteners in a minimum of four locations, spaced near corners of luminaire.
3. Use approved devices and support components to connect luminaire to ceiling grid and building structure in a minimum of four locations, spaced near corners of luminaire.

I. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for wiring connections.

3.4 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

3.5 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
 - 2. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.
- B. Luminaire will be considered defective if it does not pass operation tests and inspections.
- C. Prepare test and inspection reports.

3.6 ADJUSTING

- A. Occupancy Adjustments: When requested within 12 months of date of Final Acceptance, provide on-site assistance in adjusting the direction of aim of luminaires to suit occupied conditions. Make up to two visits to Project during other-than-normal hours for this purpose. Some of this work may be required during hours of darkness.
 - 1. During adjustment visits, inspect all luminaires. Replace lamps or luminaires that are defective.
 - 2. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.
 - 3. Adjust the aim of luminaires in the presence of the Architect.

END OF SECTION

SECTION 265213 - EMERGENCY AND EXIT LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Emergency lighting.
 - 2. Exit signs.
 - 3. Materials.
 - 4. Luminaire support components.

1.3 DEFINITIONS

- A. CCT: Correlated color temperature.
- B. CRI: Color Rendering Index.
- C. Emergency Lighting Unit: A lighting unit with internal or external emergency battery powered supply and the means for controlling and charging the battery and unit operation.
- D. Fixture: See "Luminaire" Paragraph.
- E. Lumen: Measured output of lamp and luminaire, or both.
- F. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of emergency lighting unit, exit sign, and emergency lighting support.
 - 1. Include data on features, accessories, and finishes.
 - 2. Include physical description of the unit and dimensions.
 - 3. Battery and charger for light units.
 - 4. Include life, output of luminaire (lumens, CCT, and CRI), and energy-efficiency data.
 - 5. Include photometric data and adjustment factors based on laboratory tests, complying with IES LM-45, for each luminaire type.

- a. Testing Agency Certified Data: For indicated luminaires and signs, photometric data certified by a qualified independent testing agency. Photometric data for remaining luminaires and signs shall be certified by manufacturer.
 - b. Manufacturers' Certified Data: Photometric data certified by manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program for Energy Efficient Lighting Products.
- B. Shop Drawings: For nonstandard or custom luminaires.
1. Include plans, elevations, sections, and mounting and attachment details.
 2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 3. Include diagrams for power, signal, and control wiring.
- C. Samples: For each product and for each color and texture specified.
- D. Samples for Initial Selection: For each type of luminaire with factory-applied finishes.
- E. Samples for Verification: For each type of luminaire.
1. Include Samples of luminaires and accessories to verify finish selection.
- F. Product Schedule:
1. For emergency lighting units. Use same designations indicated on Drawings.
 2. For exit signs. Use same designations indicated on Drawings.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
1. Luminaires.
 2. Suspended ceiling components.
 3. Partitions and millwork that penetrate the ceiling or extend to within 12 inches of the plane of the luminaires.
 4. Structural members to which equipment will be attached.
 5. Size and location of initial access modules for acoustical tile.
 6. Items penetrating finished ceiling including the following:
 - a. Other luminaires.
 - b. Air outlets and inlets.
 - c. Speakers.
 - d. Ceiling-mounted projectors.
 - e. Sprinklers.
 - f. Access panels.
 7. Moldings.

- B. Qualification Data: For testing laboratory providing photometric data for luminaires.
- C. Product Certificates: For each type of luminaire.
- D. Seismic Qualification Data: For luminaires, accessories, and components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
 - 4. Provide seismic qualification certificate for each piece of equipment.
- E. Product Test Reports: For each luminaire for tests performed by a qualified testing agency.
- F. Sample Warranty: For manufacturer's warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For luminaires and lighting systems to include in emergency, operation, and maintenance manuals.
 - 1. Provide a list of all lamp types used on Project; use ANSI and manufacturers' codes.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Lamps: 10 for every 100 of each type and rating installed. Furnish at least one of each type.
 - 2. Luminaire-mounted, emergency battery pack: One for every 20 emergency lighting units. Furnish at least one of each type.
 - 3. Diffusers and Lenses: One for every 100 of each type and rating installed. Furnish at least one of each type.
 - 4. Globes and Guards: One for every 20 of each type and rating installed. Furnish at least one of each type.

1.8 QUALITY ASSURANCE

- A. Luminaire Photometric Data Testing Laboratory Qualifications: Luminaire manufacturer's laboratory that is accredited under National Volunteer Laboratory Accreditation Program for Energy Efficient Lighting Products and complying with applicable IES testing standards.
- B. FM Global Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by FM Global.

- C. Mockups: For interior luminaires in room or module mockups, complete with power and control connections.
1. Obtain Architect's approval of luminaires and signs in mockups before starting installations.
 2. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Final Acceptance.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Protect finishes of exposed surfaces by applying a strippable, temporary protective covering before shipping.

1.10 WARRANTY

- A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within specified warranty period.
1. Warranty Period: Two year(s) from date of Final Acceptance.
- B. Special Warranty for Emergency Lighting Batteries: Manufacturer's standard form in which manufacturer of battery-powered emergency lighting unit agrees to repair or replace components of rechargeable batteries that fail in materials or workmanship within specified warranty period.
1. Warranty Period for Emergency Power Unit Batteries: Five years from date of Final Acceptance. Full warranty shall apply for the entire warranty period.
 2. Warranty Period for Self-Powered Exit Sign Batteries: Two years from date of Final Acceptance. Full warranty shall apply for the entire warranty period.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Luminaires shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
1. The term "withstand" means "the luminaire will remain in place without separation of any parts when subjected to the seismic forces specified and the luminaire will be fully operational during and after the seismic event."

2.2 GENERAL REQUIREMENTS FOR EMERGENCY LIGHTING

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NRTL Compliance: Fabricate and label emergency lighting units, exit signs, and batteries to comply with UL 924.
- C. Comply with NFPA 70 and NFPA 101.
- D. Comply with NEMA LE 4 for recessed luminaires.
- E. Comply with UL 1598 for fluorescent luminaires.
- F. Lamp Base: Comply with ANSI C81.61.
- G. Bulb Shape: Complying with ANSI C79.1.
- H. Internal Type Emergency Power Unit: Self-contained, modular, battery-inverter unit, factory mounted within luminaire body.
 - 1. Emergency Connection: Operate one lamp(s) continuously at an output of 1100 lumens each upon loss of normal power. Connect unswitched circuit to battery-inverter unit and switched circuit to luminaire ballast.
 - 2. Operation: Relay automatically turns lamp on when power-supply circuit voltage drops to 80 percent of nominal voltage or below. Lamp automatically disconnects from battery when voltage approaches deep-discharge level. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
 - 3. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
 - a. Ambient Temperature: Less than 0 deg F or exceeding 104 deg F, with an average value exceeding 95 deg F over a 24-hour period.
 - b. Ambient Storage Temperature: Not less than minus 4 deg F and not exceeding 140 deg F.
 - c. Humidity: More than 95 percent (condensing).
 - d. Altitude: Exceeding 3300 feet.
 - 4. Nightlight Connection: Operate lamp continuously at 40 percent of rated light output.
 - 5. Test Push-Button and Indicator Light: Visible and accessible without opening luminaire or entering ceiling space.
 - a. Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
 - b. Indicator Light: LED indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
 - 6. Battery: Sealed, maintenance-free, nickel-cadmium type.
 - 7. Charger: Fully automatic, solid-state, constant-current type with sealed power transfer relay.

8. Remote Test: Switch in handheld remote device aimed in direction of tested unit initiates coded infrared signal. Signal reception by factory-installed infrared receiver in tested unit triggers simulation of loss of its normal power supply, providing visual confirmation of either proper or failed emergency response.
 9. Integral Self-Test: Factory-installed electronic device automatically initiates code-required test of unit emergency operation at required intervals. Test failure is annunciated by an integral audible alarm and a flashing red LED.
- I. External Type: Self-contained, modular, battery-inverter unit, suitable for powering one or more lamps, remote mounted from luminaire.
1. Emergency Connection: Operate one LED lamp continuously. Connect unswitched circuit to battery-inverter unit and switched circuit to luminaire.
 2. Operation: Relay automatically turns lamp on when power-supply circuit voltage drops to 80 percent of nominal voltage or below. Lamp automatically disconnects from battery when voltage approaches deep-discharge level. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
 3. Nightlight Connection: Operate lamp in a remote luminaire continuously.
 4. Battery: Sealed, maintenance-free, nickel-cadmium type.
 5. Charger: Fully automatic, solid-state, constant-current type.
 6. Housing: NEMA 250, Type 1 enclosure listed for installation inside, on top of, or remote from luminaire. Remote assembly shall be located no less than half the distance recommended by the emergency power unit manufacturer, whichever is less.
 7. Test Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
 8. LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
 9. Remote Test: Switch in handheld remote device aimed in direction of tested unit initiates coded infrared signal. Signal reception by factory-installed infrared receiver in tested unit triggers simulation of loss of its normal power supply, providing visual confirmation of either proper or failed emergency response.
 10. Integral Self-Test: Factory-installed electronic device automatically initiates code-required test of unit emergency operation at required intervals. Test failure is annunciated by an integral audible alarm and a flashing red LED.

2.3 EMERGENCY LIGHTING

- A. General Requirements for Emergency Lighting Units: Self-contained units.
- B. Emergency Luminaires:
1. Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.
 2. Emergency Luminaires: as indicated on Interior Luminaire Schedule and Drawings, with the following additional features:
 - a. Operating at nominal voltage of 120 V ac.
 - b. Internal emergency power unit.
 - c. Rated for installation in damp locations, and for sealed and gasketed luminaires in wet locations.

d. UL 94 5VA flame rating.

C. Emergency Lighting Unit:

- 1.Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.
- 2.Emergency Lighting Unit: as indicated on Interior Luminaire Schedule.
- 3.Operating at nominal voltage of 120 V ac.
- 4.Wall with universal junction box adaptor.
- 5.UV stable thermoplastic housing, rated for damp locations.
- 6.Two LED lamp heads.
- 7.Internal emergency power unit.

2.4 EXIT SIGNS

A. General Requirements for Exit Signs: Comply with UL 924; for sign colors, visibility, luminance, and lettering size, comply with authorities having jurisdiction.

B. Internally Lighted Signs:

- 1.Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.
- 2.Operating at nominal voltage of 120 V ac.
- 3.Lamps for AC Operation:
 - a. Fluorescent, two for each luminaire; 20,000 hours of rated lamp life.
 - b. LEDs; 50,000 hours minimum rated lamp life.
- 4.Self-Powered Exit Signs (Battery Type): Internal emergency power unit.
- 5.Master/Remote Sign Configurations:
 - a. Master Unit: Comply with requirements above for self-powered exit signs, and provide additional capacity in LED power supply for power connection to remote unit.
 - b. Remote Unit: Comply with requirements above for self-powered exit signs, except omit power supply, battery, and test features. Arrange to receive full power requirements from master unit. Connect for testing concurrently with master unit as a unified system.

C. Self-Luminous Signs:

- 1.Manufacturers: Subject to compliance with requirements. Refer to lighting schedule.
- 2.Powered by tritium gas, with universal bracket for flush-ceiling, wall, or end mounting. Signs shall be guaranteed by manufacturer to maintain the minimum brightness requirements in UL 924 for 10 years.
- 3.Use strontium oxide aluminate compound to store ambient light and release the stored energy when the light is removed. Include universal bracket for flush-ceiling, wall, or end mounting.

2.5 MATERIALS

A. Metal Parts:

- 1.Free of burrs and sharp corners and edges.
- 2.Sheet metal components shall be steel unless otherwise indicated.
- 3.Form and support to prevent warping and sagging.

B. Doors, Frames, and Other Internal Access:

- 1.Smooth operating, free of light leakage under operating conditions.
- 2.Designed to permit relamping without use of tools.
- 3.Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

C. Diffusers and Globes:

- 1.Prismatic acrylic.
- 2.Glass: Annealed crystal glass unless otherwise indicated.
- 3.Acrylic: 100 percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
- 4.Lens Thickness: At least 0.125 inch minimum unless otherwise indicated.

D. Housings:

- 1.Extruded aluminum housing and heat sink.
- 2.Powder coat finish.

E. Conduit: Electrical metallic tubing, minimum 3/4 inch in diameter.

2.6 METAL FINISHES

- A. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.7 LUMINAIRE SUPPORT COMPONENTS

- A. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for channel and angle iron supports and nonmetallic channel and angle supports.
- B. Support Wires: ASTM A641/A641M, Class 3, soft temper, zinc-coated steel, 12 gage.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for conditions affecting performance of luminaires.
- B. Examine roughing-in for luminaire to verify actual locations of luminaire and electrical connections before luminaire installation.
- C. Examine walls, floors, roofs, and ceilings for suitable conditions where emergency lighting luminaires will be installed.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with NECA 1.
- B. Install luminaires level, plumb, and square with ceilings and walls unless otherwise indicated.
- C. Install lamps in each luminaire.
- D. Supports:
 - 1. Sized and rated for luminaire and emergency power unit weight.
 - 2. Able to maintain luminaire position when testing emergency power unit.
 - 3. Provide support for luminaire and emergency power unit without causing deflection of ceiling or wall.
 - 4. Luminaire-mounting devices shall be capable of supporting a horizontal force of 100 percent of luminaire and emergency power unit weight and vertical force of 400 percent of luminaire weight.
- E. Wall-Mounted Luminaire Support:
 - 1. Attached to structural members in walls.
 - 2. Do not attach luminaires directly to gypsum board.
- F. Suspended Luminaire Support:
 - 1. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
 - 2. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.
 - 3. Continuous Rows of Luminaires: Use tubing or stem for wiring at one point and tubing or rod for suspension for each unit length of luminaire chassis, including one at each end.
 - 4. Do not use ceiling grid as support for pendant luminaires. Connect support wires or rods to building structure.

G. Ceiling Grid Mounted Luminaires:

1. Secure to any required outlet box.
2. Secure emergency power unit using approved fasteners in a minimum of four locations, spaced near corners of emergency power unit.
3. Use approved devices and support components to connect luminaire to ceiling grid and building structure in a minimum of four locations, spaced near corners of luminaire.

3.3 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

3.4 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 1. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.
- B. Luminaire will be considered defective if it does not pass operation tests and inspections.
- C. Prepare test and inspection reports.

3.5 STARTUP SERVICE

- A. Perform startup service:
 1. Charge emergency power units and batteries minimum of one hour and depress switch to conduct short-duration test.
 2. Charge emergency power units and batteries minimum of 24 hours and conduct one-hour discharge test.

3.6 ADJUSTING

- A. Adjustments: Within 12 months of date of Final Acceptance, provide on-site visit to do the following:
 1. Inspect all luminaires. Replace lamps, emergency power units, batteries, signs, or luminaires that are defective.
 - a. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.
 2. Conduct short-duration tests on all emergency lighting.

END OF SECTION

SECTION 284621.11 - ADDRESSABLE FIRE-ALARM SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Addressable fire-alarm system.
2. Fire-alarm control unit (FACU).
3. Manual fire-alarm boxes.
4. System smoke detectors.
5. Heat detectors.
6. Fire-alarm notification appliances.
7. Firefighters' two-way telephone communication service.
8. Fire-alarm graphic annunciators.
9. Fire-alarm remote annunciators.
10. Fire-alarm addressable interface devices.
11. Fire-alarm radio transmitters.

B. Related Requirements:

1. Section 087100 "Door Hardware" for magnetic door holders that release in response to fire-alarm outputs.
2. Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for cables and conductors for fire-alarm systems.

1.3 DEFINITIONS

- A. DACT: Digital alarm communicator transmitter.
- B. EMT: Electrical metallic tubing.
- C. FACU: Fire-alarm control unit.
- D. Mode: The terms "Active Mode," "Off Mode," and "Standby Mode" are used as defined in the 2007 Energy Independence and Security Act (EISA).
- E. NICET: National Institute for Certification in Engineering Technologies.
- F. PC: Personal computer.

- G. Voltage Class: For specified circuits and equipment, voltage classes are defined as follows:
1. Control Voltage: Listed and labeled for use in remote-control, signaling, and power-limited circuits supplied by a Class 2 or Class 3 power supply having rated output not greater than 150 V and 5 A, allowing use of alternate wiring methods complying with NFPA 70, Article 725.
 2. Low Voltage: Listed and labeled for use in circuits supplied by a Class 1 or other power supply having rated output not greater than 1000 V, requiring use of wiring methods complying with NFPA 70, Article 300, Part I.

1.4 ACTION SUBMITTALS

- A. Approved Permit Submittal: Submittals must be approved by authorities having jurisdiction prior to submitting them to Architect.
- B. Product Data: For each type of product, including furnished options and accessories.
1. Include construction details, material descriptions, dimensions, profiles, and finishes.
 2. Include rated capacities, operating characteristics, and electrical characteristics.
- C. Shop Drawings: For fire-alarm system.
1. Comply with recommendations and requirements in "Documentation" section of "Fundamentals" chapter in NFPA 72.
 2. Include plans, elevations, sections, and details, including details of attachments to other Work.
 3. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and locations. Indicate conductor sizes, indicate termination locations and requirements, and distinguish between factory and field wiring.
 4. Graphic Annunciator panel details as required by authorities having jurisdiction.
 5. Detail assembly and support requirements.
 6. Include voltage drop calculations for notification-appliance circuits.
 7. Include battery-size calculations.
 8. Include input/output matrix.
 9. Include written statement from manufacturer that equipment and components have been tested as a system and comply with requirements in this Section and in NFPA 72.
 10. Include performance parameters and installation details for each detector.
 11. Verify that each duct detector is listed for complete range of air velocity, temperature, and humidity possible when air-handling system is operating.
 12. Provide program report showing that air-sampling detector pipe layout balances pneumatically within airflow range of air-sampling detector.
 13. Provide control wiring diagrams for fire-alarm interface to HVAC; coordinate location of duct smoke detectors and access to them.
 - a. Show critical dimensions that relate to placement and support of sampling tubes, detector housing, and remote status and alarm indicators.
 - b. Show field wiring and equipment required for HVAC unit shutdown on alarm.
 - c. Locate detectors in accordance with manufacturer's written instructions.
 - d. Show air-sampling detector pipe routing.

14. Include voice/alarm signaling-service equipment rack or console layout, grounding
- D. Delegated Design Submittal: For notification appliances and smoke and heat detectors, in addition to submittals listed above, indicate compliance with performance requirements and design criteria, including analysis data signed and sealed by qualified professional engineer responsible for their preparation.
1. Drawings showing location of each notification appliance and smoke and heat detector, ratings of each, and installation details as needed to comply with listing conditions of device.
 2. Design Calculations: Calculate requirements for selecting spacing and sensitivity of detection, complying with NFPA 72. Calculate spacing and intensities for strobe signals and sound-pressure levels for audible appliances.
 3. Indicate audible appliances required to produce square wave signal per NFPA 72.

1.5 INFORMATIONAL SUBMITTALS

- A. Certificates:
1. Seismic Performance Certificates: For FACU, accessories, and components, from manufacturer. Include the following information:
 - a. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - b. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - c. Detailed description of equipment anchorage devices on which certification is based and their installation requirements.
- B. Field quality-control reports.
- C. Qualification Statements: For Installer.
- D. Sample Warranty: Submittal must include line item pricing for replacement parts and labor.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals.
1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following and deliver copies to authorities having jurisdiction:
 - a. Comply with "Records" section of "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - b. Provide "Fire-Alarm and Emergency Communications System Record of Completion Documents" in accordance with "Completion Documents" Article in "Documentation" section of "Fundamentals" chapter in NFPA 72.

- c. Complete wiring diagrams showing connections between devices and equipment. Each conductor must be numbered at every junction point with indication of origination and termination points.
- d. Riser diagram.
- e. Device addresses.
- f. Air-sampling system sample port locations and modeling program report showing layout meets performance criteria.
- g. Record copy of site-specific software.
- h. Provide "Inspection and Testing Form" in accordance with "Inspection, Testing and Maintenance" chapter in NFPA 72, and include the following:
 - 1) Equipment tested.
 - 2) Frequency of testing of installed components.
 - 3) Frequency of inspection of installed components.
 - 4) Requirements and recommendations related to results of maintenance.
 - 5) Manufacturer's user training manuals.
- i. Manufacturer's required maintenance related to system warranty requirements.
- j. Abbreviated operating instructions for mounting at FACU and each annunciator unit.

B. Software and Firmware Operational Documentation:

- 1. Software operating and upgrade manuals.
- 2. Program Software Backup: On USB media.
- 3. Device address list.
- 4. Printout of software application and graphic screens.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Extra Stock Material: Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

- 1. Lamps for Remote Indicating Lamp Units: Quantity equal to 10 percent of amount installed, but no fewer than one unit.
- 2. Lamps for Strobe Units: Quantity equal to 10 percent of amount installed, but no fewer than one unit.
- 3. Smoke Detectors, Fire Detectors: Quantity equal to 10 percent of amount of each type installed, but no fewer than one unit of each type.
- 4. Detector Bases: Quantity equal to two percent of amount of each type installed, but no fewer than one unit of each type.
- 5. Keys and Tools: One extra set for access to locked or tamper proof components.
- 6. Audible and Visual Notification Appliances: One of each type installed.
- 7. Fuses: Two of each type installed in system. Provide in box or cabinet with compartments marked with fuse types and sizes.
- 8. Filters for Air-Sampling Detectors: Quantity equal to two percent of amount of each type installed, but no fewer than one unit of each type.
- 9. Air-Sampling Fan: Quantity equal to one for every five detectors, but no fewer than one unit of each type.

1.8 QUALITY ASSURANCE

A. Installer Qualifications:

1. Personnel must be trained and certified by the manufacturer for installation of units required for this Project.
2. Installation must be by personnel certified by NICET as fire-alarm Level III technician.
3. Obtain certification by NRTL in accordance with NFPA 72.
4. Licensed or certified by authorities having jurisdiction.

1.9 FIELD CONDITIONS

A. Seismic Conditions: Unless otherwise indicated on Contract Documents, specified Work in this Section must withstand the seismic hazard design loads determined in accordance with ASCE/SEI 7.

1. The term "withstand" means "unit must remain in place without separation of parts from unit when subjected to specified seismic design loads and unit must be fully operational after seismic event."

1.10 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace fire-alarm system equipment and components that fail because of defects in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 ADDRESSABLE FIRE-ALARM SYSTEM

A. Description:

1. Noncoded, UL-certified addressable system, with multiplexed signal transmission and horn-and-strobe notification for evacuation.

B. Performance Criteria:

1. Regulatory Requirements:

- a. Fire-Alarm Components, Devices, and Accessories: Listed and labeled by a NRTL in accordance with NFPA 70 for use with selected fire-alarm system and marked for intended location and application.

2. General Characteristics:

- a. Automatic sensitivity control of certain smoke detectors.

- b. Fire-alarm signal initiation must be by one or more of the following devices and systems:
 - 1) Manual stations.
 - 2) Heat detectors.
 - 3) Smoke detectors.
 - 4) Fire-extinguishing system operation.

- c. Fire-alarm signal must initiate the following actions:
 - 1) Continuously operate alarm notification appliances.
 - 2) Identify alarm and specific initiating device at FACU, connected network control panels, off-premises network control panels, and remote annunciators.
 - 3) Transmit alarm signal to remote alarm receiving station.
 - 4) Unlock electric door locks in designated egress paths.
 - 5) Release fire and smoke doors held open by magnetic door holders.
 - 6) Activate voice/alarm communication system.
 - 7) Switch HVAC equipment controls to fire-alarm mode.
 - 8) Activate emergency lighting control.
 - 9) Activate emergency shutoffs for gas and fuel supplies, except for shutoffs serving legally required life-safety systems such as emergency generators.
 - 10) Record events in system memory.
 - 11) Record events by system printer.
 - 12) Indicate device in alarm on graphic annunciator.

- d. Supervisory signal initiation must be by one or more of the following devices and actions:
 - 1) Zones or individual devices have been disabled.
 - 2) FACU has lost communication with network.

- e. System trouble signal initiation must be by one or more of the following devices and actions:
 - 1) Open circuits, shorts, and grounds in designated circuits.
 - 2) Opening, tampering with, or removing alarm-initiating and supervisory signal-initiating devices.
 - 3) Loss of communication with addressable sensor, input module, relay, control module, remote annunciator, printer interface, or Ethernet module.
 - 4) Loss of primary power at FACU.
 - 5) Ground or single break in internal circuits of FACU.
 - 6) Abnormal ac voltage at FACU.
 - 7) Break in standby battery circuitry.
 - 8) Failure of battery charging.
 - 9) Abnormal position of switch at FACU or annunciator.
 - 10) Voice signal amplifier failure.
 - 11) Hose cabinet door open.

- f. System Supervisory Signal Actions:
 - 1) Initiate notification appliances.
 - 2) Identify specific device initiating event at FACU, connected network control panels, off-premises network control panels, and remote annunciators.
 - 3) Record event on system printer.
 - 4) After time delay of 200 seconds, transmit trouble or supervisory signal to remote alarm receiving station.
 - 5) Transmit system status to building management system.
 - 6) Display system status on graphic annunciator.

- g. Network Communications:
 - 1) Provide network communications for fire-alarm system in accordance with fire-alarm manufacturer's written instructions.
 - 2) Provide network communications pathway per manufacturer's written instructions and requirements in NFPA 72 and NFPA 70.
 - 3) Provide integration gateway using Modbus for connection to building automation system.

- h. System Printer:
 - 1) Printer must be listed and labeled as integral part of fire-alarm system.

- i. Device Guards:
 - 1) Description: Welded wire mesh of size and shape for manual station, smoke detector, gong, or other device requiring protection.
 - a) Factory fabricated and furnished by device manufacturer.
 - b) Finish: Paint of color to match protected device.

- j. Document Storage Box:
 - 1) Description: Enclosure to accommodate standard 8-1/2-by-11 inch manuals and loose document records. Legend sheet will be permanently attached to door for system required documentation, key contacts, and system information. Provide two key ring holders with location to mount standard business cards for key contact personnel.
 - 2) Material and Finish: 18-gauge cold-rolled steel; four mounting holes.
 - 3) Color: Red powder-coat epoxy finish.
 - 4) Labeling: Permanently screened with 1 inch high lettering "SYSTEM RECORD DOCUMENTS" with white indelible ink.
 - 5) Security: Locked with 3/4 inch barrel lock. Provide solid 12 inch stainless steel piano hinge.

2.2 FIRE-ALARM CONTROL UNIT (FACU)

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

1. Gamewell-FCI; Honeywell International, Inc.
 2. Notifier; Honeywell International, Inc.
 3. Simplex; brand of Johnson Controls International plc, Building Solutions North America.
- B. Description: Field-programmable, microprocessor-based, modular, power-limited design with electronic modules.
- C. Performance Criteria:
1. Regulatory Requirements: Comply with NFPA 72 and UL 864.
 2. General Characteristics:
 - a. System software and programs must be held in nonvolatile flash, electrically erasable, programmable, read-only memory, retaining information through failure of primary and secondary power supplies.
 - b. Include real-time clock for time annotation of events on event recorder and printer.
 - c. Provide communication between FACU and remote circuit interface panels, annunciators, and displays.
 - d. FACU must be listed for connection to central-station signaling system service.
 - e. Provide nonvolatile memory for system database, logic, and operating system and event history. System must require no manual input to initialize in the event of complete power down condition. FACU must provide minimum 500-event history log.
 - f. Addressable Initiation Device Circuits: FACU must indicate which communication zones have been silenced and must provide selective silencing of alarm notification appliance by building communication zone.
 - 1) Addressable Control Circuits for Operation of Notification Appliances and Mechanical Equipment: FACU must be listed for releasing service.
 - g. Fire-Alarm Annunciator: Arranged for interface between human operator at FACU and addressable system components including annunciation and supervision. Display alarm, supervisory, and component status messages and programming and control menu.
 - 1) Annunciator and Display: LCD, 80 characters, minimum.
 - 2) Keypad: Arranged to permit entry and execution of programming, display, and control commands.
 - h. Alphanumeric Display and System Controls: Arranged for interface between human operator at FACU and addressable system components including annunciation and supervision. Display alarm, supervisory, and component status messages and programming and control menu.
 - 1) Annunciator and Display: LCD, two line(s) of 80 characters, minimum.
 - 2) Keypad: Arranged to permit entry and execution of programming, display, and control commands and to indicate control commands to be entered into system for control of smoke-detector sensitivity and other parameters.
 - i. Initiating-Device, Notification-Appliance, and Signaling-Line Circuits:

- 1) Pathway Class Designations: NFPA 72, Class A (Signaling-Line) and Class B (Initiating, Notification-Appliances).
 - 2) Pathway Survivability: Level 1.
 - 3) Install no more than 50 addressable devices on each signaling-line circuit.
 - 4) Install fault circuit isolators to comply with circuit performance requirements of NFPA 72 or with manufacturer's written instructions, whichever is more conservative.
- j. Serial Interfaces:
- 1) One dedicated RS 485 port for central-station operation using point ID DACT.
 - 2) One RS 485 port for remote annunciators, Ethernet module, or multi-interface module (printer port).
 - 3) One USB port for PC configuration.
 - 4) One RS 232 port for air-aspirating smoke detector connection.
 - 5) One RS 232 port for voice evacuation interface.
- k. Notification-Appliance Circuit:
- 1) Audible appliances must sound in three-pulse temporal pattern, as defined in NFPA 72.
 - 2) Where notification appliances provide signals to sleeping areas, alarm signal must be 520 Hz square wave with intensity 15 dB above average ambient sound level or 5 dB above maximum sound level, or at least 75 dB(A-weighted), whichever is greater, measured at pillow.
 - 3) Visual alarm appliances must flash in synchronization where multiple appliances are in same field of view, as defined in NFPA 72.
- l. Door Controls: Door hold-open devices that are controlled by smoke detectors at doors in smoke-barrier walls must [not]be connected to fire-alarm system.
- m. Voice/Alarm Signaling Service: Central emergency communication system with redundant microphones, preamplifiers, amplifiers, and tone generators provided as special module that is part of FACU.
- n. Indicate number of alarm channels for automatic, simultaneous transmission of different announcements to different zones or for manual transmission of

announcements by use of central-control microphone. Amplifiers must comply with UL 1711.

- 1) Allow application of, and evacuation signal to, indicated number of zones and simultaneously allow voice paging to other zones selectively or in combination.
 - 2) Programmable tone and message sequence selection.
 - 3) Standard digitally recorded messages for "Evacuation" and "All Clear."
 - 4) Generate tones to be sequenced with audio messages of type recommended by NFPA 72 and that are compatible with tone patterns of notification-appliance circuits of FACU.
- o. Status Annunciator: Indicate status of various voice/alarm speaker zones and status of firefighters' two-way telephone communication zones.
 - p. Preamplifiers, amplifiers, and tone generators must automatically transfer to backup units, on primary equipment failure.
 - q. Printout of Events: On receipt of signal, print alarm, supervisory, and trouble events. Identify zone, device, and function. Include type of signal (alarm, supervisory, or trouble) and date and time of occurrence. Differentiate alarm signals from other printed indications. Also, print system reset event, including same information for device, location, date, and time. Commands initiate printing of list of existing alarm, supervisory, and trouble conditions in system and historical log of events.
 - r. Primary Power: 24 V(dc) obtained from 120 V(ac) service and power-supply module. Initiating devices, notification appliances, signaling lines, trouble signals, and supervisory signals must be powered by 24 V(dc) source.
 - s. Alarm current draw of entire fire-alarm system must not exceed 80 percent of power-supply module rating.
 - t. Secondary Power: 24 V(dc) supply system with batteries, automatic battery charger, and automatic transfer switch.
 - 1) 60 hours of battery power capacity, plus 15 minutes of full alarm load.
 - u. Batteries: Sealed lead calcium.

D. Accessories:

1. Instructions: Computer printout or typewritten instruction card mounted behind plastic or glass cover in stainless steel or aluminum frame. Include interpretation and describe appropriate response for displays and signals. Briefly describe functional operation of system under normal, alarm, and trouble conditions.

2.3 MANUAL FIRE-ALARM BOXES

- A. General Requirements for Manual Fire-Alarm Boxes: Comply with UL 38. Boxes must be finished in red with molded, raised-letter operating instructions in contrasting color; must show

visible indication of operation; and must be mounted on recessed outlet box. If indicated as surface mounted, provide manufacturer's surface back box.

1. Double-action mechanism requiring two actions to initiate alarm, pull-lever type; with integral addressable module arranged to communicate manual-station status (normal, alarm, or trouble) to FACU.
2. Station Reset: Key- or wrench-operated switch.
3. Weatherproof Protective Shield: Factory-fabricated, clear plastic enclosure hinged at top to permit lifting for access to initiate alarm.
4. Able to perform at up to 90 percent relative humidity at 90 deg F.

2.4 SYSTEM SMOKE DETECTORS

A. Photoelectric Smoke Detectors:

1. Performance Criteria:

a. Regulatory Requirements:

- 1) NFPA 72.

b. General Characteristics:

- 1) Detectors must be four-wire type.
- 2) Base Mounting: Detector and associated electronic components must be mounted in twist-lock module that connects to fixed base. Provide terminals in fixed base for connection to building wiring.
- 3) Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
- 4) Integral Visual-Indicating Light: LED type, indicating detector has operated and power-on status.
- 5) Detector address must be accessible from FACU and must be able to identify detector's location within system and its sensitivity setting.
- 6) Operator at FACU, having designated access level, must be able to manually access the following for each detector:
 - a) Primary status.
 - b) Device type.
 - c) Present average value.
 - d) Present sensitivity selected.
 - e) Sensor range (normal, dirty, etc.).
- 7) Detector must have functional humidity range within 10 to 90 percent relative humidity.
- 8) Color: White.

2.5 HEAT DETECTORS

A. Fixed-Temperature-Type Heat Detectors:

1. Performance Criteria:

- a. Regulatory Requirements:
 - 1) NFPA 72.
 - 2) UL 521.
- b. General Characteristics:
 - 1) Actuated by temperature that exceeds fixed temperature of 190 deg F.
 - 2) Mounting: Twist-lock base interchangeable with smoke-detector bases.
 - 3) Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to FACU.
 - 4) Detector must have functional humidity range of 10 to 90 percent.
 - 5) Color: White.

2. DUCT SMOKE DETECTORS

- a. Description: Photoelectric-type, duct-mounted smoke detector.
- b. Performance Criteria:
 - 1) Regulatory Requirements:
 - a) NFPA 72.
 - b) UL 268A.
 - 2) General Characteristics:
 - a) Detectors must be four-wire type.
 - b) Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to FACU.
 - c) Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
 - d) Integral Visual-Indicating Light: LED type, indicating detector has operated.
 - e) Detector address must be accessible from FACU and must be able to identify detector's location within system and its sensitivity setting.
 - f) Operator at FACU, having designated access level, must be able to manually access the following for each detector:
 - 1. Primary status.
 - 2. Device type.
 - 3. Present average value.
 - 4. Present sensitivity selected.
 - 5. Sensor range (normal, dirty, etc.).
 - g) Weatherproof Duct Housing Enclosure: NEMA 250, Type 4X; NRTL listed for use with supplied detector for smoke detection in HVAC system ducts.
 - h) Each sensor must have multiple levels of detection sensitivity.

- i) Sampling Tubes: Design and dimensions as recommended by manufacturer for specific duct size, air velocity, and installation conditions where applied.
- j) Relay Fan Shutdown: Fully programmable relay rated to interrupt fan motor-control circuit.

2.6 FIRE-ALARM NOTIFICATION APPLIANCES

1. Description: Horns, bells, or other notification devices that cannot output voice messages.
2. Performance Criteria:
 - a. Regulatory Requirements:
 - 1) NFPA 72.
 - b. General Characteristics:
 - 1) Individually addressed, connected to signaling-line circuit, equipped for mounting as indicated, and with screw terminals for system connections.
 - 2) Connected to notification-appliance signal circuits, zoned as indicated, equipped for mounting as indicated, and with screw terminals for system connections.
 - 3) Chimes, Low-Level Output: Vibrating type, 85 dB(A-weighted) minimum rated output.
 - 4) Chimes, High-Level Output: Vibrating type, 85 dB(A-weighted) minimum rated output.
 - 5) Sounders, High Volume 24 V(dc): Less than 6 mA of alarm current.
 - 6) Sounders, Low Volume 24 V(dc): Less than 4 mA of alarm current.
 - 7) Audible notification appliances must have functional humidity range of 10 to 95 percent relative humidity.
 - 8) ISO Temporal 3 Evacuation Tone: 90 plus or minus 4 dB(A-weighted) at 24 V.
 - 9) ISO Temporal 3 Alert Tone: 95 plus or minus 5 dB(A-weighted) at 24 V.
 - 10) AS2220 Evacuation Tone: 93 plus or minus 4 dB(A-weighted) at 24 V.
 - 11) AS2220 Alert Tone: 93 plus or minus 5 dB(A-weighted) at 24 V.
 - 12) Horns: Electric-vibrating-polarized type, 24 V(dc); with provision for housing operating mechanism behind grille. Comply with UL 464. Horns must produce sound-pressure level of 90 dB(A-weighted), measured 10 ft. from horn, using coded signal prescribed in UL 464 test protocol.

B. Fire-Alarm Visible Notification Appliances:

1. Performance Criteria:
 - a. Regulatory Requirements:
 - 1) NFPA 72.
 - 2) UL 1971.
 - b. General Characteristics:
 - 1) Rated Light Output:
 - a) 15/30/75/110 cd, selectable in field.
 - 2) Clear or nominal white polycarbonate lens mounted on aluminum faceplate.
 - 3) Mounting: Wall mounted unless otherwise indicated.
 - 4) For units with guards to prevent physical damage, light output ratings must be determined with guards in place.
 - 5) Flashing must be in temporal pattern, synchronized with other units.
 - 6) Strobe Leads: Factory connected to screw terminals.
 - 7) Mounting Faceplate: Factory finished, red.

2.7 FIREFIGHTERS' TWO-WAY TELEPHONE COMMUNICATION SERVICE

- A. Description: Dedicated, two-way, supervised, telephone voice communication links between FACU and remote firefighters' telephone stations. Supervised telephone lines must be connected to talk circuits by controls in control module.
- B. Performance Criteria:
 1. Regulatory Requirements:
 - a. NFPA 72.
 2. General Characteristics:
 - a. Common-talk type for firefighter use only.
 - b. Controls to disconnect phones from talk circuits if too many phones are in use simultaneously. Indicator lamp must flash if phone is disconnected from talk circuits.
 - c. Addressable firefighters' phone modules to monitor and control loop of firefighter phones. Module must be capable of differentiating between normal, off-hook, and trouble conditions.
 - d. Audible Pulse and Tone Generator, and High-Intensity Lamp: When remote telephone is taken off hook, it causes audible signal to sound and high-intensity lamp to flash at FACU.
 - e. Selector panel controls to provide for simultaneous operation of up to six telephones in selected zones. Indicate ground faults and open or shorted telephone lines on panel front by individual LEDs.
 - f. Display: Graphic to indicate location of caller.
 - g. Remote Telephone Cabinet: Flush- or surface-mounted cabinet as indicated; factory-standard red finish; with handset.

- 1) Install one-piece handset to cabinet with vandal-resistant armored cord. Silk-screened or engraved label on cabinet door, designating "Fire Emergency Phone."
 - 2) With "break-glass" door access lock.
- h. Remote Telephone Jack Stations: Single-gang, stainless steel-plate mounted plug, engraved "Fire Emergency Phone."
- i. Handsets: push-to-talk stored in cabinet adjacent to FACU.

2.8 FIRE-ALARM GRAPHIC ANNUNCIATORS

A. Performance Criteria:

1. Regulatory Requirements:

- a. NFPA 72.

2. General Characteristics:

- a. Graphic Annunciator Panel: Mounted in aluminum frame with nonglare, minimum 3/16 inch thick, clear acrylic cover over graphic representation of facility. Detector locations must be represented by red LED lamps. Normal system operation must be indicated by lighted, green LED. Trouble and supervisory alarms must be represented by amber LED.
 - 1) Comply with UL 864.
 - 2) Operating voltage must be 24 V(dc) provided by local 24 V power supply provided with annunciator.
 - 3) Include built-in voltage regulation, reverse polarity protection, RS 232/422 serial communications, and lamp test switch.
 - 4) Surface mounted in NEMA 250, Type 1 cabinet, with key lock and no exposed screws or hinges.
 - 5) Graphic representation of facility must be CAD drawing and each detector must be represented by LED in its actual location. CAD drawing must be at 1:96 scale or larger.
 - 6) LED representing detector must flash two times per second while detector is in alarm.

2.9 FIRE-ALARM REMOTE ANNUNCIATORS

A. Performance Criteria:

1. Regulatory Requirements:

- a. NFPA 72.

2. General Characteristics:

- a. Annunciator functions must match those of FACU for alarm, supervisory, and trouble indications. Manual switching functions must match those of FACU, including acknowledging, silencing, resetting, and testing.
 - 1) Mounting: Flush cabinet, NEMA 250, Type 1.
- b. Display Type and Functional Performance: Alphanumeric display and LED indicating lights must match those of FACU. Provide controls to acknowledge, silence, reset, and test functions for alarm, supervisory, and trouble signals.

2.10 FIRE-ALARM ADDRESSABLE INTERFACE DEVICES

A. Performance Criteria:

1. Regulatory Requirements:
 - a. NFPA 72.
2. General Characteristics:
 - a. Include address-setting means on module.
 - b. Store internal identifying code for control panel use to identify module type.
 - c. Listed for controlling HVAC fan motor controllers.
 - d. Monitor Module: Microelectronic module providing system address for alarm-initiating devices for wired applications with normally open contacts.

2.11 FIRE-ALARM RADIO TRANSMITTERS

A. Performance Criteria:

1. Regulatory Requirements:
 - a. NFPA 72.
 - b. NFPA 1221.
 - c. 47 CFR 90.
2. General Characteristics:
 - a. Must be factory assembled, wired, and tested; ready for installation and operation.
 - b. Packaging: Single, modular, NEMA 250, Type 1 metal enclosure with tamper-resistant flush tumbler lock.
 - c. Signal Transmission Mode and Frequency: VHF or UHF 2-W power output, coordinated with operating characteristics of established remote alarm receiving station designated by Owner.
 - d. Normal Power Input: 120 V(ac).
 - e. Secondary Power: Integral-sealed, rechargeable, 12 V battery and charger. Comply with NFPA 72 requirements for battery capacity; submit calculations.
 - 1) Antenna: Omnidirectional, coaxial half-wave, dipole type with driving point impedance matched to transmitter and antenna cable output impedance.

- Wind-load strength of antenna and mounting hardware and supports must withstand 100 mph with gust factor of 1.3 without failure.
- 2) Antenna Cable: Coaxial cable with impedance matched to transmitter output impedance.
 - 3) Antenna-Cable Connectors: Weatherproof.
 - 4) Alarm Interface Devices: Circuit boards, modules, and other auxiliary devices, integral to transmitter, matching fire-alarm and other system outputs to message-generating inputs of transmitter that produce required message transmissions.
- f. Functional Performance: Unit must receive alarm, supervisory, or trouble signal from FACU or from its own internal sensors or controls and must automatically transmit signal along with unique code that identifies transmitting station to remote alarm receiving station. Transmitted messages must correspond to standard designations for fire-reporting system to which signal is being transmitted and must include separately designated messages in response to the following events or conditions:
- 1) Transmitter Low-Battery Condition: Sent when battery voltage is below 85 percent of rated value.
 - 2) System Test Message: Initiated manually by test switch within transmitter cabinet, or automatically at optionally preselected time, once every 24 hours, with transmission time controlled by programmed timing device integral to transmitter controls.
 - 3) Transmitter Trouble Message: Actuated by failure, in excess of one-minute duration, of transmitter normal power source, derangement of wiring of transmitter, or alarm input interface circuit or device connected to it.
 - 4) Local Fire-Alarm-System Trouble Message: Initiated by events or conditions that cause trouble signal to be indicated on building system.
 - 5) Local Fire-Alarm-System Alarm Message: Actuated when building system goes into alarm state. Identifies device that initiated alarm.
 - 6) Local Fire-Alarm-System, Supervisory-Alarm Message: Actuated when building alarm system indicates supervisory alarm.

2.12 DIGITAL ALARM COMMUNICATOR TRANSMITTERS (DACTs)

A. Manufacturer:

1. Preferred Brand Alternate: Digital Security Controls #DSC300TLF

B. Performance Criteria:

1. Regulatory Requirements:

- a. NFPA 72.

2. General Characteristics:

- a. DACT must be acceptable to remote central station and must be listed for fire-alarm use.

3. Functional Performance: Unit must receive alarm, supervisory, or trouble signal from FACU and automatically capture two data cables and dial preset number for remote central

station. When contact is made with central station(s), signals must be transmitted. If service on either line is interrupted for longer than 45 seconds, transmitter must initiate local trouble signal and transmit signal indicating loss of telephone line to remote alarm receiving station over remaining line. Transmitter must automatically report telephone service restoration to central station. If service is lost on both telephone lines, transmitter must initiate local trouble signal.

a. Local functions and display at DACT must include the following:

- 1) Verification that both telephone lines are available.
- 2) Programming device.
- 3) LED display.
- 4) Manual test report function and manual transmission clear indication.
- 5) Communications failure with central station or FACU.
- 6) Digital data transmission must include the following:
 - a) Address of alarm-initiating device.
 - b) Address of supervisory signal.
 - c) Address of trouble-initiating device.
 - d) Loss of ac supply.
 - e) Loss of power.
 - f) Low battery.
 - g) Abnormal test signal.
 - h) Communication bus failure.
 - i) Secondary Power: Integral rechargeable battery and automatic charger.
 - j) Self-Test: Conducted automatically every 24 hours with report transmitted to central station.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions for compliance with requirements for ventilation, temperature, humidity, and other conditions affecting performance of the Work.
 1. Verify that manufacturer's written instructions for environmental conditions have been permanently established in spaces where equipment and wiring are installed, before installation begins.
- B. Examine roughing-in for electrical connections to verify actual locations of connections before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Preinstallation Testing: Perform verification of functionality of installed components of existing system prior to starting work. Document equipment or components not functioning as designed.
- B. Protection of In-Place Conditions: Protect devices during construction unless devices are placed in service to protect facility during construction.

3.3 INSTALLATION OF EQUIPMENT

- A. Comply with NECA 305, NFPA 72, NFPA 101, and requirements of authorities having jurisdiction for installation and testing of fire-alarm equipment. Install electrical wiring to comply with requirements in NFPA 70 including, but not limited to, Article 760, "Fire Alarm Systems."
 - 1. Devices placed in service before other trades have completed cleanup must be replaced.
 - 2. Devices installed, but not yet placed, in service must be protected from construction dust, debris, dirt, moisture, and damage in accordance with manufacturer's written storage instructions.
- B. Connecting to Existing Equipment: Verify that existing fire-alarm system is operational before making changes or connections.
 - 1. Connect new equipment to existing control panel in existing part of building.
 - 2. Connect new equipment to existing monitoring equipment at supervising station.
 - 3. Expand, modify, and supplement existing [control] [monitoring] equipment as necessary to extend existing [control] [monitoring] functions to new points. New components must be capable of merging with existing configuration without degrading performance of either system.
 - 4. Install seismic bracing. Comply with requirements in Section 270548.16 "Seismic Controls for Communications Systems."
 - 5. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18 inch centers around full perimeter of concrete base.
 - 6. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
 - 7. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 8. Install anchor bolts to elevations required for proper attachment to supported equipment.
- C. Install wall-mounted equipment, with tops of cabinets not more than 78 inch above finished floor.
 - 1. Comply with requirements for seismic-restraint devices specified in Section 270548.16 "Seismic Controls for Communications Systems."
- D. Manual Fire-Alarm Boxes:
 - 1. Install manual fire-alarm box in normal path of egress within 60 inch of exit doorway.
 - 2. Mount manual fire-alarm box on background of contrasting color.

3. Operable part of manual fire-alarm box must be between 42 and 48 inch above floor level. Devices must be mounted at same height unless otherwise indicated.
 4. Smooth ceiling spacing must not exceed 30 ft..
 5. Spacing of detectors for irregular areas, for irregular ceiling construction, and for high ceiling areas must be determined in accordance with Annex A in NFPA 72.
 6. HVAC: Locate detectors not closer than 36 inch from air-supply diffuser or return-air opening.
 7. Lighting Fixtures: Locate detectors not closer than 12 inch from lighting fixture and not directly above pendant mounted or indirect lighting.
- E. Install cover on each smoke detector that is not placed in service during construction. Cover must remain in place except during system testing. Remove cover prior to system turnover.
- F. Single-Station Smoke Detectors: Where more than one smoke alarm is installed within dwelling or suite, they must be connected so that operation of smoke alarm causes alarm in smoke alarms to sound.
- G. Remote Status and Alarm Indicators: Install in visible location near each smoke detector, sprinkler water-flow switch, and valve-tamper switch that is not readily visible from normal viewing position.
- H. Audible Alarm-Indicating Devices: Install not less than 6 inch below ceiling. Install bells and horns on flush-mounted back boxes with device-operating mechanism concealed behind grille. Install devices at same height unless otherwise indicated.
- I. Visible Alarm-Indicating Devices: Install adjacent to each alarm bell or alarm horn and at least 6 inch below ceiling. Install devices at same height unless otherwise indicated.
- J. Device Location-Indicating Lights: Locate in public space near device they monitor.
- K. Antenna for Radio Alarm Transmitter: Mount to building structure where indicated. Use mounting arrangement and substrate connection that resists wind load of 100 mph with gust factor of 1.3 without damage.

3.4 ELECTRICAL CONNECTIONS

- A. Connect wiring in accordance with Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- B. Ground equipment in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."
- C. Install electrical devices furnished by manufacturer, but not factory mounted, in accordance with NFPA 70 and NECA 1.
- D. Install nameplate for each electrical connection, indicating electrical equipment designation and circuit number feeding connection.
 1. Nameplate must be laminated acrylic or melamine plastic signs, as specified in Section 260553 "Identification for Electrical Systems."

2. Nameplate must be laminated acrylic or melamine plastic signs with black background and engraved white letters at least 1/2 inch high.

3.5 CONTROL CONNECTIONS

- A. Install control and electrical power wiring to field-mounted control devices.
- B. Connect control wiring in accordance with Section 260523 "Control-Voltage Electrical Power Cables."
- C. Install nameplate for each control connection, indicating field control panel designation and I/O control designation feeding connection.

3.6 PATHWAYS

- A. Pathways above recessed ceilings and in inaccessible locations may be routed exposed.
 1. Exposed pathways located less than 96 inch above floor must be installed in EMT.
- B. Pathways must be installed in EMT.
- C. Exposed EMT must be painted red enamel.

3.7 CONNECTIONS

- A. For fire-protection systems related to doors in fire-rated walls and partitions and to doors in smoke partitions, comply with requirements in Section 087100 "Door Hardware." Connect hardware and devices to fire-alarm system.
 1. Verify that hardware and devices are listed for use with installed fire-alarm system before making connections.
- B. Make addressable connections with supervised interface device to the following devices and systems. Install interface device less than 36 inch from device controlled. Make addressable confirmation connection when such feedback is available at device or system being controlled.
 1. Smoke dampers in air ducts of designated HVAC duct systems.
 2. Electronically locked doors and access gates.
 3. Alarm-initiating connection to activate emergency lighting control.
 4. Data communication circuits for connection to building management system.
 5. Supervisory connections at fire-extinguisher locations.

3.8 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 270553 "Identification for Communications Systems."
- B. Install framed instructions in location visible from FACU.

3.9 GROUNDING

- A. Ground FACU and associated circuits in accordance with Section 260526 "Grounding and Bonding for Electrical Systems."
- B. Ground shielded cables at control panel location only. Insulate shield at device location.

3.10 FIELD QUALITY CONTROL

- A. Field tests must be witnessed by authorities having jurisdiction.
- B. Administrant for Tests and Inspections:
 - 1. Engage factory-authorized service representative to administer and perform tests and inspections on components, assemblies, and equipment installations, including connections.
- C. Tests and Inspections:
 - 1. Visual Inspection: Conduct visual inspection prior to testing.
 - a. Inspection must be based on completed record Drawings and system documentation that is required by "Completion Documents, Preparation" table in "Documentation" section of "Fundamentals" chapter in NFPA 72.
 - b. Comply with "Visual Inspection Frequencies" table in "Inspection" section of "Inspection, Testing and Maintenance" chapter in NFPA 72; retain "Initial/Reacceptance" column and list only installed components.
 - 2. System Testing: Comply with "Test Methods" table in "Testing" section of "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - 3. Test audible appliances for public operating mode in accordance with manufacturer's written instructions. Perform test using portable sound-level meter complying with Type 2 requirements in ASA S1.4 Part 1/IEC 61672-1.
 - 4. Test audible appliances for private operating mode in accordance with manufacturer's written instructions.
 - 5. Test visible appliances for public operating mode in accordance with manufacturer's written instructions.
 - 6. Factory-authorized service representative must prepare "Fire Alarm System Record of Completion" in "Documentation" section of "Fundamentals" chapter in NFPA 72 and "Inspection and Testing Form" in "Records" section of "Inspection, Testing and Maintenance" chapter in NFPA 72.
- D. Reacceptance Testing: Perform reacceptance testing to verify proper operation of added or replaced devices and appliances.
- E. Fire-alarm system will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.

- G. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.
- H. Annual Test and Inspection: One year after date of Substantial Completion, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

3.11 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system.

3.12 MAINTENANCE

- A. Maintenance Service: Beginning at Substantial Completion, maintenance service must include 12 months' full maintenance by skilled employees of manufacturer's designated service organization. Include preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper operation. Parts and supplies must be manufacturer's authorized replacement parts and supplies.
 - 1. Include visual inspections in accordance with "Visual Inspection Frequencies" table in "Testing" paragraph of "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - 2. Perform tests in "Test Methods" table in "Testing" paragraph of "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - 3. Perform tests per "Testing Frequencies" table in "Testing" paragraph of "Inspection, Testing and Maintenance" chapter in NFPA 72.

3.13 SOFTWARE SERVICE AGREEMENT

- A. Comply with UL 864.
- B. Technical Support: Beginning at Substantial Completion, service agreement must include software support for two years.
- C. Upgrade Service: At Substantial Completion, update software to latest version. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software must include operating system and new or revised licenses for using software.
 - 1. Upgrade Notice: At least 30 days to allow Owner to schedule access to system and to upgrade computer equipment if necessary.

END OF SECTION

SECTION 311000 – SITE CLEARING

PART 1 GENERAL

1.01 SUMMARY

- A. Section Includes:
 - 1. Protecting existing vegetation to remain.
 - 2. Removing existing vegetation.
 - 3. Clearing and grubbing.
 - 4. Stripping and stockpiling topsoil.
 - 5. Stripping and stockpiling rock.
 - 6. Removing above- and below-grade site improvements.
 - 7. Disconnecting, capping or sealing, and removing site utilities.
 - 8. Temporary erosion and sedimentation control.

1.02 DEFINITIONS

- A. Subsoil: Soil beneath the level of subgrade; soil beneath the topsoil layers of a naturally occurring soil profile, typified by less than 1 percent organic matter and few soil organisms.
- B. Surface Soil: Soil that is present at the top layer of the existing soil profile. In undisturbed areas, surface soil is typically called "topsoil," but in disturbed areas such as urban environments, the surface soil can be subsoil.
- C. Topsoil: Top layer of the soil profile consisting of existing native surface topsoil or existing in-place surface soil; the zone where plant roots grow. Its appearance is generally friable, pervious, and black or a darker shade of brown, gray, or red than underlying subsoil; reasonably free of subsoil, clay lumps, gravel, and other objects larger than 2 inches in diameter; and free of weeds, roots, toxic materials, or other non-soil materials.
- D. Plant-Protection Zone: Area surrounding individual trees, groups of trees, shrubs, or other vegetation to be protected during construction and indicated on Drawings.
- E. Tree-Protection Zone: Area surrounding individual trees or groups of trees to be protected during construction and indicated on Drawings.
- F. Vegetation: Trees, shrubs, groundcovers, grass, and other plants.

1.03 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.04 MATERIAL OWNERSHIP

- A. Except for materials indicated to be stockpiled or otherwise remain Owner's property, cleared materials shall become Contractor's property and shall be removed from Project site.

1.05 INFORMATIONAL SUBMITTALS

- A. Existing Conditions: Documentation of existing trees and plantings, adjoining construction, and site improvements that establishes preconstruction conditions that might be misconstrued as damage caused by site clearing.
 - 1. Use sufficiently detailed photographs or video recordings.
 - 2. Include plans and notations to indicate specific wounds and damage conditions of each tree or other plant designated to remain.
- B. Record Drawings: Identifying and accurately showing locations of capped utilities and other subsurface structural, electrical, and mechanical conditions.

1.06 FIELD CONDITIONS

- A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during site-clearing operations.
 - 1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
 - 2. Provide alternate routes around closed or obstructed trafficways if required by Owner or authorities having jurisdiction.
- B. Improvements on Adjoining Property: Authority for performing site clearing indicated on property adjoining Owner's property will be obtained by Owner before award of Contract.
 - 1. Do not proceed with work on adjoining property until directed by Designer.
- C. Salvageable Improvements: Carefully remove items indicated to be salvaged and store on Owner's premises where indicated.
- D. Utility Locator Service: Notify utility locator service for area where Project is located before site clearing.
- E. Do not commence site clearing operations until temporary erosion- and sedimentation-control and plant-protection measures are in place.
- F. Soil Stripping, Handling, and Stockpiling: Perform only when the soil is dry or slightly moist.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Satisfactory Soil Material: Requirements for satisfactory soil material are specified in Section 312000 "Earth Moving."

1. Obtain approved borrow soil material off-site when satisfactory soil material is not available on-site.
- B. Antirust Coating: Fast-curing, lead- and chromate-free, self-curing, universal modified-alkyd primer complying with MPI #23 (surface-tolerant, anticorrosive metal primer) or SSPC-Paint 20 or SSPC-Paint 29 zinc-rich coating. If known, consider inserting manufacturer's name and product name for antirust coating.

PART 3 EXECUTION

3.01 PREPARATION

- A. Protect and maintain benchmarks and survey control points from disturbance during construction.
- B. Protect existing site improvements to remain from damage during construction.
 1. Restore damaged improvements to their original condition, as acceptable to Owner.

3.02 TEMPORARY EROSION AND SEDIMENTATION CONTROL

- A. Provide temporary erosion- and sedimentation-control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to erosion- and sedimentation-control Drawings and that complies with EPA 832/R-92-005, NCDEQ or local jurisdiction approval permit, and requirements of authorities having jurisdiction.
- B. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.
- C. Inspect, maintain, and repair erosion- and sedimentation-control measures during construction until permanent vegetation has been established.
- D. Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

3.03 TREE AND PLANT PROTECTION

- A. Erect and maintain temporary fencing around tree protection zones before starting site clearing. Remove fence when construction is complete.
 1. Do not store construction materials, debris, or excavated material within fenced area.
 2. Do not permit vehicles, equipment, or foot traffic within fenced area.
 3. Maintain fenced area free of weeds and trash.
- B. Do not excavate within tree protection zones, unless otherwise indicated.
- C. Where excavation for new construction is required within tree protection zones, hand clear and excavate to minimize damage to root systems. Use narrow-tine spading forks, comb soil to expose roots, and cleanly cut roots as close to excavation as possible.

1. Cover exposed roots with burlap and water regularly.
 2. Temporarily support and protect roots from damage until they are permanently redirected and covered with soil.
 3. Coat cut faces of roots more than 1-1/2 inches in diameter with an emulsified asphalt or other approved coating formulated for use on damaged plant tissues.
 4. Backfill with soil as soon as possible.
- D. Repair or replace trees and vegetation indicated to remain that are damaged by construction operations, in a manner approved by Designer.
1. Employ an arborist, licensed in jurisdiction where Project is located, to submit details of proposed repairs and to repair damage to trees and shrubs.
 2. Replace trees that cannot be repaired and restored to full-growth status, as determined by the Designer.

3.04 EXISTING UTILITIES

- A. Contractor will arrange for disconnecting and sealing indicated utilities that serve existing structures before site clearing.
1. Verify that utilities have been disconnected and capped before proceeding with site clearing.
- B. Locate, identify, disconnect, and seal or cap utilities indicated to be removed.
1. Arrange with utility companies to shut off indicated utilities.
 2. Owner will arrange to shut off indicated utilities when requested by Contractor.
- C. Locate, identify, and disconnect utilities indicated to be abandoned in place.
- D. Interrupting Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others, unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
1. Notify Designer not less than two days in advance of proposed utility interruptions.
 2. Do not proceed with utility interruptions without Designer's written permission.
- E. Excavate for and remove underground utilities indicated to be removed.
- F. Removal of underground utilities is included in earthwork sections; in applicable fire suppression, plumbing, HVAC, electrical, communications, electronic safety and security, and utilities sections; and in Section 02 41 00 "Demolition."

3.05 CLEARING AND GRUBBING

- A. Remove obstructions, trees, shrubs, and other vegetation to permit installation of new construction.
1. Do not remove trees, shrubs, and other vegetation indicated to remain or to be relocated.
 2. Cut minor roots and branches of trees indicated to remain in a clean and careful manner where such roots and branches obstruct installation of new construction.
 3. Completely remove trees and stumps by digging, pushing, and pulling stump out.

- a. Trench roots around stump to reduce impact of stump removal.
 4. Use only hand methods or air space for grubbing within protection zones.
 5. Chip removed tree branches and haul off site to legal disposal area.
- B. Fill depressions caused by clearing and grubbing operations with satisfactory soil material unless further excavation or earthwork is indicated.
1. Place fill material in horizontal layers not exceeding a loose depth of 8 inches and compact each layer to a density equal to adjacent original ground.

3.06 TOPSOIL STRIPPING

- A. Remove sod and grass before stripping topsoil.
- B. Strip topsoil in a manner to prevent intermingling with underlying subsoil or other waste materials.
1. Remove subsoil and nonsoil materials from topsoil, including clay lumps, gravel, and other objects larger than 2 inches in diameter; trash, debris, weeds, roots, and other waste materials.
- C. Stockpile topsoil away from edge of excavations without intermixing with subsoil or other materials. Grade and shape stockpiles to drain surface water. Cover to prevent windblown dust and erosion by water.
1. Limit height of topsoil stockpiles to 72 inches.
 2. Do not stockpile topsoil within protection zones.
 3. Dispose of surplus topsoil. Surplus topsoil is that which exceeds quantity indicated to be stockpiled or reused.
 4. Dispose of all naturally formed rock.

3.07 STOCKPILING ROCK

- A. Remove from construction area naturally formed rocks that measure more than 1 foot across in least dimension. Do not include excavated or crushed rock.
1. Separate or wash off non-rock materials from rocks, including soil, clay lumps, gravel, and other objects larger than 2 inches in diameter; trash, debris, weeds, roots, and other waste materials.
- B. Stockpile rock away from edge of excavations without intermixing with other materials. Cover to prevent windblown debris from accumulating among rocks.
1. Limit height of rock stockpiles to 36 inches.
 2. Do not stockpile rock within protection zones.
 3. Dispose of surplus rock. Surplus rock is that which exceeds quantity indicated to be stockpiled or reused.
 4. Stockpile surplus rock to allow later use by the Owner.

3.08 SITE IMPROVEMENTS

- A. Remove existing above- and below-grade improvements as indicated and necessary to facilitate new construction.
- B. Remove slabs, paving, curbs, gutters, and aggregate base as indicated.
 - 1. Unless existing full-depth joints coincide with line of demolition, neatly saw-cut along line of existing pavement to remain before removing adjacent existing pavement. Saw-cut faces vertically.
 - 2. Paint cut ends of steel reinforcement in concrete to remain with two coats of antirust coating, following coating manufacturer's written instructions. Keep paint off surfaces that will remain exposed.

3.09 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Remove surplus soil material, rock, unsuitable topsoil, obstructions, demolished materials, and waste materials including trash and debris, and legally dispose of them off Owner's property.
- B. Separate recyclable materials produced during site clearing from other nonrecyclable materials. Store or stockpile without intermixing with other materials and transport them to recycling facilities. Do not interfere with other Project work.

END OF SECTION 311000

SECTION 31 20 40 – EROSION AND SEDIMENT CONTROL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Erosion and sediment control includes, but is not limited to the following:
 - 1. Standard control measures such as storm structure protection, gravel construction entrance / exit, silt fence, sediment trap(s), and sediment basin(s).
 - 2. Seeding.
- B. Review Contract Documents for requirements that affect work of this section. Specification Sections that directly relate to work of this section include, but are not limited to:
 - 1. NCDENR or Local Jurisdiction Erosion Control Permit
 - 2. Section 311000 "Site Clearing."
 - 3. Section 312000 "Earth Moving."
 - 4. Section 329200 "Turf and Grasses."

1.3 QUALITY ASSURANCE

- A. Perform erosion and sediment control in compliance with applicable requirements of Local and State governing authorities having jurisdiction

1.4 PRODUCT DELIVERY AND STORAGE

- A. Take all required measures to ensure that all materials are protected from damage.
- B. Special care shall be exercised during delivery and storage, to avoid damage to the products.
- C. All materials shall be delivered and stored within the Contractor's work limits or in an area approved by the Owner.

PART 2 - PRODUCTS

2.1 INLET PROTECTION FILTER FABRIC

- A. Inlet protection wire mesh shall be a 3/8 Mesh Galvanized hardwire wire.

2.2 SILT FENCE

- A. Standard Strength Siltation Fence: Polypropylene filter fabric backed with industrial netting and metal posts.
 - 1. Basis-of-Design: Subject to compliance with requirements, provide Mirafi 100X, Exxon GTF-103S or comparable products by one of the following as approved by the Designer:
 - a. Cherokee Manufacturing, LLC; DOT Grade 100 gram silt fence.
 - b. Granite Environmental, Inc.; DOT Grade 100 gram silt fence.
 - c. Hanes Geo Components; DOT Grade 100 gram silt fence.
 - d. HD Supply Construction and Industrial; DOT Grade 100 gram silt fence.
 - e. US Construction Fabrics, LLC; DOT Grade 100 gram silt fence.

2.3 SEEDING, SODDING, AND JUTE MESH

- A. Erosion Control Seeding Rates: As indicated on the Erosion Control Detail Drawings.

2.4 RIPRAP

- A. Provide riprap as indicated on the Drawings and per applicable codes.

PART 3 - EXECUTION

3.1 GENERAL EROSION CONTROL

- A. Provide erosion control during construction and changes.
 - 1. Provide modifications to required erosion control device.
 - 2. If any erosion control device cannot be installed, notify the Owner immediately.
 - 3. Maintain the devices and relocates as needed to prevent sediment leaving the site.
- B. Install construction erosion control features, as indicated on Drawings prior to topsoil stripping, earthwork, and removal of existing vegetation. Keep the disturbance to a minimum. Install other features as described in the sequence of erosion, sediment and pollution control on the Drawings.
- C. Contractor to place temporary seeding at the rate specified in the drawings perennial rye within fourteen (14) days on all non paved areas. If adverse weather conditions prevent good germination in two (2) weeks, repeat seeding until the area is stabilized. Till under temporary grass when preparing for final seeding.
- D. Until a disturbed area is stabilized, trap runoff sediment by the use of methods acceptable to governing authorities.
- E. Provide erosion controls on slopes and swales traversing, bordering, or leaving the site. Limit the water flow to a non-erosive velocity.
- F. Inspect all erosion and sediment control measures immediately after each rainfall and at least daily during prolonged rainfall. Make required repairs immediately.

- G. Remove sediment deposits when they reach approximately one half of the height of the barrier (silt fence). Dispose sediment in a manner that does not result in additional erosion or pollution.
- H. Promptly remove and dispose of all rubbish and debris in accordance with the governing authorities.
- I. Provide copies of inspection reports and maintenance items completed with each pay application. If inspection reports, maintenance, and or necessary modifications to erosion control devices are not completed, 10% of monthly pay application may be withheld.
- J. Any runoff that leaves the site must be under the State established threshold for turbidity.

3.2 SILT FENCE

- A. Construct the sediment barrier of standard strength or extra strength synthetic filter fabrics.
- B. Install posts 2 feet deep on downstream side of the silt fence enabling posts to support the fabric from upstream water pressure. Install posts with nipples facing away from the silt fabric.
 - 1. Posts: 1.33 lb per linear foot steel with a minimum length of 5 feet with projections to facilitate fastening of the fabric.
- C. Ensure that the height of the sediment fence does not exceed 24 inches above the ground surface.
- D. Construct the filter fabric from a continuous roll cut to the length of the barrier to avoid joints. When joints are necessary, securely fasten the filter cloth only at a support post with 4 feet minimum overlap to the next post.
- E. Support standard strength filter fabric by wire mesh (minimum 14 gauge with maximum mesh spacing of 6 inches) fastened securely to the upslope side of the posts. Extend the wire mesh support to the bottom of the trench. Fasten the wire reinforcement, then fabric on the upslope side of the fence post. Wire or plastic zip ties should have a minimum 50 pound tensile strength.
- F. When a wire mesh support fence is used, space posts a maximum of 8 feet apart. Support posts should be driven securely into the ground a minimum of 24 inches.
- G. Extra strength filter fabric with 6 feet post spacing does not require wire mesh support fence. Securely fasten the filter fabric directly to the posts. Wire or plastic zip ties should have a minimum of 50 pound tensile strength.
- H. Attach the fabric to each post with three ties, all spaced within the top 8 inches of the fabric. Attach each tie diagonally 45 degrees through the fabric, with each puncture at least 1 inch vertically apart. Also, each tie should be positioned to hang on a post nipple when tightened to prevent sagging.
- I. Wrap approximately 6 inches of fabric around the end posts and secure with 3 ties.

- J. Excavate a trench approximately 4 inches wide and 8 inches deep along the pro-posed line of posts and upslope from the barrier.
- K. Place 12 inches of the fabric along the bottom and side of the trench.
- L. Backfill the trench with soil placed over the filter fabric and thoroughly compact

3.3 TEMPORARY SEEDING

- A. Erosion Control Seeding Rates: As indicated on the Erosion Control Detail Drawing.
- B. Complete grading before preparing seedbeds, and install all necessary erosion control practices such as, dikes, waterways, and basins. If soils become compacted during grading, loosen them to a depth of 6 to 8 inches using a ripper, harrow, or chisel plow.
- C. Seed Bed Preparation: Well-pulverize, loosen, and uniform grading.
- D. Liming: Apply lime according to soil test recommendations. If the pH (acidity) of the soil is not known, an application of ground agricultural limestone at the fine textured soils is sufficient. Apply limestone uniformly and incorporate onto the top 4-6 inches of soil. Soils with a pH of 6 or higher need not be limed.
- E. Fertilizer: Install per rates on drawings
- F. Surface roughening: If recent tillage operations have resulted in a loose surface, additional roughening may not be required, except to break up large clods. If rainfall causes the surface to become sealed or crusted, loosen it just prior to seeding by disking, raking, harrowing, or other suitable methods. Groove or furrow slopes steeper than 3:1 on the contour before seeding, brace, and secure edge forms, bulkheads, and intermediate screed guides for pavement to required lines, grades, and elevations. Install forms to allow continuous progress of work and so forms can remain in place at least 24 hours after concrete placement.
- G. Amendments and soil preparation of final lift of planting soil provided per Section 329200 "Turf and Grasses." Stabilization with temporary seeding completed per time periods on the Drawings or as directed by Engineer. The Contractor is responsible for fully stabilizing site to 95 percent coverage, unless otherwise indicated on the Drawings, without limit to re-seeding.
- H. Watering and mowing of temporary seeding will be responsibility of contractor for construction duration until final close out of project or installation of permanent vegetation by NCSU.

3.4 MULCHING

- A. The use of an appropriate mulch for temporary coverage is allowed under the following conditions:
 - 1. Seeding in fall for winter cover.
 - a. Wood fiber mulches are not considered adequate for this use.

2. Slopes steeper than 3:1
3. Excessively hot or dry weather
4. Adverse soils (shallow, rocky, or high in clay or sand), and areas receiving concentrated flow.
5. If the area to be mulched is subject to concentrated waterflow, as in channels, anchor mulch with netting.

3.5 TEMPORARY DIVERSION DITCH

- A. Remove and properly dispose of all trees, brush, stumps, and other objectionable material.
- B. Ensure that the minimum constructed cross section meets all design requirements.
- C. Ensure that the top of the dike is not lower at any point than the design elevation plus the specified settlement.
- D. Provide sufficient room around diversions to permit machine regrading and cleanout.
- E. Vegetate the ridge immediately after construction, unless it will remain in place less than 30 working days.
- F. As necessary during grading operation re-direct, re0locate or adjust diversion ditch such that drainage continues as shown on the plans (i.e. the area which drains to a diversion ditch must continue to do so throughout the phase of erosion control).

3.6 RIPRAP

- A. Subgrade Preparation: Prepare the subgrade for riprap and filter to the required lines and grades shown on the Drawings. Compact any fill required in the subgrade to a density approximating that of the surrounding undisturbed material or overfill depressions with riprap. Remove brush, trees, stumps, and other objectionable material. Cut the subgrade sufficiently deep that the finished grade of the riprap will be at the elevation of the surrounding area.
- B. Excavated channels sufficiently to allow placement of the riprap so that the finished inside dimensions and grade of the riprap meet design specifications.
- C. Sand and Gravel Filter Blanket: Place the filter blanket immediately after the ground foundation is prepared. For gravel, spread filter stone in a uniform layer to the specified depth. Where more than one layer of filter material is used, spread the layers with minimal mixing.
- D. Synthetic Filter Fabric: Place the cloth filter directly on the prepared foundation. Overlap the edges by at least 12 inches, and space anchor pins every 3 ft along the overlap. Bury the upstream end of the cloth a minimum of 12 inches below ground and where necessary, bury the lower end of the cloth or overlap with the next section as required.
- E. Take care not to damage the cloth when placing riprap. If damage occurs remove the riprap, and repair the sheet by adding another layer of filter material with a minimum overlap of 12 inches around the damaged area. If extensive damage is suspected, remove and replace the entire sheet.

Where large stones are used or machine placement is difficult, a 4-inch layer of fine gravel or sand may be needed to protect the filter cloth.

- F. Stone Placement: Placement of riprap to follow immediately after placement of the filter. Place riprap so that it forms a dense, well-graded mass of stone with a minimum of voids. The desired distribution of stones throughout the mass may be obtained by selective loading at the quarry, and controlled dumping during final placement. Place riprap to its full thickness in one operation. Do not place riprap by dumping through chutes or other methods that cause segregation of stone sizes. Take care not to dislodge the underlying base or filter when placing the stones. The toe of the riprap slope should be keyed to a stable foundation at its base. The toe should be excavated to a depth about 1.5 times the design thickness of the riprap, and should extend horizontally from the slope.

3.7 CLEAN UP

- A. Clear the site of all extraneous materials, rubbish, and debris during construction and at intervals as directed by the Designer as erosion, sediment and pollution control procedures are completed. Leave the site in a clean, safe, well draining, and neat condition.

END OF SECTION 31 20 40

SECTION 321220 – AGGREGATES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Aggregate base course.
- 2. Open graded stone or surface course.
- 3. Porous stone.

B. Related Requirements:

- 1. Section 012200 "Unit Prices" for aggregate unit prices.
- 2. Section 312000 "Earth Moving."
- 3. Section 321216 "Asphalt Paving."
- 4. Section 321313 "Concrete Paving."

1.3 REFERENCES

- A. Comply with applicable requirements of the following standards. In the event these standards conflict with other specified requirements, the most restrictive requirement governs.

1. American Society for Testing and Materials (ASTM):

- a. C 33: Concrete Aggregates
- b. C 136: Sieve Analysis of Fine and Course Aggregates
- c. D 422: Particle - Size Analysis of Soils
- d. D 698: Laboratory Compaction Characteristics of Soils Using Standard Effort
- e. D 1556: Density of Soils by the Sand Cone Method
- f. D 1557: Laboratory Compaction Characteristics of Soils Using Modified Effort
- g. D 2216: Laboratory Determination of Water Content of Soil and Rock
- h. D 2922: Density of Soil and Soil - Aggregate in Place by Nuclear Methods (shallow depth)
- i. D 3017: Moisture Content of Soil and Soil Aggregate In Place by Nuclear Methods (shallow depth)
- j. D 4318: Liquid Limit, Plastic Limit, and Plasticity Index of Soils.

- 2. Occupational Safety and Health Administration (OSHA).
- 3. NCDOT Standard Specifications.

1.4 SUBMITTALS

A. Certifications of Laboratory Test Reports:

1. Provide certifications stating that the material complies with the requirements indicated on the Drawings and within this Section.

1.5 QUALITY ASSURANCE

- A. Provide all aggregates as specified in the Section, unless otherwise indicated on the Drawings.
- B. Submit laboratory test reports to the Engineer.
- C. Provide field density reports of in-place material.

1.6 PRODUCT DELIVERY AND STORAGE

- A. Deliver and store all materials within the Contractor's work limits or in an area approved by the Engineer.

1.7 REGULATORY REQUIREMENTS

- A. Regulatory Requirements: Unless otherwise indicated, comply with materials, workmanship, and other applicable requirements of North Carolina Department of Transportation Standard Specifications for Roads and Structures for aggregates.
 1. NCDOT Specifications: North Carolina Department of Transportation Standard Specifications for Roads and Structures.
- B. Delivery and storage of aggregate to comply NCDOT Standard Specification Section 510.

PART 2 - PRODUCTS

2.1 AGGREGATE BASE COURSE (ABC)

- A. Type B Aggregate: Comply with NCDOT Specifications Section 510 for base course under pavement.
- B. Gradation Acceptable Ranges:

1. <u>Sieve size</u>	<u>Percent Passing by Weight</u>
1 1/2"	100
1"	75 - 97
1/2"	55-80
No.4	35-55
No. 10	25-45

No. 40	14-30
No. 200	14-12

2. In addition to the gradation acceptance requirements listed in Table above, the material passing the No. 40 sieve must not have a liquid limit in excess of 30 nor a plasticity index in excess of 6. If any individual test results indicate values exceeding these, the Engineer may reject the entire lot.
3. For each sampling unit, two random samples will be taken. The average gradation test results of these samples will be used to determine the acceptability of the unit.
4. When a unit fails to meet the specification requirements of Article 10103(B) **Is this within NCDOT Specifications?** the unit represented must be removed from the stockpile or covered by spreading the required amount of corrective material over the surface of the unit. Correction will not be allowed when the amount of corrective material required exceeds 5 inches depth in which case the unit will be rejected and shall be removed from the stockpile. **(See Standard Special Provisions)** **Is this within NCDOT Specifications?**

2.2 OPEN GRADED STONE (Surface Course)

A. Open graded stone must be a uniformly processed stone drainage course meeting the following gradation:

1.	<u>Sieve Size</u>	<u>Percent Passing by Weight</u>
	2"	100
	3/4"	90 - 100
	3/8"	20-55
	No.4	10 - 15
	No.16	1 - 10
	No. 200	1 - 4

2. In addition to the gradation acceptance requirements listed in Table above, the material passing the No. 40 sieve must not have a liquid limit in excess of 30 nor a plasticity index less than 4 or in excess of 12. If any individual test results indicate values exceeding these, the Engineer may reject the entire lot.

2.3 POROUS STONE

A. Porous Stone: Comply with the following gradation:

1.	<u>Sieve Size</u>	<u>Percent Passing by Weight</u>
	3/8"	100
	No. 4	95 – 100
	No. 8	85 – 100
	No. 16	45 - 95
	No. 30	25 - 65
	No. 50	5 - 40
	No. 100	1 - 10
	No. 200	0 - 5

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Provide aggregates to the limits and dimensions as indicated on the Drawings.
- B. General Compaction Requirements: Provide the following general compaction requirements unless more stringent compaction requirements are indicated:
1. General Applications: 90% minimum.
 2. Bedding and Pipe Backfills: 90% minimum.
 3. Structural Backfills: 98% minimum.
 4. Structural Bases and Subbases: 98% minimum; ASTM D 698.
- C. Regulate loose lift thickness by the compaction equipment used to produce the above minimum standards. The maximum allowable lift thickness must not exceed 8 inches with the exception of an initial "bridging" lift used only where indicated or allowed by the soil conditions and as approved by the Engineer. Normal lift thickness must be in a range of 6 to 8 inches and conform to the industry standard that the maximum aggregate size particle cannot exceed 2/3 of the loose lift thickness.

3.2 TESTING

- A. Perform applicable testing conforming to the standards of the American Society for Testing and Materials (ASTM) prior to the delivery or incorporation of the material specified herein, unless otherwise indicated. Submit test results to the Engineer.
- B. Provide certification issued by the testing agency or supplier indicating the materials meet the requirements and conform to applicable standards of the NCDOT Specifications.

- C. Conduct suitable in-place testing upon installation of the materials to confirm adequate compaction and quality control results.
 - 1. Perform required field density tests: Comply with ASTM D 1556, ASTM D 2922, or ASTM D 3017.
 - a. For Gravel Pavement: Provide one field density test for every 10,000 sq. ft. per lift layer or a minimum of three (3) tests per work zone.
 - b. For All Other Applications: Provide field density test for appropriate area as referenced in Section 312000 "Earth Moving."

END OF SECTION 321220

SECTION 321313 – CONCRETE PAVING

PART 1 - GENERAL

1.01 SUMMARY

- A. Section Includes: Exterior concrete paving for the following:
 - 1. Driveways.
 - 2. Curbs and gutters.
 - 3. Walks.
 - 4. Unit paver base.

1.02 DEFINITIONS

Definition in "Cementitious Materials" Paragraph below refers to materials that make up the cementitious component of the w/c ratio.

- A. Cementitious Materials: Portland cement alone or in combination with one or more of blended hydraulic cement, fly ash, slag cement, and other pozzolans.
- B. W/C Ratio: The ratio by weight of water to cementitious materials.

1.03 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Review methods and procedures related to concrete paving, including but not limited to, the following:
 - a. Concrete mixture design.
 - b. Quality control of concrete materials and concrete paving construction practices.
 - c. Installation of concrete base for ramps and walks. Review slope requirements prior to installation.

1.04 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples for Verification: For each type of product or exposed finish, prepared as Samples of size indicated below:
 - 1. Colored Concrete: Provide manufacturer's standard sample size.
- C. Design Mixtures: For each concrete paving mixture. Comply with NCDOT Standard Specification, Section 1000. Include alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

1.05 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer of ready-mix concrete manufacturer, and testing agency.
- B. Material Certificates: For the following, from manufacturer:
 - 1. Cementitious materials.

2. Steel reinforcement and reinforcement accessories.
 3. Fiber reinforcement.
 4. Admixtures.
 5. Curing compounds.
 6. Applied finish materials.
 7. Bonding agent or epoxy adhesive.
 8. Joint fillers.
- C. Material Test Reports: Provide test results from a qualified testing agency indicating and interpreting test results for compliance of the following per NCDOT Standard Specification, Sections 700, 710, and 1000:
1. Thickness tolerances.
 2. Surface finish tolerance (modified.)
 3. Air Content.
 4. Slump.
 5. Flexural strength.
 6. Compression Test.
- D. Report test results in writing to Designer, within 48 hours of testing. Reports of compressive-strength tests must contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for 7-day and 28-day tests.
- E. Provide all field quality-control reports and testing.

1.06 QUALITY ASSURANCE

- A. Ready-Mix-Concrete Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C 94/C 94M requirements for production facilities and equipment.
1. Manufacturer certified according to NRMCA's "Certification of Ready Mixed Concrete Production Facilities" (Quality Control Manual - Section 3, "Plant Certification Checklist").
- B. Testing Agency Qualifications: Qualified according to ASTM C 1077 and ASTM E 329 for testing indicated.
1. Personnel conducting field tests shall be qualified as ACI Concrete Field Testing Technician, Grade 1, according to ACI CP-1 or an equivalent certification program.
- C. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
1. Notify Designer 7 days in advance of mockup installation.
 2. Build mockups of full-thickness sections of concrete paving to demonstrate typical joints; surface finish, texture, and color; curing; and standard of workmanship.
 3. Build mockups of concrete paving in the location and of the size indicated or, if not indicated, build mockups where directed by Designer and not less than 96 inches by 96 inches.
 4. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Designer specifically approves such deviations in writing.

5. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.07 PRECONSTRUCTION TESTING

- A. Preconstruction Testing Service: Engage a qualified independent testing agency to perform preconstruction testing on concrete paving mixtures.

1.08 REGULATORY REQUIREMENTS

- A. Regulatory Requirements: Unless otherwise indicated, comply with materials, workmanship, and other applicable requirements of North Carolina Department of Transportation Standard Specifications for Roads and Structures and ACI "Specification for Concrete" for concrete paving work.
 1. Measurement and payment provisions and safety program submittals included in standard specifications do not apply to this Section.
 2. NCDOT Specifications: North Carolina Department of Transportation Standard Specifications for Roads and Structures.
 3. Any reference to "NCDOT", "Department" or "Unit" within the NCDOT Specifications applies to the "Owner".

1.09 FIELD CONDITIONS

- A. Traffic Control: Maintain access for vehicular and pedestrian traffic as required for other construction activities.
- B. Cold-Weather Concrete Placement: Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing, or low temperatures. Comply with NCDOT Standard Specifications, Section 700-5, and the following:
 1. Do not pave when a descending air temperature reaches 35°F. Do not resume until the temperature is 35°F and rising.
 2. Do not place concrete over frozen subgrade or base course or aggregate.
 3. When air temperature has fallen to or is expected to fall below 40°F, uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50°F and not more than 80°F at point of placement.
 4. Do not use frozen materials or materials containing ice or snow.
 5. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in design mixtures.
- C. Hot-Weather Concrete Placement: Comply with ACI 301 and as follows when hot-weather conditions exist:
 1. Cool ingredients before mixing to maintain concrete temperature below 90 deg F at time of placement. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated in total amount of mixing water. Using liquid nitrogen to cool concrete is Contractor's option.
 2. Cover steel reinforcement with water-soaked burlap, so steel temperature will not exceed ambient air temperature immediately before embedding in concrete.
 3. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade moisture uniform without standing water, soft spots, or dry areas.

PART 2 - PRODUCTS

2.01 CONCRETE, GENERAL

- A. ACI Publications: Comply with ACI 301 unless otherwise indicated.

2.02 FORMS

- A. Form Materials: Plywood, metal, metal-framed plywood, or other approved panel-type materials to provide full-depth, continuous, straight, and smooth exposed surfaces.
 - 1. Use flexible or uniformly curved forms for curves with a radius of 100 feet or less.
- B. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and that will not impair subsequent treatments of concrete surfaces.

2.03 STEEL REINFORCEMENT

- A. Steel Reinforcements: Comply NCDOT Standard Specifications, Section 1070.

2.04 CONCRETE MATERIALS

- A. Portland Cement Concrete for Paving: Comply with NCDOT Standard Specifications, Section 700.
- B. Normal-Weight Aggregates: Comply with NCDOT Standard Specifications, Section 1014.
- C. Air-Entraining Admixture: Comply with NCDOT Standard Specifications, Section 1000.
- D. Chemical Admixtures: Admixtures certified by manufacturer to be compatible with other admixtures and to contain not more than 0.1 percent water-soluble chloride ions by mass of cementitious material.
 - 1. Water-Reducing Admixture: Comply with NCDOT Standard Specifications, Section 1000.
 - 2. Retarding Admixture: Comply with NCDOT Standard Specifications, Section 1000;
 - 3. Water-Reducing and Retarding Admixture: Comply with NCDOT Standard Specifications, Section 1000.
 - 4. High-Range, Water-Reducing Admixture: Comply with NCDOT Standard Specifications, Section 1000.
 - 5. High-Range, Water-Reducing and Retarding Admixture: Comply with NCDOT Standard Specifications, Section 1000.
 - 6. Plasticizing and Retarding Admixture: Comply with NCDOT Standard Specifications, Section 1000.
- E. Color Pigment: ASTM C 979/C 979M, synthetic mineral-oxide pigments or colored water-reducing admixtures; color stable, free of carbon black, nonfading, and resistant to lime and other alkalis.
 - 1. Color: As selected by Designer from manufacturer's full range.
- F. Water: Potable and complying with ASTM C 94/C 94M.

2.05 CURING MATERIALS

- A. Concrete Curing Agents: Free of impurities and complying with NCDOT Standard Specifications, Section 1026.

- B. Absorptive Cover: AASHTO M 182, Class 3, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. dry.
- C. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.
- D. Water: Potable.
- E. Evaporation Retarder: Waterborne, monomolecular, film forming, manufactured for application to fresh concrete.
1. Products: Subject to compliance with requirements, provide one of the following:
 - a. BASF Corporation-Construction Systems; MasterKure ER 50 (Pre-2014: Confilm.
 - b. Bon Tool Co.; 32-301-B7 BonWay Evaporation Retarder.
 - c. Brickform; a division of Solomon Colors; Evaporation Retarder.
 - d. ChemMasters, Inc; Spray-Film.
 - e. Dayton Superior; AquaFilm Concentrate J74.
 - f. Euclid Chemical Company (The); an RPM company; Eucobar.
 - g. Kaufman Products, Inc; VaporAid.
 - h. L&M Construction Chemicals, Inc; E-CON.
 - i. Lambert Corporation; LAMBCO Skin.
 - j. Metalcrete Industries; Waterhold.
 - k. Nox-Crete Products Group; MONOFILM.
 - l. Sika Corporation; SikaFilm.
 - m. SpecChem, LLC; SpecFilm.
 - n. TK Products; TK-2120 TRI-FILM.
 - o. Vexcon Chemicals Inc.; Certi-Vex EnvioAssist.
 - p. W.R. Meadows, Inc; EVAPRE.
- F. Clear, Waterborne, Membrane-Forming Curing Compound: ASTM C 309, Type 1, Class B, dissipating.
1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Anti-Hydro International, Inc; A-H Curing Compound #2 DR WB.
 - b. ChemMasters, Inc; Safe-Cure Clear DR.
 - c. Dayton Superior; Clear Resin Cure J11W.
 - d. Euclid Chemical Company (The); an RPM company; Kurez DR VOX or Kurez W VOX.
 - e. Kaufman Products, Inc; DR Cure.
 - f. L&M Construction Chemicals, Inc; L&M CURE R.
 - g. Lambert Corporation; AQUA KURE - CLEAR.
 - h. Nox-Crete Products Group; Res-Cure DH or Res-Cure DS.
 - i. Right Pointe; Clear Water Resin.
 - j. SpecChem, LLC; PaveCure Rez.
 - k. TK Products; TK-2519 DC WB.
 - l. Unitex by Dayton Superior; Hydroseal 18.
 - m. Vexcon Chemicals Inc.; Certi-Vex Enviocure 100.
 - n. W.R. Meadows, Inc; 1100-CLEAR SERIES.

- G. White, Waterborne, Membrane-Forming Curing Compound: ASTM C 309, Type 2, Class B, dissipating.
1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Anti-Hydro International, Inc; A-H Curing Compound #2 WP WB.
 - b. ChemMasters, Inc; Safe-Cure 2000.
 - c. Dayton Superior; White Resin Cure J10W.
 - d. Euclid Chemical Company (The); an RPM company; Kurez VOX White Pigmented.
 - e. Kaufman Products, Inc; Thinfilm 450.
 - f. L&M Construction Chemicals, Inc; L&M CURE R-2.
 - g. Lambert Corporation; AQUA KURE - WHITE.
 - h. SpecChem, LLC; PaveCure Rez White.
 - i. Vexcon Chemicals Inc.; Certi-Vex Enviocure White 100.
 - j. W.R. Meadows, Inc; 1100-WHITE SERIES or 1200-White.

2.06 RELATED MATERIALS

- A. Joint Fillers: Comply with NCDOT Standard Specifications, Section 1028-1; ASTM D 1751, asphalt-saturated cellulosic fiber or ASTM D 1752, cork or self-expanding cork in preformed strips.
- B. Slip-Resistive Aggregate Finish: Factory-graded, packaged, rustproof, nonglazing, abrasive aggregate of fused aluminum-oxide granules or crushed emery aggregate containing not less than 50 percent aluminum oxide and not less than 20 percent ferric oxide; unaffected by freezing, moisture, and cleaning materials.

2.07 CONCRETE MIXTURES

- A. Prepare design mixtures, proportioned according to ACI 301, for each type and strength of normal-weight concrete, and as determined by either laboratory trial mixtures or field experience.
 1. Use a qualified independent testing agency for preparing and reporting proposed concrete design mixtures for the trial batch method.
 2. When automatic machine placement is used, determine design mixtures and obtain laboratory test results that comply with or exceed requirements.
- B. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement in concrete to comply with ACI 301.
- C. Portland Cement Concrete: Comply with NCDOT Standard Specifications, Section 1000.
 1. Concrete paving mix design must comply to the following requirements in addition to NCDOT Standard Specifications;
 - a. Walkways and curb and gutter:
 - 1) Compressive strength of 4,000 psi at 28 days.
 - b. Unit paver base:
 - 1) Compressive strength of 3,000 psi at 28 days

2.08 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, and mix concrete and concrete materials to comply with NCDOT Standard Specifications, Section 1000.
 - 1. Place concrete per NCDOT Standard Specifications, Sections 700, 710, and 1000.
 - a. Elapsed Time for Placing Concrete: NCDOT Standard Specifications, Section 1000-4(E).

Table 1000-2 (Elapsed Time for Placing Concrete)		
Air or Concrete Temp (whichever is Higher)	Maximum Elapsed Time.	
	No Retarding Admixture	Retarding Admixture Used
90F or above	30 min	1 hr. 15 min
80F – 89F	45 min	1 hr. 30 min
79F or below	60 min	1 hr. 25 min

- B. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete according to ASTM C 94/C 94M. Mix concrete materials in appropriate drum-type batch machine mixer.
 - 1. For concrete batches of 1 cu. yd. or smaller, continue mixing at least 1-1/2 minutes, but not more than 5 minutes after ingredients are in mixer, before any part of batch is released.
 - 2. For concrete batches larger than 1 cu. yd., increase mixing time by 15 seconds for each additional 1 cu. yd.
 - 3. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture type, mixing time, quantity, and amount of water added.

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Examine exposed subgrades and subbase surfaces for compliance with requirements for dimensional, grading, and elevation tolerances.
- B. Provide compaction per Drawings and as specified below.
- C. Proof-roll prepared subbase surface below concrete paving to identify soft pockets and areas of excess yielding.
 - 1. Completely proof-roll subbase in one direction and repeat in perpendicular direction. Limit vehicle speed to 3 mph.
 - 2. Proof-roll with a pneumatic-tired and loaded, 10-wheel, tandem-axle dump truck weighing not less than 15 tons.
 - 3. Correct subbase with soft spots and areas of pumping or rutting exceeding depth of 1/2 inch according to requirements in Section 312000 "Earth Moving."
- D. Proceed with concrete pavement operations only after nonconforming conditions have been corrected and subgrade is ready to receive pavement.

3.02 PREPARATION

- A. Remove loose material from compacted subbase surface immediately before placing concrete.

3.03 EDGE FORMS AND SCREED CONSTRUCTION

- A. Set, brace, and secure edge forms, bulkheads, and intermediate screed guides to required lines, grades, and elevations. Install forms to allow continuous progress of work and so forms can remain in place at least 24 hours after concrete placement.
- B. Clean forms after each use and coat with form-release agent to ensure separation from concrete without damage.

3.04 STEEL REINFORCEMENT INSTALLATION

- A. Install steel reinforcement to comply with NCDOT Standard Specifications.
- B. Zinc-Coated Reinforcement: Use galvanized-steel wire ties to fasten zinc-coated reinforcement. Repair cut and damaged zinc coatings with zinc repair material.
- C. Epoxy-Coated Reinforcement: Use epoxy-coated steel wire ties to fasten epoxy-coated reinforcement. Repair cut and damaged epoxy coatings with epoxy repair coating according to ASTM D 3963/D 3963M.
- D. Install fabricated bar mats in lengths as long as practicable. Handle units to keep them flat and free of distortions. Straighten bends, kinks, and other irregularities, or replace units as required before placement. Set mats for a minimum 2-inch overlap of adjacent mats.

3.05 JOINTS

- A. Install joints to comply with NCDOT Standard Specifications, Section 700-11.
- B. General: Saw-cut construction, isolation, and contraction joints true to line, with faces perpendicular to surface plane of concrete. Construct transverse joints at right angles to centerline unless otherwise indicated.
 - 1. When joining existing paving, place transverse joints to align with previously placed joints unless otherwise indicated.
- C. Construction Joints: Set construction joints at side and end terminations of paving and at locations where paving operations are stopped for more than one-half hour unless paving terminates at isolation joints.
 - 1. Continue steel reinforcement across construction joints unless otherwise indicated. Do not continue reinforcement through sides of paving strips unless otherwise indicated.
 - 2. Provide tie bars at sides of paving strips where indicated.
 - 3. Butt Joints: Use bonding agent or epoxy-bonding adhesive at joint locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
 - 4. Keyed Joints: Provide preformed keyway-section forms or bulkhead forms with keys unless otherwise indicated. Embed keys at least 1-1/2 inches into concrete.
 - 5. Doweled Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or coat with asphalt one-half of dowel length to prevent concrete bonding to one side of joint.
- D. Isolation Joints: Form isolation joints of preformed joint-filler strips abutting concrete curbs, catch basins, manholes, inlets, structures, other fixed objects, and where indicated.
 - 1. Locate expansion joints at intervals of 50 feet unless otherwise indicated.
 - 2. Extend joint fillers full width and depth of joint.

3. Terminate joint filler not less than 1/2 inch or more than 1 inch below finished surface if joint sealant is indicated.
 4. Place top of joint filler flush with finished concrete surface if joint sealant is not indicated.
 5. Furnish joint fillers in one-piece lengths. Where more than one length is required, lace or clip joint-filler sections together.
 6. During concrete placement, protect top edge of joint filler with metal, plastic, or other temporary preformed cap. Remove protective cap after concrete has been placed on both sides of joint.
- E. Contraction Joints: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-fourth of the concrete thickness, as follows:
1. Grooved Joints: Not allowed.
 2. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- wide joints into concrete when cutting action will not tear, abrade, or otherwise damage surface and before developing random contraction cracks.
 - a. Tolerance: Ensure that sawed joints are within 3 inches either way from centers of dowels.
 3. Doweled Contraction Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or coat with asphalt one-half of dowel length to prevent concrete bonding to one side of joint.
- F. Edging: After initial floating, tool edges of paving, gutters, curbs, and joints in concrete with an edging tool to a 1/4-inch radius. Repeat tooling of edges after applying surface finishes. Eliminate edging-tool marks on concrete surfaces.

3.06 CONCRETE PLACEMENT

- A. Do not place additional pavement, aggregate, or soil next to newly placed concrete until the concrete has attained a compressive strength of at least 3,500 psi.
- B. Before placing concrete, inspect and complete formwork installation, steel reinforcement, and items to be embedded or cast-in.
- C. Remove snow, ice, or frost from subbase surface and steel reinforcement before placing concrete. Do not place concrete on frozen surfaces.
- D. Moisten subbase to provide a uniform dampened condition at time concrete is placed. Do not place concrete around manholes or other structures until they are at required finish elevation and alignment.
- E. Comply with ACI 301 requirements for measuring, mixing, transporting, and placing concrete.
- F. Do not add water to concrete during delivery or at Project site. Do not add water to fresh concrete after testing.
- G. Deposit and spread concrete in a continuous operation between transverse joints. Do not push or drag concrete into place or use vibrators to move concrete into place.
- H. Uniformly vibrate the concrete after it has been spread. Consolidate the full width and depth in a single pass.
- I. Consolidate concrete according to ACI 301 by mechanical vibrating equipment supplemented by hand spading, rodding, or tamping.

1. Consolidate concrete along face of forms and adjacent to transverse joints with an internal vibrator. Keep vibrator away from joint assemblies, reinforcement, or side forms. Use only square-faced shovels for hand spreading and consolidation. Consolidate with care to prevent dislocating reinforcement, dowels, and joint devices.
- J. Screed paving surface with a straightedge and strike off.
- K. Commence initial floating using bull floats or darbies to impart an open-textured and uniform surface plane before excess moisture or bleedwater appears on the surface. Do not further disturb concrete surfaces before beginning finishing operations or spreading surface treatments.
- L. Curbs and Gutters: Use design mixture for automatic machine placement. Produce curbs and gutters to required cross section, lines, grades, finish, and jointing.
- M. Slip-Form Paving: Use design mixture for automatic machine placement. Produce paving to required thickness, lines, grades, finish, and jointing.
 1. Compact subbase and prepare subgrade of sufficient width to prevent displacement of slip-form paving machine during operations.

3.07 FLOAT FINISHING

- A. General: Do not add water to concrete surfaces during finishing operations.
- B. Float Finish: Begin the second floating operation when bleedwater sheen has disappeared and concrete surface has stiffened sufficiently to permit operations. Float surface with power-driven floats or by hand floating if area is small or inaccessible to power units. Finish surfaces to true planes. Cut down high spots and fill low spots. Refloat surface immediately to uniform granular texture.
 1. Burlap Finish: Drag a seamless strip of damp burlap across float-finished concrete, perpendicular to line of traffic, to provide a uniform, gritty texture.
 2. Medium-to-Fine-Textured Broom Finish: Draw a soft-bristle broom across float-finished concrete surface, perpendicular to line of traffic, to provide a uniform, fine-line texture.
 3. Medium-to-Coarse-Textured Broom Finish: Provide a coarse finish by striating float-finished concrete surface 1/16 to 1/8 inch deep with a stiff-bristled broom, perpendicular to line of traffic.

3.08 SPECIAL FINISHES

- A. Monolithic Exposed-Aggregate Finish: Expose coarse aggregate in paving surface as follows:
 1. Immediately after float finishing, spray-apply chemical surface retarder to paving according to manufacturer's written instructions.
 2. Cover paving surface with plastic sheeting, sealing laps with tape, and remove when ready to continue finishing operations.
 3. Without dislodging aggregate, remove mortar concealing the aggregate by lightly brushing surface with a stiff, nylon-bristle broom. Do not expose more than one-third of the average diameter of the aggregate and not more than one-half of the diameter of the smallest aggregate.
 4. Fine-spray surface with water and brush. Repeat cycle of water flushing and brushing until cement film is removed from aggregate surfaces to depth required.
- B. Seeded Exposed-Aggregate Finish: Immediately after initial floating, spread a single layer of aggregate uniformly on paving surface. Tamp aggregate into plastic concrete and float finish to entirely embed aggregate with mortar cover of 1/16 inch.

1. Spray-apply chemical surface retarder to paving according to manufacturer's written instructions.
 2. Cover paving surface with plastic sheeting, sealing laps with tape, and remove sheeting when ready to continue finishing operations.
 3. Without dislodging aggregate, remove mortar concealing the aggregate by lightly brushing surface with a stiff, nylon-bristle broom. Do not expose more than one-third of the average diameter of the aggregate and not more than one-half of the diameter of the smallest aggregate.
 4. Fine-spray surface with water and brush. Repeat cycle of water flushing and brushing until cement film is removed from aggregate surfaces to depth required.
- C. Slip-Resistive Aggregate Finish: Before final floating, spread slip-resistive aggregate finish on paving surface according to manufacturer's written instructions and as follows:
1. Uniformly spread dampened, slip-resistive aggregate over paving surface in two applications at manufacturer's recommended rate to achieve required slip-resistance. Tamp aggregate flush with surface using a steel trowel, but do not force below surface.
 2. Uniformly distribute approximately two-thirds of slip-resistive aggregate over paving surface with mechanical spreader, allow to absorb moisture, and embed by power floating. Follow power floating with a second slip-resistive aggregate application, uniformly distributing remainder of material at right angles to first application to ensure uniform coverage, and embed by power floating.
 3. Cure concrete with curing compound recommended by slip-resistive aggregate manufacturer. Apply curing compound immediately after final finishing.
 4. After curing, lightly work surface with a steel-wire brush or abrasive stone and water to expose nonslip aggregate.
- D. Rock-Salt Finish: After initial floating, troweling, or brooming, uniformly spread rock salt over paving surface at the rate of 5 lb/100 sq. ft.
1. Embed rock salt into plastic concrete with roller or magnesium float.
 2. Cover paving surface with 1-mil- thick polyethylene sheet and remove sheet when concrete has hardened and seven-day curing period has elapsed.
 3. After seven-day curing period, saturate concrete with water and broom-sweep surface to dissolve remaining rock salt, thereby leaving pits and holes.
- E. Pigmented Mineral Dry-Shake Hardener Finish: After initial floating, apply dry-shake materials to paving surface according to manufacturer's written instructions and as follows:
1. Uniformly spread dry-shake hardener at a rate of 100 lb/100 sq. ft. unless greater amount is recommended by manufacturer to match paving color required.
 2. Uniformly distribute approximately two-thirds of dry-shake hardener over the concrete surface with mechanical spreader; allow hardener to absorb moisture and embed it by power floating. Follow power floating with a second application of pigmented mineral dry-shake hardener, uniformly distributing remainder of material at right angles to first application to ensure uniform color, and embed hardener by final power floating.
 3. After final power floating, apply a hand-troweled finish followed by a broom finish.
 4. Cure concrete with curing compound recommended by dry-shake hardener manufacturer. Apply curing compound immediately after final finishing.
- F. Light Sand Finish: See Section 32 13 16 – Decorative Concrete Paving.

3.09 CONCRETE PROTECTION AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
- B. Comply with NCDOT Standard Specifications, Sections 700 and 710.
- C. Comply with ACI 306.1 for cold-weather protection.
- D. Evaporation Retarder: Apply evaporation retarder to concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete but before float finishing.
- E. Begin curing after finishing concrete but not before free water has disappeared from concrete surface.
- F. Curing Methods: Cure concrete by moisture curing, moisture-retaining-cover curing, curing compound, or a combination of these as follows:
 - 1. Moisture Curing: Keep surfaces continuously moist for not less than seven days with the following materials:
 - a. Water.
 - b. Continuous water-fog spray.
 - c. Absorptive cover, water saturated and kept continuously wet. Cover concrete surfaces and edges with 12-inch lap over adjacent absorptive covers.
 - 2. Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive. Immediately repair any holes or tears occurring during installation or curing period, using cover material and waterproof tape.
 - 3. Curing Compound: Apply uniformly in continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating, and repair damage during curing period.

3.10 PAVING TOLERANCES

- A. Comply with tolerances in NCDOT Standard Specifications and as follows:
 - 1. Elevation: 1/4 inch.
 - 2. Thickness: Plus 3/8 inch, minus 1/4 inch.
 - 3. Surface: Gap below 10-feet- long; unlevelled straightedge not to exceed 1/4 inch.
 - 4. Alignment of Tie-Bar End Relative to Line Perpendicular to Paving Edge: 1/2 inch per 12 inches of tie bar.
 - 5. Lateral Alignment and Spacing of Dowels: 1 inch.
 - 6. Vertical Alignment of Dowels: 1/4 inch.
 - 7. Alignment of Dowel-Bar End Relative to Line Perpendicular to Paving Edge: 1/4 inch per 12 inches of dowel.
 - 8. Joint Spacing: 3 inches.
 - 9. Contraction Joint Depth: Plus 1/4 inch, no minus.
 - 10. Joint Width: Plus 1/8 inch, no minus.

3.11 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Testing Services: Testing and inspecting of composite samples of fresh concrete obtained according to NCDOT Standard Specifications, Sections 700, 710, and 1000 shall be performed according to the following requirements:
 - 1. Testing Frequency: Obtain at least one composite sample for each 400 cu. yd. or fraction thereof of each concrete mixture placed each day.
 - a. When frequency of testing will provide fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.
 - 2. Slump: One test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture. Perform additional tests when concrete consistency appears to change.
 - 3. Air Content: Pressure method; one test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
 - 4. Concrete Temperature: One test hourly when air temperature is 40 deg F and below and when it is 80 deg F and above, and one test for each composite sample.
 - 5. Compression Test Specimens: Cast and laboratory cure one set of three standard cylinder specimens for each composite sample.
 - 6. Compressive-Strength Tests: Test one specimen at seven days and two specimens at 28 days.
 - a. A compressive-strength test shall be the average compressive strength from two specimens obtained from same composite sample and tested at 28 days.
 - 7. Flexural Strength Test: NCDOT Standard Specifications, Section 700-15. Provide one beam taken every 400 cubic yards for 28-day strength test for each mix identified with a flexural strength rating.
 - 8. Thickness Tolerances: NCDOT Standard Specifications, Section 700-15 and Sections 710-9. Provide one core every 1000 cubic yards, or distinct project area.
 - 9. Surface Tolerance: Finish surface must be within 1/4-inch when checked longitudinally with a 10-foot straight edge.
- C. Strength of each concrete mixture will be satisfactory if average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi.
- D. Test results shall be reported in writing to Designer, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests shall contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for both 7- and 28-day tests.
- E. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Designer but will not be used as sole basis for approval or rejection of concrete.
- F. Additional Tests: Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Designer.

See Section 014000 "Quality Requirements" for retesting and reinspecting requirements and Section 017300 "Execution" for requirements for correcting the Work.

- G. Concrete paving will be considered defective if it does not pass tests and inspections.
- H. Remove and replace concrete pavement where test results indicate that it does not comply with specified requirements.
- I. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.
- J. Prepare test and inspection reports.

3.12 REPAIR AND PROTECTION

- A. Remove and replace concrete paving that is broken, damaged, or defective or that does not comply with requirements in this Section. Remove work in complete sections from joint to joint unless otherwise approved by Designer.
- B. Drill test cores, where directed by Designer, when necessary to determine magnitude of cracks or defective areas. Fill drilled core holes in satisfactory paving areas with portland cement concrete bonded to paving with epoxy adhesive.
- C. Protect concrete paving from damage. Exclude traffic from paving for at least 14 days after placement. When construction traffic is permitted, maintain paving as clean as possible by removing surface stains and spillage of materials as they occur.
- D. Maintain concrete paving free of stains, discoloration, dirt, and other foreign material. Sweep paving not more than two days before date scheduled for Substantial Completion inspections.

END OF SECTION 321313

SECTION 321373 – CONCRETE PAVING JOINT SEALANTS

PART 1 - GENERAL

1.01 SUMMARY

- A. This Section includes the following:
Adjust list below to suit Project.
 - 1. Expansion and contraction joints within cement concrete pavement and site walls.
 - 2. Joints between cement concrete and asphalt pavement.

1.02 SUBMITTALS

- A. Product Data: For each joint-sealant product indicated.
- B. Product Certificates: For each type of joint sealant and accessory, signed by product manufacturer.
- C. Compatibility and Adhesion Test Reports: From sealant manufacturer, indicating the following:
 - 1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
 - 2. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion.
- D. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for sealants.

1.03 QUALITY ASSURANCE

- A. Installer Qualifications: An employer of workers trained and approved by manufacturer.
- B. Source Limitations: Obtain each type of joint sealant through one source from a single manufacturer.
- C. Preconstruction Compatibility and Adhesion Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.
 - 1. Use ASTM C 1087 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.

2. Submit not fewer than eight pieces of each type of material, including joint substrates, shims, joint-sealant backings, secondary seals, and miscellaneous materials.
 3. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
 4. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures including use of specially formulated primers.
- D. Product Testing: Obtain test results for "Product Test Reports" Paragraph in "Submittals" Article from a qualified testing agency based on testing of current sealant products within a 36-month period preceding the Notice to Proceed with the Work.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to Project site in original unopened containers or bundles with labels indicating manufacturer, product name and designation, color, expiration date, pot life, curing time, and mixing instructions for multicomponent materials.
- B. Store and handle materials to comply with manufacturer's written instructions to prevent their deterioration or damage due to moisture, high or low temperatures, contaminants, or other causes.

1.05 PROJECT CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
 2. When joint substrates are wet or covered with frost.
 3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
 4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, products listed in other Part 2 articles.

2.02 MATERIALS, GENERAL

- A. Compatibility: Provide joint sealants, backing materials, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer based on testing and field experience.

2.03 COLD-APPLIED JOINT SEALANTS

- A. Multicomponent Jet-Fuel-Resistant Sealant for Concrete: Pourable, chemically curing elastomeric formulation complying with the following requirements for formulation and with ASTM C 920 for type, grade, class, and uses indicated:
 - 1. Urethane Formulation: Type M; Grade P; Class 12-1/2; Uses T, M, and, as applicable to joint substrates indicated, O.
 - a. Products:
 - 1) Pecora Corporation; Urexpan NR-300.
 - 2) Or Approved Equal
 - 2. Bitumen-Modified Urethane Formulation: Type M; Grade P; Class 25; Uses T, M, and, as applicable to joint substrates indicated, O.
 - a. Products:
 - 1) Tremco Sealant/Waterproofing Division; Vulkem 202.
 - 2) Or Approved Equal
- B. Single-Component Jet-Fuel-Resistant Urethane Sealant for Concrete: Single-component, pourable, coal-tar-modified, urethane formulation complying with ASTM C 920 for Type S; Grade P; Class 25; Uses T, M, and, as applicable to joint substrates indicated, O.
 - 1. Products:
 - a. Sonneborn, Div. of ChemRex, Inc.; Sonomeric 1.
 - b. Or Approved Equal
- C. Type NS Silicone Sealant for Concrete: Single-component, low-modulus, neutral-curing, nonsag silicone sealant complying with ASTM D 5893 for Type NS.
 - 1. Products:
 - a. Crafcro Inc.; RoadSaver Silicone.
 - b. Dow Corning Corporation; 888.
 - c. Or Approved Equal
- D. Type SL Silicone Sealant for Concrete and Asphalt: Single-component, low-modulus, neutral-curing, self-leveling silicone sealant complying with ASTM D 5893 for Type SL.
 - 1. Products:
 - a. Crafcro Inc.; RoadSaver Silicone SL.
 - b. Dow Corning Corporation; 890-SL.
 - c. Or Approved Equal
- E. Multicomponent Low-Modulus Sealant for Concrete and Asphalt: Proprietary formulation consisting of reactive petropolymer and activator components producing a pourable, self-leveling sealant.
 - 1. Products:

- a. Meadows, W. R., Inc.; Sof-Seal.
- b. Or Approved Equal

2.04 HOT-APPLIED JOINT SEALANTS

- A. Jet-Fuel-Resistant Elastomeric Sealant for Concrete: Single-component formulation complying with ASTM D 3569.
 - 1. Products:
 - a. Crafcoc Inc.; Superseal 444/777.
 - b. Meadows, W. R., Inc.; Poly-Jet 3569.
 - c. Or Approved Equal

Products complying with paragraph above and first paragraph below are unsuitable for use with asphalt pavement.
- B. Jet-Fuel-Resistant Sealant for Concrete and Tar Concrete: Single-component formulation complying with ASTM D 3581.
 - 1. Products:
 - a. Crafcoc Inc.; Superseal 1614A.
 - b. Meadows, W. R., Inc.; Poly-Jet 1614.
 - c. Meadows, W. R., Inc.; Poly-Jet 3406.
 - d. Meadows, W. R., Inc.; Poly-Jet 3569.
 - e. Or Approved Equal
- C. Elastomeric Sealant for Concrete: Single-component formulation complying with ASTM D 3406.
 - 1. Products:
 - a. Crafcoc Inc.; Superseal 444/777.
 - b. Meadows, W. R., Inc.; Poly-Jet 3406.
 - c. Or Approved Equal
- D. Sealant for Concrete and Asphalt: Single-component formulation complying with ASTM D 3405.
 - 1. Products:
 - a. Koch Materials Company; Product No. 9005.
 - b. Koch Materials Company; Product No. 9030.
 - c. Meadows, W. R., Inc.; Sealtight Hi-Spec.
 - d. Or Approved Equal

2.05 JOINT-SEALANT BACKER MATERIALS

- A. General: Provide joint-sealant backer materials that are nonstaining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by joint-sealant manufacturer based on field experience and laboratory testing.

- B. Round Backer Rods for Cold- and Hot-Applied Sealants: ASTM D 5249, Type 1, of diameter and density required to control sealant depth and prevent bottom-side adhesion of sealant.
- C. Backer Strips for Cold- and Hot-Applied Sealants: ASTM D 5249; Type 2; of thickness and width required to control sealant depth, prevent bottom-side adhesion of sealant, and fill remainder of joint opening under sealant.
- D. Round Backer Rods for Cold-Applied Sealants: ASTM D 5249, Type 3, of diameter and density required to control sealant depth and prevent bottom-side adhesion of sealant.

2.06 PRIMERS

- A. Primers: Product recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.
 - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions.
- B. Joint Priming: Prime joint substrates where indicated or where recommended in writing by joint-sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

3.03 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

- B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Install backer materials of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 - 1. Do not leave gaps between ends of backer materials.
 - 2. Do not stretch, twist, puncture, or tear backer materials.
 - 3. Remove absorbent backer materials that have become wet before sealant application and replace them with dry materials.
- D. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
 - 1. Place sealants so they directly contact and fully wet joint substrates.
 - 2. Completely fill recesses provided for each joint configuration.
 - 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- E. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
 - 1. Remove excess sealants from surfaces adjacent to joint.
 - 2. Use tooling agents that are approved in writing by joint-sealant manufacturer and that do not discolor sealants or adjacent surfaces.
- F. Provide joint configuration to comply with joint-sealant manufacturer's written instructions, unless otherwise indicated.
- G. Provide recessed joint configuration for silicone sealants of recess depth and at locations indicated.

3.04 CLEANING

- A. Clean off excess sealants or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved by manufacturers of joint sealants and of products in which joints occur.

3.05 PROTECTION

- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately and replace with joint sealant so installations with repaired areas are indistinguishable from the original work.

END OF SECTION 321373

SECTION 32 17 13 - PARKING BUMPERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes wheel stops.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples for Initial Selection: For each type of exposed finish requiring color selection.
- C. Samples for Verification: For wheel stops, 6 inches long, showing color and cross section; with fasteners.

PART 2 - PRODUCTS

2.1 PARKING BUMPERS

- A. Concrete Wheel Stops: Precast, steel-reinforced, air-entrained concrete, 2500-psi minimum compressive strength, 4-1/2 inches high by 9 inches wide by 72 inches long, unless otherwise indicated. Provide chamfered corners, transverse drainage slots on underside, and a minimum of two factory-formed or -drilled vertical holes through wheel stop for anchoring to substrate.
 - 1. Surface Appearance: Free of pockets, sand streaks, honeycombs, and other obvious defects. Corners shall be uniform, straight, and sharp.
 - 2. Mounting Hardware:
 - a. Asphalt Surfaces: Galvanized-steel spike or dowel, 1/2-inch diameter, 10-inch minimum length
 - b. Concrete Surfaces: Galvanized-steel lag screw, shield, and washers; 1/2-inch diameter, 8-inch minimum length.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that pavement is in suitable condition to begin installation according to manufacturer's written instructions.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Install wheel stops according to manufacturer's written instructions unless otherwise indicated.
- B. Install wheel stops in bed of adhesive before anchoring.
- C. Securely attach wheel stops into pavement with not less than two galvanized steel dowels embedded in holes drilled or cast into wheel stops at one-quarter to one-third points. Firmly bond each dowel to wheel stop and to pavement. Securely install dowels into pavement and bond to wheel stop. Recess head of dowel beneath top of wheel stop.

END OF SECTION 321713

SECTION 321723 - PAVEMENT MARKINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes thermoplastic pavement markings applied to asphalt pavement.
- B. Related Requirements:
 - 1. Section 321216 "Asphalt Paving."

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Review methods and procedures related to marking pavement including, but not limited to, the following:
 - a. Pavement aging period before application of pavement markings.
 - b. Review requirements for protecting pavement markings, including restriction of traffic during installation period.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include technical data and tested physical and performance properties.
- B. Shop Drawings: For pavement markings.
 - 1. Indicate pavement markings, colors, lane separations, defined parking spaces, and dimensions to adjacent work.
 - 2. Indicate, with international symbol of accessibility, spaces allocated for people with disabilities.
- C. Samples: For each exposed product and for each color and texture specified; on rigid backing, 8 inches square.

1.5 QUALITY ASSURANCE

- A. Regulatory Requirements: Comply with materials, workmanship, and other applicable requirements of NCDOT Standard Specifications for pavement-marking work.
 - 1. Measurement and payment provisions and safety program submittals included in standard specifications do not apply to this Section.

1.6 FIELD CONDITIONS

- A. Environmental Limitations: Proceed with pavement marking only on clean, dry surfaces and at a minimum ambient or surface temperature of 40 deg F for alkyd materials and 55 deg F for water-based materials, and not exceeding 95 deg F.
- B. Thermoplastic Pavement-Markings: Proceed with pavement marking only on clean, dry surfaces and at a minimum ambient and pavement surface temperature of 55° F. Maximum pavement temperature shall not exceed 160° F at time of thermoplastic application.

1.7 WARRANTY

- A. Warranty: Replace pavement markings that prematurely deteriorate, failed to adhere to the pavement, lack reflectivity (if applicable) or are otherwise unsatisfactory during the life of the project.

PART 2 - PRODUCTS

2.1 PAVEMENT-MARKINGINGS

- A. Thermoplastic Pavement Markings: Comply with NCDOT Standard Specifications, Sections 1087 and 1205-4.
- B. Glass Beads: AASHTO M 247, Type 1.
 - 1. Roundness: Minimum 80 percent true spheres by weight.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that pavement is dry and in suitable condition to begin pavement marking according to manufacturer's written instructions.
- B. Proceed with pavement marking only after unsatisfactory conditions have been corrected.

3.2 PAVEMENT MARKING

- A. Layout all pavement marking to be reviewed and approved by NCSU Transportation prior to application.
- B. Do not apply thermoplastic pavement markings until layout, colors, and placement have been verified with Designer.
- C. Allow paving to age for a minimum of 30 days before starting pavement marking.
- D. Sweep and clean surface to eliminate loose material and dust.
- E. Apply thermoplastic pavement markings with mechanical equipment to produce pavement markings, of dimensions indicated, with uniform, straight edges. Apply at manufacturer's recommended rates to provide a minimum wet film thickness of 15 mils.
 - 1. Number of Coats: Two; comply with NCDOT Standard Specifications, Section 1205.
 - 2. Apply graphic symbols and lettering with thermoplastic-resistant, die-cut stencils, firmly secured to pavement. Mask an extended area beyond edges of each stencil to prevent thermoplastic marking application beyond the stencil. Apply thermoplastic pavement marking so that it cannot run beneath the stencil.
 - 3. Broadcast glass beads uniformly into wet markings at a rate complying with NCDOT Standard Specifications, Section 1205.

3.3 PROTECTING AND CLEANING

- A. Protect pavement markings from damage and wear during remainder of construction period.
- B. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

3.4 MAINTENANCE

- A. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance. Include monthly preventive maintenance, repair or replacement of worn or defective components as required at no cost to the Owner.

END OF SECTION 321723

SECTION 321726 - TACTILE WARNING SURFACING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Detectable warning unit pavers.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples for Initial Selection: For each type of exposed finish requiring color selection.
- C. Samples for Verification: For each type of tactile warning surface, in manufacturer's standard sizes unless otherwise indicated, showing edge condition, truncated-dome pattern, texture, color, and cross section; with fasteners and anchors.

1.4 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For tactile warning surfacing, to include in maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
 - 1. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.6 PROJECT CONDITIONS

- A. Cold-Weather Protection: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen subgrade or setting beds. Remove and replace unit paver work damaged by frost or freezing.

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of tactile warning surfaces that fail in materials or workmanship within specified warranty period.
1. Failures include, but are not limited to, the following:
 - a. Deterioration of finishes beyond normal weathering and wear.
 - b. Separation or delamination of materials and components.
 2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 TACTILE WARNING SURFACING, GENERAL

- A. Accessibility Requirements: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines for Buildings and Facilities and ICC A117.1 for tactile warning surfaces.
1. For tactile warning surfaces composed of multiple units, provide units that when installed provide consistent side-to-side and end-to-end dome spacing that complies with requirements.
- B. Source Limitations: Obtain each type of tactile warning surfacing from single source with resources to provide materials and products of consistent quality in appearance and physical properties.

2.2 DETECTABLE WARNING UNIT PAVERS

- A. Detectable Warning Concrete Unit Pavers: Solid paving units, made from normal-weight concrete with a compressive strength of not less than 5000 psi, water absorption of not more than 5 percent according to ASTM C 140, and no breakage and not more than 1 percent mass loss when tested for freeze-thaw resistance according to ASTM C 67, with accessible detectable warning truncated domes on exposed surface of units.
1. Basis-of-Design: Subject to compliance with requirements, provide product by Hanover Architectural Products, or a comparable product by one of the following as approved by the Designer:
 - a. Belgard.
 - b. Wausau Tile.
 2. Shapes and Sizes:
 - a. Thickness: 3-1/8 inches.
 - b. Face Size: Nominal 12 by 12 inches.
 3. Truncated Dome Spacing and Configuration: Manufacturer's standard compliant spacing, in square pattern.

4. Color: Charcoal.

B. Aggregate Setting Bed:

1. Graded Aggregate for Base: Sound, crushed stone or gravel complying with ASTM D 448 for Size No. 8.
2. Sand for Leveling Course: Sound, sharp, washed, natural sand or crushed stone complying with gradation requirements in ASTM C 33/C 33M for fine aggregate.
3. Sand for Joints: Fine, sharp, washed, natural sand or crushed stone with 100 percent passing No. 16 sieve and no more than 10 percent passing No. 200 sieve.

2.3 ACCESSORIES

A. Fasteners and Anchors: Manufacturer's standard as required for secure anchorage of tactile warning surfaces, noncorrosive and compatible with each material joined, and complying with the following:

1. Furnish Type 304 stainless-steel fasteners for exterior use.
2. Fastener Heads: For nonstructural connections, use flathead or oval countersunk screws and bolts with tamper-resistant heads, colored to match tile.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that pavement is in suitable condition to begin installation according to manufacturer's written instructions. Verify that installation of tactile warning surfacing will comply with accessibility requirements upon completion.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF TACTILE WARNING SURFACING

- A. General: Prepare substrate and install tactile warning surfacing according to manufacturer's written instructions unless otherwise indicated.
- B. Place tactile warning surfacing units in dimensions and orientation indicated. Comply with location requirements of AASHTO MP 12.

3.3 INSTALLATION OF DETECTABLE WARNING UNIT PAVERS

A. Unit Paver Installation, General:

1. Setting-Bed and Unit Paver Installation: Comply with installation requirements in Section 321400 "Unit Paving."
2. Mix unit pavers from several pallets or cubes, as they are placed, to produce uniform blend of colors and textures.

3. Cut unit pavers with motor-driven masonry saw equipment to provide pattern indicated and to fit adjoining work neatly. Use full units without cutting where possible.
4. Tolerances: Do not exceed 1/4 inch in 10 feet from level, or indicated slope, for finished surface of paving.

B. Aggregate Setting-Bed Applications:

1. Place aggregate base, compact by tamping with plate vibrator, and screed to depth indicated.
2. Place leveling course and screed to a thickness of 1 to 1-1/2 inches, taking care that moisture content remains constant and density is loose and uniform until unit pavers are set and compacted.
3. Treat leveling course with herbicide to inhibit growth of grass and weeds.
4. Set unit pavers with a minimum joint width of 1/16 inch and a maximum of 1/8 inch, being careful not to disturb leveling base. If pavers have spacer bars, place pavers hand tight against spacer bars. Use string lines to keep straight lines.
5. Vibrate pavers into leveling course with a low-amplitude plate vibrator capable of a 3500- to 5000-lbf compaction force at 80 to 90 Hz.
6. Spread dry sand and fill joints immediately after vibrating pavers into leveling course. Vibrate pavers and add sand until joints are completely filled, then remove excess sand. Leave a slight surplus of sand on the surface for joint filling.

3.4 CLEANING AND PROTECTION

- A. Remove and replace tactile warning surfacing that is broken or damaged or does not comply with requirements in this Section. Remove in complete sections from joint to joint unless otherwise approved by Designer. Replace using tactile warning surfacing installation methods acceptable to Designer.
- B. Protect tactile warning surfacing from damage and maintain free of stains, discoloration, dirt, and other foreign material.

END OF SECTION 321726

SECTION 323300 - SITE FURNISHINGS

PART 1 - GENERAL

1.01 SUMMARY

- A. This Section includes the following:
 - 1. Chair.
 - 2. Lounge Furniture

1.02 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples for Initial Selection: For units with factory-applied color finishes.
- C. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.
 - 1. Size: Not less than 6-inch- long linear components and 4-inch- square sheet components.
- D. Product Schedule: For site furnishings. Use same designations indicated on Drawings.
- E. Material Certificates: For site furnishings, signed by manufacturers.
- F. Edit subparagraphs below to suit Project.
 - 1. Wood Preservative Treatment: Include certification by treating plant stating type of preservative solution and pressure process used, net amount of preservative retained, and compliance with applicable standards.
 - 2. Sustainably Harvested Wood: Include certification by manufacturer and from sources that participate in sustained yield programs.
- G. Maintenance Data: For site furnishings to include in maintenance manuals.

1.03 QUALITY ASSURANCE

- A. Source Limitations: Obtain each type of site furnishing(s) through one source from a single manufacturer.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. Aluminum: Alloy and temper recommended by aluminum producer and finisher for type of use and finish indicated; free of surface blemishes and complying with the following:
1. Rolled or Cold-Finished Bars, Rods, and Wire: ASTM B 211.
 2. Extruded Bars, Rods, Wire, Profiles, and Tubes: ASTM B 221.
 3. Structural Pipe and Tube: ASTM B 429.
 4. Sheet and Plate: ASTM B 209.
 5. Castings: ASTM B 26/B 26M.
- B. Steel and Iron: Free of surface blemishes and complying with the following:
1. Plates, Shapes, and Bars: ASTM A 36/A 36M.
 2. Steel Pipe: Standard-weight steel pipe complying with ASTM A 53, or electric-resistance-welded pipe complying with ASTM A 135.
 3. Tubing: Cold-formed steel tubing complying with ASTM A 500.
 4. Mechanical Tubing: Cold-rolled, electric-resistance-welded carbon or alloy steel tubing complying with ASTM A 513, or steel tubing fabricated from steel complying with ASTM A 1011/A 1011M and complying with dimensional tolerances in ASTM A 500; zinc coated internally and externally.
 5. Sheet: Commercial steel sheet complying with ASTM A 1011/A 1011M.
 6. Expanded Metal: Carbon-steel sheets, deburred after expansion, and complying with ASTM F 1267.
 7. Malleable-Iron Castings: ASTM A 47/A 47M, grade as recommended by fabricator for type of use intended.
 8. Gray-Iron Castings: ASTM A 48/A 48M, Class 200.
- C. Stainless Steel: Free of surface blemishes and complying with the following:
1. Sheet, Strip, Plate, and Flat Bars: ASTM A 666.
 2. Pipe: Schedule 40 steel pipe complying with ASTM A 312/A 312M.
 3. Tubing: ASTM A 554.
- D. Wood: Surfaced smooth on four sides with eased edges; kiln dried, free of knots, solid stock of species indicated.
1. Wood Species: Ipe, Teak, Redwood
- E. Fiberglass: Multiple laminations of glass-fiber-reinforced polyester resin with UV-light stable, colorfast, nonfading, weather- and stain-resistant, colored polyester gel coat, and manufacturer's standard finish.
- F. Plastic: Color impregnated, color and UV-light stabilized, and mold resistant.
1. Polyethylene: Fabricated from virgin plastic HDPE resin.
 2. Recycled Polyethylene: Fabricated from not less than [96 percent recycled, purified, fractional-melt plastic resin] <Insert percentage of recycled plastic and resin characteristics> with not less than [90 percent recycled postconsumer waste by weight] <Insert recycled plastic characteristic such as percent postconsumer recycled content> HDPE.

- G. Anchors, Fasteners, Fittings, and Hardware: Manufacturer's standard
 - 1. Angle Anchors: For inconspicuously bolting legs of site furnishings to on or below-grade substrate; extent as indicated.
- H. Nonshrink, Nonmetallic Grout: Premixed, factory-packaged, nonstaining, noncorrosive, nongaseous grout complying with ASTM C 1107; recommended in writing by manufacturer, for exterior applications.
- I. Erosion-Resistant Anchoring Cement: Factory-packaged, nonshrink, nonstaining, hydraulic-controlled expansion cement formulation for mixing with potable water at Project site to create pourable anchoring, patching, and grouting compound; resistant to erosion from water exposure without needing protection by a sealer or waterproof coating; recommended in writing by manufacturer, for exterior applications.
- J. Galvanizing: Where indicated for steel and iron components, provide the following protective zinc coating applied to components after fabrication:
 - 1. Zinc-Coated Tubing: External, zinc with organic overcoat, consisting of a minimum of 0.9 oz./sq. ft. of zinc after welding, a chromate conversion coating, and a clear, polymer film. Internal, same as external or consisting of 81 percent zinc pigmented coating, not less than 0.3 mil thick.
 - 2. Hot-Dip Galvanizing: According to ASTM A 123/A 123M, ASTM A 153/A 153M, or ASTM A 924/A 924M.

2.02 PRODUCTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. See plans (Sheet L7.20) for specified manufacturers, products, colors and materials.

2.03 FABRICATION

- A. Metal Components: Form to required shapes and sizes with true, consistent curves, lines, and angles. Separate metals from dissimilar materials to prevent electrolytic action.
- B. Welded Connections: Weld connections continuously. Weld solid members with full-length, full-penetration welds and hollow members with full-circumference welds. At exposed connections, finish surfaces smooth and blended so no roughness or unevenness shows after finishing and welded surface matches contours of adjoining surfaces.
- C. Pipes and Tubes: Form simple and compound curves by bending members in jigs to produce uniform curvature for each repetitive configuration required; maintain cylindrical cross section of member throughout entire bend without buckling, twisting, cracking, or otherwise deforming exposed surfaces of handrail and railing components.

- D. Preservative-Treated Wood Components: Complete fabrication of treated items before treatment if possible. If cut after treatment, apply field treatment complying with AWPA M4 to cut surfaces.
- E. Exposed Surfaces: Polished, sanded, or otherwise finished; all surfaces smooth, free of burrs, barbs, splinters, and sharpness; all edges and ends rolled, rounded, or capped.
- F. Factory Assembly: Assemble components in the factory to greatest extent possible to minimize field assembly. Clearly mark units for assembly in the field.

2.04 FINISHES, GENERAL

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.05 ALUMINUM FINISHES

- A. Baked-Enamel, Powder-Coat Finish: Manufacturer's standard, baked, polyester, powder-coat finish complying with finish manufacturer's written instructions for surface preparation, including pretreatment, application, baking, and minimum dry film thickness.

2.06 STEEL AND GALVANIZED STEEL FINISHES

- A. Baked-Enamel, Powder-Coat Finish: Manufacturer's standard, baked, polyester, powder-coat finish complying with finish manufacturer's written instructions for surface preparation, including pretreatment, application, baking, and minimum dry film thickness.
- B. PVC Finish: Manufacturer's standard, UV-light stabilized, mold-resistant, slip-resistant, matte-textured, dipped or sprayed-on, PVC-plastisol finish, with flame retardant added; complying with coating manufacturer's written instructions for pretreatment, application, and minimum dry film thickness.

2.07 STAINLESS-STEEL FINISHES

- A. Remove tool and die marks and stretch lines or blend into finish.
- B. Grind and polish surfaces to produce uniform, directionally textured, polished finish indicated, free of cross scratches. Run grain with long dimension of each piece.

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Examine areas and conditions, with Installer present, for compliance with requirements for correct and level finished grade, mounting surfaces, installation tolerances, and other conditions affecting performance.
 - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 INSTALLATION, GENERAL

- A. Comply with manufacturer's written installation instructions unless more stringent requirements are indicated. Complete field assembly of site furnishings where required.
- B. Unless otherwise indicated, install site furnishings after landscaping and paving have been completed.
- C. Install site furnishings level, plumb, true, and securely anchored at locations indicated on Drawings.
- D. Post Setting: Set cast-in support posts in concrete footing with smooth top, shaped to shed water. Protect portion of posts above footing from concrete splatter. Verify that posts are set plumb or at correct angle and are aligned and at correct height and spacing. Hold posts in position during placement and finishing operations until concrete is sufficiently cured.
- E. Posts Set into Voids in Concrete: Form or core-drill holes for installing posts in concrete to depth recommended in writing by manufacturer of site furnishings and 3/4 inch larger than OD of post. Clean holes of loose material, insert posts, and fill annular space between post and concrete with nonshrink, nonmetallic grout, mixed and placed to comply with anchoring material manufacturer's written instructions, with top smoothed and shaped to shed water.

3.03 CLEANING

- A. After completing site furnishing installation, inspect components. Remove spots, dirt, and debris. Repair damaged finishes to match original finish or replace component.

END OF SECTION 323300

SECTION 329100 - PLANTING SOIL

PART 1 – GENERAL

1.01 SUMMARY

- A. The scope of work includes all labor, materials, tools, supplies, equipment, facilities, transportation, and services necessary for, and incidental to performing all operations in connection with furnishing, delivery, and installation of Planting Soil and /or the modification of existing site soil for use as Planting Soil, complete as shown on the drawings and as specified herein.
- B. The scope of work in this section includes, but is not limited to, the following:
 - 1. Locate, purchase, deliver and install Imported Planting Soil and soil amendments.
 - 2. Harvest and stockpile existing site soils suitable for Planting Soil.
 - 3. Modify existing stockpiled site soil.
 - 1. Modify existing site soil in place for use as Planting Soil.
 - 2. Install existing or modified existing soil for use as Planting Soil.
 - 3. Locate, purchase, deliver and install subsurface Drain Lines.
 - 4. Fine grade Planting Soil.
 - 5. Install Compost into Planting Soil.
 - 6. Clean up and disposal of all excess and surplus material.

1.02 CONTRACT DOCUMENTS

- A. Shall consist of specifications, general conditions, and the drawings. The intent of these documents is to include all labor, materials, and services necessary for the proper execution of the work. The documents are to be considered as one. Whatever is called for by any parts shall be as binding as if called for in all parts.

1.03 RELATED DOCUMENTS AND REFERENCES

- A. Related Documents:
 - 1. Drawings and general provisions of contract, including general and supplementary conditions and Division I specifications, apply to work of this section.
 - 2. Related Specification Section
 - 1. Section 01 56 39 – Temporary Tree and Plant Protection
 - 2. Section 32 93 00 - Planting
 - 3. Section 32 92 00 – Turf and Grasses
- B. References: The following specifications and standards of the organizations and documents listed in this paragraph form a part of the Specification to the extent required by the references thereto. In the event that the requirements of the following referenced standards and specification conflict with this specification section the requirements of this specification shall prevail. In the event that the requirements of any of the following referenced standards and specifications conflict with each other the more stringent requirement shall prevail.

1. ASTM: American Society of Testing Materials cited section numbers.
2. U.S. Department of Agriculture, Natural Resources Conservation Service, 2003. National Soil Survey Handbook, title 430-VI. Available Online.
3. US Composting Council
4. Methods of Soil Analysis, as published by the Soil Science Society of America (<http://www.soils.org/>).
5. Up by Roots: healthy soils and trees in the built environment. 2008. J. Urban. International Society of Arboriculture, Champaign, IL.

1.04 VERIFICATION

- A. All scaled dimensions on the drawings are approximate. Before proceeding with any work, the Contractor shall carefully check and verify all dimensions and quantities and shall immediately inform the Owner's Representative of any discrepancies between the information on the drawings and the actual conditions, refraining from doing any work in said areas until given approval to do so by the Owner's Representative.

1.05 PERMITS AND REGULATIONS

- A. The Contractor shall obtain and pay for all permits related to this section of the work unless previously excluded under provision of the contract or general conditions. The Contractor shall comply with all laws and ordinances bearing on the operation or conduct of the work as drawn and specified. If the Contractor observes that a conflict exists between permit requirements and the work outlined in the contract documents, the Contractor shall promptly notify the Owner's Representative in writing including a description of any necessary changes and changes to the contract price resulting from changes in the work.
- B. Wherever references are made to standards or codes in accordance with which work is to be performed or tested, the edition or revision of the standards and codes current on the effective date of this contract shall apply, unless otherwise expressly set forth.
- C. In case of conflict among any referenced standards or codes or among any referenced standards and codes and the specifications, the more restrictive standard shall apply or Owner's Representative shall determine which shall govern.

1.05 PROTECTION OF WORK, PROPERTY AND PERSON

- A. The Contractor shall adequately protect the work, adjacent property, and the public, and shall be responsible for any damages or injury due to the Contractor's actions.

1.06 CHANGES IN WORK

- A. The Owner's Representative may order changes in the work, and the contract sum adjusted accordingly. All such orders and adjustments plus claims by the Contractor for extra compensation must be made and approved in writing before executing the work involved.
- B. All changes in the work, notifications and contractor's request for information (RFI) shall conform to the contract general condition requirements.

1.07 CORRECTION OF WORK

- A. The Contractor shall re-execute any work that fails to conform to the requirements of the contract and shall remedy defects due to faulty materials or workmanship upon written notice from the Owner's Representative, at the soonest possible time that can be coordinated with other work and seasonal weather demands but not more than 180 (one hundred and eighty) days after notification.

1.08 DEFINITIONS

- A. Acceptable drainage: Drainage rate is sufficient for the plants to be grown. Not too fast and not too slow. Typical rates for installed Planting Soil are between 1 - 5 inches per hour. Turf soils are often higher, but drainage rates above 2 - 3 inches per hour will dry out very fast. In natural undisturbed soil a much lower drainage rate, as low as 1/8th inch per hour can still support good plant growth. Wetland plants can grow on top of perched water layers or even within seasonal perched water layers but could become unstable in high wind events.
- B. Amendment: material added to Topsoil to produce Planting Soil Mix. Amendments are classified as general soil amendments, fertilizers, biological, and pH amendments.
- C. Biological Amendment: Amendments such as Mycorrhizal additives, compost tea or other products intended to change the soil biology.
- D. Compacted soil: soil where the density of the soil is greater than the threshold for root limiting, and further defined in this specification.
- E. Compost: well decomposed stable organic material as defined by the US Composting Council and further defined in this specification.
- F. Drainage: The rate at which soil water moves through the soil transitioning the soil from saturated condition to field capacity. Most often expressed as saturated hydraulic conductivity (Ksat; units are inches per hour).
- G. End of Warranty Acceptance: The date when the Owner's Representative accepts that the plants and work in this section meet all the requirements of the warranty. It is intended that the materials and workmanship warranty for Planting, Planting Soil, and Irrigation (if applicable) work run concurrent with each other, and further defined in this specification.
- H. Existing Soil: Mineral soil existing at the locations of proposed planting after the majority of the construction within and around the planting site is completed and just prior to the start of work to prepare the planting area for soil modification and/or planting, and further defined in this specification.
- I. Fertilizer: amendment used for the purpose of adjusting soil nutrient composition and balance.
- J. Fine grading: The final grading of the soil to achieve exact contours and positive drainage, often accomplished by hand rakes or drag rakes or other suitable devices, and further defined in this specification, and further defined in this specification.
- K. Finished grade: surface or elevation of Planting Soil after final grading and 12 months of settlement of the soil, and further defined in this specification.
- L. Graded soil: Soil where the A horizon has been stripped and relocated or re-spread; cuts and fills deeper than 12 inches, and further defined in this specification.
- M. Installed soil: Planting soil and existing site soil that is spread and or graded to form a planting soil, and further defined in this specification.
- N. Minor disturbance: Minor grading as part of agricultural work that only adjusts the A horizon soil, minor surface compaction in the top 6 inches of the soil, applications of fertilizers, installation of utility pipes smaller than 18 inches in diameter thru the soil zone.
- O. Owner's Representative: The person or entity, appointed by the Owner to represent their interest

- in the review and approval of the work and to serve as the contracting authority with the Contractor. The Owner's Representative may appoint other persons to review and approve any aspects of the work.
- P. Ped: a clump or clod of soil held together by a combination of clay, organic matter, and fungal hyphae, retaining the original structure of the harvested soil.
 - Q. Planting Soil: Topsoil, or Planting Soil Mixes which are imported or existing at the site, or made from components that exist at the site, or are imported to the site; and further defined in this specification.
 - R. Poor drainage: Soil drainage that is slower than that to which the plants can adapt. This is a wide range of metrics, but generally if the soil is turning grey in color it is reasonable preferable to either to plant moisture adaptive plants at smaller sizes that are young in age with shallow root balls or look at options to improve the drainage
 - S. Scarify: Loosening and roughening the surface of soil and sub soil prior to adding additional soil on top, and further defined in this specification.
 - T. Soil Fracturing: Deep loosening the soil to the depths specified by using a back hoe, and further defined in this specification.
 - U. Soil Horizons: as defined in the USDA National Soil Survey Handbook
http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242.
 - V. Soil Ripping: Loosening the soil by dragging a ripping shank or chisel thru the soil to the depths and spacing specified, and further defined in this specification.
 - W. Soil Tilling: Loosening the surface of the soil to the depths specified with a rotary tine tilling machine, roto tiller, (or spade tiller), and further defined in this specification.
 - X. Soil trenching: Cutting narrow trenches thru the soil at the depths and spacing specified to loosen the soil profile, and further defined in this specification.
 - Y. Subgrade: surface or elevation of subsoil remaining after completing excavation, or top surface of a fill or backfill, before placing Planting Soil.
 - Z. Substantial Completion Acceptance: The date at the end of the Planting, Planting Soil, and Irrigation installation (if applicable) where the Owner's Representative accepts that all work in these sections is complete, and the Warranty period has begun. This date may be different than the date of substantial completion for the other sections of the project, and further defined in this specification.
 - AA. Topsoil: naturally produced and harvested soil from the A horizon or upper layers or the soil as further defined in this specification.
 - BB. Undisturbed soil: Soils with the original A horizon intact that have not been graded or compacted. Soils that have been farmed, subjected to fire or logged but not graded, and natural forested land will be considered as undisturbed.

1.09 SUBMITTALS

- A. See the contract General Conditions for policy and procedures related to submittals.
- B. Submit all product submittals eight weeks prior to the start of the soil work.
- C. Product data and certificates: For each type of manufactured product, submit data and certificates that the product meets the specification requirements, signed by the product manufacturer, and complying with the following:
 - 1. Submit manufacturers or supplier's product data and literature certified analysis for standard

products and bulk materials, complying with testing requirements and referenced standards and specific requested testing.

1. For each Compost product submit the following analysis by a recognized laboratory:
 - 1.) pH
 - 2.) Salt concentration (electrical conductivity)
 - 3.) Moisture content %, wet weight basis
 - 4.) Particle size % passing a selected mesh size, dry weight basis
 - 5.) Stability carbon dioxide evolution rate mg CO₂-C per g OM per day
 - 6.) Solvita maturity test
 - 7.) Physical contaminants (inerts) %, dry weight basis
 - 8.) US EPA Class A standard, 40CFR § 503.13, Tables 1 and 3 levels Chemical Contaminants mg/kg (ppm)
 2. For Coarse Sand product submit the following analysis by a recognized laboratory:
 - 1.) pH
 - 2.) Particle size distribution (percent passing the following sieve sizes):
 - 3/8 inch (9.5 mm)
 - No 4 (4.75 mm)
 - No 8 (2.36 mm)
 - No 16(1.18 mm)
 - No 30 (.60 mm)
 - No 50 (.30 mm)
 - No 100 (.15 mm)
 - No 200 (.075 mm)
- D. Samples: Submit samples of each product and material, where required by Part 2 of the specification, to the Owner's Representative for approval. Label samples to indicate product, characteristics, and locations in the work. Samples will be reviewed for appearance only.
1. Submit samples a minimum of 8 weeks prior to the anticipated date of the start of soil installation.
 2. Samples of all Topsoil, Coarse Sand, Compost and Planting Soil shall be submitted at the same time as the particle size and physical analysis of that material.
- E. Soil testing for Imported and Existing Topsoil, existing site soil to be modified as Planting Soil and Planting Soil Mixes.
1. Topsoil, existing site soil and Planting Soil Mix testing: Submit soil test analysis report for each sample of Topsoil, existing site soil and Planting Soil from an approved soil-testing laboratory and where indicated in Part 2 of the specification as follows:
 1. Submit Topsoil, Planting Soil, Compost, and Coarse Sand for testing at least 8 weeks before scheduled installation of Planting Soil Mixes. Submit Planting Soil Mix test no more than 2 weeks after the approval of the Topsoil, Compost and Coarse Sand. Do not submit to the testing laboratory, Planting Soil Mixes, for testing until all Topsoil, Compost and Coarse Sand have been approved.
 2. If tests fail to meet the specifications, obtain other sources of material, retest and resubmit until accepted by the Owner's Representative.
 3. All soil testing will be at the expense of the Contractor.
 2. Provide a particle size analysis (% dry weight) and USDA soil texture analysis. Soil testing of Planting Soil Mixes shall also include USDA gradation (percentage) of gravel, coarse sand, medium sand, and fine sand in addition to silt and clay.
 3. Provide the following other soil properties:
 1. pH and buffer pH.
 2. Percent organic content by oven dried weight.
 3. Nutrient levels by parts per million including: phosphorus, potassium, magnesium,

manganese, iron, zinc and calcium. Nutrient test shall include the testing laboratory recommendations for supplemental additions to the soil for optimum growth of the plantings specified.

4. Soluble salt by electrical conductivity of a 1:2 soil water sample measured in Milliohm per cm.
5. Cation Exchange Capacity (CEC).

F. Shop Drawings:

1. Submit layouts and details of the structural soil system for review.

1.09 SOIL INSTALLATION MOCKUP

- A. Prior to installation or modification of Topsoil, site soil, Planting Soil, or Planting Soil Mixes, construct at the site, a mockup of each soil type using the means and methods and equipment proposed by the Contractor to complete the work. Installation of the mockup shall be in the presence of the Owner's Representative. The purpose of the mockup is to test the methods of installation and compaction of the soil and to serve as a benchmark for completed soil compaction and serve to calibrate penetrometer readings to the known proctor density of the mockup. The mockup shall be as follows:
1. Following acceptance of the soil submittals, in areas that can be protected from disturbance and further compaction, install mockups of each soil type and soil modification, 20-foot X 20 foot X the full depth of the deepest installation, using the requirements of these specifications. Compaction methods, including the type of compaction equipment and number of passes required to achieve the required compaction, shall be evaluated and results measured.
 2. Compaction in the mockup soil shall be tested using the penetrometer. A minimum of four penetrometer readings from each Planting Soil shall be taken at the specified depths of the soil profile. Record the soil moisture at each penetrometer test site. In the event that the penetrometer readings exceed the specified densities, reconstruct the mockup, adjusting the soil density to achieve the desired results. Where the modification requires ripping, tilling or fracturing soils that are over compacted, start the procedure in a new location so that the process is working on soil that is similar to the density of the expected soil.
 3. Submit a report of the final methods of soil installation, the penetrometer and soil moisture readings to the Owner's Representative.
 4. The mockup area may remain as part of the installed work at the end of the project if protected from further compaction, contamination or other disturbance.
 5. Provide a protective 4-foot-high fence on metal posts around each mockup to keep all work and equipment from entering the surface of the mockup area.

1.10 OBSERVATION OF THE WORK

- A. The Owner's Representative may observe the work at any time. They may remove samples of materials for conformity to specifications. Rejected materials shall be immediately removed from the site and replaced at the Contractor's expense. The cost of testing materials not meeting specifications shall be paid by the Contractor.
1. The Owner's Representative may utilize the Contractor's penetrometer and moisture meter at any time to check soil compaction and moisture.
- B. The Owner's Representative shall be informed of the progress of the work so the work may be observed at the following key times in the construction process. The Owner's Representative shall be afforded sufficient time to schedule visit to the site. Failure of the Owner's

Representative to make field observations shall not relieve the Contractor from meeting all the requirements of this specification.

1. SOIL MOCKUP REVIEW: At the time of construction of all soil mockups.
2. EXISTING SOIL CONDITIONS REVIEW: Prior to the start of any soil modification that will utilize or modify the existing soil.
3. EXCAVATION REVIEW: Observe each area of excavation prior to the installation of any Planting Soil.
4. DRAIN LINE INSTALLATION REVIEW: Upon completion of the installation of drain lines and prior to the installation of any Planting Soil
5. COMPLETION of SOIL MODIFICATIONS REVIEW: Upon completion of all soil modification and installation of planting soil.
6. COMPLETION OF FINE GRADING AND SURFACE SOIL MODIFICATIONS REVIEW: Upon completion of all surface soil modifications and fine grading but prior to the installation of shrubs, ground covers, or lawns.

1.11 PRE-CONSTRUCTION CONFERENCE

- A. Schedule a pre-construction meeting with the Owner's Representative at least seven (7) days before beginning work to review any questions the Contractor may have regarding the work, administrative procedures during construction and project work schedule.

1.12 QUALITY ASSURANCE

- A. Installer Qualifications: The installer shall be a firm having at least 5 years of experience of a scope similar to that required for the work, including the preparation, mixing and installation of soil mixes to support planting. The installer of the work in Section: Planting, shall be the same firm installing the work in this section.
 1. The bidders list for work under this section shall be approved by the Owner's Representative.
 2. Installer Field Supervision: When any Planting Soil work is in progress, installer shall maintain, on site, an experienced full-time supervisor who can communicate in English with the Owner's Representative.
 3. Installer's field supervisor shall have a minimum of five years' experience as a field supervisor installing soil, shall be trained and proficient in the use of field surveying equipment to establish grades and can communicate in English with the Owner's Representative.
 4. The installer's crew shall be experienced in the installation of Planting Soil, plantings, and irrigation (where applicable) and interpretation of planting plans, soil installation plans, and irrigation plans (where applicable).
 5. Submit references of past projects and employee training certifications that support that the Contractors meet all of the above installer qualifications and applicable licensures.
- B. Soil testing laboratory qualifications: an independent laboratory, with the experience and capability to conduct the testing indicated and that specializes in USDA agricultural soil testing, Planting Soil Mixes, and the types of tests to be performed. Geotechnical engineering testing labs shall not be used.
- C. All delivered and installed Planting Soil shall conform to the approved submittals sample color,

- texture, and approved test analysis.
1. The Owner's Representative may request samples of the delivered or installed soil be tested for analysis to confirm the Planting Soil conforms to the approved material.
 2. All testing shall be performed by the same soil lab that performed the original Planting Soil testing.
 3. Testing results shall be within 10% plus or minus of the values measured in the approved Planting Soil Mixes.
 4. Any Planting Soil that fails to meet the above criteria, if requested by the Owner's Representative, shall be removed and new soil installed.
- D. Soil compaction testing: following installation or modification of soil, test soil compaction with a penetrometer.
1. Maintain at the site at all times a soil cone penetrometer with pressure dial and a soil moisture meter to check soil compaction and soil moisture.
 1. Penetrometer shall be AgraTronix Soil Compaction Meter distributed by Ben Meadows, www.benmeadows.com or approved equal.
 2. Moisture meter shall be "general digital soil moisture meter" distributed by Ben Meadows, www.benmeadows.com or approved equal.
 2. Prior to testing the soil with the penetrometer check the soil moisture and penetrometer readings in the mockup soils. Penetrometer readings are impacted by soil moisture and excessively wet or dry soils will read significantly lower or higher than soils at optimum moisture.
 3. The penetrometer readings shall be within 20% plus or minus of the readings in the approved mockup when at similar moisture levels.

1.13 SITE CONDITIONS

- A. It is the responsibility of the Contractor to be aware of all surface and subsurface conditions, and to notify the Owner's Representative, in writing, of any circumstances that would negatively impact the health of plantings. Do not proceed with work until unsatisfactory conditions have been corrected.
1. Should subsurface drainage or soil conditions be encountered which would be detrimental to growth or survival of plant material, the Contractor shall notify the Owner's Representative in writing, stating the conditions and submit a proposal covering cost of corrections. If the Contractor fails to notify the Owner's Representative of such conditions, they shall remain responsible for plant material under the warranty clause of the specifications.
 2. This specification requires that all Planting Soil and Irrigation (if applicable) work be completed and accepted prior to the installation of any plants.

1.14 SOIL COMPACTION – GENERAL REQUIREMENTS

- A. Except where more stringent requirements are defined in this specification. The following parameters shall define the general description of the threshold points of soil compaction in existing, modified, or installed soil and subsoil.
- B. The following are threshold levels of compaction as determined by each method.
1. Acceptable Compaction: Good rooting anticipated, but increasing settlement expected as compaction is reduced and/or in soil with a high organic matter content.
 1. Bulk Density Method – Varies by soil type see Chart on page 32 in Up By Roots.

2. Standard Proctor Method – 75-85%; soil below 75% is unstable and will settle excessively.
3. Penetration Resistance Method – about 75-250 psi, below 75 psi soil becomes increasingly unstable and will settle excessively.
2. Root limiting Compaction: Root growth is limited with fewer, shorter and slower growing roots.
 1. Bulk Density Method – Varies by soil type see Chart on page 32 in Up By Roots.
 2. Standard Proctor Method – above approximately 85%.
 3. Penetration Resistance Method – about 300 psi.
3. Excessive Compaction: Roots not likely to grow but can penetrate soil when soil is above field capacity.
 1. Bulk Density Method – Varies by soil type see Chart on page 32 in Up By Roots.
 2. Standard Proctor Method – Above 90%.
 3. Penetration Resistance Method – Approximately above 400 psi
4. Allowed Compaction Testing Method: Penetration Resistance Method

1.15 DELIVERY, STORAGE, AND HANDLING

- A. Weather: Do not mix, deliver, place or grade soils when frozen or with moisture above field capacity.
- B. Protect soil and soil stockpiles, including the stockpiles at the soil blender's yard, from wind, rain and washing that can erode soil or separate fines and coarse material, and contamination by chemicals, dust and debris that may be detrimental to plants or soil drainage. Cover stockpiles with plastic sheeting or fabric at the end of each workday.
- C. All manufactured packaged products and material shall be delivered to the site in unopened containers and stored in a dry enclosed space suitable for the material and meeting all environmental regulations. Biological additives shall be protected from extreme cold and heat. All products shall be freshly manufactured and dated for the year in which the products are to be used.
- D. Deliver all chemical amendments in original, unopened containers with original labels intact and legible, which state the guaranteed chemical analysis. Store all chemicals in a weather protected enclosure.
- E. Bulk material: Coordinate delivery and storage with Owner's Representative and confine materials to neat piles in areas acceptable to Owner's Representative.

1.16 EXCAVATING AND GRADING AROUND UTILITIES

- A. Contractor shall carefully examine the civil, record, and survey drawings to become familiar with the existing underground conditions before digging.
- B. Determine location of underground utilities and perform work in a manner that will avoid damage. Hand excavate as required. Maintain grade stakes set by others until parties concerned mutually agree upon removal.
- C. Notification of the local utility locator service is required for all planting areas. The Contractor is responsible for knowing the location and avoiding utilities that are not covered by the local utility locator service.

PART 2 – PRODUCTS

2.01 COMPOST

- A. Compost: Blended and ground leaf, wood and other plant-based material, composted for a minimum of 9 months and at temperatures sufficient to break down all woody fibers, seeds and leaf structures, free of toxic material at levels that are harmful to plants or humans. Source material shall be yard waste trimmings blended with other plant or manure-based material designed to produce Compost high in fungal material.
 - 1. Compost shall be commercially prepared Compost and meet US Compost Council STA/TMECC criteria or as modified in this section for “Compost as a Landscape Backfill Mix Component”.
http://compostingcouncil.org/admin/wp-content/plugins/wp-pdfupload/pdf/191/LandscapeArch_Specs.pdf
 - 2. Compost shall comply with the following parameters:
 - 1. pH: 5.5 - 8.0.
 - 2. Soil salt (electrical conductivity): maximum 5 dS/m (mmhos/cm).
 - 3. Moisture content %, wet weight basis: 30 – 60.
 - 4. Particle size, dry weight basis: 98% pass through 3/4 inch screen or smear.
 - 5. Stability carbon dioxide evolution rate: mg CO₂-C/ g OM/ day < 2.
 - 6. Solvita maturity test: > 6.
 - 7. Physical contaminants (inerts), %, dry weight basis: <1%.
 - 8. Chemical contaminants, mg/kg (ppm): meet or exceed US EPA Class A standard, 40CFR § 503.13, Tables 1 and 3 levels.
 - 9. Biological contaminants select pathogens fecal coliform bacteria, or salmonella, meet or exceed US EPA Class A standard, 40 CFR § 503.32(a) level requirements.
- B. Provide a two-gallon sample with manufacturer’s literature and material certification that the product meets the requirements.

2.02 COARSE SAND

- A. Clean, washed, sand, free of toxic materials
 - 1. Coarse concrete sand, ASTM C-33 Fine Aggregate, with a Fines Modulus Index of 2.8 and 3.2.
 - 2. Coarse Sands shall be clean, sharp, natural Coarse Sands free of limestone, shale and slate particles. Manufactured Coarse Sand shall not be permitted.
 - 3. pH shall be lower than 7.0.
 - 4. Provide Coarse Sand with the following particle size distribution:

Sieve	Percent passing
3/8 inch (9.5 mm)	100
No 4 (4.75 mm)	95-100
No 8 (2.36 mm)	80-100
No 16 (1.18 mm)	50-85
No 30 (.60 mm)	25-60
No 50 (.30 mm)	10-30
No 100 (.15 mm)	2-10
No 200 (0.75 mm)	2-5
- B. Provide a two-gallon sample with manufacturer’s literature and material certification that the product meets the requirements.

2.03 FERTILIZER, BIOLOGICAL AND OTHER AMENDMENTS

- A. As required based upon review of required soil testing.

2.04 LIME

- A. ASTM C 602, agricultural limestone containing a minimum 80 percent calcium carbonate equivalent and as follows:
 - 1. Class: Class T, with a minimum 99 percent passing through No. 8 (2.36-mm) sieve and a minimum 75 percent passing through No. 60 (0.25-mm) sieve.
 - 2. Provide lime in form of dolomitic limestone.
- B. Provide manufacturer's literature and material certification that the product meets the requirements.

2.05 EXISTING IN-SITU SOIL (Acceptable for planting with minimum modifications)

- A. General definition of existing soil: Surface soil in the areas designated on the soils plan as existing soil, that is not altered, compacted to root limiting density, graded or contaminated before or during the construction process and considered acceptable for planting and long-term health of the plants specified either as it exists or with only minor modification.
 - 1. The Owner's Representative shall verify that the soil in the designated areas is suitable at the beginning of planting bed preparation work in that area. In the event that the work of this project construction has damaged the existing soil in areas designated for use as Planting Soil to the point where the soil is no longer suitable to support the plants specified, the Owner's Representative may require modification of the damaged soil up to and including removal and replacement with soil of equal quality to the soil that existed prior to construction. Examples of damage include further compaction, contamination, grading, creation of hard pan or drainage problems, and loss of the O, and or A horizon.
 - 1. Do not begin work on additional modifications until changes to the contract price are approved by Owner's Representative.
 - 2. Soil testing results and soil observation notes that describe the pre-construction soil conditions in the existing soil areas are included as an appendix to this specification:
- B. Protect existing soil from compaction, contamination, and degradation during the construction process.
- C. Unless otherwise instructed, remove all existing plants, root thatch, and non-soil debris from the surface of the soil using equipment that does not increase compaction of soil to root limiting levels.
- D. Modifications:
 - 1. When results of soil tests recommend chemical adjustments, till surface soil to six inches or greater after chemical adjustments have been applied.
 - 2. Remove existing turf thatch, ground cover plants and weeds.
 - 3. Provide pre-emergent weed control if indicated.
 - 4. Make chemical adjustment as recommended by the soil test.

2.06 PLANTING SOIL TYPE C: MODIFIED EXISTING SOIL (SOIL SUITABLE FOR PLANTING WITH

INDICATED MODIFICATION)

- A. General definition: Surface soil in the areas designated on the soils plan as Modified Existing Soil has been altered and or graded before or during the construction process but is still considered acceptable for planting and long-term health of the plants specified with the proposed modifications. Modifications respond to the soil problems expected or encountered. The Owner's Representative shall verify that the soil in the designated areas is suitable for modification at the beginning of planting bed preparation work in that area.
1. The Owner's Representative shall verify that the soil in the designated areas is suitable for the specified modification at the beginning of planting bed preparation work in that area. In the event that the work of this project construction has damaged the existing soil in areas designated for modification to the point where the soil is no longer suitable to support the plants specified with the specified modification, the Owner's Representative may require further modification of the damaged soil up to an including removal and replacement with soil of equal quality to the soil that would have resulted from the modification. Damage may include further compaction, contamination, grading, creation of hard pan or drainage problem, and loss of the O, and or A horizon.
 2. General requirements for all soil modifications:
 1. Take soil samples, test for chemical properties, and make appropriate adjustments.
 2. Unless otherwise instructed, remove all existing plants, root thatch, and non-soil debris from the surface of the soil using equipment that does not add to the compaction in the soil.
 3. All soil grading, tilling and loosening must be completed at times when the soil moisture is below field capacity. Allow soil to drain for at least two days after any rain event more than 1 inch in 24 hours, or long enough so that the soil does not make the hand muddy when squeezed.
 4. Provide pre-emergent weed control after the soil work is complete and plants planted but prior to adding mulch to the surface, if indicated by weed type and degree of threat.
- B. Modified existing soil – soil removed, stockpiled, and spread
1. Description of condition to be modified: Existing soil that is suitable for reuse as Planting Soil but is in the wrong place of elevation or cannot be adequately protected during construction. Soil is to be harvested, stockpiled and re-spread with or without further modifications as indicated.
 2. Modifications:
 1. Excavate existing soil from the areas and to depths designated on the drawings. Stockpile in zones noted on the drawings or in areas proposed by the Contractor.
 - 1.) Prepare a soil stockpile plan for approval.
 2. Excavate soil using equipment and methods to preserve the clumps and peds in the soil. Generally this means using the largest piece of equipment that is practical for the project size and scope.
 3. Protect stockpiles from erosion by compacting or tracking the soil surface, covering with breathable fabric or planting with annual grasses as appropriate for the season, location, and length of expected time of storage.
 4. Re-spread soil as required in Part 3 of this specification.
- C. Modified existing soil – compacted surface soil (Tilling Option)
1. Description of condition to be modified: Surface soil compaction to a maximum of 6 inches deep from traffic or light grading. Original A horizon may be previously removed or graded but lower profile intact with acceptable compaction levels and limited grading. The soil organic matter, pH and chemistry in the A horizon may not be suitable for the proposed plants and may need to be modified as required.

2. Modifications:
 1. Till top 6 inches or deeper of the soil surface, with a roto tiller, spade tiller, ripper or agricultural plow. Spread 2 - 3 inches of Compost on the surface of the tilled soil and make any chemical adjustment as recommended by the soil test.
 2. Till or disk the Compost into the loosened soil. Smooth out grades with a drag rake or drag slip.
- D. Modified existing soil – compacted surface soil (Radial Trenching Option)
 1. Description of condition to be modified: Surface soil compaction to a maximum of 24 inches deep from traffic or light grading. Original A horizon may be previously removed or graded but lower profile below 24 inches intact with acceptable compaction levels and limited grading. The soil organic matter, pH and chemistry in the A horizon may not be suitable for the proposed plants and may need to be modified as required.
 2. Modifications:
 1. Using a trenching machine, dig trenches to the extent and depth shown on the plans and details.
 2. Backfill the trench with the soil removed from the trench. Add additional site soil if needed to fill the trench to be flush to the existing grade after the soil settlement.
- E. Modified existing soil – compacted subsoil
 1. Description of condition to be modified: Deep soil compaction the result of previous grading, filling and dynamic or static compaction forces. Original A horizon likely removed or buried. The soil organic matter, pH and chemistry in the A horizon is likely not suitable for the proposed plants and should be modified as required.
 2. Soil Ripping:
 1. Step one: After grading and removing all plants and debris from the surface, using a tracked dozer or similar large grading equipment, loosen the soil by dragging a ripping shank or chisel thru the soil to depths of 24 inches with ripping shanks spaced 18 inches or less apart in two directions. The number of shanks per pull is dependent on the degree of soil compaction and the size of the dozer.
 2. Step 2: Spread 3-4 inches of Compost over the ripped area and till into the top 6 inches of the soil surface.
 3. Soil Fracturing:
 1. Step one: After grading and removing all plants and debris from the surface, spread 2 – 3 inches of Compost over the surface of the soil. Loosen the soil to depth of 18 - 24 inches, using a backhoe to dig into the soil through the Compost. Lift and then drop the loosened soil immediately back into the hole. The bucket then moves to the adjacent soil and repeats the process until the entire area indicated has been loosened.
 2. Step 2: Spread 3-4 inches of Compost over the ripped area and till into the top 6 inches of the soil surface.
 4. Trenching:
 1. Step one: After grading and removing all plants and debris from the surface using a chain trenching machine, dig 24-inch-deep trenches, 24 inches apart across the entire area. Maintain an 18-inch standoff from the edges of all curbs, paving and structures. Backfill the trenches with Compost.
 2. Step 2: Spread 3-4 inches of Compost over the trenches area and till into the top 6 inches of the soil surface. Compost tilling treatment shall extend to the edges of curbs, paving and structures.
 5. Following soil ripping or fracturing the average penetration resistance should be less than 250 psi to the depth of the ripping or fracturing.

6. Do not start planting into ripped or fractured soil until soil has been settled or leave grades sufficiently high to anticipate settlement of 10 – 15% of ripped soil depth.
- F. Modified existing soil – low organic matter
1. Description of condition to be modified: Low soil organic matter and/or missing A horizon but soil is not compacted except for some minor surface compaction. The soil organic matter, pH and/or chemistry are likely not suitable for the proposed plants and should be modified as required.
 2. Modifications:
 1. Spread 3 - 4 inches of Compost over the surface of the soil and make chemical adjustment as recommended by the soil test.
 2. Till Compost into the top 6 inches of the soil.
- G. Modified existing soil – soil within the root zone of existing established trees
1. Description of condition to be modified: Surface compaction near or above root limited levels in the upper soil horizon the result of traffic or other mechanical compaction.
 2. Modifications:
 1. Remove the tops of all plants to be removed from the root zone. Remove sod with a walk behind sod cutter. Do not grub out the roots of plants to be removed.
 2. Use a pneumatic air knife to loosen the top 9 – 12 inches of the soil. Surface roots may move and separate from soil during this process but the bark on roots should not be broken
 - 1.) Pneumatic air knife shall be as manufactured by:
Concept Engineering Group, Inc., Verona, PA (412) 826-8800
or
Supersonic Air Knife, Inc., Allison Park, PA (866) 328 5723
 3. Make chemical adjustment as recommended by the soil test and add 2 - 3 inches of Compost over the soil.
 4. Using the pneumatic air knife, mix the Compost into the top 6 – 8 inches of the loosened soil.
 5. Work in sections such that the entire process - including irrigation - can be completed in one day. Apply approximately one inch of water over the loosened soil at the completion of each day's work. Apply mulch or turf as indicated on the drawings within one week of the completion of work.
- 2.07 PLANTING SOIL TYPE A: IMPORTED OR MANUFACTURED TOPSOIL
- A. Manufactured or imported topsoil is suitable topsoil procured from off-site sources.
 - B. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land bogs, or marshes.
 - C. Imported Topsoil for Planting Soil shall NOT have been screened and shall retain soil peds or clods larger than 2 inches in diameter throughout the stockpile after harvesting.
 - D. Stockpiled Existing Topsoil at the site meeting the above criteria may be acceptable.
 - E. Provide a two-gallon sample from each Imported Topsoil source with required soil testing results. The sample shall be a mixture of the random samples taken around the source stockpile or field. The soil sample shall be delivered with soil peds intact that represent the size and quantity of expected peds in the final delivered soil.
 - F. Additional Properties of Imported Topsoil or Manufactured Topsoil: free of stones 1 inch or larger in any dimension; free of roots, plants, sod, clay lumps, pockets of coarse sand, paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, building debris, oils,

gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, acid, and other extraneous materials harmful to plant growth; free of obnoxious weeds and invasive plants including quackgrass, Johnsongrass, poison ivy, nutsedge, nimblewill, Canada thistle, bindweed, bentgrass, wild garlic, ground ivy, perennial sorrel, and bromegrass; not infested with nematodes; grubs; or other pests, pest eggs, or other undesirable organisms and disease-causing plant pathogens; friable and with sufficient structure to give good tilth and aeration. Continuous, air-filled pore space content on a volume/volume basis shall be at least 15 percent when moisture is present at field capacity. Soil shall have a field capacity of at least 15 percent on a dry weight basis.

- G. Mix imported topsoil or manufactured topsoil with the following soil amendments and fertilizers in the following quantities to produce planting soil.
 - a. Ratio of soil conditioner to Topsoil by Volume: 1:10.
 - b. Weight of Slow-Release Fertilizer as per soil test.
 - c. Weight of dolomitic limestone as per soil test.

2.08 PLANTING SOIL TYPE B: SOIL IN STRUCTURAL SOIL CELL

- A. Product: StrataCell by GreenBlue Urban or Silva Cell by Deeproot
- B. Submit shop drawings showing layout and details of structural soil system for review and approval.
- C. Install per manufacturer's written specifications.
- D. Soil mix should be a screened sandy loam with 4-8% organic content by volume.

2.09 PLANTING SOIL TYPE E: LIGHTWEIGHT ON-STRUCTURE PLANTING SOIL

- A. Mix produced by modifying planting soil as follows:
 - 1. Manufacturer: American Hydrotech, Inc
 - 2. Soil Mix Name: Intensive LiteTop® Growing Media

2.10 PLANTING SOIL TYPE F: BIO-RETENTION PLANTING SOIL (NCDENR APPROVED)

- A. Soil mix approved by NCDENR for use in regulated bio-retention planting beds.

2.11 PLANTING SOIL TYPE G: STRUCTURAL SOILS

- A. Reference Section 32 91 13 – Structural Soil Mixing.

2.12 LANDSCAPING DRAINAGE

- A. Reference Section 33 46 00 - Subdrainage

2.13 PRE-EMERGENT HERBICIDES

- A. Chemical herbicides are designed to prevent seeds of selective plants from germinating. Exact type of herbicide shall be based on the specific plants to be controlled and the most effective date of application.
- B. Submit report of expected weed problems and the recommendation of the most effective control for approval by Owner's Representative. Provide manufacturer's literature and material certification that the product meets the requirements.

PART 3 EXECUTION

3.01 SITE EXAMINATION

- A. Prior to installation of Planting Soil, examine site to confirm that existing conditions are satisfactory for the work of this section to proceed.
 - 1. Confirm that the subgrade is at the proper elevation and compacted as required. Subgrade elevations shall slope toward the under-drain lines as shown on the drawings.
 - 2. Confirm that surface all areas to be filled with Planting Soil are free of construction debris, refuse, compressible or biodegradable materials, stones greater than 2 inches diameter, soil crusting films of silt or clay that reduces or stops drainage from the Planting Soil into the subsoil; and/or standing water. Remove unsuitable material from the site.
 - 3. Confirm that no adverse drainage conditions are present.
 - 4. Confirm that no conditions are present which are detrimental to plant growth.
 - 5. Confirm that utility work has been completed per the drawings.
 - 6. Confirm that irrigation work, which is shown to be installed below prepared soil levels, has been completed.
- B. If unsatisfactory conditions are encountered, notify the Owner's Representative immediately to determine corrective action before proceeding.

3.02 COORDINATION WITH PROJECT WORK

- A. The Contractor shall coordinate with all other work that may impact the completion of the work.
- B. Prior to the start of work, prepare a detailed schedule of the work for coordination with other trades.
- C. Coordinate the relocation of any irrigation lines, heads or the conduits of other utility lines that are in conflict with tree locations. Root balls shall not be altered to fit around lines. Notify the Owner's Representative of any conflicts encountered.

3.03 GRADE AND ELEVATION CONTROL

- A. Provide grade and elevation control during installation of Planting Soil. Utilize grade stakes, surveying equipment, and other means and methods to assure that grades and contours conform to the grades indicated on the plans.

3.04 SITE PREPARATION

- A. Excavate to the proposed subgrade. Maintain all required angles of repose of the adjacent materials as shown on the drawings or as required by this specification. Do not over excavate compacted subgrades of adjacent pavement or structures. Maintain a supporting 1:1 side slope of compacted subgrade material along the edges of all paving and structures where the bottom of the paving or structure is above the bottom elevation of the excavated planting area.
- B. Remove all construction debris and material including any construction materials from the subgrade.
- C. Confirm that the subgrade is at the proper elevation and compacted as required. Subgrade elevations shall slope approximately parallel to the finished grade and/or toward the subsurface drain lines as shown on the drawings.
- D. In areas where Planting Soil is to be spread, confirm subgrade has been scarified.
- E. Protect adjacent walls, walks and utilities from damage or staining by the soil. Use 1/2 inch plywood and or plastic sheeting as directed to cover existing concrete, metal and masonry work and other items as directed during the progress of the work.
 - 1. At the end of each working day, clean up any soil or dirt spilled on any paved surface.

2. Any damage to the paving or site features or work shall be repaired at the Contractor's expense.

3.05 SOIL MOISTURE

A. Volumetric soil moisture level, in both the Planting Soil and the root balls of all plants, prior to, during and after planting shall be above permanent wilt point and below field capacity for each type of soil texture within the following ranges.

Soil texture	Permanent wilting point	Field capacity
Sand, Loamy sand, Sandy loam	5-8%	12-18%
Loam, Sandy clay, Sandy clay loam	14-25%	27-36%
Clay loam, Silt loam	11-22%	31-36%
Silty clay, Silty clay loam	22-27%	38-41%

B. The Contractor shall confirm the soil moisture levels with a moisture meter (Digital Soil Moisture Meter, DSMM500 by General Specialty Tools and Instruments, or approved equivalent). If moisture is found to be too low, the planting holes shall be filled with water and allowed to drain before starting any planting operations. If the moisture is too high, suspend planting operations until the soil moisture drains to below field capacity.

3.06 EXISTING SOIL MODIFICATION

A. Follow the requirements for modifying existing soil as indicated in Part 2 for the different types of soil modifications. The extent of the areas of different soil modification types are indicated on the Soils Plan or as directed by the Owner's Representative.

3.07 PLANTING SOIL AND PLANTING SOIL MIX INSTALLATION

- A. Prior to installing any Planting Soil from stockpiles or Planting Soil Mixes blended off site, the Owner's Representative shall approve the condition of the subgrade and the previously installed subgrade preparation and the installation of subsurface drainage.
- B. All equipment utilized to install or grade Planting Soils shall be wide track or balloon tire machines rated with a ground pressure of 4 psi or less. All grading and soil delivery equipment shall have buckets equipped with 6-inch-long teeth to scarify any soil that becomes compacted.
- C. In areas of soil installation above existing subsoil, scarify the subgrade material prior to installing Planting Soil.
 - 1. Scarify the subsoil of the subgrade to a depth of 3 – 6 inches with the teeth of the back hoe or loader bucket, tiller or other suitable device.
 - 2. Immediately install the Planting Soil. Protect the loosened area from traffic. DO NOT allow the loosened subgrade to become compacted.
 - 3. In the event that the loosened area becomes overly compacted, loosen the area again prior to installing the Planting Soil.
- D. Install the Planting Soil in 12 - 18-inch lifts to the required depths. Apply compacting forces to each lift as required to attain the required compaction. Scarify the top of each lift prior to adding more Planting Soil by dragging the teeth of a loader bucket or backhoe across the soil surface to roughen the surface.

- E. Phase work such that equipment to deliver or grade soil does not have to operate over previously installed Planting Soil. Work in rows of lifts the width of the extension of the bucket on the loader. Install all lifts in one row before proceeding to the next. Work out from the furthest part of each bed from the soil delivery point to the edge of each bed area.
- F. Where possible place large trees first and fill Planting Soil around the root ball.
- G. Installing soil with soil or mulch blowers or soil slingers shall not be permitted due to the over mixing and soil ped breakdown cause by this type of equipment.
- H. Where travel over installed soil is unavoidable, limit paths of traffic to reduce the impact of compaction in Planting Soil. Each time equipment passes over the installed soil it shall reverse out of the area along the same path with the teeth of the bucket dropped to scarify the soil. Comply with the paragraph "Compaction Reduction" (section 3.9) in the event that soil becomes over compacted.
- I. The depths and grades shown on the drawings are the final grades after settlement and shrinkage of the compost material. The Contractor shall install the Planting Soil at a higher level to anticipate this reduction of Planting Soil volume. A minimum settlement of approximately 10 - 15% of the soil depth is expected. All grade increases are assumed to be as measured prior to addition of surface Compost till layer, mulch, or sod.

3.08 COMPACTION REQUIREMENTS FOR INSTALLED OR MODIFIED PLANTING SOIL

- A. Compact installed Planting Soil to the compaction rates indicated and using the methods approved for the soil mockup. Compact each soil lift as the soil is installed.
- B. Existing soil that is modified by tilling, ripping or fracturing shall have a density to the depth of the modification, after completion of the loosening, such that the penetrometer reads approximately 75 to 250 psi at soil moisture approximately the mid-point between wilting point and field capacity. This will be approximately between 75 and 82% of maximum dry density standard proctor.
- C. Installed Planting Soil Mix and re-spread existing soil shall have a soil density through the required depth of the installed layers of soil, such that the penetrometer reads approximately 75 to 250 psi at soil moisture approximately the mid-point between wilt point and field capacity. This will be approximately between 75 and 82% of maximum dry density standard proctor.
- D. Planting Soil compaction shall be tested at each lift using a penetrometer calibrated to the mockup soil and its moisture level. The same penetrometer and moisture meter used for the testing of the mockup shall be used to test installed soil throughout the work.
- E. Maintain moisture conditions within the Planting Soil during installation or modification to allow for satisfactory compaction. Suspend operations if the Planting Soil becomes wet. Apply water if the soil is overly dry.
- F. Provide adequate equipment to achieve consistent and uniform compaction of the Planting Soils. Use the smallest equipment that can reasonably perform the task of spreading and compaction. Use the same equipment and methods of compaction used to construct the Planting Soil mockup.
- G. Do not pass motorized equipment over previously installed and compacted soil except as authorized below.
 - 1. Light weight equipment such as trenching machines or motorized wheelbarrows is permitted to pass over finished soil work.
 - 2. If work after the installation and compaction of soil compacts the soil to levels greater than the above requirements, follow the requirements of the paragraph "Over Compaction Reduction" below.

3.09 OVER COMPACTION REDUCTION

- A. Any soil that becomes compacted to a density greater than the specified density and/or the density in the approved mockup shall be dug up and reinstalled. This requirement includes compaction caused by other sub-contractors after the Planting Soil is installed and approved.
- B. Surface roto tilling shall not be considered adequate to reduce over compaction at levels 6 inches or greater below finished grade.

3.10 INSTALLATION OF CHEMICAL ADDITIVES

- A. Following the installation of each soil and prior to fine grading and installation of the Compost till layer, apply chemical additives as recommended by the soil test, and appropriate to the soil and specific plants to be installed.
- B. Types, application rates and methods of application shall be approved by the Owner's Representative prior to any applications.

3.10 FINE GRADING

- A. The Owner's Representative shall approve all rough grading prior to the installation of Compost, fine grading, planting, and mulching.
- B. Grade the finish surface of all planted areas to meet the grades shown on the drawings, allowing the finished grades to remain higher (10 – 15% of depth of soil modification) than the grades on the grading plan, as defined in paragraph Planting Soil Installation, to anticipate settlement over the first year.
- C. Utilize hand equipment, small garden tractors with rakes, or small garden tractors with buckets with teeth for fine grading to keep surface rough without further compaction. Do not use the flat bottom of a loader bucket to fine grade, as it will cause the finished grade to become overly smooth and or slightly compressed.
- D. Provide for positive drainage from all areas toward the existing inlets, drainage structures and or the edges of planting beds. Adjust grades as directed to reflect actual constructed field conditions of paving, wall and inlet elevations. Notify the Owner's Representative in the event that conditions make it impossible to achieve positive drainage.
- E. Provide smooth, rounded transitions between slopes of different gradients and direction. Modify the grade so that the finish grade before adding mulch and after settlement is one or two inches below all paving surfaces or as directed by the drawings.
- F. Fill all dips and remove any bumps in the overall plane of the slope. The tolerance for dips and bumps in shrub and ground cover planting areas shall be a 2-inch deviation from the plane in 10 feet. The tolerance for dips and bumps in lawn areas shall be a 1-inch deviation from the plane in 10 feet.

3.11 INSTALLATION OF COMPOST TILL LAYER

- A. After Planting Soil Mixes are installed in planting bed areas and just prior to the installation of shrub or groundcover plantings, spread 3 – 4 inches of Compost over the beds and roto till into the top 4 - 6 inches of the Planting Soil. This step will raise grades slightly above the grades required in paragraph "Fine Grading". This specification anticipates that the raise in grade due to this tilling will settle within a few months after installation as Compost breaks down. Additional settlement as defined in paragraph "Planting Soil and Planting Soil Mix installation" must still be accounted for in the setting of final grades.

3.12 CLEAN-UP

- A. During installation, keep the site free of trash, pavements reasonably clean and work area in an

orderly condition at the end of each day. Remove trash and debris in containers from the site no less than once a week.

1. Immediately clean up any spilled or tracked soil, fuel, oil, trash or debris deposited by the Contractor from all surfaces within the project or on public right of ways and neighboring property.
- B. Once installation is complete, wash all soil from pavements and other structures. Ensure that mulch is confined to planting beds and that all tags and flagging tape are removed from the site. The Owner's Representative seals are to remain on the trees and removed at the end of the warranty period.
1. Make all repairs to grades, ruts, and damage to the work or other work at the site.
 2. Remove and dispose of all excess Planting Soil, subsoil, mulch, plants, packaging, and other material brought to the site by the Contractor.

3.13 PLANTING SOIL AND MODIFIED EXISTING SOIL PROTECTION

- A. The Contractor shall protect installed and/or modified Planting Soil from damage including contamination and over compaction due to other soil installation, planting operations, and operations by other Contractors or trespassers. Maintain protection during installation until acceptance. Utilize fencing and matting as required or directed to protect the finished soil work. Treat, repair or replace damaged Planting Soil immediately.
- B. Loosen compacted Planting Soil and replace Planting Soil that has become contaminated as determined by the Owner's Representative. Planting Soil shall be loosened or replaced at no expense to the Owner.
1. Till and restore grades to all soil that has been driven over or compacted during the installation of plants.
 2. Where modified existing soil has become contaminated and needs to be replaced, provide imported soil that is of similar composition, depth and density as the soil that was removed.

3.14 PROTECTION DURING CONSTRUCTION

- A. The Contractor shall protect planting and related work and other site work from damage due to planting operations, operations by other Contractors or trespassers.
1. Maintain protection during installation until the date of plant acceptance (see specifications section – Planting). Treat, repair or replace damaged work immediately.
 2. Provide temporary erosion control as needed to stop soil erosion until the site is stabilized with mulch, plantings or turf.
- B. Damage done by the Contractor, or any of their sub-contractors to existing or installed plants, or any other parts of the work or existing features to remain, including large existing trees, soil, paving, utilities, lighting, irrigation, other finished work and surfaces including those on adjacent property, shall be cleaned, repaired or replaced by the Contractor at no expense to the Owner. The Owner's Representative shall determine when such cleaning, replacement or repair is satisfactory. Damage to existing trees shall be assessed by a certified arborist.

3.15 SUBSTANTIAL COMPLETION ACCEPTANCE

- A. Upon written notice from the Contractor, the Owners Representative shall review the work and make a determination if the work is substantially complete.
- B. The date of substantial completion of the planting soil shall be the date when the Owner's Representative accepts that all work in Planting, Planting Soil, and Irrigation installation sections is complete.

3.15 FINAL ACCEPTANCE / SOIL SETTLEMENT

- A. At the end of the plant warrantee and maintenance period, (see Specification section - Planting) the Owner's Representative shall observe the soil installation work and establish that all provisions of the contract are complete and the work is satisfactory.
 - 1. Restore any soil settlement and or erosion areas to the grades shown on the drawings. When restoring soil grades remove plants and mulch and add soil before restoring the planting. Do not add soil over the root balls of plants or on top of mulch.
- B. Failure to pass acceptance: If the work fails to pass final acceptance, any subsequent observations must be rescheduled as per above. The cost to the Owner for additional observations will be charged to the Contractor at the prevailing hourly rate of the Owner's Representative.

END OF SECTION 329100

SECTION 329200 – TURF AND GRASSES

PART 1 - GENERAL

1.01 SUMMARY

- A. Section Includes:
 - 1. Lawn Seeding
 - 2. Lawn Sodding
 - 3. Meadow grasses and wildflowers

1.02 DEFINITIONS

- A. Substantial Completion: The proper installation of seed, sod, and meadow with final grades, mulch and irrigation functioning (if provided) with no indication of widespread plant death. For seeded and meadow areas, the seed must show germination with green shoots visible. It is possible to grant substantial completion to portions of the site without total project completion however all construction activities must be completed in the requested area.
- B. Finish Grade: Elevation of finished surface of planting soil.
- C. Pesticide: A substance or mixture intended for preventing, destroying, repelling, or mitigating a pest. This includes insecticides, miticides, herbicides, fungicides, rodenticides, and molluscicides. It also includes substances or mixtures intended for use as a plant regulator, defoliant, or desiccant.
- D. Pests: Living organisms that occur where they are not desired or that cause damage to plants, animals, or people. These include insects, mites, grubs, mollusks (snails and slugs), rodents (gophers, moles, and mice), unwanted plants (weeds), fungi, bacteria, and viruses.
- E. Planting Soil: The prepared earth [existing or imported as specified herein] used to backfill lawn or sod areas.
- F. Subgrade: Surface or elevation of subsoil remaining after excavation is complete, or top surface of a fill or backfill before planting soil is placed.
- G. Surface Soil: Soil that is present at the top layer of the existing soil profile at the Project site. In undisturbed areas, the surface soil is typically topsoil, but in disturbed areas such as urban environments, the surface soil can be subsoil.
- H. Turf: A groundcover established from either lawn type seeds, lawn type sod or meadow seeds.

1.03 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

1. Pesticides and Herbicides: Include product label and manufacturer's application instructions specific to this Project.

1.04 INFORMATIONAL SUBMITTALS

- A. Certification of Grass Seed: From seed vendor for each grass-seed monostand or mixture stating the botanical and common name, percentage by weight of each species and variety, and percentage of purity, germination, and weed seed. Include the year of production and date of packaging.
 1. Certification of each seed mixture for turfgrass sod. Include identification of source and name and telephone number of supplier.
- B. Qualification Data: For qualified landscape Installer.
- C. Product Certificates: For soil amendments and fertilizers, from manufacturer.
- D. Maintenance Instructions: Recommended procedures to be established by Owner for maintenance of turf and meadows during a calendar year. Submit before expiration of required initial maintenance periods.

1.05 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified landscape Installer whose work has resulted in successful turf and meadow establishment.
 1. Professional Membership: Installer shall be a member in good standing of the Professional Landcare Network, the NC Landscape Contractors Association, or the American Nursery and Landscape Association.
 2. Experience: Three years' experience in turf installation in addition to requirements in Division 01 Section "Quality Requirements."
 3. Installer's Field Supervision: Require Installer to maintain an experienced full-time supervisor on Project site when work is in progress.
 4. Personnel Certifications: All personnel who handle herbicides and herbicides shall be State licensed, for commercial.
- B. Soil-Testing Laboratory Qualifications: An independent laboratory or university laboratory, recognized by the State Department of Agriculture, with the experience and capability to conduct the testing indicated and that specializes in types of tests to be performed.
- C. Soil Analysis: For each un-amended soil type, furnish soil analysis and a written report by a qualified soil-testing laboratory stating percentages of organic matter; gradation of sand, silt, and clay content; cation exchange capacity; deleterious material; pH; and mineral and plant-nutrient content of the soil.
 1. Test native in place surface soil and soil components of Planting Soils Type A
 2. Testing methods and written recommendations shall comply with USDA's Handbook No. 60.
 3. Test shall include mechanical analysis of sand, silt and clay components.
 4. The soil-testing laboratory shall oversee soil sampling; with depth, location, and number of samples to be taken per instructions from Architect. A minimum of three

representative samples shall be taken from varied locations for each soil to be used or amended for planting purposes.

5. Soil tests shall include the following information:
 - a. Cation exchange capacity.
 - b. Percent of organic matter.
 - c. Stated recommendations for soil treatments and soil amendments to be incorporated. State recommendations in weight per 1000 sq. ft. for nitrogen, phosphorus, and potash nutrients and soil amendments to be added to produce satisfactory planting soil suitable for healthy, viable plants.
 - d. Report presence of problem salts, minerals, or heavy metals, including aluminum, arsenic, barium, cadmium, chromium, cobalt, lead, lithium, and vanadium. If such problem materials are present, provide additional recommendations for corrective action.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Seed and Other Packaged Materials: Deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and indication of conformance with state and federal laws, as applicable.
- B. Sod: Harvest, deliver, store, and handle sod according to requirements in "Specifications for Turfgrass Sod Materials" and "Specifications for Turfgrass Sod Transplanting and Installation" in TPI's "Guideline Specifications to Turfgrass Sodding." Deliver sod in time for planting within 24 hours of harvesting. Protect sod from breakage and drying.
- C. Bulk Materials:
 1. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
 2. Provide erosion-control measures to prevent erosion or displacement of bulk materials, discharge of soil-bearing water runoff, and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
 3. Accompany each delivery of bulk fertilizers, lime, and soil amendments with appropriate certificates.

1.07 PROJECT CONDITIONS

- A. Planting Restrictions: Plant during one of the following periods. Coordinate planting periods with initial maintenance periods to provide required maintenance from date of Substantial Completion.

Weather Limitations: Proceed with planting only when existing and forecasted weather conditions permit planting to be performed when beneficial and optimum results may be obtained. Apply products during favorable weather conditions according to manufacturer's written instructions.

Grass Type	Fall Season	Spring Season
------------	-------------	---------------

Cool season grasses	September 15-December 15	February 1 to May 15
Warm season grasses	Sept 1 to Oct 15	May 15- July 15
Grassy Meadows	Sept 1 to Oct 15	May 15- July 15

- 1.08 Construction Water: During the construction period water will be provided by the Contractor.

- 1.09 Construction Maintenance Water: During the maintenance period water will be provided by the Owner.
 - A. Initial Maintenance Service for Lawns [sod and seed areas]: Provide maintenance by skilled employees of landscape Installer. Maintain as required in Part 3. Begin maintenance immediately after lawns are installed and continue until plantings are acceptably healthy and well established but for not less than maintenance period below.
 - 1. Construction Maintenance Period for areas that are completed prior to Final Completion and Acceptance for entire project: 6 months. The Construction Maintenance Period will begin from the date of Substantial Completion for the last sub-phase of work completed, not the final phase of the project. Partial substantially completed areas will require continued maintenance until the Final Completion date set by the final phase of work.
 - 2. Landscape Maintenance Period: 12 months from Substantial Completion of entire project- The Maintenance Period will begin from the date the Maintenance period [described above] lapses.
 - B. Meadow Construction Maintenance Service: Provide full maintenance by skilled employees of landscape Installer. Maintain as required in Part 3. Begin maintenance immediately after each area is planted and continue until acceptable meadow is established, but for not less than 6 months from date of Substantial Completion. Partial substantially completed areas will require continued maintenance until the completion date set by the final phase of work.

PART 2 - PRODUCTS

- 2.01 SEED
 - A. Grass Seed: Fresh, clean, dry, new-crop seed complying with AOSA's "Journal of Seed Technology; Rules for Testing Seeds" for purity and germination tolerances.

- B. Seed Species: Seed of grass species as follows, with not less than 95 percent germination, not less than 85 percent pure seed, and not more than 0.5 percent weed seed:

Lawn Type	Turfgrass Seed Mix	Notes
Warm Season	TifTuf Bermuda	
Warm Season	Zeon or Zenith Zoysia	
Cool Season	Elite Tall Fescue	

2.02 TURFGRASS SOD

- A. Turfgrass Sod: Provide sod meeting "Specifications for Turfgrass Sod Materials" in TPI's "Guideline Specifications to Turfgrass Sodding." Furnish viable sod of uniform density, color, and texture, strongly rooted, and capable of vigorous growth and development when planted.

- B. Turfgrass Species: (SELECT BELOW FOR YOUR PROJECT SPECIFICS)

Lawn Type	Turfgrass Sod Species	Notes
Warm Season Lawn	TifTuf Bermuda	
Cool Season	Elite Tall Fescue	

2.03 INORGANIC SOIL AMENDMENTS

- A. Lime: ASTM C 602, agricultural liming material containing a minimum of 80 percent calcium carbonate equivalent and as follows:
1. Provide lime in form of ground dolomitic limestone or calcitic limestone depending on soil test.

2.04 ORGANIC SOIL AMENDMENTS

- A. Soil Conditioner: Well-composted, stable, and weed-free organic matter, pH range of 5.5 to 8; moisture content 35 to 55 percent by weight; 100 percent passing through 1/2-inch sieve; soluble salt content of 5 decisiemens/m; not exceeding 0.5 percent inert contaminants and free of substances toxic to plantings; and as follows:
1. Organic Matter Content: 70 percent of dry weight.
 2. Sources: Agricultural, bark, bio-solids; municipal compost; or source-separated or compostable mixed solid waste.
 - a. Free of toxic materials to plant growth

- b. Free of weed seeds.

2.05 FERTILIZERS

- A. Superphosphate: Commercial, phosphate mixture, soluble; a minimum of 20 percent available phosphoric acid.
- B. Commercial Fertilizer: Commercial-grade complete fertilizer of neutral character, consisting of fast- and slow-release nitrogen, 50 percent derived from natural organic sources of urea formaldehyde, phosphorous, and potassium in the following composition:
 - 1. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing laboratory.
- C. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:
 - 1. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing laboratory.

2.06 PLANTING SOILS

- A. Planting Soil Type A: Existing, in-place surface soil. Verify suitability of existing surface soil to produce viable planting soil. Remove stones, roots, plants, sod, clods, clay lumps, pockets of coarse sand, concrete slurry, concrete layers or chunks, cement, plaster, building debris, and other extraneous materials harmful to plant growth. Mix surface soil with the following soil amendments and fertilizers in the following quantities to produce planting soil:
 - 1. Depth of soil conditioner to mix in Planting Soil: 1/2".
 - 2. Weight of Slow-Release Fertilizer per 1000 Sq. Ft. consult soil test.
 - 3. Weight of dolomitic limestone per soil test.
- B. Planting Soil Type B: Imported topsoil or manufactured topsoil from off-site sources. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land bogs, or marshes.
 - 1. Additional Properties of Imported Topsoil or Manufactured Topsoil: Screened and free of stones 1 inch or larger in any dimension; free of roots, plants, sod, clods, clay lumps, pockets of coarse sand, paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, building debris, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, acid, and other extraneous materials harmful to plant growth; free of obnoxious weeds and invasive plants including quackgrass, Johnsongrass, poison ivy, nutsedge, nimblewill, Canada thistle, bindweed, bentgrass, wild garlic, ground ivy, perennial sorrel, and brome grass; not infested with nematodes; grubs; or other pests, pest eggs, or other undesirable organisms and disease-causing plant pathogens; friable and with sufficient structure to give good tilth and aeration. Continuous, air-filled pore space content on a volume/volume basis shall be at least 15 percent when moisture is present at field capacity. Soil shall have a field capacity of at least 15 percent on a dry weight basis.
 - 2. Mix imported topsoil or manufactured topsoil with the following soil amendments and fertilizers in the following quantities to produce planting soil.

- a. Ratio of soil conditioner to Topsoil by Volume: 1:10.
- b. Weight of Slow-Release Fertilizer as per soil test.
- c. Weight of dolomitic limestone as per soil test.

2.07 SEED STABILIZATION

A. Grass and meadow seed blankets and coverings:

1. Products for lawn areas: Free of plastic or other non-biodegradable materials, seed free; available products that may be incorporated into the Work include, but are not limited to, the following:
 - a. American Excelsior Company, Curlex NetFree
 - b. Granite Environmental, Coconut Blanket C4000BD
 - c. Tensar BioNet
2. Products for storm water management areas: Made from biodegradable jute matting, free of plastic or other non-biodegradable materials, seed free.

2.08 MULCHES

- ### A. General: The Contractor shall select the mulching products that best suit the grass seed selected. Choose from the following mulches:
1. Straw Mulch: Provide air-dry, clean, mildew- and seed-free, salt hay or threshed straw of wheat, rye, oats, or barley.
 2. Fiber Mulch: Biodegradable, dyed-wood, cellulose-fiber mulch; nontoxic and free of plant-growth or germination inhibitors; with a maximum moisture content of 15 percent and a pH range of 4.5 to 6.5.
- ### B. Non-asphaltic Tackifier: Colloidal tackifier recommended by fiber-mulch manufacturer for slurry application; nontoxic and free of plant-growth or germination inhibitors.

2.09 PESTICIDES

- ### A. General: Pesticide, registered and approved by EPA, acceptable to authorities having jurisdiction, and of type recommended by manufacturer for each specific problem and as required for Project conditions and application. Do not use restricted pesticides unless authorized in writing by authorities having jurisdiction.
- ### B. Pre-Emergent Herbicide (Selective and Non-Selective): Effective for controlling the germination or growth of weeds within planted areas at the soil level directly below the mulch layer.
- ### C. Post-Emergent Herbicide (Selective and Non-Selective): Effective for controlling weed growth that has already germinated.

PART 3- EXECUTION

3.01 EXAMINATION

- A. Examine areas to be planted for compliance with requirements and other conditions affecting performance. Notify the Architect immediately and do not start landscape construction operations if:
1. Grades or site features do not match the design.
 2. There is ponding or areas that do not appear to drain
 3. The subsoil contains no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in soil within a planting area.
 4. If the soils are frozen or moist beyond that required to produce optimal working conditions.
 5. Excessively dry soil that is not workable and which is too dusty.
 6. If the subsoil is over compacted.
 7. If irrigation main and lateral lines have not been installed.
 8. If irrigation main or lateral line trenches have not been compacted.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
- C. Erosion Control Seeding Contamination – Evaluate the erosion control seeding used and confirm that potential seed sources will not interfere with the establishment of seeded lawns or meadows. Confer with the General Contractor on usage of erosion control seeding and potential threats to establishing lawns or meadows.

3.02 PREPARATION

Protect structures, utilities, sidewalks, pavements, and other facilities, trees, shrubs, and plantings from damage caused by planting operations.

1. Protect adjacent and adjoining areas from hydroseeding and hydro-mulching overspray.
2. Protect grade stakes set by others until directed to remove them.
3. Protect areas that should not receive seed such as planting beds.

3.03 TURF AREA PREPARATION

- A. Limit turf subgrade preparation to areas to be planted.
- B. Newly Graded Subgrades: Loosen subgrade to a minimum depth of 4 inches.
1. General

- a. SOIL COMPACTION – GENERAL REQUIREMENTS
 - 1) Acceptable Compaction: Good rooting anticipated, but increasing settlement expected as compaction is reduced and/or in soil with a high organic matter content.
 - 2) Standard Proctor Method – 75-85%; soil below 75% is unstable and will settle excessively.
- b. Delay mixing fertilizer with planting soil if planting will not proceed within a few days.
- c. Remove stones larger than 1 inch in any dimension and sticks, roots, trash, and other extraneous matter.
- d. Legally dispose of waste material, including grass, vegetation, and turf, off Owner's property.
- e. Reduce elevation of planting soil to allow for soil thickness of sod.

2. Type A Soils: Apply amendments directly to final grade before loosening. Mix to a total depth of 4”.

3. Type B and C Soils: Spread planting soil to a depth of 4 inches but not less than required to meet finish grades after light rolling and natural settlement. Do not spread if planting soil or subgrade is frozen, muddy, or excessively wet.

4. Thoroughly blend planting soil with organic amendments off-site before spreading

5. Apply lime and fertilizers on surface, and thoroughly blend planting soil.

D. Finish Grading: Grade planting areas to a smooth, uniform surface plane with loose, uniformly fine texture. Grade to within plus or minus 1/2 inch of finish elevation. Roll and rake, remove ridges, and fill depressions to meet finish grades. Limit finish grading to areas that can be planted in the immediate future.

D. Moisten prepared area before planting if soil is dry. Water thoroughly and allow surface to dry before planting. Do not create muddy soil.

E. Before planting, obtain Architect's acceptance of finish grading; restore planting areas if eroded or otherwise disturbed after finish grading.

3.04 LAWN SEEDING

A. Sow seed with spreader or seeding machine. Do not broadcast or drop seed when wind velocity exceeds 5 mph. Evenly distribute seed by sowing equal quantities in two directions at right angles to each other.

1. Do not use wet seed or seed that is moldy or otherwise damaged.

2. Do not seed against existing trees. Limit extent of seed to outside edge of planting saucer.

B. Sow seed at rates as specified by seed provider.

C. Rake seed lightly into top 1/8 inch of soil, roll lightly, and water with fine spray.

D. Protect seeded areas with erosion-control mats where slopes exceed 3:1 and as shown on Drawings; install and anchor according to manufacturer's written instructions.

- E. Protect seeded areas with slopes not exceeding 1:6 by spreading straw mulch. Spread uniformly at a rate to form a continuous blanket 1 inch in loose thickness over seeded areas. Spread by hand, blower, or other suitable equipment.
 - 1. Bond straw mulch by spraying with non-asphalt emulsion at a rate to resist wind and erosion. Take precautions to prevent damage or staining of structures or other plantings adjacent to mulched areas. Immediately clean damaged or stained areas.
- F. Protect seeded areas from hot, dry weather or drying winds by applying hydro-mulch within 4 hours after completing seeding operations.

3.05 HYDROSEEDING

- A. Two Step Hydroseeding: Mix specified seed and fertilizer in water, using equipment specifically designed for hydroseed application.
- B. Apply seed and fertilizer at the recommended rates to bare soil.
- C. Apply hydro-mulch over seed mix. Continue mixing until uniformly blended into homogeneous slurry suitable for hydraulic application.
 - 1. Mix slurry with non-asphaltic tackifier.
 - 2. Apply slurry uniformly to all areas to be seeded in a one-step process. Apply slurry at a rate so that mulch component is deposited at not less than 1500-lb/acre dry weight.

3.06 SODDING

- A. Lay sod within 24 hours of harvesting. Do not lay sod if dormant or if ground is frozen or muddy.
- B. Lay sod to form a solid mass with tightly fitted joints. Butt ends and sides of sod; do not stretch or overlap. Stagger sod strips or pads to offset joints in adjacent courses. Avoid damage to subgrade or sod during installation. Tamp and roll lightly to ensure contact with subgrade, eliminate air pockets, and form a smooth surface. Work sifted soil or fine sand into minor cracks between pieces of sod; remove excess to avoid smothering sod and adjacent grass.
 - 1. Lay sod across angle of slopes exceeding 1:3.
 - 2. Anchor sod on slopes exceeding 1:6 or in the bottom of swales with steel staples spaced as recommended by sod manufacturer but not less than 2 anchors per sod strip to prevent slippage.
- C. Saturate sod with fine water spray within two hours of planting. During first week after planting, water daily or more frequently as necessary to maintain moist soil to a minimum depth of 1-1/2 inches below sod.

3.07 STORM WATER MANAGEMENT PLANTING STABILIZATION

- A. Planting seed or meadow in storm water management areas:
 - 1. Prepare the soils according to plans and details including amendments.
 - 2. Micro grade to meet the requirements of the grading plan.
 - 3. Apply seed and hydro-mulch slurry to soil surface.
 - 4. Apply jute mat in continuous runs and attach with staples at 30" oc.
- B. Remove sod and vegetation from diseased or unsatisfactory turf areas; do not bury in soil.
- C. Remove topsoil containing foreign materials such as oil drippings, fuel spills, stones, gravel, and other construction materials resulting from Contractor's operations, and replace with new planting soil.
- D. Mow, dethatch, core aerate, and rake existing turf.
- E. Remove weeds before seeding. Where weeds are extensive, apply selective herbicides as required. Do not use pre-emergence herbicides.
- F. Remove waste and foreign materials, including weeds, soil cores, grass, vegetation, and turf, and legally dispose of them off Owner's property.
- G. Till stripped, bare, and compacted areas thoroughly to a soil depth of 4 inches.
 - 1. Confirm that there are no protected root zone areas that would require special procedures.
- H. Apply soil amendments and initial fertilizers required for establishing new turf and mix thoroughly into top 4 inches of existing soil. Install new planting soil to fill low spots and meet finish grades.
- I. Apply seed or sod as shown on the plans and as required for new turf.
- J. Water newly planted areas and keep moist until new turf is established.

3.08 TURF MAINTENANCE

- A. Maintain and establish turf by watering, fertilizing, weeding, mowing, trimming, replanting, and performing other operations as required to establish healthy, viable turf. Roll, regrade, and replant bare or eroded areas and remulch to produce a uniformly smooth turf. Provide materials and installation the same as those used in the original installation.
 - 1. Repair turf as necessary because of settling, erosion or settlement or other processes.
 - 2. In areas where mulch has been disturbed by wind or maintenance operations, add new mulch and anchor as required to prevent displacement.
 - 3. Apply treatments as required to keep turf and soil free of pests and pathogens or disease. Use integrated pest management practices whenever possible to minimize the use of pesticides and reduce hazards.

- B. Watering: Install and maintain irrigation systems, temporary piping, hoses, and turf-watering equipment to convey water from sources and to keep turf uniformly moist to a depth of 4-inches.
1. Schedule watering to prevent wilting, puddling, erosion, and displacement of seed or mulch. Lay out temporary watering system to avoid walking over muddy or newly planted areas.
 2. Water turf with fine spray at a minimum rate of 1 inch per week unless rainfall precipitation is adequate.
- C. Mow turf as soon as top growth is tall enough to cut. Repeat mowing to maintain specified height without cutting more than 1/3 of grass height. Remove no more than 1/3 of grass-leaf growth in initial or subsequent mowings. Do not delay mowing until grass blades bend over and become matted. Do not mow when grass is wet. Schedule initial and subsequent mowings to maintain the following grass height:
1. Mow bermudagrass to a height of 1/2 to 1 inch.
 2. Mow turf-type tall fescue to a height of 2 to 3 inches.
- D. Turf Postfertilization: Apply fertilizer after initial mowing and when grass is dry.
2. Use fertilizer that will provide actual nitrogen of at least 1 lb/1000 sq. ft. to turf area.

3.09 SATISFACTORY TURF

- A. Turf installations shall meet the following criteria as determined by Architect:
1. Satisfactory Seeded Turf: At end of maintenance period, a healthy, uniform, close stand of grass has been established, free of weeds and surface irregularities, with coverage exceeding 90 percent over any 10 sq. ft. and bare spots not exceeding 3 by 3 inches.
 2. Satisfactory Sodded Turf: At end of maintenance period, a healthy, well-rooted, even-colored, viable turf has been established, free of weeds, open joints, bare areas, and surface irregularities.
 3. Satisfactory Plugged Turf: At end of maintenance period, the required number of plugs has been established as well-rooted, viable patches of grass, and areas between plugs are free of weeds and other undesirable vegetation.
 4. Satisfactory Sprigged Turf: At end of maintenance period, the required number of sprigs has been established as well-rooted, viable plants, and areas between sprigs are free of weeds and other undesirable vegetation.
- B. Use specified materials to reestablish turf that does not comply with requirements and continue maintenance until turf is satisfactory.

3.10 PESTICIDE APPLICATION

- A. Apply pesticides and other chemical products and biological control agents in accordance with requirements of authorities having jurisdiction and manufacturer's written

recommendations. Coordinate applications with Owner's operations and others in proximity to the Work. Notify Owner before each application is performed.

- B. Post-Emergent Herbicides (Selective and Non-Selective): Apply only as necessary to treat already-germinated weeds and in accordance with manufacturer's written recommendations.

3.11 CLEANUP AND PROTECTION

- A. Promptly remove soil and debris created by turf work from paved areas. Clean wheels of vehicles before leaving site to avoid tracking soil onto roads, walks, or other paved areas.
- B. Erect temporary fencing or barricades and warning signs as required to protect newly planted areas from traffic. Maintain fencing and barricades throughout initial maintenance period and remove after plantings are established.
- C. Remove nondegradable erosion-control measures after grass establishment period.

PART 4- MEASUREMENT AND PAYMENT

- 4.01 Turf & Grass will be measured and paid in square feet, accepted in place. Work includes all materials, labor, and incidentals necessary to complete this work.

END OF SECTION 329200

SECTION 329300 – PLANTS

PART 1 - GENERAL

1.01 SECTION INCLUDES:

- A. Plants.
- B. Planting soils.
- C. Tree stabilization.
- D. Tree-watering devices.
- E. Landscape edgings.

1.02 DEFINITIONS

- A. Backfill: The earth used to replace or the act of replacing earth in an excavation.
- B. Balled and Burlapped Stock: Plants dug with firm, natural balls of earth in which they were grown, with a ball size not less than the diameter and depth recommended by ANSI Z60.1 for type and size of plant required; wrapped with burlap, tied, rigidly supported, and drum laced with twine with the root flare visible at the surface of the ball as recommended by ANSI Z60.1.
- C. Container-Grown Stock: Healthy, vigorous, well-rooted plants grown in a container, with a well-established root system reaching sides of container and maintaining a firm ball when removed from container. Container shall be rigid enough to hold ball shape and protect root mass during shipping and be sized according to ANSI Z60.1 for type and size of plant required.
- D. Finish Grade: Elevation of finished surface of planting soil.
- E. Pesticide: A substance or mixture intended for preventing, destroying, repelling, or mitigating a pest. Pesticides include insecticides, miticides, herbicides, fungicides, rodenticides, and molluscicides. They also include substances or mixtures intended for use as a plant regulator, defoliant, or desiccant. Some sources classify herbicides separately from pesticides.
- F. Pests: Living organisms that occur where they are not desired or that cause damage to plants, animals, or people. Pests include insects, mites, grubs, mollusks (snails and slugs), rodents (gophers, moles, and mice), unwanted plants (weeds), fungi, bacteria, and viruses.
- G. Planting Area: Areas to be planted.
- H. Planting Soil: Existing, on-site soil; imported soil; or manufactured soil that has been modified with soil amendments and perhaps fertilizers to produce a soil mixture best for plant growth. See Section 329113 "Soil Preparation" for drawing designations for planting soils.
- I. Plant; Plants; Plant Material: These terms refer to vegetation in general, including trees, shrubs, vines, ground covers, ornamental grasses, bulbs, corms, tubers, or herbaceous vegetation.
- J. Root Flare: Also called "trunk flare." The area at the base of the plant's stem or trunk where the stem or trunk broadens to form roots; the area of transition between the root system and the stem or trunk.
- K. Stem Girdling Roots: Roots that encircle the stems (trunks) of trees below the soil surface.

- L. Subgrade: The surface or elevation of subsoil remaining after excavation is complete, or the top surface of a fill or backfill before planting soil is placed.
- M. Surface Soil: Soil that is present at the top layer of the existing soil profile at the Project site. In undisturbed areas, the surface soil is typically topsoil; but in disturbed areas such as urban environments, the surface soil can be subsoil.

1.03 COORDINATION

- A. Coordination with Turf Areas (Lawns): Plant trees, shrubs, and other plants after finish grades are established and before planting turf areas unless otherwise indicated.
 - 1. When planting trees, shrubs, and other plants after planting turf areas, protect turf areas, and promptly repair damage caused by planting operations.

1.04 PREINSTALLATION MEETINGS

- A. Pre-installation Conference: Conduct conference at Project site.

ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - Plant Materials: Include quantities, sizes, quality, and sources for plant materials.
 - Plant Photographs: Include color photographs in digital format of each required species and size of plant material as it will be furnished to Project. Take photographs from an angle depicting true size and condition of the typical plant to be furnished. Include a scale rod or other measuring device in each photograph. For species where more than 20 plants are required, include a minimum of three photographs showing the average plant, the best quality plant, and the worst quality plant to be furnished. Identify each photograph with the full scientific name of the plant, plant size, and name of the growing nursery.
- B. Samples for Verification: For each of the following:
 - Trees and Shrubs: Three Samples of each variety and size delivered to site for review. Maintain approved Samples on-site as a standard for comparison.
 - Mulch: 1-quart volume of each type of mulch required; in sealed plastic bags labeled with composition of materials by percentage of weight and source of mulch. Each Sample shall be typical of the lot of material to be furnished; provide an accurate representation of color, texture, and organic makeup.
 - Weed Control Barrier: 12 by 12 inches.
 - Proprietary Root-Ball-Stabilization Device: One unit.
 - Slow-Release, Tree-Watering Device: One unit of each size required.
 - Edging Materials and Accessories: Manufacturer's standard size, to verify color selected.
 - Tree Grates, Frames, and Accessories: Manufacturer's standard size delivered to site for review, to verify design and color selected.
 - Root Barrier: Width of panel by 12 inches.
- C. Soil Analysis: For each un-amended soil type, furnish soil analysis and a written report by a qualified soil-testing laboratory stating percentages of organic matter; gradation of sand, silt, and clay content; cation exchange capacity; deleterious material; pH; and mineral and plant-nutrient content of the soil.
 - 1. Test native in place surface soil
 - Testing methods and written recommendations shall comply with USDA's Handbook No. 60.
 - Test shall include mechanical analysis of sand, silt and clay components.
 - The soil-testing laboratory shall oversee soil sampling; with depth, location, and number of samples to be taken per instructions from Designer. A minimum of three

representative samples shall be taken from varied locations for each soil to be used or amended for planting purposes.

2. Soil tests shall include the following information:
 - a. Cation exchange capacity.
 - b. Percent of organic matter.
 - c. Stated recommendations for soil treatments and soil amendments to be incorporated. State recommendations in weight per 1000 sq. ft. for nitrogen, phosphorus, and potash nutrients and soil amendments to be added to produce satisfactory planting soil suitable for healthy, viable plants.
 - d. Report presence of problem salts, minerals, or heavy metals, including aluminum, arsenic, barium, cadmium, chromium, cobalt, lead, lithium, and vanadium. If such problem materials are present, provide additional recommendations for corrective action.

D. Requests for Substitution:

Substitutions for Convenience: Not accepted.

Substitutions for Cause: Submit written request for substitution with reason for substitution and alternate suggestion.

1. Plant List: Investigate sources of supply prior to submitting bid. Confirm that size, variety and quantity of plants specified on Plant List can be supplied. Failure to take this precaution will not relieve the successful bidder from his responsibility for furnishing and installing all plants in strict accordance with the Contract requirements and without additional expense to the Owner.
2. Substitutions will not be permitted unless substantiated written proof is supplied that a specified plant is not obtainable. In this situation, a proposal to use the nearest equivalent size or variety with an equitable adjustment of Contract Price will be considered.

1.06 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For landscape Installer. Include list of similar projects completed by Installer demonstrating Installer's capabilities and experience. Include project names, addresses, and year completed, and include names and addresses of owners' contact persons.
- B. Product Certificates: For each type of manufactured product, from manufacturer, and complying with the following:
 - Manufacturer's certified analysis of standard products.
 - Analysis of other materials by a recognized laboratory made according to methods established by the Association of Official Analytical Chemists, where applicable.
- C. Pesticides and Herbicides: Product label and manufacturer's application instructions specific to Project.
- D. Sample Warranty: For special warranty.

1.07 CLOSEOUT SUBMITTALS

- A. Maintenance Data: Recommended procedures to be established by Owner for maintenance of plants during a calendar year. Submit before expiration of required maintenance periods.

1.08 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified landscape installer whose work has resulted in successful establishment of plants.

Professional Membership: Installer shall be a member in good standing of either the Professional Landcare Network or the American Nursery and Landscape Association.

Experience: Five years' experience in landscape installation in addition to requirements in Section 014000 "Quality Requirements."

Installer's Field Supervision: Require Installer to maintain an experienced full-time supervisor on Project site when work is in progress.

Personnel Certifications: Installer's field supervisor shall have certification in one or more of the following categories from the Professional Landcare Network:

- a. Landscape Industry Certified Technician - Exterior.
- b. Landscape Industry Certified Interior.
- c. Landscape Industry Certified Horticultural Technician.
- d. Pesticide Applicator: State licensed, commercial.

- B. Provide quality, size, genus, species, and variety of plants indicated, complying with applicable requirements in ANSI Z60.1.
Selection of plants purchased under allowances is made by Designer, who tags plants at their place of growth before they are prepared for transplanting.
- C. Measurements: Measure according to ANSI Z60.1. Do not prune to obtain required sizes.
Trees and Shrubs: Measure with branches and trunks or canes in their normal position. Take height measurements from or near the top of the root flare for field-grown stock and container-grown stock. Measure main body of tree or shrub for height and spread; do not measure branches or roots tip to tip. Take caliper measurements 6 inches above the root flare for trees up to 4-inch caliper size, and 12 inches above the root flare for larger sizes.
Other Plants: Measure with stems, petioles, and foliage in their normal position.
- D. Plant Selection:
Container Plant Photographs: Include color photographs in digital format of each required species and size of plant material as it will be furnished to the Project. Take photographs from an angle depicting true size and condition of the typical plant to be furnished. Include a scale rod or other measuring device in each photograph. For species where more than 20 plants are required, include a minimum of three photographs showing the average plant, the best quality plant, and the worst quality plant to be furnished. Identify each photograph with the full scientific name of the plant, plant size, and name of the growing nursery.
Select Plant Tagging: The Contractor will submit photos prior to nursery tagging to confirm the nursery has acceptable material for consideration.
- E. Plant Material Observation: Designer may observe plant material either at place of growth or at site before planting for compliance with requirements for genus, species, variety, cultivar, size, and quality. Designer may also observe trees and shrubs further for size and condition of balls and root systems, pests, disease symptoms, injuries, and latent defects and may reject unsatisfactory or defective material at any time during progress of work. Remove rejected trees or shrubs immediately from Project site.
Notify Designer of sources of planting materials seven days in advance of delivery to site.

1.09 PREINSTALLATION CONFERENCE

- A. Pre-installation Conference: Conduct conference at Project site.
The following individuals must be present:
- a. GC Contractor's site representative responsible for the Landscape Contractor's work
 - b. The Landscape Contractor's branch manager [or Owner] and job estimator.
 - c. The Project supervisor who will be directly responsible for field work and/or paperwork.

1.10 DELIVERY, STORAGE, AND HANDLING

- A. Packaged Materials: Deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and indication of compliance with state and Federal laws if applicable.
- B. Bulk Materials:
Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
Provide erosion-control measures to prevent erosion or displacement of bulk materials; discharge of soil-bearing water runoff; and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
Accompany each delivery of bulk materials with appropriate certificates.
- C. Do not prune trees and shrubs before delivery. Protect bark, branches, and root systems from sun scald, drying, wind burn, sweating, whipping, and other handling and tying damage. Do not bend or bind-tie trees or shrubs in such a manner as to destroy their natural shape. Provide protective covering of plants during shipping and delivery. Do not drop plants during delivery and handling.
- D. Handle planting stock by root ball.
- E. Store bulbs, corms, and tubers in a dry place at 60 to 65 deg F until planting.
- F. Apply antidesiccant to trees and shrubs using power spray to provide an adequate film over trunks (before wrapping), branches, stems, twigs, and foliage to protect during digging, handling, and transportation.
If deciduous trees or shrubs are moved in full leaf, spray with antidesiccant at nursery before moving and again two weeks after planting.
- G. Wrap trees and shrubs with burlap fabric over trunks, branches, stems, twigs, and foliage to protect from wind and other damage during digging, handling, and transportation.
- H. Deliver plants after preparations for planting have been completed, and install immediately. If planting is delayed more than six hours after delivery, set plants and trees in their appropriate aspect (sun, filtered sun, or shade), protect from weather and mechanical damage, and keep roots moist.
- I. If plants are stored for over 24 hours provide the following:
Set balled stock upright on ground and cover ball with soil, peat moss, sawdust, or other acceptable material to prevent wind, cold, or heat damage to the roots.
Provide shade to shade requiring trees and shrubs.
Water root systems of plants stored on-site deeply and thoroughly with a fine-mist spray. Water as often as necessary to maintain root systems in a moist, but not overly wet condition.

1.11 FIELD CONDITIONS

- A. Field Measurements: Verify actual grade elevations, service and utility locations, irrigation system components, and dimensions of plantings and construction contiguous with new plantings by field measurements before proceeding with planting work.
- B. Interruption of Existing Services or Utilities: Do not interrupt services or utilities to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary services or utilities according to requirements indicated:

Notify Owner and Designer no fewer than two days in advance of proposed interruption of each service or utility.
Do not proceed with interruption of services or utilities without Designer's written permission.

- C. Planting Restrictions: Plant during one of the following periods. Coordinate planting periods with maintenance periods to provide required maintenance from date of Substantial Completion.
Spring Planting: March 15 – May 15.
Fall Planting: September 15 – December 15.
- D. Weather Limitations: Proceed with planting only when existing and forecasted weather conditions permit planting to be performed when beneficial and optimum results may be obtained. Apply products during favorable weather conditions according to manufacturer's written instructions and warranty requirements.
- E. Coordination with Turf Areas (Lawns): Plant trees, shrubs, and other plants after finish grades are established and before planting turf areas unless otherwise indicated.
When planting trees, shrubs, and other plants after planting turf areas, protect turf areas, and promptly repair damage caused by planting operations.
- F. Under no circumstances should work proceed prior to establishment of appropriate grades.
- G. The Contractor shall provide water for:
The construction period till final acceptance
Final acceptance through the maintenance period
- H. The Contractor shall supply watering labor as follows:
The construction period till final acceptance
Final acceptance through the maintenance period
- I. Unusual Field Conditions: It is the Contractor's responsibility to communicate to the Designer unusual field conditions found at the project site before and during construction. The presence of unusual field conditions such as wind, wetness, soil issues, invasive weeds, will require the Contractor take note and advise the Designer on how best to remedy the discovery.

1.12 WARRANTY

- A. Special Warranty: Installer agrees to repair or replace plantings and accessories that fail in materials, workmanship, or growth within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Death and unsatisfactory growth, except for defects resulting from abuse, lack of adequate maintenance, or neglect by Owner.
 - b. Structural failures including plantings falling or blowing over.
 - c. Faulty performance of tree stabilization, edgings, and tree grates.
 - d. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
 - Warranty Periods: From date of Final Acceptance.
 - e. Trees, Shrubs, Vines, and Ornamental Grasses: 12 months.
 - f. Ground Covers, Biennials, Perennials, and Other Plants: 12 months.
 - g. Annuals: Three months.
 - Include the following:
 - h. Remove tree staking systems, above and below grade.
 - i. Remove tree saucers.
 - j. Expose root crowns of all trees planted on the job.
 - Include the following remedial actions as a minimum:

- k. Immediately remove dead plants and replace unless required to plant in the succeeding planting season.
- l. Replace plants that are more than 25 percent dead or in an unhealthy condition at end of warranty period.
- m. A limit of one replacement of each plant is required except for losses or replacements due to failure to comply with requirements.
- n. Provide extended warranty for period equal to original warranty period, for replaced plant material.

PART 2 - PRODUCTS

2.01 PLANT MATERIAL

- A. General: Furnish nursery-grown plants true to genus, species, variety, cultivar, stem form, shearing, and other features indicated in Plant List, Plant Schedule, or Plant Legend indicated on Drawings and complying with ANSI Z60.1; and with healthy root systems developed by transplanting or root pruning. Provide well-shaped, fully branched, healthy, vigorous stock, densely foliated when in leaf and free of disease, pests, eggs, larvae, and defects such as knots, sun scald, injuries, abrasions, and disfigurement.
Trees with damaged, crooked, or multiple leaders; tight vertical branches where bark is squeezed between two branches or between branch and trunk ("included bark"); crossing trunks; cut-off limbs more than 3/4 inch in diameter; or with stem girdling roots are unacceptable.
Collected Stock: Do not use plants harvested from the wild, from native stands, from an established landscape planting, or not grown in a nursery unless otherwise indicated.
Provide trees from active, consistently aged specimens.
Unless directly specified, provide only trees that are genetic clones of the requested variety.
- B. Select balled and burlapped material from nurseries who utilize root pruning practices and have a systematic approach to hardening off newly dug material.
- C. Provide plants of sizes, grades, and ball or container sizes complying with ANSI Z60.1 for types and form of plants required. Plants of a larger size may be used if acceptable to Designer, with a proportionate increase in size of roots or balls.
- D. Provide small trees and shade trees that are grown on their own roots, not utilizing grafting or budding techniques (unless directed in the plant list).
- E. Provide container plant material that is free from circling roots or pot bound conditions.
- F. Root-Ball Depth: Furnish trees and shrubs with root balls measured from top of root ball, which begins at root flare according to ANSI Z60.1. Root flare shall be visible before planting.
- G. Labeling: Label at least one plant of each variety, size, and caliper with a securely attached, waterproof tag bearing legible designation of common name and full scientific name, including genus and species. Include nomenclature for hybrid, variety, or cultivar, if applicable for the plant.
- H. If formal arrangements or consecutive order of plants is indicated on Drawings, select stock for uniform height and spread, and number the labels to assure symmetry in planting.

2.02 INORGANIC SOIL AMENDMENTS

- A. Lime: ASTM C 602, agricultural liming material containing a minimum of 80 percent calcium carbonate equivalent and as follows:

Provide lime in form of ground dolomitic limestone.

2.03 ORGANIC SOIL AMENDMENTS

- A. Soil Conditioner: Well-composted, stable, and weed-free organic matter, pH range of 5.5 to 8; moisture content 35 to 55 percent by weight; 100 percent passing through 1/2-inch sieve; soluble salt content of 5 decisiemens/m; not exceeding 0.5 percent inert contaminants and free of substances toxic to plantings; and as follows:
Pine bark soil conditioner: finely ground, well composted, pine bark mulch with a maximum particle size of 1/4 inch.
Organic Matter Content: 70 percent of dry weight.
Sources: Agricultural, bark, biosolids; yard trimmings; or source-separated or compostable mixed solid waste.
- a. Free of toxic materials to plant growth
 - b. Free of weed seeds.

2.04 FERTILIZERS

- A. Superphosphate: Commercial, phosphate mixture, soluble; a minimum of 20 percent available phosphoric acid.
- B. Chelated Iron: Commercial-grade FeEDDHA for dicots and woody plants, and commercial-grade FeDTPA for ornamental grasses and monocots.
- C. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:
Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing laboratory. Several different blends may be necessary to meet the requirements.

2.05 PLANTING SOILS

- A. Planting Soil Type A: Existing, in-place surface soil. Verify suitability of existing surface soil to produce viable planting soil. Remove stones, roots, plants, sod, clods, clay lumps, pockets of coarse sand, concrete slurry, concrete layers or chunks, cement, plaster, building debris, and other extraneous materials harmful to plant growth. Mix surface soil with the following soil amendments and fertilizers in the following quantities to produce planting soil:
Screen to remove extraneous materials.
Ratio of soil conditioner to Surface Soil by Volume: 1:5.
Weight of Slow-Release Fertilizer per 1000 Sq. Ft. consult soil test.
Weight of dolomitic limestone per soil test.
- B. Planting Soil Type B: Imported topsoil or manufactured topsoil from off-site sources. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land bogs, or marshes.
Additional Properties of Imported Topsoil or Manufactured Topsoil: Screened and free of stones 1 inch or larger in any dimension; free of roots, plants, sod, clods, clay lumps, pockets of coarse sand, paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, building debris, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, acid, and other extraneous materials harmful to plant growth; free of obnoxious weeds and invasive plants including quackgrass, Johnsongrass, poison ivy, nutsedge, nimblewill, Canada thistle, bindweed, bentgrass, wild garlic, ground ivy, perennial sorrel, and bromegrass; not infested with nematodes; grubs; or other pests, pest eggs, or other undesirable organisms and disease-causing plant pathogens; friable and with sufficient structure to give good tilth and aeration. Continuous, air-filled pore space content on a volume/volume basis shall be at least 15 percent

when moisture is present at field capacity. Soil shall have a field capacity of at least 15 percent on a dry weight basis.

Mix imported topsoil or manufactured topsoil with the following soil amendments and fertilizers in the following quantities to produce planting soil.

- a. Ratio of soil conditioner to Topsoil by Volume: 1:10.
- b. Weight of Slow-Release Fertilizer as per soil test.
- c. Weight of dolomitic limestone as per soil test.

2.06 MULCHES

- A. Mulch: Well-composted, stable, and weed-free organic matter, pH of 5.5 to 8; moisture content 35 to 55 percent by weight; 100 percent passing through a 1-inch sieve; soluble-salt content of 2 dS/m; not exceeding 0.5 percent inert contaminants and free of substances toxic to plantings; and as follows:
Type: Triple shredded hardwood.
Color: Natural.

2.07 PESTICIDES

- A. General: Pesticide registered and approved by the EPA, acceptable to authorities having jurisdiction, and of type recommended by manufacturer for each specific problem and as required for Project conditions and application. Do not use restricted pesticides unless authorized in writing by authorities having jurisdiction.
Use pesticides on an as-needed basis.

2.08 HERBICIDES

- A. General: Pesticide registered and approved by EPA, acceptable to authorities having jurisdiction, and of type recommended by manufacturer for each specific problem and as required for Project conditions and application. Do not use restricted pesticides unless authorized in writing by authorities having jurisdiction.
- B. Pre-Emergent Herbicide (Selective and Non-Selective): Effective for controlling the germination or growth of weeds within planted areas at the soil level directly below the mulch layer.
- C. Post-Emergent Herbicide (Selective and Non-Selective): Effective for controlling weed growth that has already germinated.

2.09 PLANTING STABILIZATION MATERIALS

- A. Seed blankets and coverings:
Products for Steep Slopes (Greater than 3:1): Made from biodegradable jute matting, free of plastic or other non-biodegradable materials, seed free.
Staples: Galvanized staples 6" in length.

2.10 TREE-STABILIZATION MATERIALS

- A. Trunk-Stabilization Materials:
Upright and Guy Stakes: Rough-sawn, sound, new hardwood, free of knots, holes, cross grain, and other defects, 2-by-2-inch nominal by length indicated, pointed at one end.
Guys and Tie Wires: ASTM A 641/A 641M, Class 1, galvanized-steel wire, two-strand, twisted, 0.106 inch in diameter.
Tree-Tie Webbing: UV-resistant polypropylene or nylon webbing with brass grommets.
Flags: Standard surveyor's plastic flagging tape, white, 6 inches long.

LANDSCAPE EDGINGS

- A. Aluminum Edging: Standard commercial-aluminum edging, fabricated in sections of standard lengths, with stamped holes to receive fastener nails for slump footing. Submit sample for approval.
Edging Size: As approved by the Designer.
Accessories: mortar nails and concrete slump footing (see detail).
Finish: milled.

RIVER STONE

- A. River Stone: Standard commercial rounded and washed Tennessee River Stone 3" -5" in size. Submit sample for approval.

MISCELLANEOUS PRODUCTS

- A. Planter Drainage Gravel: Washed, sound crushed stone or gravel complying with ASTM D 448 for Size No. 8.
- B. Planter Filter Fabric: Nonwoven geotextile manufactured for separation applications and made of polypropylene, polyolefin, or polyester fibers or combination of them.

PART 3 - EXECUTION

3.01 GENERAL

- A. To achieve Substantial Completion, provide proper installation of plant material with final grades, mulch and irrigation (if provided) functioning with no indication of widespread plant death. Portions of the site may be granted Substantial Completion if all construction activities are completed in that area.

3.02 EXAMINATION

- A. Examine areas to receive plants, with Installer present, for compliance with requirements and conditions affecting installation and performance of the Work.
Verify that no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in soil within a planting area.
Conduct water percolation tests to verify that planting depths and drainage will meet the needs of the plants that have been selected. Inform the Designer of any drainage issues.
Verify that plants and vehicles loaded with plants can travel to planting locations with adequate overhead clearance.
Along roadways and in landscape islands, remove gravel and asphalt from landscape beds.
Do not mix or place soils and soil amendments in frozen, wet, or muddy conditions.
Suspend planting operations during periods of excessive soil moisture until the moisture content reaches acceptable levels to attain the required results.
Uniformly moisten excessively dry soil that is not workable or which is dusty.
- B. If contamination by foreign or deleterious material or liquid is present in soil within a planting area, remove the soil and contamination as directed by Designer and replace with new planting soil.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.03 PREPARATION

- A. Protect structures, utilities, sidewalks, pavements, and other facilities and turf areas and existing plants from damage caused by planting operations.
- B. Install erosion-control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways.
- C. Lay out individual tree and shrub locations and areas for multiple plantings. Stake locations, outline areas, adjust locations when requested, and obtain Designer's acceptance of layout before excavating or planting. Make minor adjustments as required.

3.04 GENERAL REQUIREMENTS FOR ALL PLANTING TYPES

- A. Before planting, verify that root flare is visible at top of root ball according to ANSI Z60.1. If root flare is not visible, remove soil in a level manner from the root ball to where the top-most root emerges from the trunk. After soil removal to expose the root flare, verify that root ball still meets size requirements.
- B. Remove stem girdling roots and kinked roots. Remove injured roots by cutting cleanly; do not break.
- C. Obstructions: Notify Designer if unexpected rock or obstructions detrimental to trees or shrubs are encountered in excavations.
- D. Before planting, obtain Designer's acceptance of finish grading; restore planting areas if eroded or otherwise disturbed after finish grading.
- E. Excavate planting pits with sides sloping inward at a 45-degree angle. Excavations with vertical sides are not acceptable. Trim perimeter of bottom leaving center area of bottom raised slightly to support root ball and assist in drainage away from center. Do not further disturb base. Ensure that root ball will sit on undisturbed base soil to prevent settling. Scarify sides of planting pit smeared or smoothed during excavation.

Do not excavate deeper than depth of the root ball, measured from the root flare to the bottom of the root ball.

If area under the plant was initially dug too deep, add soil to raise it to the correct level and thoroughly tamp the added soil to prevent settling.

Maintain required angles of repose of adjacent materials as shown on the Drawings. Do not excavate subgrades of adjacent paving, structures, hardscapes, or other new or existing improvements.

Maintain supervision of excavations during working hours.

Keep excavations covered or otherwise protected when unattended by Installer's personnel.

If subdrainage is shown on Drawings or required under planting areas, insure contact between the root ball and subdrain pipe.

- F. After excavation examine the area for potential drainage difficulties matched to plant varieties and inform the Designer of potential poorly drained areas. Notify Designer if subsoil conditions evidence unexpected water seepage or retention in tree or shrub planting pits. Discuss variations in the depth of planting with the Designer prior to planting.
- G. Fill excavations with water and allow it to percolate away before positioning trees and shrubs.
- H. Set out and space plants according to the planting plans and notes in even rows with triangular spacing unless otherwise indicated.

- I. When planting on slopes, set the plant so the root flare on the uphill side is flush with the surrounding soil on the slope; the edge of the root ball on the downhill side will be above the surrounding soil. Apply enough soil to cover the downhill side of the root ball.
- J. Work soil around roots to eliminate air pockets and leave a slight saucer indentation around plants to hold water.
- K. Water thoroughly after planting, taking care not to cover plant crowns with wet soil.
- L. Finish Grading: Grade planting areas to a smooth, uniform surface plane with loose, uniformly fine texture. Roll and rake, remove ridges, and fill depressions to meet finish grades.
- M. Backfill plants with the materials and methods indicated in the Tables below and with the following instructions:

After placing some backfill around root ball to stabilize plant, carefully cut and remove burlap, rope, and wire baskets from tops of root balls and from sides, but do not remove from under root balls. Remove pallets, if any, before setting. Do not use planting stock if root ball is cracked or broken before or during planting operation. Backfill around root ball in layers, tamping to settle soil and eliminate voids and air pockets. When planting pit is approximately one-half filled, water thoroughly before placing remainder of backfill. Repeat watering until no more water is absorbed. Continue backfilling process. Water again after placing and tamping final layer of soil.

3.05 MASS PLANTING AREA REQUIREMENTS

- A. Preparation - Loosen area of planting areas to a minimum depth indicated in the table below. Remove stones larger than 1 inch in any dimension and sticks, roots, rubbish, and other extraneous matter and legally dispose of them off Owner's property.

B.

PLANTING TYPE	TREATMENT AREA	PLANTING SOIL DEPTH	BACKFILL FOR EXCAVATION
Shrub and Groundcover Masses	Entire planting area	See Soils Plan	Use Planting Soil Type A or Type B
Mass Perennials	Entire planting area	See Soils Plan	Use Planting Soil Type A or Type B
Mass Annuals	Entire planting area	See Soils Plan	Use Planting Soil Type A or Type B

- C. Apply slow release fertilizer and amendments directly to grade before loosening. Thoroughly mix amendments and soil to the depths indicated in Table 1 to produce a uniform, loose, friable planting bed. Soil generated from excavations may be used after properly amended as specified.

3.06 STORM WATER MANAGEMENT PLANTING STABILIZATION

- A. Planting plugs and small container plants in storm water management areas: Prepare the soils according to plans and details including amendments. Micro grade to meet the requirements of the grading plan. Apply jute mat in continuous runs and attach with staples at 30" oc. Cut a small slit in the jute matt and install plugs into soil.

If deer or water fowl pose a potential threat, use a single staple for each plant across the root ball to prevent the roots from being dislodged.

3.07 SOLITARY TREES AND SHRUBS PLANTING REQUIREMENTS

- A. Preparation - Loosen area of planting areas to a minimum depth indicated in the table below. Remove stones larger than 1 inch in any dimension and sticks, roots, rubbish, and other extraneous matter and legally dispose of them off Owner's property. Place planting soil type A or B to the depth of soil treatment as shown in table below.

B.

	Treatment area	Planting soil depth	Backfill from excavation
Solitary Trees	10' wider than the root ball	Loosen 12" deep	Use Planting Soil Type A or Type B
Solitary Shrubs	10' wider than the root ball	Loosen 12" deep	Use Planting Soil Type A or Type B

- C. Soil generated from excavations may be used after properly amended as specified.

3.08 MECHANIZED TREE-SPADE PLANTING

- A. Supply trees as indicated in the plant list as harvested local trees.
- B. The Designer shall tag all trees to be locally harvested with tree spade techniques.
- C. Trees shall be planted with an approved mechanized tree spade at the designated locations. Do not use tree spade to move trees larger than the maximum size allowed for a similar field-grown, balled-and-burlapped root-ball diameter according to ANSI Z60.1, or larger than manufacturer's maximum size recommendation for the tree spade being used, whichever is smaller.
- D. When extracting the tree, center the trunk within the tree spade and move tree with a solid ball of earth.
- E. Cut exposed roots cleanly during transplanting operations.
- F. Use the same tree spade to excavate the planting hole as will be used to extract and transport the tree.
- G. When extracting the tree, center the trunk within the tree spade and move tree with a solid ball of earth.
- H. Cut exposed roots cleanly during transplanting operations.
- I. Plant trees as shown on Drawings, with the following procedures :
 Lower trees without damaging trunk or major branches
 Fit the root ball into the hole leaving a minimum of gap between the root ball and hole.
 Fill the remaining gap with a 70% sandy loam topsoil, 30% organic matter and fertilizer blend. Use water to carry mixture to the bottom of the excavation to insure the gap is full. Allow to drain and return the next day and repeat as necessary until all gaps are filled.
 Stake the tree with appropriate cabling systems and insure the tree is plumb.
 Mulch the tree planting area.

- J. Where possible, orient the tree in the same direction as in its original location.
- K. Supply one slow release watering bag per 4.5" caliper of tree.

3.09 PLANT STABILIZATION

- A. Install plant stabilization as follows unless otherwise indicated:

B. PLANT SIZE	C. STABILIZATION METHOD
D. 3" to 6" in Caliper	E. Anchor 3 guys to 30" wood stakes. Install guy wires allowing enough slack to avoid rigid restraint of tree. Provide soft flexible protection of the trunk from the guy wires. Attach flags to each guy wire, 30 inches above finish grade.
F. Less than 12' tall	Provide two 6' tall hardwood stakes driven into the ground at the edge of the root ball 2' deep. Fasten the tree to the stakes with flexible bands capable of holding the plant steady but not binding.

3.10 PLANT PRUNING

- A. Remove only dead, dying, or broken branches. Do not prune for shape.

3.11 PLANTING AREA MULCHING

- A. Layout mulch beds carefully with smooth lines and as indicated on the drawings. Mulch backfilled surfaces of planting areas and other areas indicated.
- B. Organic Mulch in Planting Areas: Apply over whole surface of mass planting areas or on isolated plantings as follows:
 - 3" minimum depth for trees, shrubs and groundcovers
 - 1 1/2" minimum depth for groundcovers, perennials, and annual beds.
- C. Do not place mulch within 3 inches of tree or large shrub trunks.

3.12 EDGING INSTALLATION

- A. Chiseled Edging: Construct chiseled edge separating mulch areas from lawn as shown in the drawings.
- B. Steel Edging: Install steel edging where indicated according to manufacturer's written instructions. Anchor with steel stakes spaced approximately 30 inches apart, driven below top elevation of edging.

3.13 TREE GRATE INSTALLATION

- A. Tree Grates: Install according to manufacturer's written instructions. Set grate segments flush with adjoining surfaces. Shim from supporting substrate with soil-resistant plastic. Maintain a 3-inch-minimum growth radius around base of tree; break away portions of casting, if necessary, according to manufacturer's written instructions.

PLANT MAINTENANCE

- A. Maintain plantings by pruning, cultivating, watering, weeding, fertilizing, mulching, restoring planting saucers, adjusting and repairing tree-stabilization devices, resetting to proper grades or vertical position, and performing other operations as required to establish healthy, viable plantings.
- B. Fill in, as necessary, soil subsidence that may occur because of settling or other processes. Replace mulch materials damaged or lost in areas of subsidence.
- C. Apply treatments as required to keep plant materials, planted areas, and soils free of pests and pathogens or disease. Use integrated pest management practices when possible to minimize use of pesticides and reduce hazards. Treatments include physical controls such as hosing off foliage, mechanical controls such as traps, and biological control agents.

3.15 PESTICIDE APPLICATION

- A. Apply pesticides and other chemical products and biological control agents according to authorities having jurisdiction and manufacturer's written recommendations. Coordinate applications with Owner's operations and others in proximity to the Work. Notify Owner before each application is performed.
- B. Pre-Emergent Herbicides (Selective and Nonselective): Apply to tree, shrub, and ground-cover areas according to manufacturer's written recommendations. Do not apply to seeded areas.
- C. Post-Emergent Herbicides (Selective and Nonselective): Apply only as necessary to treat already-germinated weeds and according to manufacturer's written recommendations.

3.16 REPAIR AND REPLACEMENT

- A. General: Repair or replace existing or new trees and other plants that are damaged by construction operations, in a manner approved by Designer.
Submit details of proposed pruning and repairs.
Perform repairs of damaged trunks, branches, and roots within 24 hours, if approved.
Replace trees and other plants that cannot be repaired and restored to full-growth status, as determined by Designer.
- B. Remove and replace trees that are more than 25 percent dead or in an unhealthy condition before the end of the corrections period or are damaged during construction operations that Designer determines are incapable of restoring to normal growth pattern.
Provide new trees of same size as those being replaced.
Species of Replacement Trees: Same species being replaced.

3.17 CLEANING AND PROTECTION

- A. During planting, keep adjacent paving and construction clean and work area in an orderly condition. Clean wheels of vehicles before leaving site to avoid tracking soil onto roads, walks, or other paved areas.
- B. Remove surplus soil and waste material including excess subsoil, unsuitable soil, trash, and debris and legally dispose of them off Owner's property.
- C. Protect plants from damage due to landscape operations and operations of other contractors and trades. Maintain protection during installation and maintenance periods. Treat, repair, or replace damaged plantings.

- D. After installation and before Substantial Completion, remove nursery tags, nursery stakes, tie tape, labels, wire, burlap, and other debris from plant material, planting areas, and Project site.

3.18 MAINTENANCE SERVICE

- A. Maintenance Service for Trees and Shrubs: Provide maintenance by skilled employees of landscape Installer. Maintain as required in "Plant Maintenance" Article. Begin maintenance immediately after plants are installed and continue until plantings are acceptably healthy and well established, but for not less than maintenance period below:

Maintenance Period: 12 months from date of Substantial Completion.

- B. Maintenance Service for Ground Cover and Other Plants: Provide maintenance by skilled employees of landscape Installer. Maintain as required in "Plant Maintenance" Article. Begin maintenance immediately after plants are installed and continue until plantings are acceptably healthy and well established, but for not less than maintenance period below:

Maintenance Period: 12 months from date of Substantial Completion.

- C. For Mechanized Tree Spade Trees: Provide 3 months of watering by refilling slow-release water bags from the date of installation.

END OF SECTION 329300

SECTION 33 12 00 – WATER UTILITY DISTRIBUTION EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes water-distribution piping and specialties outside the building for the following:
 - 1. Water services.

1.3 DEFINITIONS

- A. Combined Water Service and Fire-Service Main: Exterior water piping for both domestic-water and fire-suppression piping.
- B. Fire-Service Main: Exterior fire-suppression-water piping.
- C. Fire-Suppression-Water Piping: Interior fire-suppression-water piping.
- D. Water-Distribution Piping: Interior domestic-water piping.
- E. Water Service: Exterior domestic-water piping.
- F. The following are industry abbreviations for plastic materials:
 - 1. PA: Polyamide (nylon) plastic.
 - 2. PE: Polyethylene plastic.
 - 3. PP: Polypropylene plastic.
 - 4. PVC: Polyvinyl chloride plastic.
 - 5. DIP: Ductile Iron Pipe

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Piping specialties.
 - 2. Valves and accessories.
- B. Shop Drawings: For the following:

1. Precast concrete vaults, including frames and covers, ladders, and drains.
 2. Wiring Diagrams: Power, signal, and control wiring.
- C. Coordination Drawings: For piping and specialties including relation to other services in same area. Show piping and specialty sizes and valves, meter and specialty locations, and elevations.
- D. Field quality-control test reports.
- E. Operation and Maintenance Data: For specialties to include in emergency, operation, and maintenance manuals. Include the following product data for Operation and Maintenance Manual:
1. Valves.

1.5 QUALITY ASSURANCE

- A. Product Options: Drawings indicate size, profiles, and dimensional requirements of piping and specialties and are based on the specific system indicated. Refer to Division 1 Section "Product Requirements."
- B. Regulatory Requirements:
1. Comply with requirements of utility company or local jurisdiction supplying water. Include tapping of water mains and backflow prevention.
 2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
 3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing. All threads to be NST.
- C. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- D. Include all survey as-builts needed for City of Raleigh approval in CAD and mylar prepared and stamped by Professional Land Surveyor.
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- F. Comply with ASTM F 645 for selection, design, and installation of thermoplastic water piping.
- G. Comply with FM's "Approval Guide" or UL's "Fire Protection Equipment Directory" for fire-service-main products.
- H. NFPA Compliance: Comply with NFPA 24 for materials, installations, tests, flushing, and valve and hydrant supervision for fire-service-main piping for fire suppression.
- I. NSF Compliance:
1. Comply with NSF 14 for plastic potable-water-service piping.

2. Comply with NSF 61 for materials for water-service piping and specialties for domestic water.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Preparation for Transport: Prepare valves, including fire hydrants, according to the following:
 1. Ensure that valves are dry and internally protected against rust and corrosion.
 2. Protect valves against damage to threaded ends and flange faces.
 3. Set valves in best position for handling. Set valves closed to prevent rattling.
- B. During Storage: Use precautions for valves, including fire hydrants, according to the following:
 1. Do not remove end protectors unless necessary for inspection; then reinstall for storage.
 2. Protect from weather. Store indoors and maintain temperature higher than ambient dew-point temperature. Support off the ground or pavement in watertight enclosures when outdoor storage is necessary.
- C. Handling: Use sling to handle valves and fire hydrants if size requires handling by crane or lift. Rig valves to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.
- D. Deliver piping with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe-end damage and to prevent entrance of dirt, debris, and moisture.
- E. Protect stored piping from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor when storing inside.
- F. Protect flanges, fittings, and specialties from moisture and dirt.
- G. Store plastic piping protected from direct sunlight. Support to prevent sagging and bending.

1.7 PROJECT CONDITIONS

- A. Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
 1. Notify Owner's Representative not less than two days in advance of proposed utility interruptions.
 2. Do not proceed with utility interruptions without Owner's Representative written permission.

1.8 COORDINATION

- A. Coordinate connection to water main with utility company.

PART 2 - PRODUCTS

2.1 DUCTILE-IRON PIPE AND FITTINGS

- A. Mechanical-Joint, Ductile-Iron Pipe: AWWA C151, cement and mortar lined with seal coat in accordance with AWWA Standard C104, with mechanical-joint, bell- and plain-spigot end unless grooved or flanged ends are indicated.
1. Mechanical-Joint, Ductile-Iron Fittings: AWWA C110, ductile- or gray-iron standard pattern or AWWA C153, ductile-iron compact pattern.
 - a. Glands, Gaskets, and Bolts: AWWA C111, ductile- or gray-iron glands, rubber gaskets, and steel bolts.
 2. Restrained Joint Products: Subject to compliance with requirements, provide one of the following products:
 - a. American Cast Iron Pipe Company; Flex-Ring or Lok-Ring.
 - b. Griffin Pipe Products Company; Snap-Lok.
 - c. U.S. Pipe and Foundry Company; Bolt-Lok, Flex-Ring, HP Lok, or TR Flex.
- B. Push-on-Joint, Ductile-Iron Pipe: AWWA C151, cement and mortar lined with seal coat in accordance with AWWA Standard C104, with push-on-joint, bell- and plain-spigot end unless grooved or flanged ends are indicated.
1. Push-on-Joint, Ductile-Iron Fittings: AWWA C110, ductile- or gray-iron standard pattern or AWWA C153, ductile-iron compact pattern.
 - a. Gaskets: AWWA C111, rubber.
 2. Push-on-Joint Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. American Cast Iron Pipe Company.
 - b. Griffin Pipe Products Company.
 - c. McWane Cast Iron Pipe Company.
 - d. U.S. Pipe and Foundry Company.
- C. Ductile-Iron Flexible Expansion Joints: Compound, ductile-iron fitting with combination of flanged and mechanical-joint ends complying with AWWA C110 or AWWA C153. Include two gasketed ball-joint sections and one or more gasketed sleeve sections. Assemble components for offset and expansion indicated. Include AWWA C111, ductile-iron glands, rubber gaskets, and steel bolts.
- D. Ductile-Iron Deflection Fittings: Compound, ductile-iron coupling fitting with sleeve and flexing sections for up to 20-degree deflection, gaskets, and restrained-joint ends complying with AWWA C110 or AWWA C153. Include AWWA C111, ductile-iron glands, rubber gaskets, and steel bolts.

- E. Ductile-Iron Expansion Joints: Three-piece, ductile-iron assembly consisting of telescoping sleeve with gaskets and restrained-type, ductile-iron, bell-and-spigot end sections complying with AWWA C110 or AWWA C153. Select and assemble components for expansion indicated. Include AWWA C111, ductile-iron glands, rubber gaskets, and steel bolts.

2.2 COPPER TUBE AND FITTINGS

- A. Soft Copper Tube: ASTM B 88, Type K, water tube, annealed temper.
 - 1. Copper Fittings: ASME B16.18, cast-copper-alloy or ASME B16.22, wrought-copper, solder-joint pressure type. Furnish only wrought-copper fittings if indicated.
- B. Bronze Flanges: ASME B16.24, Class 150, with solder-joint end. Furnish Class 300 flanges if required to match piping.
- C. Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body with ball-and-socket, metal-to-metal seating surfaces, and solder-joint or threaded ends.

2.3 PIPE AND FITTINGS

- A. Mechanical-Joint, Ductile-Iron Fittings: AWWA C110, ductile- or gray-iron standard pattern or AWWA C153, ductile-iron compact pattern.
 - 1. Glands, Gaskets, and Bolts: AWWA C111, ductile- or gray-iron glands, rubber gaskets, and steel bolts.

2.4 JOINING MATERIALS

- A. Transition Couplings:
 - 1. Underground Piping, NPS 1-1/2 and Smaller: Manufactured fitting or coupling same size as, with pressure rating at least equal to and ends compatible with, piping to be joined.
 - 2. Underground Piping, NPS 2 and Larger: AWWA C219, metal, sleeve-type coupling same size as, with pressure rating at least equal to and ends compatible with, piping to be joined.
 - 3. Aboveground or Vault Piping: Pipe fitting same size as, with pressure rating at least equal to and ends compatible with, piping to be joined.
- B. Brazing Filler Metals: AWS A5.8, BCuP Series.
- C. Soldering Flux: ASTM B 813, water-flushable type.
- D. Solder Filler Metal: ASTM B 32, lead-free type with 0.20 percent maximum lead content.
- E. Plastic Pipe-Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer, unless otherwise indicated.

2.5 GATE VALVES

A. UL/FM, Cast-Iron Gate Valves:

1. Manufacturers: Subject to compliance with requirement, provide products by one of the following as approved by the local jurisdiction and pre-approved by the Designer:
 - a. American AVK co.
 - b. Clow.
 - c. Kennedy.
 - d. M&H.
 - e. Mueller.
 - f. Waterous.
2. UL/FM, Nonrising-Stem Gate Valves: UL 262, FM-approved iron body and bonnet with flange for indicator post, bronze seating material, and inside screw.
 - a. Minimum Working Pressure: 175 psig.
 - b. End Connections: Flanged.

2.6 GATE VALVE ACCESSORIES AND SPECIALTIES

A. Tapping-Sleeve Assemblies: Comply with MSS SP-60. Include sleeve and valve compatible with drilling machine.

1. Manufacturers: Subject to compliance with requirement, provide products that match valve manufacturer as approved by the local jurisdiction and pre-approved by the Designer.

B. Valve Boxes: Adjustable valve boxes to be 35 gray cast iron and manufactured in accordance with ASTM A48. Include top section, adjustable extension of length required for depth of burial of valve, plug with lettering "WATER," bottom section with base of size to fit over valve, and approximately 5-inch- diameter barrel.

1. Operating Wrenches: Steel, tee-handle with one pointed end, stem of length to operate deepest buried valve, and socket matching valve operating nut.

C. Indicator Posts: UL 789, FM-approved, vertical-type, cast-iron body with operating wrench, extension rod, and adjustable cast-iron barrel of length required for depth of burial of valve.

D. Indicator Posts: UL 789, FM-approved, horizontal, wall-type, cast-iron body with operating wrench, extension rod, and cast-iron barrel.

2.7 CORPORATION VALVES AND CURB VALVES

A. Manufacturers: Subject to compliance with requirement, provide products by one of the following as approved by the local jurisdiction and pre-approved by the Designer:

1. Amcast Industrial Corporation; Lee Brass Co.

2. Ford Meter Box Company, Inc. (The).
 3. Grinnell Corporation; Mueller Co.; Water Products Div.
 4. Jones, James Company.
 5. Master Meter, Inc.
 6. McDonald, A. Y. Mfg. Co.
 7. Red Hed Manufacturing Co.
- B. Service-Saddle Assemblies: Comply with AWWA C800. Include saddle and valve compatible with tapping machine.
1. Service Saddle: Copper alloy with seal and AWWA C800, threaded outlet for corporation valve.
 2. Corporation Valve: Bronze body and ground-key plug, with AWWA C800, threaded inlet and outlet matching service piping material.
 3. Manifold: Copper fitting with two to four inlets as required, with ends matching corporation valves and outlet matching service piping material.
- C. Curb Valves: Comply with AWWA C800. Include bronze body, ground-key plug or ball, and wide tee head, with inlet and outlet matching service piping material.
- D. Service Boxes for Curb Valves: Similar to AWWA M44 requirements for cast-iron valve boxes. Include cast-iron telescoping top section of length required for depth of burial of valve, plug with lettering "WATER," bottom section with base of size to fit over curb valve, and approximately 3-inch-diameter barrel.
1. Shutoff Rods: Steel, tee-handle with one pointed end, stem of length to operate deepest buried valve, and slotted end matching curb valve.

PART 3 - EXECUTION

3.1 EARTHWORK

- A. See Section 312000 "Earth Moving" for excavating, trenching, and backfilling.

3.2 PIPING APPLICATIONS

- A. General: Use pipe, fittings, and joining methods for piping systems according to the following applications.
- B. Transition couplings and special fittings with pressure ratings at least equal to piping pressure rating may be used in applications below, unless otherwise indicated.
- C. Do not use flanges, unions, or keyed couplings for underground piping.
- D. Flanges, unions, keyed couplings, and special fittings may be used, instead of joints indicated, on aboveground piping and piping in vaults.

- E. Underground Water-Service Piping and or Fire Service Main Piping: Use the following piping materials for each size range as indicated by the Drawings or per local jurisdiction standard construction specifications;
1. NPS 3/4 to NPS 2 Soft copper tube, Type K; wrought-copper fittings; and or soldered joints.
 2. NPS 2 - 12 : Ductile-iron, push-on-joint pipe; ductile-iron, class 350.
- F. Vault Water-Service Piping: Use the following piping materials for each size range as indicated on the drawings
1. NPS 3/4 to NPS 2 Soft copper tube, Type K; wrought-copper fittings; and brazed or soldered joints.
 2. NPS 2 - 12 : Ductile-iron, mechanical-joint pipe; ductile-iron, mechanical-joint fittings; and mechanical joints.
- G. Vault Fire-Service-Main Piping: Ductile-iron pipe with grooved ends; ductile-iron, grooved-end fittings; ductile-iron keyed couplings; and grooved joints.

3.3 VALVE APPLICATIONS

- A. General Application: Use mechanical-joint-end valves for NPS 3 and larger underground installation. Use threaded- or flanged-end valves for installation in vaults. Use UL/FM, nonrising-stem gate valves for installation with indicator posts. Use corporation valves and curb valves with ends compatible with piping, for NPS 2 and smaller installation.
- B. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
1. Underground Valves, NPS 3 and Larger: AWWA, cast-iron, nonrising-stem, resilient - seated gate valves with valve box.
 2. Underground Valves, NPS 4 and Larger, for Indicator Posts: UL/FM, cast-iron, nonrising-stem gate valves with indicator post.
 3. Use the following for valves in vaults and aboveground:
 - a. Gate Valves, NPS 2 and Smaller: Bronze, nonrising stem.
 - b. Gate Valves, NPS 3 and Larger: AWWA and UL/FM approved, cast iron, OS&Y rising stem, resilient seated.
 - c. Check Valves: AWWA C508 and UL/FM, swing-check valves.

3.4 JOINT CONSTRUCTION

- A. See Division 2 Section "Utility Materials" for basic piping joint construction.
- B. Make pipe joints according to the following:
1. Ductile-Iron Piping, Gasketed Joints for Water-Service Piping: AWWA C600 and AWWA M41.
 2. Ductile-Iron Piping, Gasketed Joints for Fire-Service-Main Piping: UL 194.

3. Ductile-Iron Piping, Grooved Joints: Cut-groove pipe. Assemble joints with keyed couplings, gaskets, lubricant, and bolts according to coupling manufacturer's written instructions.
4. Copper Tubing Soldered Joints: ASTM B 828. Use flushable flux and lead-free solder.
5. PVC Piping Gasketed Joints: Use joining materials according to AWWA C900. Construct joints with elastomeric seals and lubricant according to ASTM D 2774 or ASTM D 3139 and pipe manufacturer's written instructions.
6. PE Piping Insert-Fitting Joints: Use plastic insert fittings and fasteners according to fitting manufacturer's written instructions.
7. Dissimilar Materials Piping Joints: Use adapters compatible with both piping materials, with OD, and with system working pressure. Refer to Division 2 Section "Utility Materials" for joining piping of dissimilar metals.

3.5 PIPING INSTALLATION

- A. Water-Main Connection: Arrange with utility company for tap of size and in location indicated in water main.
- B. Water-Main Connection: Tap water main according to requirements of water utility company and of size and in location indicated.
- C. Make connections larger than NPS 2 with tapping machine according to the following:
 1. Install tapping sleeve and tapping valve according to MSS SP-60.
 2. Install tapping sleeve on pipe to be tapped. Position flanged outlet for gate valve.
 3. Use tapping machine compatible with valve and tapping sleeve; cut hole in main. Remove tapping machine and connect water-service piping.
 4. Install gate valve onto tapping sleeve. Comply with MSS SP-60. Install valve with stem pointing up and with valve box.
- D. Make connections NPS 2 and smaller with drilling machine according to the following:
 1. Install service-saddle assemblies and corporation valves in size, quantity, and arrangement required by utility company standards.
 2. Install service-saddle assemblies on water-service pipe to be tapped. Position outlets for corporation valves.
 3. Use drilling machine compatible with service-saddle assemblies and corporation valves. Drill hole in main. Remove drilling machine and connect water-service piping.
 4. Install corporation valves into service-saddle assemblies.
 5. Install manifold for multiple taps in water main.
 6. Install curb valve in water-service piping with head pointing up and with service box.
- E. Comply with NFPA 24 for fire-service-main piping materials and installation.
 1. Install PE corrosion-protection encasement according to ASTM A 674 or AWWA C105.
- F. Install ductile-iron, water-service piping according to AWWA C600 and AWWA M41.
 1. Install PE corrosion-protection encasement according to ASTM A 674 or AWWA C105.

- G. Install copper tube and fittings according to CDA's "Copper Tube Handbook."
- H. Install PE pipe according to ASTM D 2774 and ASTM F 645.
- I. Install PEX tubing according to ASTM D 2774 and ASTM F 645.
- J. Bury piping with depth of cover over top as indicated on the drawings or as required by the local jurisdiction.
- K. Install piping by tunneling, jacking, or combination of both, under streets and other obstructions that cannot be disturbed.
- L. Extend water-service piping and connect to water-supply source and building water piping systems at outside face of building wall in locations and pipe sizes indicated.
 - 1. Terminate water-service piping at building wall until building water piping systems are installed. Terminate piping with caps, plugs, or flanges as required for piping material. Make connections to building water piping systems when those systems are installed.
- M. Sleeves are specified in Division 2 Section "Utility Materials."
- N. Install underground piping with restrained joints at horizontal and vertical changes in direction. Use restrained-joint piping, thrust blocks, anchors, tie-rods and clamps, and other supports.
- O. Anchor service-entry piping to building wall.
- P. See Division 15 Section "Domestic Water Piping" for potable-water piping inside the building.
- Q. See Division 13 Sections for fire-suppression water piping inside the building.
- R. Install trap below frost line on drain outlet of each drinking fountain.

3.6 ANCHORAGE INSTALLATION

- A. Install anchorages for tees, plugs and caps, bends, crosses, valves, and hydrant branches. Include anchorages for the following piping systems:
 - 1. Gasketed-Joint, Ductile-Iron, Water-Service Piping: According to AWWA C600.
 - 2. Gasketed-Joint, PVC Water-Service Piping: According to AWWA M23.
 - 3. Fire-Service-Main Piping: According to NFPA 24.
- B. Apply full coat of asphalt or other acceptable corrosion-resistant material to surfaces of installed ferrous anchorage devices.

3.7 VALVE INSTALLATION

- A. Corporation Valves and Curb Valves: Install each underground curb valve with head pointed up and with service box.

3.8 CONNECTIONS

- A. Piping installation requirements are specified in other Division 2 Sections. Drawings indicate general arrangement of piping and specialties.
- B. See Division 2 Section "Utility Materials" for piping connections to valves and equipment.
- C. Connect water-distribution piping to as shown on the drawings.
- D. Connect water-distribution piping to interior domestic-water and fire-suppression piping.
- E. Connect waste piping from drinking fountains to sanitary sewerage system. See Division 2 Section "Sanitary Sewerage" for connection to sanitary-sewer] piping.
- F. Ground equipment according to Division 16 Section "Grounding and Bonding."
- G. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- H. Provide connection to existing Asbestos Concrete pipes and all necessary water treatment, asbestos abatement procedures, capture, and disposal of asbestos cement chips and capture/disposal of exposed water.

3.9 FIELD QUALITY CONTROL

- A. Piping Tests: Conduct piping tests before joints are covered and after thrust blocks have hardened sufficiently. Fill pipeline 24 hours before testing and apply test pressure to stabilize system. Use only potable water.
- B. Hydrostatic Tests: Test at not less than 1-1/2 times working pressure or 200 psi for 2 hours.
 - 1. Increase pressure in 50-psig increments and inspect each joint between increments. Hold at test pressure for 1 hour; decrease to 0 psig . Slowly increase again to test pressure and hold for 1 more hour. Maximum allowable leakage is 2 quarts per hour per 100 joints. Remake leaking joints with new materials and repeat test until leakage is within allowed limits.
 - 2. Test is to be observed by the utility engineer and Owner's Representative and report to be completed and submitted to Owner.
- C. Fire Service Lines: Testing and reports of testing activities for any fire supply line or water line with hydrant shall be in accordance with NFPA 24. Test shall be observed by utility engineer and the Owner's Representative.

3.10 IDENTIFICATION

- A. Install continuous underground detectable warning tape during backfilling of trench for underground water-service piping. Locate below finished grade, directly over piping. See Division 2 Section "Earthwork" for underground warning tapes.
- B. Permanently attach equipment nameplate or marker, indicating plastic water-service piping, on main electrical meter panel. See Division 2 Section "Utility Materials" for identifying devices.

3.11 ADJUSTING

- A. Adjust drinking fountain flow regulators for proper flow and stream height.

3.12 CLEANING

- A. Clean and disinfect water-distribution piping as follows:
 - 1. Purge new water-distribution piping systems and parts of existing systems that have been altered, extended, or repaired before use.
 - 2. Use purging and disinfecting procedure prescribed by authorities having jurisdiction or, if method is not prescribed by authorities having jurisdiction, use procedure described in NFPA 24 for flushing of piping. Flush piping system with clean, potable water until dirty water does not appear at points of outlet.
 - 3. Use purging and disinfecting procedure prescribed by authorities having jurisdiction or, if method is not prescribed by authorities having jurisdiction, use procedure described in AWWA C651 or as described below:
 - a. Fill system or part of system with water/chlorine solution containing at least 50 ppm of chlorine; isolate and allow to stand for 24 hours.
 - b. Drain system or part of system of previous solution and refill with water/chlorine solution containing at least 200 ppm of chlorine; isolate and allow to stand for 3 hours.
 - c. After standing time, flush system with clean, potable water until no chlorine remains in water coming from system.
 - d. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedure if biological examination shows evidence of contamination.
- B. Prepare reports of purging and disinfecting activities.
- C. After completing drinking fountain installation, inspect unit. Remove paint splatters and other spots, dirt, and debris. Repair damaged finish to match original finish.
- D. Clean drinking fountains, on completion of installation, according to manufacturer's written instructions.

END OF SECTION 33 12 00

SECTION 33 30 00 – SANITARY SEWERAGE UTILITIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes gravity-flow, nonpressure sanitary sewerage outside the building, with the following components:
 - 1. Special fittings for expansion and deflection.
 - 2. Cleanouts.

1.3 PERFORMANCE REQUIREMENTS

- A. Gravity-Flow, Nonpressure, Drainage-Piping Pressure Rating: 10-foot head of water.

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Special pipe fittings.
- B. Field quality-control test reports.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Do not store plastic manholes, pipe, and fittings in direct sunlight.
- B. Protect pipe, pipe fittings, and seals from dirt and damage.

PART 2 - PRODUCTS

2.1 PVC PIPE AND FITTINGS

- A. PVC Building Service Pipe and Fittings: ASTM D 1785, Schedule 40 pipe, with plain ends for solvent-cemented joints with ASTM D 2466, Schedule 40, socket-type fittings.

- B. PVC Sewer Pipe and Fittings, NPS 15 and Smaller: ASTM D 3034, SDR 35, with bell-and-spigot ends for gasketed joints with ASTM F 477, elastomeric seals.

2.2 NONPRESSURE-TYPE PIPE COUPLINGS

- A. Comply with ASTM C 1173, elastomeric, sleeve-type, reducing or transition coupling, for joining underground nonpressure piping. Include ends of same sizes as piping to be joined and corrosion-resistant-metal tension band and tightening mechanism on each end.
- B. Sleeve Materials:
 - 1. For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
- C. Unshielded, Flexible Couplings: Elastomeric sleeve with corrosion-resistant-metal tension band and tightening mechanism on each end.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Dallas Specialty & Mfg. Co.
 - b. Fernco Inc.
 - c. Logan Clay Products Company (The).
 - d. Mission Rubber Company; a division of MCP Industries, Inc.
 - e. NDS Inc.
 - f. Plastic Oddities, Inc.
- D. Shielded, Flexible Couplings: ASTM C 1460, elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Cascade Waterworks Mfg.
 - b. Dallas Specialty & Mfg. Co.
 - c. Mission Rubber Company; a division of MCP Industries, Inc.
- E. Ring-Type, Flexible Couplings: Elastomeric compression seal with dimensions to fit inside bell of larger pipe and for spigot of smaller pipe to fit inside ring.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Fernco Inc.
 - b. Logan Clay Products Company (The).
 - c. Mission Rubber Company; a division of MCP Industries, Inc.
- F. Nonpressure-Type, Rigid Couplings: ASTM C 1461, sleeve-type reducing- or transition-type mechanical coupling molded from ASTM C 1440, TPE material with corrosion-resistant-metal tension band and tightening mechanism on each end.

2.3 CLEANOUTS

- A. PVC Cleanouts: PVC body with PVC threaded plug. Include PVC sewer pipe fitting and riser to cleanout of same material as sewer piping.

2.4 CONCRETE

- A. General: Cast-in-place concrete according to ACI 318/318R, ACI 350R, and the following:
 - 1. Cement: ASTM C 150, Type II.
 - 2. Fine Aggregate: ASTM C 33, sand.
 - 3. Coarse Aggregate: ASTM C 33, crushed gravel.
 - 4. Water: Potable.
- B. Portland Cement Design Mix: 4000 psi minimum, with 0.45 maximum water/cementitious materials ratio.
 - 1. Reinforcement Fabric: ASTM A 185, steel, welded wire fabric, plain.
 - 2. Reinforcement Bars: ASTM A 615/A 615M, Grade 60, deformed steel.
- C. Manhole Channels and Benches: Factory or field formed from concrete. Portland cement design mix, 4000 psi minimum, with 0.45 maximum water/cementitious materials ratio. Include channels and benches in manholes.
 - 1. Channels: Concrete invert, formed to same width as connected piping, with height of vertical sides to three-fourths of pipe diameter. Form curved channels with smooth, uniform radius and slope.
 - a. Invert Slope: 1 percent through manhole.
 - 2. Benches: Concrete, sloped to drain into channel.
 - a. Slope: 4 percent.

2.5 MISCELLANEOUS MATERIALS

- A. Paint: SSPC-Paint 16.

PART 3 - EXECUTION

3.1 EARTHWORK

- A. Excavating, trenching, and backfilling as specified in Section 312000 "Earth Moving."

3.2 IDENTIFICATION

- A. Materials and their installation as specified in Section 312000 "Earth Moving." Arrange for installing green detectable warning tapes directly over piping as specified in Section 312000 "Earth Moving," Article 2.2, and at outside edges of underground structures.

3.3 TRACER WIRE REQUIREMENTS

- A. Installation of No. 12 gauge solid bare copper tracer wire required for PVC sewer mains and around circumference of manhole.
- B. Splice to tracer wire for sewer laterals at each manhole.
- C. Install test station at each downstream sewer manhole with standard H20 traffic load rated valve box.
- D. Paint top of valve box green and label "TS" with three-inch-high letters.
- E. Loop three feet of wire into each test station.
- F. Tracer wire requirements are above and beyond metallic tape requirements.

3.4 INSTALLATION, GENERAL

- A. General Locations and Arrangements: Drawing plans and details indicate general location and arrangement of underground sanitary sewerage piping. Location and arrangement of piping layout take design considerations into account. Install piping as indicated, to extent practical.
- B. Install piping beginning at low point at existing sewer, true to grades and alignment indicated with unbroken continuity of invert. Place bell ends of piping facing upstream. Install gaskets, seals, sleeves, and couplings according to manufacturer's written instructions for using lubricants, cements, and other installation requirements. Maintain swab or drag in line, and pull past each joint as it is completed.
- C. Use cleanout for changes in direction, unless manholes or fittings are indicated. Use fittings for branch connections, unless direct tap into existing sewer is indicated.
 - 1. Install gravity-flow piping and connect to building's sanitary drains, of sizes and in locations indicated. Terminate piping as indicated.
 - 2. Install piping pitched down in direction of flow, at minimum slope of 2 percent for 4-inch, 1 percent for 6-inch, and 0.5 percent for 8-inch.
 - 3. Install piping with 42-inch minimum cover.

3.5 PIPE JOINT CONSTRUCTION AND INSTALLATION

- A. General: Join and install pipe and fittings according to the following.
 - 1. PVC Sewer Pipe and Fittings: ASTM D 2321.
- B. System Piping Joints: Make joints using system manufacturer's couplings, unless otherwise indicated.

- C. Join piping made of different materials or dimensions with couplings made for this application. Use couplings that are compatible with and that fit both systems' materials and dimensions.
 - 1. Install with top surfaces of components, except piping, flush with finished surface.

3.6 FIELD QUALITY CONTROL

- A. Clear interior of piping and structures of dirt and superfluous material as work progresses. Maintain swab or drag in piping, and pull past each joint as it is completed.
 - 1. Place plug in end of incomplete piping at end of day and when work stops.
 - 2. Flush piping between manholes and other structures to remove collected debris, if required by authorities having jurisdiction.
- B. Inspect interior of piping to determine whether line displacement or other damage has occurred. Inspect after approximately 24 inches of backfill is in place, and again at completion of Project.
 - 1. Submit separate reports for each system inspection.
 - 2. Defects requiring correction include the following:
 - a. Alignment: Less than full diameter of inside of pipe is visible between structures.
 - b. Deflection: Flexible piping with deflection that prevents passage of ball or cylinder of size not less than 92.5 percent of piping diameter.
 - c. Crushed, broken, cracked, or otherwise damaged piping.
 - d. Infiltration: Water leakage into piping.
 - e. Exfiltration: Water leakage from or around piping.
 - 1) Replace defective piping using new materials, and repeat inspections until defects are within allowances specified.
 - 2) Reinspect and repeat procedure until results are satisfactory.
- C. Test new piping systems, and parts of existing systems that have been altered, extended, or repaired, for leaks and defects.
 - 1. Do not enclose, cover, or put into service before inspection and approval.
 - 2. Test completed piping systems according to authorities having jurisdiction.
 - 3. Schedule tests, and their inspections by authorities having jurisdiction, with at least 24 hours' advance notice.
 - 4. Submit separate reports for each test.
 - 5. Where authorities having jurisdiction do not have published procedures, perform tests as follows:
 - a. Sanitary Sewerage: Perform hydrostatic test.
 - 1) Allowable leakage is a maximum of 50 gallons per inch nominal pipe size, for every mile of pipe, during a 24-hour period
 - 2) Close openings in system and fill with water.
 - 3) Purge air and refill with water.
 - 4) Disconnect water supply.
 - 5) Test and inspect joints for leaks.

- b. Sanitary Sewerage: Perform air test according to UNI-B-6.
 - 1) Option: Test concrete piping according to ASTM C 924.
- 6. Manholes: Perform hydraulic test according to ASTM C 969 (ASTM C 969M).
- 7. Leaks and loss in test pressure constitute defects that must be repaired.
- 8. Replace leaking piping using new materials and repeat testing until leakage is within allowances specified.

END OF SECTION 33 30 00

SECTION 334100 - STORM UTILITY DRAINAGE PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes gravity-flow, nonpressure storm drainage outside the building, with the following components:
 - 1. Cleanouts.
 - 2. Drains.
 - 3. Precast concrete structures.

1.3 DEFINITIONS

- A. FRP: Fiberglass-reinforced plastic.
- B. PE: Polyethylene plastic.
- C. RCP: Reinforced concrete pipe.
- D. PVC: Polyvinyl chloride plastic.
- E. HDPE: High-density polyethylene plastic.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings:
 - 1. Catch Basins and Stormwater Inlets: Include plans, elevations, sections, details, frames, covers, and grates.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show pipe sizes, locations, and elevations. Show other piping in same trench and clearances from storm drainage system piping. Indicate interface and spatial relationship between manholes, piping, and proximate structures.
- B. Profile Drawings: Show system piping in elevation. Draw profiles at horizontal scale of not less than 1 inch equals 50 feet and vertical scale of not less than 1 inch equals 5 feet. Indicate manholes and piping. Show types, sizes, materials, and elevations of other utilities crossing system piping.

- C. Field quality-control reports.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Do not store plastic manholes, pipe, and fittings in direct sunlight.
- B. Protect pipe, pipe fittings, and seals from dirt and damage.
- C. Handle catch basins and stormwater inlets according to manufacturer's written rigging instructions.

1.7 PROJECT CONDITIONS

- A. Interruption of Existing Storm Drainage Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
 - 1. Notify Owner no fewer than two days in advance of proposed interruption of service.
 - 2. Do not proceed with interruption of service without Owner's written permission.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Gravity-Flow, Nonpressure, Drainage-Piping Pressure Rating: 10-foot head of water. Pipe joints shall be at least silttight, unless otherwise indicated.

2.2 PVC PIPE AND FITTINGS

- A. PVC Water-Service Piping:
 - 1. Pipe: ASTM D 1785, Schedule 80 PVC, with plain ends for solvent-cemented joints.
 - 2. Fittings: ASTM D 2467, Schedule 80 PVC, socket type.
- B. PVC Sewer Pipe and Fittings, NPS 15 and Smaller:
 - 1. Pipe: ASTM D 3034, SDR 35, with bell-and-spigot ends for gasketed joints.
 - 2. Fittings: ASTM D 3034, PVC with bell ends.
 - 3. Gaskets: ASTM F 477, elastomeric seals.
- C. PVC Profile Gravity Sewer Pipe and Fittings:
 - 1. Pipe: ASTM F 794 pipe, with bell-and-spigot ends.
 - 2. Fittings: ASTM D 3034 fittings, with bell ends.

3. Gaskets: ASTM F 477, elastomeric seals.

2.3 CONCRETE PIPE AND FITTINGS

A. Reinforced-Concrete Sewer Pipe and Fittings: ASTM C 76.

1. Bell-and-spigot ends and gasketed joints with ASTM C 443, rubber gaskets or sealant joints with ASTM C 990, bitumen or butyl-rubber sealant
2. Class III, Wall A.
3. Class IV, Wall A.

2.4 CLEANOUTS

A. Cast-Iron Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Josam Company.
 - b. MIFAB, Inc.
 - c. Smith, Jay R. Mfg. Co.
 - d. Tyler Pipe; a subsidiary of McWane Inc.
 - e. Watts; a Watts Water Technologies company.
 - f. Zurn Industries, LLC.
2. Description: ASME A112.36.2M, round, gray-iron housing with clamping device and round, secured, scoriated, gray-iron cover. Include gray-iron ferrule with inside calk or spigot connection and countersunk, tapered-thread, brass closure plug.
3. Top-Loading Classification(s): Light-duty and heavy-duty as approved by the Designer.

B. Plastic Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Canplas LLC.
 - b. IPS Corporation.
 - c. NDS Inc.
 - d. Plastic Oddities.
 - e. Sioux Chief Manufacturing Company, Inc.
 - f. Zurn Industries, LLC.
2. Description: PVC body with PVC threaded plug. Include PVC sewer pipe fitting and riser to cleanout of same material as sewer piping.

2.5 DRAINS

A. Cast-Iron Area Drains:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Josam Company.
 - b. MIFAB, Inc.
 - c. Smith, Jay R. Mfg. Co.
 - d. Tyler Pipe; a subsidiary of McWane Inc.
 - e. Watts; a Watts Water Technologies company.
 - f. Zurn Industries, LLC.
2. Description: ASME A112.6.3 gray-iron round body with anchor flange and round secured grate. Include bottom outlet with inside calk or spigot connection, of sizes indicated.
3. Top-Loading Classification(s): Heavy duty, unless otherwise approved by the Designer.

2.6 ENCASEMENT FOR PIPING

- A. Standard: ASTM A 674 or AWWA C105.
- B. Material: Linear low-density polyethylene film of 0.008-inch or high-density, cross-laminated polyethylene film of 0.004-inch minimum thickness.
- C. Form: Sheet or tube.
- D. Color: As selected by the Designer.

2.7

2.8 CONCRETE

- A. General: Cast-in-place concrete according to ACI 318, ACI 350/350R, and the following:
 1. Cement: ASTM C 150, Type II.
 2. Fine Aggregate: ASTM C 33, sand.
 3. Coarse Aggregate: ASTM C 33, crushed gravel.
 4. Water: Potable.
- B. Portland Cement Design Mix: 4000 psi minimum, with 0.45 maximum water/cementitious materials ratio.
 1. Reinforcing Fabric: ASTM A 185/A 185M, steel, welded wire fabric, plain.
 2. Reinforcing Bars: ASTM A 615/A 615M, Grade 60 (420 MPa) deformed steel.
- C. Ballast and Pipe Supports: Portland cement design mix, 3000 psi minimum, with 0.58 maximum water/cementitious materials ratio.

1. Reinforcing Fabric: ASTM A 185/A 185M, steel, welded wire fabric, plain.
2. Reinforcing Bars: ASTM A 615/A 615M, Grade 60 (420 MPa) deformed steel.

2.9 CATCH BASINS

A. Standard Precast Concrete Catch Basins:

1. Description: ASTM C 478, precast, reinforced concrete, of depth indicated, with provision for sealant joints.
2. Base Section: 6-inch minimum thickness for floor slab and 4-inch minimum thickness for walls and base riser section, and separate base slab or base section with integral floor.
3. Riser Sections: 4-inch minimum thickness, 48-inch diameter, and lengths to provide depth indicated.
4. Top Section: Eccentric-cone type unless concentric-cone or flat-slab-top type is indicated.
5. Joint Sealant: ASTM C 990, bitumen or butyl rubber.
6. Adjusting Rings: Interlocking rings with level or sloped edge in thickness and shape matching catch basin frame and grate. Include sealant recommended by ring manufacturer.
7. Steps: Individual FRP steps; FRP ladder; or ASTM A 615/A 615M, deformed, 1/2-inch steel reinforcing rods encased in ASTM D 4101, PP, wide enough to allow worker to place both feet on one step and designed to prevent lateral slippage off step. Cast or anchor steps into sidewalls at 12- to 16-inch intervals. Omit steps if total depth from floor of catch basin to finished grade is less than 60 inches.
8. Pipe Connectors: ASTM C 923, resilient, of size required, for each pipe connecting to base section.

B. Frames and Grates: ASTM A 536, Grade 60-40-18, ductile iron designed for A-16, structural loading. Include flat grate with small square or short-slotted drainage openings.

1. Size: 24 by 24 inches minimum unless otherwise indicated.
2. Grate Free Area: Approximately 50 percent unless otherwise indicated.

C. Frames and Grates: ASTM A 536, Grade 60-40-18, ductile iron designed for A-16, structural loading. Include 24-inch ID by 7- to 9-inch riser with 4-inch minimum width flange, and 26-inch- diameter flat grate with small square or short-slotted drainage openings.

1. Grate Free Area: Approximately 50 percent unless otherwise indicated.

2.10 STORMWATER INLETS

A. Curb Inlets: Made with vertical curb opening, of materials and dimensions according to utility standards.

1. Vertical curb opening, of materials and dimensions indicated.

B. Gutter Inlets: Made with horizontal gutter opening, of materials and dimensions according to utility standards. Include heavy-duty frames and grates.

1. Horizontal gutter opening, of materials and dimensions indicated. Include heavy-duty frames and grates.
- C. Combination Inlets: Made with vertical curb and horizontal gutter openings, of materials and dimensions according to utility standards. Include heavy-duty frames and grates.
1. Vertical curb and horizontal gutter openings, of materials and dimensions indicated. Include heavy-duty frames and grates.
- D. Frames and Grates: Heavy duty, according to utility standards.
1. Dimensions, opening pattern, free area, and other attributes indicated.

2.11 PIPE OUTLETS

- A. Head Walls: Cast-in-place reinforced concrete, with apron and tapered sides.
- B. Riprap Basins: Broken, irregularly sized and shaped, graded stone according to NSSGA's "Quarried Stone for Erosion and Sediment Control."
1. Average Size: NSSGA No. R-3, screen opening 2 inches.
 2. Average Size: NSSGA No. R-4, screen opening 3 inches.
 3. Average Size: NSSGA No. R-5, screen opening 5 inches.
- C. Filter Stone: According to NSSGA's "Quarried Stone for Erosion and Sediment Control," No. FS-2, No. 4 screen opening, average-size graded stone.
- D. Energy Dissipaters: According to NSSGA's "Quarried Stone for Erosion and Sediment Control," No. A-1, 3-ton average weight armor stone, unless otherwise indicated.

PART 3 - EXECUTION

3.1 EARTHWORK

- A. Excavation, trenching, and backfilling are specified in Section 312000 "Earth Moving."

3.2 PIPING APPLICATIONS

- A. Pipe couplings and special pipe fittings with pressure ratings at least equal to piping rating may be used in applications below, unless otherwise indicated.
1. Use nonpressure-type flexible couplings where required to join gravity-flow, nonpressure sewer piping, unless otherwise indicated.
 - a. Shielded flexible couplings for same or minor difference OD pipes.
 - b. Shielded, increaser/reducer-pattern, flexible couplings for pipes with different OD.
 - c. Ring-type flexible couplings for piping of different sizes where annular space between smaller piping's OD and larger piping's ID permits installation.

- B. Special Pipe Fittings: Use for pipe expansion and deflection. Pipe couplings and special pipe fittings with pressure ratings at least equal to piping rating may be used in applications below, unless otherwise indicated.
1. Gravity-Flow, Nonpressure Sewer Piping: Use any of the following pipe materials for each size range, unless notes specifically on plans:
 - a. NPS 3: PVC water-service pipe; PVC Schedule 40, water-service-pipe fittings; and solvent-cemented joints.
 - b. NPS 3: NPS 4 PVC sewer pipe and fittings; gaskets; and gasketed joints.
 - c. NPS 4 and NPS 6: PVC sewer pipe and fittings, gaskets, and gasketed joints.
 - d. NPS 8 to NPS 12: PVC sewer pipe and fittings, gaskets, and gasketed joints.
 - e. NPS 8 to NPS 12: NPS 12 reinforced-concrete sewer pipe and fittings, gaskets, and gasketed joints.
 - f. NPS 15: Reinforced-concrete sewer pipe and fittings, gaskets, and gasketed joints.
 - g. NPS 18 to NPS 36: Reinforced-concrete sewer pipe and fittings, gaskets, and gasketed joints.
 - h. NPS 42 to NPS 60: Reinforced-concrete sewer pipe and fittings, gaskets, and gasketed joints.
 - i. NPS 66 to NPS 144: Reinforced-concrete sewer pipe and fittings, gaskets, and gasketed joints.

3.3 PIPING INSTALLATION

- A. General Locations and Arrangements: Drawing plans and details indicate general location and arrangement of underground storm drainage piping. Location and arrangement of piping layout take into account design considerations. Install piping as indicated, to extent practical. Where specific installation is not indicated, follow piping manufacturer's written instructions.
- B. Install piping beginning at low point, true to grades and alignment indicated with unbroken continuity of invert. Place bell ends of piping facing upstream. Install gaskets, seals, sleeves, and couplings according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
- C. Install manholes for changes in direction unless fittings are indicated. Use fittings for branch connections unless direct tap into existing sewer is indicated.
- D. Install proper size increasers, reducers, and couplings where different sizes or materials of pipes and fittings are connected. Reducing size of piping in direction of flow is prohibited.
- E. Tunneling: Install pipe under streets or other obstructions that cannot be disturbed by tunneling, jacking, or a combination of both.
- F. When installing pipe under streets or other obstructions that cannot be disturbed, use pipe-jacking process of microtunneling.
- G. Install gravity-flow, nonpressure drainage piping according to the following:
1. Install piping pitched down in direction of flow.
 2. Install piping with 36-inch minimum cover.

3. Install piping below frost line.
4. Install PVC sewer piping according to ASTM D 2321 and ASTM F 1668.
5. Install nonreinforced-concrete sewer piping according to ASTM C 1479 and ACPA's "Concrete Pipe Installation Manual."
6. Install reinforced-concrete sewer piping according to ASTM C 1479 and ACPA's "Concrete Pipe Installation Manual."

3.4 PIPE JOINT CONSTRUCTION

- A. Basic pipe Joint Construction: As specified in Section 330500 "Common Work Results for Utilities." Where specific joint construction is not indicated, follow piping manufacturer's written instructions.
- B. Join gravity-flow, nonpressure drainage piping according to the following:
 1. Join PVC sewer piping according to ASTM D 2321 and ASTM D 3034 for elastomeric-seal joints or ASTM D 3034 for elastomeric gasket joints.
 2. Join PVC profile gravity sewer piping according to ASTM D 2321 for elastomeric-seal joints or ASTM F 794 for gasketed joints.
 3. Join reinforced-concrete sewer piping according to ACPA's "Concrete Pipe Installation Manual" for rubber-gasket joints.
 4. Join dissimilar pipe materials with nonpressure-type flexible or rigid couplings.

3.5 CLEANOUT INSTALLATION

- A. Install cleanouts and riser extensions from sewer pipes to cleanouts at grade. Install piping so cleanouts open in direction of flow in sewer pipe.
 1. Use Light-Duty, top-loading classification cleanouts in earth or unpaved foot-traffic areas.
 2. Use Heavy-Duty, top-loading classification cleanouts in vehicle-traffic service areas.
- B. Set cleanout frames and covers in concrete pavement and roads with tops flush with pavement surface.

3.6

3.7 CATCH BASIN INSTALLATION

- A. Construct catch basins to sizes and shapes indicated.
- B. Set frames and grates to elevations indicated.

3.8 STORMWATER INLET AND OUTLET INSTALLATION

- A. Construct inlet head walls, aprons, and sides of reinforced concrete, as indicated.
- B. Construct riprap of broken stone, as indicated.
- C. Install outlets that spill onto grade, anchored with concrete, where indicated.
- D. Install outlets that spill onto grade, with flared end sections that match pipe, where indicated.
- E. Construct energy dissipaters at outlets, as indicated.

3.9 CONCRETE PLACEMENT

- A. Place cast-in-place concrete according to ACI 318.

3.10 CHANNEL DRAINAGE SYSTEM INSTALLATION

- A. Install with top surfaces of components, except piping, flush with finished surface.
- B. Assemble channel sections to form slope down toward drain outlets. Use sealants, adhesives, fasteners, and other materials recommended by system manufacturer.
- C. Embed channel sections and drainage specialties in 4-inch minimum concrete around bottom and sides.
- D. Fasten grates to channel sections if indicated.
- E. Assemble channel sections with flanged or interlocking joints.
- F. Embed channel sections in 4-inch minimum concrete around bottom and sides.

3.11 STORMWATER DISPOSAL SYSTEM INSTALLATION

- A. Chamber Systems: Excavate trenches of width and depth, and install system and backfill according to chamber manufacturer's written instructions. Include storage and leaching chambers, filtering material, and filter mat.
- B. Piping Systems: Excavate trenches of width and depth, and install piping system, filter fabric, and backfill, according to piping manufacturer's written instructions.

3.12 CONNECTIONS

- A. Connect nonpressure, gravity-flow drainage piping in building's storm building drains specified in Section 221413 "Facility Storm Drainage Piping."
- B. Connect force-main piping to building's storm drainage force mains specified in Section 221413 "Facility Storm Drainage Piping." Terminate piping where indicated.
- C. Make connections to existing piping and underground manholes.
 - 1. Use commercially manufactured wye fittings for piping branch connections. Remove section of existing pipe; install wye fitting into existing piping; and encase entire wye fitting, plus 6-inch overlap, with not less than 6 inches of concrete with 28-day compressive strength of 3000 psi.
 - 2. Make branch connections from side into existing piping, NPS 4 to NPS 20. Remove section of existing pipe, install wye fitting into existing piping, and encase entire wye with not less than 6 inches of concrete with 28-day compressive strength of 3000 psi.
 - 3. Make branch connections from side into existing piping, NPS 21 or larger, or to underground manholes and structures by cutting into existing unit and creating an opening large enough to allow 3 inches of concrete to be packed around entering connection. Cut end of connection pipe passing through pipe or structure wall to conform to shape of and be flush with inside wall unless otherwise indicated. On outside of pipe, manhole, or structure wall, encase entering connection in 6 inches of concrete for minimum length of 12 inches to provide additional support of collar from connection to undisturbed ground.
 - a. Use concrete that will attain a minimum 28-day compressive strength of 3000 psi unless otherwise indicated.
 - b. Use epoxy-bonding compound as interface between new and existing concrete and piping materials.
 - 4. Protect existing piping, manholes, and structures to prevent concrete or debris from entering while making tap connections. Remove debris or other extraneous material that may accumulate.
- D. Connect to sediment interceptors specified in Section 221323 "Sanitary Waste Interceptors."

3.13

3.14 IDENTIFICATION

- A. Materials and their installation are specified in Section 312000 "Earth Moving." Arrange for installation of green warning tape directly over piping and at outside edge of underground structures.
 - 1. Use warning tape or detectable warning tape over ferrous piping.
 - 2. Use detectable warning tape over nonferrous piping and over edges of underground structures.

3.15 FIELD QUALITY CONTROL

- A. Inspect interior of piping to determine whether line displacement or other damage has occurred. Inspect after approximately 24 inches of backfill is in place, and again at completion of Project.
1. Submit separate reports for each system inspection.
 2. Defects requiring correction include the following:
 - a. Alignment: Less than full diameter of inside of pipe is visible between structures.
 - b. Deflection: Flexible piping with deflection that prevents passage of ball or cylinder of size not less than 92.5 percent of piping diameter.
 - c. Damage: Crushed, broken, cracked, or otherwise damaged piping.
 - d. Infiltration: Water leakage into piping.
 - e. Exfiltration: Water leakage from or around piping.
 3. Replace defective piping using new materials, and repeat inspections until defects are within allowances specified.
 4. Reinspect and repeat procedure until results are satisfactory.
- B. Test new piping systems, and parts of existing systems that have been altered, extended, or repaired, for leaks and defects.
1. Do not enclose, cover, or put into service before inspection and approval.
 2. Test completed piping systems according to requirements of authorities having jurisdiction.
 3. Schedule tests and inspections by authorities having jurisdiction with at least 24 hours' advance notice.
 4. Submit separate report for each test.
 5. Gravity-Flow Storm Drainage Piping: Test according to requirements of authorities having jurisdiction, UNI-B-6, and the following:
 - a. Exception: Piping with soiltight joints unless required by authorities having jurisdiction.
 - b. Option: Test plastic piping according to ASTM F 1417.
 - c. Option: Test concrete piping according to ASTM C 924.
- C. Leaks and loss in test pressure constitute defects that must be repaired.
- D. Replace leaking piping using new materials, and repeat testing until leakage is within allowances specified.

3.16 CLEANING

- A. Clean interior of piping of dirt and superfluous materials. Flush with potable water.

END OF SECTION 334100

FORM OF PROPOSAL

Apiculture Facility

Contract: _____

North Carolina State University

Bidder: _____

SCO-ID # 22-24494-01A

Date: _____

The undersigned, as bidder, hereby declares that the only person or persons interested in this proposal as principal or principals is or are named herein and that no other person than herein mentioned has any interest in this proposal or in the contract to be entered into; that this proposal is made without connection with any other person, company or parties making a bid or proposal; and that it is in all respects fair and in good faith without collusion or fraud. The bidder further declares that he has examined the site of the work and the contract documents relative thereto, and has read all special provisions furnished prior to the opening of bids; that he has satisfied himself relative to the work to be performed. The bidder further declares that he and his subcontractors have fully complied with NCGS 64, Article 2 in regards to E-Verification as required by Section 2.(c) of Session Law 2013-418, codified as N.C. Gen. Stat. § 143-129(j).

The Bidder proposes and agrees if this proposal is accepted to contract with the

State of North Carolina through North Carolina State University

in the form of contract specified below, to furnish all necessary materials, equipment, machinery, tools, apparatus, means of transportation and labor necessary to complete the construction of

Apiculture Facility

in full in complete accordance with the plans, specifications and contract documents, to the full and entire satisfaction of the State of North Carolina, and

North Carolina State University and Biloba Architecture, PLLC

with a definite understanding that no money will be allowed for extra work except as set forth in the General Conditions and the contract documents, for the sum of:

SINGLE PRIME CONTRACT:

Base Bid:

_____ Dollars(\$)

General Subcontractor:

Plumbing Subcontractor:

_____ Lic _____

_____ Lic _____

Mechanical Subcontractor:

Electrical Subcontractor:

_____ Lic _____

_____ Lic _____

GS143-128(d) requires all single prime bidders to identify their subcontractors for the above subdivisions of work. A contractor whose bid is accepted shall not substitute any person as subcontractor in the place of the subcontractor listed in the original bid, except (i) if the listed subcontractor's bid is later determined by the contractor to be non-responsible or non-responsive or the listed subcontractor refuses to enter into a contract for the complete performance of the bid work, or (ii) with the approval of the awarding authority for good cause shown by the contractor.

ALTERNATES:

Should any of the alternates as described in the contract documents be accepted, the amount written below shall be the amount to be "added to" or "deducted from" the base bid. (Strike out "Add" or "Deduct" as appropriate.)

GENERAL CONTRACT:

Alternate No. 1 Owner-Preferred Door Hardware

(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 1B</u>	Owner-Preferred Controller	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 1C</u>	Owner-Preferred Controls	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 1D</u>	Owner-Preferred Controls	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 2</u>	Barnquilt Custom Panels	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 3</u>	Moveable Glass Wall	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 4</u>	Ceramic Wall Tile	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 5</u>	Toilet Room 107C	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 6</u>	Emergency Generator	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 7</u>	Polished Concrete	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 8</u>	FRP and PVC Roll Flooring	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 9</u>	AHU Screening	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 10</u>	Existing House and Septic Demolition	
(Add) (Deduct)		Dollars(\$)
<u>Alternate No. 11</u>	Laboratory Casework	
(Add) (Deduct)		Dollars(\$)

UNIT PRICES

Unit prices quoted and accepted shall apply throughout the life of the contract, except as otherwise specifically noted. Unit prices shall be applied, as appropriate, to compute the total value of changes in the base bid quantity of the work all in accordance with the contract documents.

GENERAL CONTRACT:

No. 1 Removal and replacement of unsuitable Soils one cubic yard Unit Price (\$)_____

The bidder further proposes and agrees hereby to commence work under this contract on a date to be specified in a written order of the designer and shall fully complete all work thereunder within the time specified in the Supplementary General Conditions Article 23. Applicable liquidated damages amount is also stated in the Supplementary General Conditions Article 23.

MINORITY BUSINESS PARTICIPATION REQUIREMENTS

Provide with the bid - Under GS 143-128.2(c) the undersigned bidder shall identify **on its bid** (Identification of Minority Business Participation Form) the minority businesses that it will use on the project with the total dollar value of the bids that will be performed by the minority businesses. **Also** list the good faith efforts (Affidavit **A**) made to solicit minority participation in the bid effort.

NOTE: A contractor that performs all of the work with its own workforce may submit an Affidavit (**B**) to that effect in lieu of Affidavit (**A**) required above. The MB Participation Form must still be submitted even if there is zero participation.

After the bid opening - The Owner will consider all bids and alternates and determine the lowest responsible, responsive bidder. Upon notification of being the apparent low bidder, the bidder shall then file within 72 hours of the notification of being the apparent lowest bidder, the following:

An Affidavit (**C**) that includes a description of the portion of work to be executed by minority businesses, expressed as a percentage of the total contract price, which is equal to or more than the 10% goal established. This affidavit shall give rise to the presumption that the bidder has made the required good faith effort and Affidavit **D** is not necessary;

* **OR** *

If less than the 10% goal, Affidavit (**D**) of its good faith effort to meet the goal shall be provided. The document must include evidence of all good faith efforts that were implemented, including any advertisements, solicitations and other specific actions demonstrating recruitment and selection of minority businesses for participation in the contract.

Note: Bidders must always submit **with their bid** the Identification of Minority Business Participation Form listing all MB contractors, vendors and suppliers that will be used. If there is no MB participation, then enter none or zero on the form. Affidavit **A** or Affidavit **B**, as applicable, also must be submitted with the bid. Failure to file a required affidavit or documentation with the bid or after being notified apparent low bidder is grounds for rejection of the bid.

Proposal Signature Page

The undersigned further agrees that in the case of failure on his part to execute the said contract and the bonds within ten (10) consecutive calendar days after being given written notice of the award of contract, the certified check, cash or bid bond accompanying this bid shall be paid into the funds of the owner's account set aside for the project, as liquidated damages for such failure; otherwise the certified check, cash or bid bond accompanying this proposal shall be returned to the undersigned.

Respectfully submitted this day of _____

(Name of firm or corporation making bid)

WITNESS:

(Proprietorship or Partnership)

By: _____
Signature

Name: _____
Print or type

Title _____
(Owner/Partner/Pres./V.Pres)

Address _____

ATTEST:

By: _____

Title: _____
(Corp. Sec. or Asst. Sec. only)

License No. _____

Federal I.D. No. _____

Email Address: _____

(CORPORATE SEAL)

Addendum received and used in computing bid:

Addendum No. 1 _____ Addendum No. 3 _____ Addendum No. 5 _____ Addendum No. 6 _____

Addendum No. 2 _____ Addendum No. 4 _____ Addendum No. 6 _____ Addendum No. 7 _____

State of North Carolina AFFIDAVIT A – Listing of Good Faith Efforts

County of _____

(Name of Bidder)

Affidavit of _____

I have made a good faith effort to comply under the following areas checked:

Bidders must earn at least 50 points from the good faith efforts listed for their bid to be considered responsive. (1 NC Administrative Code 30 I.0101)

- 1 – (10 pts)** Contacted minority businesses that reasonably could have been expected to submit a quote and that were known to the contractor, or available on State or local government maintained lists, at least 10 days before the bid date and notified them of the nature and scope of the work to be performed.
- 2 --(10 pts)** Made the construction plans, specifications and requirements available for review by prospective minority businesses, or providing these documents to them at least 10 days before the bids are due.
- 3 – (15 pts)** Broken down or combined elements of work into economically feasible units to facilitate minority participation.
- 4 – (10 pts)** Worked with minority trade, community, or contractor organizations identified by the Office of Historically Underutilized Businesses and included in the bid documents that provide assistance in recruitment of minority businesses.
- 5 – (10 pts)** Attended prebid meetings scheduled by the public owner.
- 6 – (20 pts)** Provided assistance in getting required bonding or insurance or provided alternatives to bonding or insurance for subcontractors.
- 7 – (15 pts)** Negotiated in good faith with interested minority businesses and did not reject them as unqualified without sound reasons based on their capabilities. Any rejection of a minority business based on lack of qualification should have the reasons documented in writing.
- 8 – (25 pts)** Provided assistance to an otherwise qualified minority business in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letters of credit, including waiving credit that is ordinarily required. Assisted minority businesses in obtaining the same unit pricing with the bidder's suppliers in order to help minority businesses in establishing credit.
- 9 – (20 pts)** Negotiated joint venture and partnership arrangements with minority businesses in order to increase opportunities for minority business participation on a public construction or repair project when possible.
- 10 - (20 pts)** Provided quick pay agreements and policies to enable minority contractors and suppliers to meet cash-flow demands.


The undersigned, if apparent low bidder, will enter into a formal agreement with the firms listed in the Identification of Minority Business Participation schedule conditional upon scope of contract to be executed with the Owner. Substitution of contractors must be in accordance with GS143-128.2(d) Failure to abide by this statutory provision will constitute a breach of the contract.

The undersigned hereby certifies that he or she has read the terms of the minority business commitment and is authorized to bind the bidder to the commitment herein set forth.

Date: _____ Name of Authorized Officer: _____

Signature: _____

Title: _____



State of _____, County of _____

Subscribed and sworn to before me this _____ day of _____ 20____

Notary Public _____

My commission expires _____

State of North Carolina --AFFIDAVIT B-- Intent to Perform Contract with Own Workforce.

County of _____

Affidavit of _____
(Name of Bidder)

I hereby certify that it is our intent to perform 100% of the work required for the _____ contract.
(Name of Project)

In making this certification, the Bidder states that the Bidder does not customarily subcontract elements of this type project, and normally performs and has the capability to perform and will perform all elements of the work on this project with his/her own current work forces; and

The Bidder agrees to provide any additional information or documentation requested by the owner in support of the above statement. The Bidder agrees to make a Good Faith Effort to utilize minority suppliers where possible.

The undersigned hereby certifies that he or she has read this certification and is authorized to bind the Bidder to the commitments herein contained.

Date: _____ Name of Authorized Officer: _____

Signature: _____

Title: _____



State of _____, County of _____

Subscribed and sworn to before me this _____ day of _____ 20__

Notary Public _____

My commission expires _____

State of North Carolina - AFFIDAVIT C - Portion of the Work to be Performed by HUB Certified/Minority Businesses

County of _____

(Note this form is to be submitted only by the apparent lowest responsible, responsive bidder.)

If the portion of the work to be executed by HUB certified/minority businesses as defined in GS143-128.2(g) and 128.4(a),(b),(e) is equal to or greater than 10% of the bidders total contract price, then the bidder must complete this affidavit.
 This affidavit shall be provided by the apparent lowest responsible, responsive bidder within **72 hours** after notification of being low bidder.

Affidavit of _____ I do hereby certify that on the _____
 (Name of Bidder)

_____ (Project Name)
 Project ID# _____ Amount of Bid \$ _____

I will expend a minimum of _____% of the total dollar amount of the contract with minority business enterprises. Minority businesses will be employed as construction subcontractors, vendors, suppliers or providers of professional services. Such work will be subcontracted to the following firms listed below. Attach additional sheets if required

Name and Phone Number	*Minority Category	**HUB Certified Y/N	Work Description	Dollar Value


*Minority categories: Black, African American (**B**), Hispanic (**H**), Asian American (**A**) American Indian (**I**), Female (**F**) Socially and Economically Disadvantaged (**D**)

**** HUB Certification with the state HUB Office required to be counted toward state participation goals.**

Pursuant to GS143-128.2(d), the undersigned will enter into a formal agreement with Minority Firms for work listed in this schedule conditional upon execution of a contract with the Owner. Failure to fulfill this commitment may constitute a breach of the contract.

The undersigned hereby certifies that he or she has read the terms of this commitment and is authorized to bind the bidder to the commitment herein set forth.

Date: _____ Name of Authorized Officer: _____



Signature: _____

Title: _____

State of _____, County of _____

Subscribed and sworn to before me this _____ day of _____ 20____

Notary Public _____

My commission expires _____

State of North Carolina AFFIDAVIT D – Good Faith Efforts

County of _____

(Note this form is to be submitted only by the apparent lowest responsible, responsive bidder.)

If the goal of 10% participation by HUB Certified/ minority business **is not** achieved, the Bidder shall provide the following documentation to the Owner of his good faith efforts:

Affidavit of _____ I do hereby certify that on the _____
(Name of Bidder)

Project ID# _____ (Project Name) Amount of Bid \$ _____

I will expend a minimum of _____% of the total dollar amount of the contract with HUB certified/ minority business enterprises. Minority businesses will be employed as construction subcontractors, vendors, suppliers or providers of professional services. Such work will be subcontracted to the following firms listed below. (Attach additional sheets if required)

Name and Phone Number	*Minority Category	**HUB Certified Y/N	Work Description	Dollar Value

*Minority categories: Black, African American (**B**), Hispanic (**H**), Asian American (**A**) American Indian (**I**), Female (**F**) Socially and Economically Disadvantaged (**D**)

**** HUB Certification with the state HUB Office required to be counted toward state participation goals.**

Examples of documentation that may be required to demonstrate the Bidder's good faith efforts to meet the goals set forth in these provisions include, but are not necessarily limited to, the following:

- A. Copies of solicitations for quotes to at least three (3) minority business firms from the source list provided by the State for each subcontract to be let under this contract (if 3 or more firms are shown on the source list). Each solicitation shall contain a specific description of the work to be subcontracted, location where bid documents can be reviewed, representative of the Prime Bidder to contact, and location, date and time when quotes must be received.
- B. Copies of quotes or responses received from each firm responding to the solicitation.
- C. A telephone log of follow-up calls to each firm sent a solicitation.
- D. For subcontracts where a minority business firm is not considered the lowest responsible sub-bidder, copies of quotes received from all firms submitting quotes for that particular subcontract.
- E. Documentation of any contacts or correspondence to minority business, community, or contractor organizations in an attempt to meet the goal.
- F. Copy of pre-bid roster
- G. Letter documenting efforts to provide assistance in obtaining required bonding or insurance for minority business.
- H. Letter detailing reasons for rejection of minority business due to lack of qualification.
- I. Letter documenting proposed assistance offered to minority business in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letter of credit, including waiving credit that is ordinarily required.

Failure to provide the documentation as listed in these provisions may result in rejection of the bid and award to the next lowest responsible and responsive bidder.

Pursuant to GS143-128.2(d), the undersigned will enter into a formal agreement with Minority Firms for work listed in this schedule conditional upon execution of a contract with the Owner. Failure to fulfill this commitment may constitute a breach of the contract.

The undersigned hereby certifies that he or she has read the terms of this commitment and is authorized to bind the bidder to the commitment herein set forth.

Date: _____ Name of Authorized Officer: _____

Signature: _____

Title: _____



State of _____, County of _____

Subscribed and sworn to before me this _____ day of _____ 20____

Notary Public _____

My commission expires _____

FORM OF BID BOND

KNOW ALL MEN BY THESE PRESENTS THAT _____ as principal, and _____, as surety, who is duly licensed to act as surety in North Carolina, are held and firmly bound unto the State of North Carolina* through _____ as obligee, in the penal sum of _____ DOLLARS, lawful money of the United States of America, for the payment of which, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

Signed, sealed and dated this ____ day of ____ 20__

WHEREAS, the said principal is herewith submitting proposal for and the principal desires to file this bid bond in lieu of making the cash deposit as required by G.S. 143-129.

NOW, THEREFORE, THE CONDITION OF THE ABOVE OBLIGATION is such, that if the principal shall be awarded the contract for which the bid is submitted and shall execute the contract and give bond for the faithful performance thereof within ten days after the award of same to the principal, then this obligation shall be null and void; but if the principal fails to so execute such contract and give performance bond as required by G.S. 143-129, the surety shall, upon demand, forthwith pay to the obligee the amount set forth in the first paragraph hereof. Provided further, that the bid may be withdrawn as provided by G.S. 143-129.1

_____(SEAL)

_____(SEAL)

_____(SEAL)

_____(SEAL)

_____(SEAL)

FORM OF CONSTRUCTION CONTRACT

(ALL PRIME CONTRACTS)

THIS AGREEMENT, made the _____ day of _____ in the year of 20__ by _____ and _____ between _____

hereinafter called the Party of the First Part and the State of North Carolina, through the _____

_____ hereinafter called the Party of the Second Part.

WITNESSETH:

That the Party of the First Part and the Party of the Second Part for the consideration herein named agree as follows:

1. Scope of Work: The Party of the First Part shall furnish and deliver all of the materials, and perform all of the work in the manner and form as provided by the following enumerated plans, specifications and documents, which are attached hereto and made a part thereof as if fully contained herein: advertisement; Instructions to Bidders; General Conditions; Supplementary General Conditions; specifications; accepted proposal; contract; performance bond; payment bond; power of attorney; workmen's compensation; public liability; property damage and builder's risk insurance certificates; approval of attorney general; certificate by the Office of State Budget and Management, and drawings, titled:

Consisting of the following sheets:

Dated: _____ and the following addenda:

Addendum No _____ Dated: _____ Addendum No. _____ Dated: _____

Addendum No _____ Dated: _____ Addendum No. _____ Dated: _____

Addendum No _____ Dated: _____ Addendum No. _____ Dated: _____

Addendum No _____ Dated: _____ Addendum No. _____ Dated: _____

2. That the Party of the First Part shall commence work to be performed under this agreement on a date to be specified in a written order of the Party of the Second Part and shall fully complete all work hereunder within _____ consecutive calendar days

from said date. For each day in excess thereof, liquidated damages shall be as stated in Supplementary General Conditions. The Party of the First Part, as one of the considerations for the awarding of this contract, shall furnish to the Party of the Second Part a construction schedule setting forth planned progress of the project broken down by the various divisions or part of the work and by calendar days as outlined in Article 14 of the General Conditions of the Contract.

3. The Party of the Second Part hereby agrees to pay to the Party of the First Part for the faithful performance of this agreement, subject to additions and deductions as provided in the specifications or proposal, in lawful money of the United States as follows:

(\$ _____).

Summary of Contract Award:

4. In accordance with Article 31 and Article 32 of the General Conditions of the Contract, the Party of the Second Part shall review, and if approved, process the Party of the First Party's pay request within 30 days upon receipt from the Designer. The Party of the Second Part, after reviewing and approving said pay request, shall make payments to the Party of the First Part on the basis of a duly certified and approved estimate of work performed during the preceding calendar month by the First Party, less five percent (5%) of the amount of such estimate which is to be retained by the Second Party until all work has been performed strictly in accordance with this agreement and until such work has been accepted by the Second Party. The Second Party may elect to waive retainage requirements after 50 percent of the work has been satisfactorily completed on schedule as referred to in Article 31 of the General Conditions.

5. Upon submission by the First Party of evidence satisfactory to the Second Party that all payrolls, material bills and other costs incurred by the First Party in connection with the construction of the work have been paid in full, final payment on account of this agreement shall be made within thirty (30) days after the completion by the First Party of all work covered by this agreement and the acceptance of such work by the Second Party.

6. It is further mutually agreed between the parties hereto that if at any time after the execution of this agreement and the surety bonds hereto attached for its faithful performance, the Second Party shall deem the surety or sureties upon such bonds to be unsatisfactory, or if, for any reason, such bonds cease to be adequate to cover the performance of the work, the First Party shall, at its expense, within five (5) days after the receipt of notice from the Second Party so to do, furnish an additional bond or bonds in such form and amount, and with such surety or sureties as shall be satisfactory to the Second Party. In such event no further payment to the First Party shall be deemed to be due under this agreement until such new or additional security for the faithful performance of the work shall be furnished in manner and form satisfactory to the Second Party.

7. The Party of the First Part attest that it and all of its subcontractors have fully complied with all requirements of NCGS 64 Article 2 in regards to E-Verification as required by Section 2.(c) of Session Law 2013-418, codified as N.C. Gen. Stat. § 143-129(j).

IN WITNESS WHEREOF, the Parties hereto have executed this agreement on the day and date first above written in _____ counterparts, each of which shall without proof or accounting for other counterparts, be deemed an original contract.

Witness:

(Proprietorship or Partnership)

Contractor: (Trade or Corporate Name)

By: _____

Title: _____
(Owner, Partner, or Corp. Pres. or Vice Pres. only)

Attest: (Corporation)

By: _____

Title: _____
(Corp. Sec. or Asst. Sec. only)

The State of North Carolina through*

(CORPORATE SEAL)

(Agency, Department or Institution)

Witness:

By: _____

Title: _____

FORM OF PERFORMANCE BOND

Date of Contract: _____

Date of Execution: _____

Name of Principal
(Contractor) _____

Name of Surety: _____

Name of Contracting
Body: _____

Amount of Bond: _____

Project

KNOW ALL MEN BY THESE PRESENTS, that we, the principal and surety above named, are held and firmly bound unto the above named contracting body, hereinafter called the contracting body, in the penal sum of the amount stated above for the payment of which sum well and truly to be made, we bind, ourselves, our heirs, executors, administrators, and successors, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH, that whereas the principal entered into a certain contract with the contracting body, identified as shown above and hereto attached:

NOW, THEREFORE, if the principal shall well and truly perform and fulfill all the undertakings, covenants, terms, conditions and agreements of said contract during the original term of said contract and any extensions thereof that may be granted by the contracting body, with or without notice to the surety, and during the life of any guaranty required under the contract, and shall also well and truly perform and fulfill all the undertakings, covenants, terms, conditions and agreements of any and all duly authorized modifications of said contract that may hereafter be made, notice of which modifications to the surety being hereby waived, then, this obligation to be void; otherwise to remain in full force and virtue.

IN WITNESS WHEREOF, the above-bounden parties have executed this instrument under their several seals on the date indicated above, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

Executed in _____ counterparts.

Witness:

(Proprietorship or Partnership)

Attest: (Corporation)

By: _____

Title: _____
(Corp. Sec. or Asst. Sec. only)

(Corporate Seal)

Contractor: (Trade or Corporate Name)

By: _____

Title: _____
(Owner, Partner, or Corp. Pres. or Vice Pres. only)

(Surety Company)

By: _____

Title: _____
(Attorney in Fact)

(Surety Corporate Seal)

Witness:

Countersigned:

(N.C. Licensed Resident Agent)

Name and Address-Surety Agency

Surety Company Name and N.C.
Regional or Branch Office Address

FORM OF PAYMENT BOND

Date of Contract: _____
Date of Execution: _____
Name of Principal
(Contractor) _____
Name of Surety: _____
Name of Contracting
Body: _____
Amount of Bond: _____
Project _____

KNOW ALL MEN BY THESE PRESENTS, that we, the principal and surety above named, are held and firmly bound unto the above named contracting body, hereinafter called the contracting body, in the penal sum of the amount stated above for the payment of which sum well and truly to be made, we bind ourselves, our heirs, executors, administrators, and successors, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH, that whereas the principal entered into a certain contract with the contracting body identified as shown above and hereto attached:

NOW, THEREFORE, if the principal shall promptly make payment to all persons supplying labor/material in the prosecution of the work provided for in said contract, and any and all duly authorized modifications of said contract that may hereafter be made, notice of which modifications to the surety being hereby waived, then this obligation to be void; otherwise to remain in full force and virtue.

IN WITNESS WHEREOF, the above-bounden parties have executed this instrument under their several seals on the date indicated above, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

Executed in _____ counterparts.

Witness:

(Proprietorship or Partnership)

Attest: (Corporation)

By: _____

Title: _____
(Corp. Sec. or Asst. Sec.. only)

(Corporate Seal)

Witness:

Countersigned:

(N.C. Licensed Resident Agent)

Name and Address-Surety Agency

Surety Company Name and N.C.
Regional or Branch Office Address

Contractor: (Trade or Corporate Name)

By: _____

Title _____
(Owner, Partner, or Corp. Pres. or Vice
Pres. only)

(Surety Company)

By: _____

Title: _____
(Attorney in Fact)

(Surety Corporate Seal)

Sheet for Attaching Power of Attorney

Sheet for Attaching Insurance Certificates

APPROVAL OF THE ATTORNEY GENERAL

**CERTIFICATION BY THE OFFICE OF STATE
BUDGET AND MANAGEMENT**

Provision for the payment of money to fall due and payable by the

under this agreement has been provided for by allocation made and is available for the purpose of carrying out this agreement.

This _____ day of _____ 20____.

Signed _____
Budget Officer